

NORFOLK INTERNATIONAL AIRPORT

# MASTER PLAN UPDATE







NORFOLK AIRPORT AUTHORITY

CHA

JANUARY 2021

# DISCLAIMER

The preparation of this document was supported in part with financial assistance through the Airport Improvement Program from the Federal Aviation Administration (AIP Grant Number 3-51-0036-67-2017) as provided under Title 49 USC § 47104. The contents do not necessarily reflect the official views or policy of the FAA. Acceptance of this report by the FAA does not in any way constitute a commitment on the part of the United States to participate in any development depicted therein, nor does it indicate that the proposed development is environmentally acceptable in accordance with appropriate public laws.

# TABLE OF CONTENTS

1 Introduction ..... 1-1
1.1 Project Description ..... 1-1
1.1.1 Purpose and Objectives ..... 1-2
1.1.2 Public and Stakeholder Involvement Program ..... 1-3
1.2 Airport Background ..... 1-4
1.2.1 History ..... 1-4
1.2.2 Location and Service Area ..... 1-5
1.2.3 Airport Role ..... 1-6
1.3 Airport Governance ..... 1-9
1.4 Major Airport Tenants ..... 1-9
1.4.1 Passenger Airlines ..... 1-9
1.4.2 Air Cargo Operators ..... 1-11
1.4.3 Fixed-Base Operator (FBO) ..... 1-12
1.4.4 Maintenance, Repairs, and Overhaul (MRO) ..... 1-12
1.4.5 Military ..... 1-12
1.4.6 Rental Car Companies ..... 1-13
1.4.7 Concessionaires ..... 1-13
1.4.8 Department of Homeland Security ..... 1-14
1.5 Study Focus Area ..... 1-14
2 Inventory of Facilities and Existing Conditions ..... 2-1
2.1 Airfield ..... 2-2
2.1.1 Airport Design Criteria ..... 2-5
2.1.2 Runway System ..... 2-6
2.1.3 Taxiway System ..... 2-7
2.1.4 Aircraft Parking Aprons ..... 2-10
2.1.5 Airfield Markings ..... 2-13
2.1.6 Airfield Signage ..... 2-15
2.1.7 Airfield Pavement Condition ..... 2-16
2.2 Navigational Aids (NAVAIDs) and Instrument Procedures ..... 2-18
2.2.1 En-route NAVAIDs ..... 2-18

2.2.2 Standard Terminal Arrival Routes (STARs) ..... 2-18
2.2.3 Types of Instrument Approach Procedures (IAPs) and Instrument Approach NAVAIDs 2-19
2.2.4 Standard Instrument Departures (SIDs) ..... 2-22
2.2.5 Airfield Lighting ..... 2-22
2.3 Terminal Facility ..... 2-24
2.3.1 Terminal Facility Layout ..... 2-25
2.3.2 Main Passenger Terminal Building and Arrivals Building Functional Areas ..... 2-30
2.3.3 Airline Ticketing Lobby ..... 2-32
2.3.4 Checked Baggage Screening ..... 2-33
2.3.5 Passenger Security Screening ..... 2-33
2.3.6 Airline Gates and Holdrooms ..... 2-34
2.3.7 Terminal Concessions and Amenities ..... 2-35
2.3.8 Baggage Claim ..... 2-37
2.3.9 Rental Car Counters ..... 2-38
2.3.10 Airport Administrative and Support Areas ..... 2-38
2.3.11 Airline Service and Support Areas ..... 2-38
2.3.12 Back Office Space ..... 2-38
2.3.13 Federal Inspection Services (FIS) ..... 2-38
2.3.14 Terminal Signage and Wayfinding ..... 2-39
2.4 Automobile Access and Parking ..... 2-39
2.4.1 Existing ORF Parking ..... 2-40
2.4.2 Observed Utilization of Parking ..... 2-43
2.4.3 Parking Rates ..... 2-43
2.4.4 Off-Airport Competing Parking ..... 2-44
2.4.5 Curb-Front Traffic ..... 2-44
2.4.6 Regional Roadway Network ..... 2-44
2.4.7 Airport Roadway System ..... 2-45
2.5 Support Facilities ..... 2-47
2.5.1 Airport Perimeter Fence ..... 2-47
2.5.2 Airport Equipment Storage and Maintenance ..... 2-47

2.5.3 Air Traffic Control Tower (ATCT) ..... 2-48
2.5.4 Aircraft Rescue and Firefighting (ARFF) ..... 2-48
2.5.5 Aircraft Fueling ..... 2-50
2.5.6 Snow and Ice Control ..... 2-51
2.5.7 Air Cargo Facilities ..... 2-52
2.5.8 General Aviation (GA) Facilities and Activities ..... 2-52
2.5.9 MRO Facility ..... 2-53
2.5.10 Rental Car Facilities ..... 2-55
2.6 Airspace Environment ..... 2-55
2.7 Meteorological Conditions ..... 2-57
2.7.1 Local Climate ..... 2-58
2.7.2 Wind Coverage ..... 2-58
3 Forecasts of Aviation Activity ..... 3-1
3.1 Introduction ..... 3-1
3.1.1 Forecast Data Sources ..... 3-1
3.1.2 ORF Catchment and Core Area ..... 3-2
3.1.3 Nearby Airports ..... 3-4
3.2 Socioeconomic Data ..... 3-5
3.3 Commercial Activity Region and Destinations ..... 3-8
3.3.1 Region and Destinations ..... 3-9
3.4 Commercial Activity Historical Trends ..... 3-10
3.5 Commercial Activity Demand Forecasts ..... 3-14
3.5.1 Enplanements Forecast ..... 3-14
3.5.2 Commercial Operations Forecast ..... 3-25
3.5.3 Commercial Carrier Fleet Mix ..... 3-27
3.5.4 Effective Enplanements Range ..... 3-30
3.6 Airport Categorization ..... 3-31
3.7 Air Cargo Forecast ..... 3-32
3.7.1 Historical Trends ..... 3-32
3.7.2 Cargo Traffic Forecast ..... 3-35
3.7.3 All-Cargo Traffic by Volume Forecast ..... 3-37

3.7.4 Operations Forecast ..... 3-38
3.8 General Aviation and MIlitary forecast ..... 3-40
3.8.1 Historical General Aviation Activity ..... 3-41
3.8.2 GA Based Aircraft Forecasts ..... 3-42
3.8.3 GA Operations Forecast ..... 3-43
3.8.4 General Aviation Recommended Forecast Summary ..... 3-46
3.9 Recommended Forecast Summary ..... 3-47
3.10 Peak Activity Forecast ..... 3-49
3.10.1 Peak Enplanements ..... 3-49
3.10.2 Peak Deplanements ..... 3-51
3.10.3 Peak Passengers ..... 3-51
3.10.4 Peak Operations ..... 3-52
3.10.5 ORF Peak Activity Forecast Summary ..... 3-53
3.11 Current and Projected Critical Aircraft ..... 3-54
4 Facility Requirements ..... 4-1
4.1 Planning Factors ..... 4-2
4.1.1 Planning Activity Levels (PALs) ..... 4-2
4.1.2 Aircraft Classification ..... 4-4
4.1.3 Design Aircraft Family ..... 4-4
4.1.4 Airport & Runway Classification ..... 4-5
4.2 Airfield Capacity Requirements ..... 4-6
4.2.1 FAA AC 150/5060-5, *Airport Capacity and Delay* ..... 4-6
4.3 Airfield Facility Requirements ..... 4-14
4.3.1 Runway Requirements ..... 4-14
4.3.2 Airfield Lighting and Navigational Systems ..... 4-23
4.3.3 Taxiway Requirements ..... 4-25
4.3.4 Aprons ..... 4-27
4.4 Passenger Terminal Facility Building and Gate Requirements ..... 4-34
4.4.1 Summary Evaluation Conclusions ..... 4-35
4.4.2 Needs Analysis Summary ..... 4-36
4.4.3 Level of Service Standards ..... 4-40

4.4.4 Gate Demand Analysis ..... 4-41
4.4.5 Narrow-body Equivalent Gates and Equivalent Aircraft Gate Analysis ..... 4-43
4.4.6 Concourse Hold Room Analysis ..... 4-44
4.4.7 Concourse Circulation ..... 4-46
4.4.8 Check-in Lobby ..... 4-47
4.4.9 Airline Ticket Offices (ATO) ..... 4-51
4.4.10 Airlines Operations Areas at Gates (Concourse) ..... 4-51
4.4.11 Security Checkpoint Screening ..... 4-52
4.4.12 Outbound Baggage Facilities ..... 4-56
4.4.13 Inbound Baggage Claim and Sortation ..... 4-58
4.4.14 Inbound Baggage Handling Sort Make-up and Feed Belts ..... 4-60
4.4.15 Airline Baggage Service Offices (BSO) ..... 4-60
4.4.16 U.S. Customs and Border Protection (CBP)/Federal Inspection Services (FIS) ..... 4-60
4.4.17 Concessions ..... 4-61
4.4.18 Rental Car Concessions and Ground Transportation ..... 4-62
4.4.19 Administration Areas ..... 4-63
4.4.20 Restrooms Facilities ..... 4-64
4.4.21 Terminal Circulation ..... 4-75
4.4.22 Service Animal Relief Areas ..... 4-77
4.5 Support Facility Requirements ..... 4-77
4.5.1 General Aviation and MRO Facilities ..... 4-77
4.5.2 Air Cargo Facilities ..... 4-80
4.5.3 TSA Cargo Facilities ..... 4-81
4.5.4 Aviation Fueling Facilities ..... 4-81
4.5.5 Aircraft Deicing Facilities ..... 4-82
4.5.6 Aircraft Rescue and Firefighting Facilities (ARFF) ..... 4-83
4.5.7 NAA Maintenance Facilities ..... 4-83
4.5.8 Ground Support Equipment Facilities and Fuel Truck Storage ..... 4-83
4.5.9 Air Traffic Facilities ..... 4-84
4.6 Surface Transportation and Parking Requirements ..... 4-84
4.6.1 Passenger Parking Demand Projections ..... 4-84

4.6.2 Parking Supply Changes ..... 4-84
4.6.3 Future Adequacy of the ORF Parking Inventory ..... 4-85
4.6.4 Future Capacity of ORF Curb front ..... 4-87
4.6.5 Curbside Management Plan ..... 4-90
4.6.6 Rental Car Ready/Return Parking ..... 4-90
4.6.7 Rental Car Vehicle Storage and Maintenance Facilities ..... 4-90
4.6.8 Commercial Vehicles and TNC Staging Area ..... 4-91
4.7 Access Roadways and Circulation ..... 4-91
4.7.1 Regional Access ..... 4-91
4.7.2 Local Access ..... 4-91
4.7.3 Circulation ..... 4-92
4.7.4 Parking Cashier Plaza Requirements ..... 4-92
4.7.5 High Capacity Transit (BRT or Light Rail) Route ..... 4-92
5 Airport development concepts ..... 5-1
5.1 Concept Evaluation ..... 5-1
5.2 Current Airfield Compliances and Deficiencies ..... 5-1
5.2.1 Runway 5/23 ..... 5-2
5.2.2 Runway 14/32 ..... 5-3
5.2.3 Taxiways ..... 5-4
5.3 Airfield Development Concepts ..... 5-4
5.3.1 Initial Runway Alternatives ..... 5-5
5.3.2 Eliminated Runway Alternatives ..... 5-6
5.3.3 Runway Alternatives for Further Consideration ..... 5-7
5.3.4 Taxiway Alternatives ..... 5-17
5.4 Passenger Terminal Facility alternatives ..... 5-22
5.4.1 Status Quo Alternative ..... 5-22
5.4.2 2009 Master Plan Alternative ..... 5-22
5.4.3 Passenger Terminal Facility Alternative 1 ..... 5-24
5.4.4 Passenger Terminal Facility Alternative 2A ..... 5-27
5.4.5 Passenger Terminal Facility Alternative 2B ..... 5-29
5.4.6 Passenger Terminal Facility Alternative 3A ..... 5-31

5.4.7 Passenger Terminal Facility Alternative 3B ..... 5-33
5.4.8 Passenger Terminal Facility Alternative 4A ..... 5-35
5.4.9 Passenger Terminal Facility Alternative 4B ..... 5-37
5.5 Landside Commercial Development Options ..... 5-39
5.6 Support Facilities Development Concepts ..... 5-41
5.6.1 Rental Car Concessions Alternatives ..... 5-41
5.6.2 Air Cargo Facilities Alternatives ..... 5-46
5.6.3 General Aviation Facilities Alternatives ..... 5-52
5.6.4 Aviation Fueling Facilities Alternatives ..... 5-56
5.6.5 Aircraft Deicing Facilities Alternatives ..... 5-58
5.6.6 Airfield Maintenance Facilities Alternatives ..... 5-60
5.7 Recommended Development Plan Summary ..... 5-62
5.7.1 Airside Development ..... 5-62
5.7.2 Passenger Terminal Facility Development ..... 5-63
5.7.3 Landside Commercial Development or Airfield Maintenance Facilities Relocation . 5-64
5.7.4 Support Facilities Development ..... 5-64
6 Environmental Overview ..... 6-1
6.1 Air Quality ..... 6-1
6.2 Biological Resources (Including Fish, Wildlife, and Plants) ..... 6-2
6.2.1 Threatened and Endangered Species ..... 6-3
6.3 Climate ..... 6-5
6.4 Coastal Resources ..... 6-5
6.5 Department of Transportation Act, Section 4(f) ..... 6-5
6.6 Farmlands ..... 6-6
6.7 Hazardous Materials, Solid Waste, and Pollution Prevention ..... 6-6
6.8 Historic, Architectural, Archaeological, and Cultural Resources ..... 6-9
6.9 Land Use ..... 6-10
6.9.1 General Land Use ..... 6-11
6.9.2 South Property ..... 6-12
6.9.3 North/Northwest Property ..... 6-14
6.9.4 West/Southwest Property ..... 6-14

6.10 Natural Resources and Energy Supply ..... 6-20
6.11 Noise and Compatible Land use ..... 6-20
6.12 Socioeconomics, Environmental Justice, and Children's Environmental Health and Safety Risks 6-20
6.13 Visual Effects (Including Light Emissions) ..... 6-20
6.14 Water Resources ..... 6-20
6.14.1 Wetlands ..... 6-20
6.14.2 Floodplains ..... 6-23
6.14.3 Wild and Scenic Rivers ..... 6-25
6.14.4 Water Quality ..... 6-25
6.15 Summary ..... 6-27
7 Financial plan ..... 7-1
7.1 Activity Forecast ..... 7-1
7.2 Capital Program and Cost Summaries ..... 7-1
7.3 Capital Program Funding Sources ..... 7-2
7.3.1 AIP Grants ..... 7-2
7.3.2 State Grants ..... 7-3
7.3.3 Third Party ..... 7-4
7.3.4 Local Funds ..... 7-4
7.4 Authority's Accounting Structure ..... 7-6
7.5 Financial Feasibility ..... 7-7
7.5.1 Operating Expenses ..... 7-7
7.5.2 Debt Service ..... 7-8
7.5.3 Capital Improvement Amortization ..... 7-8
7.5.4 Operating Revenues ..... 7-9
7.5.5 Pro Forma Cash Flow ..... 7-10
7.6 Summary ..... 7-10
8 Airport Layout Plan ..... 8-1
8.1 Summary of Recommendation Plan ..... 8-1
8.2 Airport Layout Plan ..... 8-3
8.2.1 Existing and Future/Ultimate Airport Layout Plan ..... 8-3

8.2.2 Airspace Plan ..... 8-4
8.2.3 Passenger Terminal Area Plan ..... 8-7
8.2.4 Cargo Area Plan ..... 8-7
8.2.5 General Aviation Area Plan ..... 8-7
8.2.6 Land Use Map ..... 8-8
8.2.7 Airport Property Map / Data Tables ..... 8-8
Appendix A – Historical Data Sets ..... I
Appendix B – National TAF and Projected Enplanements ..... III
Appendix C – Regressions ..... IV
Appendix D – General Aviation Forecasts ..... VI
Appendix E – Airport-Provided Data ..... XIII
Appendix F – ORF Scheduling Data ..... XIX
Appendix G – FAA Required Appendices ..... XXI
Appendix H – New Air Service Route Announcements ..... XXIII
Appendix I – Airline Schedules (July 2017) ..... XXXIII
Appendix J – FAA AC 150/5060-5 ..... XLV
Appendix K – Airport Weather Data: Provided by NOAA's National Climate Data Center (NCDC) L
Appendix L – TFMSC/Distributed OPSNET Data (2018) ..... XLV
Appendix M – Runway 14/32 RSA Evaluation ..... XLIX
Appendix N – Eliminated Runway Alternatives ..... LXXV
Appendix O – Recycling, Reuse, & Waste Reduction Plan ..... LXXXIX
Appendix P – Energy Efficiency Assessment ..... CX

# LIST OF FIGURES

Figure 1-1 – Master Planning Process ..... 1-1
Figure 1-2 – Location Map ..... 1-7
Figure 1-3 – Vicinity Map ..... 1-8
Figure 1-4 – ORF Non-Stop Route Map ..... 1-10
Figure 2-1 – Existing Facilities ..... 2-3
Figure 2-2 – Building Diagram ..... 2-4
Figure 2-3 – Taxiway Configuration ..... 2-9
Figure 2-4 – Aircraft Parking Aprons ..... 2-10
Figure 2-5 – Gate Layout ..... 2-12
Figure 2-6 – Runway Markings ..... 2-14
Figure 2-7 – Existing Airfield Pavement Conditions ..... 2-17
Figure 2-8 – MALSR Configuration ..... 2-21
Figure 2-9 – Arrivals Terminal ..... 2-26
Figure 2-10 – Main Passenger Terminal: Second Level ..... 2-27
Figure 2-11 – Main Passenger Terminal: First Level ..... 2-28
Figure 2-12 – Main Passenger Terminal: Lower Level ..... 2-29
Figure 2-13 – ORF On-Airport Parking Facilities ..... 2-41
Figure 2-14 – Off-Site Employee Parking Lot ..... 2-42
Figure 2-15 – Regional Roadway Network ..... 2-45
Figure 2-16 – Local Roadway Network Access ..... 2-46
Figure 2-17 – Existing Airport Access ..... 2-46
Figure 2-18– GA & MRO Facilities ..... 2-54
Figure 2-19– U.S. Airspace Profile ..... 2-56
Figure 2-20– Washington Sectional, 103rd Edition [Effective 1 Feb 2018] ..... 2-57
Figure 2-21– Windroses ..... 2-3
Figure 3-1 – ORF Catchment and Core Areas ..... 3-3
Figure 3-2 – Drive Time to Nearby Major Airports ..... 3-4
Figure 3-3 – Population (Historical & Projected) ..... 3-6
Figure 3-4 – Employment (Historical & Projected) ..... 3-7
Figure 3-5 – Per Capita Income (Historical & Projected) ..... 3-8

Figure 3-6 – Enplaned Passengers at ORF ..... 3-11
Figure 3-7 – Commercial Operations at ORF ..... 3-11
Figure 3-8 – Scheduled Seats at ORF ..... 3-12
Figure 3-9 – Average Seats per Departure ..... 3-12
Figure 3-10 - Commercial Load Factors ..... 3-14
Figure 3-11 – Historical Trend Time Series ..... 3-16
Figure 3-12 – Market Share Time Series ..... 3-18
Figure 3-13 – ORF Percentage of Seats Filled ..... 3-26
Figure 3-14 – ORF Estimated Total Commercial Operations ..... 3-27
Figure 3-15 – Recommended Enplanement Forecast Range Comparison ..... 3-31
Figure 3-16 – ORF Cargo vs. Catchment Area Growth ..... 3-35
Figure 3-17 – Comparison of Integrator Forecasts ..... 3-37
Figure 4-1 – Enplanement Planning Activity Levels (PALs) ..... 4-3
Figure 4-2 – Projected Demand (Single Runway Configuration) ..... 4-13
Figure 4-3 –Design Standard Deficiencies ..... 4-20
Figure 4-4 – Apron Areas ..... 4-28
Figure 4-5 – Passenger Terminal Through Process ..... 4-41
Figure 4-6 – Wait Time Calculation ..... 4-53
Figure 4-7 – Standard TSA Security Checkpoint Lane ..... 4-54
Figure 4-8 – Total Concession Calculation ..... 4-61
Figure 4-9 – Administration Demand Calculation ..... 4-63
Figure 4-10 – Restroom Demand ..... 4-65
Figure 4-11 – Loaded vs. Double-Loaded Concourse Exhibit ..... 4-66
Figure 4-12 – Design Passengers Restroom Calculation ..... 4-66
Figure 4-13 – Restroom Demand (20-min Peak) ..... 4-66
Figure 4-14 – Restroom Demand (Two Concourses) ..... 4-67
Figure 4-15 – Men's Fixtures Calculation (Separate Concourses) ..... 4-67
Figure 4-16 – Women's Fixtures Calculation (Separate Concourses) ..... 4-67
Figure 4-17 – Restroom Fixture Calculation (Two Concourse) ..... 4-67
Figure 4-18 – Men's Rest Area Calculation ..... 4-68
Figure 4-19 – Women's Rest Area Fixture Calculations ..... 4-68

Figure 4-20 – Restroom Facility Calculation ..... 4-71
Figure 4-21 – Check-In Fixtures Calculation ..... 4-71
Figure 4-22 – Check-In Male Fixtures Calculation ..... 4-71
Figure 4-23 – Check-In Female Fixtures Calculation ..... 4-71
Figure 4-24 – Baggage Claim Demand ..... 4-72
Figure 4-25 – Baggage Claim Male Fixtures Calculation ..... 4-72
Figure 4-26 – Baggage Claim Female Fixtures Calculation ..... 4-72
Figure 4-27 – Male Fixtures Calculation ..... 4-73
Figure 4-28 – Female Fixtures Calculation ..... 4-73
Figure 4-29 – Men's Rest Area Calculation ..... 4-74
Figure 4-30 – Women's Rest Area Calculation ..... 4-74
Figure 4-31 – Existing Curb Front Layout ..... 4-89
Figure 5-1 – Alterative 2: Reconfigure Runway 14/32 ..... 5-9
Figure 5-2 – Alternative 3: Close Runway 14/32 ..... 5-10
Figure 5-3 – Alternative 8: Runway 5R/23L (6,000', ARC C-III) ..... 5-14
Figure 5-4 – Alternative 11: Runway 5R/23L (Length: 4,876', ARC B-II) ..... 5-15
Figure 5-5 – Alternative 12B: Runway 5R/23L (Length: 5,500', ARC C-II) ..... 5-16
Figure 5-6 – Taxiway Alternative 1 ..... 5-19
Figure 5-7 – Taxiway Alternative 2 ..... 5-20
Figure 5-8 – Taxiway Alternative 3 ..... 5-21
Figure 5-9 – 2009 Passenger Terminal Alternative ..... 5-23
Figure 5-10 – Existing Terminal Curbside Layout ..... 5-25
Figure 5-11 – Terminal Facility Alternative 1 ..... 5-26
Figure 5-12 – Terminal Facility Alternative 2A ..... 5-28
Figure 5-13 – Terminal Facility Alternative 2B ..... 5-30
Figure 5-14 – Terminal Facility Alternative 3A ..... 5-32
Figure 5-15 – Terminal Facility Alternative 3B ..... 5-34
Figure 5-16 – Terminal Facility Alternative 4A ..... 5-36
Figure 5-17 – Terminal Facility Alternative 4B ..... 5-38
Figure 5-18 – Landside Commercial Development Options ..... 5-40
Figure 5-19 – QTA Alternatives ..... 5-44

Figure 5-20 – CONRAC Alternatives ..... 5-45
Figure 5-21 – North Cargo/MRO Area Alternative 1 ..... 5-49
Figure 5-22 – North Cargo/MRO Area Alternative 2 ..... 5-50
Figure 5-23 – North Cargo/MRO Area Alternative 3 ..... 5-51
Figure 5-24 – General Aviation Alternative 1 ..... 5-54
Figure 5-25 – General Aviation Alternative 2 ..... 5-55
Figure 5-26 – Fuel / Glycol Storage Facility Alternatives ..... 5-57
Figure 5-27 –Deicing Apron Alternatives ..... 5-59
Figure 5-28 – Airfield Maintenance Alternatives ..... 5-61
Figure 5-29 –Recommended Development Plan ..... 5-68
Figure 6-1 – Existing or Historical Permits Under the RCRA ..... 6-7
Figure 6-2 – Historical Resources ..... 6-10
Figure 6-3 – Non-Aeronautical Airport Property ..... 6-16
Figure 6-4 – Non-Aeronautical Airport Property (South) ..... 6-17
Figure 6-5 – Non-Aeronautical Airport Property (North) ..... 6-18
Figure 6-6 – Non-Aeronautical Airport Property (West) ..... 6-19
Figure 6-7 – NWI Wetland Map ..... 6-21
Figure 6-8 – Runway 23 Wetland Detail ..... 6-22
Figure 6-9 – Runway 5 Wetland Detail ..... 6-23
Figure 6-10 – Floodplain Map ..... 6-24
Figure N-1 – Alternative 1: Relocate Runway 5 Threshold ..... LXXVIII
Figure N-2– Alternative 4: Proposed 5R/23L (Length: 9,001', Separation: 400') ..... LXXIX
Figure N-3 – Alternative 5: Proposed 5R/23L (Length: 9,001', Separation: 876') ..... LXXX
Figure N-4 – Alternative 6: Proposed 5R/23L (Length: 7,900', Separation: 876') ..... LXXXI
Figure N-5– Alternative 7: Proposed 5R/23L (Length: 7,200', Separation: 876') ..... LXXXII
Figure N-6 – Alternative 9: Runway 5R/23L (6,000', ARC C-II) ..... LXXXIII
Figure N-7 – Alternative 10: Runway 5R/23L (5,500', ARC C-II) ..... LXXXIV
Figure N-8 – Alternative 12A: Runway 5R/23L (Length: 5,500', ARC C-II) ..... LXXXV
Figure N-9 – Alternative 13A: Runway 5R/23L Option A (Realignment) ..... LXXXVI
Figure N-10 – Alternative 13B: Runway 5R/23L (Shift) ..... LXXXVII
Figure N-11 – Alternative 14: Crosswind Runway ..... LXXXVIII

# LIST OF TABLES

Table 1-1 – Stakeholder Involvement Meetings ..... 1-4
Table 1-2 – NPIAS Airport Classifications ..... 1-6
Table 1-3 – Non-Stop Air Service Destinations ..... 1-11
Table 2-1 – Airport Reference Code ..... 2-6
Table 2-2 – Existing Runway Specifications ..... 2-7
Table 2-3 – Existing Taxiway Specifications ..... 2-8
Table 2-4 – Gate Specifications ..... 2-11
Table 2-5 – Runway Markings ..... 2-13
Table 2-6 – Taxiway Markings ..... 2-15
Table 2-7 – Airfield Signage ..... 2-16
Table 2-8 – Airside Pavement Condition ..... 2-16
Table 2-9 – Navigational Aids (NAVAIDs) and Airfield Lighting ..... 2-18
Table 2-10 – Main Passenger Terminal Building Functional Areas ..... 2-30
Table 2-11 – Main Passenger Terminal Building Functional Areas (Continued) ..... 2-31
Table 2-12 – Arrivals Terminal Building Functional Areas ..... 2-32
Table 2-13 – Air Carrier Gate Assignments ..... 2-35
Table 2-14 – Concessions ..... 2-36
Table 2-15 – Existing NAA Parking Facilities ..... 2-40
Table 2-16 – Observed Utilization of ORF Parking Facilities ..... 2-43
Table 2-17 – ORF Public Parking Facility Rates ..... 2-44
Table 2-18 – Cargo Service Destinations ..... 2-52
Table 2-19 – Crosswind Components ..... 2-58
Table 2-20 – Weather Classification Criteria ..... 2-58
Table 2-21 – ORF Wind Coverage ..... 2-2
Table 3-1 – Population (Historical & Projected) ..... 3-6
Table 3-2 – Employment (Historical & Projected) ..... 3-7
Table 3-3 – Per Capita Income (Historical & Projected) ..... 3-8
Table 3-4 – Comparison of Airports in the Region ..... 3-9
Table 3-5 – New Service Announcements/Increases in Capacity ..... 3-9
Table 3-6 – Commercial Aircraft Serving ORF (July) ..... 3-13

Table 3-7 – Historical Trend Forecast Comparisons ..... 3-16
Table 3-8 – Market Share Comparisons ..... 3-18
Table 3-9 – Regression Comparison ..... 3-19
Table 3-10 – Historical Load Factor Percentages by Destination ..... 3-21
Table 3-11 – Short-Term Growth Scenario ..... 3-23
Table 3-12 – Medium-Long-Term Growth Scenario ..... 3-24
Table 3-13 – Recommended Commercial Enplanements Forecast vs. FAA TAF ..... 3-25
Table 3-14 – Recommended Commercial Forecast ..... 3-27
Table 3-15 – Commercial Fleet Mix ..... 3-30
Table 3-16 – Comparison of Enplanements Forecast Scenarios ..... 3-31
Table 3-17 – NPIAS Airport Classifications ..... 3-32
Table 3-18 – ORF All-Cargo Traffic Weight by Carrier Type ..... 3-34
Table 3-19 – ORF All-Cargo Flight Operations by Carrier Type ..... 3-34
Table 3-20 – Air Cargo Traffic Forecasts Summary ..... 3-37
Table 3-21 – All-Cargo Volume Forecast ..... 3-38
Table 3-22 – All-Cargo Operations Forecast ..... 3-38
Table 3-23 – Domestic Cargo Freighter Fleet Forecast ..... 3-39
Table 3-24 – Cargo Carrier Fleet Mix at ORF ..... 3-40
Table 3-25 – FAA TAF (Condensed to GA Only) ..... 3-41
Table 3-26 – ORF's Historical General Aviation Activity ..... 3-42
Table 3-27 – Based Aircraft Forecast Comparisons ..... 3-43
Table 3-28 – FAA TAF Vs. ORF- Reported Operations (With Split) ..... 3-44
Table 3-29 – General Aviation Operations Forecast Comparisons ..... 3-46
Table 3-30 – Recommended GA Forecast ..... 3-47
Table 3-31 – Recommended Forecast Summary ..... 3-48
Table 3-32 – Recommended Forecast vs. FAA TAF ..... 3-48
Table 3-33 – Historical Peak Enplanements ..... 3-50
Table 3-34 – Peak Month Average Day Enplanements ..... 3-50
Table 3-35 – Peak Hour Enplanements ..... 3-51
Table 3-36 – Peak Hour Deplanements ..... 3-51
Table 3-37 – Peak Month Average Day Passengers ..... 3-52

Table 3-38 – Peak Hour Passengers ..... 3-52
Table 3-39 – Peak Month Average Day Commercial Operations ..... 3-53
Table 3-40 – Peak Hour Operations ..... 3-53
Table 3-41 – Peak Month Average Day Total Airport Operations ..... 3-53
Table 3-42 – Projected Activity Forecast Summary ..... 3-54
Table 3-43 – Fleet Mix and Design Aircraft Families (Runway 5/23) ..... 3-55
Table 3-44 – Fleet Mix and Design Aircraft Families (Runway 14/32) ..... 3-56
Table 4-1 – Planning Activity Levels (PALs) ..... 4-3
Table 4-2 – Applicability of Aircraft Classifications ..... 4-4
Table 4-3 – Fleet Mix and Design Aircraft Family ..... 4-5
Table 4-4 – Fleet Mix and Design Aircraft Family by AAC and ADG ..... 4-6
Table 4-5 – Aircraft Capacity Classifications ..... 4-7
Table 4-6 – Aircraft Mix Index ..... 4-8
Table 4-7 – Calculated Capacity Parameters ..... 4-10
Table 4-8 – Calculated Hourly Capacity (Single Runway Configuration) ..... 4-11
Table 4-9 – Demand Ratios ..... 4-12
Table 4-10 – Annual Service Volume (Single Runway Configuration) ..... 4-13
Table 4-11 – ORF Wind Coverage ..... 4-14
Table 4-12 – FAA Runway Design Standards ..... 4-19
Table 4-13 – Runway Pavement and Non-Standard Conditions ..... 4-19
Table 4-14 – Existing Takeoff (TO) Length Requirements (90% Payload) ..... 4-22
Table 4-15 – Existing Takeoff (TO) Length Requirements (100% Payload) ..... 4-22
Table 4-16 – NAVAIDs ..... 4-24
Table 4-17 – Taxiway Design Standards based on Airplane Design Group (ADG) ..... 4-26
Table 4-18 – Taxiway Design Standards based on Taxiway Design Group (TDG) ..... 4-26
Table 4-19 – GA Itinerant Aircraft Parked on the Apron ..... 4-29
Table 4-20 – Based Aircraft (As of July 2017) ..... 4-30
Table 4-21– Anticipated Apron Space ..... 4-30
Table 4-22 – Based Aircraft Leasing Tie-Down Spaces (As of July 2018) ..... 4-31
Table 4-23 – Apron and Tie-Down Space ..... 4-31
Table 4-24 – All-Cargo Annual Operations Forecast (Square Yards) ..... 4-32

Table 4-25 – PMAD Cargo Operations ..... 4-33
Table 4-26 – Cargo Fleet Mix Apron Sizing ..... 4-33
Table 4-27 – PMAD Air Cargo Apron Space ..... 4-33
Table 4-28 – Facility Sizing Summary ..... 4-36
Table 4-29 – IATA Level of Service Grades ..... 4-40
Table 4-30 – Enplaned Passenger per Gate Approach (PALs) ..... 4-42
Table 4-31 – Departures per Gate Approach (PALs) ..... 4-42
Table 4-32 – Gate Forecast Demand (PALs) ..... 4-42
Table 4-33 – Gate Equivalencies (PALs) ..... 4-43
Table 4-34 – Single NBEG Hold Room Area Evaluation (PALs) ..... 4-45
Table 4-35 – Inclusive Hold Room Space Requirements (PALs) ..... 4-45
Table 4-36 – Single-loaded Concourse Corridor Length (PALs) ..... 4-46
Table 4-37 – Double-loaded Concourse Corridor Length and Area (PALs) ..... 4-47
Table 4-38 – IATA Level of Wait Time Standard for Check-In (Minutes) ..... 4-48
Table 4-39 – IATA Level of Service Space Standard for Check-In (sq. ft. per PAX) ..... 4-48
Table 4-40 – Enplaned Passenger Check-in Utilizations (PALs) ..... 4-49
Table 4-41 – Passenger Check-in Requirements (PALs) ..... 4-50
Table 4-42 – Passenger Check-in Hall Area Requirements (PALs) ..... 4-51
Table 4-43 – Airline Ticketing Offices (PALs) ..... 4-51
Table 4-44 – Airline Operation Areas at Gates (PALs) ..... 4-52
Table 4-45 – IATA Level of Service Standards for Security Screening Checkpoints ..... 4-53
Table 4-46 – No. of Security Screening Lanes at Checkpoints ..... 4-55
Table 4-47 – Security Screening Checkpoint Area Requirements (Not Including Queuing Area) ..... 4-55
Table 4-48 – Queue Area for All Security Checkpoint Lane (PALs) ..... 4-55
Table 4-49 – Security Screening Checkpoint TSA/LEO Office Requirements (PALs) ..... 4-56
Table 4-50 – Security Screening Checkpoint Exit Lane Requirements (PALs) ..... 4-56
Table 4-51 – Checked Baggage Inspection System Requirements (CBIS) (PALs) ..... 4-57
Table 4-52 – Outbound Baggage System Area Requirements (BHS) ..... 4-58
Table 4-53 – Deplaned PAX Baggage Claim Space Requirements (PALs) ..... 4-59
Table 4-54 – Commercial Peak Hour Airline Operations (PALs) ..... 4-59

Table 4-55 – Baggage Claim Device Capacity (PALs) ..... 4-60
Table 4-56 – Airline Baggage Service Offices (PALs) ..... 4-60
Table 4-57 – U.S. Customs and Border Protection (CBP)/Federal Inspection Services (FIS) ..... 4-61
Table 4-58 – Concession Areas (PALs) ..... 4-62
Table 4-59 – Rental Car Concessions (PALs) ..... 4-63
Table 4-60 – Airport Administration Area (PALs) ..... 4-63
Table 4-61 – TSA Administration Area (PALs) ..... 4-64
Table 4-62 – Two Concourses: Number of Restroom Modules Required (PALs) ..... 4-65
Table 4-63 – Two Concourses: Design Passengers (PALs) ..... 4-66
Table 4-64 – Two Concourses: Peak 20-Minute Restroom Demand (PALs) ..... 4-67
Table 4-65 – Two Concourses: Design Factor (PALs) ..... 4-67
Table 4-66 – Two Concourses: Required Fixtures (PALs) ..... 4-67
Table 4-67 – Two Concourses: Fixtures Required per Module (PALs) ..... 4-68
Table 4-68 – Two Concourses: Single Module Area Requirements (PALs) ..... 4-68
Table 4-69 – Two Concourses: Total Restroom Module Area Requirements (PALs) ..... 4-69
Table 4-70 – Three Concourses: Fixtures Required per Module (PALs) ..... 4-69
Table 4-71 – Three Concourses: Single Module Area Requirements (PALs) ..... 4-70
Table 4-72 – Three Concourse: Total Restroom Module Area Requirements (PALs) ..... 4-70
Table 4-73 – Connected Concourse: Single Module Area Requirements (PALs) ..... 4-70
Table 4-74 – Connected Concourse: Total Restroom Module Area Requirements (PALs) ..... 4-70
Table 4-75 – Non-Secure Landside: Check-in Restroom Design Demand (PALs) ..... 4-71
Table 4-76 – Non-Secure Landside: Check-in Men's and Women's Fixture Requirements (PALs) 4-72
Table 4-77 – Non-Secure Landside: Baggage Claim Restroom Design Demand (PALs) ..... 4-72
Table 4-78 – Non-Secure Landside: Baggage Claim Men's and Women's Fixture Requirements (PALs) ..... 4-72
Table 4-79 – Non-Secure Landside: Total Fixtures Requirements (PALs) ..... 4-73
Table 4-80 – Non-Secure Airside: Single Restroom Module Area Requirements (PALs) ..... 4-74
Table 4-81 – Non-Secure Airside: Total Restroom Module Area Requirements (PALs) ..... 4-74
Table 4-82 – Meeter and Greeter Area (PALs) ..... 4-75
Table 4-83 – Based Aircraft Leasing Hangar Spaces (As of July 2018) ..... 4-78
Table 4-84– Aircraft Hangar Units ..... 4-78

Table 4-85– Hangar Space (Stalls) Requirements ..... 4-79
Table 4-86 – Hangar Space Requirements (Sq. Ft.) ..... 4-79
Table 4-87 – All-Cargo Annual Forecasts ..... 4-80
Table 4-88 – All-Cargo Building Space Requirements ..... 4-80
Table 4-89 – Air Carrier and GA Operations ..... 4-81
Table 4-90 – Fueling Storage Requirements (Gallons) ..... 4-82
Table 4-91 – Projected Parking Needs ..... 4-85
Table 4-92 – Projected Parking Inventory ..... 4-85
Table 4-93 – Projected Parking Inventory by Type of User ..... 4-85
Table 4-94 – Projected Adequacy of the ORF Parking Inventory ..... 4-86
Table 4-95 – Summary of Projected Parking Needs by User Group ..... 4-87
Table 4-96 – Current Useable Curb Front Length ..... 4-87
Table 4-97 – Projected Curb Needs ..... 4-90
Table 5-1 – Initial Runway Alternatives ..... 5-6
Table 5-2 – Alternative 2: Reconfigure Runway 14/32 ..... 5-7
Table 5-3 – Alternative 3: Close Runway 14/32 ..... 5-8
Table 5-4 – Alternative 8: Runway 5R/23L (6,000', ARC C-III) ..... 5-12
Table 5-5 – Alternative 11: Runway 5R/23L (Length: 4,876', ARC B-II) ..... 5-13
Table 5-6 – Alternative 12B: Runway 5R/23L (Length: 5,500', ARC C-II) ..... 5-13
Table 5-7 – Taxiway Alternatives ..... 5-18
Table 5-8 – 2009 Passenger Terminal Facility Summary ..... 5-24
Table 5-9 – Passenger Terminal Facility Alternative 1 Summary ..... 5-25
Table 5-10 – Passenger Terminal Facility Alternative 2A Summary ..... 5-27
Table 5-11 – Passenger Terminal Facility Alternative 2B Summary ..... 5-29
Table 5-12 – Passenger Terminal Facility Alternative 3A Summary ..... 5-31
Table 5-13 – Passenger Terminal Facility Alternative 3B Summary ..... 5-33
Table 5-14 – Passenger Terminal Facility Alternative 4A Summary ..... 5-35
Table 5-15 – Passenger Terminal Facility Alternative 4B Summary ..... 5-37
Table 5-16 – Landside Commercial Development Options ..... 5-39
Table 5-17 – Rental Car Alternatives (QTA and/or CONRAC) ..... 5-43
Table 5-18 – North Cargo/MRO Area Alternative 1 Summary ..... 5-47

Table 5-19 – North Cargo/MRO Area Alternative 2 Summary ..... 5-47
Table 5-20 – North Cargo/MRO Area Alternative 3 Summary ..... 5-48
Table 5-21 – General Aviation Alternative 1 Summary ..... 5-52
Table 5-22 – General Aviation Alternative 2 Summary ..... 5-53
Table 5-23 – Airfield Maintenance Alternatives ..... 5-60
Table 5-24 – Recommended Development Plan ..... 5-65
Table 6-1 – Parcel Acquisition History ..... 6-12
Table 7-1 – Activity Forecast ..... 7-11
Table 7-2 – ACIP and Funding Sources ..... 7-12
Table 7-3 – ACIP Funding Sources by Year ..... 7-16
Table 7-4 – Application of AIP and State Grants ..... 7-17
Table 7-5 – Calculation of AIP Entitlements ..... 7-17
Table 7-6 – Application of PFCs ..... 7-18
Table 7-7 – PFC-Eligible Debt Service ..... 7-18
Table 7-8 – Application of CFCs ..... 7-19
Table 7-9 – Operating Expenses ..... 7-20
Table 7-10 – Outstanding Debt Service Requirement ..... 7-21
Table 7-11 – Future Debt Service Requirement ..... 7-22
Table 7-12 – Capital Improvement Amortization ..... 7-22
Table 7-13 – Airline Rates and Charges ..... 7-23
Table 7-14 – Operating Revenues ..... 7-24
Table 7-15 – Pro Forma Cash Flow ..... 7-25
Table 7-16 – Debt Service Coverage and Days Cash on Hand ..... 7-25
Table 8-1 – ALP Drawing Index ..... 8-3
Table 8-2 – Approach Surface Dimensions (Existing) ..... 8-6
Table 8-3 – Approach Surface Dimensions (Future & Ultimate) ..... 8-6
Table A-1– Socioeconomic Factors ..... I
Table A-2 – Commercial Activity ..... I
Table A-3 – FAA TAFs: Enplanements ..... I
Table A-4 – ORF's Percent Market Shares: Enplanements ..... II
Table A-5 – ORF's General Aviation and Military Activity ..... II

Table B-1 – National TAF and Projected Enplanements ..... III
Table C-1 – Socioeconomic Regression Calculations ..... IV
Table C-2 – Air Service Regression Calculations ..... V
Table D-1 – TAF Based Growth Scenario ..... VI
Table D-2 – FAA National Average Annual Growth Rates for GA Aircraft ..... VI
Table D-3 – FAA Aerospace Forecast ..... VII
Table D-4 – Market Share Scenario ..... VIII
Table D-5 – OPBA Scenario ..... IX
Table D-6 – Market Share Scenario ..... X
Table D-7 – Recommended GA Forecast ..... XI
Table D-8 – Based Aircraft by Aircraft Type ..... XII
Table F-1 – ORF Scheduling Data ..... XIX
Table G-1 – Forecast Levels and Growth Rates ..... XXI
Table G-2 – Operational Factors ..... XXI
Table G-3 – Comparing Airport Planning and TAF Forecasts ..... XXII
Table N-1 – Eliminated Runway Alternatives Summary ..... LXXV

# 1 INTRODUCTION

The Norfolk Airport Authority ('NAA' or 'the Authority') retained CHA Consulting, Inc. ('CHA') to prepare a Master Plan Update (Study) for the Norfolk International Airport ('ORF' or 'the Airport'). The purpose of the Study was to evaluate the current space utilization and operational characteristics of the airfield, terminal facility, support facilities, ground access, and land development considerations. It was the intent to consider all alternatives that could be developed for the best use of space and logical guidance provided for the continued improvements necessary to accommodate projected aviation activity in a logical and financially feasible manner throughout the 20-year planning period.

This introductory chapter provides a description of the project and a background overview of the Airport and its facilities. Additional information about the Airport and the Study can be found on its website at www.norfolkairport.com/about-us/master-plan-update. The Airport's website has destination and flight information, airport maps, driving directions, ground transportation, and parking information.

## 1.1 PROJECT DESCRIPTION

An airport master plan is a comprehensive study of an airport that is conducted via a systematic process that evaluates existing facility and market conditions, identifies anticipated stakeholders' needs, and formulates short-, medium-, and long-term development plans to meet future aviation demand. The process, methods, and ultimate products are guided by Federal Aviation Administration (FAA) Advisory Circular (AC) 150/5070-6B, *Airport Master Plans*. Consistent with this guidance, the process followed for preparing the ORF Master Plan Update is outlined in **Figure 1-1**.

It is important to note that since this Study encompassed 2+ years to complete, some information contained in the inventory may not match existing conditions in early 2020. Data considered to be critical to the recommendations generated herein have been updated; however, updating all existing conditions to be consistent with those in early 2020 is beyond the project scope.

**Figure 1-1 – Master Planning Process**



### 1.1.1 Purpose and Objectives

The purpose of this Study is to provide long-term guidance for continued airport improvements necessary to satisfy projected aviation demand in a logical and financially feasible manner. Consistent with this purpose, the Authority has indicated that the goals and objectives of the Study should include, at a minimum, the following:

- Airfield safety and standards, such as Runway Safety Areas (RSAs), Runway Protection Zones (RPZs), etc.
- Airfield considerations with a focus on the runway/taxiway system to meet the long-term needs of ORF's users
- Key terminal building planning issues, such as functional, safety, security, aesthetic, sustainability, and economic concerns
- Land use/economic development issues, such as infrastructure, access, and best use
- Surface access/parking considerations
- Environmental considerations, including air quality, storm water management, and sustainability
- Financial viability of recommended actions

In addition to addressing these objectives, this study will also fulfill the broad master planning goals set forth by the FAA in AC 150/5070-6B *Airport Master Plans*. These goals are:

- Document issues that the proposed development will address.
- Justify the proposed development through the technical, economic and environmental investigation of concepts and alternatives.
- Provide an effective graphic presentation of the development of the Airport and anticipated land uses in the vicinity of the Airport.
- Establish a realistic schedule for the implementation of the development proposed in the study, particularly the short-term capital improvement program.
- Propose an achievable financial plan to support the implementation schedule.
- Provide sufficient project definition and detail for subsequent environmental evaluations that may be required before the project is approved.
- Present a plan that adequately addresses the issues and satisfies local, state, and Federal regulations.
- Document policies and future aeronautical demand to support municipal or local deliberations on spending, debt, land use controls, and other policies necessary to preserve the integrity of the Airport and its surroundings.
- Set the stage and establish the framework for a continuing planning process. Such a process should monitor key conditions and permit changes in plan recommendations as required.

### 1.1.2 Public and Stakeholder Involvement Program

Public and stakeholder involvement is an integral part of any significant airport planning study, as it encourages information-sharing and collaboration among the community and airport stakeholders that hold a collective interest in the outcome of the Study. For the purpose of this study, stakeholders include the airport sponsor, airlines, tenants, users and travelers, local businesses, military interests, residents, resource agencies, elected and appointed officials, and the general public. During the Study, a variety of forums, such as committees, public information meetings/workshops, and public awareness campaigns, were necessary to mitigate setbacks that may arise from having a large, diverse stakeholder group.

For this Study, a Planning Advisory Committee (PAC) was established. The PAC consisted of technical level representatives of the Authority, airlines, airport tenants, general aviation users, the FAA, the Virginia Department of Aviation (DOAV), the U.S. Department of Defense (DOD), and other key agencies and interest groups. In addition, the PAC included representation from local municipalities, regional planning agencies, economic development organizations, land use and transportation planning groups, business-related organizations, and local neighborhood groups from Norfolk, Virginia Beach, and surrounding areas. The PAC was asked to provide guidance and advice on technical and local issues and also reviewed working papers at various milestones throughout the course of the project to ensure that all relevant issues were adequately addressed. The PAC was also asked to provide broad input and insight on non-technical issues affecting the community.

Three PAC meetings were held throughout the duration of the program as part of a coordinated series of meetings at key decision points in the study process. In addition to the PAC meetings and project meetings, other forms of stakeholder involvement utilized during this Study included two individual meetings on technical issues with the airlines, FAA, DOAV, DOD, and other key stakeholders, as well as three briefings for the Airport Authority Board and one briefing for special interest groups. The Airport Authority Board briefings covered topics of special concern or interest to the Authority. The purpose of the public meetings and workshops was to provide opportunities for the Authority to engage the public in purposeful conversation about the Airport and Master Plan Update. These meetings were conducted in an ‘open house’ format with interactive information stations staffed by Airport personnel and the consultant team. Other briefings were organized with key agencies, stakeholders, or public officials as needed for various topics. A Master Plan Update website, located on the Authority’s website, was made available to enable the public to conveniently access project specific information in a narrative and graphical format throughout the Study’s duration. **Table 1-1** lists each of the key involvement briefings, workshops, and meetings carried out and planned during the Study process.

**Table 1-1 – Stakeholder Involvement Meetings**

| Meeting | Date |
|---|---|
| Project Kickoff Meeting | 9/7/2017 |
| PAC Meeting #1 (PAC Kick-Off) | 1/24/2018 |
| Board Briefing #1 (Inventory & Preliminary Forecast) | 5/24/2018 |
| PAC Meeting #2 (Inventory & Preliminary Forecast) | 5/30/2018 |
| Public Meeting #1 (Inventory & Preliminary Forecast) | 5/30/2018 |
| Briefings for Special Interest Groups (CBDA) | 9/18/2018 |
| State of the Airport Meeting (2018) | 10/18/2018 |
| Board Briefing #2 (Recommended Forecast & Facility Requirements) | 6/27/2019 |
| Board Working Session (Development Concepts) | 7/31/2019 |
| Public Meeting #2 (Facility Requirements & Development Concepts) | 9/12/2019 |
| PAC Meeting #3 (Facility Requirements & Development Concepts) | 9/16/2019 |
| State of the Airport Meeting (2019) | 10/23/2019 |

Source: CHA, 2020.

## 1.2 AIRPORT BACKGROUND

Understanding the background of an airport and the region it serves is essential in making informed decisions pertaining to airport-related improvements. This section discusses ORF in the context of its location, service area, history, and role in the National Airspace System (NAS).

### 1.2.1 History

Norfolk International Airport can be traced back to the 1920s when World War I veteran, Ben Epstein, began operating an air taxi service between Norfolk and Richmond, Virginia, along with the first daily scheduled air service in the area by Ludington Lines and Eastern Airlines.


In 1938, the present Airport was opened after the city-owned golf course was converted to a municipal airport with a 3,500-foot runway. One airline operated at the airport when it opened, utilizing the renovated golf clubhouse as a passenger terminal.

In the 1940s, like many airports at the time, Norfolk Municipal Airport served as a vital resource to the war efforts of World War II, with the Army Air Corps assuming control of airport operations between 1942 and 1947. As a result, the 3,500-foot runway was extended, and two additional runways were developed to accommodate the increase in air traffic and size of aircraft. The Army Air Corps released control of airport operations after the war concluded, instigating new airlines to begin providing service to-and-from Norfolk, Virginia.

In 1948, the Airport began construction of a modernized terminal building, with construction concluding in 1951. In 1950, the newly established Norfolk Port and Industrial Authority (NPIA), which would become the Norfolk Airport Authority (NAA) in 1988, was given responsibility for the Airport. Air service continuously grew during the 1960s as propeller driven aircraft were replaced by jets, persuading the NPIA to change the Airport's name to Norfolk Regional Airport. The growth prompted the Airport to build a new terminal facility in the 1970s and change the Airport's name to Norfolk International Airport. The first portions of the present-day passenger terminal opened in 1974.

Additional changes occurred at the Airport in the 1980s, including the completion of a new fixed-base operator (FBO) and general aviation (GA) facilities, a new air cargo terminal, and an expansion of airport parking facilities. Changes to the Airport continued throughout the 1990s,

with expansions to the air cargo terminal and renovations to public areas of the passenger terminal. In 1990, a 10-gate extension to Concourse B was completed. On January 22, 1995, a new Air Traffic Control Tower began operation. In the early 2000s, the Airport's Arrivals Terminal underwent construction. From 2000 to present day, the Airport has added new concessions, built new Aircraft Rescue and Firefighting (ARFF) facilities, and implemented renovations to the terminal building and general aviation facilities. As of May 2018, ORF owns 1,300 acres of land[1], approximately 212 acres of which are located outside of the ORF operational area.



Source: USGS Geology Survey (left), Norfolk International Airport (right)

### 1.2.2 Location and Service Area

Norfolk International Airport is a major airport for Southeastern coastal Virginia and northeastern North Carolina. As shown in **Figure 1-2** and **Figure 1-3**, the Airport is within 12 miles of downtown Norfolk and is located one mile east of Interstate I-64. As the primary commercial service airport in the America's First Region, which is tied to the Hampton Road's Partnership (a public-private partnership for economic development), the Airport's service area extends beyond Norfolk and into other parts of Virginia and northern North Carolina. ORF's location, regarding time[2] and distance in nautical miles (nm), in comparison to other major airports is as follows:

- Newport News/Williamsburg International Airport (PHF) – 20 nm; 40-minute drive; northwest of ORF
- Richmond International Airport (RIC) – 65 nm; 90-minute drive; northwest of ORF

The Airport is located within the Virginia Beach-Norfolk-Newport News VA-NC Metropolitan Statistical Area (MSA). The MSA, with a population of approximately 1.7 million people (Woods & Poole Economics, Inc., 2017), consists of the following cities and counties:

- Cities in Virginia – Chesapeake, Franklin, Hampton, Newport News, Norfolk, Poquoson, Portsmouth, Suffolk, Virginia Beach, and Williamsburg

[1] Norfolk Airport Authority, "Norfolk International Airport History," Norfolk International Airport website, https://www.norfolkairport.com/about-us/mission-history, accessed November 15, 2017.

[2] Drive times may be impacted during certain times of the day due to traffic congestion and/or construction activity.

- Counties in Virginia – Gloucester, Isle of Wight, James City, Mathews, Southampton, and York
- Counties in North Carolina – Camden, Chowan, Currituck, Hertford, Pasquotank, and Perquimans

### 1.2.3 Airport Role

In addition to connecting the America's First Region to the global transportation network, the Airport plays a significant role in the nation's air travel system. The National Plan of Integrated Airports Systems (NPIAS) identifies existing and proposed airports that are important to national air transportation and provides a forward-looking estimate of the type and cost of Airport Improvement Program (AIP)-eligible development needed to meet the needs of civil aviation. Airports included in the NPIAS are considered significant to national air transportation and are eligible to receive grants under the FAA's Airport Improvement Program (AIP).

The NPIAS further categorizes the nation's airports based on types of service provided and quantity of passengers enplaned. In the 2017 to 2021 NPIAS, ORF is classified as a small-hub primary commercial service airport. Small hubs are defined as airports that enplane 0.05 percent to 0.25 percent of total U.S. passenger enplanements. The 72 small hub airports account for nine percent of all U.S. enplanements. **Table 1-2** outlines the specifics of each NPIAS category and provides examples of each type in the region.

**Table 1-2 – NPIAS Airport Classifications**

| Airport Classifications | | Hub Type: % of Annual Passenger Boardings | Example Airport |
|---|---|---|---|
| **Commercial Service**: *Publicly owned airports that have at least 2,500 passenger boardings each calendar year and receive scheduled passenger service* | **Primary**: *Have more than 10,000 passenger boardings each year* | **Large Hub**: *1% or more* | Ronald Reagan Washington National Airport (DCA)<br>Washington Dulles International Airport (IAD) |
| | | **Medium Hub**: *At least .25%, but less than 1%* | Pittsburgh International Airport (PIT) |
| | | **Small Hub**: *At least .05%, but less than .25%* | **Norfolk International Airport (ORF)** |
| | | **Non-hub Primary**: *More than 10,000, but less than .05%* | Newport News/Williamsburg International Airport (PHF) |
| | **Non-primary** | **Non-primary Commercial Service**: *At least 2,500, and no more than 10,000* | Shenandoah Valley Regional Airport (SHD) |
| **Non-primary** (*Except Commercial Service*) | | **Reliever** | Chesterfield County Airport (FCI) |
| | | **General Aviation** | Chesapeake Regional Airport (CPK) |


Source: FAA 2017-2021 NPIAS Report.




NORFOLK INTERNATIONAL AIRPORT
MASTER PLAN UPDATE

NOT TO SCALE

Figure 1-**2**
Location Map




NORFOLK INTERNATIONAL AIRPORT
MASTER PLAN UPDATE

NOT TO SCALE

Figure 1-3
Vicinity Map

## 1.3 AIRPORT GOVERNANCE

The NAA is a political subdivision of the Commonwealth of Virginia and is an independent agency of the City of Norfolk. The Authority is governed by a Board of Commissioners consisting of up to nine members appointed by Norfolk City Council for four-year terms, as well as an Executive Director that manages routine operations at the Airport. The Board is made up of representatives from various organizations and backgrounds.

## 1.4 MAJOR AIRPORT TENANTS

The Airport hosts a variety of aviation and non-aviation tenants that provide services to the traveling public and aviation community. The major tenants include the airlines, air cargo operators, FBO/GA facilities, a Maintenance Repair and Overhaul (MRO) facility, concessionaires, and rental car companies.

### 1.4.1 Passenger Airlines

At the commencement of the Study, ORF was ranked as the 70th largest primary airport in the United States in passenger arrivals and 72nd in passenger departures, serving over three-million passengers annually. Six airlines provide scheduled passenger service at the Airport. When the Study began, these airlines at ORF offered daily, non-stop service to 23 domestic destinations[3], as depicted in **Figure 1-4** and **Table 1-3**. Domestic service is primarily to key markets and hubs in the Northeast, Midwest, and South, as well as leisure markets in Florida.

The commercial passenger service airlines at ORF are:

*Allegiant Air (Allegiant)*

*American Airlines (American)*

*Delta Air Lines (Delta)*


*Frontier Airlines (Frontier)*[4]

*Southwest Airlines (Southwest)*

*United Airlines (United)*

[3] Additional destinations have been added since the development of the Inventory.

[4] Services began in August 2018.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

NOT TO SCALE

**Figure 1-4**

ORF Non-Stop Route Map

*The map has been updated since completion of the Inventory to include recent service announcements (as discussed in **Chapter 3**, **Table 3-5**).

**Table 1-3 – Non-Stop Air Service Destinations**

| Airlines | Destinations |
|---|---|
| Allegiant | Fort Lauderdale-Hollywood International Airport (FLL), Jacksonville International Airport (JAX), St. Pete-Clearwater International Airport (PIE), Orlando Sanford International Airport (SFB) |
| American | Charlotte Douglas International Airport (CLT), Ronald Reagan Washington National (DCA), Dallas/Fort Worth International Airport (DFW), John F. Kennedy International Airport (JFK), LaGuardia Airport (LGA), Miami International Airport (MIA), Chicago O'Hare International Airport (ORD), Philadelphia International Airport (PHL) |
| Delta | Hartsfield-Jackson Atlanta International Airport (ATL), Boston Logan International Airport (BOS), Detroit Metropolitan Wayne County Airport (DTW), John F. Kennedy International Airport (JFK), LaGuardia Airport (LGA), Minneapolis-St. Paul International Airport (MSP) |
| Frontier | Denver International Airport (DEN), Orlando International Airport (MCO) |
| Southwest | Baltimore Washington International Airport (BWI), Orlando International Airport (MCO), Chicago Midway International Airport (MDW) |
| United | Denver International Airport (DEN), Newark Liberty International Airport (EWR), Washington Dulles International Airport (IAD), George Bush Intercontinental Airport (IAH), Chicago O'Hare International Airport (ORD) |

Note: Destinations presented represent those at the time the Inventory was developed. Additional service routes have since been added but are not reflected in this table.
Source: Airline Tenants, 2017.

### 1.4.2 Air Cargo Operators

ORF has two dedicated air cargo terminals and includes an aircraft parking apron dedicated to the loading and unloading of aircraft. The Airport has several types of air cargo activities being conducted including small freight operations (belly cargo), dedicated freight operations (cargo integrators, i.e., UPS, FedEx), and other all-cargo freight forwarding services. Most domestic passenger airlines listed in **Section 1.4.1** have transport cargo on scheduled passenger flights using the spare volume in the aircraft's baggage hold, or belly, that is not being used for passenger luggage. These operations include air freight and airmail services.

The cargo airlines that have regular operations at ORF include:

*Federal Express (FedEx)*

*Mountain Air Cargo (MAC)*

*United Parcel Service (UPS)*

FedEx and UPS are known as integrated carriers. Integrated carriers are companies that transport cargo via air, as well as ground-vehicular methods, such as delivery through the United States Postal Service (USPS). Mountain Air Cargo (MAC) provides cargo flight and maintenance services in the eastern half of the United States and Caribbean Islands and is a contract carrier for FedEx.

### 1.4.3 Fixed-Base Operator (FBO)

Signature Flight Support, previously Landmark Aviation, is the single full-service FBO providing aviation services and amenities to the airlines, GA users, and pilots operating out of ORF. Signature Flight Support is the world's largest FBO and distribution network for business aviation services. A summary of the services offered by Signature includes aircraft fueling, deicing, maintenance, ground handling, hangar storage, and tie-down areas, as well as a business center, conference rooms with conference call capabilities, crew transportation services and capabilities, and crew rooms and rest areas.



Source: Signature Flight Support.

### 1.4.4 Maintenance, Repairs, and Overhaul (MRO)

The maintenance of aircraft is strictly regulated to ensure aircraft are meeting the requirements set forth to ensure airworthiness and safety while transporting passengers and cargo. The MRO facility at ORF, located in the general aviation area, is leased to PSA Airlines.



Source: Google Earth.

### 1.4.5 Military

ORF does not have any designated Military facilities on the airfield; however, the Airport does recognize military personal through various services and facilities. On the second level of the Arrivals Terminal above baggage claim, active duty and retired military, as well as their families can utilize the Airport's United Service Organizations (USO) Welcome Center. Military personnel also receive discounts on ground

transportation services at the Airport, as well as discounts at all of the Airport's retail shops and restaurants. The airlines providing services at ORF often extend discounted rates, per airline policy, to active duty military personnel and their dependents.

### 1.4.6 Rental Car Companies

Eight rental car companies provide services at ORF, along with one off-site service provider. Each on-site company has a separate counter in the Arrivals Terminal, dedicated ready parking in the parking garage, and return parking on the second level of Garage A. Quick Turn Around (QTA) services and vehicle maintenance for all rental car companies are handled off-site on Military Highway. The rental car operators at ORF have indicated that this split operation has created efficiency and safety issues, warranting some attention in future planning.

The rental car companies operating at ORF are:

*Alamo*

*Avis*

*Budget*

*Dollar Rent a Car*

*Enterprise*

*Hertz*

*National*

*Thrifty*

*Payless* (Off-Site)

### 1.4.7 Concessionaires

Concessionaires at an airport provide travelers in the sterile and non-sterile/non-secured areas (defined in **Section 1.4.8**), as well as meeters/greeters in the non-sterile area, with amenities such as restaurants / food vendors, newsstands, gift shops, and foreign currency exchange.

The following concessionaires operate at ORF:

*HMS Host*

*Hudson Group*

*Travelex*

### 1.4.8 Department of Homeland Security

The Department of Homeland Security provides ORF with services from the Transportation Security Administration (TSA), as well as Customs and Border Protection (CBP). Airports and airlines are required to meet security regulations established in Title 49 Code of Federal Regulations (CFR) Part 1542, *Airport Security,* and Title 49 CFR Part 1540, *Civil Aviation Security: General Rules*. As set forth in Title 49 CFR Part 1540.5, the "sterile area" refers to the most restrictive areas of the Airport (e.g. the concourses) and cannot be accessed by the public or badged personnel until being processed through security measures specified in 49 CFR Part 1542. "Secured areas" are areas outside the concourse that are accessible only to badged personnel (proximity of baggage makeup and aircraft parking). "Non-sterile/non-secure areas" do not have regulated security measures and are accessible to the general public. The Security Identification Display Area (SIDA), means that all personnel must display a SIDA badge issued by ORF. SIDA areas can include non-secure areas, as well as the airfield.

CBP is responsible for processing international passengers and baggage arriving at the Airport from international airports that do not have pre-screening facilities. CBP does not process passengers departing the Airport. Airlines are responsible for adequately screening passengers prior to departure.

## 1.5 STUDY FOCUS AREA

The ORF Master Plan Update encompasses the current utilization and operational characteristics of the Airport, which includes the passenger terminal complex, general aviation facilities, landside facilities, ground access, the airfield and airfield support areas, and future land development areas. The study focus area is bounded by the following:

- North – Norview Avenue
- Northeast – Airport Parking Departure Road and the Norfolk Botanical Garden
- East – Lake Whitehurst and U.S. 60
- South – Miller Store Road
- West – Military Highway (from Hampton Roads Beltway to Croft Street)
- Northwest – Robin Hood Road (east of Gurley Street) and Airport Road

# 2 INVENTORY OF FACILITIES AND EXISTING CONDITIONS

The initial step in the master planning process was to develop an inventory of the existing physical conditions and operational characteristics of the Airport and its surroundings. The information presented in this chapter was the basis for evaluating the Airport's existing and future facility requirements. The following elements are detailed in this chapter:

- Airfield
  - Airport Design Criteria
  - Runway System
  - Taxiway System
  - Aircraft Parking Aprons
  - Airfield Markings
  - Airfield Signage
  - Airside Pavement Condition
- Navigational Aids (NAVAIDs) and Instrument Procedures
  - En-Route NAVAIDs
  - Standard Terminal Arrival Routes
  - Types of Instrument Approach Procedures and Instrument Approach NAVAIDs
  - Standard Instrument Departures
  - Airfield Lighting
- Terminal Facility
  - Terminal Facility Layout
  - Terminal Building Functional Areas
  - Airline Ticketing Lobby
  - Checked Baggage Screening
  - Passenger Security Screening
  - Airline Gates and Holdrooms
  - Terminal Concessions and Amenities
  - Baggage Claim
  - Rental Car Counters
  - Airport Administrative and Support Areas
  - Airline Service and Support Areas
  - Concession Storage and Support Areas
  - Back Office Space
  - Federal Inspection Services (FIS)
  - Terminal Signage and Wayfinding
- Automobile Access and Parking
- Support Facilities
  - Airport Perimeter Fence
  - Airport Equipment Storage and Maintenance
  - Air Traffic Control Tower (ATCT)
  - Aircraft Rescue and Firefighting (ARFF)
  - Aircraft Fueling
  - Snow and Ice Control
  - Air Cargo Facilities
  - General Aviation (GA) Facilities and Activities
  - MRO Facility
  - Rental Car Facilities
- Airspace Environment
- Meteorological Conditions
  - Local Climate
  - Wind Coverage

## 2.1 AIRFIELD

The Airport's airside and airfield facilities generally include the facilities located within the airport perimeter fence that are most closely associated with the movement and operation of aircraft, such as taxiing, takeoff, landing, and parking. Additional elements related to airfield activity and infrastructure include the runway and taxiway systems, aircraft parking aprons and hangars, and airfield pavement, markings, signage, lighting, and NAVAIDs. The existing facilities, as well as descriptions of the characteristics and conditions are depicted in **Figure 2-1** and **Figure 2-2**.




Source: NAA.

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

NORVIEW AVENUE
RUNWAY 24 RPZ
Parking Structures
Taxi Staging Lot
Rental Car Return/Ready Lot
Arrivals Terminal
Main Passenger Terminal
Deicing Pad - RON/Diversion Parking (Four Positions)
TNC Staging Lot
Concourse B
ARFF
Fueling Facility
Glycol Storage Tanks
AIRPORT ROAD
Cargo Facilities
Employee Parking
ROBIN HOOD ROAD
RUNWAY 14-32 (4,875' x 150')
RUNWAY 5 RPZ
RUNWAY 5-23 (9,001' x 150')
RUNWAY 23 RPZ
VORTAC
Snow Removal Equipment Storage
MRO Facility
FBO Terminal/Hangar
Fuel Storage
HAMPTON ROADS BELTWAY
Airfield Maintenance
T-Hangars (FBO)
FBO Maintenance Shop
Bulk Hangars (FBO)
RUNWAY 32 RPZ
MILLER STORE ROAD
Air Traffic Control Tower (ATCT)

- Property Line
- RPZ
- Permimeter Fence
- Terminal Complex
- Support Facilities
- Runways
- Taxiways
- Aprons

**Figure 2-1**
Existing Facilities

**NORFOLK INTERNATIONAL AIRPORT**

# MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)
0 600 1200

| # | Name of Existing Facility |
|---|---|
| 1 | Main Terminal Complex |
| 2 | Automobile Parking Garage |
| 3 | Airfield Lighting Vault |
| 4 | Triturator |
| 5 | Arrivals Building and Baggage Claim |
| 6 | Aircraft Rescue and Firefighting Station |
| 7 | ARFF Storage Building |
| 8 | Air Cargo Building |
| 9 | Air Cargo Building |
| 10 | Catering Facility |
| 11 | FAA Remote Communications Facility |
| 12 | TNC Staging Area |
| 13 | FAA Support Building |
| 14 | FAA Air Traffic Control Tower |
| 15 | Fuel Farm |
| 16 | Former FAA Support Buildings (Abandoned) |
| 17 | Ground Run-Up Enclosure (GRE) |
| 18 | FAA Support Building |
| 19 | FAA ASR-9 Radar |
| 20 | GA Terminal/Hangar Facility C-1 |
| 21 | Hangar C-2 |
| 22 | Hangar C-2 |
| 23 | T-Hangar Building #1 |
| 24 | T-Hangar Building #2 |
| 25 | T-Hangar Building #3 |
| 26 | Aircraft Maintenance Hangar |
| 27 | Airfield Maintenance Facility |
| 28 | General Aviation Fuel Farm |
| 29 | ARFF Training Facility |
| 30 | Hangar C-5 |
| 31 | Hangar C-3 |
| 32 | Hangar C-4 |
| 33 | FBO Maintenance Shop |
| 34 | Airfield Maintenance Building |
| 35 | Long-Term Parking Lot |
| 36 | Short-Term Parking Lot |
| 37 | VOR Facility |

**Figure 2-2**
Building Diagram

### 2.1.1 Airport Design Criteria

The FAA uses a classification system, known as the Airport Reference Code (ARC), to signify the airport's highest Runway Design Code (RDC), the design standards to which the runway is to be built. RDC consists of three components: aircraft approach speed (AAC), airplane design group (ADG) relating to either the aircraft wingspan or tail height (whichever is more restrictive), and visibility minimums. ARC is determined by taking the highest RDC minus the visibility component. It affects runway and taxiway dimensions, separation standards, pavement marking standards, and other safety standards. Furthermore, it is used for planning and design only and does not limit the aircraft that may be able to operate safely at the airport. The relationship between the ARC and design standards is further described in FAA AC 150/5300-13A, *Airport Design*. The characteristics of the RDC are shown in **Table 2-1**.

As previously noted, the ARC is based on an aircraft's approach speed and wingspan or tail height, whichever is most restrictive. The most demanding aircraft is commonly referred to as the critical, or design, aircraft and must account for a minimum of 500 annual itinerant operations. An itinerant operation is the takeoff or landing of an aircraft going from one airport to another, at least 20-miles from each other. The ARC consists of a letter designating the aircraft approach category and a Roman numeral designating the Airplane Design Group (ADG). ORF is currently designated with an ARC D-IV. The critical aircraft at ORF is the Boeing 757-200.

Approach categories A and B include small piston-engine aircraft and corporate jets with approach speeds of less than 121 knots, while categories C, D, and E include larger aircraft with approach speeds of 121 knots or greater (those typically associated with commercial or military use). Similarly, design groups I and II typically include small piston-engine aircraft and light to midsize corporate jets, as well as single- and twin-engine turboprop aircraft. Design groups III, IV, and V include larger corporate jets and the majority of the commercial jet fleet, as well as numerous military aircraft. Design group VI includes very large jets such as the Airbus A380 and the military C-5 transport aircraft.

TDG represents the Taxiway Design Group, which relates to the undercarriage dimensions of the aircraft. Preliminary review of operations data for 2016 indicates that the MD-88 (ADG C-III, TDG IV) is the most demanding passenger aircraft and the B757 (ADG D-IV, TDG IV) is the most demanding cargo aircraft that operates regularly at ORF with over 500 annual operations. The existing and future ARC are analyzed in greater detail in **Chapter 4**, *Facility Requirements*.

**Table 2-1 – Airport Reference Code**

| Approach Categories | | |
|---|---|---|
| **Approach Category** | **Airspeed (Knots)** | **Example Aircraft** |
| A | <91 | Beechcraft-E33 Bonanza, Cessna 152 |
| B | 91 ≤ 121 | CRJ-200, ERJ-135/140/145 |
| C | 121 ≤ 141 | B737-700W, MD-88 |
| D | 141 ≤ 166 | A300, B757 |
| E | 166+ | B-52H, B-2 Spirit |

| Airplane Design Group | | | |
|---|---|---|---|
| **Design Group** | **Tail Height (feet)** | **Wingspan (feet)** | **Example Aircraft** |
| I | <20 | <49 | Beechcraft-E33 Bonanza, Cessna 152 |
| II | 20-<30 | 49 ≤ 79 | CRJ-700, ERJ-145 |
| III | 30-<45 | 79 ≤ 118 | A319, CRJ-900 |
| IV | 45-<60 | 118 ≤ 171 | Boeing 757, MD 11 |
| V | 60-<66 | 171 ≤ 214 | A300, B757 |
| VI | 66-<80 | 214 ≤ 262 | B-52H, B-2 Spirit |

Source: FAA AC 150/5300-13 *Airport Design*, CHA, 2017.

### 2.1.2 Runway System

The existing airfield configuration at ORF consists of two intersecting runways, identified as Runway 5/23 and Runway 14/32. Runway 5/23 is oriented in a northeast/southwest direction, and Runway 14/32 is oriented in a northwest/southeast direction. **Table 2-2** presents the characteristics of each runway.

ORF's primary runway, Runway 5/23, is situated east of the terminal building. The runway is 150 feet wide and has a usable runway length of 8,001 feet, accompanied by a 1,000-foot-long displaced threshold, for a total pavement length of 9,001 feet. It is constructed of both asphalt and concrete, has a grooved surface, and is supplemented by 12.5-foot wide, paved shoulders along the asphalt-paved portion. The runway's load-bearing capacity is 150,000 pounds single-wheel; 200,000 pounds dual-wheel; 350,000 pounds duel tandem; and 475,000 pounds dual double tandem.

Situated south of the terminal building, Runway 14/32 is the Airport's crosswind runway. The runway is 150 feet wide and has a usable runway length of 4,300 feet, with a 575-foot displaced threshold, for a total pavement length of 4,875 feet. It is constructed of asphalt and has a grooved surface. The runway's load-bearing capacity is 75,000 pounds single-wheel and 100,000 pounds dual-wheel.

**Table 2-2 – Existing Runway Specifications**

| | Runway 5/23 | Runway 14/32 |
|---|---|---|
| Runway Length (feet) | 9,001 | 4,875 |
| Displaced Threshold (feet) | 1,000 | 575 |
| Width (feet) | 150 | 150 |
| Runway End Elevation (feet above MSL) | **Runway 5:** 18.1<br>**Runway 23:** 15.5 | **Runway 14:** 18.2<br>**Runway 32:** 22.1 |
| Pavement Type | Asphalt/Concrete/Grooved | Asphalt/Grooved |
| Pavement Load Bearing | 475,000 lbs.<br>(Dual Double Tandem) | 100,000<br>(Dual-Wheel) |
| Effective Runway Gradient | 0.1% | 0.1% |
| Aircraft Approach Category | D | C |
| Airplane Design Group | IV | III |
| Runway Markings | Precision | Non-Precision |
| Runway and Approach Lighting | HIRL, C/L<br>**Runway 5:** TDZL, PAPI-4, MALSR<br>**Runway 23:** PAPI-4, MALSR | MIRL, REIL<br>**Runway 14:** PAPI-2<br>**Runway 32:** PAPI-2 |
| Navigational Aids | ILS/DME, RNAV (RNP, GPS) | VOR/DME, RNAV (GPS) |
| Runway Design Code | D-IV | C-III |

Sources: AirNav.com; FAA Form 5010-1, *Airport Master Record-February 2018*, CHA, 2017.

C/L – Centerline Lights
DME – Distance Measuring Equipment
GPS – Global Positioning System
HIRL – High Intensity Runway Lights
ILS – Instrument Landing System
MALSR – Medium-Intensity Approach Lighting System with Runway Alignment Indicator
MIRL – Medium-Intensity Runway Lighting
PAPI-4 – Four-Box Precision Approach Path Indicator
PAPI-2 – Two-Box Precision Approach Path Indicator
REIL – Runway End Identifier Lights
RNAV – Area Navigation
RNP – Required Navigational Performance
TDZL – Touchdown Zone Lights

### 2.1.3 Taxiway System

An airport's taxiway system connects the runways to aircraft parking aprons, storage hangars and other facilities. ORF has nine operative taxiways. The Airport also utilizes one taxiway holding bay at the Runway 23 approach end. A taxiway holding bay allows standing space for an aircraft that is waiting to receive takeoff clearance or small piston aircraft performing ground run-up procedures to allow aircraft already cleared for takeoff to move to their runway takeoff position. **Table 2-3** provides the characteristics and specifications of each taxiway. **Figure 2-3** displays the existing taxiway system at ORF.

## Table 2-3 – Existing Taxiway Specifications

| Taxiway | Description | Width (feet) | Airplane Design Group (ADG) | Taxiway Design Group (TDG) | Taxiway Shoulder (feet) |
|---|---|---|---|---|---|
| A | Provides access from TWY 'C' and from the GA area to RWY 5/23; Provides access from the GA area to RWY 32; Provides access to TWY 'J'. | 75 | IV | 5 | 30 |
| B | Provides access from RWY 5/23 to TWY 'C' / Terminal Ramp (Highspeed TWY). | 75 | IV | 5 | 40 |
| C | Parallel to RWY 5/23 and the Terminal Ramp. | 75 | IV | 5 | 40 |
| E | Provides access from RWY 5/23 to TWY 'C' | 75 | IV | 5 | 40 |
| F | Connects RWY 5/23 to RWY 32; Provides access to Ground Run-up Enclosure (GRE) | 50 | III | 3 | 20 |
| G | Provides access from RWY 5/23 to TWY 'C' / Terminal Ramp (Highspeed TWY); Connects RWY 5/23 to TWY 'F' and RWY 32. | 75 | IV | 5 | 40 |
| H | Provides access from RWY 5/23 to TWY 'C' | 75 | IV | 5 | 30 |
| J | Partial Parallel to RWY 5/23; Connects TWY 'A' and RWY 5 | 75 | IV | 5 | 30 |
| V | Partial Parallel to RWY 14/32 and the Cargo Ramp; Provides access to RWY 14/32 and TWY 'C' from the Cargo Ramp | 75 | IV | 5 | 30 |

Source: FAA Airport Diagram, AC 150/5300-13A, CHA 2017.


RWY – Runway

TWY – Taxiway

GRE – designated area for mitigating noise disturbance from aircraft running-up engines prior to takeoff

.

| Taxiway | Width (feet) | Airplane Design Group (ADG) | Taxiway Design Group (TDG) |
|---|---|---|---|
| A | 75 | IV | 6 |
| B | 125 | IV | 7 |
| C | 100 | IV | 7 |
| D (Closed) | 70 | N/A | N/A |
| E | 125 | IV | 7 |
| F | 50 | III | 4 |
| G | 100 | IV | 7 |
| H | 75 | IV | 6 |
| J | 75 | IV | 6 |
| V | 75 | IV | 6 |




**NORFOLK INTERNATIONAL AIRPORT**
MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)
0 500 1000

**Figure 2-3**
Taxiway Configuration

### 2.1.4 Aircraft Parking Aprons

Airport aprons, also referred to as ramps, provide space for short-term and long-term aircraft parking and deicing operations, as well as the loading/unloading of passengers and goods. As depicted in **Figure 2-4** and described below, ORF has three aprons: a terminal apron, a general aviation/Fixed Base Operator (FBO) apron, and an air cargo apron.

**Figure 2-4 – Aircraft Parking Aprons**




Source: Norfolk International Airport, CHA 2017.

***Terminal Apron***

The terminal apron consists of approximately 2,000,000 square feet of cement/concrete pavement. Activities on the terminal apron primarily include passenger airline and belly cargo loading and unloading. The terminal has 23 gate positions. **Table 2-4** provides gate specifications, while a schematic of the gate layout is presented in **Figure 2-5.** Approximately 371,591 square feet of the apron is utilized for gate parking at Concourse A, and approximately 528,842 square feet of the apron is utilized for gate parking at Concourse B. The remainder of the apron is utilized for aircraft maneuvering, Remain Overnight Parking (RON), and aircraft deicing services.

**Table 2-4 – Gate Specifications**


| Gate Position | Apron Area (Sq. Feet) | Aircraft Design Group |
|---|---|---|
| Gate A1 | 41,370 | III |
| Gate A2 | 35,096 | III |
| Gate A3 | 34,155 | III |
| Gate A4 | 45,195 | III |
| Gate A5 | 28,980 | III |
| Gate A6 | 32,747 | III |
| Gate A7 | 28,834 | III |
| Gate A8 | 35,616 | III |
| Gate A9 | 27,712 | III |
| Gate A (Unassigned) | 29,270 | III |
| Gate B16 | 31,121 | II |
| Gate B17 | 37,849 | III |
| Gate B18 | 37,932 | III |
| Gate B19 | 44,962 | III |
| Gate B20 | 59,715 | III |
| Gate B21 | 40,854 | III |
| Gate B23 | 42,400 | III |
| Gate B24 | 31,829 | III |
| Gate B25 | 26,793 | III |
| Gate B26 | 31,484 | II |
| Gate B27 | 33,480 | III |
| Gate B28 | 30,429 | II |
| Gate B29 | 30,291 | III |
| Gate B30 | 49,703 | III |

Source: NAA, 2017.

ADG III (Example Aircraft): A320-200, Boeing 737-300, EMB 170 STD

ADG II (Example Aircraft): CRJ-700, ERJ 145

**Figure 2-5 – Gate Layout**




Source: Norfolk International Airport, CHA, 2017.

***General Aviation (GA) Use Aprons***

The GA apron area is broken-up into sections including bulk hangars and T-hangars. The total apron area comprising the GA area is approximately 709,200 square feet. These aprons provide parking for transient aircraft, allow access to the GA facilities and fixed-base operator facilities, and provide space for aircraft tie-downs.

***Air Cargo Use Aprons***

The air cargo-dedicated area, which is shared by FedEx, Mountain Air Cargo, and UPS, is served by one apron. The apron is used for cargo transfer operations, aircraft storage, and maintenance. The apron, measuring approximately 265,000 square feet, is located on the east side of the cargo facilities and south of Runway 14/32.

***Remain Overnight (RON) and Diversion Ramp Parking***

At ORF, remain overnight (RON) and diversion parking support operations for commercial and general aviation traffic. RON and diversion parking at ORF vary for each airline. The RON aircraft park overnight at gates or designated RON parking stands on the terminal ramp, or in hangars located on the southside of the airfield.

American Airlines typically has six RON aircraft. Two of the aircraft are positioned on the terminal ramp, while the remaining four aircraft park inside hangars in the GA area. Delta Air Lines leases

four gates for regularly scheduled arrivals and departures. A fifth gate is leased for overnight operations. Delta utilizes all five gates (Gates B19, B21, B23, B24, & B25) for RON aircraft, with three additional RON aircraft parked on the terminal ramp. Southwest has two RON aircraft that utilize Gates A3 and A5. United regularly has two RON aircraft that each utilize one of United's leased gates (Gates B27, B28, B29, & B30). Allegiant does not have scheduled RON aircraft at ORF. Airlines have advised the potential for an increase for RON aircraft in the short-term.

An aircraft diversion is when an aircraft that was originally intended to fly to a specific airport unexpectedly experiences a situation requiring the pilot to change his or her route to an alternate airport. ORF can accommodate diverted aircraft on a case-by-case basis and, on occasion, provide terminal gate parking if available. When gate parking is not available, the diverted aircraft are parked on the northeast side of the main terminal apron where the RON parking positions and deicing operations are performed during unfavorable weather conditions.

### 2.1.5 Airfield Markings

FAA AC 150/5340-1L, *Standards for Airport Markings*, provides the standards for surface markings used on airfield roadways and airfield pavements, such as runways, taxiways, and aprons, assuming the surfaces are built in accordance to the standard dimensions and layouts in AC 15/5300-13, *Airport Design* (this excludes privately owned apron areas). The most recent version of this guidance was published in September 2013; however, the FAA released a draft version of FAA AC 150/5340-1M in March 2017 that includes new standards for enhanced taxiway centerline markings, surface-painted hold sign markings and the extension of the runway holding position markings onto the paved shoulders. These standards apply to all airports certificated under Title 14 CFR Part 139, which establishes certification requirements for airports serving scheduled air carrier operations in aircraft designed for more than nine passenger seats but fewer than 31 passenger seats. Examples of airfield markings are provided in **Table 2-5**, **Figure 2-6**, and **Table 2-6**.

**Table 2-5 – Runway Markings**

| Type of Marking | Purpose of Marking |
|---|---|
| Designation | Numbers and letters are determined from approach direction; labeled according to Compass Rose |
| Centerline | Identifies the center of the runway; Provides alignment guidance during takeoff and landings |
| Threshold | Delineates the beginning of the runway that is available for landing |
| Aiming Point | Serve as a visual aiming point for a landing aircraft, located approximately 1,000 feet from the landing threshold |
| Touchdown Zone | Identify the touchdown zone for landing operations and are coded to provide distance information in 500 feet increments |
| Runway Edge Marking | Define the edge of the usable, full-strength surface |

**Figure 2-6 – Runway Markings**








**Table 2-6 – Taxiway Markings**

| Type of Marking | Purpose of Marking | Visual Representation of Marking |
|---|---|---|
| Normal Centerline | Provides a visual cue to permit taxiing along a designated path |  |
| Enhanced Centerline | Intended to warn the pilot that he/she is approaching a runway holding position marking and should prepare to stop unless he/she has been cleared onto or across the runway by ATC; Usually at larger, commercial service airports |  |
| Edge Markings | Continuous- Define the taxiway edge from the shoulder or other abutting paved surface not intended for use by aircraft; Dashed- Defines the taxiway edge from the adjoining pavement intended for use by aircraft |  |
| Shoulder Markings | Identifies paved shoulders (areas intended to prevent blast and water erosion); not intended for use by aircraft (may not be full-strength pavement) |  |
| Runway Holding Position | Indicate where an aircraft is supposed to stop when approaching a runway |  |
| Taxiway/Taxiway Intersection | Indicate where an aircraft is supposed to stop when approaching intersecting taxiways |  |

### 2.1.6 Airfield Signage

According to Title 14 CFR Part 139.311, *Marking, Signs, and Lighting*, each certificate holder, such as ORF, must provide and maintain sign systems for air carrier operations on the airport that are authorized by the Administrator and consist of at least the following:

- Signs identifying taxiing routes on the movement area.
- Holding position signs.
- Instrument Landing System (ILS) critical area signs.

The holding position signs, as well as the ILS critical area signs, must be internally illuminated. FAA AC 150/5340-18F, *Standards for Airport Sign Systems*, contains all regulations pertaining to airfield signage for Part 139 airports, while specifications are contained in AC 150/5345-44K, *Specifications for Runway and Taxiway Signs*. A further description of typical airfield signage is

included in **Table 2-7**. See AC 150/5340-18F's Glossary of Sign Types for additional sign type descriptions.

Upon visual inspection, lighted airfield signage currently found on ORF's airfield consists of all required signage for a Part 139 certificated airport including airfield location signage, mandatory instruction signage, and runway hold position signage. An airfield signage project is currently underway and is expected to be completed in during the summer of 2020; however, additional signage may be required to accommodate future improvements or additions to airfield pavements.

**Table 2-7 – Airfield Signage**

| Type of Sign | Purpose of Sign | Visual Description of Sign |
|---|---|---|
| Mandatory Instruction Sign | Denote taxiway/runway intersections, runway/runway intersections, Instrument Landing System (ILS) critical areas, Precision Obstacle Free Zone (POFZ) boundaries, runway approach areas, CAT II/III operations area, military zones, and no entry zones | White Inscription/Red Background |
| Location Sign | Identify the taxiway or runway apron upon which the aircraft is located | Yellow Inscription/Black Background |
| Boundary Sign | Identify the boundary of the Runway Safety Area (RSA)/Object Free Zone (OFZ) or ILS critical are for a pilot exiting the runway | Black Inscription/Yellow Background |
| Directional Sign | Indicate directions of other taxiways leading out of an intersection | Black Inscription/Yellow Background; Always Contains an Arrow |
| Destination Sign | Indicate the direction to a remote location | Black Inscription/Yellow Background; Always Contains an Arrow |
| Runway Distance Remaining Sign | Provide distance remaining information to pilots during takeoff and landing operations | White Inscription/Black Background |

Source: FAA AC 150/5340-18F.

### 2.1.7 Airfield Pavement Condition


ORF has an established pavement management plan (PMP) that provides a consistent and systematic procedure for making decisions about pavement maintenance and rehabilitation. The load-carrying capacity of the pavement for unrestricted operations is expressed as a Pavement Classification Number (PCN). According to AC 150/5335-5C, *Standardized Method of Reporting Airport Pavement Strength-PCN*, in 1977, the International Civil Aviation Organization (ICAO) adopted the Aircraft Classification Number-Pavement Classification Number (ACN-PCN) method. The PCN is a five-part number which includes a numerical PCN value [indicating the load-carrying capacity of a pavement (between 0 and 100)], pavement type (flexible-F or rigid-R), subgrade category (high-A, medium-B, low-C, ultra-low-D), allowable tire pressure (unlimited/no pressure-W, high/pressure limited to 254 psi-X, medium/pressure limited to 181 psi-Y, and low/pressure limited to 73psi-Z), and the method used to determine the PCN (via technical study-T or evaluation based on using aircraft experience-U). The PCN for each runway at ORF is shown in **Table 2-8**, while existing airfield pavement conditions are shown in **Figure 2-7**.

**Table 2-8 – Airside Pavement Condition**

| Runway | PCN Classification | Numerical Value (0-100) | Pavement Type | Subgrade Strength Category | Allowable Tire Pressure | Method |
|---|---|---|---|---|---|---|
| 5/23 | PCN 53/R/C/W/T | 53 | Rigid | Low | Unlimited / No-Pressure | Technical Study |
| 14/32 | PCN 27/F/A/W/T | 27 | Flexible | High | Unlimited / No-Pressure | Technical Study |

Note: psi (pounds per square inch); Source: NAA, 2018.

Source:
*ORF 2016 Pavement Management System Update* -
Applied Pavement Technology,
Delta Airport Consultants




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

NOT TO SCALE

## LEGEND

PAVEMENT CONDITION INDEX





**Figure 2-7**
Existing Airfield
Pavement Conditions

## 2.2 NAVIGATIONAL AIDS (NAVAIDS) AND INSTRUMENT PROCEDURES

Pilots utilize a variety of navigational aids (NAVAIDs) and instrument procedures, including Very High Frequency (VHF) Omni Direction Range (VORs), standard terminal arrival routes (STARs), instrument approach procedures (IAPs) and NAVAIDs, approach lighting systems (ALS), airfield lighting, and rotating beacons. By providing point-to-point guidance information or position data, NAVAIDs assist pilots to safely and efficiently locate airports, land aircraft, taxi aircraft, and depart from airports during nearly all meteorological conditions. **Table 2-9** summarizes the Airport's existing instrument approach procedures, by runway, and the NAVAIDs required.

**Table 2-9 – Navigational Aids (NAVAIDs) and Airfield Lighting**

| Runway | Runway Markings | Navigational Aids | Lighting | Minimum Ceiling (AGL)/ Visibility | Instrument Approach Types |
|---|---|---|---|---|---|
| 5 | Precision | ILS/DME, RNP, GPS | HIRL, PAPI-4, MALSR, C/L, TDZL | 200 ft. / ½ mile | ILS or LOC, RNAV (RNP), RNAV (GPS) |
| 23 | Precision | ILS/DME, RNP, GPS | HIRL, PAPI-4, MALSR, C/L | 200 ft. / ½ mile | ILS or LOC, RNAV (RNP), RNAV (GPS) |
| 14 | Non-Precision | GPS, VOR/DME | MIRL, PAPI-2, REIL | 500 / 1 mile | RNAV (GPS), VOR/DME |
| 32 | Non-Precision | GPS, VOR/DME | MIRL, PAPI-2, REIL | 500 / 1 mile | RNAV (GPS), VOR/DME |

Source: FAA Airport Master Record (Form 5010), Accessed 2017.

C/L – Centerline Lights
DME – Distance Measuring Equipment
GPS – Global Positioning System
HIRL – High Intensity Runway Lights
ILS – Instrument Landing System
MALSR – Medium-Intensity Approach Lighting System with Runway Alignment Indicator
MIRL – Medium-Intensity Runway Lighting
PAPI-4 – Four-Box Precision Approach Path Indicator
PAPI-2 – Two-Box Precision Approach Path Indicator
REIL – Runway End Identifier Lights
RNAV – Area Navigation
RNP – Required Navigational Performance
TDZL – Touchdown Zone Lights

### 2.2.1 En-route NAVAIDs

En-Route NAVAIDs assist pilots during navigation between airports. These facilities are usually ground-based and electronically emit signals that are received by aircraft on a specific radio frequency. They are almost always used in some manner by pilots operating on Instrument Flight Rule (IFR) flight plans but can also be used during Visual Flight Rule (VFR) flights for position information. At ORF, Runway 14 and Runway 32 utilize VOR/DME, which are ground-based en-route NAVAIDs.

### 2.2.2 Standard Terminal Arrival Routes (STARs)

Standard Terminal Arrival Routes (STARs) are preplanned IFR air traffic control arrival procedures published for pilot use. STARs serve as a critical form of communication between pilots and ATC by providing a method and criteria for descent, routing, and communications when navigating to the destination after leaving the en-route structure. The STAR and approach procedures virtually connect to each other in such a way as to create a seamless transition.

Once a flight crew has accepted a clearance for a STAR, they have communicated with the controller what route, and in some cases what altitude and airspeed, they will fly during the arrival, depending on the type of clearance.

When air traffic is arriving to the Norfolk region, ORF's ATC has two STAR procedures: *DRONE ONE* and *TERKS TWO*. The *DRONE ONE* arrival utilizes the *RALEIGH/DURHAM and KINSTON* VORTACs (RDU and ISO, respectively), which feed traffic from the west and south. The *TERKS TWO ARRIVAL* utilizes the *MONTEBELLO (MOL) VOR/DME* intersection, which feeds traffic from the north.

### 2.2.3 Types of Instrument Approach Procedures (IAPs) and Instrument Approach NAVAIDs

Based on current FAA classifications, there are four types of instrument approach categories:

- Visual (V) – Approaches performed under visual flight rules only, when meteorological conditions include a cloud ceiling height of 1,000 feet or greater and visibility of 3 miles or greater. None of the runways at ORF operate strictly under this category.
- Non-Precision Approach (NPA) – Instrument approach procedures providing only lateral guidance with a ceiling minimum of 400 feet above the threshold. These can include VHF Omnidirectional Range (VOR), non-directional beacon (NDB), area navigation (RNAV), lateral navigation (LNAV), localizer performance (LP), and localizer (LOC) equipment. At ORF, Runways 5, 23, 14, and 32 all have a NPA procedure.
- Approach Procedure with Vertical Guidance (APV) – Instrument approach procedures providing vertical guidance minimums of 250 feet above the threshold and visibility minimums as low as ¾ mile. These can include an ILS, LNAV/Visual Navigation Aids (VNAV), Localizer Performance with Vertical Guidance (LPV) or Area Navigation (RNAV) Required Navigation Performance (RNP). Runways 5, 23, 14, and 32 maintain this type of procedure.
- Precision Approach (PA) – Instrument approach procedures providing vertical guidance less than 250 feet above the threshold and visibility minimums lower than ¾ mile. These can include an ILS, LPV, and Global Navigation Satellite System (GNSS) Landing System (GLS). This category applies to Runways 5 and 23.

The precision approach is one component that determines the minimum ceiling and visibility for each runway (other variables may influence the minimums - obstructions to the approach, buildings, terrain, etc.). The NAVAIDs that make up the ground-based equipment required to perform the approach procedures are divided into two categories: precision and non-precision. The NAVAIDs supporting traditional ground-based precision approaches are collectively called an Instrument Landing System (ILS). According to FAA Order 6750.16E, *Siting Criteria for Instrument Landing Systems*, the ILS provides guidance to pilots of properly equipped aircraft to assist them in landing safely under conditions of reduced ceilings and lowered visibility. The Airport operates an ILS for approaches to Runway 5 and Runway 23.

Two components of an ILS include: a localizer (LOC) and a glide slope (GS). A localizer is situated 1,000 feet past the departure-end of the runway that has the approach and provides lateral positioning guidance to pilots. It utilizes radio frequencies (RF) to transmit signals to aircraft by focusing the RF beam down the centerline of the runway toward the approach end of the runway for approximately 10 miles, focused within 35 degrees to the left or right of the runway centerline. The glide slope is located near the runway approach end at a distance from the threshold to provide optimum crossing height, with a preferred offset of 400 feet from the

runway centerline. It transmits a signal for approximately 10 nautical miles, with a horizontal coverage of eight degrees on each side of the localizer course, measured from the origin of the glide slope beam. The glide slope must be established between 2.0 and 4.0 degrees and is typically established with a glide path angle of 3.00 degrees.

Additionally, all runways at ORF utilize Global Positioning System (GPS) based technology to enable vertically-guided instrument approach procedures with approach capabilities similar to ILS approaches without the need for the traditional ground-based ILS NAVAID components.

***Approach Lighting Systems (ALS)***

The third component of an ILS, in addition to the localizer and glideslope, is the approach lighting system (ALS). The ALS provides a lighted approach path along the extended centerline of the runway. Runway alignment indicator lights flash in sequence as a series of white lights moving toward the runway threshold, which emphasize runway centerline alignment. Roll indication is emphasized by a single row of white lights located on either side of, and symmetrically, along the column of approach lights.


Typically, airports with non-precision approaches utilize Medium Intensity Approach Lighting Systems (MALS), along with Runway Alignment Indicator Lights (RAILS). Together, these systems form the Medium Intensity Approach Lighting Systems with Runway Alignment Indicator Lights (MALSR) that are utilized for precision runways, such as Runway 5 and Runway 23 at ORF.

According to FAA Order 6850.2B, *Visual Guidance Lighting Systems*, the MALSR consists of a threshold light bar and seven five-light bars located on the extended runway centerline, the first bar being located 200 feet from the runway threshold, with the remaining bars each at 200-foot intervals out to 1,400 feet from the threshold. One additional five-light bar is located on each side of the centerline bar, 1,000 feet from the runway threshold, to form a 66-foot-long crossbar known as a roll bar. The individual lights in all bars are approximately 2½ feet apart and are aimed into the approach to the runway, away from the runway threshold. All lights in the MALSR system are steady burning white, except for the threshold lights, which have green filters. The threshold lights are a row of lights on 10-foot centers located coincident with and within the runway edge lights near the threshold and extend across the runway threshold.

At ORF, the runway centerline lights within the displaced area of Runway 5 are non-compliant with two conditions set-forth in AC 150/5340-30H, *Design and Installation Details for Airport Visual Aids*. According to regulations and standards set forth in paragraph 3.3 (a), for threshold displacements over 700 feet, the centerline lights in the displaced area are to be circuited separately from the centerline lights in the non-displaced runway area and the MALSR lights are to interlock with the runway centerline on the displaced area to ensure that when the approach lights are “on,” the displaced area centerline lights are “off,” and vice versa. In 2010, as a result of Runway 5 being non-compliant with both the previously mentioned standards, the Norfolk Airport Authority submitted a request to the FAA Washington Airports District Office (WAS-ADO) to re-approve and extend the time of the Modification of Standards (MOS) to continue the use of the existing configuration of the runway centerline lights within the displaced area of Runway 5 at ORF. The FAA approved the MOS under the condition that the non-standard conditions will be eliminated when the existing MALSR is replaced with a High Intensity ALS with Sequenced Flashers (ALSF-II) system.

RAIL's consist of five sequenced flashers located on the extended runway center line, the first being located 200 feet beyond the approach end of the MALS with successive units at each 200-foot interval, out to 2,400 feet from the runway threshold. All lights are aimed into the approach to the runway, away from the runway threshold, and flash in sequence toward the threshold at the rate of twice per second. A diagram for the commonly used MALSR configuration is depicted in **Figure 2-8**.

**Figure 2-8 – MALSR Configuration**




Source: FAA Order 6850.2B, *Visual Guidance Lighting Systems*.

### 2.2.4 Standard Instrument Departures (SIDs)

Standard Instrument Departure (SID) routes, also known as departure procedures, are published flight procedures followed by aircraft on an IFR flight plan immediately after takeoff from an airport. They provide an easy to understand departure procedure that airports use to balance terrain and obstacle avoidance, noise abatement (if necessary), and other airspace management considerations. SIDs are always printed graphically, rather than textually.

ORF has one SID procedure for departing IFR aircraft. The SID, identified as *KISRR THREE*, instructs aircraft to maintain runway heading after departure and expect ATC to advise the radar vectors to the assigned departure. FAA Joint Order (JO) 7400.2L, *Procedures for Handling Airspace Matters*, identifies specific turns off each runway end to avoid residential areas. Pilots should reference any Special Take-Off Minimums/Departure Procedures that may apply.


### 2.2.5 Airfield Lighting

In addition to the visual aids previously described, lighting on the airfield includes the rotating beacon, Precision Approach Path Indicator (PAPI) lights, runway threshold lighting, runway edge lighting, Runway End Identifier Lights (REILs), runway centerline lights, Runway Touchdown Zone Lights (TDZLs), taxiway edge lighting and apron lighting. Each of the lighting systems/types are described below:

***Rotating Beacon:***

The rotating beacon functions as the universal indicator for locating an airport at night. For a civilian airport, it has one clear and one green lens, 180 degrees apart, and is generally visible 10 miles from the airport. According to the Aeronautical Information Manual, October 2017, at Class C airports, the operation of the airport beacon during the hours of daylight often indicates that the ground visibility is less than three miles, and/or the ceiling is less than 1,000 feet. The rotating beacon at ORF is located south of the airfield and on the south side of Miller Store Road, near the GA facilities and the airfield maintenance facilities.

*ORF's Rotating Beacon*




***Precision Approach Path Indicator (PAPI) Lights**:*

A PAPI is a system of lights located near a runway end. It provides pilots with visual glide slope guidance information during an approach to the runway. PAPIs typically have an effective visual range of at least three miles during the day and up to 20 miles at night and inform pilots if they are high, low or on the correct approach descent path for the threshold. Runways 5 and 23 are equipped with PAPI-4 (four-light unit) systems, while Runways 14 and 32 are equipped with PAPI-2 (two-light unit) systems.

*PAPIs; Runway Threshold, Edge, & Centerline Lighting*



***Runway Threshold Lighting:***




Runway threshold lighting emits green light outward from the runway and red light toward the runway to mark the ends of the runway. The green lights indicate the landing threshold to arriving aircraft, whereas the red lights indicate the end of the runway for departing aircraft. The red and green lights are usually combined into a single fixture and special lenses or filters are used to emit the desired light in the appropriate direction. For displaced thresholds, the red lights and green lights are in separate fixtures. The fixtures containing the green lights are positioned at the displaced threshold, while the fixtures containing the red lighting are located in the area before the threshold. At ORF, Runways 23 and 32 have standard runway threshold lighting. Runway 5 has a 1,000-foot displaced threshold, and Runway 14 has a 575-foot displaced threshold; Therefore, they utilize the displaced threshold lighting system.

***Runway Edge Lighting:***

Runway edge lighting is white in color and is used to outline the edges of a runway during periods of darkness or restricted visibility. The runway edge lights are positioned parallel to the runway centerline at least two feet from the edge of the full-strength pavement designated for runways not used by jet aircraft and 10 feet from the edge of the full-strength pavement designated for runways used by jet aircraft. The spacing of the light units must not exceed 200 feet. These systems are classified according to their intensity, or brightness: High-Intensity Runway Light (HIRL), Medium-Intensity Runway Light (MIRL), and Low-Intensity Runway Light (LIRL). Some airports utilize a pilot-controlled system where the light-intensity can be changed, or stepped up/down, by clicking a button located on the radio. Runway 5/23 is equipped with a HIRL system, while Runway 14/32 is equipped with a MIRL system.

***Runway End Identifier Lights (REILs):***

The primary function of the REIL is to provide rapid and positive identification of the end of the runway. The REIL system consists of two synchronized, unidirectional flashing white lights that are positioned on each corner of the runway landing threshold, facing the approach area and aimed at an angle of 10 to 15 degrees. Runway 14/32 is equipped with REILs.

***Runway Centerline Lights:***

Runway centerline lights are required for Category (CAT) II and III precision approach runways, as well as CAT I approaches, where the Runway Visual Range (RVR) is less than 2,400 feet. The lighting system consists of embedded lights located along the centerline at 50-foot, equally spaced, longitudinal intervals. The lights are white in color, except for the last 3,000 feet. From 3,000 feet to 1,000 feet, the centerline lights consist of alternating red and white lights, with the last 1,000 feet being all red. Runway 5/23 has runway centerline lights.

***Runway Touchdown Zone Lights (TDZL):***

The TDZLs indicate the touchdown zone when landing under adverse visibility conditions. They consist of two rows of transverse light bars disposed symmetrically about the runway centerline. The system consists of steady-burning white lights beginning 100 feet beyond the landing threshold and extend to 3,000 feet beyond the landing threshold or to the midpoint of the

runway, whichever is less. All ORF runways have touchdown point markings, but only Runway 5 has TDZLs.

***Taxiway Edge Lighting:***

Taxiway lighting delineates the taxiway' guidance to pilots during periods of low visibility and at night. The most commonly used type of taxiway lighting is a series of blue fixtures, which are sometimes supplemented by blue edge reflectors, set at 200-foot intervals along the taxiway edges, but not more than 10 feet outward from the edge of the full-strength pavement. All the Airport's taxiways are equipped with Medium-Intensity Taxiway Lighting (MITL) systems.

*Taxiway Edge Light*



***Apron Lighting:***

Apron floodlight systems illuminate the terminal apron, the general aviation apron, and the air c cargo apron.

## 2.3 TERMINAL FACILITY

An assessment of the ORF terminal was completed based on site visits and tenant interviews, as well as analysis of historical airport data and reviews of previous studies. The intention of this effort was to develop a general understanding of the existing terminal facility.

*Documents Reviewed:*

- GA Aircraft Requirements, 2006
- Airline Operational Surveys, January/March 2008
- Norfolk International Airport Master Plan Update, October 2008
- Norfolk International Airport Supplemental Technical Analyses, December 2008
- Norfolk International Airport Executive Summary, December 2008
- Modification of Standards: MALSRs, September 2010
- ORF Revised Airfield Plan, December 2010
- ORF Existing ALP, October 2011
- Norfolk International Airport Parking Space Inventory, July 2016
- Air Carrier Schedules, 2017

*Tenants Interviewed:*


- Norfolk Airport Authority (NAA)
- Allegiant Air
- American Airlines
- Delta Air Lines
- Southwest Airlines

- United Airlines
- Transportation Security Administration (TSA)
- Customs and Border Protection (CBP)
- HMS Host
- Hudson Group
- Avis/Budget Car Rental
- Enterprise/Alamo/National Car Rental
- Hertz/Dollar/Thrifty Car Rental


### 2.3.1 Terminal Facility Layout

The terminal facility at ORF is separated into an Arrivals Terminal and Main Passenger Terminal. The Arrivals Terminal is primarily utilized by passengers concluding their flight at ORF and contains baggage claim services, as well as rental car and transportation network companies. The Main Passenger Terminal serves as the primary terminal for passenger processing, passenger security screening, and passenger enplaning and deplaning. The terminal is based on a pier layout. **Figure 2-9** depicts the layout for the Arrivals Terminal, while **Figure 2-10**, **Figure 2-11**, and **Figure 2-12** depict the layout for the three levels of the Main Passenger Terminal Building.


| | |
|---|---|
| | American Airlines |
| | Delta Air Lines |
| | Allegiant Air |
| | Southwest Airlines |
| | United Airlines |




## Level Two




## Level One




## Level Zero / Basement

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 50 100

## LEGEND

- Common Use Airline
- Concessions/Other Tenants
- Rental Car
- Norfolk Airport Authority
- Utilities/Storage
- Security/Regulatory
- Other Airport Services
- Circulation
- Elevator
- Escalator

**Figure 2-9**
Arrivals Terminal

| | |
|---|---|
| | American Airlines |
| | Delta Air Lines |
| | Allegiant Air |
| | Southwest Airlines |
| | United Airlines |

A9
A7
A5
A3
A1
A8
A6
A4
A2

International Arrivals Gate
PSA Airlines Crew Lounge
ATM / Charging Station
Restrooms
Mother's Room
Security Screening
NAA Admin. / Conference Rooms
Currency Exchange
Restrooms
Walkway to Arrivals Building
Info. Center/ ATM
NAA Admin. Offices
Restrooms
NAA Admin. Offices
Mother's Room
B17
B19
B21
B23
B24
B25
B26
B27
B16
B18
B20
B30
B28
B29
Restrooms
ATM
*Common Use: Allegiant/United*
Restrooms

**NORFOLK INTERNATIONAL AIRPORT**


MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)
0 50 100


## LEGEND

- Common Use Airline
- HMS Host Concessions (Dining)
- Hudson Group Concessions (Retail)
- Norfolk Airport Authority
- Utilities
- Transportation Security Administration
- Customs and Border Patrol
- Other Airport Services
- Circulation
- X1 Passenger Gate
- Elevator
- Escalator

**Figure 2-10**
Main Passenger Terminal: Second Level




| | |
|---|---|
| | American Airlines |
| | Delta Air Lines |
| | Allegiant Air |
| | Southwest Airlines |
| | United Airlines |




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)

0 50 100

## LEGEND

- Common Use Airline
- Concessions
- Norfolk Airport Authority
- Utilities
- Customs and Border Patrol
- Circulation
- Elevator
- Escelator

**Figure 2-11**
Main Passenger Terminal:
First Level




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 25 50

**LEGEND**

- Concessions
- Norfolk Airport Authority
- Utilities
- Airport Police
- Circulation
- Elevator

**Figure 2-12**
Main Passenger Terminal:
Lower Level

### 2.3.2 Main Passenger Terminal Building and Arrivals Building Functional Areas

The Airport terminal is comprised of several areas, each accommodating multiple stakeholder functions including law enforcement, airline services, administrative services, concessions, ground transportation services, CBP offices and processing areas, and TSA security screening and administrative offices. **Table 2-10**, **Table 2-11**, and **Table 2-12** provide an inventory of the terminal facility, listed by location, primary function, and area.

**Table 2-10 – Main Passenger Terminal Building Functional Areas**

| Location and Use | Element Length (LF) | Area (SF) |
|---|---|---|
| **Main Passenger Terminal: Lower Level** | | |
| Airport Police Department | | 2,160 |
| Storage Space | | 12,075 |
| **TOTAL LOWER LEVEL** | | **14,235** |
| **Main Passenger Terminal: First Level** | | |
| **Airline Ticketing Functions** | | |
| Airline Ticket Counters – LF & SF | 238 | 3,230 |
| Airline Ticket Offices | | 7,170 |
| Departures Curbside (East and West) | 600 | |
| **Outbound Airline Baggage Makeup** | | 7,578 |
| **Airline Operation Space** | | |
| Concourse A | | 15,685 |
| Concourse B | | 21,575 |
| **TOTAL FIRST LEVEL** | **838** | **55,238** |
| **Main Passenger Terminal: Second Level (Non-Sterile Area)** | | |
| **ATRIUM SERVICES** | | |
| Airport Administration | | 14,240 |
| Conference Center | | 2,164 |
| ATM/Foreign Currency Exchange/Mailbox Area | | 690 |
| Business Center | | 2,165 |
| **CONCESSION SPACE** | | |
| Burger King | | 2,435 |
| Discover Hampton Roads | | 1,980 |
| The Local at ORF | | 8,457 |
| Starbucks | | 1,048 |
| Tech on the Go/Hudson News | | 2,430 |
| **TOTAL SECOND LEVEL (NON-STERILE)** | | **35,627** |

**Table 2-11 – Main Passenger Terminal Building Functional Areas (Continued)**

| Location and Use | Element Length (LF) | Area (SF) |
|---|---|---|
| **Main Passenger Terminal: Second Level (Passenger Security Screening & Sterile Area)** | | |
| **PASSENGER SECURITY SCREENING** | | |
| TSA Screening for Concourse A | | 10,752 |
| TSA Screening for Concourse B | | 10,720 |
| TSA Office Space | | 1,750 |
| **AIRLINE GATES/HOLDROOMS** | | |
| Concourse A | | 13,375 |
| Concourse B | | 22,270 |
| **CONCESSION SPACE** | | |
| $10 Boutique (Concourse B) | | 515 |
| Back Bay Bistro (Concourse B) | | 2,475 |
| Great American Bagel (Concourse A) | | 450 |
| Here's to the Heroes (Concourse A) | | 1,415 |
| Hudson News (Concourse A) | | 925 |
| Hudson News (Concourse B-Location 1) | | 800 |
| Hudson News (Concourse B-Location 2) | | 920 |
| James River Grill (Concourse A) | | 1,880 |
| MKT at ORF (Concourse B) | | 850 |
| Starbucks (Concourse A) | | 940 |
| Starbucks (Concourse B) | | 950 |
| Tech on the Go (Concourse A) | | 455 |
| Unoccupied (Concourse A) | | 130 |
| Mother's Rooms | | 363 |
| **TOTAL SECOND LEVEL (STERILE)** | | **72,655** |
| **TOTAL MAIN PASSENGER TERMINAL FUNCTIONAL SPACE** | **820** | **142,128** |

**Table 2-12 – Arrivals Terminal Building Functional Areas**

| Location and Use | Element Length (LF) | Area (SF) |
|---|---|---|
| **Arrivals Terminal: First Level** | | |
| **AIRLINE BAGGAGE CLAIM** | | |
| Baggage Claim | | 19,385 |
| Arrivals Curbside | 730 | 40,356 |
| **GROUND TRANSPORTATION CENTER** | | |
| Rental Car Counter Services | | 5,943 |
| Rental Car Counters – Linear Footage | 163 | |
| Transportation Services | | 292 |
| **TOTAL FIRST LEVEL** | **893** | **65,976** |
| **Arrivals Terminal: Second Level** | | |
| **ADMINISTRATIVE OFFICES** | | |
| Airport Parking Office | | 2,506 |
| TSA Administration | | 2,828 |
| **MILITARY** | | |
| USO Welcome Center | | 2,000 |
| **TOTAL SECOND LEVEL** | | **7,334** |
| **TOTAL ARRIVALS TERMINAL FUNCTIONAL SPACE** | | **73,310** |
| **Unsure of Location or has Multiple Locations** | | |
| Concession Storage | | 2,217 |
| Public Restrooms | | 11,600 |
| Escalators | | 1,280 |
| **TOTAL** | | **15,097** |
| **TOTAL AIRPORT FUNCTIONAL SPACE (MAIN PASSENGER TERMINAL, ARRIVALS, & OTHER)** | **1,731** | **230,535** |

Note: Concession operators are subject to change.
Source (Tables 2-8, 2-9, & 2-10): NAA, 2017.

### 2.3.3 Airline Ticketing Lobby

The ticketing lobby is located on the first level of the Main Passenger Terminal and serves as the primary space for departing passengers to check-in for flights, obtain boarding passes, and drop-off baggage to be checked and screened prior to enplaning. The ticketing lobby can be accessed by various means. When parking in the Airport's parking garage, passengers will make their way from the Arrivals Terminal to the Main Passenger Terminal via a pedestrian bridge, which disperses into the atrium on the second level of the Main Passenger Terminal. Passengers can then take an elevator, escalator, or stairs down to the ticketing lobby. The most direct method of accessing the ticketing lobby is via one of the eight enclosed passageways between the outer door and inner door, also known as vestibules. The vestibule configuration for the Main Passenger Terminal is as follows: three to the south, two to the west, and three to the north. The ticketing lobby has a square/rectangular shape.

Within the first floor of the Main Passenger Terminal, there are two separate ticketing lobbies on the north and south sides, with a combined five commercial air carrier ticket counters in service. In the west side lobby, Delta operates from three counters, each measuring approximately 18 feet. Southwest operates from the opposite side of the lobby from one counter measuring approximately 46 feet in length. At the south side lobby, American operates from one counter measuring approximately 60 feet. Allegiant and United are co-located at the opposite side, with

Allegiant operating from one ticket counter measuring approximately 36 feet, and United operating from two counters, measuring approximately nine feet and 33 feet. Located between the north and south ticket lobbies is the outbound baggage makeup area, a common space shared by the carriers.

Airlines also provide passengers with access to self-serve, automated kiosks. The kiosks provide passengers with capabilities and amenities including checking-in for flights and printing boarding passes, as well as making alterations to seat assignments. With the exception of two kiosks, passengers are also able to check baggage and print checked baggage tags.

### 2.3.4 Checked Baggage Screening

To meet federal mandates, all checked baggage must go through the sort-controlled Checked Baggage Inspection System (CBIS). Bags are screened by one of the seven CT-80 Explosive Detection System (EDS) machines, operated by TSA personnel. The bag scan machines for Allegiant, American, Southwest, and United are positioned in front of the airline ticket counters, between the queue space. To maximize the use of the queuing area, TSA and the airlines have been in the process of relocating the baggage screening machines from the ticketing lobby floor to a secure area behind the ticket counters, in line with the baggage conveyor belt system. When the Study began, only the baggage screening device for Delta had been relocated. In addition, the Authority is working with United, Allegiant, and TSA to procure a second EDS machine for joint use on the east side of the ticketing lobby, as there is one EDS machine for both carriers. The baggage transfer process is further explained in **Section 2.3.8.**


### 2.3.5 Passenger Security Screening

ORF has two separate TSA passenger screening checkpoints: one for Concourse A and one for Concourse B. Prior to accessing either concourse, all enplaning passengers must pass through the TSA security screening checkpoint (SSCP) that corresponds to the concourse where their departing gates are located. The checkpoint for Concourse A has three pre-screening stands and Concourse B has two pre-screening stands located outside the checkpoints, where passengers have their travel documents verified prior to proceeding through the SSCP. TSA pre-check passengers and employees/crews have separate lanes at both checkpoints that are commonly accommodated by the active stand during non-peak hours. During peak hours, pre-check and employee lanes are accommodated via separate lanes and stands.

The checkpoint for Concourse A consists of four passenger screening lanes (with room for an additional fifth lane when capacity warrants expansion) containing two passenger walk-through metal detectors, and one Millimeter Wave Advanced Imaging Technology (AIT) scanner. Concourse B checkpoint consists of four passenger screening lanes (with room for up to six lane) containing a total of two passenger walk-through x-ray machines and one AIT scanner. Separate Advanced Technology (AT) X-ray systems, utilized to detect threats in carry-on baggage by providing a high-definition x-ray image, are also located at each checkpoint, four at the checkpoint for Concourse A and four for the checkpoint at Concourse B. Once on the sterile side, passengers circulate to their respective gate areas. Passengers are unable to access the alternate concourse without being reprocessed through the SSCP at the respective concourse. Arriving passengers exit the concourse via exit hallways, located adjacent to each of the SSCPs. After

exiting, arriving passengers will disperse in the Main Passenger Terminal. Meeter/greeter seating is located throughout the lobby area.

The Authority has space available, and a plan in place to expand each other the security checkpoints in both concourses when capacity throughput warrants opening more security lanes to maintain a high level of service at the Airport. These expansion plans are reflected in the Demand Capacity and Alternatives analysis of this Master Plan Update.



Source: NAA, 2017.

### 2.3.6 Airline Gates and Holdrooms

ORF has 23 air carrier gates, with an additional gate dedicated to Federal Inspection Services (FIS). The existing Gates are dispersed throughout concourse A and B, with Gates 1 through 9 (future) on Concourse A and Gates 16 through 30 on Concourse B. As currently constructed, Gates 7, 9, and 11 are on the end of Concourse A. The Airport has identified a potential extension to Concourse A that will consolidate Gates 7 and 9 into larger holdrooms to accommodate larger airframes, while eliminating Gate 11. American and Southwest operate from Concourse A, while Allegiant, Delta, Frontier, and United operate from Concourse B.

A fully-functioning FIS facility is located at Gate A1. It is used for international flights and charters but can be used as a swing-gate, or a multi-function gate, when needed. Multi-function gates are gates within the terminal concourse that can be used for multiple purposes. As international flights arrive, these gates allow temporary barriers to separate international passengers that have not been pre-cleared and provides access to CBP booths via separate corridors. The FIS can process up to 175 passengers per hour (PPH).

All active gates are located on the second level of each concourse and are equipped with passenger boarding bridges, except for Gates A9, B17, and B18. When occupied, these gates utilize ground-level boarding via stairs accessible from the Concourse. The active gates are also equipped with a conveyance system to carry gate-checked baggage from the gate area to the ramp level.

**Table 2-13** presents the air carrier gate assignments based on existing lease agreements when the Study commenced.

**Table 2-13 – Air Carrier Gate Assignments**

| Concourse A Holdroom/Gate | Airline | Boarding Bridge Owner | Concourse B Holdroom/Gate | Airline | Boarding Bridge Owner |
|---|---|---|---|---|---|
| Gate A1 | CBP: FIS Facility | NAA | Gate B16 | Unoccupied | NAA |
| Gate A2 | American | American | Gate B17 | Unoccupied | - |
| Gate A3 | Southwest | NAA | Gate B18 | Unoccupied | - |
| Gate A4 | American | American | Gate B19 | Delta | NAA |
| Gate A5 | Southwest | NAA | Gate B20 | Common Use* | NAA |
| Gate A6 | American | American | Gate B21 | Delta | Delta |
| Gate A7 | American | NAA | Gate B23 | Delta | Delta |
| Gate A8 | American | American | Gate B24 | Delta | NAA |
| Gate A9 | Unoccupied | - | Gate B25 | Delta | NAA |
| | | | Gate B26 | Unoccupied | NAA |
| | | | Gate B27 | United | NAA |
| | | | Gate B28 | United | NAA |
| | | | Gate B29 | United | NAA |
| | | | Gate B30 | United | NAA |

Note: * - Gate shared by Allegiant Air, Frontier Airlines, and United Airlines; Assigned gates are subject to change.
Source: NAA, 2017.

### 2.3.7 Terminal Concessions and Amenities

Concessions throughout the terminal facility provide a varied selection of goods and services for passengers, employees, and meeters/greeters. Concessionaires include food and beverage services, magazine, book, and gift shops.

Hudson Group operates retail concessions throughout the Airport. A gift shop, as well as a separate, co-located retail and news shop, were located prior to screening in the atrium at the center of the Main Passenger Terminal when the Study began. Two news shops and one gift shop were also located in Concourse B. Concourse A had one news store and two retail stores. In the future, Hudson Group would like to open a larger store on Concourse A. They do not see a need for additional pre-security sales space. Normal operating hours for Hudson Group retail services are 3:30 am to 8:30 pm, local time, with the busiest times typically being 2:00 pm to 4:00 pm on Concourse A and 3:00 pm to 5:00 pm on Concourse B.

HMS Host operates food and beverage concessions at the Airport. When this Study began, three food and beverage concessions were located prior to screening in the main lobby of the Main Passenger Terminal. Four additional food and beverage concessions operated out of Concourse A, as well as three additional on Concourse B. In the future, HMS Host would like to operate a second full-service restaurant on Concourse B. The kitchen facilities are currently inadequate, per HMS designs. HMS Host's dining services on Concourses A and B are typically busiest around 11:00 am, as well as 4:00 pm to close, which is dependent on flight delays. **Table 2-14** depicts the concessions and amenities within the airport terminal facility, including location, at the time this Study originated.

**Table 2-14 – Concessions**

| Concession/Amenity | Type | Operator | Location |
|---|---|---|---|
| **Main Passenger Terminal/Atrium – Pre-Security** | | | |
| Burger King | Food/Beverage | HMS Host | South Corner of Atrium |
| Discover Hampton Roads | Gift | Hudson Group | West Corner of Atrium |
| The Local at ORF | Full-Service Food & Beverage | HMS Host | East Corner of Atrium |
| Starbucks (24-Hours) | Café | HMS Host | East Corner of Atrium |
| Tech on the Go/Hudson News | Retail/News | Hudson Group | South Corner of Atrium |
| Travelex | Foreign Currency Exchange | Travelex | North Side of Atrium |
| **Concourse A** | | | |
| Great American Bagel | Food/Beverage | HMS Host | Gate A7 |
| Here's to the Heroes | Full-Service Food & Beverage | HMS Host | Gate A3 |
| Hudson News | News | Hudson Group | Gate A5 |
| James River Grill | Full-Service Food & Beverage | HMS Host | Between Gates A4 & A6 |
| Starbucks | Café | HMS Host | Between Gates A4 & A6 |
| Sweet Indulgences | Candy Store | Hudson Group | Between SSCP & Gate A2 |
| Tech on the Go | Retail | Hudson Group | Gate A4 |
| **Concourse B** | | | |
| $10 Boutique | Gift | Hudson Group | Between Gates B19 & B21 |
| Back Bay Bistro | Full-Service Food & Beverage | HMS Host | Gate B23 |
| Hudson News - Location 1 | News | Hudson Group | Between Gates B19 & B21 |
| Hudson News - Location 2 | News | Hudson Group | Across from Gate B27 |
| MKT at ORF | Express Food & Beverage | HMS Host | Across from Gate B21 |
| Starbucks | Café | HMS Host | Between Gates B16 & B18 |
| FAO Sweets (Summer 2018) | Candy Store | Hudson Group | Near SSCP |

Note: The concessions depicted in this table represent those present when this Study began. Concessions are subject to change.
Source: Hudson Group/HMS Host, 2017.

### *Additional Amenities*

Additional amenities within the main lobby and concourses include three mother's rooms: one in the main lobby near the family restrooms, one on Concourse A next to Gate A2, and one on Concourse B next to Gate B17. The NAA is in the process of developing a business center in the main passenger terminal atrium pre-security screening, in the northeastern quadrant. This will be located adjacent to the Authority's existing conference center. NAA also operates an information center, previously located in the baggage claim area, now located at the entry to the Level 2 Atrium, from the Arrivals Building. Travelex operates a Currency Exchange directly across from the Information Center, and there is an ATM located in the baggage claim, atrium, Concourse A, and Concourse B. The USO Lounge is located on the upper level of the Arrivals Building.

### *Concession Storage and Support Areas*

Each concessionaire has its own storage area, which is not accessible or in view of the public. Prior to being transported from the storage area, located in a non-SIDA location, to the stores on the Concourses, TSA requires that all merchandise, boxes, bags, and containers be scanned at the security checkpoint to ensure that ORF's safety and security is not being compromised. Since each concessionary item must be individually scanned by TSA, concessionaires are limited to screening only during non-peak hours. After being cleared, the items are permitted to be taken to the Concourses.

Hudson Group has a storage area pre-security behind Discover Hampton Roads in the basement of the Departures Terminal, as well as a storage area post-security, which have both reached capacity.

HMS Host's food and beverage storage, located pre-security in a central storage area in the basement of the Airport, has reached capacity. When transporting goods to and from the storage area, employees must utilize a freight elevator.

### 2.3.8 Baggage Claim



The baggage claim area is located on the first floor of the Arrivals Terminal and serves as the location for deplaning passengers to retrieve their checked baggage. Arriving passengers can access baggage claim by passing through the Main Passenger Terminal lobby, located on the second level, and proceeding across the pedestrian bridge that connects to the Arrivals Terminal. Seating for meeters/greeters is available throughout the baggage claim area. At ORF, there are five baggage claim carrousels and two oversized baggage claim areas. The five carrousels are identified numerically from one to five, staring at the north end of baggage claim. The baggage claim units are centered in the Arrivals Terminal, each measuring approximately 20 feet by 73 feet. The oversized baggage claims, each approximately 1,550 square feet, are located against the wall on the east side of the Arrivals Terminal. International arrivals utilize a separate baggage claim area housed within the FIS facility, and is controlled by CBP (see **Section 2.3.13**).

***Baggage Makeup Areas***

Each airline operating at ORF has its own baggage makeup space, located behind the ticketing lobby. The space includes a conveyer system that collects passengers' checked luggage from the ticketing counter, runs back parallel to the airline office and support facilities, and discharges into the baggage make-up area beneath the Main Terminal Building. Delta Air Lines has an enclosed baggage make-up room to process outbound baggage prior to loading luggage on the bag carts to transport to the aircraft. The general baggage make-up area is comprised of two lanes, each one adjacent to the airline operating areas on the north and southsides of the building. Each baggage makeup room has access to the terminal aprons via ramps from the lower level of the Main Terminal building underneath Concourse B. As previously noted, the baggage screening machines in the ticketing lobby queuing area are in the process of being relocated to the baggage makeup area. Due to the size of the machines, the amount of usable space in Delta's baggage makeup room has been greatly reduced.

When this Study began, the other airlines advised that the space in the baggage makeup rooms, without having the TSA baggage screening machine, was adequate but constrained during peak hours.

***Inbound Baggage Systems***

Inbound baggage, which has been loaded to baggage tugs from the aircraft, is transported from the Terminal Apron to the Arrivals Building via an underground tunnel on the northside of the Terminal Apron. Direct access to the tunnel is available from both sides of Concourse A, and the north side of Concourse B. Due to gate layout and movement restrictions at the end of Concourse B, airline and baggage operations on the south side of Concourse B must return to the baggage make-up ramp and cross under Concourse B to the north in order to access the baggage tunnel to the Arrivals Building.

Inbound baggage has access to the Arrivals building via a tug ramp on the north end of the building. There are five baggage devices with a circulation road that navigates around the central devices returning to the tug ramp with 2-way traffic. Once unloaded, baggage tugs are stored in the GSE areas for each airline, or under the Main Terminal Building in the baggage make-up area.

### 2.3.9 Rental Car Counters

Rental car counters are located along the east and west walls on the north end of the first level of the Arrivals Terminal. Eight rental car companies operate at the Airport, each one having a separate reservation desk. Along the west wall, in order from south to north and measuring approximately 22 linear feet each, are the counters for Avis, Hertz, Enterprise, Budget, and Alamo. Along the east wall, in order from south to north and measuring approximately 17.5 linear feet each, are the counters for National, Dollar, and Thrifty.

### 2.3.10 Airport Administrative and Support Areas

Airport administration is located on the second level of the Departures Terminal, in three separate areas surrounding the atrium. This area includes administrative offices, a conference center, a break room, a future business center, and restroom facilities.

### 2.3.11 Airline Service and Support Areas

Beyond those operated by the Airport, airlines and tenants also lease dedicated space for service and support functions. During the summer 2018, PSA Airlines began operating a crew lounge in Concourse A, adjacent to the security screening area.

### 2.3.12 Back Office Space

Tenants at the Airport, such as airlines, concessionaires, and rental car providers, each utilize back office space within the terminal. Airline storage space is located in the secure area; however, the airlines have offices in both the secure and non-secure areas of the terminal. Rental car offices are in the non-secure area of the terminal and are sometimes shared depending on lease agreements. TSA Administration and Airport Parking office spaces are located on the second level of the Arrivals Terminal. Employees can only access office space for their respective employer.

### 2.3.13 Federal Inspection Services (FIS)

ORF has a fully-functioning FIS facility at Gate A1. Based on discussions with the Airport's CBP representative, there are approximately 20 full-time employees; however, the staffing levels are based on the capacity and demand for each international operation. The number of staff at a

given time are based on demand of number of operations and passengers. The fully-equipped FIS meets the needs for the Airport's current demand and can handle up to 175 passengers per hour. The Airport does not currently have scheduled international service; however, on occasion, diversions do occur. In the event a flight is diverted to ORF, CBP will process the passengers and baggage. CBP also handles approximately three charter flights per year and can accommodate aircraft as large as a Boeing 747, with constraints. After being processed, passengers will gather luggage from a baggage claim area designated for international arrivals only.

The current FIS facility will need to be upgraded before being able to process scheduled international service.

### 2.3.14 Terminal Signage and Wayfinding

A main contributor to customer and passenger satisfaction is effective wayfinding. Signage and wayfinding in the airport terminal should be clear and intuitive. Efficient wayfinding systems can create a sense of comfort and security; however, too much information can have the opposite effect and cause confusion and disorientation. It is important that the airport's signage and wayfinding system is simple and well organized. Airport wayfinding systems can include the following types of signage: directional signs, identification signs, informational signs, and regulatory signs. Signage and wayfinding regarding vehicular circulation and parking are discussed later in this chapter.

When approaching the Airport, signage increases to include information pertaining to the Arrivals Terminal and Main Passenger Terminal, as well as their relative functions. Outside the Main Passenger Terminal, signage designates the entryway closest to each airline ticket counter, in addition to signage for airlines providing curb-side check-in. Inside the Main Passenger Terminal, enplaning passengers can utilize signage to locate the airline ticketing counters, airport security, or the appropriate gate departure concourse. Signage also depicts directions and information for various concessions and amenities such as food and beverage providers, technology charging stations, ATM machines and a foreign currency exchange location (Western Union at Travelex), a mail drop-box, and the conference center. Deplaning passengers can utilize signage in the Main Passenger Terminal to locate the gate for a connecting flight or to exit the concourse for baggage claim or ground transportation located in the Arrivals Terminal.

Once in the Arrivals Terminal, passengers utilize Airport signage to locate the appropriate baggage claim device based on their flight information. The rental car agencies, as well as the shuttle and transportation network companies, have designated signage to aid passenger flow in the Arrivals Terminal. Signage for other amenities incudes wayfinding and location information for the United Service Organizations (USO) Lounge, ATM machines, and the Airport Information desk. Signage and wayfinding in the Arrivals Terminal also assists passengers and other customers needing to access the Main Passenger Terminal. Signage at ORF also includes regulatory signage depicting prohibited areas, secure areas, employee or airport authorized areas only, etc.

## 2.4 AUTOMOBILE ACCESS AND PARKING

This section of the report details the existing inventory of parking, both on- and off-Airport, as well as the existing traffic conditions at the Airport's departure and arrival curbside. The data

presented was gathered from a variety of sources, including on-site observations by CHA, information provided by the Norfolk Airport Authority, and other public data sources.

The on-site observations were conducted on Tuesday, January 23, 2018 and Wednesday, January 24, 2018, days of the week identified by the NAA as typical busy weekdays at ORF.

### 2.4.1 Existing ORF Parking

The on-Airport parking facilities are owned and operated by the NAA and provide parking for a combination of public parkers, NAA and other airport employees, rental cars, and taxis. In addition, the NAA maintains an employee parking lot off-site at the corner of N. Military Highway and Robin Hood Road. A taxi queuing lot is located on Airport Road, adjacent to the Long-Term Lot.

The Airport parking functions consist of three parking garages and six surface parking lots (five on-site and the off-site Employee Lot). In total, ORF controls 8,582 parking spaces, of which 7,258 (85%) are for public parking, 636 (7%) are for rental cars and 688 (8%) are for Airport employee and NAA parking.


**Table 2-15** presents a detailed breakdown of the existing ORF parking inventory by facility and type of user served. As shown in the "Facility ID" column in the table, each parking facility has been assigned a letter designation, which helps to identify the geographical locations of the on-Airport parking facilities in **Figure 2-13**, as well as the off-site Employee Lot in **Figure 2-14**.

**Table 2-15 – Existing NAA Parking Facilities**

| Facility ID | Facility Name | Short-Term | Long-Term | Accessible Parking (ADA) | Employee | Reserved or Permit | Rental Car | TOTAL SPACES |
|---|---|---|---|---|---|---|---|---|
| A | Garage A | 275 | 2,260 | 37 | 0 | 0 | 636 | **3,208** |
| B | Garage B | 0 | 1,090 | 21 | 0 | 2 | 0 | **1,113** |
| C | Garage C | 0 | 1,089 | 21 | 0 | 0 | 0 | **1,110** |
| D | Surface Lot D | 0 | 72 | 4 | 0 | 6 | 0 | **82** |
| E | Long-Term Lot | 0 | 1,999 | 42 | 0 | 11 | 0 | **2,052** |
| F | Departures North | 146 | 0 | 6 | 0 | 0 | 0 | **152** |
| G | Departures South | 171 | 0 | 6 | 0 | 0 | 0 | **177** |
| H | Permit Lot | 0 | 0 | 5 | 0 | 87 | 0 | **92** |
| I | Employee Lot | 0 | 0 | 12 | 580 | 4 | 0 | **596** |
| **TOTAL PARKING INVENTORY** | | **592** | **6,510** | **154** | **580** | **110** | **636** | **8,582** |

Source: NAA, 2018.

**Figure 2-13 – ORF On-Airport Parking Facilities**




Source: DESMAN, 2018.

**Figure 2-14 – Off-Site Employee Parking Lot**




Source: DESMAN, 2018.

A few items of note related to the existing parking inventory:

- In Garage A, the rental car ready spaces are located on the ground level and rental car return is on the second level, which are physically separated from the short- and long-term spaces. The short-term spaces are also physically separated from the long-term spaces in this facility.
- While the Long-Term Lot is shown as one facility, it is possible to block off the southern portion of the Lot, while still allowing access to the rest of the facility.
- All three garages, including the Short-Term Garage, and Surface Lot D share a common exit plaza where customer payments are processed. Garage A also has a separate exit lane from the rental car level of the Garage which allows rental car customers to avoid exiting through the regular exit plaza.
- All of the public parking facilities typically have cashiers stationed at the exits to collect payments, in addition to automated payment machines located in a number of the exit lanes.

ORF does not offer shuttle buses to move public parkers from any of the previously mentioned parking facilities due to the walking distances being in proximity to the terminal building; however, shuttle buses are provided to transport employees to and from the off-site Employee Lot.

### 2.4.2 Observed Utilization of Parking

The on-site observations of parking and traffic activity at ORF parking facilities on a Tuesday and Wednesday were intended to capture and understand typical levels of parking demand at the Airport. While the absolute peak activity period for most airports in the U.S. is around the Thanksgiving holiday, in terms of providing an adequate quantity of parking capacity, the objective is to try and accommodate the typical peak demand, not these periods of extraordinary demand. If airports constructed enough parking spaces to accommodate these occasional demand spikes, a large number of spaces would sit empty for all but a few days out of the year.

**Table 2-16** presents a summary of the number of vehicles observed parking in each of the NAA's parking facilities on Tuesday, January 23, 2018 and Wednesday, January 24, 2018, between noon (12:00 pm) and 2:00 pm, Eastern Standard Time (EST). For comparison, further on-site observations will take place during the peak demands of summer and Thanksgiving.

**Table 2-16 – Observed Utilization of ORF Parking Facilities**

| Facility ID | Facility Name | Inventory | Parked Vehicles January 23rd | Utilization % | Parked Vehicles January 24th | Utilization % |
|---|---|---|---|---|---|---|
| A | Garage A | 3,208 | 2,652 | 83% | 2,704 | 84% |
| B | Garage B | 1,113 | 624 | 56% | 669 | 60% |
| C | Garage C | 1,110 | 235 | 21% | 271 | 24% |
| D | Surface Lot D | 82 | 64 | 78% | 70 | 85% |
| E | Long-Term Lot | 2,052 | 919 | 45% | 691 | 34% |
| F | Departures North | 152 | 46 | 30% | 39 | 26% |
| G | Departures South | 177 | 95 | 52% | 96 | 54% |
| H | North Lot | 92 | 60 | 65% | 62 | 67% |
| I | Employee Lot | 596 | 236 | 40% | 258 | 43% |
| **TOTALS** | | **8,582** | **4,931** | **57%** | **4,860** | **57%** |
| **Public Parking Spaces** | | **7,258** | **3,999** | **55%** | **3,904** | **54%** |
| **All Other Spaces** | | **1,324** | **932** | **70%** | **956** | **72%** |

Source: NAA, 2018.

Ideally, during a typical peak demand period, 5 percent to 15 percent of the spaces in a parking facility remain available to accommodate new parkers. Maintaining an inventory of available spaces, even during the peak demand period, makes it easier for parkers to find a space, reduces the amount of time drivers spend searching for empty spaces and generally results in a more positive parking experience. This concept, referred to as "practical capacity", refers to that point at which a parking facility or system has reached its functional limit and is unable to efficiently or safely accommodate additional parking demand.

As shown in the table, with an observed peak utilization of 3,999 spaces, ORF's public parking inventory is currently operating at approximately 55 percent of capacity. This data indicates that, ORF has an ample supply of parking to accommodate it existing needs.

### 2.4.3 Parking Rates

**Table 2-17** presents the rates charged for public parking in each of the ORF facilities.

**Table 2-17 – ORF Public Parking Facility Rates**

| Facilities | Current Parking Rates |
|---|---|
| Garage A Short-Term<br>Departures North<br>Departures South | $1.00 per 30 minutes, or any part thereof;<br>$24.00 maximum per day |
| Garage A Long-Term<br>Garage B<br>Garage C<br>Surface Lot D<br>Long-Term Lot | $1.00 per 30 minutes, or any part thereof;<br>$10.00 maximum per day |

Note: Prices are subject to change.
Source: NAA, 2020.

### 2.4.4 Off-Airport Competing Parking

In addition to researching public data sources, CHA spent time in the field working to identify private property owners offering long-term off-Airport parking; however, companies do not appear to be offering off-airport competing parking locations in the vicinity of ORF.

### 2.4.5 Curb-Front Traffic

In order to determine the capacity of the airport curb front to accommodate future levels of vehicular activity, it was necessary to first understand the functionality of the curb front during periods of peak demand. For this reason, observations of traffic flow and congestion were performed at the Airport on the same days as the observations of parking activity, Tuesday, January 23, 2018 and Wednesday, January 24, 2018.

The terminal curb front on the departure side has five lanes on each side of the building that are separated by an island, (3 lanes and 2 lanes) with the addition of a small parking lot on each side. The five lanes are each approximately 400 feet in length, for a total of 2,000 curb front feet on either side of the building. The arrivals curb front consists of five lanes running the length of the terminal, which are approximately 900 feet long. The 4,500 lane feet are divided into 2,700 feet adjacent to the building and 1,800 feet beyond the island.

On both days, over the course of the day, CHA never observed any significant traffic issues of note. At no time did passenger pick-up or drop-off activity, whether by personal vehicle, hotel shuttle, rideshare vehicle, or other means, appear to significantly block traffic or create significant congestion on the roadways near the Airport terminal. In conclusion, the terminal curb front and the departure lanes are adequate to accommodate the existing passenger activity.

### 2.4.6 Regional Roadway Network

Primary regional access to the airport terminal is provided from I-64 via Norview Avenue (RT 247), with additional access from I-64 available at Robin Hood Road. Route 192 (Azalea Garden Road) provides access from the northeast and southwest. See **Figure 2-15**.

I-64 is a six-lane Interstate Highway encircling Norfolk, Portsmouth, and Hampton and connecting to Richmond and on to St. Louis, MO. It provides easy access to the Airport from southeast Virginia, northwest North Carolina, southern Delaware, and southern Maryland.


Norview Avenue (RT 247) is a four-lane arterial road connecting the Airport with I-64 and points to the west. Route 192 varies between a two- and four-lane arterial which accesses the terminal via Route 247.

Together, these and other adjacent roads provide quick and easy access to the local and regional roadway network. See **Figure 2-16**.

### 2.4.7 Airport Roadway System

Norview Avenue terminates at the Airport. When it reaches the Airport, it divides into a two- lane departure road and a two-lane arrival road. These encircle the terminal and parking garages and provide direct access for passengers, providing as many as six lanes in certain areas. The departure road also provides access to surface parking lots on either side of the terminal building. There are over seven miles of roadways adjacent to the parking lots, garages and terminal curb front. These roadways are adequate to accommodate the current peak volumes of traffic with little or no congestion observed. See **Figure 2-17**.

**Figure 2-15 – Regional Roadway Network**




Source: Google Earth, CHA, 2018.

## Figure 2-16 – Local Roadway Network Access




Source: Google Earth.

## Figure 2-17 – Existing Airport Access




Source: Google Earth.

## 2.5 SUPPORT FACILITIES

Support facilities provide vital functions related to the overall operation of the Airport and typically include facilities related to the following: airport fencing, airport equipment storage and maintenance, Air Traffic Control (ATC), Aircraft Rescue and Firefighting (ARFF), aircraft fueling, snow and ice control, air cargo, FBO/GA and Maintenance/Repair/Overhaul (MRO) services, and rental cars. **Figure 2-1** depicts the location of key facilities around the airfield.

The following tenants were interviewed in addition to those previously mentioned in **Section 2.3**:

- Signature Flight Support – Fixed Base Operator (FBO)
- United Parcel Service (UPS)

### 2.5.1 Airport Perimeter Fence

As required by TSA, the airfield is protected by a chain-link fence that encloses the runways, taxiways, and aircraft movement and non-movement areas. The airfield fence, which has 16 gates that provide access to various points of the airfield, is eight feet high, with various areas of fencing reaching 10 feet high for wildlife hazard mitigation. The entire airfield fence is topped with three-strands of barbed wire, totaling one-foot high.



Source: Google Earth

### 2.5.2 Airport Equipment Storage and Maintenance

Located on the southeast end of the airfield are ORF's maintenance and equipment storage facilities. The Airport's airfield maintenance area consists of two facilities: one on the north side and one in the southeast corner. The northern facility is approximately 40,000 square feet and includes three bay doors and two roll-up doors. This facility houses the Airport's snow removal equipment. The southeastern facility is approximately 6,000 square feet and includes seven bay doors, serves as the sand storage facility, and houses the Airport's maintenance and utility vehicles.




Source: Google Earth.

### 2.5.3 Air Traffic Control Tower (ATCT)

The current ATCT opened on January 22, 1995 and is located on the east side of the airfield. In addition to administrative and support facilities for local FAA operations at ORF, this facility includes the Norfolk Tower Terminal Radar Approach Control (TRACON). The 134-foot-high facility manages traffic in a 30 to 50 nautical mile radius around ORF, with radar coverage provided by an ASR-9 terminal system with a six-level weather detection capability. The ATCT is in operation 24 hours a day, 365 days a year.



Source: Google Earth.

### 2.5.4 Aircraft Rescue and Firefighting (ARFF)

ARFF vehicles are designed to provide an invaluable service to the commercial and private users of the Airport and the passengers and cargo they transport. The aviation industry is reliant on prompt and effective fire and rescue services during aircraft emergencies. These services include fire containment and suppression, passenger and crew rescue, airframe and cargo preservation, and maintenance of the site to aid in after-incident investigations. The vehicles that airport fire departments employ serve as the medium to deliver firefighters, specialized tools and equipment, and firefighting agents to the scene of an aircraft incident. They must be designed to

perform specific functions, constructed for longevity and ease of maintenance, and tailored to the airport's needs.

Within three minutes from the initial alarm, a minimum of one required ARFF vehicle must reach the midpoint of the farthest runway serving air carrier aircraft from its assigned post or must reach any other specified point of comparable distance on the movement area that is available to air carriers and begin application of the extinguishing agent. Within four minutes from the initial alarm, all other required vehicles must reach the previously stated locations and begin application of the extinguishing agent. ORF has one ARFF facility on the north side of the airfield, northeast of the terminal building. The location of the ARFF facility allows firefighting equipment to access any airfield pavement within the required time established by Federal regulations.

A training aircraft for the ARFF department is located on the southeast side of the airfield, north of the airfield maintenance building.

The document used to determine an airport's index is Title 14 CFR Part 139.315, *Aircraft Rescue and Firefighting: Index Determination*. ORF operates as an ARFF Index C. The requirements for ARFF vehicles to transport a specific quantity and type of firefighting agents are established by Title 14 CFR Part 139.317, *Airport Rescue and Firefighting: Equipment and Agents*. As an ARFF Index C, the Airport can choose to have a minimum of either three or two vehicles; however, specifications of the vehicles depend upon the total number of vehicles chosen. ORF has chosen to keep a minimum of three ARFF vehicles.

ORF currently has a rapid intervention vehicle and four ARFF trucks meeting the specifications as described below:

- Two vehicles carrying the following extinguishing agents:
  - 500 pounds of sodium-based dry chemical, halon 1211, or clean agent or
  - 450 pounds of potassium-based dry chemical and water with a commensurate quantity of Aqueous Film Forming Foam (AFFF) to total 100 gallons for simultaneous dry chemical and AFFF application
- Two vehicles carrying an amount of water and commensurate quantity of AFFF so the total quantity of water for foam production carried by all three vehicles is at least 3,000 gallons




Source: Google Earth.

### 2.5.5 Aircraft Fueling

Signature Flight Support is responsible for operating the fuel farm, the GA fuel farm, and the fuel dispensing area at ORF. These operations include services to commercial, GA, and cargo aircraft. The Airport's fuel farm is located north of the Air Traffic Control Tower and includes four above-ground fuel tanks with fuel storage capacities of 210,000-gallons per tank (Jet-A).

Fuel is transported from the fuel farm and GA fuel farm via underground pipes to a dispensing area located north of the ARFF facility. Fuel is then transported from the dispensing area to aircraft via specialized fuel trucks, which make approximately 13 to 15 deliveries per day. The types of trucks and their carrying capacities are as follows:

- One 750-gallon truck (Avgas)
- One 1,000-gallon truck (Avgas)
- Ten 5,000-gallon trucks (Jet-A)
- One 10,000-gallon truck (Jet-A)

The GA fuel farm is located in the general aviation area, south of the T-Hangars. This fueling location includes three underground storage tanks with fuel storage capacities as follows:

- Two 10,000-gallon tanks (Jet-A)
- One 10,000-gallon tank (Avgas)










Source: Google Earth.

### 2.5.6 Snow and Ice Control

As guided by FAA AC 150/5200-30D, *Airport Winter Safety and Operations,* snow, ice, and slush should be removed as expeditiously as practicable to maintain runways, high-speed turnoffs, and taxiways in a "no worse than wet" (i.e., no contaminant accumulation) condition. To meet these guidelines during the winter months, personnel at ORF are on-call at all times for snow removal to ensure adequate response to weather events. In addition to regularly mandated inspections, airfield conditions are monitored throughout the day, or as often as needed by the on-duty airfield maintenance and airport operations personnel. The inspections are conducted visually and with runway friction measuring equipment. Airfield conditions are transmitted electronically to pilots via NOTAMS (Notice to Airmen). Other sources of information include reports from the National Weather Service (NWS), the Airport's Automated Surface Observation System (ASOS) weather station, and pilot reports (PIREPs). Based on these observations and information, Airport personnel can determine the proper equipment and surface treatment to be used. Approved equipment for contaminant removal includes high-speed rotary plows, snowplows, material spreaders, and runway brooms. Approved chemicals include fluid deicers/anti-icers and solid deicers/anti-icers. Fluid deicers/anti-icers consist of glycol-based fluids, potassium acetate base, and potassium formate-based fluids. Solid deicers/anti-icers consists of sodium formate and sodium acetate.

Most equipment is stored in the airfield maintenance building so that it is protected from weather and to prolong the operational life expectancy.

***Aircraft Deicing***

Deicing operations at ORF are confined to the main terminal apron and the cargo apron on the west side of the airfield. The Airport's main deicing facility/pad is located on the northeast side of the main terminal apron and consists of four deicing positions, which are utilized on a first-come-first-serve basis. Signature Flight Support provides the deicing services for aircraft operating at ORF including Allegiant, American, Delta, United, FedEx, and UPS.

Southwest handles its own deicing services. Signature provides deicing services via two 1,100-gallon deicing trucks.

Sweeper trucks are utilized to collect glycol from the pavement after application and to transfer the collected material to the glycol storage tanks near the fuel dispensing area. After deicing services have ceased for the season, the glycol tanks are taken to an off-site facility where the recovered fluid is analyzed and disposed of accordingly. Although Signature provides deicing services, each airline stores its own glycol. Delta and Southwest have their own storage tanks located beside the fuel farm, while the storage tanks for American and United are located under the concourse.

Deicing services on the cargo apron are authorized in the non-movement area parallel to Taxiway 'V'. Deicing services are not permitted within 100 feet of a storm-drain or on the GA side of the airfield at ORF.

### 2.5.7 Air Cargo Facilities

ORF leases property to Aeroterm for air cargo in a dedicated area that is shared by FedEx, Mountain Air Cargo, and UPS. The cargo area is located on the west side of the airfield, south of the terminal. It consists of two multipurpose processing buildings, providing users with 88,000 square feet of space. The western facility is the largest of the two facilities, measuring approximately 65,000 square feet. FedEx is the primary operator of the facility, along with Mountain Air Cargo (MAC), which is a major contract carrier for FedEx. The second building, measuring approximately 23,000 square feet, is primarily operated and maintained by UPS. Adjacent to the air cargo facilities is an aircraft ramp which is approximately 265,000 square feet. The ramp provides the cargo operators with direct access to Taxiway 'V', which connects directly to Taxiway 'C' and Runway 14/32.




Source: Google Earth.

Air cargo service destinations are depicted in **Table 2-18**.

**Table 2-18 – Cargo Service Destinations**

| Airlines | Destinations |
|---|---|
| Federal Express (FedEx) | Indianapolis International Airport (IND), Memphis International Airport (MEM), Dare County Regional Airport (MEO), McGhee Tyson Airport (TYS) |
| United Parcel Service (UPS) | Louisville International Airport (SDF), Richmond International Airport (RIC), Roanoke-Blacksburg Regional Airport (ROA) |

** MAC is a contract carrier for FedEx and is not included in the table as its operations are unscheduled, have varying destinations, and are inconsistent.
Note: Destinations are subject to change.
Source: FedEx, UPS, U.S. DOT, T-100 statistics, CHA.

Non-aviation tenants also utilize the cargo facilities, including Quantem, Wright Bros. Aero, Philadelphia Truck Lines, and Coinmach.

### 2.5.8 General Aviation (GA) Facilities and Activities

Signature Flight Support, the airports sole FBO, operates a 29.5-acre site which includes hangars, a terminal building, and apron space.

The FBO operates six bulk-storage hangars, three sections of T-hangars, and a large aircraft parking apron. The largest hangar on the southwest side of the GA area is used for MRO services and is leased to PSA Airlines (see **Section 2.5.9**). Five additional box hangars ranging from approximately 18,000 square feet to 46,500 square feet are used for aircraft storage. Three T-

hangars, ranging from approximately 12,700 square feet to 24,200 square feet are used for small aircraft storage and leased by the FBO. A large apron area that can provide up to 36 tie-down positions (depending on aircraft size), is used for short term storage of transient aircraft parking.

Signature primarily hosts corporate jets and on standard to busy days, has 35 to 50 itinerant aircraft, with 50 percent remaining overnight.

In addition to supporting GA parking and infrastructure, Signature provides fueling and deicing services to tenants and operators at ORF, in addition to ground handling services for UPS. Small flight schools periodically sublease approximately 10 aircraft from the FBO. A detailed depiction of Signature Flight Support's facilities is shown in **Figure 2-18**.

### 2.5.9 MRO Facility

ORF leases property for one MRO-dedicated facility, located in the general aviation area and measuring approximately 49,000 square feet, to PSA Airlines. It is a full-service, overnight MRO facility that provides maintenance support for all aircraft operating at the Airport. The MRO facility is also depicted in **Figure 2-18**.

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

Taxiway A

TOF

32

MRO Facility

Bulk Hangars (FBO)

T-Hangars (FBO)

FBO Maintenance Shop

GA Fuel Farm

FBO Terminal/Hangar

Bulk Hangars (FBO)

Property Line

GA Facilities

Runway

Taxiway

**Figure 2-18**
GA & MRO Facilities

### 2.5.10 Rental Car Facilities

When picking up rental cars, passengers first proceed to the rental car counters, located in the Arrivals Terminal. Bypass booths are installed in the Airport Parking Garage that allow VIP customers to go directly to the Ready booth and bypass the rental car counters, saving the customer time. After being processed, passengers pick up rental cars at the Rental Car Ready lot, located in the Airport Parking Garage. When finished with rental vehicles and after completing rental return paperwork, customers can proceed to the rental car return area on the second level of Garage A. After rental cars have been returned, the vehicles are taken to a remote QTA facility, located west of Airport property on Military Highway.

## 2.6 AIRSPACE ENVIRONMENT

The National Airspace System (NAS) is made up of a network of air navigation facilities, Air Traffic Control (ATC) facilities, airports, technology, and appropriate rules and regulations that are needed to operate the system. The FAA created the NAS to protect persons and property on the ground, and to establish a safe and efficient airspace environment for civil, commercial, and military aviation within the United States. Airspace is broken down into two categories: regulatory and non-regulatory. Within the regulatory airspace category, there are two types of airspace: controlled and uncontrolled. Categories and types of airspace are defined based on their complexity or density of aircraft movements, or the nature of the operations conducted within the airspace, which dictates the level of safety required and the level of national and public interest.

The purpose of controlled airspace is to provide adequate separation between IFR and VFR aircraft, thus, IFR services are available, but not required, within all controlled airspace. Airspace designated as Class A, B, C, D, and E is controlled airspace.


VFR aircraft operating in Class B, C, or D airspace must be in contact with ATC. This gives ATC the authority to manage IFR and VFR traffic in the proximity to airports and ensure proper separation. Controlled airspace designations do not affect IFR traffic, as IFR traffic is cleared through controlled airspace by ATC.

Class G airspace is uncontrolled and IFR services may or may not be available.

Large sections of controlled and uncontrolled airspace have been designated as special use airspace. Special use airspace is further defined as prohibited, restricted, warning, military operations, and alert areas. Civil operations within special use airspace may be limited or even prohibited, depending on the area, as operations within these areas are considered hazardous to civil aircraft.

ORF is located within Class C airspace, extending from the runway surface up to 4,000 feet mean sea level (MSL) for a 5-nm radius, and from 1,200 feet MSL to 4,000 feet MSL for a 10-nm radius. A graphic of the U.S. Airspace Profile is presented in **Figure 2-19**.

**Figure 2-19– U.S. Airspace Profile**




Source: Federal Aviation Administration.

The National Aeronautical Charting Office (NACO) of the FAA publishes special aeronautical charts used by pilots to navigate through the National Airspace System. These charts are called sectional charts, or sectionals. A sectional chart provides detailed information on airspace classes, ground-based NAVAIDS, radio frequencies, longitude and latitude, navigational waypoints and navigational routes. It also offers topographical features, such as terrain elevations and ground features that are important to aviators, such as landmarks that will be identifiable from a given altitude. Although these charts are used for VFR and IFR navigation, they are a VFR pilot's primary navigation tool.

**Figure 2-20** displays a segment of the Washington Sectional Chart, centered on ORF.

**Figure 2-20– Washington Sectional, 103rd Edition [Effective 1 Feb 2018]**




Source: aeronav.faa.gov

## 2.7 METEOROLOGICAL CONDITIONS

Meteorological conditions affect airport operations at an airport in many ways. Winds, precipitation, and temperature influence decisions pertaining to NAVAIDs, runway orientation, and required runway length. ORF is equipped with an Automatic Surface Observation System (ASOS), a highly sophisticated weather data sensing, processing, and dissemination system that is designed to support weather forecast activities and aviation operations. While meteorological readings are taken every minute, 24-hours a day, every day of the year, these systems generally report at hourly intervals, but also report special observations if weather conditions change rapidly and cross aviation operation thresholds. Maintained, controlled, and operated by the FAA and the National Weather Service, the ASOS automatically observes, formats, archives, and transmits observations.

When weather conditions exceed predetermined weather element thresholds, a special report is transmitted through an automated very-high-frequency (VHF) airband radio frequency (127.15 MHz) to pilots operating at or near ORF. These messages are also available via phone by calling 757-460-9348.

### 2.7.1 Local Climate

The average annual temperature in Norfolk, Virginia is 60.05 degrees Fahrenheit. The average low is 52.00 degrees Fahrenheit, while the average high is 68.10 degrees Fahrenheit. When the Study commenced, July was the warmest month, with a mean temperature of 87.00 degrees Fahrenheit. Average monthly precipitation ranges from 3.11 inches to 5.51 inches, with annual precipitation averaging 46.55 inches. Average monthly snowfall during the months of December through February range from one to two inches, with an annual average of five inches of snowfall. The local climate requires the Airport to support snow removal and aircraft deicing services.

This climate data for Norfolk, Virginia was obtained from the National Oceanic and Atmospheric Administration (NOAA) and the NWS.

### 2.7.2 Wind Coverage

In addition to climate data, the ASOS (Station 13737 – Norfolk International Airport) at ORF collects wind speed and direction data, which can influence airfield development decisions on runway orientation and length. Local wind conditions at an airport are a key factor in determining runway use. Aircraft operational safety and performance is enhanced when aircraft depart and land into the wind; therefore, runways that are not oriented to take full-advantage of the prevailing wind patterns are not utilized as frequently as runways that are appropriately oriented. According to FAA AC 150/5300-13A, *Airport Design*, the desirable wind coverage for an airport is at least 95 percent at all speeds, meaning that the primary runway at an airport has at least 95 percent wind coverage and that the wind at the airport is within certain limits of crosswind conditions. Wind coverage is calculated using the highest crosswind component that is acceptable for the type of aircraft expected to use the runway system. Larger aircraft have a higher tolerance for crosswinds than smaller aircraft due to their size, weight, and operational speed. **Table 2-19** provides the standard crosswind component by aircraft size. **Table 2-20** outlines the weather classification criteria and the number of recorded observations at ORF between 2007 and 2016.

**Table 2-19 – Crosswind Components**

| Runway Design Code (RDC) | Maximum Crosswind Component |
|---|---|
| A-I and B-I aircraft* | 10.5 knots |
| A-II and B-II aircraft | 13.0 knots |
| A-III, B-III,<br>C-I through D-III<br>D-I through D-III | 16.0 knots |
| A-IV, B-IV,<br>C-IV through C-VI,<br>D-IV through D-VI | 20.0 knots |
| E-I through E-VI | 20.0 knots |

Source: FAA AC/5300-13A *Airport Design*

**Table 2-20 – Weather Classification Criteria**

| Weather Class | Recorded Observations at ORF (2007-2016) |
|---|---|
| All Weather | 131,281 |
| VFR Conditions | 15,056 |
| IFR Conditions | 92,646 |

Source: NOAA, National Climate Center; Station 723080 (2007-2016)
VFR – Visual Flight Rule
IFR – Instrument Flight Rule

The combination of the crosswind and the weather classification allows for the calculation of the wind coverage, which is presented in **Table 2-21** for ORF. Wind coverage is the percent of time crosswind components are below an acceptable velocity. The 95 percent wind coverage is computed on the basis of crosswinds not exceeding 10.5 knots for ARC A-I and B-I; 13 knots for ARC A-II and B-II; 16 knots for ARC A-III, B-III, and C-I through D-III, and 20 knots for ARC A-IV through D-VI. The calculated wind coverage for ORF facilities shows that all runways exceed the 95 percent wind coverage threshold when combined in all modeled weather conditions (all weather, VFR-only, and IFR-only), as well as individually for crosswind coverage of 20 knots.

Runway 5/23 meets the 95 percent wind coverage threshold for each crosswind speed in all modeled weather conditions, with the exception of during IFR conditions when the crosswind speed is 10.5 knots.

Runway 14/32 does not meet the 95 percent wind coverage threshold in IFR conditions when the crosswind speed is 16 knots or in any modeled weather conditions when the crosswind speed is 10.5 knots or 13 knots.

**Table 2-21 – ORF Wind Coverage**


| | Runway | 10.5 Knots | 13 Knots | 16 Knots | 20 Knots |
|---|---|---|---|---|---|
| AW | 5/23 | 95.56% | 98.14% | 99.62% | 99.93% |
| | 14/32 | 80.00% | 87.77% | 95.89% | 98.81% |
| | All Combined | 98.58% | 99.64% | 99.93% | 99.99% |
| VFR | 5/23 | 95.75% | 98.27% | 99.70% | 99.96% |
| | 14/32 | 78.79% | 87.17% | 96.01% | 99.04% |
| | VFR Combined | 98.77% | 99.72% | 99.96% | 100% |
| IFR | 5/23 | 92.05% | 96.34% | 98.9% | 99.75% |
| | 14/32 | 76.67% | 84.58% | 92.52% | 96.68% |
| | IFR Combined | 96.51% | 98.88% | 99.75% | 99.98% |

Source: NOAA, National Climate Center; Station 725080 (2007-2016)

Weather observations are presented in a format that is specifically designed by the FAA to be useful for evaluating weather conditions at an airport. Wind direction is grouped according to a 16-point compass rose (N, NNE, NE, ENE, E, ESE, SE, SSE, S, SSW, SW, WSW, W, WNW, NW and NNW).

Wind speed is organized into groups of 0-3, 4-6, 7-10, 11-16, 17-21, 22-27, 28-33, 34-40, and 41 knots per hour or greater. This data is typically displayed on a wind rose for each weather classification. Windroses are depicted in **Figure 2-21**.

## VFR Windrose





### VFR Observations

| RUNWAY | 10.5 KNOTS | 13 KNOTS | 16 KNOTS | 20 KNOTS |
|---|---|---|---|---|
| Runway 5/23 | 95.75% | 98.27% | 99.70% | 99.96% |
| Runway 14/32 | 78.79% | 87.17% | 96.01% | 99.04% |
| Combined | 98.77% | 99.72% | 99.96% | 100% |

DATA SOURCE: NOAA National Center for Environmental Information - Southeast Regional Climate Center
Chapel Hill, NC
Norfolk International Airport
Norfolk, VA
Station 723080

OBSERVATIONS: 92,646 Observations
2007-2017

## IFR Windrose





### IFR Observations

| RUNWAY | 10.5 KNOTS | 13 KNOTS | 16 KNOTS | 20 KNOTS |
|---|---|---|---|---|
| Runway 5/23 | 92.05% | 96.34% | 98.90% | 99.75% |
| Runway 14/32 | 76.67% | 84.58% | 92.52% | 96.68% |
| Combined | 96.51% | 98.88% | 99.75% | 99.98% |

DATA SOURCE: NOAA National Center for Environmental Information - Southeast Regional Climate Center
Chapel Hill, NC
Norfolk International Airport
Norfolk, VA
Station 723080

OBSERVATIONS: 15,056 Observations
2007-2017

## All-Weather Windrose




### All-Weather Observations

| RUNWAY | 10.5 KNOTS | 13 KNOTS | 16 KNOTS | 20 KNOTS |
|---|---|---|---|---|
| Runway 5/23 | 95.56% | 98.14% | 99.62% | 99.93% |
| Runway 14/32 | 80.00% | 87.77% | 95.89% | 98.81% |
| Combined | 98.58% | 99.64% | 99.93% | 99.99% |

DATA SOURCE: NOAA National Center for Environmental Information - Southeast Regional Climate Center
Chapel Hill, NC
Norfolk International Airport
Norfolk, VA
Station 723080

OBSERVATIONS: 131,281 Observations
2007-2017

**Figure 2-21**
Windroses

# 3 FORECASTS OF AVIATION ACTIVITY

## 3.1 INTRODUCTION

This chapter of the Master Plan Update projects aviation demand over a 20-year planning horizon for the Norfolk International Airport (ORF). Facility sizing and capacity recommendations, both airside and landside, are directly impacted by the projected aviation activity levels presented in this chapter. The projections were derived from approved methodologies in accordance with the requirements provided in Federal Aviation Administration (FAA) Advisory Circular (AC) 150/5070-6B, *Airport Master Plans*.

To develop these forecasts, an understanding of current and historical airport operations, industry trends, and economic conditions within ORF's market was necessary. These variables were detailed and factored into individual forecast scenarios that comprise the commercial passenger and operations forecasts. For the purposes of this Study, the Airport's historical calendar year (January-December) data was organized according to the FAA fiscal year (October-September) and was used in the scenarios, forecasts, and FAA forecast comparisons within this chapter. It is important to reaffirm that all scenarios and forecast projections of enplanements and operational activity (Air Carrier and General Aviation) were developed according to the FAA's fiscal year (FY) for the purposes of direct comparison to the FAA Terminal Area Forecast.

The assumptions, methodologies, and data used to create the various projections are presented and analyzed in the following sections. The specific activity elements for which forecasts were prepared include:

- Enplaned Passengers
  - 5-, 10-, and 20-year forecasts
  - Load Factors
- Air Carrier Activity
  - Operations
  - Fleet Mix
- Air Cargo Activity
  - Operations
  - Cargo Volume
- General Aviation Activity (GA)
  - Based Aircraft
  - Operations
- Military Aviation Activity
  - Operations
- Peak Activity
  - Enplaned Passengers
  - Operations

### 3.1.1 Forecast Data Sources

Information factored into both the planning and the forecasting efforts included commercial air carrier industry trends, airframe orders and retirement programs, GA operational trends, and anticipated changes in the aircraft fleet mix operating at ORF. The data and assumptions used to define baseline conditions and future activity trends were derived from the following data sources:

- Airport Management – Airport management representatives typically provide the most accurate historical data and future assumptions at the Airport. Data provided by the Airport included passenger and operational activity, facility needs, gate requirements, fleet mix transition, and anticipated service growth.

- FAA Terminal Area Forecast (TAF)[5] – TAF activity estimates are derived by the FAA from national estimates of aviation activity. These estimates are then assigned to individual airports based upon multiple market and forecast factors. The FAA looks at local and national economic conditions, as well as trends within the aviation industry, to develop each forecast.
- Airline Management – Airline representatives provided insight on planned and future airline routes and airframe changes, which were directly factored into the assumptions and methodologies of the demand projections.
- FAA Aerospace Forecast 2018-2038 – This forecast provided an overview of aviation industry trends and expected growth for the commercial passenger air carrier activity segments. National growth rates in enplanements and operations, as well as growth and mix for commercial fleets, were provided over a 20-year forecast horizon. For the purposes of this forecast, the FAA Aerospace Forecasts were used as comparisons for the basis of determining the growth of the ORF general aviation and commercial fleet. This forecast also provided insight into future air cargo growth trends on a national and international level.
- The Boeing Commercial Market Outlook 2018-2038 – This market outlook provided information detailing future fleet mix transitions, such as new aircraft entering the market and future equipment retirements, for commercial and air cargo carriers.
- Airbus Global Market Forecast FY 2018-2037 & Boeing World Air Cargo Forecast 2016-2017 – These forecasts provided insight into future commercial cargo fleet growth and anticipated fleet mix of both domestic and foreign airlines. These insights were used to assist in developing and confirming the validity of future ORF cargo carrier fleet mix and projected volume assumptions.
- Woods & Poole Economics, Inc. – Woods & Poole Economics, Inc. is an independent firm that specializes in developing long-term economic and demographic projections. Their database includes every State, Metropolitan Statistical Area (MSA), and county in the United States (U.S.) and contains historical data and projections from 1970 through 2050, utilizing more than 900 economic and demographic variables.
- Aviation DataMiner (Boyd Group International) – This data source provided access and analyzation of metrics and projections related to air traffic, cost factors, schedules, revenue sources, fares, and other customizable data. This data was used to derive T-100 data including specific route load factors, seats per departure, fleet mix, airline schedules, and other related data sets.

### 3.1.2 ORF Catchment and Core Area


An airport's catchment area, or market, is defined as the area in which an airport captures the majority of its airport users. To determine the catchment area, an evaluation using socioeconomic factors was conducted to identify which airports the local area population are

[5] Note, the 'FAA 2018 TAF', which was pulled in February 2019, represents the TAF containing all data from FY 2018.

most likely to use, based on the proximity with respect to other airports in the region, drive-time, and demographics. For the purposes of this forecast, the catchment area for ORF traffic exists primarily in the following Virginia Counties and *Independent Cities: Accomack, *Chesapeake, Gloucester, *Hampton, Isle of Wight, James City & Williamsburg, Mathews, *Newport News, *Norfolk, Northampton, *Portsmouth, Southampton & *Franklin, *Suffolk, *Virginia Beach, and York & *Poquoson. The catchment area also extends partially into North Carolina to include the following Counties: Camden, Chowan, Currituck, Gates, Hertford, Pasquotank, and Perquimans.

Based on its location relative to major airports in Virginia and North Carolina and drive times associated with the surrounding roadway network, ORF depends on a core region within its catchment area for a large portion of its passenger activity. The core region consists of areas located within a 30-minute drive-time. This region includes portions of Chesapeake, Norfolk, Portsmouth, and Virginia Beach, which are all in the top-six most populated counties within the region. **Figure 3-1** shows the catchment area, as well as the core area.

**Figure 3-1 – ORF Catchment and Core Areas**




Source: CHA, 2018.


### 3.1.3 Nearby Airports

As shown in **Figure 3-2**, ORF is located within 20 to 95 nautical miles (nm) and a 40-minute to a 2 ½-hour drive-time of the following major airports:

- Newport News/Williamsburg International Airport (PHF) – 20 nm; 40-minute drive; northwest of ORF
- Richmond International Airport (RIC) – 65 nm; 90-minute drive; northwest of ORF
- Pitt-Greenville Airport (PGV) – 95 nm; 150-minute drive; southwest of ORF

ORF and RIC are primary, small-hub airports, while PHF and PGV are both primary, non-hub airports.

**Figure 3-2 – Drive Time to Nearby Major Airports**




Source: CHA, 2018.

## 3.2 SOCIOECONOMIC DATA

The factors that have the greatest impact on the growth prospects of an airport are the socioeconomic characteristics (i.e., population, income, and employment) present within the Airport's catchment, or market, area. In addition to the common demographic factors, the ORF area has a large contingent of military personnel. According to a survey conducted by the NAA, *Characteristics of Passengers Using Norfolk International Airport: 2018*, members of active duty and their dependents accounted for approximately 16 percent of the passengers utilizing the Airport in 2018. Of all passengers interviewed, 30 percent had a military connection. According to Dragas Center for Economic Analysis and Policy's report, *The State of the Region*[6], Hampton Roads is home to more than 80,000 military personnel, with approximately four percent of national defense spending occurring in this area. From 2000 to 2012, the Department of Defense (DOD) spending was booming but became dissolute with the onset of sequestration in 2013 and remained fairly constant through 2016. In 2017, the DOD had an increase of approximately one-billion dollars in spending.

As such, changes in military missions, assignments, and programs have large impacts on the socioeconomic variables within the region. The economic and demographic growth patterns for this core area will have major impacts on future demand for air service at ORF.

***Population***

In 2017, the Virginia Beach-Norfolk-Newport News VA-NC Metropolitan Statistical Area (MSA), consisting of Chesapeake, Gloucester, Hampton, Isle of Wight, James City & Williamsburg, Mathews, Newport News, Norfolk, Portsmouth, Suffolk, Virginia Beach, York & Poquoson, and Currituck Counties, had a population of approximately 1.7 million while the ORF catchment area had a population of approximately 1.9 million. The Average Annual Growth Rate (AAGR) for the Virginia Beach-Norfolk-Newport News VA-NC MSA and the ORF catchment area were 0.5 and 0.4 percent, respectively, which were below the Commonwealth of Virginia AAGR of 0.9 percent and the National AAGR of 0.7 percent, despite having a steady increase in population from 2008-2017. The Virginia Beach-Norfolk-Newport News VA-NC MSA and the ORF catchment area are both projected to grow, with AAGRs of 0.6 percent, a lesser rate of growth than the projected AAGRs for the Commonwealth of Virginia (1.1 percent) and the United States (0.9 percent).

The lesser growth rate indicates that the Airport is dependent upon more than resident travelers for passenger activity growth and relies on passenger leakage from nearby airports in the Hampton Roads and surrounding area. It also indicates that the Airport is heavily impacted by Federal decisions with respect to military operations, such as sequestration. Passenger leakage occurs when travelers choose to utilize airports outside their core area when flying. See **Table 3-1** and **Figure 3-3.**


[6] Dragas Center for Economic Analysis and Policy (2018). State of the Region: Hampton Roads 2018 [PDF file]. Retrieved from https://www.ceapodu.com/wp-content/uploads/2018/10/SOR-2018-FINAL090518.pdf

**Table 3-1 – Population (Historical & Projected)**

| Year | ORF Catchment Area (000) | AAGR | MSA (000) | AAGR | Commonwealth of Virginia (000) | AAGR | United States (000) | AAGR |
|---|---|---|---|---|---|---|---|---|
| **2008** | 1,839.3 | - | 1,662.5 | - | 7,833.5 | - | 304,093.9 | - |
| **2013** | 1,881.2 | 0.4% | 1,706.7 | 0.4% | 8,267.9 | 0.9% | 316,427.3 | 0.7% |
| **2017** | 1,922.5 | 0.4% | 1,747.4 | 0.5% | 8,567.5 | 0.7% | 327,167.9 | 0.7% |
| **AAGR 2008-2017** | - | **0.4%** | - | **0.5%** | - | **0.9%** | - | **0.7%** |
| **2018** | 1,935.1 | 0.7% | 1,759.4 | 0.7% | 8,664.6 | 1.1% | 330,206.7 | 0.9% |
| **2023** | 1,999.1 | 0.7% | 1,820.2 | 0.7% | 9,167.6 | 1.1% | 345,864.6 | 0.9% |
| **2028** | 2,062.9 | 0.6% | 1,881.2 | 0.7% | 9,694.7 | 1.1% | 362,086.9 | 0.9% |
| **2033** | 2,123.0 | 0.6% | 1,938.8 | 0.6% | 10,229.1 | 1.1% | 378,237.1 | 0.9% |
| **2038** | 2,174.7 | 0.5% | 1,989.1 | 0.5% | 10,748.6 | 1.0% | 393,507.4 | 0.8% |
| **AAGR 2018-2038** | - | **0.6%** | - | **0.6%** | - | **1.1%** | - | **0.9%** |

Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017 – Woods & Poole Economics, Inc., CHA, 2018.

**Figure 3-3 – Population (Historical & Projected)**




Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017 – Woods & Poole Economics, Inc., CHA, 2018.

### *Employment*

In 2017, the Virginia Beach-Norfolk-Newport News VA-NC MSA had employment levels of approximately 1.0 million, while the ORF catchment area had employment levels of approximately 1.1 million. The AAGR for the Virginia Beach-Norfolk-Newport News VA-NC MSA and the ORF catchment area were both 0.2 percent, which was below the Commonwealth of Virginia and National AAGRs of 0.7 and 0.9 percent, respectively.

The lower AAGRs for the ORF catchment area and Virginia Beach-Norfolk-Newport News VA-NC MSA were due to a decline in employment levels in 2009. The decline in employment levels for the catchment area ended in 2011; however, the decline for the MSA continued through 2013. As mentioned previously, the military impact on socioeconomics in the ORF area is significant as much of this decline in employment in the primary catchment area was due to military sequestration leading up to and in 2013.


According to the Bureau of Labor Statistics, after a large spike in the unemployment rate from 2008 to 2009 (the peak resulting in 9.4 percent in October 2009), except for sequestration in 2013, the resulting unemployment rate in the MSA has been steadily declining since 2010, with the unemployment rate falling to 4.0 percent in March 2018. This coincides with the projections of employment growth within the Virginia Beach-Norfolk-Newport News VA-NC MSA and the ORF catchment areas, which are projected to grow at the same rate, with AAGRs of 1.0 percent. The Commonwealth of Virginia and the United States are projected to grow at a higher rate, with AAGRs of 1.3 and 1.2 percent, respectively. Possibly most important is the evidence that the MSA and catchment areas are not anticipated to experience declines in employment levels as they had historically. See Table 3-2 and **Figure 3-4.**

**Table 3-2 – Employment (Historical & Projected)**

| Year | ORF Catchment Area (000) | AAGR | MSA (000) | AAGR | Commonwealth of Virginia (000) | AAGR | United States (000) | AAGR |
|---|---|---|---|---|---|---|---|---|
| **2008** | 1,123.0 | - | 1,035.3 | - | 4,882.8 | - | 179,639.9 | - |
| **2013** | 1,086.0 | -0.6% | 1,004.3 | -0.5% | 4,899.8 | 0.1% | 182,408.0 | 0.3% |
| **2017** | 1,140.6 | 1.0% | 1,055.0 | 1.0% | 5,220.6 | 1.3% | 195,849.2 | 1.4% |
| **AAGR 2008-2017** | - | **0.2%** | - | **0.2%** | - | **0.7%** | - | **0.9%** |
| **2018** | 1,154.3 | 1.2% | 1,067.8 | 1.2% | 5,300.7 | 1.5% | 198,635.3 | 1.4% |
| **2023** | 1,221.3 | 1.1% | 1,130.9 | 1.2% | 5,704.3 | 1.5% | 212,627.0 | 1.4% |
| **2028** | 1,287.1 | 1.1% | 1,193.0 | 1.1% | 6,114.2 | 1.4% | 226,668.6 | 1.3% |
| **2033** | 1,350.8 | 1.0% | 1,253.2 | 1.0% | 6,519.5 | 1.3% | 240,285.0 | 1.2% |
| **2038** | 1,412.4 | 0.9% | 1,311.6 | 0.9% | 6,920.0 | 1.2% | 253,386.2 | 1.1% |
| **AAGR 2018-2038** | - | **1.0%** | - | **1.0%** | - | **1.3%** | - | **1.2%** |

Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017– Woods & Poole Economics, Inc., CHA, 2018.

**Figure 3-4 – Employment (Historical & Projected)**




Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017 – Woods & Poole Economics, Inc., CHA, 2018.

***Income***


In 2017, the Virginia Beach-Norfolk-Newport News VA-NC MSA had a per capita income of approximately $50,000, while the ORF catchment area had a per capita income of approximately $45,000. The AAGR for the Virginia Beach-Norfolk-Newport News VA-NC MSA was 2.0 percent, while the AAGR for the catchment area was 1.8 percent. The AAGR for the Commonwealth of Virginia and the United States were 1.9 percent and 2.1 percent, respectively, which were above the ORF catchment area and MSA AAGRs. Despite having the lowest AAGR, the ORF catchment area is projected to grow at the same rate as the Commonwealth of Virginia and United States, with AAGRs of 4.5 percent. The per capita income for the MSA is projected to grow at a rate of approximately 4.6 percent. See **Table 3-3** and **Figure 3-5**.

**Table 3-3 – Per Capita Income (Historical & Projected)**

| Year | ORF Catchment Area ($) | AAGR | MSA ($) | AAGR | Commonwealth of Virginia ($) | AAGR | United States ($) | AAGR |
|---|---|---|---|---|---|---|---|---|
| **2008** | 37,255.0 | - | 40,639.0 | - | 45,707.0 | - | 41,082.0 | - |
| **2013** | 39,821.6 | 1.1% | 43,245.0 | 1.0% | 48,460.0 | 1.0% | 44,462.0 | 1.3% |
| **2017** | 44,649.0 | 2.3% | 49,550.0 | 2.8% | 55,176.0 | 2.6% | 50,801.0 | 2.7% |
| **AAGR 2008-2017** | - | **1.8%** | - | **2.0%** | - | **1.9%** | - | **2.1%** |
| **2018** | 45,968.9 | 3.0% | 51,056.0 | 3.0% | 56,793.0 | 2.9% | 52,321.0 | 3.0% |
| **2023** | 55,060.0 | 3.7% | 61,431.0 | 3.8% | 67,973.0 | 3.7% | 62,813.0 | 3.7% |
| **2028** | 68,830.3 | 4.6% | 77,190.0 | 4.7% | 85,034.0 | 4.6% | 78,738.0 | 4.6% |
| **2033** | 87,070.3 | 4.8% | 98,339.0 | 5.0% | 108,019.0 | 4.9% | 99,977.0 | 4.9% |
| **2038** | 110,462.2 | 4.9% | 125,762.0 | 5.0% | 137,841.0 | 5.0% | 127,307.0 | 5.0% |
| **AAGR 2018-2038** | - | **4.5%** | - | **4.6%** | - | **4.5%** | - | **4.5%** |

Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017 – Woods & Poole Economics, Inc., CHA, 2018.

**Figure 3-5 – Per Capita Income (Historical & Projected)**




Note: Woods & Poole Economics, Inc. data is estimated.
Source: 2017 – Woods & Poole Economics, Inc., CHA, 2018.

## 3.3 COMMERCIAL ACTIVITY REGION AND DESTINATIONS

This section provides a brief overview of recent commercial aviation trends at ORF. The section then identifies four different methodologies analyzed for developing the commercial passenger

forecast and makes the final recommendation for commercial passengers and operations through FY 2038. Cargo trends and the forecast are covered later in the chapter.

### 3.3.1 Region and Destinations

As of the August 2018 published schedule, ORF had service to 26 destinations (23 year-round and three seasonal destinations), via six air carriers: Allegiant Air (G4), American Airlines (AA), Delta Air Lines (DL), Frontier (F9), Southwest (WN), and United Airlines (UA). Southwest was the largest airline at ORF in terms of seats per departure in FY 2017, followed by Delta, United, and American, respectively. Since Allegiant did not begin operating at ORF until September 2017, it was not incorporated in the seats per departure evaluation. As shown in **Table 3-4**, ORF, Richmond International Airport, Newport News/Williamsburg International Airport, and Pitt-Greenville Airport have varied numbers of destinations and non-stop domestic flights.

**Table 3-4 – Comparison of Airports in the Region**

| Flights | ORF | RIC | PHF | PGV |
|---|---|---|---|---|
| Nonstop Destinations | 26 | 17 | 3 | 1 |
| Avg. Daily Flights | 137 | 200 | 16 | 8 |

Source: Airport Websites (ORF, RIC, PHF, PGV), NAA, CHA, 2018.

***New Service Announcements***

Although common for airports to receive new service, in the case of ORF, the amount of new service announcements occurring as of recent is uncommon. Between September 2017 and the development of the forecasts herein, ORF saw 13 new service announcements from five different carriers. These new service announcements included nine new destinations and multiple carriers to Denver International Airport (DEN). In addition to new destinations, airlines increased capacity and frequency to existing destinations, as detailed in subsequent sections of this chapter. See **Table 3-5** and **Appendix H**.

**Table 3-5 – New Service Announcements/Increases in Capacity [7]**

| Airline | Destination | Service Launch |
|---|---|---|
| Allegiant | CLE | June 7, 2019 |
| | CVG | June 7, 2019 |
| | JAX | June 14, 2018 |
| | SFB | November 17, 2017 |
| | FLL | November 17, 2017 |
| | PIE | October 4, 2017 |
| Delta | BOS | September 10, 2017 |
| | MSP | June 14, 2018 |
| Frontier | DEN | August 12, 2018 |
| | LAS | August 12, 2018 |
| | MCO | August 12, 2018 |
| | PHX | November 17, 2018 |
| | TPA | November 17, 2018 |
| Southwest | BNA | June 9, 2019 |
| | SAN | June 9, 2019 |
| | DEN | June 7, 2018 |
| United | DEN | June 7, 2018 |

Source: Airport and Airline Representatives, CHA, 2018.

[7] Nashville International Airport (BNA), Boston Logan International Airport (BOS), Cleveland Hopkins International Airport (CLE), Cincinnati/Northern Kentucky International Airport (CVG), Fort Lauderdale-Hollywood International Airport (FLL), Jacksonville International Airport (JAX), McCarran International Airport (LAS), Orlando International Airport (MCO), Minneapolis-St. Paul International Airport (MSP), Phoenix Sky Harbor International Airport (PHX), St. Pete-Clearwater International Airport (PIE), San Diego International Airport (SAN), Orlando Sanford International Airport (SFB), Tampa International Airport (TPA). (See **Figure 1-4** for ORF's Non-Stop Route Map).

## 3.4 COMMERCIAL ACTIVITY HISTORICAL TRENDS

***Enplanements***

An enplanement is defined as a revenue-paying passenger boarding an aircraft at a given airport. Enplanements are the primary measure of a commercial service airport's passenger activity and are key factors for terminal building and parking facility requirements. In addition to being an important trend tracking tool for airport management, an airport's reported annual enplanements are also used by the FAA to calculate Airport Improvement Program (AIP) passenger entitlement funding through its apportionment formula. For the purposes of this Study, forecast enplanements serve as the basis for the Airport's facility requirements and financial projections. These include:

- Airfield Requirements
- Airline Support Functions
- CBP/FIS Facilities
- Non-Public Areas
- Secured Public Areas
- Non-Secured Public Areas
- Concessions
- Surface Transportation and Parking Requirements
- Service Animal Relief Area


Historical enplanements at ORF have shown to ebb and flow consistent with most small-hub commercial service airports since FY 2008, showing fluctuating enplanement levels over the historical period; however, in FY 2017, ORF reached its highest level of enplanements since FY 2010 with approximately 1,672,024 enplanements, as shown in **Figure 3-6**. The historical decline in enplanements can be attributed to the 2007-2009 economic recession which had a heavy impact on the aviation industry, specifically smaller commercial service airports, including ORF. Additional factors include higher fare rates on legacy carriers, military sequestration that impacted the Hampton Roads region, and the lack of low-cost options in the market; however, after sequestration and the introduction of ultra-low-cost carriers, ORF began to see consistent growth in enplanements beginning in FY 2015. From 2015 to 2016, enplanements grew by 6.9 percent, with an additional increase of 4.3 percent from FY 2016 to FY 2017. Based on the previously mentioned influx of new airlines, ultra-low-cost carriers, and travel destinations, this trend is anticipated to continue through the short-term (five-year) time frame, ultimately resulting in steady growth for ORF.

***Operations***

Commercial operators include scheduled air carriers and their regional partners. Similar to enplanements, ORF has seen a decline in air carrier operations since FY 2008, as shown **in Figure 3-7**, specifically reaching the lowest number of operations in FY 2015, the lowest in 10-years for the Airport. The drastic decline in air carrier operations can be attributed to a number of factors including airline bankruptcies and consolidation, higher fuel prices, the economic recession, and airlines transitioning their fleets from smaller 50-seat regional jet to larger 60-90 seat regional jet and narrow-body aircraft. On the surface, the decrease is significant, resulting in lower flight frequencies on some routes; however, this is not indicative of passenger activity at the Airport. Although operations are still below their peak in FY 2008, with the recent airline transitions to


larger aircraft equipment, passenger enplanements have steadily increased; however, the number of operations necessary to accommodate the increased demand is lesser with larger 90-177 seat aircraft.

**Figure 3-6 – Enplaned Passengers at ORF**




Source: NAA, CHA, 2018.

**Figure 3-7 – Commercial Operations at ORF**





AAGR Change in Operations 2008-2017: -3.0%
Source: NAA, CHA, 2018.

### *Commercial Seats and Average Aircraft Size*

ORF'S approximate 4.2 million scheduled seats in FY 2017 was relatively consistent with the previous nine years, with fluctuations between approximately 5.1 million in FY 2008 and 3.6 million in FY 2015. As shown in **Figure 3-8**, FY 2008 was the peak year with approximately 5.1 million seats. The number of seats decreased between FY 2011 and FY 2015, averaging 4.2


million. During the nine-year period, ORF's scheduled seats reached its lowest count in FY 2015 with 3.5 million seats. This can be attributed to the previously mentioned transition in airframe from smaller 50-seat aircraft with increased frequency to larger regional jets (RJs) and narrow-body aircraft. It is important to note the sharp increase in seats per departure in FY 2017 because of this transition. See **Figure 3-9** for average seats per departure.

**Figure 3-8 – Scheduled Seats at ORF**




Source: NAA, CHA, 2018.

**Figure 3-9 – Average Seats per Departure**




Source: NAA, CHA, 2018.

***Historical Commercial Fleet Mix***

The types of commercial aircraft serving ORF in a typical week in July, the Airport's peak month, in the years 2008, 2013, and 2017 are shown in **Table 3-6** below. July was chosen because it showed to have schedule continuity. ORF continues to be served, in large part, by 50-seat regional jets; however, as shown below, with the recent announcements by Allegiant and

Frontier, the transition from smaller 50-seat CRJ200s to larger regional jet and narrow-body aircraft will be sooner than originally anticipated.

**Table 3-6 – Commercial Aircraft Serving ORF (July)**

| Aircraft Type | July 2008 | July 2013 | July 2017 | Seating Capacity |
|---|---|---|---|---|
| CRJ-2/4 | 1,108 | 1,180 | 1,176 | 50 |
| ERJ145 | 741 | 678 | 642 | 50 |
| MD80 | 414 | 208 | 503 | 130-172 |
| CRJ900 | 76 | 233 | 418 | 76 |
| B737-7 | 534 | 537 | 361 | 140 |
| CRJ700 | 630 | 454 | 257 | 65-70 |
| A319 | 57 | 163 | 206 | 130-140 |
| B757-2 | - | 111 | 123 | 169-185 |
| A320-1/2 | 72 | | 116 | 150-177 |
| E175 | 257 | 77 | 109 | 76 |
| B737-8 | 2 | 10 | 90 | 162, 189 |
| B737-9 | - | - | 86 | 177, 189 |
| B737-3 | 393 | 316 | 80 | 145-188 |
| DHC8-200 | - | - | 30 | 37 |
| E170 | 252 | 76 | 22 | 70 |
| DHC8-300 | 2 | - | 12 | 48-50 |
| MD90 | - | 220 | 10 | 158 |
| B737-4 | - | - | 2 | 143-180 |
| PC-12 | - | - | 2 | 8 |
| B737-5 | 5 | 3 | - | 143-180 |
| DASH8-1 | 264 | 157 | - | 37 |
| DASH8-Q4 | 302 | 279 | - | 68-90 |
| DC-9-30 | 2 | - | - | 105 |
| DC-9-40 | 5 | - | - | 125 |
| DC-9-50 | 54 | - | - | 139 |
| EMB120 | - | 29 | - | 21-40 |
| ERJ135 | 16 | - | - | 37 |
| E190 | 181 | 2 | - | 100-124 |
| CRJ100/ER | 226 | - | - | 50 |
| **TOTAL** | **5,593** | **4,733** | **4,245** | **-** |


Source: NAA, CHA, 2018.

***Load Factor***

Load factor (LF) measures the capacity utilization and was used to measure efficiency in filling air carrier seats and in generating revenue. LF was calculated by dividing the total number of revenue passengers by total available seats. The LF at ORF, as depicted in **Figure 3-10**, decreased from 75.2 percent in FY 2009 to a low of 71.3 in FY 2013, a 3.9 percent drop. LFs began rising in FY 2014 and reached a high of 83.8 in FY 2015, a 12.5 percent increase from FY 2013. From FY 2008 to FY 2017, ORF experienced a 6.1 percent increase in LF; however, LF began decreasing again in recent years (FY 2015 to FY 2017). The decrease in LF can be attributed to the airlines' transitions in fleet mixes. Currently, airlines are increasing aircraft seating capacities at a quicker rate than what is dictated by demand. From FY 2015 to FY 2017, ORF experienced a growth of

18.1 percent in the number of available seats, while total passenger counts only increased by 11.4 percent.

**Figure 3-10 - Commercial Load Factors**




Source: NAA, CHA, 2018.

## 3.5 COMMERCIAL ACTIVITY DEMAND FORECASTS

To determine the facility sizing requirements necessary to adequately accommodate the current and future activity demand, a forecast of annual enplaned passengers and annual commercial aircraft operations was developed. The most basic indicator of activity demand for a commercial service airport is the number of annual enplaned passengers. It is the number of forecast enplanements that drive passenger terminal sizing requirements, and to a lesser extent, commercial air carrier operations and fleet mix. Historical and forecast enplanement data can provide relevant evidence that improvements and/or expansions to an airport may be necessary. Commercial aircraft operations and fleet mix influence the requirements for passenger terminal and airside infrastructure.

This section provides the methodology for the development of the forecasts of commercial enplanements and operations at ORF, as well as the methodologies analyzed for developing the commercial forecast, and details the final recommendation for commercial passengers and operations through FY 2038.

### 3.5.1 Enplanements Forecast

***Forecast Methodologies***

Several FAA-approved forecast methodologies and statistical analyses were used to provide a range of potential passenger activity levels. From these forecasts, a recommended forecast was developed that represents the most likely projection of future activity based on existing data and current trends (detailed in the following section) in passenger activity.

Four different methodologies were considered and analyzed in the development of the recommended ORF enplanement forecast. Each of the methodologies, along with accompanying enplanement forecasts, are shown below and then compared to each other.

Forecast Methodologies

- Historical Trend – A method to predict the future based on past results. The 5- and 10-year annual growth rates were calculated and used to estimate growth at ORF.
- Market Share Analysis – A "top-down" method where projected growth rates of larger aggregates (e.g., the nation, the state, and/or the region) are used to derive forecasts for smaller areas (e.g., airports). In other words, a market share forecast essentially applies national, state, and/or regional forecast growth rates to airport-specific market areas. For this analysis, future ORF enplanements were estimated by applying the future share trend and the FAA's National TAF enplanement numbers.
- Regression Analysis – An examination of aviation and passenger activity through the scope of current and historical activity levels, seeking to find a relationship between the activity levels and the socioeconomic conditions prevalent during that period. Causal relationships between population, employment, and income are examined to determine if there is a statistically valid correlation that may assist in projecting future activity. Demographic projections for the catchment area, provided by Woods & Poole Economics, Inc., were used to estimate growth at ORF.
- Air Service Analysis – ORF enplanements and operations were estimated based on FY 2017 schedules filed by the air carriers and included expected service changes, as well as the potential for additional air carriers and service routes, for FY 2018 through FY 2038. Key forecast assumptions were developed to include expected schedule changes, average seats per departure, and percentage of seats filled (load factor). This methodology included multiple facets, such as air service growth in varying market sectors including the Ultra Low-Cost Carrier (ULCC), Legacy Carrier, and International market segments. Although this methodology was a singular methodology, it was linear in nature as varying air service scenarios can be combined to determine a service analysis across multiple market platforms.

**Appendix B** presents the findings of all the previously described methodologies.

***Historical Trend***

A historical trend forecast is a simple time-series model that relies on extrapolating historical enplanements and operations growth, specific to the Airport, into the future. Examining the historical growth rates and projecting them forward provides a picture of growth, assuming the market area and the state of the commercial passenger airline industry reflect past trends through the forecast period. For the historical trend scenario, the historical enplanement data was projected forward through the forecast horizon.

As previously mentioned (in **Section 3.4, Commercial Activity Historical Trends**), ORF's historical trend of passenger enplanements have shown to ebb and flow consistent with most small-hub commercial service airports since FY 2008, showing fluctuating enplanement levels over the

historical period. In FY 2017, ORF reached its highest level of enplanements (1,672,024 in FY 2017) since FY 2010 (1,697,663 in FY 2010). The AAGR from FY 2008 to FY 2017 was negative 1.0 percent; however, from FY 2015 to FY 2016, ORF experienced a 6.92 percent growth in enplanements, along with another 4.3 percent growth from FY 2016 to FY 2017. For the purposes of the Historical Trend Analysis, two scenarios were identified in the evaluation (5-year and 10-year) of the time series model, as shown in **Table 3-7**.

As shown in **Figure 3-11**, the historical time trend analysis resulted in varying degrees of growth rates. The cyclical nature of passenger growth of the previous 10-year period at ORF revealed a steady drop in enplanements between the 5- and 10-year period. The following details the AAGR within the various time periods included in this evaluation:

- 5-Year Historical Trend – resulted in a 0.7 percent AAGR FY 2013-2017
- 10-Year Historical Trend – resulted in a negative 1.0 percent AAGR FY 2008 -2017


**Table 3-7 – Historical Trend Forecast Comparisons**

| Fiscal Year | TAF | 5-Year Time Series | 10-Year Time Series |
|---|---|---|---|
| **2017** | 1,652,323 | 1,672,024 | 1,672,024 |
| **2018** | 1,815,241 | 1,683,609 | 1,655,925 |
| **2023** | 2,147,644 | 1,742,750 | 1,577,724 |
| **2028** | 2,294,704 | 1,803,969 | 1,503,217 |
| **2033** | 2,458,050 | 1,867,338 | 1,432,228 |
| **2038** | 2,627,295 | 1,932,933 | 1,364,591 |
| **AAGR 2018-2038** | **1.9%** | **0.7%** | **-1.0%** |
| **Growth 2018-2038** | **44.7%** | **14.8%** | **-17.6%** |

Source: FAA 2018 TAF, NAA, CHA, 2019.

The 5-year and 10-year time trend scenarios represented projections that are significantly less than the TAF (19.5 percent and 43.2 percent, respectively); therefore, based on recent growth trends, these scenarios were not considered to be reliable projections.

**Figure 3-11 – Historical Trend Time Series**




Source: FAA 2018 TAF, NAA, CHA, 2019.

***Market Share Analysis***

In a market share forecast, the dependent variables of the item being forecast (i.e., airport specific operations or enplanements) are compared to independent variables of a larger aggregate (i.e., region, state, or national operations or enplanements). For example, ORF had an identified enplanement level within each fiscal year. When this level was compared to a total of a larger whole (national enplanements), a percentage (i.e., market share) could be determined. This analysis showed that growth in an airport's market can be correlated to aviation activity on a larger scale. Through a direct comparison of various levels of enplanement projections versus ORF market area growth rates, the forecasts were adjusted to reflect differing larger scale markets to local growth trends. (See **Appendix A** for a breakdown of annual market share for each scenario including historical market share).

- Average National Market Share – This methodology used the aggregate, national level forecast of commercial enplanements identified in the FAA's 2018 TAF to derive forecasts for the Airport based on market share. This forecast assumed that ORF will maintain a level market share based on its 10-year average, or static market share, of commercial enplanements (0.22 percent) relative to national activity projections throughout the planning period.
- Static State Market Share – While similar to the National Market Share methodology, this forecast used State activity projections derived from the 2018 TAF[8] and airport reported enplanement levels as the basis for determining market share. This forecast assumed that ORF will maintain its current FY 2017 level of commercial enplanements (6.24 percent) relative to State market activity projections throughout the planning period. The Static State Market Share forecast was considered a relatively conservative range of potential commercial activity based on market conditions within the State; therefore, for the purposes of this forecast, this scenario was chosen to represent the low-end range of possible enplanements for ORF. See **Section 3.5.4 (Effective Enplanements Range)** for further detail.
- Static Regional Market Share – This methodology used the aggregate, regional level forecast of commercial activity projections from the FAA's 2018 TAF for the individual commercial service airports in the Virginia and northeast North Carolina region, which includes ORF, RIC, PHF, and PGV, to derive forecasts for the Airport based on market share. This forecast assumed that ORF will maintain its current level, or static market share (44.96 percent), of commercial enplanements relative to regional activity projections throughout the planning period.


[8] In this scenario, it is important to note that in addition to the TAF for Virginia, the 2018 TAF for the District of Columbia was incorporated because the TAF accounts for three airports located in Virginia: Ronald Reagan Washington National Airport (DCA), Washington Dulles International Airport (IAD), and Manassas Regional Airport (HEF).

**Table 3-8 – Market Share Comparisons**

| Year | TAF | Average National Market Share | Static State Market Share | Static Regional Market Share |
|---|---|---|---|---|
| **2017** | 1,652,323 | 1,672,024 | 1,672,024 | 1,672,024 |
| **2018** | 1,815,241 | 1,953,884 | 1,723,608 | 1,816,656 |
| **2023** | 2,147,644 | 2,237,531 | 2,035,945 | 2,224,870 |
| **2028** | 2,294,704 | 2,450,873 | 2,231,077 | 2,407,978 |
| **2033** | 2,458,050 | 2,686,764 | 2,407,453 | 2,617,059 |
| **2038** | 2,627,295 | 2,936,370 | 2,582,498 | 2,839,646 |
| **AAGR 2018-2038** | **1.9%** | **2.1%** | **2.0%** | **2.3%** |
| **Growth 2018-2038** | **44.7%** | **50.3%** | **49.9%** | **56.3%** |

Source: FAA 2018 TAF, NAA, CHA 2019.

**Figure 3-12 – Market Share Time Series**




Source: FAA 2018 TAF, NAA, CHA, 2019.

***Regression Analysis***

As mentioned previously, regression-based forecasts examine aviation and passenger activity to determine if there is a causal relationship between the activity levels and the socioeconomic conditions prevalent during that period. Several different economic-, income- and population-based regression analyses were performed. The first step was to conduct a regression analysis to determine if there was a relationship between any of the socioeconomic factors (i.e., population, income, and employment) addressed earlier in the chapter and the historical level of enplanements. The output of a regression analysis is the 'coefficient of determination', or $R^2$, which ranges from 0 to 1.0. If the $R^2$ of an analysis falls between 0.85 and 1.0, there is a statistical correlation; if it falls below 0.85, there is not a statistical correlation. In other words, the higher the $R^2$ value, the stronger the correlation is between the variables; however, if the $R^2$ of an analysis is above 1.0, an anomaly, or outlier, has been detected.

The following regression analyses were conducted:

- Population-Based Regression: R2-value = 0.48
- Employment Based Regression: R2-value = 0.00
- Income-Based Regression: R2-value = 0.36
- Population-Income Regression: R2-value = 0.64
- Employment-Income Based Regression: R2-value = 0.67
- Population-Income-Employment Regression: R2-value = 0.71

Though the socioeconomic indicators have grown at rates that are consistent with those at the state and national levels, the 10-year historical ORF enplanements have shown to primarily trend down, with small pockets of annual growth in first seven years of the 10-year historical period: declining from 2008 to 2010, increasing in 2010, and then declining again until 2016. In FY 2016, enplanements began rising and continued throughout FY 2017. As discussed in **Section 3.4**, the overall decline in passengers and cyclical nature of growth and declines within the 10-year historical period can be attributed to regional and national economic impacts. For example, national recession, military sequestration, and high fare prices all contributed to decreasing enplanement activity at ORF. Based on these parameters and fluctuations in Airport activity, it is evident that there may be poor correlation between the 10-year relatively stable socioeconomic history in the study area and the Airport.

Recently, with the introduction of ultra-low-cost carriers, and competitive service routes, ORF enplanement figures have begun to rebound and trend towards historical highs. As such, the 10-year historical socioeconomic regression analyses did not show a strong correlation to enplanements to serve as the preferred forecast scenario. The results of these analyses are presented in **Table 3-9**. Additional, more in-depth regression analyses were performed, and similar to the forecast, were not considered realistic for representation of enplanements at ORF. All additional regression analyses are summarized in **Appendix C**.

**Table 3-9 – Regression Comparison**

| Year | TAF | Population -Based | Employment-Based | Income-Based | Population-Income Based | Employment-Income Based | Population-Income-Employment-Based |
|---|---|---|---|---|---|---|---|
| **2017** | 1,652,323 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 |
| **2018** | 1,815,241 | 1,513,586 | 1,657,072 | 1,524,971 | 1,546,545 | 1,585,688 | 1,575,919 |
| **2023** | 2,147,644 | 1,356,750 | 1,661,755 | 1,326,358 | 1,617,702 | 1,428,578 | 1,547,086 |
| **2028** | 2,294,704 | 1,200,085 | 1,666,352 | 1,025,523 | 2,047,371 | 1,080,783 | 1,602,247 |
| **2033** | 2,458,050 | 1,052,830 | 1,670,798 | 627,038 | 2,856,304 | 547,830 | 1,755,160 |
| **2038** | 2,627,295 | 925,988 | 1,675,099 | 116,000 | 4,140,458 | -197,307 | 2,041,693 |
| **AAGR 2018-2038** | **1.9%** | **-2.4%** | **0.1%** | **-12.1%** | **5.0%** | **-9.9%** | **1.3%** |
| **Growth 2018-2038** | **44.7%** | **-38.8%** | **1.1%** | **-92.4%** | **167.7%** | **-112.4%** | **29.6%** |

Source: FAA 2018 TAF, NAA, CHA, 2019.

***Air Service Forecasts***

The air service analysis acknowledged historic market share growth and recent airline activity trends including the new routes, increased airframes on specific routes, and high load factors. In addition, this scenario took into account the new service announcements made during the 12-month period prior to the development of the forecasts and anticipated service announcements within the following 12-month period, as discussed with airline representatives at ORF. The following describes the methodology and development of the air service analysis in further detail.

As assessed in **Section 3.4**, per the FAA TAF for the Airport, ORF experienced record growth in enplaned passengers from FY 2015 to throughout FY 2018. Though this spike in growth is not directly sustainable throughout the 20-year forecast period, it was assumed to continue through the short-term forecast period (five-years), as evidenced by the increasing number of new service announcements and announcements of service expansion to existing destinations (discussed in **Section 3.3.1**). This indicates that ORF continues to maintain a strong aviation presence within the regional and national air transportation systems.

As mentioned previously, the TAF considers socioeconomic and demographic factors, local industry growth, and regional commercial service growth on market basis. This scenario utilized the 2017 FAA TAF for baseline short-term growth (which at the time of the development of these forecasts, was the most recent TAF available) and applied additional airlines service that was recently announced, but not included in the FAA TAF, and included these new service operations for the first five years of the forecast period. For forecast years 2024 through 2038, long-term 10-year population regression variables (2014 through 2023) were applied and projected throughout the remainder of the forecast period. Although previous historical socioeconomic growth did not show a strong correlation, since the rebound of the recession and the end of military sequestration, the local and regional economic variables have been strong (**Section 3.2**), and future Airport growth can be directly attributable to population growth in the region.

This resulted in an analysis of non-stop route destinations from ORF that were experiencing higher than normal load factors operated by specific airlines. The following table provides load factors per airline destination, from FYs 2008 through FY 2017, which at the time of this report was the most recent Airport Authority-reported LF data.

The new service routes and the increase in airframe size and fleet mix transitions currently underway are anticipated to result in ORF capturing a larger percentage of travelers within the Airport's core market area. Through FYs 2015, 2016, and 2017, airlines serving ORF increased service to their existing network of hub airports [Hartsfield-Jackson Atlanta International Airport (ATL), Baltimore Washington International Airport (BWI), Charlotte Douglas International Airport (CLT), Ronald Reagan Washington National Airport (DCA), LaGuardia Airport (LGA), Chicago Midway International Airport (MDW), Miami International Airport (MIA), Chicago O'Hare International Airport (ORD), Denver International Airport (DEN), and Orlando Sanford International Airport (SFB)]. **Table 3-10** shows the historical load factors for ORF.

**Table 3-10 – Historical Load Factor Percentages by Destination**

| Destination | FY 2008 | FY 2009 | FY 2010 | FY 2011 | FY 2012 | FY 2013 | FY 2014 | FY 2015 | FY 2016 | FY 2017 |
|---|---|---|---|---|---|---|---|---|---|---|
| ATL | 83.9% | 86.2% | 79.5% | 78.4% | 76.4% | 70.6% | 80.8% | 87.4% | 86.6% | 83.6% |
| BOS | 50.5% | 63.5% | 88.5% | 75.9% | 67.1% | 53.9% | 55.7% | 81.0% | 86.9% | 74.4% |
| BWI | 68.6% | 70.1% | 75.8% | 75.0% | 75.4% | 68.8% | 78.3% | 83.7% | 82.0% | 77.4% |
| CLT | 72.4% | 79.9% | 78.7% | 76.5% | 80.8% | 81.0% | 84.5% | 89.2% | 84.0% | 84.8% |
| DCA | 55.9% | 61.8% | 54.3% | 47.6% | 56.8% | 62.5% | 66.6% | 76.8% | 67.4% | 67.7% |
| DEN | 82.5% | - | - | - | 95.4% | 50.0% | - | 91.4% | 98.6% | 93.5% |
| DFW | 75.8% | 80.9% | 81.0% | 80.7% | 78.7% | 77.6% | 83.6% | 84.4% | 81.8% | 82.6% |
| DTW | 80.6% | 82.0% | 74.4% | 75.0% | 79.3% | 76.3% | 77.4% | 81.2% | 78.9% | 76.4% |
| EWR | 68.6% | 65.9% | 60.9% | 56.6% | 66.1% | 65.9% | 72.1% | 78.4% | 79.3% | 75.5% |
| FLL | 75.2% | 87.3% | 92.0% | 91.2% | 87.1% | 66.6% | 88.2% | 91.9% | 64.6% | 83.7% |
| IAD | 80.2% | 78.1% | 76.8% | 72.5% | 75.5% | 78.7% | 81.8% | 82.8% | 85.9% | 77.7% |
| IAH | 89.8% | 89.7% | 88.2% | 84.1% | 74.3% | 84.1% | 88.9% | 85.1% | 83.3% | 85.1% |
| JAX | 71.8% | 66.7% | 71.1% | 63.8% | 58.6% | 62.2% | 64.0% | 94.9% | 84.7% | 91.1% |
| JFK | 65.8% | - | - | 69.8% | 69.3% | 65.0% | 72.7% | 66.6% | 66.9% | 69.6% |
| LGA | 45.4% | 59.4% | 54.2% | 51.9% | 54.3% | 46.9% | 53.9% | 63.9% | 60.5% | 58.8% |
| MCO | 69.6% | 71.3% | 73.2% | 67.5% | 72.4% | 65.9% | 88.8% | 88.9% | 83.8% | 87.3% |
| MDW | 68.9% | 68.5% | 76.1% | 78.5% | 78.3% | 76.6% | 89.4% | 89.6% | 78.4% | 78.9% |
| MIA | 79.7% | 81.3% | 68.2% | 72.5% | 78.0% | 80.2% | 82.9% | 83.6% | 77.3% | 81.3% |
| MSP | 79.0% | 67.4% | 80.9% | 74.5% | 82.1% | 82.9% | 79.6% | 85.4% | 84.2% | 75.5% |
| ORD | 84.3% | 81.6% | 79.8% | 76.5% | 80.9% | 83.7% | 87.5% | 87.9% | 83.2% | 80.6% |
| PHL | 63.8% | 68.2% | 60.8% | 61.5% | 68.2% | 67.7% | 76.0% | 85.3% | 77.3% | 80.1% |
| SFB | 0.0% | - | - | 98.7% | - | - | - | 88.3% | - | 89.8% |

Source: NAA, CHA, 2018.

The air service assumptions that were used in this analysis were then developed by applying historical load factor assumptions projected through the forecast period. The load factor was derived by using data, which was provided by Aviation DataMiner, to compute the estimated number of passengers per departure. The additional load factor assumptions were made based on fleet mix restructuring by individual airlines transitioning from smaller regional jets to larger regional and narrow-body jets.

The air service scenario was broken down into domestic short-term growth and domestic medium- to long-term growth scenarios. The domestic short-term growth scenario first built out a five-year annual schedule based on likely routes and services that were announced within the 12-month period prior to the development of the forecasts or are expected to be introduced soon. The domestic medium- to long-term growth scenario considered possible future routes that are either not guaranteed or are an aggressive assumption.

The following sections provide the assumptions applied to develop the domestic short-term growth and domestic medium- to long-term growth scenarios, assuming no loss in frequencies. It was assumed that the load factors will grow consistent with the overall airport load factors.

Domestic Short-Term Growth Assumptions:

Service Route Expansions

- ORF will experience an increase in enplanements in 2018 due to a legacy carrier expanding services in the fall to two of its current destinations. The routes will become year-round routes the following year.
  - Delta Air Lines to BOS
    - CRJ700, 65 seats/departure
      - 52 flights in 2018, increasing to 104 annual flights in 2019
  - Delta Air Lines to MSP
    - CRJ900, 96 seats/departure
      - 140 flights in 2018, increasing to 364 annual flights in 2019

New Routes Announced:

- In the summer of 2018, an airline currently serving ORF will begin seasonal service to two new destinations.
  - Allegiant Air to JAX
    - A320, 177 seats/departure
      - 26 annual flights throughout the planning period
  - Allegiant Air to FLL
    - A320, 177 seats/departure
      - 52 annual flights (2018) increasing to 104 throughout the planning period

- In 2018, a new ULCC service provider will provide service to three destinations new to ORF, expanding or potentially expanding to year-round in 2019.
  - Frontier Airlines to LAS
    - A320, 180 seats/departure
      - 60 flights in 2018, increasing to 156 annual flights in 2019
  - Frontier Airlines to PHX (Seasonal beginning Winter 2018)
    - A320, 180 seats/departure
      - 14 flights in 2018, increasing to 26 annual flights in 2019
  - Frontier Airlines to TPA (Seasonal beginning Winter 2018)
    - A320, 180 seats/departure
      - 14 flights in 2018, increasing to 26 annual flights in 2019

Additional Services

- In 2018, ORF will experience growth resulting from airlines currently operating, providing additional services to current locations serviced by competing airlines from ORF.
  - Southwest Airlines to DEN
    - B737, 143 seats/departure
      - 40 annual flights throughout the planning period
  - United Airlines to DEN
    - A319, 128 seats/departure

- 203 flights in 2018, increasing to 364 annual flights in 2019

- In 2018, a new ULCC service provider will be introduced, providing additional service to destinations serviced by other airlines operating at ORF. These routes will be serviced daily, year-round starting in 2018.
  - Frontier Airlines to DEN
    - A320, 180 seats/departure
      - 104 flights in 2018, increasing to 364 annual flights in 2019
  - Frontier Airlines to MCO
    - A320, 180 seats/departure
      - 104 flights in 2018, increasing to 364 annual flights in 2019

**Table 3-11 – Short-Term Growth Scenario**

| Fiscal Year | Enplanements |
|---|---|
| **2017** | 1,672,024 |
| **2018** | 1,857,487 |
| **2023** | 2,115,424 |
| **2028** | 2,376,990 |
| **2033** | 2,622,848 |
| **2038** | 2,834,623 |
| **AAGR 2018-2038** | **2.1%** |
| **Growth 2018-2038** | **52.1%** |

Source: NAA, CHA, 2019.

Domestic Medium- to Long-Term Growth Assumptions:

New Routes

- In the long-term, ORF will experience growth resulting from an airline currently operating at ORF beginning services to new destinations.
  - Two destinations to the southwest
    - A320, 177 seats/departure
      - 26 annual flights throughout the planning period (Starting in 2021)
    - A320, 177 seats/departure
      - 26 annual flights throughout the planning period (Starting in 2023)
  - One destination to the northeast
    - A320, 177 seats/departure
      - 26 annual flights throughout the planning period (Starting in 2023)

- In the long-term, new ULCC service providers will provide services to destinations not currently serviced by ORF.
  - Destination to the south
    - CRJ200, 50 seats/departure
      - 26 annual flights throughout the planning period (Starting in 2028)
  - Destination to the west
    - A320, 150 seats/departure
      - 104 annual flights throughout the planning period (Starting in 2028)

Additional Services

- In the long-term, ORF will experience growth resulting from airlines currently operating at ORF, as well as a new carrier, providing additional services to current locations only serviced by competing airlines from ORF.
    - Destination to the northeast
        - A320, 177 seats/departure
            - 26 annual flights throughout the planning period (Starting in 2023)
    - Destination to the west
        - B737, 143 seats/departure
            - 26 annual flights throughout the planning period (Starting in 2028)

**Table 3-12 – Medium-Long-Term Growth Scenario**

| Fiscal Year | Enplanements |
|---|---|
| **2017** | 1,672,024 |
| **2018** | 1,857,487 |
| **2023** | 2,234,279 |
| **2028** | 2,640,381 |
| **2033** | 3,022,093 |
| **2038** | 3,350,889 |
| **AAGR 2018-2038** | **2.99%** |
| **Growth 2018-2038** | **80.4%** |

Source: NAA, CHA, 2019.

The analysis for the Short-Term Air Service scenario resulted in an $R^2$ value of 0.85, and the Medium- to Long-Term resulted in an $R^2$ value of 0.90. Although the Medium- to Long Term forecasts considered new service routes and anticipated service route expansions and had a higher $R^2$ value, projecting Airport enplanement growth purely based on assumptions was not practical when trying to identify demand capacities in different areas of the Airport. As such, the Short-term forecast incorporated actual new service route and service route expansion announcements made at ORF within the 12-month period prior to developing the forecast. The 20-year projections made within these scenarios combined and incorporated recent airline activity trends at the Airport, socioeconomic variables within the Airport's catchment area, anticipated new service announcements within CY 2019, and strong socioeconomic growth throughout the forecast period; therefore, for planning purposes, the Short-Term Air Service forecast was used as the recommended commercial enplanement forecast in the Master Plan Update.

It is important to note that based on the comparison with the FAA TAF, the recommended forecast scenario projections fall within the FAA criteria for commercial forecasts as required by FAA AC 150/5070-6B, *Airport Master Plans*, which states enplanement and operational forecasts must be within 10 percent in the short-term (five-year) period and 15 percent within the 10-year period. **Table 3-13** details the recommended enplanement forecast against the FAA TAF for the 20-year forecast period.

**Table 3-13 – Recommended Commercial Enplanements Forecast vs. FAA TAF**

| Fiscal Year | Enplanements | | |
|---|---|---|---|
| | 2018 ORF TAF | Recommended Forecast | Recommended Forecast vs. TAF |
| **2017** | 1,652,323 | 1,672,024 | 1.2% |
| **2018** | 1,815,241 | 1,857,487 | 2.3% |
| **2023** | 2,147,644 | 2,115,424 | -1.5% |
| **2028** | 2,294,704 | 2,376,990 | 3.6% |
| **2033** | 2,458,050 | 2,622,848 | 6.7% |
| **2038** | 2,627,295 | 2,834,623 | 7.9% |
| **AAGR 2018-2038** | **1.9%** | **2.1%** | - |
| **Growth 2018-2038** | **44.7%** | **52.1%** | - |

Source: FAA 2018 TAF, NAA, CHA, 2019.

### 3.5.2 Commercial Operations Forecast

As assessed in **Section 3.4**, and as shown by the FAA TAF and Airport records provided by the NAA, ORF experienced dramatic growth in enplaned passengers from FY 2015 through FY 2017. It is highly likely that ORF's growth in enplanements will not be sustained at the rate of the past three years; however, it is anticipated that enplanements and air carrier operations will continue to incrementally increase throughout the 20-year planning horizon, which is acknowledged in the FAA TAF. Growth in commercial air carrier operations will likely be at a lesser pace than enplanements due to the expected transition to larger aircraft.

***Methodology***

The operations forecast from 2018 to 2022 came from the monthly schedule used for the creation of the domestic short-term growth scenario. The schedule was broken down by market, airline and equipment type. The long-term operation forecast from 2023 to 2038 was estimated by taking the recommended enplanement forecast, growth trends in percentage of seats filled, and average seats per departure to derive the long-term commercial operations forecast.

Commercial Load Factors

The forecast of ORF percentage of seats filled for FY 2018 through FY 2038 was calculated by dividing the forecasted enplaned passengers by the forecasted percentage of seats that were filled by year. The percentage of seats filled was determined by taking the estimated 2017 to 2022 percentage of seats filled and growing the seat factor modestly each year through 2038. Once the percentage of seats filled reached 85.0 percent per route, it was capped[9] at this value for all future years. This methodology was also included in the FAA TAF which had the national load factor continuing to grow each year through the end of the TAF period, capping between 86 and 87 percent[10].


To determine the estimated total seats-departures, the forecasted enplaned passengers per year were divided by the estimated percentage of annual seats filled. Total operations were forecast by multiplying total seats-departures by two (to get to total seats) and then dividing by the

[9] The 85% is a proxy, or benchmark, as airlines approach an 85 (or higher) percent load factor, they typically evaluate the cost and benefits of either increasing frequency of that route or upgrading to larger aircraft for the high-load factor routes. As such, for the purposes of this forecast, it was assumed that airlines would up-gauge aircraft.

[10] Provided in the Load Factor section of the 2017 National Forecast and FAA Aerospace forecast.

forecast of seats per departure by year. The forecast for average seats per departure was assumed to grow by 0.6 percent per year after 2022. The growth rate of 0.6[11] percent was a proxy from the 2017 National Forecast for domestic average aircraft seats per mile. Assumed within the forecast, by 2038, is the replacement of several equipment types currently flying at ORF with younger, more fuel-efficient aircraft of similar capacity. The resulting estimate for percentage of seats filled is shown in **Figure 3-13.**

**Figure 3-13 – ORF Percentage of Seats Filled**





Source: NAA, CHA, 2018.

Operations

As previously mentioned, aircraft size and service routes were both taken into consideration when determining load factors. The departure seats were calculated by taking each year's projected enplanements and multiplying by the corresponding year's average projected load factor. Average seats per departure were calculated by taking the total projected departure seats each year and dividing by the number of commercial departures during the corresponding year. Operations were then determined by multiplying the previously calculated departure seats by the average seats per departure, with the result then being doubled to account for departures and arrivals. The resulting forecast for total operations is shown in **Figure 3-14**.

[11] Provided in the Load Factor section of the 2017 National Forecast and FAA Aerospace forecast.

**Figure 3-14 – ORF Estimated Total Commercial Operations**




Source: NAA, CHA, 2018.

**Table 3-14** shows a summary of the recommended commercial enplanements and operations forecast, with average seats per departure and percent of seats filled detailed. As mentioned earlier in this section, average aircraft size grows at 1.5 percent per year after 2022, similar to the 2018 National FAA TAF change in domestic average aircraft seats per mile, and the percentage of seats filled results in 84.2 percent in 2038, an approximate total growth of 5.2 percent over the forecast period.

**Table 3-14 – Recommended Commercial Forecast**

| Fiscal Year | Enplanements | Operations | Average Seats Per Departure | Load Factor |
|---|---|---|---|---|
| **2017** | 1,672,024 | 47,195 | 89.8 | 79.0% |
| **2018** | 1,857,487 | 48,986 | 96.0 | 79.5% |
| **2023** | 2,115,424 | 51,889 | 100.5 | 81.1% |
| **2028** | 2,376,990 | 55,177 | 104.6 | 82.4% |
| **2033** | 2,622,848 | 57,488 | 109.4 | 83.4% |
| **2038** | 2,834,623 | 61,430 | 109.6 | 84.2% |
| **AAGR 2018-2038** | **2.1%** | **1.1%** | **0.7%** | **0.3%** |
| **Growth 2018-2038** | **52.1%** | **25.4%** | **14.2%** | **5.8%** |

Source: FAA Terminal Area Forecast, CHA, 2018.

### 3.5.3 Commercial Carrier Fleet Mix

The commercial aircraft fleet mix projections are a function of the scheduled commercial passenger air carriers that operate (or are expected to operate) at the Airport during the forecast period. Each carrier's anticipated future fleet mix (i.e., aircraft acquisitions, aircraft phase-outs, retirements, route demand, etc.) and forecast enplanement levels influence a carrier's aircraft type and level of operations. This data is then coupled with the forecasted commercial air carrier operations to determine the number of annual departures by aircraft type to the greatest extent practical. It is important to note that the assumptions provided within this section are a function of seats per departure and annual seats applied to an assumed LF. The operational fleet mix

forecast provided within this section serves as practical planning activity levels for the purposes of developing airside and terminal development initiatives.

The first step in determining ORF's future commercial carrier fleet mix was to identify the overall market trends that will drive future airline fleets, as well as aircraft fleet mix decisions specific to each airline operating at the Airport and its demand associated with individual routes by load factor. It is important to reiterate that overall passenger enplanements are projected to grow incrementally and maintain a positive stable growth throughout the planning period. With the increase in the number of short to medium haul, low-cost air carriers, and the replacement of older larger aircraft, such as early versions of the Boeing B737, Boeing 757, Airbus A320, and the MD80, the demand for smaller single-aisle aircraft has grown within the past two decades, trending the industry toward aircraft with fewer seats, peaking in 2007. In general, this has translated to a higher passenger load factor per flight; however, per the Boeing Commercial Market Outlook (2018-2037), domestic air carriers have begun trending away from regional jet aircraft and retiring smaller 50-seat aircraft at an accelerated rate.

These 50-seat aircraft are being replaced with larger 70- and 90-plus seat regional jets, as well as larger narrow-body aircraft; however, replacements will not keep pace with retirements. Boeing predicts that in 2030, the fleet of regional jets will consist of 760 aircraft, down from 1,780 in 2010. Single-aisle mainline aircraft will continue to comprise much of the domestic fleet and will increase market share from 56 percent in 2009 to 73 percent in 2030.

As with the predicted national fleet shift toward newer, larger, and more efficient aircraft, ORF-specific fleet mix characteristics and trends were identified and applied directly to the preferred passenger carrier forecasts through 2038. To provide a detailed picture of future ORF operations, the following assumptions were based upon airline-specific fleet plans and aircraft orders, as well as overall industry trends:

- Based on Airbus Fleet Orders and on discussions with airline representatives, Allegiant's McDonnell Douglas MD80 aircraft (166-seats) will be phased out of service and replaced with A319 and A320 series aircraft. Although most Allegiant sources (AllegiantAir.com) show the phase out of the MD80 aircraft happening by calendar year (CY) 2019, according to airline representatives the final MD80/90 series flight is expected to be completed in November 2018. For forecasting purposes, it was assumed that the smaller A319 (128 to 132-seats) will be used to service non-peak routes and the larger A320 (177-seats) will be used during peak periods and high demand flights. Based on the age of the aircraft, and no orders or deliveries of the A319 aircraft identified on the Airbus website, it was assumed that the A319 operations will be transitioned to the newer A320s.
- As announced in 2016 (Delta.com), Delta is currently planning an aggressive overhaul of their small-plane fleet both through the mainline carrier and Delta Connection carriers. According to Delta.com, the airline plans to buy larger regional jets with a list value up to $2.3 billion, pending pilot union approval. This will provide Delta the option of adding 50 aircraft, each with 70-76 seats. This is indicative of the airline progressing towards eliminating their fleet of 50-seat aircraft.

- Delta Air Lines regional jet aircraft with a passenger capacity of 50-seats or under (CRJ200, ERJ145, ERJ140, etc.) will be gradually phased out of service and replaced with larger 70-seat plus regional jet aircraft (CRJ700/900) and larger narrow-body B717s, which were leased from Southwest after the Southwest/Air Tran merger.
- In addition to transitioning to larger RJs and B717s, according to a Delta Air Lines press release (Delta.com), and according to Bombardier Orders & Deliveries, Delta Air Lines has ordered 75 A220 (formerly Bombardier CS100s) airplanes (pending congressional legislation on imports). This aircraft will be utilized on the short- and medium-haul routes and will host a two-class 100-seat configuration. It is unlikely that ORF will see this airframe in the short-term, however in the five- to 15-year time frame it is likely this airframe will serve the ORF-ATL route.
- According to SkyWest Airlines representatives, the airline is in transition to flying primarily dual-class aircraft on its CRJ operations (specifically through ExpressJet) by reducing the number of CRJ200s in service. This will result in an increase of ERJ145 operations as the airline (ExpressJet) will not phase out these aircraft until a later date (unannounced). Currently, the ExpressJet fleet consists of 35 CRJ700s, 28 CRJ900ERs, and 164 ERJ145s. In December 2016, SkyWest announced that ExpressJet and American Airlines have agreed to place 12 dual-class CRJ700s into a multi-year service term.
- CRJ200 operations on short stage length flights (i.e., ORF to BWI) via smaller regional feeder airlines are expected to remain in the short-term period and are expected to transition out of service in the short- to medium-term time periods. This transition is assumed to take place over the next five years.

Using ORF's commercial air carrier schedule data provided by Aviation DataMiner and supplemented by the NAA, the commercial air carrier fleet mix forecast considered the assumptions listed above, as well as the projected annual departures for the Airport associated with the enplanement projections listed in the recommended forecast. A departure is considered a single operation, while an arrival is another. Simply put, departures equal one-half of total operations. For future facility planning purposes, annual commercial operations were converted to operations by aircraft type for select years. The 2017 fleet mix was taken as the baseline, with adjustments for retiring fleet types (e.g. MD80s, Dash-8s, 50-seat regional jets) and reasonable replacement aircraft types through the forecast period. **Table 3-15** below shows the fleet mix and departures for FYs 2018, 2023, 2028, 2033, and 2038.

**Table 3-15 – Commercial Fleet Mix**

| Aircraft Series | Operations | | | | | |
|---|---|---|---|---|---|---|
| | FY 2017 | FY 2018 | FY 2023 | FY 2028 | FY 2033 | FY 2038 |
| **B737-7** | 4,108 | 7,175 | 7,600 | 8,082 | 8,420 | 8,998 |
| **CRJ-700** | 3,205 | 2,687 | 4,524 | 6,159 | 7,822 | 8,358 |
| **ERJ-170/175** | 2,701 | 2,900 | 4,340 | 5,964 | 7,619 | 8,142 |
| **EMB-190/195** | 0 | 378 | 5,053 | 5,373 | 5,598 | 5,982 |
| **A320** | 840 | 3,077 | 5,049 | 5,369 | 5,594 | 5,977 |
| **A220** | 0 | 0 | 3,560 | 4,362 | 4,544 | 4,856 |
| **A319** | 2,699 | 3,583 | 3,795 | 4,036 | 4,205 | 4,493 |
| **B737-8** | 1,821 | 3,402 | 3,603 | 3,832 | 3,992 | 4,266 |
| **EMB E2*** | 0 | 0 | 1,866 | 3,575 | 3,724 | 3,980 |
| **CRJ-900** | 1,685 | 2,728 | 2,890 | 3,073 | 3,202 | 3,421 |
| **B737-9** | 904 | 1,441 | 1,526 | 1,623 | 1,691 | 1,807 |
| **A321** | 0 | 119 | 538 | 1,009 | 1,051 | 1,123 |
| **B767-4** | 4 | 17 | 18 | 20 | 20 | 22 |
| **CRJ-2/4** | 14,209 | 7,184 | 5,073 | 2,697 | 0 | 0 |
| **EMB-145** | 5,940 | 2,824 | 1,496 | 0 | 0 | 0 |
| **B717-2** | 374 | 703 | 542 | 0 | 0 | 0 |
| **B757-2** | 1,205 | 776 | 411 | 0 | 0 | 0 |
| **MD-80 Series** | 5,959 | 5,882 | 0 | 0 | 0 | 0 |
| **DASH8-1** | 777 | 386 | 0 | 0 | 0 | 0 |
| **ATR 42s** | | 94 | 0 | 0 | 0 | 0 |
| **B737-3** | 756 | 0 | 0 | 0 | 0 | 0 |
| **B737-4** | 48 | 0 | 0 | 0 | 0 | 0 |
| **A330-3** | 4 | 0 | 0 | 0 | 0 | 0 |
| **Other** | 5 | 5 | 5 | 6 | 6 | 6 |

*E2 represents the new E2 Boing Embraer line including the E175/109/195
Source: NAA, CHA, 2018.

### 3.5.4 Effective Enplanements Range

The purpose of this forecast is to reasonably predict future airport activity to support development at the Airport throughout the forecast period and to provide a realistic range of annual enplanements which drive all other aspects of commercial activity at the airport. **Figure 3-15** depicts a range of enplanement forecasts in comparison to the FAA TAF. This range was considered during the demand capacity and facility requirements evaluation in the subsequent chapters of this Study. The purpose of this range is to provide the Norfolk Airport Authority (NAA) with a basis from which to plan future development at the Airport. The range (used in the subsequent chapter for facility demand capacity calculations), provides varying Planning Activity Levels (PALs), described in subsequent chapters, which were used as benchmarks for future development.


As mentioned previously, the Low-Growth scenario was derived from the Static State Market Share forecast described in **Section 3.5.1 (Market Share Analysis)**. The High-Growth forecast (Medium- to Long-Term Air Service Scenario) shown was derived from a similar methodology as the recommended forecast (five-year schedule through 2022 and long-term regression variables determining projections through 2038), and the High-Growth forecast incorporates the remainder of non-population socioeconomic variables (employment, income, GRP) to determine the long-term forecast. This resulted in an $R^2$ value of .90 and 3,167,611 enplanements by 2038.

**Table 3-16 – Comparison of Enplanements Forecast Scenarios**

| Fiscal Year | Enplanements | | | |
|---|---|---|---|---|
| | ORF TAF | Low-Growth | Recommended | High-Growth |
| **2017** | 1,652,323 | 1,672,024 | 1,672,024 | 1,672,024 |
| **2018** | 1,815,241 | 1,723,608 | 1,857,487 | 1,857,487 |
| **2023** | 2,147,644 | 2,035,945 | 2,115,424 | 2,234,279 |
| **2028** | 2,294,704 | 2,231,077 | 2,376,990 | 2,640,381 |
| **2033** | 2,458,050 | 2,407,453 | 2,622,848 | 3,022,093 |
| **2038** | 2,627,295 | 2,582,498 | 2,834,623 | 3,350,889 |
| **AAGR 2018-2038** | **1.9%** | **2.04%** | **2.1%** | **2.99%** |
| **Growth 2018-2038** | **44.7%** | **49.83%** | **52.6%** | **80.4%** |

Source: FAA 2018 TAF, NAA, CHA, 2019.

**Figure 3-15 – Recommended Enplanement Forecast Range Comparison**




Source: FAA Terminal Area Forecast, CHA, 2018.

## 3.6 AIRPORT CATEGORIZATION

Based on FAA guidelines, ORF is categorized as a Commercial Service Airport – Primary, within the National Plan of Integrated Airport Systems (NPIAS). Primary airports are grouped into four categories defined as: large, medium, small, and non-hub airports. Primary airports receive an annual apportionment of federal grants based on the number of enplaned passengers at the airport. Based on the CY 2017 enplanements at ORF, the Airport qualifies as a primary, small-hub airport.

Small-hub airports are defined as airports that enplane 0.5 to 0.25 percent of the total U.S. passenger enplanements annually. Additionally, at the end of FAA CY 2017, ORF was ranked the 72nd largest airport in the United States by total number of enplanements (1,694,232 per FAA). This qualifies ORF as a small-hub airport within the NPIAS. **Table 3-17** below breaks down the categories of airport activities by classification and percentage of annual passenger boardings.

Based on the information shown below, and the FAA National Forecast for all commercial service airports, ORF is expected to remain in the small-hub category throughout the forecast period.

**Table 3-17 – NPIAS Airport Classifications**

<table>
<tr><th colspan="2">Airport Classifications</th><th>Hub Type: Percentage of Annual Passenger Boardings</th><th>Common Name</th></tr>
<tr><td rowspan="4">Commercial Service:<br>Publicly owned airports that have at least 2,500 passenger boardings each calendar year and receive scheduled passenger service<br>§47102(7)</td><td rowspan="3">Primary:<br>Have more than 10,000 passenger boardings each year<br>§47102(16)</td><td>Large:<br>1% or more</td><td>Large-Hub</td></tr>
<tr><td>Medium:<br>At least 0.25%,<br>but less than 1%</td><td>Medium-Hub</td></tr>
<tr><td>Small:<br>At least 0.05%,<br>but less than 0.25%</td><td>Small-Hub</td></tr>
<tr><td>Non-hub:<br>More than 10,000,<br>but less than 0.05%</td><td>Non-hub Primary</td></tr>
<tr><td>Nonprimary</td><td>Non-hub:<br>At least 2,500<br>and no more than 10,000</td><td>Non-primary Commercial Service</td></tr>
<tr><td colspan="2" rowspan="2">Nonprimary<br>(Except Commercial Service)</td><td rowspan="2">Not Applicable</td><td>Reliever<br>§(47102(23))</td></tr>
<tr><td>General Aviation<br>§(47102(8))</td></tr>
</table>

Source: FAA, CHA, 2018.

## 3.7 AIR CARGO FORECAST

Air cargo traffic is comprised of freight, express, and airmail. Air cargo is typically transported via three different methods: commercial air carrier "belly cargo", dedicated commercial cargo carriers (integrators), or all-cargo charter services. Air cargo activity and demand is cyclical in nature and fluctuates based on national and global economic trends. Factors that affect air cargo growth are fuel price volatility, movement of real yields, and globalization.

This section analyzes historical trends in air cargo traffic and aircraft operations and develops forecasts of commercial cargo (integrator) traffic and all-cargo aircraft operations by type, based on projected economic trends in the Hampton Roads Region. For the purposes of this forecast, only domestic air cargo analyses were evaluated. ORF does not currently have, and is not anticipated to receive, international air cargo services within the forecast period.

### 3.7.1 Historical Trends

Based on FAA records, ORF's cargo activity ranked 88$^{th}$ among U.S. airports in CY 2017 (in terms of all-cargo cargo landed weights). ORF's cargo activity is dominated by domestic traffic for the U.S. integrated air carriers, FedEx and UPS, which accounted for 85.4 to 99.4 percent of the Airport's total landed weight from FY 2008 to FY 2017 (**Table 3-18**), resulting in the total integrator landing weight increasing by 66.6 percent from FY 2008 to 2017. In 2017, the United States' domestic cargo industry revenue ton miles (RTMs) was 14.6 billion, 120 thousand tons of which were at ORF. The forecasts of RTMs were based on the following assumptions:

- The FAA and TSA security regulations and restrictions on air cargo transportation will remain in place and continue to be enforced.
- The shift from air to ground transportation has occurred.
- Long-term cargo activity will correspond to economic growth.

The integrator flights at ORF connect the local market with the U.S. domestic market. FedEx operates jet flights to its national hub at Memphis International Airport (MEM), with additional flights to Newark Liberty International Airport (EWR). UPS similarly operates jet flights to and from its national hub at Louisville International Airport (SDF), with additional flights to Richmond International Airport (RIC).

According to *Hampton Roads Regional Freight Study, 2017 Update*., in 2012 over 146 million tons of domestic freight was transported by all modes to, from, within, and through the Hampton Roads region, which included ORF, as the primary mode for air cargo for all the Hampton Roads Region and is expected to increase by 53 percent in tonnage to 223 million tons by 2040. As shown in the table below, the Airport was on a steady increase in cargo operations from 2008 through 2012; however, like the economic impacts on ORF commercial passenger and operations, during the CY 2013 and 2014, is when military sequestration had a significant fiscal and economical impact on the local and regional demographic, leading to declines in all economical categories. This had an impact on ORF cargo as well, showing declines from historical highs from 2012 through 2014. As sequestration ended, the local economy has continued to recover and surpass previous historical cargo activity. As such, ORF is experiencing even more record growth in cargo at the Airport, aligning the Hamptons Roads Region with original forecasts of 53 percent growth in all cargo modes by 2040.

In FY 2017, 2,429 cargo operations occurred, 93.3 percent of which were integrator flights (see **Table 3-19**). From FY 2008 to 2017, integrator operations increased by 8.1 percent; however, other all-cargo operations declined by 71.7 over the same period. The decrease can be attributed to recent industry trends, as previously stated, showing a shift from air to other modes (especially truck).

**Table 3-18 – ORF All-Cargo Traffic Weight by Carrier Type**

| Fiscal Year | Integrators | | Other All-Cargo | | Belly Cargo | | Total Cargo Weight | % Total Integrators |
|---|---|---|---|---|---|---|---|---|
| | Freight | % Change | Freight | % Change | Freight/Mail | % Change | | |
| **2008** | 71,793 | - | 11,354 | - | 913 | - | 84,059 | 85.4% |
| **2009** | 94,062 | 31.0% | 2,776 | -75.6% | 676 | -26.0% | 97,513 | 96.5% |
| **2010** | 101,694 | 8.1% | 3,866 | 39.3% | 770 | 13.9% | 106,330 | 95.6% |
| **2011** | 107,606 | 5.8% | 726 | -81.2% | 727 | -5.5% | 109,059 | 98.7% |
| **2012** | 110,206 | 2.4% | 12 | -98.3% | 679 | -6.7% | 110,897 | 99.4% |
| **2013** | 105,546 | -4.2% | 2 | -87.3% | 731 | 7.8% | 106,279 | 99.3% |
| **2014** | 99,125 | -6.1% | 236 | 15033.6% | 729 | -0.3% | 100,090 | 99.0% |
| **2015** | 98,160 | -1.0% | 10 | -95.8% | 727 | -0.2% | 98,897 | 99.3% |
| **2016** | 103,895 | 5.8% | 17 | 71.3% | 603 | -17.1% | 104,515 | 99.4% |
| **2017** | 119,622 | 15.1% | 12 | -32.1% | 703 | 16.5% | 120,337 | 99.4% |
| **AAGR 2008-2017** | **5.2%** | - | **-49.8%** | - | **-2.6%** | - | **3.7%** | - |
| **Growth 2008-2017** | **66.6%** | - | **-99.9%** | - | **-23.0%** | - | **43.2%** | - |

Note: Units are in tons.
Source: Data Miner, US DOT T-100, NAA, CHA, 2018.

**Table 3-19 – ORF All-Cargo Flight Operations by Carrier Type**

| Fiscal Year | Integrators | % Change | Other All-Cargo | Total Cargo Operations | % Total Integrators |
|---|---|---|---|---|---|
| **2008** | 2,096 | - | 576 | 2,672 | 78.4% |
| **2009** | 2,416 | 15.3% | 24 | 2,440 | 99.0% |
| **2010** | 2,590 | 7.2% | 22 | 2,612 | 99.2% |
| **2011** | 2,618 | 1.1% | 4 | 2,622 | 99.8% |
| **2012** | 2,378 | -9.2% | 4 | 2,382 | 99.8% |
| **2013** | 2,522 | 6.1% | 1 | 2,523 | 99.96% |
| **2014** | 2,392 | -5.2% | 6 | 2,398 | 99.7% |
| **2015** | 2,388 | -0.2% | 793 | 3,181 | 75.1% |
| **2016** | 2,338 | -2.1% | 640 | 2,978 | 78.5% |
| **2017** | 2,266 | -3.1% | 163 | 2,429 | 93.3% |
| **AAGR 2008-2017** | **0.8%** | - | **-11.9%** | **-0.9%** | - |
| **Growth 2008-2017** | **8.1%** | - | **-71.7%** | **-9.1%** | - |


Note: Excludes Belly Cargo.
Source: NAA, CHA, 2018.

As shown in **Figure 3-16**, the pattern of growth since 2007 for all cargo has been cyclical, with major declines in traffic in 2009 and 2012. The cyclical nature of cargo operations at ORF correlates with military sequestration. As discussed in **Section 3.2**, Hampton Roads is home to more than 80,000 military personnel, with approximately four percent of national defense spending occurring in this area. Department of Defense (DOD) spending became dissolute with the onset of sequestration in 2013 and remained fairly constant through 2016. In addition to military sequestration, as discussed in the publication, *State of the Region*[12], the Great Recession also contributed to the cyclical nature of cargo in the area surrounding ORF, as the Great

[12] Dragas Center for Economic Analysis and Policy (2018). State of the Region: Hampton Roads 2018 [PDF file]. Retrieved from https://www.ceapodu.com/wp-content/uploads/2018/10/SOR-2018-FINAL090518.pdf

Recession resulted in an immediate decline in cargo tonnage in 2008 and 2009. Many factors contributed to the Great Recession and instability in the market. The ability to create new lines of credit changed, drying up the flow of money and slowing new economic growth over several markets, decreasing the buying and selling of assets in the United States. This, in turn, hurt individuals, financial institutions, and businesses (including cargo companies). The Bureau of Transportation Statistics (BTS) measures movement of freight and models the data using a BTS's Freight Transportation Services Index (TSI). BTS identified that the air freight was impacted more than any other source of freight movement, as air freight saw a 26.5 percent decrease from January 2008 to April 2009[13].

**Figure 3-16 – ORF Cargo vs. Catchment Area Growth**




Source: U.S. DOT, T-100 statistics, Woods & Poole Economics, Inc., NAA, CHA, 2018.

### 3.7.2 Cargo Traffic Forecast

The future growth of cargo activity at ORF will primarily depend on growth in the demand for integrator cargo services provided by FedEx and UPS. Most of the traffic is next-day and second-day delivery traffic, which is affected by local consumer and business demand for both inbound and outbound services, specifically the continued expansion of e-commerce-based traffic. Based on smaller contract and non-integrator cargo traffic carried on non-integrator cargo, operations will likely continue to contribute a minor amount of traffic throughout the forecast period, though is not anticipated to incrementally increase. ORF does not have scheduled international all-cargo service due to a low level of demand within ORF's service area. International cargo is typically received at the integrators hubs and distributed domestically thereafter.

Due to the cyclical nature of cargo and poor correlation with historical socioeconomic factors, the cargo forecasts were based on research and findings by industry experts, such as those found in the FAA Aerospace Forecast (2018-2038), Boeing World Air Cargo Forecast (2016-2017), and

[13] Bureau of Transportation Statistics (2017). Freight by Mode Since the Recession. Retrieved from https://www.bts.gov/newsroom/freight-mode-recession

the Airbus Global Market Forecast (FY 2018-2037), and the Hampton Roads Regional Freight Study, 2017 Update.

***Integrated Carrier Cargo Traffic***

The current and historical traffic levels for the integrated carriers at ORF are representative of the demand and can be used as a basis for forecasting. As previously mentioned, cargo demand in specific regions is predicated upon economic and socioeconomic variables. As such, it was necessary to examine the comparison between socioeconomic factors described in **Section 3.2** (**Socioeconomic Data**) and economic variables (Gross Regional Product (GRP), Manufacturing Earning, Transportation & Warehousing Earnings, etc.) in the Hampton Roads area to identify growth patterns directly associated with cargo imports and exports.

The industry forecasts of RTMs presented in this section were developed by world cargo experts and were based on models that link cargo activity to Gross Domestic Product (GDP). These forecasts of domestic cargo RTMs were developed with real U.S. GDP as the primary driver. The distribution of RTMs between passenger and all-cargo carriers were forecast based on an analysis of historical trends in shares, changes in industry structure, and market assumptions. The U.S. economic recovery is projected to continue, influencing the forecast for domestic cargo in the U.S. In 2018, domestic air cargo RTMs in the U.S. were forecast to grow 1.3 percent and were projected to maintain that growth throughout the forecast period. According to the Boeing World Cargo Forecast, the domestic economy is forecast to grow at an average annual rate of 2.3 percent through 2025 and 2.2 percent over the entire forecast period.

In addition to UPS and FedEx, Amazon has recently begun service within the air cargo industry and, according to industry experts, is expected to become a primary competitor to integrated carriers. Although it is unknown to what extent Prime Air will serve the air cargo industry, it is not unreasonable to expect the new cargo service to arrive at ORF sometime within the forecast period.

Air cargo is also affected by local economic factors, such as local demographics, socioeconomics, commodity and fuel prices, the need or desire for merchandise, and the behaviors of local shippers (public customers). As discussed in **Section 3.2** (**Socioeconomic Data**), data collected from Woods & Poole Economics, Inc. for the years 2008 through 2017 was analyzed prior to examining trends and projecting growth for integrated cargo and other all-cargo passenger traffic. The data analyzed included personal income, population, GRP, manufacturing earnings, and transportation and warehousing earnings. As shown, the population, employment rate, and income in the local economy around ORF is expected to incrementally increase during the forecast period. These increases will drive the need and desire for merchandise, as well as increase the amount of online purchases and needs for quick delivery.

***Other All-Cargo and Passenger Volume***

GDP, as previously mentioned, is the main driver in air cargo activity and is used as the basis for the FAA, Boeing, and Airbus forecasts. The integrator traffic growth and service patterns, as well as the other categories of cargo traffic ("Other All Cargo" and "Passenger"), have been cyclical in the historical 10-year time frame. The other all-cargo and belly cargo traffic show no indication of any future growth in flight or traffic activity outside of typical national growth patterns for mail and belly cargo; therefore, the FY 2018 level and future projections were set at the FY 2017 levels


and incremental growth was based on national trends in aviation and projected throughout the forecast period. The resulting volume levels for each of the traffic forecasts are shown in **Table 3-20**. As shown in **Figure 3-17**, the Boeing forecast produced the highest growth rate while the Airbus forecast had the lowest growth for total cargo operations.

**Table 3-20 – Air Cargo Traffic Forecasts Summary**

| Fiscal Year | Integrators | | | Other All-Cargo | | |
|---|---|---|---|---|---|---|
| | National FAA | National Boeing | National Airbus | National FAA | National Boeing | National Airbus |
| **2017** | 119,622 | 119,622 | 119,622 | 12 | 12 | 12 |
| **2018** | 129,073 | 122,374 | 121,417 | 13 | 12 | 12 |
| **2023** | 141,809 | 137,109 | 130,800 | 14 | 13 | 13 |
| **2028** | 155,803 | 153,019 | 141,187 | 15 | 15 | 14 |
| **2033** | 171,178 | 170,608 | 152,849 | 17 | 17 | 15 |
| **2038** | 188,069 | 190,219 | 165,475 | 18 | 18 | 16 |
| **AAGR 2018-2038** | **1.9%** | **2.2%** | **1.6%** | **1.9%** | **2.2%** | **1.6%** |
| **Growth 2018-2038** | **45.7%** | **55.4%** | **36.3%** | **45.7%** | **55.4%** | **36.3%** |

Note: Units are in tons; Excludes Belly Cargo.
Source: FAA Aerospace Forecast FY 2018-2038, Airbus Global Market Forecast FY 2018-2037, Boeing Commercial Market Outlook 2018-2037, CHA, 2018.

**Figure 3-17 – Comparison of Integrator Forecasts**




Source: FAA Aerospace Forecast FY 2018-2038, Airbus Global Market Forecast FY 2018-2037, Boeing Market Outlook 2017, CHA, 2018.

### 3.7.3 All-Cargo Traffic by Volume Forecast

The recommended forecast is the average of the three forecasts, which falls between the Boeing-based and the Airbus-based forecasts. The average for the integrated carriers and all-cargo carriers is 1.9 percent.

The volume forecast for the integrators and other all-cargo operators assumed that the average load for 2017 will apply for the entire forecast period. **Table 3-21** shows the forecasted totals in this scenario (see **Table 3-18** for historical cargo volume at ORF).

**Table 3-21 – All-Cargo Volume Forecast**

| Fiscal Year | Integrators | Other All-Cargo | Total |
|---|---|---|---|
| **2017** | 119,622 | 12 | 119,634 |
| **2018** | 121,891 | 12 | 121,903 |
| **2023** | 133,897 | 13 | 133,910 |
| **2028** | 147,086 | 14 | 147,101 |
| **2033** | 161,574 | 16 | 161,590 |
| **2038** | 177,489 | 17 | 177,506 |
| **AAGR 2018-2038** | **1.9%** | **1.9%** | **1.9%** |
| **Growth 2018-2038** | **45.6%** | **45.6%** | **45.6%** |

Note: Units are in tons; Excludes Belly Cargo.
Source: NAA, CHA, 2018.

### 3.7.4 Operations Forecast

Similar to the all-cargo volume forecast, the recommended all-cargo operations forecast was based on the average of the FAA, Boeing, and Airbus forecasts. The averages for the integrators and other all-cargo were less than 2 percent.

**Table 3-22** presents the estimated number of operations by ORF's integrated and all-cargo carriers based on annual operations. It is anticipated that any additional capacity required will likely be accommodated by upsizing the aircraft in lieu of adding an additional flight (**Table 3-19** for historical cargo operations at ORF).

**Table 3-22 – All-Cargo Operations Forecast**

| Fiscal Year | Integrators | Other All-Cargo | Total |
|---|---|---|---|
| **2017** | 2,266 | 163 | 2,429 |
| **2018** | 2,309 | 166 | 2,475 |
| **2023** | 2,536 | 182 | 2,719 |
| **2028** | 2,786 | 200 | 2,987 |
| **2033** | 3,061 | 220 | 3,281 |
| **2038** | 3,362 | 242 | 3,604 |
| **AAGR 2018-2038** | **1.9%** | **1.9%** | **1.9%** |
| **Growth 2018-2038** | **45.6%** | **45.6%** | **45.6%** |

Note: Excludes Belly Cargo.
Source: NAA, CHA, 2018.

***Fleet Mix of Operations***

Future fleet mix patterns for integrator cargo should remain relatively unchanged due to the consistency of the fleet mix over the historical time-period. For the integrators, the stability of ORF's role in their networks, the long operating life for freighter aircraft, and the ability to add converted passenger aircraft to replace aging freighter models contributes to this assumption. It is likely that the split between narrow body and wide body jets will be maintained, although it is probable that there will be some shift between wide body jet aircraft types as determined by the likely future composition of cargo carrier fleets.

Air cargo fleet mix directly correlates to growth of air cargo traffic; therefore, as air cargo experiences growth, fleet mix expands to meet the projected needs. The freighter aircraft fleet is categorized as standard-body, medium-widebody, and large-widebody freighters. The projected fleet growth in the United States from 2016 to 2036 is depicted in **Table 3-23**.

**Table 3-23 – Domestic Cargo Freighter Fleet Forecast**

| Year | Widebody | Standard-Body | Total |
|---|---|---|---|
| **2016** | 1,150 | 660 | 1,810 |
| **2036** | 1,780 | 1,250 | 3,030 |

*Standard body freighters: less than 45 tons of carrying capacity. (Boeing 737-800).
*Widebody freighters include Medium widebody and large freighters

The change in domestic freighter fleet mix will consist of 1,260 aircraft being retired and replaced by new freighter deliveries, along with 920 freighter deliveries that will be added to expand the fleet mix, meeting projected traffic growth. As the cargo fleet mix becomes more concentrated with standard-body passenger aircraft, the industry will experience a decline in the medium-widebody and large-widebody aircraft comprising the fleet mix.

According to the FAA Aerospace Forecast, the cargo carrier large jet aircraft fleet is forecast to increase from 855 aircraft in 2017 to 1,178 aircraft in 2038, driven by the growth in freight RTMs. The narrow-body cargo jet fleet is projected to increase by less than one aircraft a year as B757s and B737s are converted from passenger use to cargo service aircraft. The wide-body cargo fleet is forecast to increase by 15 aircraft per year as new B747-800, B777-200, and the new and converted B767-300 aircraft are added, replacing older MD11, A300/310, and B767-200 freighters. According to the Boeing World Air Cargo Forecast, the freighter fleet forecast calls for 3,010 airplanes in service by 2035, an increase of 70 percent compared to the in-service 2015 fleet of 1,770.

The integrated carriers serve the ORF market with a mix of turbo-prop, narrow body, and wide-body jet aircraft. The standard weekday hub flights are supplemented with additional peak capacity supplied by: (1) more flights from the hubs and other airports; and (2) the use of larger aircraft in some cases. The fleet mix of cargo aircraft is shown in **Table 3-24**. Wide-body aircraft are further broken down into three general categories based on average traffic load: standard wide body, medium widebody, and large wide-body. Standard wide-body freighters have less than 45 tons of cargo capacity. The standard wide-body fleet (Boeing 757) is not expected to increase during the forecast period. Medium wide-body freighters (Boeing 767-300F) have 40 to 80 tons of cargo capacity. Large wide-body freighters (Airbus A300) have a minimum of 80 tons of cargo capacity.

In early 2018, UPS announced a purchase agreement with Boeing of 14 additional B747-8 freighters, as well as four (4) B767 freighters. In 2017, FedEx announced a purchase agreement with ATR of 30 ATR 72-600 aircraft, with the option of purchasing up to 20 additional aircraft. FedEx is scheduled to begin receiving the ATRs in 2020 and will continue to receive them over a five-year period until all purchased aircraft are received. In June 2018, FedEx also announced a new order for 12 B767 Freighters (to be delivered between FY 2020 and 2022) and 12 B777 Freighters (to be delivered between FY 2021 and 2025). According to FedEx.com, the freight company is phasing out Boeing 757-200 and McDonnell Douglas MD-11 aircraft and replacing those operations with new Boeing 767 and 777 aircraft respectively. According to Airfleets.net, which tracks individual aircraft by registration and ownership, as of June 2018, FedEx owns and operates over 65 Airbus A300 aircraft, replacing B757-200 operations in smaller markets; however, the average age of these A300 aircraft have over 23 years of operational life. With the FedEx trend of retiring aircraft before 30-years of operational life (see Boeing 757-200, MD-11,

A310), it was assumed that within the next 10 years, FedEx will begin to phase-out A300 aircraft and replace those with newer B767 and B777 aircraft as orders have continued.

As with the traffic forecasts, it was assumed that the fleet mix for other all-cargo operations at ORF will be relatively constant throughout the forecast period; however, due to the increase in B767 orders, it was projected that ORF will see B767 operations within the long-term forecast period. As such, the future critical aircraft for ORF airfield and pavement design is projected to be the B767-3 (D-IV). See **Section 3.11** (**Current and Projected Critical Aircraft**).

Operations of other all-cargo aircraft by non-integrated all-cargo carriers are conducted via Dassault Falcon, McDonnell Douglas DC-9s, and minimal Cessna 208 Caravans. Based on industry trends, the Falcons and DC-9s are expected to be phased out within the short-term time frame in favor of smaller turboprop aircraft (i.e. Cessna 208 Caravan, Metroliner Metro 23, etc.) and older retrofitted narrow-body passenger aircraft (i.e. Boeing 737-400).

**Table 3-24 – Cargo Carrier Fleet Mix at ORF**

| Aircraft Configuration/Group | Aircraft Type |
|---|---|
| **Current** | |
| **Integrators** | |
| Jet, 2-Engine | Airbus A300, Airbus A600, Boeing 757 |
| Turbo-Prop | Cessna 208 Caravan |
| **Other All-Cargo** | |
| Jet, 2-Engine | McDonnell Douglas DC-9-30, McDonnell Douglas MD-83, Dassault Falcon, Learjet |
| **Projected** | |
| **Integrators** | |
| Jet, 2-Engine | Airbus A300, Airbus A600, Boeing 757, Boeing 767 |
| Turbo-Prop | Cessna 208 Caravan |
| **Other All-Cargo** | |
| Jet, 2-Engine | Dassault Falcon, Learjet |

Source: NAA, CHA, 2018.

## 3.8 GENERAL AVIATION AND MILITARY FORECAST

General aviation (GA) includes all segments of the aviation industry except commercial air carriers/regional/commuter service, scheduled cargo, and military operations. General aviation represents the largest percentage of civil aircraft in the U.S. and accounts for most operations handled by towered and non-towered airports. Its activities include flight training, sightseeing, recreational, aerial photography, law enforcement, and medical flights, as well as business, corporate, and personal travel via air taxi charter operations. General aviation aircraft encompass a broad range of types, from single-engine piston aircraft to large corporate jets, as well as helicopters, gliders, and amateur-built aircraft.

Military activity is often included in the based aircraft and operations projections but are not forecast in the same manner as general aviation activity since their number, location, and activity levels are not a function of anticipated market and economic conditions, but are rather a function of military decisions, national security priorities, and budget pressures that cannot be predicted over the course of the forecast period. Typically, military based aircraft and military operations, for forecasting purposes, remain static at baseline year levels throughout the forecast period.

General aviation and military operations are further categorized as either itinerant or local operations. Local operations are those performed by aircraft that remain in the local traffic pattern or within a 20-mile radius of the tower. Local operations are commonly associated with training activity and flight instruction and include touch and go operations. Itinerant operations are arrivals or departures, other than local operations, performed by either based or transient aircraft that do not remain in the airport traffic pattern or within a 20-nautical mile radius. It is important to note that as shown in **Table 3-25**, the 2018 TAF indicated essentially no growth in GA operations at ORF, however shows a considerable spike in based aircraft. For GA operations at FAA facilities, the FAA TAF used trend models to project growth in the future. Based on the historical decline in GA activity, the TAF does not project growth at ORF until trends show incremental growth in consecutive years.

**Table 3-25 – FAA TAF (Condensed to GA Only)**

| Fiscal Year | Itinerant Operations | | | Local Operations | | | | Based Aircraft |
|---|---|---|---|---|---|---|---|---|
| | GA | Military | Total | GA | Military | Total | Total Ops | |
| **2017** | 17,289 | 521 | 17,810 | 1,167 | 92 | 1,259 | 19,069 | 95 |
| **2018** | 15,944 | 590 | 16,534 | 413 | 82 | 495 | 17,029 | 95 |
| **2023** | 14,846 | 590 | 15,436 | 519 | 82 | 601 | 16,037 | 105 |
| **2028** | 14,846 | 590 | 15,436 | 524 | 82 | 606 | 16,042 | 115 |
| **2033** | 14,846 | 590 | 15,436 | 529 | 82 | 611 | 16,047 | 125 |
| **2038** | 14,846 | 590 | 15,436 | 534 | 82 | 616 | 16,052 | 135 |
| **AAGR 2018-2038** | **-0.4%** | **0.0%** | **-0.3%** | **1.3%** | **0.0%** | **1.1%** | **-0.3%** | **1.8%** |
| **Growth 2018-2038** | **-6.9%** | **0.0%** | **-6.6%** | **29.3%** | **0.0%** | **24.4%** | **-5.7%** | **42.1%** |

Source: FAA 2018 TAF, NAA, CHA, 2019.

### 3.8.1 Historical General Aviation Activity

Much like national general aviation activity trends, ORF has seen a decline in GA activity at the Airport over the historical 10-year period. Based on interviews and evaluations of GA activity at ORF with the Airport's FBO, Signature Flight Support, this can be attributed to many different factors with the predominate factor being based aircraft. Like commercial and cargo activity, the economic recession and sequestration in the Hampton Roads Region has had an impact on the decrease in total activity. Based on cost of operations, fuel, and time, many of the smaller recreational based aircraft have seen a dramatic drop in activity over the past few years. According to the FBO, based aircraft activity at the airport has been volatile, with fluctuations in total based aircraft and transition of smaller based aircraft to larger GA airframes. GA operational activity is dominated by the based aircraft at ORF. Local operations from based aircraft, and itinerant traffic from those same based aircraft have created significant impacts, not just to operational activity, but the FBO's ability to grow the number of active based aircraft, and the ability to replace inactive based aircraft that utilize valuable hangar space at the Airport. As shown in **Table 3-26**, itinerant and local traffic have decreased, in totality, at the same rate, with total operations decreases in each category by approximately 10 thousand operations.

In discussions with the FBO, the decrease in total based aircraft since 2008 can be largely attributed to aircraft that were previously stored via tie-downs on the FBO apron and have since sought out covered hangar storage for their aircraft, this is especially true as the year over year numbers from 2017 to 2018 showed a change from 95 based aircraft to 87 in June of 2018. Hangar space at the Airport is in high demand, and the FBO currently has no vacancy; thus, the

FBO is unable to accommodate new based aircraft at the Airport. Additionally, current tenants have expressed the desire to store larger airframes, which the FBO is unable to support, leading to current and potential tenants to seek other airports in the area for hangar aircraft storage. The FBO has expressed that there is a significant demand, i.e., waitlist, for hangar storage for new and current aircraft (aircraft currently stored via tie-downs on the FBO apron), and new hangar facilities would be immediately filled.

**Table 3-26 – ORF's Historical General Aviation Activity**

| Year | Itinerant | Local | Total Operations | Based Aircraft |
|---|---|---|---|---|
| **2008** | 31,713 | 11,553 | 43,266 | 106 |
| **2009** | 25,720 | 7,719 | 33,439 | 103 |
| **2010** | 25,865 | 5,558 | 31,423 | 103 |
| **2011** | 26,390 | 4,274 | 30,664 | 107 |
| **2012** | 24,680 | 3,152 | 27,832 | 95 |
| **2013** | 22,011 | 2,491 | 24,502 | 96 |
| **2014** | 22,756 | 4,091 | 26,847 | 91 |
| **2015** | 21,044 | 1,488 | 22,532 | 94 |
| **2016** | 21,287 | 1,943 | 23,230 | 93 |
| **2017** | 21,207 | 1,157 | 22,364 | 95 |

Note: Excludes Cargo and Military operations.
Source: Signature, NAA, CHA, 2018.

### 3.8.2 GA Based Aircraft Forecasts

***Forecast Methodologies***

Like commercial operations forecasts, the FAA provides multiple methodologies to be used to forecast GA based aircraft. To determine the most reasonable scenario for ORF, it was necessary to compare and eliminate those forecasts that did not support the key factors and variables that comprise the specific direction of the Airport and its market. This section provides the methodology used, as well as methodologies that were analyzed, for the development of the forecasts of GA based aircraft at ORF. The following methodologies, and results therein, are described in the following sections and the results are shown in **Table 3-27**.

- FAA Aerospace Forecast Analysis – A forecasting approach that analyzes data provided in the FAA Aerospace Forecasts (FY 2018-2038), such as annual based aircraft projections by category, and then projects growth for based aircraft at the Airport based on these growth rates. This assumes that the Airport's GA based aircraft will grow at the FAA projected national rates while maintaining their respective share of fleet throughout the forecast period. As shown in **Table 3-27**, the growth was conservative compared to the TAF; however, detailed evaluation of the Aerospace methodology (See **Appendix D**), identified the single- and multi-engine market at ORF decreasing (46 single-engine and 10 multi-engine aircraft in 2017 to 37 and 9, respectively, by 2038), while the Jet and Turbo-Prop market have much more significant growth (12 additional Jet and 4 additional Turbo-Prop aircraft by 2038). See **Appendix D** for a breakdown by aircraft type.

- Market Share Analysis (Static)[14] – Similar to enplanements, a Market Share forecast is a "top-down" method where projected growth rates of larger aggregates (e.g., the nation) are used to derive forecasts for smaller areas (e.g., airports). Future ORF based aircraft were estimated by multiplying the future share trend and the Federal Aviation Administration's (FAA) Terminal Area Forecast (TAF) for National, Eastern Region, and State based aircraft numbers. **Table 3-27** and **Appendix D** (same table and Appendix as above) depict the results of this evaluation. As shown, between the State, Eastern Region, and National projections, ORF ranges from 87 to 102 based aircraft, resulting in relatively conservative growths within the ORF market for based aircraft.
- TAF Based Growth Forecast Analysis – Takes the FAA's projected based aircraft annual growth for FY 2018-2038 and applies that assumption to actual airport-reported data[15]. In other words, the TAF growth is applied to an actual FY 2017 based aircraft count and projected throughout the forecast period. For example, the 2018 TAF had an estimated 2017 based aircraft count of 95 which was correct at year end 2017; however, according to airport records, the actual number of based aircraft was 87 as of June, 2018. The year to year TAF growth rate was then applied to the actual 87 based aircraft and projected from FY 2018 through FY 2038. The result of this methodology was 126 based aircraft in 2038, approximately 6.8 percent below the 135 reported in the TAF. **Table 3-27** depicts the results of this evaluation. This scenario was believed to be the most reasonable scenario for projecting-based aircraft at ORF and was chosen to serve as the recommended forecast for based aircraft. See **Appendix D** for the full scenario results which includes historical market share data.

**Table 3-27 – Based Aircraft Forecast Comparisons**

| Fiscal Year | FAA TAF | TAF Based Growth | FAA Aerospace | Market Shares | | |
|---|---|---|---|---|---|---|
| | | | | Static National | Static State | Static Regional |
| **2017** | 95 | 87 | 87 | 87 | 87 | 87 |
| **2018** | 96 | 89 | 87 | 88 | 87 | 88 |
| **2023** | 106 | 97 | 88 | 91 | 91 | 92 |
| **2028** | 116 | 106 | 89 | 95 | 93 | 95 |
| **2033** | 126 | 115 | 91 | 99 | 96 | 99 |
| **2038** | 136 | 126 | 95 | 103 | 99 | 102 |
| **AAGR 2018-2038** | **1.8%** | **1.8%** | **0.4%** | **0.8%** | **0.6%** | **0.8%** |
| **Growth 2018-2038** | **42.1%** | **42.1%** | **8.8%** | **17.3%** | **12.8%** | **16.6%** |

Source: FAA Aerospace Forecast FY 2018-2038, FAA 2018 TAF, Signature, NAA, CHA, 2019.

### 3.8.3 GA Operations Forecast

According to the FAA, the "Air Taxi & Commuter" category of FAA reported operations data includes both scheduled Air Carrier operations with 60-seats or less (i.e., this includes all 50-seat regional jet operations) and Part 135 business and charter operations. As such, the Air Taxi & Commuter category of the 2018 FAA TAF included both scheduled airlines and non-airline

[14] ORF's GA Based Aircraft Percent Market Shares in 2017: National (0.05), Eastern Region (0.60), and State (3.40).

[15] Note: ORF-Reported numbers and data contains the most recent information, which has been updated since the development of the FAA 2018 TAF.

passenger operations. The following describes the difference between Air Carrier and Air Taxi & Commuter operations, as defined by the FAA.

- Air Carrier – Operations with aircraft designed to have a seating capacity of more than 60 seats or a maximum payload capacity of more than 18,000 pounds carrying passengers or cargo for hire or compensation. This includes US and foreign flagged carriers.
- Air Taxi & Commuter – Operations with aircraft designed to have a maximum seating capacity of 60 seats or less or a maximum payload capacity of 18,000 pounds or less carrying passengers or cargo for hire or compensation.

To accurately gauge commercial airline passenger carrying operations in comparison to GA and Part 135 operations when examining air taxi & commuter operations data, it was necessary to split Air Taxi & Commuter operations from the commercial airline operations to account for the scheduled air carrier operations using regional jet aircraft less than 60-seats.

The total scheduled commercial air carrier operations at ORF (which were derived from T-100 data) were calculated and applied the split to account for operations categorized under Air Taxi & Commuter operations and reclassifying those operations as commercial airline operations. By removing the commercial airline operations from the Air Taxi & Commuter operations (which contribute to the steep decline in operations due to 50-seat aircraft phasing out) and categorizing operations at the Airport by Air Carrier and GA, both categories then projected growth throughout the forecast period.

**Table 3-28** shows a comparison between ORF-reported operations with the previously described split, as well as the FAA-reported operations numbers for 2017. Based on schedule data and commercial airline operations counts, these operations were performed by commercial airlines utilizing 50-seat or less regional jet/turbo-prop aircraft; therefore, they were counted in the commercial airlines category. It is important to note that all cargo operations (schedule, and non-scheduled) were included within the GA Itinerant operations counts.

**Table 3-28 – FAA TAF Vs. ORF- Reported Operations (With Split)**

| Source | Fiscal Year | Itinerant Operations | | | | | Local Operations | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Commercial Airline | Air Taxi | GA | Military | Total Itinerant | GA | Military | Total Local | Total Operations |
| **FAA** | **2017** | 29,067 | 24,649 | 17,289 | 521 | 71,526 | 1,167 | 92 | 1,259 | 72,785 |
| **ORF (adjusted)** | **2017** | 47,195 | - | 23,636 | 508 | 71,339 | 1,157 | 92 | 1,249 | 72,588 |

Note: Cargo operations are included in GA operations.
Note: ORF-Reported numbers and data contains the most recent information available at the time the evaluation was conducted, which has been updated since the development of the FAA 2018 TAF.
Source: FAA 2018 TAF, Signature, NAA, CHA 2019.

Adjustment calculation example: (All numbers provided by NAA and shown in **Appendix E**)

- Air Carrier + Air Taxi = Total Air Carrier and Air Taxi Operations
  28,992 + 24,590 = **53,582**
- Total Air Carrier and Air Taxi Operations – Actual Air Carrier Operations = Adjusted Air Taxi
  53,582 – 47,195 = **6,387**
- Adjusted Air Taxi + Airport Reported Itinerant GA = Actual Itinerant GA
  6,387 + 17,249 = **23,636**
- Actual Itinerant GA + Local GA = Actual Air Taxi and GA
  23,636 + 1,157 **= 24,793 (Combined GA Itinerant and Local Operations)**

***Forecast Methodologies***

Like commercial operations forecasts and GA based aircraft forecasts, several methodologies exist that could be used to forecast GA operations. To determine the most plausible and reasonable scenario for ORF, it was necessary to compare and eliminate those forecasts that did not support the key factors and variables that comprise the specific operational direction of the Airport. This section provides the methodology used, as well as methodologies that were analyzed, for the development of the forecasts of general aviation operations at ORF. It is important to note that all cargo operations were extracted prior to performing the methodologies listed below.

- Historical Trend Analysis – Historical trend is a time trend analysis that uses the airport's historical activity as a metric to provide future growth projections. These historical trends are typically developed as 5- and 10-year historical trends. These historical growth rates are then extrapolated over the forecast horizon (20 years). ORF experienced a sharp decline in GA activity, from 43,266 total itinerant and local ops in 2008 to 22,364 total ops in FY 2017. The Historical Growth Scenario was considered unreliable and was not used for this forecasting effort.
- TAF-Based Growth Analysis – A straightforward forecasting methodology which assumes the total number of annual operations is representative of the number or aircraft based at ORF. At ORF, itinerant traffic makes up approximately 94.8 percent of all GA activity at the Airport. These operations are typically performed by aircraft based at ORF flying charter and corporate aviation operations or flight training (where the flights leave the local airport airspace and return, i.e., cross country flight training). When projecting operations using the based aircraft growth for ORF, it was assumed that GA operations [Air Taxi & GA – (Local and Itinerant)] will grow commensurate with based aircraft growth (AAGR of 1.8 percent; 42.1 overall growth). See **Table 3-29** and **Appendix D** (includes a breakdown between itinerant and local GA operations.) The results of this scenario serve as the recommended GA operations forecast for ORF.

- Market Share Analysis (Static)[16] – Compares local GA activity levels with aggregate level trends. This methodology assumes that the activity of any one airport is regular and predictable in accordance with the average of airports within the market. An evaluation of local, regional, State, and national FAA GA projections was performed and is detailed in **Table 3-29**. (See **Appendix D** for the full results of the methodology).

**Table 3-29 – General Aviation Operations Forecast Comparisons**

| Fiscal Year | TAF Based Growth | Market Shares | | |
|---|---|---|---|---|
| | | Static National | Static State | Static Regional |
| **2017** | 22,364 | 22,364 | 22,364 | 22,364 |
| **2018** | 22,760 | 22,598 | 22,428 | 22,192 |
| **2023** | 24,850 | 23,031 | 22,692 | 22,385 |
| **2028** | 27,132 | 23,441 | 22,955 | 22,827 |
| **2033** | 29,624 | 23,882 | 23,225 | 23,289 |
| **2038** | 32,344 | 24,358 | 23,502 | 23,782 |
| **AAGR 2018-2038** | **1.8%** | **0.4%** | **0.2%** | **0.3%** |
| **Growth 2018-2038** | **42.1%** | **7.8%** | **4.8%** | **7.2%** |

Note: Excludes Cargo and Military Operations.
*Scenario results based on the recommended based aircraft forecast
Source: FAA 2018 TAF, Signature, NAA, CHA 2019.

### 3.8.4 General Aviation Recommended Forecast Summary

The following table presents a summary of the recommended GA activity forecasts for based aircraft and operations, along with military activity as detailed in the previous sections. Although conservative, based on the transient nature of the corporate growth market at ORF, the OPBA Scenario was believed to be the most reasonable scenario for the ORF forecast based on the nature of GA itinerant operations of aircraft based at the Airport's FBO.

The recommended forecasts are the preferred projections on which future planning for the Airport are based. **Table 3-30** presents the complete summary of the preferred GA forecast for based aircraft and operations by type. The full recommended GA Forecast can be found in **Appendix D**.

[16] ORF's GA Operations Percent Market Shares in 2017: National (Itinerant 0.1) (Local 0.003), Regional (Itinerant 0.7) (Local 0.03), State (Itinerant 4.1) (Local 0.2).

**Table 3-30 – Recommended GA Forecast**

| Fiscal Year | Based Aircraft | Operations | | | | Total GA Operations |
|---|---|---|---|---|---|---|
| | | Itinerant | Local | Total Civil | Military | |
| **2017** | 87 | 21,207 | 1,157 | 22,364 | 600 | 22,964 |
| **2018** | 89 | 21,583 | 1,178 | 22,760 | 600 | 23,360 |
| **2023** | 97 | 23,565 | 1,286 | 24,850 | 600 | 25,450 |
| **2028** | 106 | 25,729 | 1,404 | 27,132 | 600 | 27,732 |
| **2033** | 115 | 28,091 | 1,533 | 29,624 | 600 | 30,224 |
| **2038** | 126 | 30,670 | 1,673 | 32,344 | 600 | 32,944 |
| **AAGR 2018-2038** | **1.8%** | **1.8%** | **1.8%** | **1.8%** | **0.0%** | **1.7%** |
| **Growth 2018-2038** | **42.1%** | **42.1%** | **42.1%** | **42.1%** | **0.0%** | **41.0%** |

Note: Excludes Cargo Operations.
Source: Signature, CHA, 2018.

## 3.9 RECOMMENDED FORECAST SUMMARY

To ensure that factors specific to the ORF market were accurately integrated into this forecast scenario, as stated in **Section 3.5.1**, the Air Service Scenario was developed based upon the following factors:

- Steady enplanement and airport growth based on strong socioeconomic variables (see **Section 3.2**)
- New service announcements made within the past 12-months[17] (**Section 3.3**)
- A shift from smaller 50-seat regional jets to larger 63-76 seat regional jets and 124-160 seat narrow-body aircraft

The following tables present a summary of the preferred aviation activity forecasts for air carrier activity (operations and enplanements), GA activity (based aircraft and operations), and military activity as detailed in the previous sections. Additionally, direct comparisons to the FAA's TAF for ORF are provided for evaluation purposes. The recommended forecasts are the preferred projections on which future planning for the Airport was based and are the result of the analysis provided in the previous section and is intended to be for summary purposes. **Table 3-31** presents the complete summary of the preferred forecast for based aircraft, enplanements, and operations by type.

**Table 3-32** details the recommended forecast of enplanements and total airport operations (all activity types) in comparison to the FAA 2018 TAF forecast. At the end of the planning period, the recommended forecast predicts a level of enplanements 7.9 percent above the ORF TAF, and total Airport operations 7.6 percent above what was reported in the TAF. Per FAA requirements, forecasts should be within 10 percent of the TAF in the first 5 years and 15 percent in 10 years, as set forth by the FAA in AC 150/5070-6B*, Airport Master Plans,* for approval of Master Plan forecasts. Although the Airport operations forecast is outside of the FAA's recommended range,

[17] The past 12-month period is representative of the 12 months prior to the development of the forecasts herein.

the growth is considered acceptable because ORF is not expected to experience decreases in operations as it had historically.

**Table 3-31 – Recommended Forecast Summary**

| Fiscal Year | Based Aircraft | Enplanements | Total Operations | | | | |
|---|---|---|---|---|---|---|---|
| | | | Air Carrier | GA | Cargo | Military | Total |
| **2017** | 87 | 1,672,024 | 47,195 | 22,364 | 2,429 | 600 | 72,588 |
| **2018** | 89 | 1,857,487 | 48,986 | 22,760 | 2,475 | 600 | 74,821 |
| **2019** | 90 | 2,003,360 | 51,752 | 23,164 | 2,522 | 600 | 78,038 |
| **2020** | 92 | 2,038,176 | 51,944 | 23,574 | 2,570 | 600 | 78,688 |
| **2021** | 93 | 2,072,287 | 52,135 | 23,992 | 2,619 | 600 | 79,346 |
| **2022** | 95 | 2,104,678 | 52,275 | 24,418 | 2,668 | 600 | 79,961 |
| **2023** | 97 | 2,115,424 | 51,889 | 24,850 | 2,719 | 600 | 80,058 |
| **2024** | 98 | 2,168,171 | 52,577 | 25,291 | 2,770 | 600 | 81,239 |
| **2025** | 100 | 2,220,800 | 53,249 | 25,739 | 2,823 | 600 | 82,412 |
| **2026** | 102 | 2,273,199 | 53,898 | 26,195 | 2,877 | 600 | 83,570 |
| **2027** | 104 | 2,325,316 | 54,551 | 26,660 | 2,931 | 600 | 84,742 |
| **2028** | 106 | 2,376,990 | 55,177 | 27,132 | 2,987 | 600 | 85,896 |
| **2029** | 107 | 2,428,333 | 55,704 | 27,613 | 3,043 | 600 | 86,960 |
| **2030** | 109 | 2,479,279 | 56,206 | 28,103 | 3,101 | 600 | 88,010 |
| **2031** | 111 | 2,528,677 | 56,673 | 28,601 | 3,160 | 600 | 89,033 |
| **2032** | 113 | 2,576,438 | 57,090 | 29,108 | 3,220 | 600 | 90,018 |
| **2033** | 115 | 2,622,848 | 57,488 | 29,624 | 3,281 | 600 | 90,992 |
| **2034** | 117 | 2,667,816 | 58,327 | 30,149 | 3,343 | 600 | 92,418 |
| **2035** | 119 | 2,711,393 | 59,145 | 30,683 | 3,406 | 600 | 93,835 |
| **2036** | 121 | 2,753,696 | 59,933 | 31,227 | 3,471 | 600 | 95,231 |
| **2037** | 124 | 2,794,755 | 60,696 | 31,780 | 3,537 | 600 | 96,613 |
| **2038** | 126 | 2,834,623 | 61,430 | 32,344 | 3,604 | 600 | 97,978 |
| **AAGR 2018-2038** | **1.8%** | **2.1%** | **1.1%** | **1.8%** | **1.9%** | **0.0%** | **1.4%** |
| **Growth 2018-2038** | **42.1%** | **52.6%** | **25.4%** | **42.1%** | **45.6%** | **0.0%** | **30.9%** |

Source: FAA Aerospace Forecast FY 2018-2038, FAA 2018 TAF, NAA, CHA, 2019.

**Table 3-32 – Recommended Forecast vs. FAA TAF**

| Fiscal Year | Enplanements | | | Operations | | |
|---|---|---|---|---|---|---|
| | ORF TAF | Recommended Forecast | Recommended Forecast vs. TAF | ORF TAF | Recommended Forecast | Recommended Forecast vs. TAF |
| **2017** | 1,652,323 | 1,672,024 | 1.2% | 72,785 | 72,588 | -0.3% |
| **2018** | 1,815,241 | 1,857,487 | 2.3% | 72,073 | 74,821 | 3.8% |
| **2023** | 2,147,644 | 2,115,424 | -1.5% | 77,872 | 80,058 | 2.8% |
| **2028** | 2,294,704 | 2,376,990 | 3.6% | 81,749 | 85,896 | 5.1% |
| **2033** | 2,458,050 | 2,622,848 | 6.7% | 86,330 | 90,992 | 5.4% |
| **2038** | 2,627,295 | 2,834,623 | 7.9% | 91,083 | 97,978 | 7.6% |
| **AAGR 2018-2038** | **1.9%** | **2.1%** | - | **1.2%** | **1.4%** | - |
| **Growth 2018-2038** | **44.7%** | **52.6%** | - | **26.4%** | **30.9%** | - |

Source: FAA Aerospace Forecast FY 2018-2038, FAA 2018 TAF, NAA, CHA, 2019.

## 3.10 PEAK ACTIVITY FORECAST

Commercial service airports experience peaks in enplanements, commercial air carrier operations, and total airport operations that drive demand for various areas of airport infrastructure. To properly plan, size, and design passenger terminal facilities, an understanding of peak month-average day (PMAD) and peak hour enplanement demand is necessary. The peak month, PMAD, and peak hour forecasts are key elements in defining the future facility requirements needed to accommodate above average levels of utilization (i.e., peak activity).

The peak month is the calendar month of the year when the highest level of enplanements and commercial aircraft operations typically occur. Peak month-average day is simply the total commercial operations, or total enplanements, divided by the number of days in the peak month. To provide the necessary metrics for the demand/capacity analysis, PMAD is forecast for the following:

- Enplanements, Deplanements, and Total Passengers
- Commercial Air Carrier Aircraft Operations
- Total Aircraft Operations

Each element at an airport must be presented separately:

- Peak enplanements, deplanements, and total passengers - direct impact on terminal (e.g., ticketing and baggage claim) and landside (e.g., access roads and parking) facilities
- Peak commercial air carrier operations- define the demand for airside facilities (gates and ramp)
- Peak hour airport operations- determine runway capacity and airfield needs

Terminal facilities are generally designed to accommodate enplanements on the average day during the peak month, rather than the absolute peak level of activity.

### 3.10.1 Peak Enplanements

***Historical Peak Enplanements***

A review of historical enplanements at ORF was performed to identify the peak month for commercial activity.

**Table 3-33 – Historical Peak Enplanements**

| Fiscal Year | Annual Enplanements | Peak Month | Peak Month Enplanements | PMAD Enplanements | Peak Hour | Peak Hour Enplanements |
|---|---|---|---|---|---|---|
| **2008** | 1,841,881 | July | 179,500 | 5,998 | 6:00 am - 7:30 am | 1,524 |
| **2009** | 1,740,349 | July | 173,362 | 5,888 | 5:45 am - 7:15 am | 1,456 |
| **2010** | 1,697,663 | July | 172,674 | 5,933 | 5:45 am - 7:15 am | 1,487 |
| **2011** | 1,658,696 | July | 168,082 | 5,629 | 5:50 am -7:20 am | 1,096 |
| **2012** | 1,669,997 | August | 169,004 | 5,842 | 5:35 am -7:05 am | 1,160 |
| **2013** | 1,615,283 | July | 155,669 | 5,129 | 5:45 am - 7:15 am | 1,000 |
| **2014** | 1,534,316 | June | 143,278 | 5,187 | 5:45 am - 7:15 am | 1,091 |
| **2015** | 1,499,400 | August | 148,257 | 5,019 | 5:40 am -7:10 am | 1,277 |
| **2016** | 1,603,159 | July | 157,018 | 5,385 | 5:35 am -7:05 am | 1,140 |
| **2017** | 1,672,024 | July | 164,495 | 5,306 | 6:00 am - 7:30 am | 1,215 |

Note: Airline schedules for FY 2008- FY 2017 can be found in **Appendix I**.
Source: Data Miner, US DOT T-100, NAA, CHA, 2018.

When developing the forecast, July was determined to be the peak month in 2017.

***Peak Month – Average Day Enplanements***

During the month of July in FY 2017, ORF experienced approximately 164,495 enplanements, or approximately 9.8 percent of the total annual passengers. To calculate the PMAD, the peak month enplanements (164,495) were divided by the number of days in the peak month of July (31) to define the PMAD.

The PMAD enplanements make up approximately 3.2 percent of the enplanements in the peak month.

***Peak Hour Enplanements***

Peak hour passenger enplanements in July were calculated by using the following methodology:

- Analyze ORF commercial air carrier schedule data to determine the average air carrier departures.
- Apply average load factors per route destination to peak hour enplanements, then divide peak hour enplanements by the PMAD enplanements to determine the peak hour percentage of enplanements.

It was determined that the peak hour for enplanements was between 6:00 am and 7:30 am, with approximately 22.9 percent of enplanements occurring during this time frame. To generate a forecast of peak hour enplanements, the percentage was applied to the PMAD enplanements.

**Table 3-34 – Peak Month Average Day Enplanements**

| Fiscal Year | Enplanements | Peak Month Percent | Peak Month Enplanements | PMAD Percent | PMAD |
|---|---|---|---|---|---|
| **2017** | 1,672,024 | 9.8% | 164,495 | 3.2% | 5,306 |
| **2018** | 1,857,487 | 9.8% | 183,359 | 3.2% | 5,915 |
| **2023** | 2,115,424 | 9.8% | 208,117 | 3.2% | 6,713 |
| **2028** | 2,376,990 | 9.8% | 233,850 | 3.2% | 7,544 |
| **2033** | 2,622,848 | 9.8% | 258,038 | 3.2% | 8,324 |
| **2038** | 2,834,623 | 9.8% | 278,872 | 3.2% | 8,996 |

Source: NAA, CHA, 2018.

**Table 3-35 – Peak Hour Enplanements**

| Fiscal Year | PMAD | Peak Hour Percent | Peak Hour Enplanements |
|---|---|---|---|
| **2017** | 5,306 | 22.9% | 1,215 |
| **2018** | 5,915 | 22.9% | 1,354 |
| **2023** | 6,713 | 22.9% | 1,537 |
| **2028** | 7,544 | 22.9% | 1,727 |
| **2033** | 8,324 | 22.9% | 1,906 |
| **2038** | 8,996 | 22.9% | 2,060 |

Source: NAA, CHA, 2018.

### 3.10.2 Peak Deplanements

Although not as impactful as peak hour enplanements, it was still necessary to evaluate and identify the peak hour passengers for deplanements. The purpose of determining the peak hour deplanement projections was the future impact deplanements have on passengers exiting the airport, passenger circulation, baggage claim demand, and parking facility needs.

Using the same methodology and assumptions provided in the peak hour evaluation for enplanements, the peak deplanements were analyzed and the peak hour was determined to be between 4:30 pm and 6:00 pm (16:30 and 18:00); however, due to runway construction being conducted from approximately midnight to 5:00 am, the short-term peak operating hour is between 10:30 pm and midnight (22:30 and 00:00). For the purpose of this forecast, the peak hour between 4:30 pm and 6:00 pm (16:30 and 18:00) was used. This resulted in approximately 17.1 percent of deplanements occurring during this time frame. To generate a forecast of peak hour deplanements, the percentage was applied to the PMAD enplanements.

**Table 3-36 – Peak Hour Deplanements**

| Fiscal Year | PMAD | Peak Hour Percent | Peak Hour Deplanements |
|---|---|---|---|
| **2017** | 5,371 | 17.1% | 921 |
| **2018** | 5,964 | 17.1% | 1,022 |
| **2023** | 6,769 | 17.1% | 1,160 |
| **2028** | 7,606 | 17.1% | 1,304 |
| **2033** | 8,393 | 17.1% | 1,438 |
| **2038** | 9,070 | 17.1% | 1,555 |

Source: NAA, CHA, 2018.

### 3.10.3 Peak Passengers

***Peak Month – Average Day Passengers***

During the month of July in FY 2017, ORF had approximately 330,982 passengers, or approximately 9.9 percent of the total annual passengers. To calculate the PMAD, the peak month passengers (330,982) were divided by the number of days in the peak month of July (31) to define the PMAD.

The PMAD passengers make up approximately 3.2 percent of the enplanements in the peak month.

***Peak Hour Passengers***

Total peak hour passengers in July was calculated by using a methodology similar to as when calculating peak passenger enplanements, except that data for enplanements and deplanements

were compiled. It was determined that the peak hour for passengers was between 4:45 pm and 6:15 pm (16:45 and 18:15), with approximately 15.2 percent of total passengers occurring during this time frame. To generate a forecast of peak hour passengers, the percentage was applied to the PMAD passengers.

**Table 3-37 – Peak Month Average Day Passengers**

| Fiscal Year | Passengers | Peak Month Percent | Peak Month Passengers | PMAD Percent | PMAD |
|---|---|---|---|---|---|
| **2017** | 3,350,421 | 9.9% | 330,982 | 3.2% | 10,677 |
| **2018** | 3,727,532 | 9.9% | 368,236 | 3.2% | 11,879 |
| **2023** | 4,230,848 | 9.9% | 417,958 | 3.2% | 13,483 |
| **2028** | 4,753,980 | 9.9% | 469,637 | 3.2% | 15,150 |
| **2033** | 5,245,696 | 9.9% | 518,213 | 3.2% | 16,717 |
| **2038** | 5,669,246 | 9.9% | 560,054 | 3.2% | 18,066 |

Source: NAA, CHA, 2018.

**Table 3-38 – Peak Hour Passengers**

| Fiscal Year | PMAD | Peak Hour Percent | Peak Hour Passengers |
|---|---|---|---|
| **2017** | 10,677 | 15.2% | 1,625 |
| **2018** | 11,879 | 15.2% | 1,808 |
| **2023** | 13,483 | 15.2% | 2,052 |
| **2028** | 15,150 | 15.2% | 2,306 |
| **2033** | 16,717 | 15.2% | 2,544 |
| **2038** | 18,066 | 15.2% | 2,750 |

Source: NAA, CHA, 2018.

### 3.10.4 Peak Operations

***Peak Month – Average Day Commercial Operations***

The PMAD for commercial air carrier operations was calculated in the same manner as PMAD for enplanements. For the purposes of this forecast, the month of July was used for commercial operations at ORF, yielding approximately 4,245 commercial operations, or 9.0 percent of the total annual operations. To compute PMAD, the peak month operations (4,245) were divided by the number of days in the peak month (31) to represent the PMAD for the forecast period.

The PMAD operations make up approximately 3.2 percent of operations in the peak month.

***Peak Hour Commercial Operations***

As discussed previously, it was assumed the month of July averaged the greatest number of total Airport and commercial carrier operations in FY 2017. Before calculating the peak hour for commercial operations, it was first necessary to analyze the Authority-provided commercial carrier schedule data for arrivals and departures during the peak month of July. This analysis determined, based on a 90-minute rolling basis, the peak hour for operations was 4:45 pm to 6:15 pm (16:45 to 18:15), with 20 operations, or 14.6 percent of the PMAD commercial operations. This percentage was then applied to the PMAD operations, as depicted in **Table 3-40**.

**Table 3-39 – Peak Month Average Day Commercial Operations**

| Fiscal Year | Annual Commercial Operations | Peak Month Percent | Peak Month Operations | PMAD Percent | PMAD |
|---|---|---|---|---|---|
| **2017** | 47,195 | 9.0% | 4,245 | 3.2% | 137 |
| **2018** | 48,986 | 9.0% | 4,406 | 3.2% | 142 |
| **2023** | 51,889 | 9.0% | 4,667 | 3.2% | 151 |
| **2028** | 55,177 | 9.0% | 4,963 | 3.2% | 160 |
| **2033** | 57,488 | 9.0% | 5,171 | 3.2% | 167 |
| **2038** | 61,430 | 9.0% | 5,525 | 3.2% | 178 |

Source: NAA, CHA, 2018.

**Table 3-40 – Peak Hour Operations**

| Fiscal Year | PMAD | Peak Hour Percent | Peak Hour Operations |
|---|---|---|---|
| **2017** | 137 | 14.6% | 20 |
| **2018** | 142 | 14.6% | 21 |
| **2023** | 151 | 14.6% | 22 |
| **2028** | 160 | 14.6% | 23 |
| **2033** | 167 | 14.6% | 24 |
| **2038** | 178 | 14.6% | 26 |

Source: NAA, CHA, 2018.

***Peak Month – Average Day All Airport Operations***

The PMAD for total annual airport operations was calculated in the same manner as PMAD for commercial air carrier. For the purposes of this forecast, the month of July was used for operations at ORF, yielding approximately 6,272 operations, or 8.6 percent of the total annual operations. To compute PMAD, the peak month operations (6,272) were divided by the number of days in the peak month (31) to represent the PMAD for the forecast period.

The PMAD operations make up approximately 3.2 percent of operations in the peak month.

**Table 3-41 – Peak Month Average Day Total Airport Operations**

| Fiscal Year | Annual Airport Operations | Peak Month Percent | Peak Month Operations | PMAD Percent | PMAD |
|---|---|---|---|---|---|
| **2017** | 72,588 | 11.9% | 8,658 | 3.2% | 279 |
| **2018** | 74,821 | 11.9% | 8,924 | 3.2% | 288 |
| **2023** | 80,058 | 11.9% | 9,549 | 3.2% | 308 |
| **2028** | 85,896 | 11.9% | 10,245 | 3.2% | 330 |
| **2033** | 90,992 | 11.9% | 10,853 | 3.2% | 350 |
| **2038** | 97,978 | 11.9% | 11,686 | 3.2% | 377 |

Note: Total Airport Operations accounts for Commercial, GA, Military, and Cargo operations.
Source: Signature, NAA, CHA, 2018.

### 3.10.5 ORF Peak Activity Forecast Summary

**Table 3-42** provides a summary of PMAD enplanements, passengers, commercial operations, and annual airport operations, as well as a summary of peak hour enplanements, total passengers, and commercial operations.

**Table 3-42 – Projected Activity Forecast Summary**

| Fiscal Year | Enplanements | | Total Passengers | | Commercial Operations | | Annual Airport Operations |
|---|---|---|---|---|---|---|---|
| | PMAD | Peak Hour | PMAD | Peak Hour | PMAD | Peak Hour | PMAD |
| **2018** | 5,915 | 1,354 | 11,879 | 1,808 | 142 | 21 | 288 |
| **2023** | 6,713 | 1,537 | 13,483 | 2,052 | 151 | 22 | 308 |
| **2028** | 7,544 | 1,727 | 15,150 | 2,306 | 160 | 23 | 330 |
| **2033** | 8,324 | 1,906 | 16,717 | 2,544 | 167 | 24 | 350 |
| **2038** | 8,996 | 2,060 | 18,066 | 2,750 | 178 | 26 | 377 |

Source: NAA, CHA 2018.

## 3.11 CURRENT AND PROJECTED CRITICAL AIRCRAFT

Evaluating the Airport's current fleet mix and determining the current design aircraft, as well as the projected design aircraft, were important aspects of the Master Plan Study. The design aircraft (commonly referred to as the "critical aircraft") determination is a key consideration in FAA decision making on project justification. The "design aircraft" or "design aircraft family" represent the most demanding aircraft or grouping of aircraft with similar characteristics (relative to AAC, ADG, TDG)[18], that are currently using or are anticipated to use an airport on a regular[19] basis.

Upon review of the FAA's ETMSC data, OAG data, T100 and forecast fleet mix assumptions described in this chapter, the design aircraft family identified for ORF is presented in **Table 3-43**. This grouping represents the typical commercial aircraft and cargo aircraft anticipated to operate at ORF over the planning horizon. These aircraft generally have higher AAC, ADG, and TDG classifications than the other regularly scheduled commercial aircraft. While the Study was not limited to planning for the design aircraft, they were still considered when planning airfield and landside facilities as they may require specific facility design accommodations within their designated areas of operation.

***Runway 5/23***

The Airport's previous 2008 Airport Layout Plan (ALP) identified the Boeing 757-200 (ARC C-IV, TDG 4) as the critical aircraft for airfield and pavement design. As shown in **Table 3-43**, the Boeing 737-900 (ARC D-III) and the Airbus A-300 (ARC C-IV, TDG 5) are the current critical aircraft, resulting in an ARC of D-IV; however, due to increasing airframe size resulting from fleet mix transitions and the projected increase of B767-300ER operations from FedEx, the future critical aircraft for airfield and pavement design is the B767-300ER (ARC D-IV, TDG 5). Based on the previous ALP, the Airport Reference Code (ARC) at ORF was C-IV; however, based on current operations (i.e., operations from the B737-900 and A-300), the existing and future ARC remain D-IV. Although the ARC is expected to increase from the previous ALP, the TDG, which was 5, is expected to remain the same throughout the forecast period.

[18] AAC (Aircraft Approach Category), ADG (Airplane Design Group), TDG (Taxiway Design Group).

[19] According to FAA AC 150/5000-17, *Critical Aircraft and Regular Use Determination*, the terminology of "regular use" is defined as 500 annual operations, including itinerant and local operations but excluding touch-and-go operations. An operation is either a takeoff or landing.

## Table 3-43 – Fleet Mix and Design Aircraft Families (Runway 5/23)

| Aircraft | | 2017 | 2038 | AAC | ADG | TDG | AAC | ADG | | TDG | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Approach Speed (knots) | Wingspan (ft.) | Tail Height (ft.) | CMG (ft.) | MGW (ft.) |
| **B737-7** | | 5,643 | 8,998 | C | III | 3 | 130 | 117.42 | 41.58 | 46.58 | 22.92 |
| **CRJ-700** | | 2,284 | 8,358 | C | II | 2 | 135 | 76.27 | 24.83 | 49.25 | 16.39 |
| **ERJ-175** | | 2,564 | 8,142 | C | III | 3 | 124 | 85.33 | 32.33 | 41.33 | 20.50 |
| **EMB-190/195** | | 2 | 5,982 | C | III | 3 | 124 | 94.25 | 126.83 | 51.95 | 23.67 |
| **A 320** | | 1,132 | 5,977 | C | III | 3 | 136 | 111.88 | 39.63 | 50.20 | 29.36 |
| **A220** | | 0 | 4,856 | C | III | 3 | 130 | 115.08 | 38.67 | 45.43 | 26.28 |
| **A319** | | 3,452 | 4,493 | C | III | 3 | 126 | 111.88 | 39.73 | 44.90 | 29.36 |
| **B737-8** | | 3,219 | 4,266 | D | III | 3 | 142 | 112.58 | 41.42 | 56.42 | 22.96 |
| **EMB E2*** | | 0 | 3,980 | C | III | 3 | 124 | 101.67 | 32.67 | 41.60 | 20.34 |
| **CRJ-900** | | 2,629 | 3,421 | C | III | 2 | 140 | 81.53 | 24.12 | 56.76 | 16.39 |
| **B767-3ER** | | 0 | 2,819 | D | IV | 5 | 140 | 156.08 | 52.92 | 82.17 | 35.75 |
| **B737-9** | | 1,388 | 1,807 | D | III | 3 | 141 | 112.58 | 41.41 | 61.58 | 22.96 |
| **A321** | | 40 | 1,123 | C | III | 3 | 140 | 117.45 | 39.70 | 44.95 | 29.43 |
| **A600ST** | | 60 | 89 | C | IV | 5 | 137 | 147.14 | 56.58 | 80.38 | 35.76 |
| **B767-4** | | 10 | 22 | D | IV | 5 | 150 | 170.33 | 55.83 | 93.33 | 36.00 |
| **MD-80 Series** | | 10,991 | 0 | C | III | 4 | 134 | 107.80 | 30.15 | 70.44 | 20.42 |
| **CRJ-2/4** | | 7,383 | 0 | C | II | 1B or 2 | 140 | 68.58 | 20.75 | 37.42 | 13.25 |
| **EMB-145** | | 2,993 | 0 | C | II | 2 | 124 | 67.75 | 22.17 | 47.42 | 15.72 |
| **B737-3** | | 1,269 | 0 | C | III | 3 | 135 | 102.08 | 36.50 | 46.08 | 20.92 |
| **A300** | | 1,025 | 0 | C | IV | 5 | 137 | 147.10 | 54.66 | 75.03 | 35.68 |
| **B757** | | 876 | 0 | C | IV | 4 | 137 | 124.83 | 45.08 | 72.00 | 28.00 |
| **B757-2** | | 823 | 0 | C | IV | 4 | 137 | 134.75 | 45.08 | 72.00 | 28.00 |
| **B717-2** | | 678 | 0 | C | III | 2 | 139 | 93.33 | 29.67 | 57.75 | 19.43 |
| **B737-4** | | 58 | 0 | C | III | 3 | 139 | 94.75 | 36.33 | 52.08 | 20.92 |
| **A330-3** | | 6 | 0 | C | V | 5 | 137 | 197.83 | 56.36 | 97.28 | 41.37 |
| **TOTAL** | | **48,526** | **64,333** | - | - | - | - | - | - | - | - |
| **Subtotal by AAC** | **C** | 43,908 | 55,419 | - | - | - | - | - | - | - | - |
| | **D** | 4,618 | 8,914 | - | - | - | - | - | - | - | - |
| **Subtotal by ADG** | **II** | 12,660 | 8,358 | - | - | - | - | - | - | - | - |
| | **III** | 33,065 | 53,045 | - | - | - | - | - | - | - | - |
| | **IV** | 2,794 | 2,930 | - | - | - | - | - | - | - | - |
| | **V** | 6 | 0 | - | - | - | - | - | - | - | - |

Note: N/A refers to aircraft that are at ORF but no in the current or future design aircraft family based on aircraft characteristics.

Source: FAA Database, NAA, CHA, 2018.

***Runway 14/32***

The Airport's previous 2008 Airport Layout Plan (ALP) categorized Runway 14/32 as a C-III runway; however, due to a decrease in airframe sizes using the runway, the runway is now categorized as an A-I. Based on current aircraft usage (as shown in **Table 3-44**), the SR22 is the current critical aircraft for Runway 14/32.

**Table 3-44 – Fleet Mix and Design Aircraft Families (Runway 14/32)**

| Aircraft | | 2018 Total Ops | AAC | ADG | TDG | AAC | ADG | | TDG | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | Approach Speed (knots) | Wingspan (ft.) | Tail Height (ft.) | CMG (ft.) | MGW (ft.) |
| **C208** | | 115 | A | II | 1A | 79 | 52.08 | 14.92 | 11.67 | 11.67 |
| **SR22** | | 95 | A | I | 1A | 78 | 38.33 | 8.92 | - | - |
| **C172** | | 68 | A | I | 1A | 62 | 36.08 | 8.92 | 5.42 | - |
| **RALY** | | 68 | A | I | | 65 | 31.92 | 9.17 | - | - |
| **PA32** | | 44 | A | I | 1A | 78 | 32.67 | 7.75 | 7.96 | 11.13 |
| **BE55** | | 41 | A | I | 1A | 88 | 37.83 | 9.58 | 7 | 9.58 |
| **BE58** | | 40 | B | I | 1A | 95 | 37.83 | 9.75 | 8 | 9.58 |
| **BE36** | | 28 | A | I | 1A | 77 | 33.5 | 8.58 | <10 | 9.63 |
| **SR20** | | 26 | A | I | 1A | 74 | 38.33 | 8.92 | - | - |
| **PA24** | | 12 | A | I | 1A | 75 | 36 | 7.47 | 6.55 | 10.17 |
| **AEST** | | 12 | B | I | 1A | 104 | 36.67 | 12.67 | 11.67 | 10.21 |
| **C337** | | 11 | A | I | 1A | 70 | 38 | 9.33 | - | - |
| **C68A** | | 11 | B | II | - | 78 | 38.75 | 9.33 | - | - |
| **(41 Aircraft Types)** | | 132 | A | I | - | - | - | - | - | - |
| **(2 Aircraft Types)** | | 10 | A | II | - | - | - | - | - | - |
| **(1 Aircraft Type)** | | 1 | A | III | - | - | - | - | - | - |
| **(5 Aircraft Type)** | | 9 | B | I | - | - | - | - | - | - |
| **(13 Aircraft Type)** | | 48 | B | II | - | - | - | - | - | - |
| **(6 Aircraft Type)** | | 9 | C | II | - | - | - | - | - | - |
| **(4Aircraft Type)** | | 4 | C | III | - | - | - | - | - | - |
| **(1 Aircraft Type)** | | 2 | D | I | - | - | - | - | - | - |
| **(1 Aircraft Type)** | | 1 | D | II | - | - | - | - | - | - |
| **Unidentified** | | 93 | N/A | N/A | - | - | - | - | - | - |
| **TOTAL** | | **880** | - | - | - | - | - | - | - | - |
| **Subtotal by AAC** | **A** | 651 | - | - | - | - | - | - | - | - |
| | **B** | 120 | - | - | - | - | - | - | - | - |
| | **C** | 13 | | | | | | | | |
| | **D** | 3 | | | | | | | | |
| **Subtotal by ADG** | **I** | 588 | - | - | - | - | - | - | - | - |
| | **II** | 194 | - | - | - | - | - | - | - | - |
| | **III** | 5 | - | - | - | - | - | - | - | - |

Source: FAA Database, NAA, HMMH, CHA, 2018.

Per FAA requirements, an appendix (**Appendix G**) has been included that provides a condensed look at the various forecast levels and growth rates, which include peaks, as well as operational factors at ORF as presented in this chapter.

# 4 FACILITY REQUIREMENTS

In order to ensure that Norfolk International Airport (ORF) is capable of supporting the forecasted increase in aviation activity, evaluations were conducted to ensure that the recommendations of this Master Plan adequately accommodate existing and anticipated activity levels. The purpose of this chapter is to identify the Airport's facility development needs over the 20-year planning horizon. Using the preferred aviation activity forecast presented in **Chapter 3**, the airport facility needs were determined, which form the basis of the development concepts discussed in **Chapter 5**.

The airport demand, capacity, design standards, and the overall facility requirements at ORF were evaluated using guidance contained in several FAA publications, including:

- Advisory Circular 150/5060-5, *Airport Capacity and Delay*
- AC 150/5300-13A, *Airport Design*
- AC 150/5325-4B*, Runway Length Requirements for Airport Design*
- AC 150/5360-13A, *Airport Terminal Planning*
- Title 14 Code of Federal Regulations (CFR) Part 77*, Safe, Efficient Use, and Preservation of the Navigable Airspace*
- Order 5090.3C, *Field Formulation of the National Plan of Integrated Airport Systems (NPIAS)*

During the evaluation, additional publications served strictly as technical references (thus not substituting FAA policy), including:

- Airport Cooperative Research Program (ACRP), *Report 25: Airport Passenger Terminal Planning and Design*
- ACRP, *Report 25 – Airport Passenger Terminal Planning and Design, Volume 1: Guidebook*
- ACRP, *Report 25 – Airport Passenger Terminal Planning and Design, Volume 2: Spreadsheet Models and User's Guide*
- ACRP, *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design*
- ACRP, *Report 54 – Resource Manual for In-Terminal Concessions 2011*
- International Air Transportation Association (IATA*), Airport Development Reference Manual (ADRM), 9th Edition*
- U.S. Department of Transportation, Federal Aviation Administration, Systems Research & Development Service *Report No. FAA-RD-75-191 – The Apron & Terminal Building Planning Manual July 1975*
- *US Customs and Border Protection. Airport Technical Design Standard, 2016.*

The following elements of the Airport were addressed in this assessment:

- Airfield Capacity
- Airfield Facility Requirements
- Support Facilities (General Aviation, Cargo, etc.)
- Passenger Terminal Facilities
- Surface Transportation & Parking Facilities

## 4.1 PLANNING FACTORS

Before the facility requirements for ORF could be determined, it was necessary to establish the Planning Activity Levels (PALs) based on the preferred forecasts, the design aircraft family, and the appropriate airport, runway, and taxiway classifications that are associated with FAA design standards. These parameters are discussed in the following subsections.

### 4.1.1 Planning Activity Levels (PALs)

Since aviation activity is highly susceptible to fluctuations in economic conditions and industry trends, identifying recommended facility improvements based solely on specific years can be a challenge. The timeline associated with the preferred forecast is representative of the anticipated timing of demand (in 5-year increments – 2023, 2028, 2033, and 2038). The actual timing of demand can vary; therefore, Planning Activity Levels (PALs), rather than calendar years, were established.

The PALs represent the activity levels believed to trigger the need for additional capacity or other development at the Airport, thus identifying significant demand thresholds for implementing recommended facility improvements and providing the Norfolk Airport Authority (NAA) with the flexibility to advance or slow the rate of development in response to actualized demand. In other words, if the preferred forecast proves conservative (i.e. the high growth forecast scenarios is realized because of successful airport marketing and route development initiatives, etc.), some recommended improvements may be advanced in schedule. In contrast, if demand occurs at a rate that is slower than the preferred forecast projects, the improvements should be deferred accordingly. As actual activity levels approach a PAL and trigger the need for a facility improvement, sufficient lead time for planning, design, and construction must be also given to ensure that the facilities are available for the impending demand.

**Table 4-1** identifies the PALs used for this study, which correspond with the preferred aviation activity forecast for the base year of 2018 and the planning horizon years 2023, 2028, 2033, and 2038. **Figure 3-1** presents a graphical representation of how the PALs for passengers were established and relates them to the preferred and alternative forecast scenarios (discussed in **Chapter 3**). The graphic helps to depict the relative time range during which each PAL could be reached if one of these other forecast scenarios are actualized. For example, facilities capable of accommodating PAL 2 demands (i.e. ±2.4 million annual enplanements) could be needed as early as 2028, if the recommended-growth forecast scenario is experienced or as late as 2038 if the low-growth scenario is realized.


## Table 4-1 – Planning Activity Levels (PALs)

| Passenger Activity | | | | | | | |
|---|---|---|---|---|---|---|---|
| **Enplanements** | | **2017** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Annual | | 1,672,024 | 1,857,487 | 2,115,424 | 2,376,990 | 2,622,848 | 2,834,623 |
| Peak Month | | 164,495 | 183,359 | 208,117 | 233,850 | 258,038 | 278,872 |
| Average Day | | 5,306 | 5,915 | 6,713 | 7,544 | 8,324 | 8,996 |
| Peak Hour* | | 1,215 | 1,354 | 1,537 | 1,727 | 1,906 | 2,060 |
| **Operations** | | | | | | | |
| **Category** | **Activity** | **2017** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Commercial Aviation | Annual | 47,195 | 48,986 | 51,889 | 55,177 | 57,488 | 61,430 |
| | Peak Month | 4,245 | 4,406 | 4,667 | 4,963 | 5,171 | 5,525 |
| | Average Day | 137 | 142 | 151 | 160 | 167 | 178 |
| | Peak Hour | 20 | 21 | 22 | 23 | 24 | 26 |
| General Aviation | Annual | 22,364 | 22,760 | 24,850 | 27,132 | 29,624 | 32,344 |
| Military Aviation | Annual | 600 | 600 | 600 | 600 | 600 | 600 |
| Cargo Operations | Annual | 2,429 | 2,475 | 2,719 | 2,987 | 3,281 | 3,604 |
| **Total Operations** | **Annual** | **72,588** | **74,821** | **80,058** | **85,896** | **90,992** | **97,978** |
| | **Peak Month** | **8,658** | **8,924** | **9,549** | **10,245** | **10,853** | **11,686** |
| | **Average Day** | **279** | **288** | **308** | **330** | **350** | **377** |
| | **Peak Hour*** | **33** | **34** | **37** | **39** | **42** | **45** |

*Note: The peak hour for enplanements was determined to be between 6:00 am and 7:30 am on weekdays. When determining total operations occurring in a peak hour, the percent of peak month operations (11.9 percent) was applied to the peak month-average day operations, remaining static throughout the forecast period.

Source: CHA, 2018.

## Figure 4-1 – Enplanement Planning Activity Levels (PALs)




Source: CHA, 2018.

### 4.1.2 Aircraft Classification

The FAA has established aircraft classification systems that group aircraft types based on their performance and geometric characteristics. These classification systems were used to determine the appropriate airport design standards for specific runway, taxiway, taxilane, apron, or other facilities at ORF, as described in FAA AC 150/5300-13A, *Airport Design*.

As discussed in **Chapter 3**, the standard classifications are the Aircraft Approach Category (AAC), the Airplane Design Group (ADG), and Taxiway Design Group (TDG). **Table 4-2** presents the applicability of these classification systems to the FAA airport design standards for individual airport components (such as runways, taxiways, or aprons).

**Table 4-2 – Applicability of Aircraft Classifications**

| Aircraft Classification | Related Design Components |
|---|---|
| Aircraft Approach Category (AAC) | Runway Safety Area (RSA), Runway Object Free Area (ROFA), Runway Protection Zone (RPZ), runway width, runway-to-taxiway separation, runway-to-fixed object |
| Airplane Design Group (ADG) | Runway, Taxiway, and apron Object Free Areas (OFAs), parking configuration, taxiway-to-taxiway separation, runway-to-taxiway separation |
| Taxiway Design Group (TDG) | Taxiway width, radius, fillet design, apron area, parking layout |

Source: FAA AC 150/5300-13A, CHA, 2018.

### 4.1.3 Design Aircraft Family

The "critical aircraft" or "design aircraft family" represent the most demanding aircraft or grouping of aircraft with similar characteristics (relative to AAC, ADG, TDG) that are currently using or are anticipated to use an airport on a regular basis. The design aircraft family was identified for ORF (see **Table 4-3**) after review of the FAA's Traffic Flow Management System Counts (TFMSC) data, T100 data[20], airport-reported data, and forecast fleet mix assumptions (as described in **Chapter 3**). This grouping represents the typical commercial aircraft and cargo aircraft anticipated to operate at ORF over the planning horizon. These aircraft generally have higher AAC, ADG, and TDG classifications than the other regularly scheduled commercial aircraft. Determining the critical aircraft is important when planning airfield and landside facilities as they may require specific facility design accommodations within their designated areas of operation. It is important to note that the CRJ-700 has over 8,000 operations forecasted by PAL 4 and the CRJ-900 with over 3,000 by this period. In mid-2019, Mitsubishi Aircraft acquired the CRJ program from Bombardier and is expected to end all CRJ production in the year 2020. While they will likely implement a comparable aircraft as its replacement, it is important to note that these CRJ forecast numbers are simply representative.

[20] The Bureau of Transportation Statistics (BTS) uses a form (Form T-100) to gather monthly traffic reports from certificated air carriers in the United States. These traffic reports provide information regarding domestic and international markets, as well as domestic and international segments. The data collected is then made available to the public via BTS's Air Carrier Statistics Database, also known as the T-100 data bank.

**Table 4-3 – Fleet Mix and Design Aircraft Family**

| Aircraft | | 2017 | PAL 4 | AAC | ADG | TDG | AAC | ADG | | TDG | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Approach Speed (knots) | Wingspan (ft.) | Tail Height (ft.) | CMG (ft.) | MGW (ft.) |
| B737-7 | | 5,643 | 8,998 | C | III | 3 | 130 | 117.42 | 41.58 | 46.58 | 22.92 |
| CRJ-700 | | 2,284 | 8,358 | C | II | 2 | 135 | 76.27 | 24.83 | 49.25 | 16.39 |
| ERJ-175 | | 2,564 | 8,142 | C | III | 3 | 124 | 85.33 | 32.33 | 41.33 | 20.50 |
| EMB-190/195 | | 2 | 5,982 | C | III | 3 | 124 | 94.25 | 126.83 | 51.95 | 23.67 |
| A 320 | | 1,132 | 5,977 | C | III | 3 | 136 | 111.88 | 39.63 | 50.20 | 29.36 |
| A220 | | 0 | 4,856 | C | III | 3 | 130 | 115.08 | 38.67 | 45.43 | 26.28 |
| A319 | | 3,452 | 4,493 | C | III | 3 | 126 | 111.88 | 39.73 | 44.90 | 29.36 |
| B737-8 | | 3,219 | 4,266 | D | III | 3 | 142 | 112.58 | 41.42 | 56.42 | 22.96 |
| EMB E2* | | 0 | 3,980 | C | III | 3 | 124 | 101.67 | 32.67 | 41.60 | 20.34 |
| CRJ-900 | | 2,629 | 3,421 | C | III | 2 | 140 | 81.53 | 24.12 | 56.76 | 16.39 |
| B767-3ER | | 0 | 2,819 | D | IV | 5 | 140 | 156.08 | 52.92 | 82.17 | 35.75 |
| B737-9 | | 1,388 | 1,807 | D | III | 3 | 141 | 112.58 | 41.41 | 61.58 | 22.96 |
| A321 | | 40 | 1,123 | C | III | 3 | 140 | 117.45 | 39.70 | 44.95 | 29.43 |
| A600ST | | 60 | 89 | C | IV | 5 | 137 | 147.14 | 56.58 | 80.38 | 35.76 |
| B767-4 | | 10 | 22 | D | IV | 5 | 150 | 170.33 | 55.83 | 93.33 | 36.00 |
| MD-80 Series | | 10,991 | 0 | C | III | 4 | 134 | 107.80 | 30.15 | 70.44 | 20.42 |
| CRJ-2/4 | | 7,383 | 0 | C | II | 1B or 2 | 140 | 68.58 | 20.75 | 37.42 | 13.25 |
| EMB-145 | | 2,993 | 0 | C | II | 2 | 124 | 67.75 | 22.17 | 47.42 | 15.72 |
| B737-3 | | 1,269 | 0 | C | III | 3 | 135 | 102.08 | 36.50 | 46.08 | 20.92 |
| A300 | | 1,025 | 0 | C | IV | 5 | 137 | 147.10 | 54.66 | 75.03 | 35.68 |
| B757 | | 876 | 0 | C | IV | 4 | 137 | 124.83 | 45.08 | 72.00 | 28.00 |
| B757-2 | | 823 | 0 | C | IV | 4 | 137 | 134.75 | 45.08 | 72.00 | 28.00 |
| B717-2 | | 678 | 0 | C | III | 2 | 139 | 93.33 | 29.67 | 57.75 | 19.43 |
| B737-4 | | 58 | 0 | C | III | 3 | 139 | 94.75 | 36.33 | 52.08 | 20.92 |
| A330-3 | | 6 | 0 | C | V | 5 | 137 | 197.83 | 56.36 | 97.28 | 41.37 |
| TOTAL | | 48,526 | 64,333 | - | - | - | - | - | - | - | - |
| Subtotal by AAC | C | 43,908 | 55,419 | | - | - | - | - | - | - | - |
| | D | 4,618 | 8,914 | | - | - | - | - | - | - | - |
| Subtotal by ADG | II | 12,660 | 8,358 | | - | - | - | - | - | - | - |
| | III | 33,065 | 53,045 | | - | - | - | - | - | - | - |
| | IV | 2,794 | 2,930 | | - | - | - | - | - | - | - |
| | V | 6 | 0 | | - | - | - | - | - | - | - |

Source: NAA, CHA, 2018.

### 4.1.4 Airport & Runway Classification

The FAA classifies airports and runways based on their current and planned operational capabilities. These classifications (described below), along with the aircraft classifications defined previously, were used to determine the appropriate FAA standards (as per AC 150/5300-13A) for airfield facilities.

***Airport Reference Code (ARC)***

ARC is an airport designation that represents the AAC and ADG of the aircraft that the airfield is intended to accommodate on a regular basis. The ARC is used for planning and design only and does not limit the aircraft that may be able to operate safely on the airport. The Airport's previous 2008 Airport Layout Plan (ALP) identified the Boeing 757-200 (which at the time the previous master plan was completed was categorized as D-IV) as the critical aircraft for airfield and

pavement design. It is important to note that new FAA guidance categorizes the B757-200 as C-IV; however, recent activity has shown the Airbus A300 and Boeing 737-900 to be the current critical aircraft, which are categorized as C-IV and D-III, respectively. As such, the current ARC remains D-IV.

Due to increasing airframe size resulting from fleet mix transitions and the projected increase of Boeing 767-300ER operations from FedEx, the future critical aircraft[21] for airfield and pavement design is the B767-300ER, maintaining the ARC of ORF as D-IV. The current taxiway design aircraft (A300) is in the same TDG category as the B767-300ER; therefore, the TDG for the Airport's airfield also remains TDG 5.

**Table 4-4 – Fleet Mix and Design Aircraft Family by AAC and ADG**

| AAC/ADG | | 2017 | PAL 4 |
|---|---|---|---|
| Operations by AAC | C | 43,908 | 55,419 |
| | D | 4,618 | 8,914 |
| Operations by ADG | II | 12,660 | 8,358 |
| | III | 33,065 | 53,045 |
| | IV | 2,794 | 2,930 |
| | V | 6 | 0 |

Source: NAA, CHA, 2018.

## 4.2 AIRFIELD CAPACITY REQUIREMENTS

Airfield capacity refers to the maximum number of aircraft operations (takeoffs or landings) an airfield can accommodate in a specified amount of time. Assessments of the airfield's current and future capacity were performed using common methods described in FAA AC 150/5060-5, *Airport Capacity and Delay*.

### 4.2.1 FAA AC 150/5060-5, *Airport Capacity and Delay*

FAA AC 150/5060-5, *Airport Capacity and Delay*, explains how to compute airfield capacity for the purposes of airport planning and design. This evaluation helped to determine any capacity-related improvements or expansions that may be needed to support flight activity levels. The estimated capacity of the airfield at ORF was expressed in the following three measurements:

- Hourly Capacity – The maximum number of aircraft operations an airfield can safely accommodate under continuous demand in a one-hour period. This expression accounts for Visual Flight Rules (VFR) and Instrument Flight Rules (IFR) conditions and is used to identify any peak-period constraints on a given day.
- Annual Service Volume (ASV) – The maximum number of aircraft operations an airfield can accommodate in a one-year period without excessive delay. This calculation is typically used in long-range planning and referenced for capacity-related improvement.
- Aircraft Delay – The average number of minutes an aircraft experiences delay on the airfield and total hours of delay incurred over a one-year period.

[21] A list of critical aircraft for existing and future conditions were previously presented in **Chapter 3** and have been approved by the FAA. It is important to note the list is representative of the types of aircraft foreseen to operate at ORF throughout the forecast period, rather than the exact aircraft that will operate at the Airport.

The tables and figures from AC 150/5060-5 that were utilized in the following evaluations can be found in **Appendix J**.

***Capacity Calculation Factors***

To calculate these three measurements of capacity and delay, several key factors and assumptions specific to ORF were defined. Consistent with the guidance provided in AC 150/5060-5, these included:

- Aircraft Fleet Mix Index – a ratio of the various classes of aircraft serving an airport
- Runway-Use Configuration – the number and orientation of the active runways
- Percentage of Aircraft Arrivals – the ratio of landing operations to total operations
- "Touch and Go" Factor – the ratio of landings with a direct takeoff to total operations
- Location of Exit Taxiways – the number of taxiways available to an aircraft within a given distance from the arrival end of a runway
- Meteorological Conditions – the percentages of times an airfield experiences VFR, IFR, and Poor Visibility Conditions (PVC) conditions

Aircraft Fleet Mix Index

An airport's fleet mix index is determined by the size of typical aircraft and the frequency of their operations. To identify the aircraft mix index, AC 150/5060-5, *Airport Capacity and Delay*, has established four categories in classifying an aircraft by its maximum takeoff weight (MTOW), as depicted in **Table 4-5**.

**Table 4-5 – Aircraft Capacity Classifications**

| Aircraft Class | MTOW (lbs) | Number of Engines | Wake Turbulence |
|---|---|---|---|
| A | <12,500 | Single | Small (S) |
| B | | Multi | |
| C | 12,500 – 300,000 | Multi | Large (L) |
| D | >300,000 | Multi | Heavy (H) |

Source: FAA AC 150/5060-5, CHA, 2018.

The aircraft mix index is calculated using the formula *%(C + 3D)*, the letters corresponding with the aircraft class. This product falls into one of the FAA-established mix index ranges listed below and is used in capacity calculations herein:

• 0 to 20 • 21 to 50 • 51 to 80 • 81 to 120 • 121 to 180

The current facilities at the Airport can accommodate all four aircraft classes. The following operations percentages for aircraft categories C and D were gathered from a review of operations that occurred in 2017:

- Class C = 77.3 percent of the Airport's operations
- Class D = 1.5 percent of the Airport's operations

As such, the base year aircraft mix index is 81.7 [77.3 + 3(1.5) = 81.7]. While the actual mix index for the Airport is subject to variations given changes in air traffic operations, the likelihood of the Airport's mix index to grow beyond the mix index grouping of 81-120 over the planning period is low. Based on the fleet mix changes described in **Chapter 3** for commercial, cargo, military, and

general aviation operations, the aircraft fleet mix index is anticipated to increase lightly from 81.7 in 2017 to 89.9 in PAL 4. See **Table 4-6** for each planning period's Aircraft Mix Index.

**Table 4-6 – Aircraft Mix Index**

| Year | Aircraft Mix Index |
|---|---|
| **2017** | 81.7 |
| **Base** | 86.7 |
| **PAL 1** | 87.7 |
| **PAL 2** | 88.6 |
| **PAL 3** | 89.2 |
| **PAL 4** | 89.9 |

Source: FAA AC 150/5060-5, CHA, 2018.

Runway Use Configuration

The principle determinants of an airfield's layout or configuration are the number and orientation of runways. The efficiency and functionality of the runways used in conjunction with the taxiways and aprons during the various levels of aviation activity directly affects an airport's operational capacity.

If an airfield layout consists of more than one runway, those runways can be termed as either "independent" or "dependent" of each other. An independent runway is one that is not operationally affected by the other runways during normal operations (e.g. parallel runways with sufficient separation). A dependent runway is one that is configured in such a way that aircraft must wait for operations to complete on another runway before resuming (e.g. intersecting runways). Due to this wait time, airfields with dependent runway systems are inherently limited compared to independent runways. The intersecting runways at ORF are thus dependent.

Runway 5/23 has a northeast/southwest orientation and serves as the primary runway for all airport operations. In addition to this runway, Runway 14/32, which has a northwest/southeast orientation, serves as the general aviation crosswind runway. Because the Airport primarily utilizes the two-main runway ends for takeoff and landing (arrival and departure) operations, the usage rates of each runway (5 and 23) were evaluated. These conclusions were established considering the combined VFR and IFR conditions. Radar data also indicated low usage of Runway 14/32. It should be noted that Runway 14/32 is a visual runway. Typically, wind is more favorable from the south. Air Traffic Control directs aircraft, including most light aircraft, to land Runway 23 during these conditions, further resulting in low usage of Runway 14/32. Due to low usage of Runway 14/32, the Airport is essentially operating under a single runway configuration, which is acknowledged by the FAA; therefore, a single runway configuration was assumed to represent the current airfield configuration when using the methodologies presented in AC 150/5060-5.

Percentage of Aircraft Arrivals

The percentage of arrivals is the ratio of landing operations to total operations at an airport during a specified period and is generally assumed to be equal to the percentage of departing operations; therefore, a factor of 50 percent was used for the capacity calculations for the Airport.

Percentage of Touch-and-Go Operations

Because a touch-and-go (T&G) is representative of two operations (i.e. a landing and takeoff performed consecutively during local flight training operations), an airfield with a higher percentage of T&G operations typically has a greater airfield capacity than one with a higher percentage of air carrier operations.

Operational statistics provided by the ORF Air Traffic Control Tower (ATCT) identified very little local or no T&G operations (less than 1 per day) at ORF. With the assumption that these operations are T&Gs and that local operations will not experience a significant growth over the planning horizon, a percentage range of zero to 20 percent was used in the capacity calculations. Based on FAA figures, this percentage equated to a T&G factor of 1.0.

Location of Exit Taxiways

The location and number of exit taxiways affect the capacity of an airport's runway system because they directly relate to an aircraft's runway occupancy time. Runway capacities are highest when they are complimented with full-length, parallel taxiways, ample runway entrance and exit taxiways, and no active runway crossings. These components reduce the amount of time an aircraft remains on the runway. FAA AC 150/5060-5 identifies the criteria for determining taxiway exit factors based on the mix index and the distance the taxiway exits are from the runway threshold and other taxiway connections. As the Airport's existing mix index range was calculated to be 81-120 over the planning period, only exit taxiways that are between 5,000 and 7,000 feet from the threshold and spaced at least 750 feet apart contribute to the taxiway exit factors. By combining the mix index, percent of aircraft arrivals, and the number of exit taxiways within the specified range, a taxiway exit factor was calculated (0.94 during VFR and 0.92 during IFR).

Meteorological Conditions

Meteorological conditions at and around an airport also have significant impacts on the capacity of an airfield. Previously described runway use percentages are a result of prevailing winds dictating which runway an aircraft should use for takeoff and landing operations.

Three measures of cloud ceiling and visibility are recognized by the FAA and were used to calculate capacity. These included:

- Visual Flight Rules (VFR) – Cloud ceiling is greater than 1,000 feet above ground level (AGL) and visibility is at least three statute miles.
- Instrument Flight Rules (IFR) – Cloud ceiling is at least 500 feet AGL but less than 1,000 feet AGL and/or the visibility is at least one statute mile but less than three statute miles.
- Poor Visibility conditions (PVC) – Cloud ceiling is less than 500 feet AGL and/or the visibility is less than one statute mile.

ORF experiences VFR conditions approximately 85.2 percent of the time, IFR conditions 13.5 percent of the time, and PVC conditions 1.3 percent of the time. These are approximate percentages derived from the historical data from the Airport's AWOS (See **Appendix K**).

Summary of Capacity Calculation Factors

**Table 4-7** summarizes these parameters calculated for ORF, which were used to define the hourly capacity (in VFR and IFR conditions-See **Appendix K**) and the ASV for the Airport.

**Table 4-7 – Calculated Capacity Parameters**

| Factor | 2017 |
|---|---|
| Aircraft Fleet Mix Index | 81.7 |
| Runway-Use Configuration | Single Runway |
| Percentage of Aircraft Arrivals | 50% |
| Touch and Go Factor (VFR / IFR) | 1.0/1.0 |
| Taxiway Exit Factor (VFR / IFR) | 0.94/0.92 |
| Meteorological Conditions (VFR / IFR) | 85.2%/13.5% |

Note: VFR/IFR percentages were derived via the Airports AWOS (PVC:1.3%)
Source: FAA Operations Network (OPSNET), FAA AC 150/5060-5, CHA, 2019.

***Current Airfield Capacity (Single Runway Assumption)***

As previously discussed, it is important to note that a single runway configuration was assumed to represent the current airfield configuration, as a capacity model for a crosswind runway configuration would not reflect the limited usage of the crosswind runway (Runway 14/32) at ORF. Instead, the crosswind runway configuration analysis would assume that Runway 14/32 is available for commercial use, thus assuming both intersecting runways are available for all operations at ORF; however, commercial service operations and larger GA and cargo operations are not currently accommodated by the crosswind runway due to runway length.

The airfield capacity analysis for a single runway configuration was evaluated with the following conditions and assumptions applied:

- Runway 14/32 does not contribute meaningfully to the capacity of the Airport given its low utilization.
- The effective runway configuration is a single runway (Runway 5/23)
- Meteorological Conditions (VFR/IFR), shown in **Table 4-7,** will remain constant throughout the forecast period

Hourly Capacity

Hourly capacity for the airfield is a measurement of the maximum number of aircraft operations (VFR and IFR) that an airfield can support in an hour based on the runway configuration. Using graphs provided in AC 150/5060-5, VFR and IFR hourly capacity bases were established by applying the given VFR and IFR operational capacities for the runway use configuration, the aircraft mix index, and the percentage of aircraft arrivals. Once the hourly capacity bases were identified, they were multiplied by the touch-and-go factors and taxiway exit factors to determine the hourly capacities. This equation is expressed as:

$$Hourly\ Capacity = C^* \times T \times E$$

*C* = Hourly Capacity Base*
*T = Touch-and-Go Factor*
*E = Taxiway Exit Factor*

**Table 4-8** shows the results of the hourly capacity for 2017, the base year, and for PALs 1 through 4. Note that as the mix index increases from 81.7 (2017) to 89.9 (PAL 4), the operational capacities decrease.

**Table 4-8 – Calculated Hourly Capacity (Single Runway Configuration)**

| Factors | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| | VFR / IFR | VFR / IFR | VFR / IFR | VFR / IFR | VFR / IFR | VFR / IFR |
| Hourly Capacity Base | 58.0/54.5 | 57.0/54.0 | 57.0/54.0 | 57.0/54.0 | 56.5/53.5 | 56.5/53.5 |
| Touch-and-Go Factor | 1.0/1.0 | 1.0/1.0 | 1.0/1.0 | 1.0/1.0 | 1.0/1.0 | 1.0/1.0 |
| Taxiway Exit Factor | 0.94/0.92 | 0.94/0.92 | 0.94/0.92 | 0.94/0.92 | 0.94/0.92 | 0.94/0.92 |
| **Calculated Hourly Capacity** | **54.5/50.1** | **53.6/49.7** | **53.6/49.7** | **53.6/49.7** | **53.1/49.2** | **53.1/49.2** |

Note: FAA AC 150/5060-5 [VFR (Figure 3-3), IFR (Figure 3-43)]
Source: FAA AC 150/5060-5, CHA, 2019.

Annual Service Volume

Annual Service Volume (ASV) is an expression of the total number of aircraft operations that an airfield can support per annum. The formula for estimating an airport's ASV is based on the ratio of annual operations to average daily operations during the peak month, multiplied by the ratio of average daily operations to average peak hour operations during the peak month. The product of these values is then multiplied by the weighted hourly capacity to determine the ASV.

Weighted hourly capacity accounts for the varying operating conditions at the airport, which are applied to the hourly capacity determined in the previous section. The formula for weighted hourly capacity is expressed as:

$$C_w = \frac{(C_{n1} \times W_{n1} \times P_{n1}) + (C_{n2} \times W_{n2} \times P_{n2})}{((W_{n1} \times P_{n1}) + (W_{n2} \times P_{n2}))}$$

*$C_w$ = Airfield weighted hourly capacity*
*$_n$ = Number of runway-use configurations.*
*C = Hourly Capacity of each configuration.* ***(2017) VFR/IFR = 54.5/50.1***
*W = FAA ASV weighting factor, based on mix index & percentage and hourly capacity.* ***VFR/IFR = 1/1*** *(See* ***Appendix J****)*
*P = Percent of time the Airport operates in each configuration.* ***VFR/IFR = 85.2%/13.5%***

Applying the 2017 ORF data to this equation yielded the following:

$$C_w = \frac{(54.5 \times 1 \times 85.2) + (50.1 \times 1 \times 13.5)}{((1 \times 85.2) + (1 \times 13.5))}$$

$$\boldsymbol{C_w = 53.9}$$

Based on the formula above, the airfield weighted hourly capacity is approximately 54 operations per hour.

The ASV formula accounts for a variety of conditions that occur at an airport, including low- and high-volume activity periods, and is expressed as:

$$ASV = C_w \times D \times H$$

*$C_w$ = Weighted Hourly Capacity.*
*D = Daily Demand Ratio (ratio of annual operations to average daily operations during peak month).*
*H = Hourly Demand Ratio (ratio of average daily operations to average peak hour operations during peak month)*

Based on the ASV metric calculated using Chapter 3 of AC 150/5060-5, only certain criteria apply when determining the demand ratios. It is important to recognize that ASV demand ratios were solely based on average daily demand during the peak month and average hourly demand during the peak month as they relate to operations; thus, they were not based on peak daily or peak hourly activity at the Airport and do not correspond with the peak activity levels presented in **Chapter 3**. The peak activity demand forecasts in **Chapter 3** were derived based on peak enplanement data and peak operating periods as they related to the enplanements, whereas the activity demand presented herein were based on aircraft operations and not enplanements. Data derived via FAA TFMSC and Distributed OPSNET was used when determining the month with the most operations, the average daily operations during the peak month, and the average hourly operations during the peak month. Reference **Appendix L**.

**Table 4-9** identifies the daily and hourly demand ratios throughout the planning period.

**Table 4-9 – Demand Ratios**

| Factor | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| Annual Operations | 72,588 | 74,821 | 80,058 | 85,896 | 90,992 | 97,978 |
| Av. Daily Operations (in Peak Month) | 220.0 | 226.8 | 242.6 | 260.3 | 275.8 | 297.0 |
| Av. Peak Hour (in Peak Month) | 15.0 | 15.0 | 16.5 | 17.8 | 18.8 | 20.2 |
| **Daily Demand Ratio (D)** | **329.9** | **329.9** | **329.9** | **329.9** | **329.9** | **329.9** |
| **Hourly Demand Ratio (H)** | **14.7** | **14.7** | **14.7** | **14.7** | **14.7** | **14.7** |

Note: Data used for determining daily and hourly demand ratios can be found in **Appendix L**.
Source: FAA AC 150/5060-5, CHA, 2019.

The ASV equation for 2017 was as follows:

*ASV* = 53.9 x 329.9 x 14.7*

***ASV = 260,936***

**Note: The numbers presented in this formula have been rounded; however, the results of the formula are based on actual, un-rounded numbers. Again, it is important to reiterate that average daily demand and average hourly demand are independent of the activity demand forecasts presented in **Chapter 3**.*

If the annual operations exceed the ASV, the airport is likely to see significant delays. It should be understood that an airport can still experience delays before capacity is reached. Activity levels that may trigger capacity planning and development are discussed in FAA Order 5090.35, *Field Formulation of the National Plan of Integrated Airport Systems (NPIAS)*, which indicates (via Table 4-4 of Order 5090.5) that 60 percent ASV is the trigger for planning a new runway or extended runway to increase hourly capacity and the trigger for development is being within five years of the ASV reaching 80 percent. This allows an airport to make necessary improvements and avoid


delays before they are anticipated to occur. The ASV for 2017 showed ORF at approximately 27.8 percent capacity (**Table 4-10**). To better understand ORF's current and projected operational capacity levels, the 2017, base year, and PALs 1 through 4 demands are compared to their respective annual service volumes in **Table 4-10**. The capacity levels are depicted in **Figure 4-2**.

**Table 4-10 – Annual Service Volume (Single Runway Configuration)**

| Factor | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| Annual Operations | 72,588 | 74,821 | 80,058 | 85,896 | 90,992 | 97,978 |
| Annual Service Volume | 260,936 | 256,705 | 256,705 | 256,705 | 257,599 | 257,599 |
| **Capacity Level** | **27.8%** | **29.1%** | **31.2%** | **33.5%** | **35.3%** | **38.0%** |

Note:, ASV was based on average peaks during the busiest month, rather than peak, activity levels.
Source: FAA AC 150/5060-5, CHA, 2019.

**Figure 4-2 – Projected Demand (Single Runway Configuration)**




Note:, ASV was based on average, rather than peak, activity levels.
Source: NAA, CHA, 2019.

Airfield Capacity Conclusion Using FAA AC/150/5060-5

As previously discussed, a single runway configuration was assumed to represent the current airfield layout at ORF due to low usage of Runway 14/32, which is recognized by the FAA. Based on the airfield capacity calculations for a single runway configuration, the Airport would currently be at approximately 27.8 percent of capacity and would only reach approximately 38.0 percent capacity by PAL 4 if Runway 14/32 is closed; therefore, based on this model, a single runway configuration can adequately accommodate forecasted growth; however, it is important to remember that only certain criteria was considered during the analysis.

Although the ASV depicts that the Airport has adequate capacity, and as previously discussed, the model was based on average daily demand and average hourly demand in the peak month. As such, during busiest hours, ORF sees significantly higher peaks, as shown in the forecasts presented in **Chapter 3**; therefore, during the busiest hours of operation, throughput capacity may be a concern, as commercial, cargo, and general aviation activities are expected to increase throughout the forecast horizon; however, it must be noted that the industry norm is to build

necessary airport infrastructure for the PMAD, rather than the top peak which is often not cost effective. FAA criteria for use of AIP/PFC is aligned to infrastructure needs for PMAD. Acknowledging this, the Airport's desire is to build infrastructure that achieves a higher level of service than industry norms.

For the purposes of this Study, the results using the model herein were used during an in-depth analysis of runway development alternatives, as well as their impact on airfield capacity, which are provided in subsequent chapters.

## 4.3 AIRFIELD FACILITY REQUIREMENTS

Airfield improvements are planned and developed according to the established ARC, ADG, and TDG for an airport. The associated design criteria are applied when planning upgrades or improvements for a runway or taxiway. An airport's ARC is determined by the critical aircraft (aircraft with the longest wingspan, highest tail, and fastest approach speeds) that makes "regular use" of the airport or a specific runway. FAA AC 150/5000-17 defines "regular use" as 500 annual operations, including both itinerant and local operations but excluding touch-and-go operations (an operation is either an arrival or departure). As stated in **Section 4.1.4**, ORF has an existing ARC of D-IV and, based on future projections of aircraft fleet mix transitions, is forecast to become a D-IV airport in the five- to ten-year range; however, this does not affect the Airport's design standards (per FAA AC 150/5300-13A).

### 4.3.1 Runway Requirements

***Airfield Configuration***

The general configuration of the airfield, including the number of runways along with their location/orientation, should allow the airport to meet anticipated air traffic demands and maximize wind coverage and operational utility for all types of aircraft. As stated in **Chapter 2**, it is a FAA recommendation that the runway system at an airport be oriented to provide at least 95 percent wind coverage. This means that 95 percent of the time in a given year, the crosswind coverage at an airport is within acceptable limits for the types of aircraft operating on the runways. As shown in **Table 4-11**, the current intersecting runway configuration at ORF provides wind coverage greater than the FAA recommended 95 percent for the design aircraft. Furthermore, Runway 5/23 alone provides over 95 percent wind coverage for all crosswind components, excluding 10.5 knots during IFR conditions.

**Table 4-11 – ORF Wind Coverage**

| | Runway | 10.5 Knots | 13 Knots | 16 Knots | 20 Knots |
|---|---|---|---|---|---|
| AW | 5/23 | 95.56% | 98.14% | 99.62% | 99.93% |
| | 14/32 | 80.00% | 87.77% | 95.89% | 98.81% |
| | All Combined | 98.58% | 99.64% | 99.93% | 99.99% |
| VFR | 5/23 | 95.75% | 98.27% | 99.70% | 99.96% |
| | 14/32 | 78.79% | 87.17% | 96.01% | 99.04% |
| | VFR Combined | 98.77% | 99.72% | 99.96% | 100% |
| IFR | 5/23 | 92.05% | 96.34% | 98.9% | 99.75% |
| | 14/32 | 76.67% | 84.58% | 92.52% | 96.68% |
| | IFR Combined | 96.51% | 98.88% | 99.75% | 99.98% |

Source: NOAA, National Climate Center; Station 725080 (2007-2016).

Air traffic records indicate limited use of A-I and B-I aircraft at ORF. Furthermore, the 2010 *General Aviation and Part 135 Activity Survey* indicated that these smaller aircraft do not fly as often during IFR weather conditions. As such, it was concluded that no changes to the runway configuration are recommended during the planning horizon to accommodate wind conditions.

***Runway Designations***

Due to the changes in the earth's magnetic declination over time, the compass heading of a runway and its associated end number can change. Current magnetic declination information was derived from the National Oceanic and Atmosphere Administration (NOAA). The current headings and declinations of the runway ends at ORF are as follows:

- Runway 5
  - Current headings: 047° magnetic, 038° true
  - Declination: 10° 55' W ± 0° 21' changing by 0° 1' W per year
- Runway 23
  - Current headings: 227° magnetic, 218° true
  - Declination: 10° 56' W ± 0° 21' changing by 0° 1' W per year
- Runway 14
  - Current headings: 137° magnetic, 128° true
  - Declination: 10° 55' W ± 0° 21' changing by 0° 1' W per year
- Runway 32
  - Current headings: 317° magnetic, 308° true
  - Declination: 10° 55' W ± 0° 21' changing by 0° 1' W per year

Currently, no changes in the runway designations are needed; however, since magnetic declination changes slowly over time, the runway numbers may need to be reevaluated by PAL 4, at which time the magnetic declination may have changed more significantly.

***Runway Design Standards***

During this master planning effort, FAA design and safety standards related to the airfield facilities were identified so that the airport may review and work to achieve compliance where needed. The standards include dimensions, separation distances, protection zones, clearance requirements, etc., which vary according to the design aircraft.

Each runway at the Airport is assigned a Runway Design Code (RDC), which signifies the design standards that the runway is to meet. As detailed in **Chapter 3, *Forecasts of Aviation Demand***, Runway 5/23 is categorized as runway design group D-IV, whereas Runway 14/32 is A-I. For Runway 14/32, based on radar data provided by the FAA, current activity levels and fleet mix on this runway no longer justify the current design standards previously required of Runway 14/32 (previous ALP defined Runway 14/32 as C-III). As such, infrastructure requirements necessary to accommodate C-III operations are no longer necessary. Additionally, given the low activity levels and that Runway 5/23 provides adequate wind coverage for all fleet types, further evaluation to the benefits and constraints of Runway 14/32 are examined in subsequent sections.

Runway 5/23 Standardization Project

The key FAA design and safety standards related to the runways at ORF (as defined in AC 150/5300-13A, *Airport Design*) are described below.

Runway Width – Runway width requirements are based on the critical aircraft associated with each runway. For ARC C-III and D-IV, the required runway width is 150 feet. Currently, both Runways 14/32 and 5/23 are 150 feet wide, thereby meeting this design requirement. Another significant design standard for safety is distance of the runway centerline to the parallel taxiway centerline. Currently, both Runways 14/32 and 5/23 are within acceptable range.

Runway Shoulders – Shoulders provide resistance to blast erosion and accommodate the passage of maintenance and emergency equipment and the occasional passage of an airplane veering from the runway. The FAA recommends paved shoulders for runways accommodating Group III aircraft and higher. FAA AC 150/5300-13A indicates the required shoulder width to be 25 feet on either side of a Group III or Group IV runway. Runway 5/23 is equipped with shoulders that vary up to 15 feet in width in some portions, lacking shoulders altogether in other portions. Given it is a D-IV runway, 25-foot shoulders are required per FAA standards; therefore, in PAL 1, it is recommended that the runway's shoulders be built out to 25-feet in accordance with FAA standards.

Runway 14/32 has turf shoulders. To comply with the FAA C-III design standards of 25 feet in width, paved shoulders would be required; however, the process of decommissioning the runway will begin in PAL 1 with an environmental assessment, followed by the official closure in PAL 2.

Runway Safety Area (RSA) – The RSA is a rectangular area bordering a runway that is intended to reduce the risk of damage to aircraft in the event of an undershoot, overrun, or excursion from the runway. The RSA is required to be cleared and graded such that it is void of potentially hazardous ruts, depressions, or other surface variations. Additionally, the RSA must be drained by grading or storm sewers to prevent water accumulation, be able to support snow removal and firefighting equipment, and be free of objects except those required because of their function.

The RSA for a Group III or IV runway is required to be 500 feet wide and extend 1,000 feet beyond the runway end. The longitudinal grade from the end of the runway should be between 0.0 percent to -3.0 percent for the first 200 feet and no more than -5.0 percent for the remaining 800 feet of the RSA. Transverse grades should be -1.5 percent to -3.0 percent away from the runway shoulder edge and beyond the runway ends.

The Runway 14/32 RSA meets the length, width, and grading requirements through the application of declared distances. For the Runway 5/23 RSA, its width currently varies between 350 feet and 500 feet, falling short of the 500-foot minimum. This is a result of a drainage structure located near the intersection with Taxiway A and the holding bay adjacent to Taxiway C on the Runway 5 end (the holding bay ROFA non-compliance was corrected via a recent Taxiway Improvement project). Furthermore, portions of the runway do not meet the transverse grading requirements per FAA, as the existing grades are 0.7 percent to 2.0 percent; therefore, it is recommended these areas be graded to meet FAA design criteria.

Runway Object Free Area (ROFA) – The ROFA is a rectangular area bordering a runway intended to provide enhanced safety for aircraft operations by ensuring the area remains clear of parked aircraft or other equipment not required to support air navigation or the ground maneuvering of aircraft. The ROFA design standard for Group III and Group IV runways is 800 feet wide, centered about the runway centerline, and extends 1,000 feet beyond each runway end. At present, both ORF runways fail to adhere to the prescribed ROFA geometry. The ROFA for Runway 5/23 varies between 750 and 800 feet. This noncompliance is a result of the glideslope shelter and antenna located within the Object Free Area. The ROFA for Runway 14/32 varies between 540 and 800 feet as a result of a public road and airport access road within the OFA. To ensure these areas are free of potentially hazardous objects non-essential to air navigation or aircraft ground movements, the Airport will work towards mitigating these issues as a first priority, with a Modification of Standards (MOS) being a secondary option.

Runway Object Free Zone (ROFZ) – The ROFZ is a volume of airspace centered above the runway that is required to be clear of all objects, except for frangible navigational aids that need to be in the ROFZ because of their function. The ROFZ provides clearance protection for aircraft landing or taking off from the runway. The ROFZ is the airspace above a surface whose elevation at any point is the same as the elevation of the nearest point on the runway centerline. The ROFZ extends 200 feet beyond each end of the runway, and its width is based on visibility minimums and aircraft size. The ROFZ width for Runways 14/32 and 5/23 is each 400 feet, meeting FAA standards.

The inner-approach OFZ is a volume of airspace and is centered on the approach area that applies only to runway ends equipped with approach lighting systems. At ORF, the inner-approach OFZ applies to Runways 5 and 23. The inner-approach OFZ begins 200 feet from the runway threshold at the same elevation as the runway threshold and extends 200 feet beyond the last unit in the approach lighting system. It has the same width as the Runway OFZ and rises at a slope of 50:1 away from the runway end. It should be noted that the OFZ is penetrated by some trees, as well as by light poles and signs along Miller Store Road and utility poles along Hwy 60 (Shore Drive).

Runway Protection Zone (RPZ) – The RPZ is a trapezoidal area located 200 feet beyond the runway end and centered on the extended runway centerline. The RPZ is primarily a land use control that is meant to enhance the protection of people and property near the airport through airport control. Such control includes clearing of RPZ areas of incompatible objects and activities. Currently, land owned and maintained by the NAA within all four RPZs at ORF comply with FAA design standards; however, there are uncontrolled areas within the RPZ's for Runway 5, Runway 23, and Runway 14 that still have non-compatible land uses within the RPZ (i.e., uncontrolled private/public property, structures, etc.). These properties are currently not owned or controlled by the Authority. It is recommended that the Airport continue to acquire the land within the RPZ's, at minimum for Runways 5 and 23, to maintain operational safety of the airfield and to be in compliance with FAA guidance on RPZ land use compatibility.

Runway Blast Pads - Similar to runway shoulders, blast pads are intended to provide erosion protection at the runway end. Conformance to FAA design criteria requires that 200-foot wide x 200-foot length blast pads be placed symmetrically at the end of each Group IV runway. At present, Runway 5/23 falls short of the design standards for Group IV runways. The blast pad

prior to both ends is approximately 200 feet in length but 150 feet in width, thereby not meeting the 200-foot requirement. Design efforts are currently underway to bring the blast pads up to FAA standards, with construction being initiated in PAL 1.

Building Restriction Line (BRL) – Though not a specific FAA design standard, the BRL is a reference line which provides generalized guidance on building location and height restrictions. The BRL is typically established with consideration to OFAs and RPZs as well airspace protection by identifying areas of allowable building heights such as 35 feet above ground level. It should be noted that site-specific terrain considerations (i.e. grade/elevation changes) may allow buildings taller than indicated by the generalized BRL to be developed within the limits of the BRL. These height restrictions are based on FAR Part 77 standards and were evaluated for each specific site development plan.

**Table 4-12** and **Figure 4-3** identify the existing conditions at ORF and the geometric requirements of the above standards relative to ARC C-III through D-IV. In addition to the runway design standards evaluated for deficiencies in this Study, an evaluation was conducted in a separate study, *Runway Pavement Rehabilitation and Lighting Improvements – Preliminary Design Report*, released in February of 2018. This study assessed both runways at the Airport for pavement conditions, grading, line of sight, markings, and other potential deficiencies. A summary of the pavement and non-standard conditions assessed in the Study can be found in **Table 4-13**. The following deficits are identified above:

- Runway 5/23
  - Existing paved shoulders do not meet requirements of 25 feet
  - RSA containing a drainage structure and locations with grading steeper than what is allowable
  - ROFA contains non-frangible glideslope shelter and antenna structure
  - Blast pad width is below the requirement of 200 feet
- Runway 14/32
  - Contains turf shoulders; paved shoulders are recommended by the FAA
  - Public road and service road are located within the ROFA

Non-standard conditions associated with Runway 5/23 are currently being addressed in the Runway 5/23 Standardization Report. Additional runway deficiencies were addressed during the development of recommended runway alternatives, as necessary, and will be further addressed through future projects at the Airport.

## Table 4-12 – FAA Runway Design Standards

| Design Standard | Existing Conditions | | Runway Design Code (RDC) (w/visibility minimums ≥ ½-mile ) | |
|---|---|---|---|---|
| | 14/32 | 5/23 | C-III | D-IV |
| | C-III (1 mi.) | D-IV (1/2 mi.) | | |
| Runway Width | 150’ | 150' | 150’ | |
| RSA Width | 500’ | 350' to 500' | 500’ | |
| RSA Length Past RW End | 1,000' / 0' | 1,000’ / 1,000’ | 1,000’ | |
| ROFA Width | 540' to 800' | 750' to 800’ | 800’ | |
| ROFA Length Past RW End | 1,000’ / 0' | 1,000’ / 1,000’ | 1,000’ | |
| Runway OFZ Width | 400’ | 400’ | 400’ | |
| **Separation Between:** | | | | |
| Runway Centerline to Parallel Taxiway Centerline | 400' | 400' to 600' | 400’ | |
| Runway Centerline to Edge of Aircraft Parking | 515’ to 590’ | 660’ | 500’ | |
| Runway Centerline to Hold line | 250’ | 250’ | 250’ | |
| **Runway Protection Zone (RPZ):** | | | | |
| Length | 1,700’ | 2,500’ | 1,700' | 2,500' |
| Inner Width | 500' | 1,000’ | 500' | 1,000’ |
| Outer Width | 1,010' | 1,750’ | 1,010' | 1,750' |

Source: FAA AC 150/5300-13A, NAA, CHA, 2018.

## Table 4-13 – Runway Pavement and Non-Standard Conditions

| Runway | Runway 5/23 | | | Runway 14/32 |
|---|---|---|---|---|
| Surface ID | 5 End | 5/23 Center | 23 End | |
| **Surface Type** | PCC | Asphalt | PCC | Asphalt |
| **Last Major Rehabilitation** | 38 Years | 18 Years | 46 Years | 28 Years |
| **Geometric Evaluation** | | | | |
| Shoulders | No | N/A | No | N/A |
| Blast Pads | No | N/A | No | No |
| Profile Slope and Curve of First 1/4 | No | N/A | No | Yes |
| Profile Slope and Curve of Middle 1/2 | N/A | Yes | N/A | Yes |
| Line of Sight | Yes | Yes / No | Yes | Yes |
| Transverse Grades | No | No | No | No |
| Runway Markings | Threshold/Arrows | Yes | Blastpad | Centerline |
| Taxiway Lead-on/Lead-off Markings | No | No | No | No |
| **Surface Evaluation** | | | | |
| Boeing Bump Index (BBI) | Acceptable | Acceptable / Acceptable | Acceptable | N/A |
| Aircraft Simulation (CPRMS) | Advisory | Advisory | Advisory | N/A |
| Groove Condition - Keel | Acceptable | Acceptable | Acceptable | N/A |
| Groove Condition - Outside Keel | Acceptable | Acceptable | Acceptable | N/A |
| Severe Distress | ASR | Cracking | Step Faulting | Yes |
| | Patching | Shoving | Cracking | Cracking |
| | | | | Exposed Aggregate |
| **Non-Destructive Testing (NFT)** | | | | |
| Load Transfer (Concrete) | Good | N/A | Poor | N/A |
| ACN/PCN Ratio | > 1.0 | < 1.0 | < 1.0 | < 1.0 |

| COLOR KEY | |
|---|---|
| Compliant | Not Applicable |
| Nearing Non-Compliance/Needing Addressed | Not Compliant |

Source: Kimley Horn and Associates, 2018.

Airport Access Road Impeding ROFA

Drainage Structures Impeding RSA

Widen Blast Pad to 200'

Taxiway 'C' Fillets Do Not Meet Standards

Add 25' Paved Shoulders to All Runways

Access Road Impedes ROFA and Taxiway Centerline Separation

Widen Blast Pad to 200'

ILS Critical Area

AWOS Critical Area

ILS Critical Area

Glideslope Antenna Impeding ROFA

Add Paved Shoulders to All Taxiways

Access Road Impedes ROFA

Access Road Impedes Taxiway OFA

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 400 800

## LEGEND

- Proposed Runway Shoulder
- Proposed Taxiway Shoulder
- AWOS Critical Area
- NAVAID Critical Areas
- RPZ — Runway Protection Zone (RPZ)
- RSA — Runway Safety Area (RSA)
- ROFA — Runway Object Free Area (ROFA)
- Runway Obstacle Free Zone (ROFZ)
- Precision Obstacle Free Zone (POFZ)
- BRL — 35' Building Restriction Line (BRL)
- Runway Visibility Zone (RVZ)
- TSA — Ex. Taxiway Safety Area (TSA)
- TOFA — Ex. Taxiway Obstacle Free Area (TOFA)
- Ex. Airport Property Line

**Figure 4-3**
Design Standard Deficiencies

***Runway Length***

To ensure that ORF can support existing and anticipated aircraft and airline operational demands, a detailed runway length analysis was performed based on specific aircraft performance characteristics as documented in the manufacturer's Aircraft Planning Manuals (APMs). Inadequate runway length can limit the operational capability of an airport, including the aircraft types that can operate and the destinations that the airport serves. Runway lengths can place restrictions on the allowable takeoff weight of the aircraft, which then reduces the amount of fuel, passengers, or cargo that can be carried. Per the guidance provided in AC 150/5325-4B, *Runway Length Requirements for Airport Design*, the following factors were used in the runway length calculations for ORF:

Aircraft Specifics

- Model and Engine Type – the aircraft version and engine type. The most common and demanding aircraft specific to ORF were used.
- Payload – represents the carrying capacity of the aircraft, including passengers, baggage, and cargo. For this analysis, both 90 percent and 100 percent were chosen as the payload for planning purposes.[22]
- Estimated Takeoff Weight – the estimated weight at takeoff, which includes the payload and the fuel required to reach the intended destination (with reserve fuel). The estimated takeoff weight varies by aircraft, payload, and destination.
- Estimated Landing Weight – the estimated weight at landing. For this analysis, maximum landing weight (MLW) was used to determine runway landing requirements.

Airport Specifics

- Temperature – the atmospheric temperature at the airport. Warmer air requires longer runway lengths because the air is less dense, thus generating less lift on the aircraft. The average temperature (87°F) of the hottest month (July) at ORF was used in the calculations.
- Elevation – the elevation above sea level at the airport. As elevation increases, air density decreases, making takeoffs longer and landings faster. The elevation at ORF is established at 27 feet mean sea level (MSL).
- Runway Gradient – the average slope of the runway, expressed as a percentage. The runway gradients at ORF are not significant enough to impact runway length requirements.
- Stage Length (flight distance) – the length in nautical miles (nm) to the intended destination. The stage length determines the amount of fuel an aircraft will require on takeoff to complete its flight, thus impacting aircraft weight and runway length requirements.

[22] It should be noted that fuel burn was not accounted for within the evaluations; therefore, the calculations presented herein would need reassessed to include fuel burn prior to any runway reconstruction.

- No obstacles impacting departure climb were not included, since this factor is not accounted for in the APMs.

Existing Aircraft and Destinations

In order to determine stage lengths for each aircraft, a destination from ORF had to be analyzed for its distance. Unique destinations were used for each aircraft, based on both existing routes and aircraft used, as well as potential routes noted in the air service forecast and potential aircraft in the fleet mix forecast, both found in **Chapter 3 Sections 3.5.1** and **3.5.3**, respectively. The stage length destinations evaluated were McCarran International Airport (LAS), Los Angeles International Airport (LAX), San Francisco International Airport (SFO), Fort Lauderdale-Hollywood International Airport (FLL), San Diego International Airport (SAN), and Louisville International Airport (SDF). These length requirements at ORF can be accommodated by Runway 5/23; therefore, the runway system at ORF is considered adequate to accommodate the current traffic. Required landing length was also evaluated and found to be adequate.

**Table 4-14 – Existing Takeoff (TO) Length Requirements (90% Payload)**

| Aircraft Model | Payload | Destination | Stage Length (nm) | Estimated Takeoff Weight (lb) | Landing Length Req. (ft) | | Takeoff Length at MTOW (ft.) | Takeoff Length to Destination (ft.) |
|---|---|---|---|---|---|---|---|---|
| | | | | | Dry Conditions | Wet Conditions | | |
| Airbus A320-200 | 90% | LAS | 1,872 | 152,755 | 4,500 | 5,175 | 7,000 | 5,250 |
| | | LAX | 2,061 | 154,985 | 4,250 | 4,890 | 7,000 | 5,500 |
| | | SFO | 2,189 | 156,495 | 4,250 | 4,890 | 7,000 | 5,500 |
| Airbus A321 | | FLL | 679 | 160,478 | 4,750 | 5,465 | 7,150 | 4,500 |
| Boeing 737-800 | | SAN | 2,025 | 150,560 | 5,250 | 6,040 | 8,250 | 6,250 |
| Boeing 737-900 | | SAN | 2,025 | 150,560 | 5,500 | 6,325 | 8,250 | 7,500 |
| Boeing 767-300ER | | SDF | 461 | 295,996 | 5,250 | 5,750 | 10,500 | 4,725 |

Note: Runway lengths were calculated at 59° F – Standard Day + 27° F at sea level. Fuel burn was not accounted for within the evaluations.

Source: Aircraft Planning Manuals[23], AC 150/5325-4B, CHA, 2018.

**Table 4-15 – Existing Takeoff (TO) Length Requirements (100% Payload)**

| Aircraft Model | Payload | Destination | Stage Length (nm) | Estimated Takeoff Weight (lb) | Landing Length Req. (ft) | | Takeoff Length at MTOW (ft.) | Takeoff Length to Destination (ft.) |
|---|---|---|---|---|---|---|---|---|
| | | | | | Dry Conditions | Wet Conditions | | |
| Airbus A320-200 | 100% | LAS | 1,872 | 156,841 | 4,750 | 5,465 | 7,000 | 5,750 |
| | | LAX | 2,061 | 154,985 | 4,250 | 4,890 | 7,000 | 5,500 |
| | | SFO | 2,189 | 156,495 | 4,250 | 4,890 | 7,000 | 5,500 |
| Airbus A321 | | FLL | 679 | 164,156 | 4,750 | 5,465 | 7,150 | 5,000 |
| Boeing 737-800 | | SAN | 2,025 | 155,260 | 5,500 | 6,325 | 8,250 | 6,250 |
| Boeing 737-900 | | SAN | 2,025 | 155,260 | 5,650 | 6,500 | 8,250 | 7,500 |
| Boeing 767-300ER | | SDF | 461 | 305,652 | 5,300 | 6,250 | 10,500 | 4,750 |

Note: Runway lengths were calculated at 59° F – Standard Day + 27° F at sea level. Fuel burn was not accounted for within the evaluations.

Source: Aircraft Planning Manuals, AC 150/5325-4B, CHA, 2018.

[23] Aircraft Planning Manuals used in the runway length analyses included: Airbus A320 Aircraft Characteristics Airport and Maintenance Planning (Jun 01/12), Airbus A321 Airplane Characteristics for Airport Planning (Jun 01/12), Boeing B737 Airplane Characteristics for Airport Planning (September 2013), Boeing B767 Airplane Characteristics for Airport Planning (September 2005).

### 4.3.2 Airfield Lighting and Navigational Systems

***Airfield Lighting and Marking***

Airfield lighting allows for the safe operation of aircraft during nighttime hours and low visibility conditions. Lighting on the airfield includes runway and taxiway edge lighting, runway centerline lighting, Precision Approach Path Indicator (PAPI) lights, Runway End Identifier Lights (REILs), runway threshold lighting, runway guard lights, runway touchdown zone lighting (TDZL), apron lighting, and the marker beacon.

Runway and Taxiway Edge Lighting

Runway 5/23 is equipped with a High-Intensity Runway Light (HIRL) system, while Runway 14/32 is equipped with a Medium-Intensity Runway Light (MIRL) system. Furthermore, all the Airport's taxiways are equipped with Medium-Intensity Taxiway Lighting (MITL) systems. The systems are up-to-date and meet FAA standards.

Runway Centerline Lighting

Runway 5/23 is the only runway at ORF with centerline lighting; however, the runway centerline lights within the displaced area of Runway 5 are non-compliant with FAA standards, which are addressed later in this section (see Navigational and Landing Air Requirements).

PAPIs

A PAPI system is located at the end of each runway at ORF. Runways 5 and 23 are each equipped with a four-light unit (PAPI-4), whereas Runways 4 and 32 are each equipped with a two-light unit (PAPI-2). All systems meet FAA guidelines.

REILs

At ORF, REILs are positioned at each end of Runway 14/32 to provide rapid and positive identification of the end of the runway. Runway 5/23 does not require REILs, as it is equipped with approach lighting systems.

Threshold Lighting

At ORF, Runways 23 and 32 have standard runway threshold lighting. Runway 5 has a 1,000-foot displaced threshold, and Runway 14 has a 575-foot displaced threshold; therefore, they utilize the displaced threshold lighting system.

Runway Guard Lights

Runway guard lights, also known as wigwags, are not required but, when used, are located on each side of a taxiway and in conjunction with the runway holding position marking. Runway guard lights are not currently utilized at ORF.

Touchdown Zone Lighting

The TDZLs indicate the touchdown zone when landing under adverse visibility conditions. All the runways at ORF have touchdown point markings; however, none of the runways have TDZLs.

Rotating Beacon

The rotating beacon at ORF is located south of the airfield on the south side of Miller Store Road, near the GA facilities and the airfield maintenance facilities. It functions as the indicator for locating the Airport at night and meets FAA standards.

Apron Lighting

Apron floodlight systems illuminate the terminal apron, the general aviation apron, and the air cargo apron.

Based on the above findings, airfield lighting systsems at ORF are adequate.

***Navigational and Landing Aid Requirements***

Pilots utilize a variety of navigational aids (NAVAIDs) and instrument procedures, including Very High Frequency (VHF) Omni Direction Range (VORs), instrument approach procedures (IAPs) and NAVAIDs, and approach lighting systems (ALS). By providing point-to-point guidance information or position data, NAVAIDs assist pilots to safely and efficiently locate airports, land aircraft, taxi aircraft, and depart from airports during nearly all meteorological conditions.

En-route NAVAIDs

At ORF, Runway 14 and Runway 32 utilize VOR/DME (very high frequency omni-direction range and distance measuring equipment) systems for a published instrument approach, which are a ground-based en-route NAVAID. The VOR/DME systems are owed by the FAA and are included on the FAA VOR Minimum Operating Networks Program's retention list. Runway 5/23 does not require a VOR procedure, as both ILS and RNAV procedures are available to both runway ends. The ILS systems at ORF are also owned and operated by the FAA.

Instrument Approach Procedures and NAVAIDs

At ORF, none of the runways operate strictly as a visual approach category. All of ORF's runways have a non-precision approach (NPA) or a precision approach. Also, all runways at ORF utilize Global Positioning System (GPS) based technology. In addition to the previously described approaches, Runways 5 and 23 also have precision approaches that include an ILS. Instrument approach procedures for each runway are presented in **Table 4-16**. It should be noted that Runway 14/32 does not have vertical guidance.

**Table 4-16 – NAVAIDs**

| Runway | Navigational Aids | Instrument Approach Types | Minimum Ceiling (AGL)/ Visibility |
|---|---|---|---|
| 5 | ILS/DME, RNP, GPS | ILS or LOC, RNAV (RNP), RNAV (GPS) | 200 ft. / ½ mile |
| 23 | ILS/DME, RNP, GPS | ILS or LOC, RNAV (RNP), RNAV (GPS) | 200 ft. / ½ mile |
| 14 | GPS, VOR/DME | RNAV (GPS), VOR/DME | 500 / 1 mile |
| 32 | GPS, VOR/DME | RNAV (GPS), VOR/DME | 500 / 1 mile |

Source: FAA Airport Master Record (Form 5010), Accessed 2018, CHA, 2018.

Instrument Approach Lighting Systems

As previously mentioned, the Airport operates an ILS for approaches to Runway 5 and Runway 23, which each consist of a localizer (LOC), a glide slope (GS), and the approach lighting system (ALS).

A Medium Intensity Approach Lighting Systems (MALS), along with Runway Alignment Indicator Lights (RAILS), together form Medium Intensity Approach Lighting Systems with Runway Alignment Indicator Lights (MALSR) that are utilized for Runway 5 and Runway 23 at ORF.

The runway centerline lights within the displaced area of Runway 5 are non-compliant with two conditions set-forth in AC 150/5340-30H, *Design and Installation Details for Airport Visual Aids*. According to regulations and standards set forth in paragraph 3.3 (a), for threshold displacements

over 700 feet, the centerline lights in the displaced area are to be circuited separately from the centerline lights in the non-displaced runway area and the MALSR lights are to interlock with the runway centerline on the displaced area to ensure that when the approach lights are "on," the displaced area centerline lights are "off," and vice versa. In 2010, as a result of Runway 5 being non-compliant with both the previously mentioned standards, the Norfolk Airport Authority submitted a request to the FAA Washington Airports District Office (WAS-ADO) to re-approve and extend the time of an existing Modification of Standards (MOS) to continue the use of the existing configuration of the runway centerline lights within the displaced area of Runway 5 at ORF. The FAA approved the MOS under the condition that the non-standard conditions will be eliminated when the existing MALSR is replaced with a High Intensity ALS with Sequenced Flashers (ALSF-II) system.

Based on the findings above, the NAVAIDs and landing aids at ORF are adequate.

***NextGen***

The FAA's Next Generation Air Transportation System (NextGen) is an ongoing and comprehensive transformation of the current National Airspace System. The conversion to NextGen includes a complete overhaul of current and outdated ground-based technology systems associated with air traffic control and navigation technology in an effort to integrate new satellite-based technologies and enhance the airspace system across multiple fronts. The NextGen system will also update and enhance GPS technology (e.g., existing GPS IAPs at ORF), reduce congestion, increase airspace capacity, minimize (or reduce) delays, reduce fuel consumption, and increase the operational safety of flight.

### 4.3.3 Taxiway Requirements

The overall goal of airfield planning and design is to enhance efficiency and the margin of safety for operational activities. After reviewing FAA guidance, as well as after discussions with the airport operations and air traffic control personnel, the following specific goals were identified for the taxiway system at ORF:

- Accommodate all existing and projected users
  - The existing and forecasted fleet mix (for commercial, cargo, and general aviation activity) should be considered when evaluating the taxiway system
- Reduce runway crossings
  - The opportunity for runway incursions can be reduced by minimizing the number of runway crossings on the primary runway
- Reduce risk of pilot confusion
  - Complexity of the taxiway system can lead to pilot confusion, which can lead to human error and the increased potential for runway incursions. Reducing the risk for pilot confusion includes:
    - Reducing the number of taxiways intersecting at a single location
    - Increasing the pilot's situational awareness (through proper signage and marking)
    - Avoiding wide expanses of pavement
    - Removing "hot spots"

- Increasing visibility

✈ Allow for expandability of all Airport facilities
  - The taxiway system should be designed to enable the long-term expansion of other aviation facilities and the ability to provide efficient airside access to developable parcels of the airport.

✈ Adhere to all FAA design standards (based on ADG and TDG).
  - Taxiways should be developed to the appropriate FAA standards associated with the ADG and TDG of the design aircraft

Many of these objectives are addressed in the development concepts of the Master Plan. The design standards are addressed below.

***Taxiway Design Standards***

Similar to runways, taxiways are subject to FAA design requirements such as pavement width, edge safety margins, shoulder width, and safety and object free area dimensions. The FAA standards in relation to taxiways (as defined in AC 150/5300-13A, *Airport Design*) are described below.

**Table 4-17 – Taxiway Design Standards based on Airplane Design Group (ADG)**

| Design Standard | ADG | | |
|---|---|---|---|
| | III | IV | V |
| **Protection Standards** | | | |
| Taxiway Safety Area (TSA) Width | 118 feet | 171 feet | 214 feet |
| Taxiway Object Free Area (TOFA) Width | 186 feet | 259 feet | 320 feet |
| Wingtip Clearance | 34 feet | 44 feet | 53 feet |
| Paved Taxiway Shoulders | Recommended | Required | |
| **Separation Standards** | | | |
| Taxiway Centerline to Parallel Taxiway | 152 feet | 215 feet | 267 feet |
| Taxiway Centerline to Fixed or Moveable Object | 93 feet | 129.5 feet | 160 feet |

Source: FAA AC 150/5300-13A, CHA, 2018.

**Table 4-18 – Taxiway Design Standards based on Taxiway Design Group (TDG)**

| Design Standard | TDG | | |
|---|---|---|---|
| | 3 | 4 | 5 |
| **Protection Standards** | | | |
| Taxiway Width | 50 feet | | 75 feet |
| Taxiway Edge Safety Margin | 10 feet | | 15 feet |
| Taxiway Shoulder Width | 20 feet | | 30 feet |

Source: FAA AC 150/5300-13A, CHA, 2018

Taxiway Width and Shoulders –Taxiway widths and standards are based on an airport's Taxiway Design Group (TDG), which is currently a 5 for ORF and TDG 3 for Taxiway 'F'. The recommended taxiway width is 75 feet for TDG 5 and 50 feet for TDG 3 taxiways. Presently, all taxiways at ORF meet the required width standards. Similar to runways, shoulders are recommended for taxiways as well. For a TDG 5 airport, this requirement is 30 feet. Only Taxiway 'V' meets the shoulder requirements. Taxiways A and F have no shoulders, while Taxiway 'C' and 'J' shoulders are too narrow and unpaved. Like runways, the distance of taxiway centerlines from fixed and/or movable objects is also critical. Taxiways 'A', 'J', and 'F' meet this design standard, while Taxiways

'C' and 'F' do not. These are both as a result of access roads impeding the object free area, by the Runway 23 end and by the fuel farm, respectively.

Taxiway Safety Area (TSA) and Taxiway Object Free Area (TOFA) – Like runway safety area and object free area standards, for taxiways these are based on the prescribed TDG of 5 at ORF. Presently, all taxiways at the Airport follow the proper TSA dimensions. Taxiways 'A', 'J', and 'V' meet TOFA dimension standards, but 'C' and 'F' do not. These deficiencies are caused by the same access road impeding the taxiway centerline to fixed/movable object design standard. To ensure these areas are free of potentially hazardous objects non-essential to air navigation or aircraft ground movements, the access road should be realigned. To enhance safety, a Modification of Standards (MOS) is required if these objects will not be relocated outside of the OFA.

Taxiway Fillets – For taxiway turns onto runways, aprons, or additional taxiways, there are FAA design standards for the geometry of the fillets, based on the angle of the turn. Currently, only Taxiway 'C' fails to comply to these fillet dimensions. It is recommended that the additional pavement necessary to bring this fillet up to standard be applied.

The identified taxiway deficiencies can be summarized as follows:


- Paved taxiway shoulders are inadequate on Taxiways 'A', 'C', 'F', and 'J'
- Taxiway 'C' and 'F' do not meet the requirements pertaining to the distance of taxiway centerlines from fixed and/or movable objects
- Taxiways 'C' and 'F' contain portions of the paved service road within the TOFA
- Taxiway 'C' fails to comply with fillet dimensions

Taxiway deficiencies were addressed during the development of recommended taxiways alternatives, as necessary, and will be further addressed through future projects at the Airport.

### 4.3.4 Aprons

Aircraft parking aprons are intended to accommodate a variety of functions, including the loading and unloading of passengers or cargo, the refueling, servicing, maintenance, and parking of aircraft, and any movements of aircraft, vehicles, and pedestrian's necessary for such purposes. As depicted in **Figure 4-4**, there are three distinct apron types at ORF that serve various functions: terminal apron, general aviation apron, and cargo apron.

**Figure 4-4 – Apron Areas**




Source: Norfolk International Airport, CHA 2018.

***Terminal Apron***

The terminal apron is comprised of the facilities used for commercial aircraft gate parking as well as airline support and servicing operations. The terminal apron and its facilities must be able to accommodate the current and future fleet mix of commercial aircraft. Currently, most commercial aircraft operating on the terminal apron consist of Group III aircraft, followed by Group II (with occasional Group IV and Group V operations). ORF has 23 gate positions, 20 of which can accommodate up to Group III aircraft, while the remaining three accommodate Group II aircraft.[24]

The terminal apron is approximately 238,600 square yards, 100,000 square yards of which is designated for aircraft parking at the gates (41,000 square yards and 59,000 square yards for aircraft gate parking at A Concourse and B Concourse, respectively). Approximately 34,300 square yards of the apron is utilized for Remain Overnight (RON) parking, diversion parking, and/or deicing operations. The remaining 10,300 square yards consist of taxilanes and general circulation areas.

<u>Remain Overnight (RON) and Commercial Air Carrier Deicing Operations</u>

The northeast side of the terminal apron is currently reserved for remain overnight (RON) aircraft but is also utilized for other activities when needed.

[24] Since the analyses conducted herein, Gate 26 has been removed; therefore, the Airport has 22 gate positions, 20 of which can accommodate up to Group III aircraft, while the remaining two accommodate Group II aircraft. It is important to note the calculations herein were based on the initial 23 gate positions.

Typically, there are 23 RON aircraft, with 14 aircraft remaining overnight at the gates, three on the RON designated ramp, two at hard-stands on the ramp, and four at a hangar in the GA area. Assuming RON growth is commensurate with commercial operational growth (approximately 1.1 percent annually or 25.4 percent total growth by PAL 4), ORF is projected to have approximately 29 RON aircraft in PAL 4. The Airport currently has the capacity to support up to 31 RON aircraft (22 RON aircraft at the gate, as well as five on the ramp, and four in the GA area); therefore, it is projected that the Airport can adequately support future RON activity.

When RON parking positions are not in use, ORF can accommodate diverted aircraft on a case-by-case basis, as well as deicing activities. Facility requirements as they pertain to deicing operations are further analyzed in **Section 4.5.5**.

***General Aviation Parking & Apron Space***

GA activity at ORF represents approximately 30.8 percent of total annual airport operations and includes various types of private, corporate, and business aircraft flights. GA aircraft are accommodated by the Fixed Based Operator (FB0), Signature Flight Support. For this analysis, a peak month-average day (PMAD) methodology was used to gauge the approximate number of GA aircraft that park on the FBO aprons during an average day of the peak month. The following is a description of the PMAD aircraft parking evaluation shown in **Table 4-19**.

- GA Itinerant Operations – According to the ORF activity data for 2017 (described in **Section 3.8.3**), itinerant GA operations accounted for approximately 94.8 percent of total GA operations.
- GA Peak Month Itinerant Operations – After analyzing data obtained from the Air Traffic Control Tower at ORF, the month of July was determined as the peak month. In July 2017, ORF received approximately 9.9 percent of its total Itinerant GA operations.
- GA PMAD Operations – The GA peak month itinerant operations were divided by the number of days in July (31).
- GA Itinerant Arrivals – The number of PMAD operations was reduced by half to derive the approximate number of GA itinerant arrivals requiring parking.
- GA Itinerant Aircraft Parked on the Apron – According to the FBOs, GA itinerant arrivals typically remain parked on the apron for an extended period during the day; therefore, parking space should be provided for the number of aircraft anticipated to use the apron during an average day of the peak month. For the purposes of this evaluation, it was assumed that 80 percent of itinerant GA operations utilize the FBO aprons and, in turn, was used in the subsequent analysis for apron space.

**Table 4-19 – GA Itinerant Aircraft Parked on the Apron**

| Activity | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|
| GA Operations | 22,760 | 24,850 | 27,132 | 29,624 | 32,344 |
| GA Itinerant Operations | 21,583 | 23,565 | 25,729 | 28,091 | 30,670 |
| Peak Month GA Itinerant Operations | 2,146 | 2,343 | 2,559 | 2,794 | 3,050 |
| PMAD Itinerant GA Operations | 69 | 76 | 83 | 90 | 98 |
| GA Itinerant Arrivals | 35 | 38 | 41 | 45 | 49 |
| GA Itinerant Arrivals Parked on Apron | 28 | 30 | 33 | 36 | 39 |

Source: NAA, CHA, 2018.

FBO Itinerant Operations Apron

The Signature Flight Support facilities at ORF, which include hangars, a terminal building, and apron space, are situated on a 29.5-acre site located on the south side of the airfield. Signature has approximately 66,210 square yards (SY) of apron space; however, 5,670 is reserved for MRO services. Of the 66,210 SY of apron space, there is approximately 60,540 SY that can be utilized solely by general aviation operators. Approximately 14,560 SY is exclusively used for aircraft maneuvering purposes, reducing the total available GA apron parking area to approximately 45,980 SY. Signature also provides multiple tie-down spaces. As of 2017, ORF has approximately 87 based aircraft, as shown in **Table 4-20**.

**Table 4-20 – Based Aircraft (As of July 2017)**

| Fiscal Year | Single Engine | Multi-Engine Piston | Turbo-Prop | Jet | Rotorcraft | Total |
|---|---|---|---|---|---|---|
| **2017** | 46 | 10 | 9 | 20 | 2 | 87 |

Source: Signature, NAA, CHA, 2018.

Signature primarily hosts corporate jets and, on standard to busy days, has 35 to 50 itinerant aircraft, with 50 percent remaining overnight. These aircraft operations are typically comprised of the following breakdown: 52.9 percent single-engine piston, 11.5 percent multi-engine piston, 10.3 percent turboprop, 23.0 percent jet, and 2.3 percent rotorcraft.

Applying these percentages to the number of GA itinerant aircraft parked on the apron at peak periods produced the number of each type of aircraft that will need space for parking. General planning assumptions and professional experience were used to determine the following apron space requirements for the different aircraft types (which included clearance and safety areas):

- Single/Multi-Engine Piston = 400 SY per aircraft
- Turboprop = 800 SY per aircraft
- Jet = 1,600 SY per aircraft
- Rotorcraft = 300 SY per aircraft

As discussed in **Chapter 3**, with anticipated growth in GA, there will be a likelihood of an increased numbers of transient aircraft to require short-term storage space at ORF. Anticipated and recommended apron space is presented in **Table 4-21**.

**Table 4-21– Anticipated Apron Space**

| Activity | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|
| Annual Operations | **22,760** | **24,850** | **27,132** | **29,624** | **32,344** |
| Total Apron Space Parking Requirements (SY) | 21,486 | 23,459 | 25,613 | 27,966 | 30,534 |
| Apron Space Available for Parking (SY) | 19,618 | 19,618 | 19,618 | 19,618 | 19,618 |
| **Surplus/(Deficit)** | **(1,868)** | **(3,841)** | **(5,995)** | **(8,348)** | **(10,916)** |

Source: AC 150/5300-13A: Appendix 5, CHA, 2018.

FBO Facilities Apron Storage Summary

According to the ORF activity data for 2017, and as previously discussed, itinerant GA operations accounted for approximately 94.8 percent of total GA operations at the Airport. Many of these operations utilized itinerant parking aprons and tie-down areas, as well as hangar space in the GA area. Itinerant aprons are typically utilized for transient aircraft that are only visiting or

remaining at the airport for a short period of time (i.e., a few hours to overnight). Should an aircraft be at the airport for longer, tie-down parking is typically used to clear the itinerant apron for additional aircraft.

Given the transient nature of the small jets in the forecast period, it is important to note that most of these aircraft will likely utilize itinerant parking aprons, tie-down areas, and apron storage space, opposed to hangar space. Aircraft aprons provide parking and tie-down positions for based and itinerant aircraft, as well as staging areas for aircraft stored in conventional hangars; however, hangar space is typically reserved for aircraft based at the FBO.

In the GA area, there is a large apron area that can provide up to 36 asphalt tie-down positions (depending on aircraft size). These tie-down spaces predominately serve Group I aircraft. Tie-down space requirements differ from itinerant apron parking space due to the clearance requirements per FAA AC 150/5300-13A, *Airport Design*. Essentially, aircraft parked in tie-down spaces must be provided adequate clearance from wing-tip to wing-tip (a minimum of 10 feet) but may park up-to the Object Free Area (OFA) of adjacent movement areas.

Given that the FBO has a limited, fixed number of tie-down points, these aircraft parking spaces are typically reserved for local aircraft with contract leases for those locations; however, apron parking is available. Signature provides both T-hangars and bulk hangar space at a daily rate for itinerant aircraft. In addition to tie-down parking, Signature typically offers hangar storage for itinerant users, should they not want the aircraft parked outside in less than optimal conditions.

As previously mentioned, there are approximately 36 apron tie-downs on the FBO's aprons; however, according to the FBO only eight tie-downs are currently under a lease contract, which leaves up to 28 available tie-downs. If additional tie-down spaces on the itinerant apron are leased, more space will be required to accommodate itinerant aircraft parking at the FBO. A breakdown of aircraft by type leasing tie-down spaces is presented in **Table 4-22**, while available apron and tie-down space is presented in **Table 4-23**.

**Table 4-22 – Based Aircraft Leasing Tie-Down Spaces (As of July 2018)**

| Aircraft Type | Tie Down |
|---|---|
| Single Engine Piston | 6 |
| Multi Engine Piston | - |
| Single Engine Turbo Prop | 0 |
| Multi Engine Turbo Prop | 2 |
| Multi Engine Jet | - |
| HELO Jet | - |
| **TOTAL:** | **8** |

Source: Signature, NAA, CHA, 2018.

**Table 4-23 – Apron and Tie-Down Space**

| Tie-Downs | Surface Type | Approximate Size per Tie-Down |
|---|---|---|
| Up to 36 | Asphalt | 443 SY |

Source: CHA, 2018.

The FBO does not anticipate the number of lease contracts for tie-downs increasing; therefore, for the purposes of this Study, it was determined that ORF has a sufficient number of tie-down spaces to accommodate future based and itinerant aircraft. As previously discussed, if additional

spaces on the itinerant apron are leased, additional parking will be needed to accommodate the loss of itinerant parking; however, it is not anticipated that additional apron parking will be needed.

MRO Aprons

Activity is also associated with one maintenance, repair, and overhaul (MRO) facility, which is subleased to PSA Airlines. In addition to the GA aprons utilized by the FBO tenants, this Study also identified apron requirements for the MRO through interviews. Although its needs were included in the GA itinerant apron requirements, they were included in the overall study. The service apron dedicated to MRO activities measures approximately 5,670 SY and accommodates parked aircraft adjacent to the hangar facility. Based on interviews with the FBO, the apron space dedicated for MRO activities is sufficient for current and future activities.

***Cargo Apron***

In addition to the GA aprons utilized by the FBO tenant (Signature) and the aprons utilized by the MRO tenant (PSA Airlines), this Study identified apron requirements for the major air cargo operators at ORF. The cargo airlines that have regular operation at ORF include: Federal Express (FedEx), Mountain Air Cargo (MAC), and United Parcel Service (UPS). MAC is a contract carrier for FedEx.

The dedicated air cargo area is on the west side of the airfield, south of the terminal. The cargo apron measures approximately 26,430 square yards; however, only 23,050 SY are utilized for aircraft parking. The remaining apron space is used for equipment storage and parking. Annual cargo operations, cargo fleet mix, and peak month average day departures were analyzed to determine if the current cargo apron can support future growth. Based on the cargo forecast identified in **Chapter 3**, **Table 4-24** shows the growth in cargo operations for the forecast period.

**Table 4-24 – All-Cargo Annual Operations Forecast (Square Yards)**

| Operator | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| Integrator | 2,266 | 2,309 | 2,536 | 2,786 | 3,061 | 3,362 |
| Other All-Cargo | 163 | 166 | 182 | 200 | 220 | 242 |
| **Total Operations** | **2,429** | **2,475** | **2,719** | **2,987** | **3,281** | **3,604** |

Note: Excludes Belly Cargo.
Source: NAA, CHA, 2018.

Cargo operations occurring in the month of December were utilized for 2017 because December was the Airport's peak month in 2017 regarding cargo operations, with approximately 196 operations. Based on the information provided in **Table 4-25**, and conversations with cargo representatives and the NAA, the cargo facilities are currently operating at capacity with all four of the current cargo parking positions currently occupied (see base year). The current cargo fleet mix (A300 and B757) requires that aircraft park at angles adjacent to the cargo building to create space for cargo operations associated with unloading and loading of cargo tonnage and not impact the TOFA of Taxiway V. This is expected to continue as the fleet mix continues to increase in size, requiring angled parking. The Airport is expected to need one additional cargo aircraft parking position by PAL 1, with an additional parking space needed in each PAL to follow for the remainder of the forecast period.

**Table 4-25 – PMAD Cargo Operations**

| Activity | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| Annual Operations | 2,429 | 2,475 | 2,719 | 2,987 | 3,281 | 3,604 |
| Annual Departures | 1,215 | 1,238 | 1,359 | 1,493 | 1,640 | 1,802 |
| PMAD Departures | 3 | 4 | 5 | 6 | 7 | 8 |

Source: NAA, CHA, 2018.

The apron footprint, or the area of space the aircraft occupies, for the cargo fleet mix operating from ORF was calculated by multiplying the aircraft wingspan by the length of the aircraft. To determine the apron requirement, an aircraft safety area of 25 feet was added to the wingspan and to the length prior to calculating area with adjacent area for the operation of ground support equipment associated with loading and unloading the aircraft. The apron requirements for the cargo fleet mix at ORF are show in **Table 4-26**.

**Table 4-26 – Cargo Fleet Mix Apron Sizing**

| Aircraft Type | Wingspan (Ft.) | Length (Ft.) | Footprint (SF) | Apron Requirement (SF) | Apron Requirement (SY) |
|---|---|---|---|---|---|
| **Current Aircraft** | | | | | |
| Airbus A300 | 147.10 | 177.40 | 26,096 | 44,823 | 4,980 |
| Boeing 757 | 124.8 | 155.3 | 19,380 | 35,890 | 3,987 |
| Cessna 208 Caravan | 52.1 | 41.66 | 2,170 | 5,881 | 653 |
| **Future Cargo Aircraft at ORF** | | | | | |
| Boeing 767-300 | 156.08 | 177.43 | 27,693 | 47,439 | 5,271 |
| ATR 72 | 88.9 | 89.1 | 7,923 | 14,147 | 1,572 |

Note: During the forecast horizon, it is expected that A300 and Cessna 208 Caravans will cease cargo operations at ORF. The A600 is expected to continue operations.
Source: NAA, CHA, 2018.

Total apron space, as shown in **Table 4-27**, was determined by taking the apron requirement of the most demanding cargo aircraft utilizing the air cargo-dedicated apron and multiplying it by the PMAD departures. Currently, the A300 is the most demanding cargo aircraft; however, for this analysis, the B767-300 aircraft was assumed to be the most demanding cargo aircraft as it is the projected future design aircraft and most demanding.

**Table 4-27 – PMAD Air Cargo Apron Space**

| Activity | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| B767-300 Apron Requirement (SY) | 5,300 | 5,300 | 5,300 | 5,300 | 5,300 | 5,300 |
| PMAD Departures | 3 | 4 | 5 | 6 | 7 | 8 |
| PMAD Aprons Space Requirement (SY) | 15,900 | 21,200 | 26,500 | 31,800 | 37,100 | 42,400 |
| Supply | 23,050 | 23,050 | 23,050 | 23,050 | 23,050 | 23,050 |
| **Surplus/(Deficit)** | **7,150** | **1,850** | **(3,450)** | **(8,750)** | **(14,050)** | **(19,350)** |

Source: NAA, CHA, 2018.

Upon evaluation, the cargo apron has capacity in the base year of approximately 1,850 SY, increasing to a deficit of approximately 19,350 SY by PAL 4; however, this may be relatively misleading. As the required apron space in SY required for one additional aircraft is 5,300 SY, the cargo facilities are operating at capacity in the base year. As such, it is recommended that the Airport expand the cargo facilities in the short-term to accommodate operational demand at the cargo facility. Options for apron expansion, as well as the feasibility of expansion, are further evaluated in **Chapter 5**.

Belly cargo operations carried out by the airlines are handled at a cargo building located outside the air cargo area. The belly cargo area does not have a designated apron area. As such, in the future, the Airport should consider the addition of a belly cargo facility located within the cargo operations area of the Airport.

## 4.4 PASSENGER TERMINAL FACILITY BUILDING AND GATE REQUIREMENTS

Based upon the activity forecasts indicated in **Chapter 3** and correlated to Planning Activity Levels (PALs) indicated in **Table 4-1**, programmatic terminal requirements were determined to accommodate the growing passenger activity and trends at ORF. Specific facility demands, quantified by area square footages and amounts for various components of the terminal, were generated by applying FAA and International Air Transportation Association (IATA) industry standards with other supporting guidelines. Development of the program projections encompassed:

- Annual and peak hour passenger enplanement data
- Peak hour passenger deplanement data
- Peak hour deplanement
- Aircraft operations data
- Fleet mix trends

The industry standards and guidelines requirements were applied in analyses with appropriate modifications to reflect ORF airline tenant needs, passenger processor functions and passenger activities.

Comparing the programmatic spatial requirements of the "base" year (2018), and each "PAL" to the existing terminal facilities (as of 2017) described in **Chapter 3**, the recommended terminal modifications were identified to accommodate projected passenger activity levels. The forecasted passenger demand throughout the planning period shows steady increase. It is important to understand the projected enplanement growth does not predetermine equal or proportional expansion across all passenger processor areas. Decisions pertaining to expanding or decreasing space take several factors into considerations aside from enplanements, such as passengers' behaviors and industry trends. Passengers are becoming more self-reliant and are using self-service functions, such as kiosks, while airlines are transitioning their fleet to include larger aircraft.

In addition, security, passenger screening and check baggage screening requirements as administered by the federally legislated U.S. Department of Homeland Security (DHS) and most commonly known as Transportation Security Administration (TSA) at airports, will often be perceived as growing disproportionally relative to other passenger processor areas. For the purposes of determining spatial needs of the terminal areas throughout the PALs, the analyses were conducted as a "free-body-analysis." This is to say area determinations did not strongly consider the existing layout, size, and configuration as a variable in determining spatial needs; however, it should be noted that the existing terminal was built in a post-generational age before technological advancements in society, enhanced concessions and security affecting passenger

behaviors and needs. This reality needed to be addressed in the development of planned alternatives for present and future needs and improvements driven by demand.

### 4.4.1 Summary Evaluation Conclusions

As a result of the analysis, the following high-level conclusions addressed on a limited basis the significant processor areas that are either deficient or in need of change as a result of passenger safety measures, passenger activity increases, enhanced passenger experience and airport offerings, or where technology has influenced processing methodologies along with passenger behavior patterns. While the conclusions presented are limited in nature and not meant to be conclusive or all encompassing, they represent overarching concerns for ORF to consider moving forward with providing a good level of service and safety for the traveling public.

- Ticket Lobby – Passenger arrival to the terminal complex in the existing parking deck coupled with passenger flow to the ground level ticketing processor area requires redundancy in vertical circulation utilization and is not intuitive for the traveling public not familiar with the airport. Additionally, the split, or non-contiguous ticket lobbies are cumbersome for passengers that are unsure as to which airline resides in what wing of the ticket lobby. The overall "impression" of the Airport is also hampered and compounded by the dark and dated architecture and furnishing. The configurations of the existing ticket lobbies with the proportions of the areas regarding queuing and circulation and the need to locate explosion detection screening equipment in the lobby is problematic for long term operational efficiencies and flexibility.

  *Corrective actions were considered in the development of alternatives that address the deficiencies with the ticket lobby to provide enhanced passenger convenience and service, flexibility in accommodating new air service, and changing passenger behaviors.*

- Outbound Baggage/Checked and Screened Baggage Processes – ORF cannot effectively address passenger growth with the current outbound baggage processing system. The problem is evident with the location of explosion detection checked baggage screening equipment in the ticket lobby and the airline exclusive use of baggage screen arrangements in the outbound baggage area. The configurations of the existing outbound checked screened baggage system(s) without fail safe redundancy and limited physical area for a 100-percent inline check baggage screening array behind the public curtain lobby is untenable.

  *Corrective actions were considered in the development of alternatives that address a consolidated checked baggage screen system with outbound baggage make-up carousels, baggage cart storage, circulation and a configuration that is flexible, to enhance security measures and accommodate for growth and new entrant air carriers.*

- Concourse and Security Check Point Screening - Out of gauge concourses, along with trending towards a larger fleet mix and accommodating future gates, coupled with the processing of passengers through multiple security checkpoints, poses challenges in regard to meeting air service demands. The existing concourses were originally designed

to accommodate a smaller fleet mix than the current conditions and the forecasted changes into a larger fleet mix, which exacerbated the need for the development of alternatives to consider all-inclusive solutions to this problem. Even though the existing security screen checkpoints were enlarged and remodeled not long ago to address future incremental growth, the idea that there may be a third checkpoint and a third concourse to address larger fleet mix and gate demand dilutes any operation efficiencies over a more conventional single source checkpoint and contiguous post-security concourse(s). Adding more building area in the limited aircraft parking and operations areas with the inherent inefficiencies of multiple checkpoint and concourses will diminish the aircraft parking and pushback operations, i.e., more potential for mishap. In addition, the alternatives presented in this Study develop strategic concession (food and beverage/gift and news) offerings for planning considerations to increase revenue for the Airport and concessionaires while providing an enhanced passenger experience and convenience. Notwithstanding, improvements to the operational conditions of the existing FIS and CBP were also factor into any viable alternatives.

*Corrective actions were strongly considered in the development of alternatives that address this very fundamental issue that will very likely impact the long-term viability of the Airport in providing a sustainable good level of service into the future.*

### 4.4.2 Needs Analysis Summary

**Table 4-28** provides a summary of the needs for each of the terminal areas analyzed and evaluated. To better understand the needs presented, the table also provides references for additional information within this chapter.

**Table 4-28 – Facility Sizing Summary**

| Needs Analysis and Evaluation Summary | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **Areas** | **Section** | **Table** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| **Gate Demand Analysis** | | | | | | | | |
| Gate Forecast Demand – *No.* | 4.4.4 | 4-36 | (23) | 25 | 26 | 27 | 27 | 29 |
| Narrow-body Equivalent Gates (NBEG) – *No.* | 4.4.4 | 4-37 | (23) | 25.8 | 26.8 | 27.8 | 27.8 | 29.8 |
| Equivalent Aircraft Gates (EQA) – No. | 4.4.4 | 4-37 | (23) | 26.8 | 26.8 | 28.8 | 28.8 | 30.8 |
| **Concourse Processors** | | | | | | | | |
| NBEG Hold Room Area Evaluation - *Sq. Ft. Ea.* | 4.4.6 | 4-38 | -- | 2,444 | 2,480 | 2,508 | 2,526 | 2,561 |
| Inclusive Hold Room Space Requirement - *Sq. Ft.* | 4.4.6 | 4-39 | (35,645) | 63,055 | 66,464 | 69,722 | 70,223 | 76,218 |
| Double-loaded Concourse Circulation - *Sq. Ft.* | 4.4.7 | 4-41 | (31,419) | 55,320 | 57,280 | 59,640 | 59,640 | 63,930 |
| **Check-in Processors** | | | | | | | | |
| Check-in Processes (Ticketing) - *Sq. Ft.* | 4.4.8 | 4-46 | (18,087) | 10,872 | 10,344 | 10,934 | 10,887 | 11,616 |
| Airline Ticketing Offices (ATO) - *Sq. Ft.* | 4.4.9 | 4-47 | (7,170) | 4,200 | 4,200 | 4,200 | 4,900 | 5,600 |
| Concourse Airline Operation Areas - *Sq. Ft.* | 4.4.10 | 4-48 | (37,260) | 13,540 | 17,270 | 17,270 | 19,060 | 20,600 |
| **Passenger Security Screening Checkpoint (SSCP) Processors** | | | | | | | | |
| **Divest/Screen/Recompose Area Requirements** | | | | | | | | |
| Concourse A - Divest/Screen/Recompose - *Sq. Ft.* | 4.4.11 | 4-51 | (8,573) | 6,480 | 8,100 | 8,100 | 9,720 | 9,720 |
| Concourse B - Divest/Screen/Recompose - *Sq. Ft.* | 4.4.11 | 4-51 | (7,330) | 6,480 | 8,100 | 8,100 | 9,720 | 9,720 |
| Consolidated - Divest/Screen/Recompose - *Sq. Ft.* | 4.4.11 | 4-51 | -- | 12,960 | 14,580 | 16,200 | 17,820 | 19,440 |
| **Queuing Area Requirements** | | | | | | | | |
| Concourse A - Queuing (10 Minute Wait) - *Sq. Ft.* | 4.4.11 | 4-52 | (2,305) | 1,280 | 1,600 | 1,920 | 1,920 | 1,920 |
| Concourse B - Queuing (10 Minute Wait) - *Sq. Ft.* | 4.4.11 | 4-52 | (2,131) | 1,280 | 1,600 | 1,920 | 1,920 | 1,920 |

| Needs Analysis and Evaluation Summary | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **Areas** | **Section** | **Table** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Consolidated - Queuing (10 Minute Wait) - *Sq. Ft.* | 4.4.11 | 4-52 | -- | 2,56d0 | 2,880 | 3,200 | 3,520 | 3,840 |
| **SSCP Divest/Screen/Recompose/Queuing Combined Area Requirements** | | | | | | | | |
| Concourse A and B Combined - *Sq. Ft.* | -- | -- | (20,329) | 15,520 | 19,400 | 21,040 | 23,280 | 23,280 |
| Consolidated SSCP - *Sq. Ft.* | -- | -- | -- | 15,520 | 17,460 | 19,400 | 21,340 | 23,280 |
| **SSCP TSA/LEO Office Requirements** | | | | | | | | |
| Concourse A - *Sq. Ft.* | 4.4.11 | 4-51 | (1,318) | 465 | 582 | 582 | 698 | 698 |
| Concourse B - *Sq. Ft.* | 4.4.11 | 4-51 | (722) | 465 | 582 | 582 | 698 | 698 |
| Consolidated - *Sq. Ft.* | 4.4.11 | 4-51 | -- | 931 | 1,047 | 1,164 | 1,280 | 1,396 |
| **SSCP Exit Lane Requirements** | | | | | | | | |
| Concourse A - *Sq. Ft.* | 4.4.11 | 4-52 | (2,639) | (2,639) | (2,639) | (2,639) | (2,639) | (2,639) |
| Concourse B - *Sq. Ft.* | 4.4.11 | 4-52 | (2,422) | (2,422) | (2,422) | (2,422) | (2,422) | (2,422) |
| Consolidated - *Sq. Ft.* | 4.4.11 | 4-52 | -- | 2,600 | 2,600 | 2,600 | 2,600 | 2,600 |
| **Baggage Processors** | | | | | | | | |
| Outbound Baggage Screening (CBIS) - *Sq. Ft.* | 4.4.12 | 4-55 | (5,550) | 6,080 | 6,120 | 7,020 | 7,920 | 8,820 |
| Outbound Baggage Make-up (BHS) - *Sq. Ft.* | 4.4.12 | 4-66 | (7,578) | 23,000 | 25,000 | 26,500 | 26,500 | 28,000 |
| Total Outbound CBIS & BHS - *Sq. Ft.* | -- | -- | (13,128) | 29,080 | 29,120 | 33,520 | 34,420 | 36,820 |
| Inbound Sort Make-up and Feed - *Sq. Ft.* | 4.4.14 | -- | (39,087) | (39,087) | (39,087) | (39,087) | (39,087) | (39,087) |
| Inbound Baggage Claim Devices Required – *No.* | 4.4.13 | 4-59 | (5) | 3.08 | 3.76 | 3.84 | 3.86 | 4.60 |
| Inbound Baggage Claim Area - *Sq. Ft.* | 4.4.13 | 4-57 | (42,720) | 38,969 | 39,635 | 40,337 | 40,967 | 41,543 |
| Airline Baggage Service Offices (BSO) - *Sq. Ft.* | 4.4.15 | 4-60 | (3,633) | 2,172 | 2,172 | 2,172 | 2,534 | 2,890 |
| **U.S. Customs and Border Protection (CBP)/Federal Inspection Service (FIS) Processors** | | | | | | | | |
| Customs and Border Protection Area - *Sq. Ft.* | 4.4.16 | 4-61 | (13,722) | 16,150 | 16,150 | 16,150 | 16,150 | 16,150 |
| **Concessions** | | | | | | | | |
| **Pre-Security Concessions** | | | | | | | | |
| Food and Beverage - *Sq. Ft.* | 4.4.17 | 4-62 | (11,940) | 3,690 | 4,189 | 4,706 | 5,193 | 5,612 |
| Gift and News - *Sq. Ft.* | 4.4.17 | 4-62 | (4,440) | 1,141 | 1,295 | 1,455 | 1,605 | 1,735 |
| Services - *Sq. Ft.* | 4.4.17 | 4-62 | (2,855) | 1,879 | 2,132 | 2,396 | 2,644 | 2,858 |
| Subtotal Pre-Security Concessions- *Sq. Ft.* | 4.4.17 | 4-62 | (19,205) | 6,710 | 7,616 | 8,557 | 9,442 | 10,205 |
| **Post-Security Concessions** | | | | | | | | |
| Food and Beverage - *Sq. Ft.* | 4.4.17 | 4-62 | (8,828) | 18,250 | 20,714 | 23,276 | 25,683 | 27,756 |
| Gift and News - *Sq. Ft.* | 4.4.17 | 4-62 | (4.240) | 8,320 | 9,443 | 10,611 | 11,708 | 12,654 |
| Services - *Sq. Ft.* | 4.4.17 | 4-62 | (0) | 268 | 305 | 342 | 378 | 408 |
| Subtotal Post-Security Concessions - *Sq. Ft.* | 4.4.17 | 4-62 | (13,068) | 26,838 | 30,462 | 34,229 | 37,769 | 40,818 |
| Total Pre & Post Security Concessions - *Sq. Ft.* | -- | 4-62 | (32,273) | 33,548 | 38,078 | 42,786 | 47,211 | 51,023 |
| Concession Storage – *Sq. Ft.* | 4.4.17 | 4-62 | (2,217) | 2,470 | 2,804 | 3,151 | 3,477 | 3,758 |
| **Rental Car Concessionaires and Ground Transportation** | | | | | | | | |
| Rental Car Concessionaires - *Sq. Ft.* | 4.4.18 | 4-63 | (12,210) | 7,400 | 7,400 | 7,400 | 7,400 | 8,325 |
| Ground Transportation - *Sq. Ft.* | 4.4.18 | -- | (292) | (292) | (292) | (292) | (292) | (292) |
| **Administration Areas** | | | | | | | | |
| Airport Administration - *Sq. Ft.* | 4.4.19 | 4-64 | (33,145) | 20,715 | 24,168 | 27,620 | 29.922 | 32,224 |
| TSA Administration - *Sq. Ft.* | 4.4.19 | 4-65 | (2,828) | 2,913 | 3,000 | 3,090 | 3,183 | 3,278 |
| **Public Restroom Facilities** | | | | | | | | |
| **Airside Post-Security Public Restrooms (Two, Three and Connected Concourse Scenarios)** | | | | | | | | |
| **Two Concourse Scenario** | | | | | | | | |
| **Concourse A Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-66 | (1) | 2 | 2 | 2 | 2 | 2 |
| Total Restroom Area- *Sq. Ft.* | 4.4.20 | 4-73 | (3,745) | 3,810 | 3,980 | 4,340 | 4,340 | 4,530 |

| Needs Analysis and Evaluation Summary | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **Areas** | **Section** | **Table** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-71 | (24) | 18 | 20 | 22 | 22 | 22 |
| Total No. of Fixtures Women's | 4.4.20 | 4-71 | (22) | 24 | 24 | 26 | 26 | 28 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-73 | (105) | 210 | 210 | 210 | 210 | 210 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-73 | (156) | 312 | 312 | 312 | 312 | 312 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-73 | (46) | 42 | 44 | 48 | 48 | 50 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-73 | (4,006) | 4,322 | 4,502 | 4,862 | 4,862 | 5,025 |
| **Concourse B Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-66 | (2) | 2 | 2 | 2 | 2 | 2 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-73 | (5,718) | 3,810 | 3,980 | 4,340 | 4,340 | 4,530 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-71 | (31) | 18 | 20 | 22 | 22 | 22 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-71 | (30) | 24 | 24 | 26 | 26 | 28 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-73 | (105) | 210 | 210 | 210 | 210 | 210 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-73 | (156) | 312 | 312 | 312 | 312 | 312 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-71 | (61) | 42 | 44 | 48 | 48 | 50 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-73 | (5,979) | 4,332 | 4,502 | 4,862 | 4,862 | 5,052 |
| Total Area Concourse A & B - *Sq. Ft.* | 4.4.20 | 4-73 | (9,985) | 8,664 | 9,004 | 9,724 | 9,724 | 10,104 |
| Total Fixtures Concourse A & B – *No.* | 4.4.20 | 4-71 | (107) | 84 | 88 | 96 | 96 | 100 |
| **Three Concourse Scenario** | | | | | | | | |
| **Concourse A Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-74 | -- | 1 | 1 | 1 | 1 | 1 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,445 | 2,625 | 2,805 | 2,805 | 2,985 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-74 | -- | 12 | 13 | 14 | 14 | 15 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-74 | -- | 15 | 16 | 17 | 17 | 18 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 156 | 156 | 156 | 156 | 156 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-74 | -- | 27 | 29 | 31 | 31 | 33 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,706 | 2,886 | 3,066 | 3,066 | 3,246 |
| **Concourse B Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-74 | -- | 1 | 1 | 1 | 1 | 1 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,445 | 2,625 | 2,805 | 2,805 | 2,985 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-74 | -- | 12 | 13 | 14 | 14 | 15 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-74 | -- | 15 | 16 | 17 | 17 | 18 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial – *Sq. Ft.* | 4.4.20 | 4-75 | -- | 156 | 156 | 156 | 156 | 156 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-74 | --- | 27 | 29 | 31 | 31 | 33 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,706 | 2,886 | 3,066 | 3,066 | 3,246 |
| **Concourse C Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-74 | -- | 1 | 1 | 1 | 1 | 1 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,445 | 2,625 | 2,805 | 2,805 | 2,985 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-74 | -- | 12 | 13 | 14 | 14 | 15 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-75 | -- | 15 | 16 | 17 | 17 | 18 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial – *Sq. Ft.* | 4.4.20 | 4-75 | -- | 156 | 156 | 156 | 156 | 156 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-74 | -- | 27 | 29 | 31 | 31 | 33 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-75 | -- | 2,706 | 2,886 | 3,066 | 3,066 | 3,246 |
| Total Fixtures Concourse A, B & C – *No.* | 4.4.20 | 4-74 | -- | 81 | 87 | 93 | 93 | 99 |
| Total Area Concourse A, B & C - *Sq. Ft.* | 4.4.20 | 4-76 | -- | 8,118 | 8,658 | 9,198 | 9,198 | 9,738 |

| Needs Analysis and Evaluation Summary | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **Areas** | **Section** | **Table** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| **Connected Concourse Scenario** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-78 | -- | 3 | 4 | 4 | 4 | 4 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-77 | -- | 7,335 | 7,620 | 8,340 | 8,340 | 9,060 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | -- | -- | 36 | 39 | 42 | 42 | 45 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | - | -- | 45 | 48 | 51 | 51 | 54 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-77 | -- | 315 | 420 | 420 | 420 | 420 |
| Custodial – *Sq. Ft.* | 4.4.20 | 4-77 | -- | 468 | 624 | 624 | 624 | 624 |
| Total M & W Fixtures Connected Concourse | 4.4.20 | -- | -- | 81 | 87 | 93 | 93 | 99 |
| Total Area Connected Concourse - *Sq. Ft.* | 4.4.20 | 4-78 | -- | 8,118 | 8,664 | 9,424 | 9,424 | 10,104 |
| **Non-Secure Landside Public Restrooms (Check-in Lobby, Baggage Claim, Atrium)** | | | | | | | | |
| **Check-in Lobby Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-85 | (2) | 2 | 2 | 2 | 2 | 2 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-84 | (924) | 2,160 | 2,520 | 2,520 | 2,880 | 2,880 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-80 | (12) | 12 | 13 | 14 | 15 | 16 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-80 | (10) | 12 | 13 | 14 | 15 | 16 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-84 | -- | 210 | 210 | 210 | 210 | 210 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-84 | (400) | 312 | 312 | 312 | 312 | 312 |
| Subtotal M & W Fixtures - *No.* | 4.4.20 | 4-80 | (22) | 24 | 26 | 28 | 30 | 32 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-85 | (1,324) | 2,682 | 3,042 | 3,042 | 3,402 | 3,402 |
| **Baggage Claim Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-85 | (2) | 2 | 2 | 2 | 2 | 2 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-84 | (1,874) | 1,820 | 2,350 | 2,350 | 2,520 | 2,520 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-82 | (16) | 10 | 11 | 12 | 13 | 14 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-82 | (12) | 10 | 11 | 12 | 13 | 14 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-84 | -- | 210 | 210 | 210 | 210 | 210 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-84 | (182) | 312 | 312 | 312 | 312 | 312 |
| Subtotal M & W Fixtures – *No.* | 4.4.20 | 4-88 | (28) | 20 | 22 | 24 | 26 | 28 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-85 | (2,056) | 2,322 | 2.682 | 2,682 | 3,044 | 3,044 |
| **Atrium Restrooms** | | | | | | | | |
| Modules – *No.* | 4.4.20 | 4-85 | (2) | 2 | 2 | 2 | 2 | 2 |
| Total Restroom Area - *Sq. Ft.* | 4.4.20 | 4-84 | (3,000) | 2,350 | 2,540 | 2,710 | 2,900 | 3,260 |
| Total No. of Fixtures Men's – *No.* | 4.4.20 | 4-83 | (32) | 11 | 12 | 13 | 14 | 15 |
| Total No. of Fixtures Women's – *No.* | 4.4.20 | 4-83 | (14) | 14 | 15 | 16 | 18 | 19 |
| Mothers Room (Family) - *Sq. Ft.* | 4.4.20 | 4-84 | -- | 210 | 210 | 210 | 210 | 210 |
| Custodial - *Sq. Ft.* | 4.4.20 | 4-84 | (150) | 312 | 312 | 312 | 312 | 312 |
| Subtotal M& W Fixtures – *No.* | 4.4.20 | 4-83 | (46) | 25 | 27 | 29 | 32 | 34 |
| Subtotal Area - *Sq. Ft.* | 4.4.20 | 4-85 | (3,150) | 2,872 | 3,062 | 3,232 | 3,422 | 3,782 |
| Total M & W Fixtures Non-Secure Landside | 4.4.20 | 4-83 | (96) | 69 | 75 | 81 | 88 | 94 |
| Total Area Non-Secure Landside - *Sq. Ft.* | 4.4.20 | 4-85 | (6,530) | 7,876 | 8,786 | 8,956 | 9,868 | 10,288 |
| **Circulation Considerations** | | | | | | | | |
| Meeter and Greeter Area - *Sq. Ft.* | 4.4.21 | 4-86 | (9,382) | 2,937 | 3,335 | 3,749 | 4,133 | 4,471 |
| Public Elevators, Escalators and Stairs | | | | | | | | |
| Baggage Claim – *No.* | 4.4.21 | -- | (2) | (2)+1=3 | (2)+1=3 | (2)+1=3 | (2)+1=3 | (2)+1=3 |
| Check-in/Atrium – *No.* | 4.4.21 | -- | (4) | (4)+2=6 | (4)+2=6 | (4)+2=6 | (4)+2=6 | (4)+2=6 |
| **Elevators** | | | | | | | | |
| Baggage Claim – *No.* | 4.4.21 | -- | (6) | (6) | (6) | (6) | (6) | (6) |
| Check-in/Atrium – *No.* | 4.4.21 | -- | (2) | 4 | 4 | 4 | 4 | 4 |

| Needs Analysis and Evaluation Summary | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Areas | Section | Table | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| **Stairs** | | | | | | | | |
| Baggage Claim – *No.* | 4.4.21 | -- | (2) | (2) | (2) | (2) | (2) | (2) |
| Check-in/Atrium - *No.* | 4.4.21 | -- | (2) | (2) | (2) | (2) | (2) | (2) |
| Moving Walkways (People Mover) – *No.* | 4.4.21 | -- | (0) | 1 | 1 | 1 | 1 | 1 |

Note: The numbers depicted in parentheses indicate existing conditions in the 2017 (Existing) column through PAL 4 column.
Source: CHA, 2019.

### 4.4.3 Level of Service Standards

Level of Service (LOS) is an accepted value system of space standards and guidelines that are used to assess performance and congestion levels within terminal facilities, as shown **Table 4-29**. The International Air Transport Association (IATA) *Airport Development Reference Manual, 9th Edition*, was used to define the recommended LOS C standards, unless superseded by ORF Authority, airline and/or other stakeholder preferences. LOS C is typically used as a baseline performance criterion target for most airport terminals and is recommended by IATA as the minimum design standard as it denotes "good level of service".


**Table 4-29 – IATA Level of Service Grades**

| Level of Service Grade (LOS) | | Level of Service Description |
|---|---|---|
| **A** | Excellent | Excellent level of service; condition of free flow; excellent level of comfort |
| **B** | High | High level of service; condition of stable flow; very few delays; high level of comfort |
| **C** | Good | Good level of service; condition of stable flow; acceptable good level of comfort |
| **D** | Adequate | Adequate level of service; condition of unstable flow; acceptable delays for short period of time; adequate level of comfort |
| **E** | Inadequate | Inadequate level of service; conditions of unstable flow; unacceptable delays; inadequate level of comfort |
| **F** | System Breakdown | Unacceptable level of service; condition of cross flows; system of breakdown and unacceptable delays; unacceptable level of comfort |

Source: International Air Transport Association (IATA), ADRM, 9th Edition, CHA, 2019.

**Figure 4-5** is a pictogram from The International Air Transport Association (IATA) *Airport Development Reference Manual, 10th Edition*, depicting graphically, in a summary presentation, optimum wait times associated with certain processor functions within the terminal building.

**Figure 4-5 – Passenger Terminal Through Process**




Source: International Air Transport Association (IATA), ADRM, 10th Edition, CHA, 2019.

### 4.4.4 Gate Demand Analysis

The analysis for gate demand, or how many aircraft gates are required, was determined using the "Enplaned Passengers per Gate Approach" and "Departures per Gate Approach" methodologies, as prescribed in Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Manual.* These analyzes are indicted in **Table 4-30** and **Table 4-31**, respectfully. The averages of the two methodologies are represented in **Table 4-32** and correlate to the PALs.

As of 2017, there were 23 existing contact gates at ORF (one-international swing gate, two gates without jet bridges, and 20 gates with jet bridges). With all 23 gates assumed to be operationally equal, each gate has approximately 2.92 ± departures per day in the "base" analysis. Small hub airports with multiple airline carriers historically have lower departures per gates, per day than medium or large hub airports. For the purposes of determining gate demand using accepted planning guidelines, this analysis did not account for gate demand beyond 3.0 departures per gate, per day. Again, this is consistent with the historic nature and practice of gate utilization at small hub airports. If the airline carriers at ORF could effectively align their schedules and maximize preferential gate usage, the number of departures per gate, per day would increase, resulting in a reduction in gate demand.

Gate demand is driven by gate utilization as mentioned above. Other sub-variables impacting gate utilization are fleet mix and departure load factors. Gate demand is not driven solely by

enplanement growth with all the other variables staying constant. The forecast data indicated that as airlines transition their fleet to include larger aircraft with more seats, passengers per departure increase; therefore, the airlines conduct fewer departures. Over the 20-year planning horizon, a lot of variable assumptions were made to come to a forecasted gate demand. The planning analysis used a contingency factor to address any erratic spikes in growth or change to address any uncertainty. The contingency factor addressed these issues in a conservative approach by adding gates to each of the calculated gate totals required for each PAL. The results of this analysis are presented in **Table 4-32.**

**Table 4-30 – Enplaned Passenger per Gate Approach (PALs)**

| Enplaned Passenger per Gate Approach | | | | | |
|---|---|---|---|---|---|
| Year/Activity Level | Annual Enplaned PAX | Annual Departures | # of Gates | Annual Enplaned PAX per Gate | Enplaned PAX per Departure |
| **2017 (Existing)** | (1,672,024) | (23,598) | (23.00) | (72,697) | (70.8545) |
| **Base** | 1,857,487 | 24,493 | 23.00 | 80,760 | 75.8375 |
| **PAL 1** | 2,115,424 | 25,945 | 24.37 | 86,800 | 81.5349 |
| **PAL 2** | 2,376,990 | 27,598 | 25.92 | 91,690 | 86.1219 |
| **PAL 3** | 2,622,848 | 28,744 | 27.00 | 97,140 | 91.2485 |
| **PAL 4** | 2,834,623 | 30,715 | 28.85 | 98,247 | 92.2879 |

Note: Those numbers depicted in parentheses indicate existing conditions in the 2017 (Existing) row.
Source: Airport Cooperative Research Program (ACRP) Report 25 – Airport Passenger Terminal Planning and Design Guidebook, CHA, 2019.

**Table 4-31 – Departures per Gate Approach (PALs)**

| Departures per Gate Approach | | | | | |
|---|---|---|---|---|---|
| Year/Activity Level | Annual Enplaned PAX | Annual Departures | # of Gates | Annual Departures per Gate | Daily Departures per Gate |
| **2017 (Existing)** | 1,672,024 | (23,598) | (23) | (1,026) | (2.81) |
| **Base** | 1,857,487 | 24,493 | 23.00 | 1,065 | 2.92 |
| **PAL 1** | 2,115,424 | 25,945 | 23.69 | 1,095 | 3.00 |
| **PAL 2** | 2,376,990 | 27,598 | 25.20 | 1,095 | 3.00 |
| **PAL 3** | 2,622,848 | 28,744 | 26.25 | 1,095 | 3.00 |
| **PAL 4** | 2,834,623 | 30,715 | 28.05 | 1,095 | 3.00 |

Note: Those numbers depicted in parentheses indicate existing conditions in the 2017 (Existing) row.
Source: Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Guidebook*, CHA, 2019.

**Table 4-32 – Gate Forecast Demand (PALs)**

| Gate Forecast Demand | | | | | | |
|---|---|---|---|---|---|---|
| Enplanements | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Forecasted Gates = N (Existing) | (23) | 23 | 24 | 25 | 26 | 28 |
| Contingency Factor | NA | 2 | 2 | 2 | 1 | 1 |
| Total Gate Demand = N + Contingency Factor | (23) | 25 | 26 | 27 | 27 | 29 |

Source: CHA, 2019.

### 4.4.5 Narrow-body Equivalent Gates and Equivalent Aircraft Gate Analysis

As discussed in **Section 4.1.3**, the "design aircraft" or "design aircraft family" represent the most demanding aircraft or grouping of aircraft with similar characteristics (relative to AAC, ADG, TDG) that are currently using or anticipated to use the airport on a regular basis. Currently, ORF has an ARC of D-IV; however, the Airport's ARC is expected to increase to D-IV over the planning horizon. The current and projected design aircraft family, as presented in **Table 4-3**, was used as the basis for normalizing the terminal gates at the Airport and for conducting the gate equivalencies analyses. Gate equivalency analyses were useful in determining holdroom spatial requirements, as well as in determining other processor evaluations and aircraft ramp frontage requirements at the terminal concourses. The results of the analyses are presented in **Table 4-33**. The results of the analyses represent narrowbody aircraft, along with two ADG IV aircraft.

It is important to note that the definition of the term "gate" varies from airport to airport; therefore, it was important to standardize the definition, as airport comparisons are frequently made on the basis of passengers per gate. To standardize the definition of gates when determining holdroom area requirements, two metrics were developed: Narrowbody Equivalent Gates (NBEG) and Equivalent Aircraft (EQA).

**Table 4-33 – Gate Equivalencies (PALs)**

| Design Group | Class and Aircraft | 2017 Gate Equivalencies (Existing) | | | | | Base Year Gate Equivalencies | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | # of Gates | NBEG | | EQA | | # of Gates | NBEG | | EQA | |
| | | | Maximum Wingspan (Feet) | Index | Typical Seats | Index | | Maximum Wingspan (Feet) | Index | Typical Seats | Index |
| I | Small Regional (Metro, B99, J31) | 0 | 49 | 0.4 | 25 | 0.2 | 0 | 49 | 0.4 | 25 | 0.2 |
| II | Medium Regionals (SF340, CRJ) | 0 | 79 | 0.7 | 50 | 0.4 | 0 | 79 | 0.7 | 50 | 0.4 |
| III | Large Regionals (DHC8, E175) | 0 | 118 | 1.0 | 75 | 0.5 | 0 | 118 | 1.0 | 75 | 0.5 |
| III | Narrow-body (A320, B737, MD80) | (21) | 118 | 1.0 | 145 | 1.0 | 23 | 118 | 1.0 | 145 | 1.0 |
| IIIa | B757 (B757, B757 w/Winglets) | 0 | 135 | 1.1 | 185 | 1.3 | 0 | 135 | 1.1 | 185 | 1.3 |
| IV | Wide-body (MD-11, B767) | (2) | 171 | 1.4 | 280 | 1.9 | 2 | 171 | 1.4 | 280 | 1.9 |
| V | Jumbo (B747, B777, A330, A340) | 0 | 214 | 1.8 | 400 | 2.8 | 0 | 214 | 1.8 | 400 | 2.8 |
| VI | A380 (A380, B747-8) | 0 | 262 | 2.2 | 525 | 3.6 | 0 | 262 | 2.2 | 525 | 3.6 |
| | Totals | (23) | **NBEG** | 23.8 | **EQA** | 24.8 | 27 | **NBEG** | 25.8 | **EQA** | 26.8 |

| Design Group | Class and Aircraft | PAL 1 Gate Equivalencies | | | | | PAL 2 Gate Equivalencies | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | # of Gates | NBEG | | EQA | | # of Gates | NBEG | | EQA | |
| | | | Maximum Wingspan (Feet) | Index | Typical Seats | Index | | Maximum Wingspan (Feet) | Index | Typical Seats | Index |
| I | Small Regional (Metro, B99, J31) | 0 | 49 | 0.4 | 25 | 0.2 | 0 | 49 | 0.4 | 25 | 0.2 |
| II | Medium Regionals (SF340, CRJ) | 0 | 79 | 0.7 | 50 | 0.4 | 0 | 79 | 0.7 | 50 | 0.4 |
| III | Large Regionals (DHC8, E175) | 0 | 118 | 1.0 | 75 | 0.5 | 0 | 118 | 1.0 | 75 | 0.5 |
| III | Narrow-body (A320, B737, MD80) | 24 | 118 | 1.0 | 145 | 1.0 | 25 | 118 | 1.0 | 145 | 1.0 |
| IIIa | B757 (B757, B757 w/Winglets) | 0 | 135 | 1.1 | 185 | 1.3 | 0 | 135 | 1.1 | 185 | 1.3 |
| IV | Wide-body (MD-11, B767) | 2 | 171 | 1.4 | 280 | 1.9 | 2 | 171 | 1.4 | 280 | 1.9 |
| V | Jumbo (B747, B777, A330, A340) | 0 | 214 | 1.8 | 400 | 2.8 | 0 | 214 | 1.8 | 400 | 2.8 |
| VI | A380 (A380, B747-8) | 0 | 262 | 2.2 | 525 | 3.6 | 0 | 262 | 2.2 | 525 | 3.6 |
| | Totals | 26 | **NBEG** | 26.8 | **EQA** | 27.8 | 27 | **NBEG** | 27.8 | **EQA** | 28.8 |

| Design Group | Class and Aircraft | PAL 3 Gate Equivalencies | | | | | PAL 4 Gate Equivalencies | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | # of Gates | NBEG | | EQA | | # of Gates | NBEG | | EQA | |
| | | | Maximum Wingspan (Feet) | Index | Typical Seats | Index | | Maximum Wingspan (Feet) | Index | Typical Seats | Index |
| I | Small Regional (Metro, B99, J31) | 0 | 49 | 0.4 | 25 | 0.2 | 0 | 49 | 0.4 | 25 | 0.2 |
| II | Medium Regionals (SF340, CRJ) | 0 | 79 | 0.7 | 50 | 0.4 | 0 | 79 | 0.7 | 50 | 0.4 |
| III | Large Regionals (DHC8, E175) | 0 | 118 | 1.0 | 75 | 0.5 | 0 | 118 | 1.0 | 75 | 0.5 |
| III | Narrow-body (A320, B737, MD80) | 25 | 118 | 1.0 | 145 | 1.0 | 27 | 118 | 1.0 | 145 | 1.0 |
| IIIa | B757 (B757, B757 w/Winglets) | 0 | 135 | 1.1 | 185 | 1.3 | 0 | 135 | 1.1 | 185 | 1.3 |
| IV | Wide-body (MD-11, B767) | 2 | 171 | 1.4 | 280 | 1.9 | 2 | 171 | 1.4 | 280 | 1.9 |
| V | Jumbo (B747, B777, A330, A340) | 0 | 214 | 1.8 | 400 | 2.8 | 0 | 214 | 1.8 | 400 | 2.8 |
| VI | A380 (A380, B747-8) | 0 | 262 | 2.2 | 525 | 3.6 | 0 | 262 | 2.2 | 525 | 3.6 |
| | Totals | 27 | **NBEG** | 27.8 | **EQA** | 28.8 | 29 | **NBEG** | 2.8 | **EQA** | 30.8 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Guidebook*, CHA, 2019.

### 4.4.6 Concourse Hold Room Analysis

The analysis for hold rooms assumed all gates are equalized to meet Narrow-Body Aircraft hold room standards. This included those aircraft classified as Aircraft Design Group III (B737, A319, A320, MD80, etc.). Based on these assumptions, it was assumed that ORF should plan two positions for Wide-body Aircraft with corresponding hold room accommodations. This included aircraft classified as Aircraft Design Group IV (B767, MD11, and including B757).

The next evaluation was to determine the optimum NBEG hold room size. For planning purposes, it was assumed that all gates are equalized to accommodate the Design Group III narrow-body fleet mix. The evaluation could have also been conducted to address gate utilization with a specific anticipated Design Group for each individual gate, which may have been appropriate in the short-term; however, long-term needs need to be based on the Design Group III-Narrow-Body Fleet Mix. Again, this approach was consistent with the trend for the fleet mix changing to Design Group III and for preferential lease agreements at the gates, allowing flexibility in gate usage by the Airport Authority. The evaluation assumptions, as indicated in **Table 4-34,** followed the progression of growth throughout the planning horizon. The evaluation was based on a LOS B/C which allots 15-square feet for seated passengers and 10 square feet for standing passengers. As a reference point, LOS A would allot 17-square feet for seated passengers and 12-square feet for standing passengers.

The analysis concluded with calculating the inclusive hold room space requirements through the planning horizon, as indicated in **Table 4-35.**

## Table 4-34 – Single NBEG Hold Room Area Evaluation (PALs)

| Single NBEG Hold Room Area Evaluation | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Input | Out | Input | Out | Input | Out | Input | Out | Input | Out | Input | Out |
| Seats on Design Aircraft – *No.* | 145 | | 145 | | 145 | | 145 | | 145 | | 145 | |
| Load Factors (%)[1] | 79.0% | | 79.5% | | 81.1% | | 82.2% | | 83.4% | | 84.2% | |
| **# of Design Passengers** | | **115** | | **116** | | **118** | | **120** | | **121** | | **123** |
| % PAX Seated | 80% | 92 | 80% | 93 | 80% | 95 | 80% | 96 | 80% | 97 | 80% | 99 |
| % PAX Standing | 20% | 23 | 20% | 23 | 20% | 23 | 20% | 24 | 20% | 24 | 20% | 24 |
| Seated PAX Area Requirement - *Sq. Ft.* | 15 | 1,380 | 15 | 1,395 | 15 | 1,425 | 15 | 1,440 | 15 | 1,455 | 15 | 1,485 |
| Standing PAX Area Requirement - *Sq. Ft.* | 10 | 230 | 10 | 230 | 10 | 230 | 10 | 240 | 10 | 240 | 10 | 240 |
| Seated & Standing Area - *Sq.Ft.* | | 1,610 | | 1,625 | | 1,655 | | 1,680 | | 1,695 | | 1,725 |
| % Increase for Amenities | 10% | 161 | 10% | 163 | 10% | 166 | 10% | 168 | 10% | 170 | 10% | 173 |
| % Increase for High Utilization | 5% | 81 | 5% | 82 | 5% | 83 | 5% | 84 | 5% | 85 | 5% | 87 |
| Hold Room Share Factor - (Decrease) | -(5%) | -(81) | -(5%) | -(82) | -(5%) | -(83) | -(5%) | -(84) | -(5%) | -(85) | -(5%) | -(87) |
| **Adj. Seated & Standing Area (sq. ft.)** | | **1,852** | | **1,870** | | **1,904** | | **1932** | | **1,950** | | **1,985** |
| Podium Width /Position - *Ft.* | 4 | | 4 | | 4 | | 4 | | 4 | | 4 | |
| Depth of Podium to Back Wall - *Ft.* | 8 | | 8 | | 8 | | 8 | | 8 | | 8 | |
| Podium Queue Depth - *Ft.* | 15 | | 15 | | 15 | | 15 | | 15 | | 15 | |
| Area / Podium Position - *Sq. Ft.* | | 92 | | 92 | | 92 | | 92 | | 92 | | 92 |
| Podium Positions – *No.* | 2 | | 2 | | 2 | | 2 | | 2 | | 2 | |
| Total Podium & Queue Area - *Sq. Ft.* | | 184 | | 184 | | 184 | | 184 | | 184 | | 184 |
| Boarding/Egress Corridor Width - *Ft.* | 6 | | 6 | | 6 | | 6 | | 6 | | 6 | |
| Depth of Hold Room - *Ft.* | 25 | | 25 | | 25 | | 25 | | 25 | | 25 | |
| Boarding/Egress per Bridge - *Sq. Ft.* | | 150 | | 150 | | 150 | | 150 | | 150 | | 150 |
| Bridges/Gate – *No.* | 1 | | 1 | | 1 | | 1 | | 1 | | 1 | |
| Boarding Corridor Area - *Sq. Ft.* | | 150 | | 150 | | 150 | | 150 | | 150 | | 150 |
| **Total NBEG Hold Room Area (sq. ft.)** | | **2,428** | | **2,444** | | **2,480** | | **2,508** | | **2,526** | | **2,561** |

Note: Taking the load factor and multiplying by the number of seats on design aircraft results in the number of design passengers.

[1] as indicated in **Figure 3-10**

Source: Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Guidebook*, CHA, 2019.

## Table 4-35 – Inclusive Hold Room Space Requirements (PALs)

| Inclusive Hold Room Space Requirements | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Contact Gates | Hold Room (SF) | NBEG | Hold Room (SF) | NBEG | Hold Room (SF) | NBEG | Hold Room (SF) | NBEG | Hold Room (SF) | NBEG | Hold Room (SF) |
| (23.0) | (35,645) | 25.8 | 63,055 | 26.8 | 66,464 | 27.8 | 69,722 | 27.8 | 70,223 | 29.8 | 76,318 |

Note: Those numbers depicted in parentheses indicate existing conditions

Source: CHA, 2019.

### 4.4.7 Concourse Circulation

For concourses without moving walkways, a corridor width of 20 feet is acceptable for single-loaded concourses and a 30-foot width for double-loaded concourses. For concourses with moving walkways, 15 feet on both sides of the walkway is recommended to allow uncongested circulation. Other factors also impact corridor width such as use of people mover carts, advertising, vending machines, drinking fountains, etc. For the purposes of this evaluation, double-loaded concourses were assumed throughout the planning horizon.

This analysis took the NBEG aircraft width requirements of 118 feet as indicated in **Table 4-33** and added 25 feet for wingtip clearance between aircraft. The widths were then multiplied by the total number of NBEGs for each activity level, as indicated in **Table 4-36**, to determine single-loaded corridor length (also concourse aircraft frontage) to support the gates; however, in the detailed design of aircraft frontage along the concourse, it may be recommended that a 20-foot wingtip clearance be used in the analysis between a narrow-body fleet mix. This would be an operational consideration for the airport to make with the air carriers, but under no circumstances would a wingtip clearance of less than 25 feet be recommend between a narrow-body aircraft and a Design Group IIIa (B757) aircraft and larger.

**Table 4-36 – Single-loaded Concourse Corridor Length (PALs)**

| Single-loaded Concourse Corridor Length | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| NBEG[1] (#) | Single-loaded Corridor Length[1] (ft.) | NBEG (#) | Single-loaded Corridor Length (ft.) | NBEG (#) | Single-loaded Corridor Length (ft.) | NBEG (#) | Single-loaded Corridor Length (ft.) | NBEG (#) | Single-loaded Corridor Length (ft.) | NBEG (#) | Single-loaded Corridor Length (ft.) |
| (23.2)[1] | (3,318 ft.)[1] | 25.8 | 3,689 ft. | 26.8 | 3,832 ft. | 27.8 | 3,975 ft. | 27.8 | 3.975 ft. | 29.8 | 4,261 ft. |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] based on the theoretical NBEG determination the single-loaded corridor length was calculated. This does not reflect the existing conditions, but represents the theoretical lengths required for a single-loaded corridor by normalizing the existing gates to accommodate Aircraft Design Group III - Narrow-body Aircraft.
Source: CHA, 2019.

The calculation could be made to determine the corridor and circulation area requirements for a double-loaded concourse based on the previously mentioned criteria for a single-loaded corridor concourse. The double-loaded corridor to support the gates, along with the fact that the existing concourses are double-loaded, was assumed to be the most practical, efficient, and usable analysis for planning purposes.

The double-loaded concourse area analysis to support the NBEGs was calculated by dividing the single-loaded corridor lengths indicated in **Table 4-37** by two, and then multiplying by 30 feet of width to support the circulation needs for a double-loaded concourse throughout the planning horizon.

**Table 4-37 – Double-loaded Concourse Corridor Length and Area (PALs)**

| Double-loaded Concourse Corridor Length and Area | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Length[1] (ft.) | Area[1] (sq. ft.) | Length (ft.) | Area (sq. ft) | Length (ft.) | Area (sq. ft.) | Length (ft.) | Area (sq. ft.) | Length (ft.) | Area (sq. ft.) | Length (ft.) | Area (sq. ft.) |
| (1,313) | (31,419) | 1,844 | 55,320 | 1,916 | 57,480 | 1,988 | 59,640 | 1,988 | 59,640 | 2,131 | 63,930 |

Note: Those numbers depicted in parentheses indicate existing conditions.
includes both existing Concourse A and B. These figures represent existing conditions.
Source: CHA, 2019.

### 4.4.8 Check-in Lobby

Passenger check-in trends are heavily reliant on technologies which will continue to drive passenger behavior regarding the check-in process. Prior to technology enhancements, the September 11th attacks in 2001, and checked baggage fees, all passengers checked-in and received boarding passes with the majority of the passengers checking a bag. Despite advancements in technology and airlines providing self-service options, some passengers still prefer checking in with an airline representative; therefore, the need to maintain an acceptable level of service remains in place, despite the airlines best marketing efforts to drive all passengers to use non-airline agent check-in procedures. General preferences and other socioeconomic factors affect this needed level of service.

The emergence of self-service equipment has proven itself beneficial for passengers (and airlines) regarding checking in and printing boarding passes, either on, or off-airport property, and self-bag check. These capabilities have the potential to reduce the demand for ticket lobby space and occupied ticket agent positions. Regardless of technological advances, there will always be a spatial need at airports for passengers to check-in, obtain a boarding pass and check baggage; however, ticketing halls as we know them now may be entirely different as time goes on. In the future the ticketing hall could be repurposed as a passenger baggage drop hall where only those passengers checking through baggage will access the processor area.; however, the need for passengers to obtain paper boarding passes, address oversize or out-of-gauge baggage requirements, and the need for access to customer services will be present throughout the planning horizon. It is not unreasonable to assume these needs may be addressed by self-help, self-service kiosks without airline agent assistance or intervention to the greatest extent possible.

This analysis for the check-in processors addressed and assumed certain passenger trends through the planning horizons (PALs) with a mix of full-service agent positions (where passengers complete their entire transaction with an agent), bag drops (where passengers drop bags after checking-in online or at a kiosk), self-service kiosks, curbside, and an estimate for the number of passengers who complete check-in offsite (i.e. at home, via mobile device, etc.) While this analysis did not consider passenger self-bag tag and drop processes, it should be noted that several large domestic terminals are installing this type of self-serve equipment; however, the current TSA protocols in place require an airline agent to determine identification. Over the planning horizon it was assumed that ORF will not see these technologies sufficiently put into service to affect the spatial needs indicated. Definitions of the types of check-in functions available at an airport are described below.

- Bypass (Internet PC/Mobile Device) Check-in: Passengers who do not check bags and are able to check-in remotely, prior to arriving to the terminal and do not use terminal check-in processors.
- Self-Service Kiosk Check-in: Stand-alone kiosks can be located remote from the ATO counter in the check-in lobby or throughout the terminal. Kiosks print boarding passes but usually do not provide the ability to print bag tags because they are not staffed. When kiosks are located at the ATO ticket counter, they are typically configured in pairs with a bag well, which often includes a baggage scale between pairs. These combined ATO/Kiosk positions provide bag tag printing and bag acceptance by airline or ground handling agents who usually support multiple kiosk positions.
- Baggage Drop Positions: Airline staff or agents accept bags from passengers who check-in via internet PC/mobile device or at a kiosk for a two-step process.
- Full Service (Agent) Check-in: Airline staff or agents may assist passengers with boarding passes, rebooking, and where check-in bags are accepted.
- Curbside Check-in Processors: Typically, curbside check-in facilities are equipped with conveyor belts located at the check-in podiums for direct input of bags into the outbound baggage system. At smaller airports (or for airlines who do not wish to pay for conveyors) checked bags may be placed on carts and taken into the check-in lobby to be transferred to the ATO counter bag conveyor.

The LOS assumptions for passenger check-in behaviors at ORF through the planning horizon are shown in **Table 4-38** and **Table 4-39**.

**Table 4-38 – IATA Level of Wait Time Standard for Check-In (Minutes)**

| Type of Service | Short to Acceptable (min.) | Acceptable to Long (min.) |
|---|---|---|
| Full Assist Economy Check-in | 0-10 | 10-20 |
| Kiosk Boarding Pass | 1-2 | 2-5 |
| Agent Assist Bag Drop | 1-5 | 5-10 |

Source: International Air Transport Association (IATA), ADRM, 10th Edition, CHA, 2019.

**Table 4-39 – IATA Level of Service Space Standard for Check-In (sq. ft. per PAX)**

| Type of Service | A | B | C | D | E | F |
|---|---|---|---|---|---|---|
| Few carts and few PAX with check-in baggage | 18.3 | 15.0 | 12.9 | 11.8 | 9.6 | <9.6 |
| Few carts and 1 or 2 pieces of baggage per PAX | 19.4 | 16.1 | 14.0 | 12.9 | 11.8 | <11.8 |
| High percentage of PAX using baggage carts | 24.8 | 20.5 | 18.3 | 17.2 | 16.1 | <16.1 |
| "Heavy aircraft" flights with 2 or more items per PAX and a high rate of PAX using baggage carts | 28.0 | 24.8 | 21.5 | 20.5 | 19.4 | <19.4 |

Note: Recommended row width between stanchions is 4.0 to 4.5 feet.
Source: International Air Transport Association (IATA), ADRM, 9th Edition, CHA, 2019.

All airlines currently in operation at ORF actively encourage online or mobile check-in before arriving at the terminal. To encourage passengers to use the self-service functions provided, one airline at ORF charges a nominal fee if the boarding pass is printed by an agent at the Airport. Another airline charges for baggage needing to be checked through at the gate to address the phenomenon of passengers by-passing the check-in processor area to avoid the checked baggage fees.

This analysis assumed 40 percent of all enplaned passengers check baggage through at the check-in lobby, with an additional 10 percent checking baggage through at the departure gate. This equated to a total of 50 percent of all passengers checking a bag with an agent. This latter passenger behavior is addressed in **Section 4.4.13** for inbound baggage claim. Without curbside check-in and remote baggage drop locations, it was assumed at ORF that 60-percent of the enplaned passengers drop baggage off in the check-in processor area. This percentage of baggage drop utilization was assumed to remain constant throughout the planning horizon.

The key to the analysis was to determine the effects of technology, passenger demographics, and trust regarding the check-in process. How many passengers (who are not checking baggage) check-in remote online or with mobile devices (digital boarding passes), thus by-passing the check-in processor area? How many passenger's check-in remote-online or with mobile devices (digital boarding passes), but still access the check-in processor area regarding needing to check their luggage? What demographics still rely strongly on expecting full-service check-in processors with agent assistance? Survey data suggests that age demographics factor into passengers' level of trust in handling their own technology processes, thus driving the need for full-service check-in processors and agent assistance.

The assumptions for passenger check-in behaviors at ORF through the planning horizon are shown in **Table 4-40**.

**Table 4-40 – Enplaned Passenger Check-in Utilizations (PALs)**

| Enplaned Passenger Check-in Utilization | | | | | | | |
|---|---|---|---|---|---|---|---|
| Check-in / Bag Drop | | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| **Passenger Ticketing by Locations** | | | | | | | |
| Traditional Ticketing Counter with Agent Assistance | | -- | 20% | 16% | 12% | 7% | 5% |
| Terminal Kiosk Ticketing Only | | -- | 10% | 8% | 6% | 5% | 2% |
| Terminal Kiosk Ticketing w/Bag Drop Function | | -- | 35% | 32% | 27% | 18% | 8% |
| Remote Check-in w/Bag Drop Function | | -- | 15% | 22% | 28% | 40% | 50% |
| Curbside Check-in Processors | | -- | 0% | 0% | 0% | 0% | 0% |
| By-Pass Check-in Remote | | -- | 20% | 22% | 27% | 30% | 35% |
| **Baggage Check or Drop Locations and Utilization** | | | | | | | |
| Terminal Building | Location | (100%) | 100% | 100% | 100% | 100% | 100% |
| | PAX Utilization | (40%) | 40% | 40% | 40% | 40% | 40% |
| Curbside | Location | (0%) | 0% | 0% | 0% | 0% | 0% |
| | PAX Utilization | (0%) | 0% | 0% | 0% | 0% | 0% |
| Off-Airport Location | Location | (0%) | 0% | 0% | 0% | 0% | 0% |
| | PAX Utilization | (0%) | 0% | 0% | 0% | 0% | 0% |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

This analysis assumed that curbside services are not going to be factors in addressing passenger check-in or checked baggage/bag drop functions. In addition, remote off-airport baggage drop locations are not foreseeable in the planning horizon. If these two functions were utilized, the demand to provide area within the terminal for these functions may have been reduced.

Assumptions:

- Transaction time for checking in at a kiosk is 2.5 minutes.
- Transaction time for agent assistance is 5.0 minutes.
- Transaction time for checking a bag (baggage drop) is 1.7 minutes.
- Ticketing check-in and bag drop counters area assumes 5.5-linear feet per position (includes baggage scale), 15-foot depth from back wall to face of counter, 8-foot circulation easement form face of counter to queuing line, and 24 feet of queue depth.
- Kiosk area, assuming free standing kiosks not integral to counter, are 9-square feet per kiosk with 25-square feet of circulation space.
- 40-percent of passengers check baggage in the traditional ticket lobby throughout the planning horizon.

Throughout the planning period:

- Curbside positions are not a service provided through the planning horizons.
- The quantity of agent assist positions decreases incrementally.
- The quantity of baggage check and drop positions increases incrementally as passengers arrive at the terminal with checked-in status only needing to check and drop baggage in the check-in hall.
- The quantity of passenger self-service kiosks within the terminal facility decreases incrementally as passenger's check-in remote and/or with mobile devices.

**Table 4-41 – Passenger Check-in Requirements (PALs)**

| Passenger Check-in Requirements | | | | | | |
|---|---|---|---|---|---|---|
| **Check-in Modes** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Traditional Agent Assist Positions (Full Service) – *No.* | (44) | 12 | 10 | 10 | 8 | 8 |
| Self-Service Kiosks – *No.* | (10) | 17 | 14 | 10 | 9 | 8 |
| Baggage Check-in and Drops Positions – *No.* | -- | 14 | 15 | 17 | 19 | 21 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Guidebook,* CHA, 2019.

In **Table 4-41**, the traditional agent assisted positions were purposely kept at a higher number than the analytical model would suggest. This accounted for any activities associated with international passengers and check-in protocols with ultra-low-cost carriers.

**Table 4-42 – Passenger Check-in Hall Area Requirements (PALs)**

| Passenger Check-in Hall Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| Areas | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Base Area - *Sq. Ft.* | -- | 7,248 | 6,896 | 7,289 | 7,258 | 7,744 |
| Circulation Factors or 1.50[1] - *Sq. Ft.* | -- | 3,624 | 3,448 | 3,645 | 3,629 | 3,872 |
| Total Passenger Check-in Hall Area - *Sq. Ft.* | (18,087)[2] | 10,872 | 10,344 | 10,934 | 10,887 | 11,616 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] the generally acceptable circulation factor is 1.25 times the base area for passenger check-in hall area requirements. This analysis concluded that an acceptable factor is 1.50 to address any errant airline operational policies and/or procedures, non-common equipment and facilities use participation among the airlines and inherent inefficiencies with the existing structure renovating existing areas into a new or expanded use.

[2] not including area for the outbound baggage screening functions and EDS equipment in the ticketing lobby.

Source: CHA, 2019.

It should be noted that during periods of low demand, the check-in lobby may be perceived as oversized. ORF has migrated towards common-use facilities to address the ultra-low-cost carriers. These efforts should continue when advancing common-use facilities to help balance demand loads between the airlines and achieve a higher level of efficiency in the check-in lobby. Partial or full common-use facilities would allow for the ticketing lobby to adequately serve a demand beyond the planning period and for more flexibility in adjusting to changing conditions, such as the addition of new carriers.

### 4.4.9 Airline Ticket Offices (ATO)

When calculating ATO requirements for legacy airline carries, 900 square feet of office space per air carrier was assumed for planning purposes. Legacy carriers have begun following market trends similar to those provided by ultra-low-cost carries (Allegiant, Frontier, etc.), offering low-cost services by eliminating many traditional passenger services and reducing many airport-specific overhead costs; therefore, for the purposes of this Study, 700 square feet of office space per air carrier was assumed, along with the assumption that ORF will gain two additional airline carriers during the planning period.

**Table 4-43 – Airline Ticketing Offices (PALs)**

| Airline Ticketing Offices | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Airlines (#) | ATO (sf) | Airlines (#) | ATO (sf) | Airlines (#) | ATO (sf) | Airlines (#) | ATO (sf) | Airlines (#) | ATO (sf) | Airlines (#) | ATO (sf) |
| (6) | (7,170)[1] | 6 | 4,200 | 6 | 4,200 | 6 | 4,200 | 7 | 4,900 | 8 | 5,600 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] as indicated in **Table 2-10**

Source: CHA, 2019.

### 4.4.10 Airlines Operations Areas at Gates (Concourse)

Much of the spatial areas beneath the two concourses are built out to support airline and Airport uses, which to some certainty could be summarized as unassigned lease space for airline use. This analysis was based on determining the programmatic area required to support airline activities, specific to ORF. Similar to the trends for ATO space, airlines are looking to reduce overhead costs at airports, as the demand for operational areas has decreased over the years; however, there is still a need for these important activities that require space. To determine the

airline operation areas at the concourse locations, a factor of 1,000 square feet for every 100 peak hour enplaned passengers was calculated, as shown in **Table 4-44.**

**Table 4-44 – Airline Operation Areas at Gates (PALs)**

| Airline Operations Areas at Gates | | | | | | |
|---|---|---|---|---|---|---|
| Function | 2017 (Existing) | BASE | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Airline Operation Areas at Gates – *Sq. Ft.* | (37,260)[1] | 13,540 | 15,370 | 17,270 | 19,060 | 20,600 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] as indicated in **Table 2-10**
Source: CHA, 2019.

### 4.4.11 Security Checkpoint Screening

Security screening requirements are subject to regulations set forth by the Transportation Security Administration. The level of security screening and the requirements are subject to change at any time based on the levels of threat and the continued advancement in security screening equipment and requirements.

ORF operates two distinct security check points: one at Concourse A and one at Concourse B. Checkpoints A and B were expanded and remodeled in 2016 and 2014, respectfully. This analysis considered capacity and needs through the planning horizon for both of the existing checkpoints and developed planning data for a single checkpoint, as well as for a consolidated checkpoint.

Checkpoint requirements define the number of TSA document checkers (TDC), the number of checkpoint lanes, and the amount of queue area required to support terminal activity. A checkpoint lane consists of a single or paired advanced imaging technology (AIT) and magnetometer, an x-ray unit with an attached divest and recompose rollers and tables, manual search stations, and benches. A supervisor station is used to monitor each checkpoint area. Demand is affected by airline flight schedules and the upstream flight check-in process. Performance criteria was applied to activity (demand) to determine the number of TDC and screening lanes needed. Dimensional criteria are based on level of service standards and operating requirements. To derive the initial space program, dimensional criteria was applied to the required numbers of TDC and screening lanes, as well as to the number of passengers in the transaction waiting (queues) and recompose areas. For the purpose of detailed planning, separate analyses would have had to be conducted for each checkpoint, taking into consideration the differences in any upstream processes that determine passenger flows into the checkpoint. Determinations for a single checkpoint would be aggregated to formulate the overall program requirement for each of the checkpoint scenarios.

Overall screening lane processing rates, typically stated in terms of passengers per hour per lane, were measured by identifying the total number of passengers passing through the AIT or magnetometer; however, multiple processes within the screening process affect overall throughput. TSA requires that each passenger pass the following screening procedures in sequence to complete the checkpoint screening process: ticketing (boarding pass and passenger identification) document check, divesture of TSA regulated items, AIT or magnetometer scans, recompose, and, if necessary, secondary screening (carry-on baggage and passenger search, or private personal search room screening). Processing rates at checkpoints vary based on the airport, passenger characteristics, and time of year; therefore, these factors were considered

when determining the processing rate to be used for calculating the number of checkpoint lanes and the size of the required areas. Divestment and recompose activities are the most time-consuming processes; thus, they were critical determinants of throughput. TSA regulations for divesting personal items requires the use of multiple bins per passenger; similarly, passenger recompose activity - post AIT/magnetometer scanning - can extend the throughput of the x-ray units. Lack of adequate divest and recompose table lengths impede materials reaching the x-ray units, resulting in decreased lane throughput. Extension and/or adding area and table lengths for divesting and recomposing has proven to yield above-average site-specific processing rates.

Checkpoint demand was analyzed against level of service standards that address performance in terms of the time passengers wait for processing, as well as the space allotted for each waiting passenger. The IATA LOS guidelines for checkpoint (same as passport control outbound) wait times are:

- Short to acceptable: 0-5 minutes
- Acceptable to long: 5-10 minutes

**Table 4-45** lists the IATA space standards for passengers waiting in a single queue to be screened.

**Table 4-45 – IATA Level of Service Standards for Security Screening Checkpoints**

| Security Screening Checkpoint | | | | | | |
|---|---|---|---|---|---|---|
| | LOS A | LOS B | LOS C | LOS D | LOS E | LOS F |
| Checkpoint (IATA Passport Control) per PAX - *Sq. Ft.* | 15.0 | 12.9 | 10.8 | 8.6 | 6.5 | <6.5 |

Source: International Air Transport Association (IATA), ADRM, 9th Edition, CHA, 2019.

TSA does not provide guidance on level of service duration or spatial guidelines for wait times, or for area per passenger, while in queue; however, it does indicate minimum area allocations for each checkpoint screening lane and its' associated support spaces. The calculations to determine queue areas based on processing rate utilized the longest acceptable IATA standard of 10 minutes with a LOS C; however, queue areas were also calculated to accommodate up to 20 minutes of accumulated passengers waiting for TDC screening to account for fluctuations in staffing. The processing rate per lane in this analysis was 175-passengers per hour, which accounted for a normalized rate of 150 passengers per hour per checkpoint lane, while factoring in TSA Pre ✓ TM and airline/airport staff utilization. **Figure 4-6** provides the formula used for calculating queuing area allowances based on wait time. The dimensional effects extended queue depths have on a checkpoint lane pair range from approximately 3,870 square feet to 4,860 square feet, depending on processing rates and wait time variables, to determine queue areas.


**Figure 4-6 – Wait Time Calculation**

$$\textit{Wait Time (min)} = \frac{\text{Total Queue Area (sf)}}{\text{LOS (sf/pax)}} \times \text{Screening Lane Throughput (min/pax)}$$

TSA recommends a minimum of 300 square feet of queuing area per screening lane. This is consistent with the formula as shown in **Figure 4-6**, which assumed a LOS C variable, 150-passenger per hour, per lane processing rate, and a wait time of about 10 minutes. TSA issued *Checkpoint Design Guideline* (CDG), which recommends that airports and local TSA authorities collaborate to establish acceptable goals for airport-terminal-specific wait times and screening

lane processing rates for planning purposes. **Figure 4-7** is a generic diagram of a pair of security checkpoint lanes, which is similar to the existing layouts at ORF.

**Figure 4-7 – Standard TSA Security Checkpoint Lane**




Utilizing the aforementioned assumptions, the dimensional guideline for a checkpoint lane pair with AIT and magnetometer was approximately 3,870-square feet, as depicted in the figure, and consisted of:

- Screening lane pair consisting of the length of each screening lane, including divest tables, x-ray
- machine, agent work area, recompose tables, AIT body scanner, magnetometer, divest bins, and recompose benches
- Private search rooms, manual carry-on baggage search tables, and screening equipment
- Circulation aisle separating the screening lane area from the boarding pass document check agent podium
- Queue stanchions
- Stanchions for ADA-accessible and family queue lanes

The number of security screening lanes was calculated using the peak hour enplanement data indicated in **Table 3-35** (**Chapter 3**). Based on conversations with NAA, it was assumed that enplanement utilization is equally split between the two existing checkpoints. This assumption was applied throughout the planning horizon for determining the number of security screening lanes.

### Table 4-46 – No. of Security Screening Lanes at Checkpoints

| No. of Security Screening Lanes at Checkpoint | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Nom. | No. | Nom. | No. | Nom. | No. | Nom. | No. | Nom. | No. | Nom. |
| Concourse A - *No.* | (5.0) | 3.87 | 4.0 | 4.39 | 5.0 | 4.93 | 5.0 | 5.45 | 6.0 | 5.88 | 6.0 |
| Concourse B – *No.* | (6.0) | 3.87 | 4.0 | 4.39 | 5.0 | 4.93 | 5.0 | 5.45 | 6.0 | 5.88 | 6.0 |
| Consolidated Checkpoint - *No.* | -- | 7.74 | 8.0 | 8.78 | 9.0 | 9.86 | 10.0 | 10.9 | 11.0 | 11.76 | 12.0 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

The total queue area requirements for all security screening lanes were determined by utilizing the formula in **Figure 4-6**. The results of the calculations, shown in **Table 4-47**, represent the longest acceptable IATA standard of 10-minutes for LOS C; however, to account for delays in TDC screening due to fluctuations in staffing, the total queue area required to accommodate the influx in passengers was determined based on a 20-minute timeframe. To maintain a LOS C, each security lane must be able to process 175 passengers per hour.

### Table 4-47 – Security Screening Checkpoint Area Requirements (Not Including Queuing Area)

| Security Checkpoint Area Requirements (Not Including Queueing Area) | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base[1] | PAL 1[1] | PAL 2[1] | PAL 3[1] | PAL 4[1] |
| Concourse A - *Sq. Ft.* | (8,573) | 6,480 | 8,100 | 8,100 | 9,720 | 9,720 |
| Concourse B -*Sq. Ft.* | (7,330) | 6,480 | 8,100 | 8,100 | 9,720 | 9,720 |
| Consolidated Checkpoint - *Sq. Ft.* | -- | 12,960 | 14,580 | 16,200 | 17,820 | 19,440 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] the area total area requirements for the security checkpoint is the 3,240 square feet as indicated in **Figure 4-7** (not including the queueing area) for every two lanes.
Source: CHA, 2019.

### Table 4-48 – Queue Area for All Security Checkpoint Lane (PALs)

| Queue Area for All Security Checkpoint Lanes | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Queue Area | 10 Min. Wait | 20 Min. Wait | 10 Min. Wait | 20 Min. Wait | 10 Min. Wait | 20 Min. Wait | 10 Min. Wait | 20 Min. Wait | 10 Min. Wait | 20 Min. Wait |
| Concourse A - *Sq. Ft.* | (2,305) | 1,280 | 2,560 | 1,600 | 3,200 | 1,600 | 3,200 | 1,920 | 3,840 | 1,920 | 3,840 |
| Concourse B - *Sq. Ft.* | (2,131) | 1,280 | 2,560 | 1,600 | 3,200 | 1,600 | 3,200 | 1,920 | 3,840 | 1,920 | 3,840 |
| Consolidated Checkpoint - *Sq. Ft.* | -- | 2,560 | 5,120 | 2,880 | 5,760 | 3,200 | 6,400 | 3,520 | 7,040 | 3,840 | 7,320 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

The TSA and LEO office areas, as shown in **Table 4-49,** accounted for three-percent of the queue area for all security checkpoint lanes as indicated in **Table 4-48** and security checkpoint area requirements (not including queuing area) as indicated in **Table 4-47**.

**Table 4-49 – Security Screening Checkpoint TSA/LEO Office Requirements (PALs)**

| Security Checkpoint TSA/LEO Office Requirements | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Concourse A - *Sq. Ft.* | (1,318) | 465 | 582 | 582 | 698 | 698 |
| Concourse B - *Sq. Ft.* | (722) | 465 | 582 | 582 | 698 | 698 |
| Consolidated Checkpoint - *Sq. Ft.* | -- | 931 | 1,047 | 1,164 | 1,280 | 1,396 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

**Table 4-50 – Security Screening Checkpoint Exit Lane Requirements (PALs)**

| Security Checkpoint Exit Lane Requirements | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Concourse A - *Sq. Ft.* | (2,639) | (2,639) | (2,639) | (2,639) | (2,639) | (2,639) |
| Concourse B - *Sq. Ft.* | (2,422) | (2,422) | (2,422) | (2,422) | (2,422) | (2,422) |
| Consolidated Checkpoint - *Sq. Ft.* | -- | 2,600[1] | 2,600[1] | 2,600[1] | 2,600[1] | 2,600[1] |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] the consolidated security checkpoint exit lane is calculated at a width of 15 feet.
Source: CHA, 2019.

### 4.4.12 Outbound Baggage Facilities

The operational functionality of the outbound baggage system at ORF consists of two components: The Checked Baggage Inspection System (CBIS) and the Baggage Handling System (BHS). The CBIS is utilized by TSA to screen passengers' checked baggage, increasing the safety of the traveling public. After being screened, the baggage is sorted via the airlines' Baggage Handling Systems, where the baggage is then transferred to the appropriate departing aircraft. This analysis looked at both components (CBIS and BHS) separately to determine the final quantities of equipment and the areas required throughout the planning horizon. Each of the six airlines (American, Delta, United, Southwest, Allegiant, Frontier) operating at ORF require baggage make-up facilities. Collectively, these existing facilities are currently housed in the ticketing lobby and behind the ticket lobby in a secure area outbound baggage make-up room. The baggage functions at ORF comprise approximately 30,876 square feet: approximately 4,550 SF in the ticketing lobby and approximately 26,326 SF in the baggage make-up area.

It should be noted that this analysis did not expand on the existing operational functionality of the outbound baggage at ORF. Rather, this analysis aimed to provide planning data for a consolidated and automated Checked Baggage Inspections System (CBIS) with an outbound Baggage Handling System (BHS), which would be located in a non-public area.

***Checked Baggage Inspection System Requirements (CBIS)***

**Table 4-51** depicts the requirements for developing a TSA sponsored and operated Check Baggage Inspection System (CBIS) at ORF.

### Table 4-51 – Checked Baggage Inspection System Requirements (CBIS) (PALs)

| Checked Baggage Inspection System Requirements (CBIS) | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| **Design Hour Baggage Load** | | | | | | |
| Design Hour PAX Checking In with Surge Factor = 1.25 – *No.* | | 1,693 | 1,921 | 2,159 | 2,382 | 2,575 |
| PAX Checking Bags – *No.* | | 40% | 40% | 40% | 40% | 40% |
| Average # of Bags per PAX – *No.* | | 1.2 | 1.2 | 1.2 | 1.2 | 1.2 |
| Bags to Process in Peak Hour – *No.* | | 813 | 922 | 1,036 | 1,143 | 1,236 |
| 10 Minute Baggage Flow Rate – *No.* | | 135 | 154 | 173 | 191 | 206 |
| TSA Surge Factor (Based on a 10 Minute Baggage Flow Rate) | | 1.17 | 1.16 | 1.15 | 1.14 | 1.14 |
| Equivalent Baggage Surge Rate | | 952 | 1.071 | 1,194 | 1,309 | 1,408 |
| % of Bags That are Over-sized & Too Big For EDS | | 3% | 3% | 3% | 3% | 3% |
| % of Over-sized Bags Requiring ETD Inspections | | 29% | 32% | 36% | 39% | 42% |
| Bags to Process Through Level 1 EDS Units – *No.* | | 924 | 1,039 | 1,158 | 1,270 | 1,366 |
| **EDS/ETD Equipment Requirements** | | | | | | |
| Level 1 EDS Screening – Process Rate (bags/hour) – *No.* | | 150 | 150 | 150 | 150 | 150 |
| Level 1 EDS Units Required – *No.* | | 7 | 7 | 8 | 9 | 10 |
| % of Scanned Bags Requiring Level 2 Screen **(Alarm Rate)** | | 25% | 25% | 25% | 25% | 25% |
| Bags Requiring Level 2 OSR – *No.* | | 231 | 260 | 290 | 317 | 341 |
| Level 2 OSR Rate (Bags/Hour per Operator) - *No.* | | 120 | 120 | 120 | 120 | 120 |
| Level 2 OSR Stations Required (1 Operator/Station) – *No.* | | 2 | 3 | 3 | 3 | 3 |
| % of Resolved OSR Bag reviews **(Clear Rate)** | | 80% | 80% | 80% | 80% | 80% |
| Bags Needing Level 3 Screening in Peak Hour – *No.* | | 75 | 85 | 94 | 103 | 111 |
| Level 3 ETD Screening - Process (Bags/Hour/Screener) | | 24 | 24 | 24 | 24 | 24 |
| Level 3 ETD Units Required (2 Screeners/Unit) – *No.* | | 2 | 2 | 2 | 3 | 3 |
| **Baggage Screening Requirements** | | | | | | |
| Level 1 Area Per EDS Screening Unit - *Sq. Ft.* | | 800 | 800 | 800 | 800 | 800 |
| Required EDS Units – *No.* | | 7 | 7 | 8 | 9 | 10 |
| Level 2 Area per OSR Station - *Sq. Ft.* | | 40 | 40 | 40 | 40 | 40 |
| OSR Stations Required - *No* | | 2 | 3 | 3 | 3 | 3 |
| Area per ETD Screening Units - *Sq. Ft.* | | 100 | 100 | 100 | 100 | 100 |
| Required ETD Units – *No.* | | 2 | 2 | 2 | 3 | 3 |
| TSA Offices - *Sq. Ft.* | | 200 | 200 | 300 | 300 | 400 |
| Total Area Requirements for CBIS - *Sq. Ft.* | | 6,080 | 6,120 | 7,020 | 7,920 | 8,820 |

Source: Airport Cooperative Research Program (ACRP) *Report 25 – Airport Passenger Terminal Planning and Design Guidebook*, CHA, 2019.

### *Outbound Baggage Handling System Requirements (BHS)*

This component of the outbound baggage process consisted of the screened and cleared baggage from the CBIS operation being sorted onto outbound baggage carousels for loading onto tug carts with ultimate delivery to departing aircraft. The analysis took a very conservative approach towards exclusive (individual) use in lieu of preferential (shared or common) use for outbound baggage carousel needs. **Table 4-52** indicates the outbound baggage area requirements, which offer a high degree of exclusive make-up device use, cart stacking, and circulation. It should be noted that the airlines were not actively involved with determining outbound baggage needs.

**Table 4-52 – Outbound Baggage System Area Requirements (BHS)**

| Outbound Baggage System Area Requirements[1] | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Outbound Baggage System Area Requirements - *Sq. Ft.* | (7,578)[2] | 23,000 | 25,000 | 26,500 | 26,500 | 28,000 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] U.S. Department of Transportation, Federal Aviation Administration, Systems Research & Development Service *Report No. FAA-RD-75-191 – The Apron & Terminal Building Planning Manual, Figure 4-16 dated July 1975*

[2] as indicated **Table 2-10**

Source: CHA, 2019.

### 4.4.13 Inbound Baggage Claim and Sortation

***Inbound Baggage Claim and Claim Devices***

The encompassing analysis below addressed both the baggage claim spatial needs for the passenger areas, as well as the capacity and requirements for the baggage claim devises. The first part of the analysis was based on the number of deplaning passengers within a peak 20-minute period to determine the requirements for the active retrieval area and baggage claim frontage, as indicated in **Table 4-53**. The peak hour deplaning data was also used in this analysis [**Table 3-36** (**Chapter 3**)]. For the purpose of this analysis, it was assumed that 50 percent of the deplaning passengers have checked a bag (40 percent at the ticketing counter and 10 percent at the gate). The analysis also assumed a LOS C (18 SF per person) for each individual within the active retrieval area at the baggage carousels. In addition, LOS C for claim frontage per person variable to calculate total claim frontage was required.

It should be noted that, upon observation, not all members of a traveling party (especially families with children) were typically at the claim unit. Rather, one member typically claimed the bags while the remaining members of the traveling party waited in the peripheral area. The number of traveling parties was calculated by taking the one member of the traveling party that actively claimed baggage and then added in the percentage of the additional passengers who may accompany that individual to the claim unit.

The methodology for determining claim device capacities and requirements was further evaluated, beginning with a peak 20-minute arrivals analysis. The forecasted peak hour arrival commercial operations are summarized in **Table 4-54.**

To determine peak hour arrivals, it was assumed that half the operations are peak hour arrivals. A factor of 50 percent was applied to the peak hour arrivals to produce the 20-minute peak arrivals.

### Table 4-53 – Deplaned PAX Baggage Claim Space Requirements (PALs)

| Deplaned PAX Baggage Claim Space Requirements | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | (Existing) | Input | Output | Input | Output | Input | Output | Input | Output | Input | Output |
| Peak Hour Deplaning PAX | | 1,022 | | 1,160 | | 1,304 | | 1,438 | | 1,555 | |
| % Deplaning in Peak 20 Minutes | | 50% | | 50% | | 50% | | 50% | | 50% | |
| % Terminating PAX | | 100% | | 100% | | 100% | | 100% | | 100% | |
| Peak 20 Min. Terminating PAX – *No.* | | | 511 | | 580 | | 652 | | 719 | | 778 |
| % PAX Checking Bags at TIX | | 40% | 204 | 40% | 232 | 40% | 260 | 40% | 288 | 40% | 311 |
| % PAX Gate Checking Bags | | 10% | 51 | 10% | 58 | 10% | 65 | 10% | 72 | 10% | 78 |
| PAX Checking Bags – *No.* | | | 255 | | 290 | | 325 | | 360 | | 389 |
| Average Travel Party Size – *No.* | | 1.3 | | 1.3 | | 1.3 | | 1.3 | | 1.3 | |
| Number of Parties – *No.* | | | 196 | | 223 | | 250 | | 278 | | 299 |
| % Additional People at Bag Claim | | 30% | | 30% | | 30% | | 30% | | 30% | |
| Total People at Claim Device – *No.* | | | 273 | | 310 | | 349 | | 384 | | 416 |
| Claim Frontage / Person - LF | | 1.5 | | 1.5 | | 1.5 | | 1.5 | | 1.5 | |
| Total Claim Frontage Required - *LF* | (841) | | 410 | | 465 | | 524 | | 576 | | 624 |
| Area/Person in Active Retrieval - *SF* | | 18 | | 18 | | 18 | | 18 | | 18 | |
| Total Area for Active Retrieval - *SF* | (9,165)[1] | | 4,914[1] | | 5,580[1] | | 6,282[1] | | 6,912[1] | | 7,488[1] |
| Claim Devices Area - *SF* | (6,630)[2] | | (6,630)[2] | | (6,630)[2] | | (6,630)[2] | | (6,630)[2] | | (6,630)[2] |
| Baggage Service Offices - *SF* | (2,986) | | (2,986) | | (2,986) | | (2,986) | | (2,986) | | (2,986) |
| Circulation - *SF* | (27,425) | | (27,425) | | (27,425) | | (27,425) | | (27,425) | | (27,425) |
| Total Baggage Claim - *SF* | (46,206) | | 41,955 | | 42,621 | | 43,323 | | 43,953 | | 44,529 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] not including area of claim device
[2] each claim device is 1,326 sq. ft x 5
Source: CHA, 2019.

### Table 4-54 – Commercial Peak Hour Airline Operations (PALs)

| Commercial Peak Hour Airline Operations | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Operations | (20) | 21 | 22 | 23 | 24 | 26 |
| Peak Hour Arrivals | (10) | 10.5 | 11 | 11.5 | 12 | 13 |
| 20-Minute Peak Arrivals | (5) | 5 | 6 | 6 | 6 | 7 |

Note: Those numbers depicted in parentheses indicate existing conditions
Source: CHA, 2019.

The analysis then normalized the aircraft to Group III Narrow-body aircraft with a 145-seat capacity. Each existing sloped bag claim device is 72 feet by 20 feet, with an effective claim frontage of 168 linear feet. The theoretical baggage storage on each carousel is 336 bags. The calculated practical operational storage was 225 bags. It was assumed that on a flight via a narrowbody aircraft, each passenger checks 1.2 bags. **Table 4-55** below demonstrates that each baggage claim device at ORF can accommodate two narrow-body flight baggage retrieval activities simultaneously. When taking into consideration the data in **Table 4-54** regarding the total number of narrow-body flights, the five existing baggage claim devices are capable of accommodating the 20-minute peak hour demands (depicted in **Table 4-53**) throughout the planning horizon.

**Table 4-55 – Baggage Claim Device Capacity (PALs)**

| Baggage Claim Device Capacity (PALs) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Input | Out | Input | Out | Input | Out | Input | Out | Input | Out | Input | Out |
| Narrow-body Seating Capacity | 145 | | 145 | | 145 | | 145 | | 145 | | 145 | |
| % Load Factor | 79% | | 79.5% | | 81.1% | | 82.2% | | 83.4% | | 84.2% | |
| Arriving PAX per Flight – *No.* | | 115 | | 116 | | 118 | | 120 | | 121 | | 123 |
| Bags per PAX – *No.* | 1.2 | | 1.2 | | 1.2 | | 1.2 | | 1.2 | | 1.2 | |
| Bags to Retrieve per Flight – *No.* | | 138 | | 139 | | 141 | | 144 | | 145 | | 148 |
| of Bag Claim Devices – *No.* | 5 | | 5 | | 5 | | 5 | | 5 | | 5 | |
| Baggage Storage per Device – *No.* | | 225 | | 225 | | 225 | | 225 | | 225 | | 225 |
| NB Flights /Device/20-min – *No.* | 1.0 | | 1.0 | | 1.2 | | 1.2 | | 1.2 | | 1.4 | |
| Bags at Each Device/20-min – *No.* | | 138 | | 139 | | 169 | | 172 | | 174 | | 207 |

Source: CHA, 2019.

### 4.4.14 Inbound Baggage Handling Sort Make-up and Feed Belts

The inbound baggage-feeds that connect to the baggage claim devices are located on a lower level under the baggage claim hall. The Airport has five baggage claim devices, with each device having one input belt-feed and the capability of accommodating two baggage tugs with carts; therefore, baggage for two arriving flights can be delivered on the same device simultaneously. This capacity is consistent with the findings from the analysis for the passenger claim devices. This analysis did not calculate the capacities for the inbound baggage handling sort and belt feed areas, but assumed the existing areas and capacities are balanced with the needs to accommodate passenger baggage claim.

### 4.4.15 Airline Baggage Service Offices (BSO)

Within the terminal and adjacent to the baggage claim devices are the airline baggage service offices, which comprise approximately 3,633 square feet of space. A typical baggage service office module at ORF is approximately 362 square feet and consists of a public service area, as well as a storage room. With all things being equal amongst the airlines in area requirements for their baggage service offices, the total existing area could support approximate 10 typical airline baggage service office modules through the planning horizon. **Table 4-56** summarizes the area needed for airline baggage service offices with the anticipated number of airline carriers in the ORF market.

**Table 4-56 – Airline Baggage Service Offices (PALs)**

| Airline Baggage Service Offices (PALs) | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | BASE | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| No. of Airlines | BSO Area | No. of Airlines | BSO Area | No. of Airlines | BSO Area | No. of Airlines | BSO Area | No, of Airlines | BSO Area | No. of Airlines | BSO Area |
| (6) | (3,633) | 6 | 2,172 | 6 | 2,172 | 6 | 2,172 | 7 | 2,534 | 8 | 2,890 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

### 4.4.16 U.S. Customs and Border Protection (CBP)/Federal Inspection Services (FIS)

ORF has a fully functioning Federal Inspection Services (FIS) at Concourse A that meets ORF's current needs and demands, with the ability process up to 175 passengers per hour. The facilities are also capable of handling aircraft as large as a Boeing 747, although, apron and terminal

constraints are present. ORF does not currently have scheduled international air carrier service; however, on occasion, the Airport will receive a diversion requiring the use of these facilities. U.S. Customs and Border Protection (CBP) will process the passengers. CBP also processes approximately three charter flights per year. This analysis assumed that ORF's current CBP facilities are adequate. Thus, an upgrade is not required to meet the current demand, subject to approval; however, if the Airport desires to provide scheduled international services, improvements and upgrades are warranted. The U.S. Customs and Border Protection's *Airport Technical Design Standards, 2006*, includes programmatic requirements for a CBP facility that can process up to 400 peak-hour arriving international passengers, which is the equivalent of two narrow-body flights, or up to one jumbo aircraft (Boeing 747), within one hour. The required spatial needs are represented in **Table 4-57**.

**Table 4-57 – U.S. Customs and Border Protection (CBP)/Federal Inspection Services (FIS)**

| U.S. Customs and Border Protection (CBP)/Federal Inspection Services (FIS) | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| CBP and International Arrivals – *Sq. Ft.* | (13,722) | 16,150 | 16,150 | 16,150 | 16,150 | 16,150 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: U.S. Customs and Border Protection, Airport Technical Design Standards, 2006, CHA, 2019.

### 4.4.17 Concessions

Concessions' space requirements represent the areas of the terminal facility directly related to and utilized for concessions, both airside and landside, including storage requirements. Each concession area requirement was divided into specific concession types: food and beverage, gift and news, and services such as advertising, information desks, banking, health counters, ATM, foreign currency exchange, etc.

The overall concession requirements were based on the formula in **Figure 4-8**.

**Figure 4-8 – Total Concession Calculation**

$$\textit{Total Concession Area (SF)} = \frac{\textit{Enplaned PAX} \times 18\ \textit{SF}}{1{,}000}$$

Industry standard planning guidelines would suggest the pre-security concessions encompass 10 percent of the total concession requirements for O&D airports, while post-security concessions would make up the remaining 90 percent. Given the characteristics of ORF, it was assumed that 20 percent of the total concessions are pre-security concessions; therefore, post-security concessions were calculated at 80 percent of the total concession requirements. The analysis did not strongly consider the validity of the percentage splits between food and beverage, gifts and news, and services; however, the percentage splits indicated for use in the analysis represented industry guidelines that have been generically applied. For this analysis, the splits between food and beverage, gifts and news, and services located pre-security were assumed at 55, 17, and 28 percent, respectively; however, post-security, the splits were assumed at 68, 31, and 1 percent, respectfully. Any significant improvements to the terminal would warrant changes to the Airport's current concessions program; therefore, it is suggested that ORF consider a comprehensive concession plan to address the market-centric variables in further detail to produce the best concessions plan moving forward.

The existing concession storage is shown as the "2017 (Existing)", as indicated in **Table 4-58**. The storage requirements throughout the planning period was calculated based on the percent increase in the projected total concessions space provided.

**Table 4-58 – Concession Areas (PALs)** [25]

| Concession Areas | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | BASE | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| **Pre-Security Concessions** | | | | | | |
| Food and Beverage - *Sq. Ft.* | (11,940) | 3,690 | 4,189 | 4,706 | 5,193 | 5,612 |
| Gifts and News - *Sq. Ft.* | (4,410) | 1,141 | 1,295 | 1,455 | 1,605 | 1,735 |
| Services - *Sq. Ft*. | (2,855) [1] | 1,879 | 2,132 | 2,396 | 2,644 | 2,858 |
| Subtotal - *Sq. Ft.* | (19,205) [3] | 6,710 | 7,616 | 8,557 | 9,442 | 10,205 |
| **Post-Security Concessions** | | | | | | |
| Food and Beverage - *Sq. Ft.* | (8,828) | 18,250 | 20,714 | 23,276 | 25,683 | 27,756 |
| Gifts and News - *Sq. Ft.* | (4,240) | 8,320 | 9,443 | 10,611 | 11,708 | 12,654 |
| Services - *Sf. Ft*. | (0) | 268 | 305 | 342 | 378 | 408 |
| Subtotal - *Sq. Ft*. | (13,068) [3] | 26,838 | 30,462 | 34,229 | 37,769 | 40,818 |
| **Total Retail Concessions (sf. ft.)** | **(32,273)** | **33,548** | **38,078** | **42,786** | **47,211** | **51,023** |
| Concessions Storage - *Sf. Ft.* | (2,217) [2] | 2,470 | 2,804 | 3,151 | 3,477 | 3,758 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] includes ATM/Foreign Currency Exchange/Mailbox Drop and Business Center as a Service concession

[2] as indicated in **Table 2-12**

[3] as indicated in **Table 2-10** or **Table 2-11**

Source: CHA, 2019.

### 4.4.18 Rental Car Concessions and Ground Transportation

***Rental Car Concessions***

Currently, eight rental car companies operate in the rental car center within the terminal building. In addition to space within the terminal, each rental car company has return/ready cars in the adjacent parking garage. From a planning perspective, the number of rental car concessionaires on-site is usually pre-determined as part of a Request for Proposal renewal process for rental car concessions, with a mutual understanding between the airport operator and the rental car companies. In the absence of criteria to determine metrics for planning, this analysis assumed a planning factor of 925 square feet per rental car company module. The rental car company module accounted for 20 linear feet of counters, 12-foot deep offices, 10-foot depth from the public face of the transaction counter to the back wall, and 15 feet for queuing with a 1.25 circulation factor.

Through the planning horizons, the current behaviors of how passengers engage the rental car companies and access/return a rental car are not expected to change; however, through the planning horizon, it was assumed that there will be one additional rental car company in the terminal building, bringing the total number of rental car operators from eight to nine.

[25] The analysis of concessions does not include the Airport's conference center, the USO Welcome Center, or rental car/transportation functions; however, a separate analysis was conducted for rental car/transportation functions (See **Section 4.4.18**).

**Table 4-59 – Rental Car Concessions (PALs)**

| Rental Car Concessions | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | | BASE | | | PAL 1 | | | PAL 2 | | | PAL 3 | | | PAL 4 | | |
| No. | LF | SF | No. | LF | SF | No. | LF | SF | No. | LF | SF | No. | LF | SF | No. | LF | SF |
| (8) | (163) | (12,210)[1] | 8 | 160 | 7,400 | 8 | 160 | 7,400 | 8 | 160 | 7,400 | 9 | 180 | 9,000 | 9 | 180 | 8,325 |

No. = Number of rental car companies on-site
LF = Linear feet of customer counter frontage
SF = Total square feet required for all rental car companies
Note: Those numbers depicted in parentheses indicate existing conditions.
[1] Includes passenger queuing area, miscellaneous storage area and circulation.
Source: CHA, 2019.

***Ground Transportation Services***

Ground Transportation Services comprise an area of 292 square feet at ORF. The current space meets the present demand and is expected to adequately support projected demand; therefore, there is not a need for the Airport to allocate additional space for use by ground transportation services during the planning horizon.

### 4.4.19 Administration Areas

***Airport Administration***

The Airport Administration areas of the terminal are those used by NAA staff for various Airport operations and include the following areas: administrative offices (14,240 SF), a conference center (2,164 SF), storage (12,075 SF), airport police and security badging offices (2,160 SF), and airport parking offices (2,506 SF), as well as internal circulation. Collectively, there is 33,145 square feet of airport administration space distributed between the different levels of the landside and airside areas of the terminal at different levels. Future needs for administrative office and support space, future staffing levels, and future facility needs correlate to passenger and facility growth, and what staffing levels and facilities are necessary, to support the overall administration needs. The needs were calculated using the formula in **Figure 4-9.**

**Figure 4-9 – Administration Demand Calculation**

FA = EA x (1.275 x .5FE) / 1.8, where:

- FA is the future program requirement to be calculated, in square feet
- EA is the 2017 (Existing) area, in square feet
- FE is the future enplanement level in Million Annual Enplanements

**Table 4-60** presents a summary of the Airport Administration programmatic space requirements throughout the planning horizon.

**Table 4-60 – Airport Administration Area (PALs)**

| Airport Administration Area | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Airport Administration Area - *Sf. Ft.* | (33,145) | 20,715 | 24,168 | 27,620 | 29,922 | 32,224 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

***TSA Administration***

Currently, TSA administration offices are located at an office complex near ORF; however, TSA has expressed interest in relocating the offices to the Airport.

The TSA administration category represents areas of the terminal directly related to TSA staff operations, specifically administrative offices and including internal circulation. To account for any staffing fluctuations throughout the planning horizon, the analysis assumed a three percent growth rate from one planning activity level to the next, as indicated in **Table 4-61.**

**Table 4-61 – TSA Administration Area (PALs)**

| TSA Administration Area | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| TSA Administration Area - *Sf. Ft.* | (2,828)[1] | 2,913 | 3,000 | 3,090 | 3,183 | 3,278 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] as indicated in **Table 2-12**
Source: CHA, 2019.

### 4.4.20 Restrooms Facilities

The restroom facilities analysis addressed public restroom facilities on both the non-secure (landside) and secure (airside) areas of the terminal buildings. It is important to note that private and non-public restroom facilities were not addressed in the analysis. On the non-secure portions of the airport terminal building (baggage claim, ticketing, etc.), the analysis was conducted as if all the processor areas were contiguously joined as one. The analysis for the secure portions of the airport terminal building (the concourses) was conducted given three separate assumptions:

- Assumption 1 – The Airport will operate two distinct concourses, similar to the existing arrangement.
- Assumption 2 – The Airport will operate three distinct concourses, with two of the three having an equal level of activity. Gate demand and associated needs will be driven by increased activity levels, which are assumed to be shared equally between the three concourses.
- Assumption 3 – The Airport will operate a conjoining concourse that will have a single security screening checkpoint, i.e., the concourse is not physically separated with each concourse requiring a separate security screening checkpoint processing area.

Optimal restroom layout plans provide partitions, giving staff the capability to close-off sections of the restroom for daily maintenance activity and renovations, while leaving other sections open for use. The need for airports to provide additional restroom amenities for passengers, such as family rooms, changing rooms, and nursing-mother rooms is a growing trend that is not addressed in local or national building codes. In addition, nursing-rooms are a requirement if federal funds are used for terminal development.

The analysis calculated the square footage requirements to support the optimal restroom layout based on the number of fixtures required for each module. The areas calculated included a diaper changing station and the door-less privacy entryway from the concourse circulation. Each

restroom module was assumed to have a mother's room (family room), as well as a custodial and service sink room, which were calculated separately.

Equivalent Aircraft (EQA) was the overarching basis of all analyses for restroom facilities. The EQA requirements throughout the planning horizons are indicated in **Table 4-33.** For the purpose of this analysis, a restroom module is defined as having separate men's and women's facilities, mother's room (family room), and a custodial area with a service sink.

***Secure Airside Terminal Restroom Facilities - Two Concourse Analysis***

The first step of the analysis was to determine the number of restroom modules necessary to service a concourse. **Figure 4-10** describes the methodology used when determining the number of modules.

**Figure 4-10 – Restroom Demand**

$$\text{No. of Restroom Modules} = \frac{EQA}{8}$$

**Figure 4-10** indicated the number of restroom modules required for each concourse throughout the planning horizon. The concourse layout was considered when determining the number of modules, e.g., single- vs. double-loaded concourses. For example, the spacing distance for modules in a double-loaded concourse is less than the required spacing distance for modules in a single-loaded concourse. The results of the analysis are depicted in **Table 4-62.** When reaching these results, the double-loaded corridor length (indicated in **Table 4-37**) was a significant factor to justify rounding up from one to two modules for each concourse.

**Table 4-62 – Two Concourses: Number of Restroom Modules Required (PALs)**

| Two Concourses: Number of Restroom Modules Required | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | EQA | (#) of Mod. | EQA[1] | (#) of Modules | EQA[1] | (#) of Modules | EQA[1] | (#) of Modules | EQA[1] | (#) of Modules | EQA[1] | (#) of Modules |
| Concourse A | -- | (1) | 13.4 | 1.675[2] (2)[3] | 13.7 | 1.713[2] (2)[3] | 14.4 | 1.800[2] (2)[3] | 14.4 | 1.800[2] (2)[3] | 15.4 | 1.925[2] (2)[3] |
| Concourse B | -- | (2) | 13.4 | 1.675[2] (2)[3] | 13.7 | 1.713[2] (2)[3] | 14.4 | 1.800[2] (2)[3] | 14.4 | 1.800[2] (2)[3] | 15.4 | 1.925[2] (2)[3] |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] the EQA values for each concourse is the activity level EQA value from Table 4-34 ÷ 2


[2] represents calculated theoretical value for number of modules required

[3] the theoretical value is rounded up to the next whole number

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design*, CHA, 2019.

The spacing of modules for single-loaded concourses and double-loaded concourses are depicted in **Figure 4-11**. The figure represents spacing of restroom modules in each concourse scenario for eight EQA. The frequency and spacing of restroom modules were consistent with the formula in **Figure 4-10**, which determined the number of restroom modules required based on a factor of eight EQA.

**Figure 4-11 – Loaded vs. Double-Loaded Concourse Exhibit**




From the data in **Table 4-62**, the peak passenger capacity (Design Passengers) was calculated using the formula shown in **Figure 4-12**. The results of the analysis are presented in **Table 4-63.**

**Figure 4-12 – Design Passengers Restroom Calculation**

*Design Passengers* = EQA x 145 Seats (1.0 EQA) x Load Factor

**Table 4-63 – Two Concourses: Design Passengers (PALs)**

| Two Concourses: Design Passengers | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Load Factor[1] | Design PAX | Load Factor[1] | Design PAX | Load Factor[1] | Design PAX | Load Factor[1] | Design PAX | Load Factor[1] | Design PAX | Load Factor[1] | Design PAX |
| Concourse A | (79.0) | -- | 79.5 | 1,545 | 81.1 | 1,611 | 82.2 | 1,716 | 83.4 | 1,741 | 84.2 | 1,880 |
| Concourse B | (79.0) | -- | 79.5 | 1,545 | 81.1 | 1,611 | 82.2 | 1,716 | 83.4 | 1,741 | 84.2 | 1,880 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] as indicated in **Figure 3-10**

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design*, CHA, 2019.

The next step in the analysis was determining the Peak 20-minute Passenger Demand for restroom facilities, using the formula in **Figure 4-13**.

**Figure 4-13 – Restroom Demand (20-min Peak)**

*Peak 20-Minute Passenger Demand* = Design Passenger x Peak 20-Minute %

*For concourse with only origin and destination (O & D) assume the Peak 20-Minute % = 50%*

### Table 4-64 – Two Concourses: Peak 20-Minute Restroom Demand (PALs)

| Two Concourses: Peak 20-Minute Restroom Demand | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Concourse A | -- | 773 | 806 | 858 | 871 | 940 |
| Concourse B | -- | 773 | 806 | 858 | 871 | 940 |

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The Design Factor calculated using the formula in **Figure 4-14** was the variable that allowed us to calculate the fixtures required. These factors are tabulated in **Table 4-65.**

### Figure 4-14 – Restroom Demand (Two Concourses)

*Design Factor* = Peak 20-Minute Passenger Demand x % Using Restroom *(utilization)*

*Note: The general utilization rate planning standard = 50% to 60%. For this analysis, 60% is used*

### Table 4-65 – Two Concourses: Design Factor (PALs)

| Two Concourses: Design Factor | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Concourse A | -- | 464 | 484 | 515 | 523 | 564 |
| Concourse B | -- | 464 | 484 | 515 | 523 | 564 |

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The formulas represented in **Figure 4-15** and **Figure 4-16** was used to determine the total number of men's and women's fixtures respectfully. A fixture is defined as a toilet or urinal. These fixture requirements are tabulated in **Table 4-66.**

### Figure 4-15 – Men's Fixtures Calculation (Separate Concourses)

*Men's Fixtures* = Design Factor x Male % ÷ 13

*Note: The passenger gender mix ratio is assumed to be a 50%/50% ratio*

### Figure 4-16 – Women's Fixtures Calculation (Separate Concourses)

*Women's Fixtures* = Male Fixtures x Female Increase Factor

*Note: The Female Increase Factor = 1.25*

### Table 4-66 – Two Concourses: Required Fixtures (PALs)

| Two Concourses: Required Fixtures | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Concourse A Men's | (24)[1] | 17.84 | 18.61 | 19.80 | 20.11 | 21.69 |
| Concourse A Women's | (22) | 22.30 | 23.27 | 24.75 | 25.14 | 27.11 |
| Concourse B Men's | (31)[2] | 17.84 | 18.61 | 19.80 | 20.11 | 21.69 |
| Concourse B Women's | (30) | 22.30 | 23.27 | 24.75 | 25.14 | 27.11 |

Note: Those numbers depicted in parentheses indicate existing conditions

[1] 12 water closets/12 urinals

[2] 13 water closets/18 urinals

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

Fixtures required for each module was then calculated with the formula in **Figure 4-17** and fixtures tabulated in **Table 4-67.**

### Figure 4-17 – Restroom Fixture Calculation (Two Concourse)

*Fixtures Required for Each Modules* = Required Fixtures ÷ No. Modules Required

### Table 4-67 – Two Concourses: Fixtures Required per Module (PALs)

| Two Concourses: Fixtures Required per Module[1] | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | | Base | | PAL 1 | |
| | No. of Modules | Fixture No. | # of Modules[1] | Fixture No. | # of Modules[1] | Fixture No. |
| Concourse A Men's | (1) | (24)[2] | 2 | 9 | 2 | 10 |
| Concourse A Women's | (1) | (22)[2] | 2 | 12 | 2 | 12 |
| Concourse B Men's | (2) | (31)[2] | 2 | 9 | 2 | 10 |
| Concourse B Women's | (2) | (30)[2] | 2 | 12 | 2 | 12 |

| Two Concourses: Fixtures Required per Module[1] | | | | | | |
|---|---|---|---|---|---|---|
| | PAL 2 | | PAL 3 | | PAL 4 | |
| | No. of Modules | Fixture No. | # of Modules[1] | Fixture No. | # of Modules[1] | Fixture No. |
| Concourse A Men's | 2 | 11 | 2 | 11 | 2 | 11 |
| Concourse A Women's | 2 | 13 | 2 | 13 | 2 | 14 |
| Concourse B Men's | 2 | 11 | 2 | 11 | 2 | 11 |
| Concourse B Women's | 2 | 13 | 2 | 13 | 2 | 14 |

Note: Those numbers depicted in parentheses indicate existing conditions.

[1] number of restroom modules required is shown in Table 4-35

[2] two modules per existing concourse

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The formulas used for calculating Concourse Men's and Women's Room area is shown in **Figure 4-18** and **Figure 4-19** respectfully and the areas are tabulated in **Table 4-68** and **Table 4-69** respectfully.

### Figure 4-18 – Men's Rest Area Calculation

*Men's Room Area* = Required Fixtures x 85 SF per Fixture Required

### Figure 4-19 – Women's Rest Area Fixture Calculations

*Women's Room Area* = Required Fixtures x 95 SF per Fixture Required

### Table 4-68 – Two Concourses: Single Module Area Requirements (PALs)

| Two Concourses: Single Module Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Men's - *Sq. Ft.* | -- | 765 | 850 | 935 | 935 | 935 |
| Women's - *Sq. Ft.* | -- | 1,140 | 1,140 | 1,235 | 1,235 | 1,330 |
| Mother's Room (Family)- *Sq. Ft.* | (105) | 105 | 105 | 105 | 105 | 105 |
| Custodial - *Sq. Ft.* | (156) | 156 | 156 | 156 | 156 | 156 |
| Module Total - *Sq. Ft.* | -- | 2,166 | 2,251 | 2,431 | 2,431 | 2,526 |

Note: Those numbers depicted in parentheses indicate existing condition.

Source: CHA, 2019.

**Table 4-69 – Two Concourses: Total Restroom Module Area Requirements (PALs)**

| Two Concourses: Total Restroom Module Area Requirements | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | Modules | Area | Modules | Area | Modules | Area | Modules | Area | Modules | Area | Modules | Area |
| Concourse A - *Sq. Ft.* | (1) | (3,745) | 2 | 4,332 | 2 | 4,502 | 2 | 4,862 | 2 | 4,862 | 2 | 5,052 |
| Concourse B - *Sq. Ft.* | (2) | (7,718) | 2 | 4,332 | 2 | 4,502 | 2 | 4,862 | 2 | 4,862 | 2 | 5,052 |
| Totals | (3) | (9,463) | 4 | 8,664 | 4 | 9,004 | 4 | 9,724 | 4 | 9,724 | 4 | 10,104 |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

***Secure Airside Terminal Restroom Facilities – Three Concourse Analysis***

This analysis assumed that the Airport will operate three separate concourses in a similar fashion to ORF's current situation with two separate concourses. The analysis was similar to the *Two-Concourse Analysis* and assumed all three concourses are equal. **Table 4-70** indicates the number of restroom modules required for each separate concourse, as well as the number of toilet fixtures necessary to service each module. The analysis concluded with *Single Module Area Requirements*, depicted in **Table 4-71**, and *Total Restroom Module Area Requirements,* depicted in **Table 4-72.**

**Table 4-70 – Three Concourses: Fixtures Required per Module (PALs)**

| Three Concourses: Fixtures Required per Module | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | | Base | | PAL 1 | |
| | No. of Modules | Fixture No. | # of Modules[1] | Fixture No. | # of Modules[1] | Fixture No. |
| Concourse A Men's | (1) | (24)[1] | 1 | 12 | 1 | 13 |
| Concourse A Women's | (1) | (22)[1] | 1 | 15 | 1 | 16 |
| Concourse B Men's | (2) | (30)[1] | 1 | 12 | 1 | 13 |
| Concourse B Women's | (2) | (31)[1] | 1 | 15 | 1 | 16 |
| Concourse C Men's | NA | NA | 1 | 12 | 1 | 13 |
| Concourse C Women's | NA | NA | 1 | 15 | 1 | 16 |

| Three Concourses: Fixtures Required per Module | | | | | | |
|---|---|---|---|---|---|---|
| | PAL 2 | | PAL 3 | | PAL 4 | |
| | # of Modules[1] | Fixture No. | # of Modules[1] | Fixture No. | # of Modules[1] | Fixture No. |
| Concourse A Men's | 1 | 14 | 1 | 14 | 1 | 15 |
| Concourse A Women's | 1 | 17 | 1 | 17 | 1 | 18 |
| Concourse B Men's | 1 | 14 | 1 | 14 | 1 | 15 |
| Concourse B Women's | 1 | 17 | 1 | 17 | 1 | 18 |
| Concourse C Men's | 1 | 14 | 1 | 14 | 1 | 15 |
| Concourse C Women's | 1 | 17 | 1 | 17 | 1 | 18 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] two modules per existing concourse.
Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

**Table 4-71 – Three Concourses: Single Module Area Requirements (PALs)**

| Two Concourses: Single Module Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| | 2017 (Existing) | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Men's - *Sq. Ft.* | -- | 1,020 | 1,105 | 1,190 | 1,190 | 1,275 |
| Women's - *Sq. Ft.* | -- | 1,425 | 1,520 | 1,615 | 1,615 | 1,710 |
| Mother's Room (Family) - *Sq. Ft.* | (105) | 105 | 105 | 105 | 105 | 105 |
| Custodial - *Sq. Ft.* | (156) | 156 | 156 | 156 | 156 | 156 |
| Module Total - *Sq. Ft.* | -- | 2,706 | 2,886 | 3,066 | 3,066 | 3,246 |

Note: Those numbers depicted in parentheses indicate existing conditions
Source: CHA, 2019.

**Table 4-72 – Three Concourse: Total Restroom Module Area Requirements (PALs)**

| Three Concourse: Total Restroom Module Area Requirements | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | No. Of Modules | Total Area | No. of Modules | Total Area | No. of Modules | Total Area | No. of Modules | Total Area | No. of Modules | Total Area |
| Totals | 3 | 8,118 | 3 | 8,658 | 3 | 9,198 | 3 | 9,198 | 3 | 9,738 |

Source: CHA, 2019.

***Secure Airside Terminal Restroom Facilities - Connected Concourse Analysis***

This analysis assumed that the Airport will operate a concourse that is contiguous with a single security screening checkpoint (i.e., the concourse is not physically separated with each concourse requiring its own separate security screening checkpoint processing areas). The analysis was similar to the *Two-Concourse Analysis*; therefore, this analysis concluded with *Single Module Area Requirements,* depicted in **Table 4-73,** and *Total Restroom Module Area Requirements*, depicted in **Table 4-74.**

**Table 4-73 – Connected Concourse: Single Module Area Requirements (PALs)**

| Connected Concourse: Single Module Area Requirements | | | | | |
|---|---|---|---|---|---|
| | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Men's - *Sq. Ft.* | 1,020 | 765 | 850 | 850 | 935 |
| Women's - *Sq. Ft.* | 1,425 | 1,140 | 1,235 | 1,235 | 1,330 |
| Mother's Room (Family) - *Sq. Ft.* | 105 | 105 | 105 | 105 | 105 |
| Custodial - *Sq. Ft.* | 156 | 156 | 156 | 156 | 156 |
| Module Total - *Sq. Ft.* | 2,706 | 2,166 | 2,346 | 2,346 | 2,526 |

Source: CHA, 2019.

**Table 4-74 – Connected Concourse: Total Restroom Module Area Requirements (PALs)**

| Connected Concourse: Total Restroom Module Area Requirements | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | No. of Modules | Total Area | No. of Modules | Total Area | No. of Modules | Total Area | No, of Modules | Total Area | No. of Modules | Total Area |
| Totals | 3 | 8,118 | 4 | 8,664 | 4 | 9,424 | 4 | 9,424 | 4 | 10,104 |

Source: CHA, 2019.

***Non-Secure Landside Terminal Restroom Facilities – Baggage Claim, Ticketing, Concessions, Pre-Security***

Landside restrooms are typically located within the major terminal areas such as the check-in lobby, baggage claim, and concessions areas. Calculations were based on the total peak-hour O&D passenger demand (PHP) and the visitors of those passengers. Visitor ratios were assumed

to increase the demand by a factor of 20 percent for well-wishers (WW) and 30 percent for meeters and greeters (M&G). Since enplaning and deplaning passenger processing functions (such as check-in/baggage claim, respectively) are on separate levels at ORF, the analysis utilized the associated visitor ratios with their respective passenger processing functions as shown in **Figure 4-20**.

**Figure 4-20 – Restroom Facility Calculation**

WW + *enplaning passengers*

and

M&G + *deplaning passengers*

The analysis assumed evaluation methodologies associated with a multi-level terminal building. Similar to the airside analysis, the scenario began by determining the landside Design Passenger Demand for each of the functional areas.

**Check-in Restroom Facilities Determinations:** The Check-in Design Demand was calculated with the formula in **Figure 4-21.** The design demands are shown in **Table 4-75.**

**Figure 4-21 – Check-In Fixtures Calculation**

*Check-in Design Demand* = Enplaning Peak-Hour Passengers x WW Ratio

*Note: WW Ratio = 1.20*

**Table 4-75 – Non-Secure Landside: Check-in Restroom Design Demand (PALs)**

| Non-Secure Landside: Check-in Restroom Design Demand | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Enplane PHP | Design Demand | Enplane PHP | Design Demand | Enplane PHP | Design Demand | Enplane PHP | Design Demand | Enplane PHP | Design Demand |
| 1,354 | 1,625 | 1,537 | 1,844 | 1,727 | 2,072 | 1,906 | 2,287 | 2,060 | 2,472 |

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The quantity of fixtures were determined from the Design Demand for Men's and Women's restroom facilities as shown by the formulas in **Figure 4-22** and **Figure 4-23,** respectfully, and the number of fixtures required was based on gender as indicated in **Table 4-76**.

**Figure 4-22 – Check-In Male Fixtures Calculation**

*Check-in Total Male Fixtures* = Design Demand ÷ Ratio

*Note: Ratio = 1 fixture per 70 enplaning PHP for first 400 enplaning PHP + 1 fixture per 200 enplaning PHP in excess of 400 enplaning PHP*

**Figure 4-23 – Check-In Female Fixtures Calculation**

*Check-in Total Female Fixtures* = Total Male Fixtures x Female Increase Factor

*Note: Female Increase Factor = 1.00*

### Table 4-76 – Non-Secure Landside: Check-in Men's and Women's Fixture Requirements (PALs)

| Non-Secure Landside Check-in: Men's and Women's Fixture Requirements | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| M | W | M | W | M | W | M | W | M | W | M | W |
| (12)[1] | (10)[1] | 12 | 12 | 13 | 13 | 14 | 14 | 15 | 15 | 16 | 16 |

M = Men's
W = Women's
Note: Those numbers depicted in parentheses indicate existing conditions.
[1] number of fixtures in the Check-in level and area only
Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

**Baggage Claim Facilities Determinations:** The terminal Design Demand was calculated with the formula in **Figure 4-24** and the Design Demands are indicated in **Table 4-77**.

### Figure 4-24 – Baggage Claim Demand

*Baggage Claim Design Demand* = Deplaning Peak-Hour Passengers x M & G Ratio
*Note: M & G Ratio = 1.30*

### Table 4-77 – Non-Secure Landside: Baggage Claim Restroom Design Demand (PALs)

| Non-Secure Landside: Baggage Claim Restroom Design Demand | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Deplane PHP | Design Demand | Deplane PHP | Design Demand | Deplane PHP | Design Demand | Deplane PHP | Design Demand | Deplane PHP | Design Demand |
| 1,022 | 1,329 | 1,160 | 1,508 | 1,304 | 1,695 | 1,438 | 1,869 | 1,555 | 2,022 |

Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The quantity of fixtures could be determined from the Design Demand for Men's and Women's restroom facilities as indicated in **Figure 4-25** and **Figure 4-26,** respectfully, and the fixture requirements are depicted in **Table 4-78.**

### Figure 4-25 – Baggage Claim Male Fixtures Calculation

*Baggage Claim Total Male Fixtures* = Design Demand ÷ Ratio
*Note: Ratio = 1 fixture per 70 deplaning PHP for first 400 deplaning PHP + 1 fixture per 200 deplaning PHP in excess of 400 deplaning PHP*

### Figure 4-26 – Baggage Claim Female Fixtures Calculation

*Baggage Claim Total Female Fixtures* = Total Male Fixtures x Female Increase Factor
*Note: Female Increase Factor = 1.00*

### Table 4-78 – Non-Secure Landside: Baggage Claim Men's and Women's Fixture Requirements (PALs)

| Non-Secure Landside: Baggage Claim Men's and Women's Fixture Requirements | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| M | W | M | W | M | W | M | W | M | W | M | W |
| (16)[1] | (12)[1] | 10 | 10 | 11 | 11 | 12 | 12 | 13 | 13 | 14 | 14 |

M = Men's / W = Women's
Note: Those numbers depicted in parentheses indicate existing conditions.
[1] number of fixtures in the Baggage Claim level and area only
Source: Airport Cooperative Research Program (ACRP) *Report 130 - Guidebook for Airport Terminal Restroom Planning and Design,* CHA, 2019.

The methodology for calculating the required toilet fixture was determined using the analytics for a multi-level terminal and addressed toilet fixture requirements for only the check-in lobby and baggage claim. For multi-level terminals, restrooms should be located in proximity to the major passenger processing functions such as check-in, baggage claim, security screening, meeter and greeter areas, and major landside concession nodes. The atrium area, unique to ORF, provides concession opportunities and a large concentration of public restrooms, as it is often used as a circulation hub that is heavily populated with well-wishers and meter/greeter personnel. All passengers, whether enplaning or deplaning, must pass through the atrium with area specific restrooms before accessing the check-in or baggage claim areas. Given ORF's physical configuration, locations of functional areas, and passenger flow, it may be acceptable to assume that the atrium restrooms also help satisfy the restroom requirements for the check-in lobby and baggage claim, as indicated in **Table 4-75** and **Table 4-77**, respectfully.

The following analysis took the physical configuration, locations of the functional areas, and passenger flow for the Airport's terminal into consideration. Again, the unique characteristics of this terminal is the Atrium space, which the analytics did not directly address; therefore, to normalize the fixture requirements with the existing check-in lobby, baggage claim, and atrium, the atrium analysis assumed similar logic to determine the fixtures required for the check-in lobby and baggage claim. The requirements for men's and women's restrooms were determined using the following formulas, as shown in **Figure 4-27** and **Figure 4-28**, respectfully.

**Figure 4-27 – Male Fixtures Calculation**

*Atrium Male Fixtures* = (Enplaning Design Demand + Deplaning Design Demand) x 0.50 ÷ Ratio

*Note: Ratio = 1 fixture per 70 deplaning PHP for first 400 deplaning PHP + 1 fixture per 200 deplaning PHP in excess of 400 deplaning PHP*

**Figure 4-28 – Female Fixtures Calculation**

*Atrium Total Female Fixtures* = Total Male Fixtures x Female Increase Factor

*Note: Female Increase Factor = 1.25*

Summarized below is in **Table 4-79** are total fixture requirements, while comparing the existing fixtures to the required fixtures through the planning horizon.

**Table 4-79 – Non-Secure Landside: Total Fixtures Requirements (PALs)**

| Non-Secure Landside: Total Fixture Requirements | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Processor Area | 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| | M | W | M | W | M | W | M | W | M | W | M | W |
| Check-in Lobby – *No.* | (12) | (10) | 12 | 12 | 13 | 13 | 14 | 14 | 15 | 15 | 16 | 16 |
| Baggage Claim – *No.* | (16) | (12) | 10 | 10 | 11 | 11 | 12 | 12 | 13 | 13 | 14 | 14 |
| Atrium – *No.* | (32) | (14) | 11 | 14 | 12 | 15 | 13 | 16 | 14 | 18 | 15 | 19 |
| Totals | (60) | (36) | 33 | 36 | 36 | 39 | 39 | 42 | 42 | 46 | 45 | 49 |

M = Men's
W = Women's
Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

The restroom area calculations assumed that each processor area (check-in lobby, baggage claim, and atrium) will each have two restroom modules; therefore, the total fixture requirements for each processor area (indicated in **Table 4-79**) were divided by a factor of two, thus, representing

a single restroom module. In addition, each module included a diaper changing station, as well as door-less privacy entryway from the public circulation area. Each restroom module was assumed to have a mother's room (family room), as well as a custodial and service sink room, which were calculated separately. The single restroom module areas are indicated in **Table 4-80**.

The formulas used for calculating landside Men's and Women's Room area are shown in **Figure 4-29** and **Figure 4-30,** respectfully, and the requirements are shown in **Table 4-80** and **Table 4-81**, respectfully.

**Figure 4-29 – Men's Rest Area Calculation**

*Men's Room Area* = Required Fixtures x 85 SF per Fixture Required

**Figure 4-30 – Women's Rest Area Calculation**

*Women's Room Area* = Required Fixtures x 95 SF per Fixture Required

**Table 4-80 – Non-Secure Airside: Single Restroom Module Area Requirements (PALs)**

| Non-Secure Airside: Single Restroom Module Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| **Functional Areas** | **2017 (Existing)** | **Base** | **PAL 1** | **PAL 2** | **PAL 3** | **PAL 4** |
| Check-in Men's (sq. ft.) | (231) | 510 | 595 | 595 | 680 | 680 |
| Check-in Women's (sq. ft.) | (231) | 570 | 665 | 665 | 760 | 760 |
| Mother's/Family Room (sq. ft.) | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial (sq. ft.) | (200) | 156 | 156 | 156 | 156 | 156 |
| **Check-in Single Module Total (sq. ft.)** | **(662)** | **1,341** | **1,521** | **1,521** | **1,701** | **1,701** |
| Baggage Claim Men's (sq. ft.) | (480) | 425 | 510 | 510 | 595 | 595 |
| Baggage Claim Women's (sq. ft.) | (457) | 475 | 570 | 570 | 665 | 665 |
| Mother's/Family Room (sq. ft.) | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial (sq. ft.) | (91) | 156 | 156 | 156 | 156 | 156 |
| **Baggage Claim Module Single Total (sq. ft.)** | **1,028** | **1,161** | **1,341** | **1,341** | **1,522** | **1,522** |
| Atrium Men's (sq. ft.) | (710) | 510 | 510 | 595 | 595 | 680 |
| Atrium Women's (sq. ft.) | (790) | 665 | 760 | 760 | 855 | 950 |
| Mother's/Family Room (sq. ft.) | -- | 105 | 105 | 105 | 105 | 105 |
| Custodial (sq. ft.) | (75) | 156 | 156 | 156 | 156 | 156 |
| **Atrium Single Module Total (sq. ft.)** | **1,575** | **1,436** | **1,531** | **1,616** | **1,711** | **1,891** |

Note: Those numbers depicted in parentheses indicate existing conditions.
Source: CHA, 2019.

**Table 4-81 – Non-Secure Airside: Total Restroom Module Area Requirements (PALs)**

| Non-Secure Airside: Total Restroom Module Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| **Processor Area** | **2017 (Existing)** | | **Base** | | **PAL 1** | |
| | **No. of Modules** | **Total Area** | **No. of Modules** | **Total Area** | **No. of Modules** | **Total Area** |
| Check-in (sq. ft.) | (2) | (1,324) | 2 | 2,682 | 2 | 3,042 |
| Bag Claim (sq. ft.) | (2) | (2,056) | 2 | 2,322 | 2 | 2,682 |
| Atrium (sq. ft.) | (2) | (3,150) | 2 | 2,872 | 2 | 3,062 |
| Totals | (6) | (6,530) | 6 | 7,876 | 6 | 8,786 |

| Non-Secure Airside: Total Restroom Module Area Requirements | | | | | | |
|---|---|---|---|---|---|---|
| Processor Area | PAL 2 | | PAL 3 | | PAL 4 | |
| | No. of Modules | Total Area | No. of Modules | Total Area | No. of Modules | Total Area |
| Check-in (sq. ft.) | 2 | 3,042 | 2 | 3,402 | 2 | 3,402 |
| Bag Claim (sq. ft.) | 2 | 2,682 | 2 | 3,044 | 2 | 3,044 |
| Atrium (sq. ft.) | 2 | 3,232 | 2 | 3,422 | 2 | 3,782 |
| Totals | 6 | 8,956 | 6 | 9,868 | 6 | 10,228 |

Note: Those numbers depicted in parentheses indicate existing conditions
Source: CHA, 2019.

### 4.4.21 Terminal Circulation

***Meeter and Greeter Lobby (Well-Wishers)***

ORF has a larger demand for meeter and greeter area than other airports, as there is a larger presence of regional military passengers. The atrium space serves as an area where these passengers can congregate with well-wishers and meters/greeters. The existing atrium meeter and greeter area is approximately 9,382 square feet. In interviews with ORF, it was confirmed yhat this area, at certain times, can reach capacity with meeter and greeters.

This analysis assumed a generic factor of 10 percent for the peak hour deplaning passengers, along with a 1.25 surge factor, to determine number of meeter and greeters. The result was then multiplied by 23 square feet, per the IATA LOS standard, to determine the overall meeter and greeter area requirements. The areas calculated through the planning horizon are substantially less than the existing area. To reduce this area for future terminal uses could cause an unacceptable LOS to the meeter and greeter area regardless of what the analytics indicate as acceptable to meet the theoretical need.

**Table 4-82 – Meeter and Greeter Area (PALs)**

| Meeter and Greeter Area | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017 (Existing) | | Base | | PAL 1 | | PAL 2 | | PAL 3 | | PAL 4 | |
| Deplane PAX Factor | Area (sf) | Deplane Pax Factor | Area (sf) | Deplane PAX Factor | Area (sf) | Deplane PAX Factor | Area (sf) | Deplane PAX Factor | Area (sf) | Deplane PAX Factor | Area (sf) |
| (1,151)[1] | (9,382) | 1,277[1] | 2,937 | 1,450[1] | 3,335 | 1,630[1] | 3,749 | 1,797[1] | 4,133 | 1,944[1] | 4,471 |

Note: Those numbers depicted in parentheses indicate existing conditions.
[1] with 1.25 surge factor
Source: CHA, 2019.

***Horizontal Circulation Area***

An overall circulation value for the terminal was not computed for this analysis, as the horizontal circulation area needs for each of the processor areas within the terminal were indicated within each processor area analyses. It should be noted; the analysis did not compute an overall inclusive circulation value for the terminal building. The processor areas with horizontal circulation values calculated and indicated separately in a tabular format are as follows:

- Re: Section 4.4.7 – Concourse Circulation
- Re: Section 4.4.8 – Check-in Circulation
- Re: Section 4.4.11 – SSCP Exit Lane

- Re: Section 4.4.13 – Inbound Baggage Claim
- Re: Section 4.4.18 – Rental Car Concessionaires
- Re: Section 4.4.21 – Meeter and Greeter Lobby

The area determinations calculated for functional areas within the terminal (i.e., administration areas, outbound baggage facilities, etc.) included considerations for internal circulation.

***Public Elevators, Escalators and Stairs***

A review of the public escalators and stairs within the terminal build was conducted. Through the process, comments were not received in regard to inadequate public escalators and stairs. While the following analysis did not attempt to quantify public escalator and stair requirements in terms of "square feet", the following comments were offered during the review:

- **Baggage Claim Facilities:** Currently, the Airport has one vertical circulation module within the bag claim area that consists of a stair system and two escalators (up/down). The module serves the passenger foot traffic from the parking areas, as well as the vertical movement to access the walkway leading to the check-in, atrium, security checkpoint, and gate areas. A bank of three elevators is located nearby for easy access. Located further to the southwest is another vertical circulation module consisting of a stair system, along with a bank of three elevators located nearby for easy access. During the planning period, NAA may want to consider redundant escalator capacity with the existing escalators by adding additional escalators, more heavily weighted with a "down" escalator at the northwest vertical circulation core as a minimum.
- **Check-in Hall/Atrium:** The Airport has two vertical circulation modules within the check-in hall/atrium that consist of a stair system and two escalators (up/down). These modules serve the passenger foot traffic between the two separate check-in wings, atrium, security checkpoint, and gate level. The two vertical circulation modules also offer the public an inherent redundant to the existing escalators for automated vertical people movers; however, the two check-in halls are physically separated by the outbound baggage functional areas and not clear and intuitive, thus diminishing any valued redundancy characteristics with the overall systems. Two public elevators are located in a hall connecting the two check-in wings.[26] The hall and the location of the public elevators are unintuitive for use from a passenger perceptive. Without addressing the separation issue between the two check-in wings, ORF may want to consider redundancy in regard to escalator capacity with the existing escalators by adding additional escalators, more heavily weighted with "up" escalators. At a minimum, it is suggested that ORF abandon the existing elevators in the connecting hall for public use and add two elevators in plain sight, thus improving the intuitive passenger flow pattern near each existing vertical circulation module.

[26] The elevators co-located with the escalators in the check-in halls are currently under construction, with the project concluding prior to the completion of the Master Plan Update.

***Moving Walkway***

Moving walkways are often considered for use in airports when walking distances between major terminal functions within the terminal complex area exceed 1,000 feet. The Airport's connecting elevated walkway is 360-feet long and allows passengers to travel safely between the parking and baggage claim areas to the check-in hall, atrium, security checkpoint, and gates without crossing the terminal road curb front complex at grade. The furthest available parking space in the parking garage is approximately 2,225 feet from the end of Concourse B; therefore, the need for a moving walkway can be justified.

It should be noted that, in the past, ORF had a moving walkway in the elevated connecting walkway between the baggage claim building and the check-in/atrium building. The moving walkway has since been removed without providing a replacement for passenger convenience. To add valued passenger convenience, it is recommended that the Airport reinstall a two-directional moving walkway in the elevated connecting walkway between the baggage claim building and the check-in/atrium building.

### 4.4.22 Service Animal Relief Areas

Per Title 49 Code of Federal Regulations (CFR) Part 27.71 (h)[27], *Service Animal Relief Areas*, "each airport with 10,000 or more annual enplanements shall provide wheelchair-accessible Service Animal Relief Areas (SARAs) for service animals that accompany passengers departing, connecting, or arriving at airports." Furthermore, per AC 150/5360-14A (Appendix A), *Guidelines for Service Animal Relief Areas*[28], "at least one SARA must be located in each public sterile area of each terminal." Since ORF only has one terminal, one security checkpoint, and one sterile area, only one SARA is required. Currently, the Airport provides one service animal relief area; however, the designated area is located in the non-sterile area outside and to the south of the departures building. Service animal relief areas are further addressed in **Chapter 5**.

## 4.5 SUPPORT FACILITY REQUIREMENTS

A review of existing and future support facilities was necessary to identify additional facilities needed over the 20-year planning horizon.

### 4.5.1 General Aviation and MRO Facilities

Hangar requirements are generally a function of the number and type of based aircraft, owner preferences, hangar rental costs, and area climate.

Due to weather conditions, hangars are highly desirable in the Norfolk, Virginia region as snowstorms, frost, ice, and intense wind can cause damage to parked aircraft. Additionally, during warmer months, heat and sun exposure can damage avionics and fade paint. Thunderstorms and hailstorms also occur, with the potential to cause considerable amounts of damage.

At ORF, available Airport property and future expansion space for the GA area is limited. Taxiway 'A' to the north, Taxiway 'J' and the ILS critical area to the northwest, the safety areas for the

[27] Title 49 CFR Part 27.71, *Airport Facilities.*

[28] AC 150/5360-14A, *Access to Airports by Individuals with Disabilities*

departure end of Runway 32 to the north, and Miller Store Road to the south of the GA area impede future growth. Based on the needs identified in this section, alternatives for additional hangar placement within Airport property is discussed in **Chapter 5**.

***General Aviation Aircraft Storage Requirements***

Locally based operators at ORF employ use of hangar space. The hangar storage areas, which are leased to the various aircraft owners, consist of six bulk-hangars (i.e., corporate hangars) and three T-hangar buildings (one building containing 11 stalls and two that each contain 16 stalls each). **Table 4-83** identifies the breakdown of aircraft based at ORF, while **Table 4-84** depicts each type of storage hangar at the airport, its approximate size, and the amount of storage provided for based aircraft at ORF (excluding tie-down spaces).

**Table 4-83 – Based Aircraft Leasing Hangar Spaces (As of July 2018)**

| Aircraft Type | Corporate Hangars | T-Hangars |
|---|---|---|
| Single Engine Piston | 8 | 32 |
| Multi Engine Piston | 7 | 3 |
| Single Engine Turbo Prop | 1 | - |
| Multi Engine Turbo Prop | 6 | - |
| Multi Engine Jet | 20 | - |
| Helicopter | 2 | - |
| **TOTAL:** | **44** | **35** |

Source: Signature, NAA, CHA, 2018.

**Table 4-84– Aircraft Hangar Units**

| Hangar Type | Approximate Size (Sq. Ft.) | Aircraft Storage Capability (Typical – Types Assumed) * |
|---|---|---|
| Bulk Hangar #1 (MRO) | 41,400 | 8 Jet, 1 Turbo, 1 Single/Multi |
| Bulk Hangar #2 | 23,806 | 4 Jet, 5 Single/Multi |
| Bulk Hangar #3 | 30,000 | 1 Jet, 10 Turbo, 1 Single/Multi |
| Bulk Hangar #4 | 46,771 | 9 Jet, 1 Turbo, 2 Single/Multi |
| Bulk Hangar #5 | 30,613 | 6 Jet, 1 Turbo |
| Bulk Hangar #6 | 12,316 | 2 Jet, 1 Turbo |
| T-Hangars (Section 1) - 16 stalls | 17,600 | 16 Single/Multi |
| T-Hangars (Section 2) - 16 stalls | 21,600 | 16 Single/Multi |
| T-Hangars (Section 3) - 11 stalls | 11,440 | 11 Single/Multi |

Note: Due to projected growth in jet aircraft and turboprop aircraft at ORF, capacity was calculated by giving priority to jet aircraft, followed by turbo prop aircraft, and lastly, by multi/single engine aircraft.
*Types of aircraft in each hangar was estimated based on sizing requirements
Source: Signature, CHA 2018.

According to Signature, 32 of the 35 T-hangar stalls are currently under lease contracts, with no waiting list; however, all bulk hangars have current lease contracts and are at or nearing capacity. With hangars at and nearing maximum capacities, along with increasing itinerant traffic and average aircraft size per tenant, the Airport is constrained to accommodate additional aircraft in bulk hangars. Signature believes that an additional 40,000 square feet of hangar space is currently needed, with a second hangar of the same size needed in the next five to ten years. Signature further advised that no additional T-hangars are needed during the forecast horizon.

Further, the fleet mix at the Airport is anticipated to change with based aircraft growth, adding jets. As such, it is likely that additional larger hangar space is warranted at ORF to accommodate demand. To develop a projection of required hangar space, assumptions were made based on average square feet of space required to store each type of aircraft and the forecasted fleet mix in the planning period, which were then compared to the projections made by the Airport's FBO. **Table 4-85** provides anticipated hangar space requirements based on these assumptions.

**Table 4-85– Hangar Space (Stalls) Requirements**

| Aircraft Type | Existing Capacity (2017) | Planning Period (Recommended Number of Hangar Stalls) | | | | |
|---|---|---|---|---|---|---|
| | | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
| Single-Engine Piston | **Aircraft Capacity: 86** | 46 | 47 | 48 | 49 | 51 |
| Multi-Engine Piston | | 10 | 10 | 11 | 11 | 12 |
| Turbo-Prop | | 10 | 11 | 13 | 15 | 17 |
| Jet | | 21 | 26 | 31 | 37 | 42 |
| Rotorcraft | | 2 | 3 | 3 | 3 | 4 |
| Total Hangar Stalls | | 89 | 97 | 106 | 115 | 126 |
| **Total Aircraft Not Stored** | - | **(3)** | **(12)** | **(21)** | **(31)** | **(40)** |

Source: CHA, 2018.

As discussed, there is an immediate demand for additional hangar space at ORF. **Table 4-86** shows the current useable hangar space, the future hangar space requirements, and the forecasted deficit of stall space by fleet mix.

**Table 4-86 – Hangar Space Requirements (Sq. Ft.)**

| Aircraft Type | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|
| **Hangar Storage Capacity (Usable Hangar Space)** | | | | | |
| Single-Engine/Multi-Engine/Rotorcraft | 51,000 | 51,000 | 51,000 | 51,000 | 51,000 |
| Turbo-Prop | 50,000 | 50,000 | 50,000 | 50,000 | 50,000 |
| Jet | 84,600 | 84,600 | 84,600 | 84,600 | 84,600 |
| **Total** | **185,600** | **185,600** | **185,600** | **185,600** | **185,600** |
| **Aircraft Hangar Space Required** | | | | | |
| Single-Engine Piston | 46,229 | 47,372 | 48,516 | 49,659 | 50,803 |
| Multi-Engine Piston | 10,095 | 10,571 | 11,046 | 11,522 | 11,997 |
| Turbo-Prop | 22,497 | 26,981 | 31,465 | 35,949 | 40,434 |
| Jet | 99,023 | 124,139 | 149,254 | 174,370 | 199,486 |
| Rotorcraft | 2,082 | 2,495 | 2,907 | 3,319 | 3,732 |
| **Total** | 179,926 | 211,557 | 243,189 | 274,820 | 306,451 |
| **Surplus/(Deficit)** | | | | | |
| Single/Multi//Rotorcraft | (7,406) | (9,438) | (11,469) | (13,500) | (15,532) |
| Turbo-Prop | 27,503 | 23,019 | 18,535 | 14,051 | 9,566 |
| Jet | (14,423) | (39,539) | (64,654) | (89,770) | (114,886) |
| **Total** | **5,674** | **(25,957)** | **(57,589)** | **(89,220)** | **(120,851)** |

Source: CHA, 2018.

This hangar deficit estimate is similar to that expressed by the FBO. Based on the forecasted growth of aircraft, hangar demand may increase from the current space of approximately 170,000 SF to approximately 300,000 SF by the end of the planning period. Current FBO plans are discussed further as alternative development plans in **Chapter 5**.

***MRO Facilities***

MRO activities take place in a bulk hangar in the GA area. The hangar space is approximately 41,400 square feet. The maintenance hangar space is sufficient and is not expected to need expansion during the forecast period.

### 4.5.2 Air Cargo Facilities

ORF has processing facilities for air cargo arriving and departing via cargo carriers. As mentioned in **Section 4.3.4**, the dedicated air cargo area is on the west side of the airfield, south of the terminal and is comprised of two multipurpose processing buildings (measuring approximately 64,720 square feet and 23,420 square feet). The smallest of the two buildings is occupied by FedEx and FedEx's contract carrier, Mountain Air Cargo (MAC). The larger building is shared between FedEx, Mountain Air Cargo, and UPS. UPS desires a consolidated facility in the future, as operations and functions are broken into four separate areas: front office space, UPS maintenance space, generalized space, and customs.

As discussed in **Chapter 3**, air cargo operators are expected to transition to new and converted B767-300 aircraft. As these new freighters are added, it is expected that ORF will also see less cargo operations via A300s and B757s. Transitioning to larger freighters, along with the projected increases in cargo operations, will result in higher volumes of cargo being brought into the Airport's cargo facilities. **Table 4-87** shows the forecast of cargo operations and volume.

**Table 4-87 – All-Cargo Annual Forecasts**

| Factor | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| **Total Operations** | 2,429 | 2,475 | 2,719 | 2,987 | 3,281 | 3,604 |
| **Total Volume (tons)** | 119,634 | 121,903 | 133,910 | 147,101 | 161,590 | 177,506 |

Source: NAA, CHA, 2018.

Available cargo processing space and cargo volume, observations of the facilities, and conversations with personnel were factors considered when determining the projected building space required for cargo operations. Based on observations of the cargo multipurpose buildings and conversations with the Airport and tenants, the cargo facilities currently exceed maximum capacity by approximately 10 percent. It was determined that the utilization rate for the cargo facilities at ORF is approximately 1.23 tons/SF. As shown in **Table 4-88**, the cargo facilities are expected to exceed capacity by approximately 63 percent in PAL 4.

**Table 4-88 – All-Cargo Building Space Requirements**

| Activity | 2017 | Base | PAL 1 | PAL 2 | PAL 3 | PAL 4 |
|---|---|---|---|---|---|---|
| Air Cargo Building Space Required | 96,953 | 98,792 | 108,523 | 119,212 | 130,954 | 143,853 |
| Available Space | 88,139 | 88,139 | 88,139 | 88,139 | 88,139 | 88,139 |
| **Surplus/(Deficit)** | **(8,814)** | **(10,653)** | **(20,384)** | **(31,073)** | **(42,815)** | **(55,714)** |

Source: CHA, 2019.

NAA should plan to reserve land, or plan for land acquisition, for future expansion of existing cargo facilities and/or the building of additional cargo facilities. If the buildings' spaces reach or exceed capacity prior to new or expanded facilities being available, current sort facility equipment can be updated to more modernized equipment (such as automated machinery), allowing for quicker processing and higher throughput.

### 4.5.3 TSA Cargo Facilities

In the past, TSA had an office in the cargo area; however, TSA no longer has a cargo-dedicated zone. Rather, TSA officers only respond to the cargo facilities when necessary.

### 4.5.4 Aviation Fueling Facilities

Signature Flight Support is responsible for operating the commercial fuel farm, the GA fuel farm, and the fuel dispensing area at ORF. The Airport's fuel farm for commercial aircraft operators, located north of the Air Traffic Control Tower (ATCT), consists of four above-ground fuel tanks with fuel storage capacities of 210,000-gallons per tank (Jet-A).

Fuel is transported from the fuel farm via underground pipes to a dispensing area located north of the Aircraft Rescue and Firefighting (ARFF) facility. Fuel is then transported from the dispensing area to aircraft via specialized fuel trucks, which make approximately 13 to 15 deliveries per day. The types of trucks and their carrying capacities are as follows:

- One 750-gallon truck (Avgas)
- One 1,000-gallon truck (Avgas)
- Ten 5,000-gallon trucks (Jet-A)
- One 10,000-gallon truck (Jet-A)

The general aviation fuel farm is located in the GA area, south of the T-hangars, and includes three underground 10,000-gallon tanks (two containing Jet-A and one containing AvGas). The Airport receives approximately 100,000 to 160,000 gallons of fuel five days per week. Based on 2017 fuel consumption data provided by Signature and the Airport, growth in fuel consumption was assumed for the 20-year forecast period by determining a ratio of the fuel delivered in 2017 to the commercial and GA operations in 2017. The ratio was then applied to each projected year's operations to determine approximate fuel consumption, assuming the ratio remains static. The results were then split by the PMAD factors identified in **Chapter 3** to estimate an average daily usage of fuel throughout the forecast period. Finally, the daily usage was applied to the actual reserve availability at the Airport.

After evaluating the Airport's fuel storage needs, it was determined that the Airport has sufficient fuel storage capacity. The reserves currently provide up to a five-day availability (the desired amount for an airport such as ORF) but can reach as many as a seven-day availability, depending on the amount of fuel delivered. **Table 4-89** depicts the forecast of air carrier and GA operations at ORF. The required fuel reserve to meet three-and-one-half-, five-, and seven-days reserves is shown in **Table 4-90**.

**Table 4-89 – Air Carrier and GA Operations**

| Year | Air Carrier | GA | Total Air Carrier and GA |
|---|---|---|---|
| **2017** | 47,195 | 22,364 | 69,559 |
| **Base** | 48,986 | 22,760 | 71,746 |
| **PAL 1** | 51,889 | 24,850 | 76,739 |
| **PAL 2** | 55,177 | 27,132 | 82,310 |
| **PAL 3** | 57,488 | 29,624 | 87,111 |
| **PAL 4** | 61,430 | 32,344 | 93,773 |

Source: Signature, NAA, CHA, 2018.

**Table 4-90 – Fueling Storage Requirements (Gallons)**

| Year | Fuel Volume (gallons) | PMAD Fuel | Reserve | | |
|---|---|---|---|---|---|
| | | | 3.5 | 5 | 7 |
| **Assuming 100,000 gallons Per Daily Delivery** | | | | | |
| **2017** | 26,000,000 | 100,038 | 350,133 | 500,189 | 700,265 |
| **Base** | 26,817,616 | 103,184 | 361,143 | 515,919 | 722,286 |
| **PAL 1** | 28,683,910 | 110,365 | 386,276 | 551,823 | 772,552 |
| **PAL 2** | 30,765,927 | 118,375 | 414,314 | 591,876 | 828,627 |
| **PAL 3** | 32,560,746 | 125,281 | 438,484 | 626,405 | 876,967 |
| **PAL 4** | 35,050,974 | 134,862 | 472,019 | 674,312 | 944,037 |
| **Assuming 160,000 gallons Per Delivery** | | | | | |
| **2017** | 41,600,000 | 160,061 | 560,212 | 800,303 | 1,120,424 |
| **Base** | 42,908,185 | 165,094 | 577,829 | 825,470 | 1,155,658 |
| **PAL 1** | 45,894,255 | 176,583 | 618,041 | 882,916 | 1,236,082 |
| **PAL 2** | 49,225,484 | 189,400 | 662,902 | 947,002 | 1,325,803 |
| **PAL 3** | 52,097,194 | 200,450 | 701,574 | 1,002,248 | 1,403,148 |
| **PAL 4** | 56,081,559 | 215,780 | 755,230 | 1,078,900 | 1,510,460 |
| **Assuming 130,000 gallons Per Delivery (Average of 100,000 and 160,000 gallons)** | | | | | |
| **2017** | 33,800,000 | 130,049 | 455,172 | 650,246 | 910,345 |
| **Base** | 34,862,901 | 134,139 | 469,486 | 670,694 | 938,972 |
| **PAL 1** | 37,289,082 | 143,474 | 502,158 | 717,369 | 1,004,317 |
| **PAL 2** | 39,995,705 | 153,888 | 538,608 | 769,439 | 1,077,215 |
| **PAL 3** | 42,328,970 | 162,865 | 570,029 | 814,327 | 1,140,058 |
| **PAL 4** | 45,566,267 | 175,321 | 613,624 | 876,606 | 1,227,249 |

Source: CHA, 2018.

The Airport's demand will not exceed its current 870,000-gallon capacity during the planning horizon if only up to 100,000 gallons of fuel are delivered per delivery; however, if the Airport wishes to achieve a 7-day reserve capability, it will need to expand to 880,000 gallons by PAL 3 and 945,000 gallons by PAL 4. Fuel storage facilities will near capacity quicker if receiving 160,000 gallons or approximately 130,000 gallons. The Airport has space available to accommodate additional fuel tanks if necessary.

### 4.5.5 Aircraft Deicing Facilities

Currently, the deicing area is located on the terminal apron and does not have a built-in collection system; rather, sweeper trucks are utilized to collect glycol from the pavement after application, which is then transferred to glycol storage tanks located near the fuel dispensing area. After deicing services have ceased for the season, the glycol tanks are taken to an off-site facility where the recovered fluid is analyzed and disposed of accordingly. Each airline is responsible for its own glycol storage units.

Although the Airport is able to support deicing activities on the terminal ramp now and in the future, it is NAA's preference to move deicing activities to a centralized location that has a built-in runoff collection system and that is accessible by commercial and cargo operators. A centralized location will provide more efficient staff utilization, while the built-in collection system will be more efficient from an environmental standpoint. Deicing development concepts are further evaluated in **Chapter 5**.

### 4.5.6 Aircraft Rescue and Firefighting Facilities (ARFF)

ORF currently has one ARFF facility, which is located on the north side of the airfield, northeast of the terminal building. This facility was constructed prior to the new FAA guidance associated with ARFF building design; however, the existing ARFF building currently meets most of the building design requirements found in AC 150/5210-15A, *Aircraft Rescue and Firefighting (ARFF) Station Building Design*. The ARFF operations has requested the need for more bunk space and the NAA is currently working on a design project to satisfy this need within the current footprint. Should the ARFF facility need more space within the planning horizon, it may be necessary to revisit the FAA guidance for ARFF requirements. The ARFF index (Index C) is expected to remain unchanged over the forecast period.

### 4.5.7 NAA Maintenance Facilities

The NAA operates maintenance and equipment storage facilities, located on the southeast end of the airfield. The northern building is approximately 40,000 square feet and houses the Airport's snow removal equipment (SRE). The southeastern building is approximately 6,000 square feet and serves as the sand storage facility, as well as a storage unit for the Airport's maintenance and utility vehicles. The facilities as currently constructed are inadequate in size via operational function and sizing and amenities. The SRE building is currently at capacity with the amount of snow removal vehicles necessary to accommodate the demand on the airfield. Based on the FAA's 'Snow Removal Equipment Calculations' worksheet for necessary snow removal equipment, it is recommended that ORF maintain at least 34 SRE vehicles (four high-speed rotary plows, eight displacement plows, eight sweepers, eight hopper spreaders, and six front end loaders); however, NAA currently owns and operates 36 SRE vehicles. Of the current vehicles, existing SRE storage facilities accommodate up to 15 vehicles, and the remaining 21 are currently parked outside due to lack of space.

Additionally, the SRE and maintenance buildings were designed and constructed prior to the update of the most recent FAA guidance FAA AC 150/5220-18A, *Buildings for Storage and maintenance of Airport Snow and Ice Control Equipment and Materials*. As such, several changes were made in the AC associated with facility sizing, sleeping quarters, wash bays, etc., all of which the current facility is lacking. For the purposes of this Study, it is recommended that the Airport consider expanding the SRE and NAA Maintenance Facilities to accommodate outdoor equipment storage (i.e., covered equipment parking) and FAA design standard recommendations; however, a further detailed analysis will be required to determine expansion needs specific to ORF.

### 4.5.8 Ground Support Equipment Facilities and Fuel Truck Storage

At ORF, the airlines (or in some cases, ground handling companies contracted out by the airlines) own and operate the ground service equipment (GSE), including a variety of aircraft tugs, cabin service vehicles, deicers, ground power units (GPUs), belt-loaders, and waste disposal vehicles. This equipment is stored outside where space is available around the terminal gates (with respect to aircraft parking safety areas) and on the south side of the cargo apron adjacent to the belly cargo buildings. Signature also has 13 fuel trucks, which are parked at fuel loading islands in the fueling areas.

A storage shelter to protect equipment from harsh weather conditions would increase the service life of the equipment. Review of the airlines' GSE inventory indicates that significant storage space would be required to house all airline GSE equipment indoors. Further evaluation is necessary to determine the amount of space required to house GSE equipment and fueling equipment. Future GSE shelter designs will include technology upgrades that meet the airlines' GSE requirements at the time of design.

### 4.5.9 Air Traffic Facilities

The Airport Traffic Control Tower (ATCT) is located at 1245 Miller Store Road. Constructed in 1995, the building is used for Air Traffic Control and contains administrative support offices, as well as the Terminal Radar Approach Control (TRACON) facility. The land is leased from the NAA, but the FAA owns the 134-foot tall (above ground level or AGL) building. Approximately 85 automobile parking spaces are available that serve the ATCT. The tower is attended 24 hours a day throughout the year, during which time its staff controls air traffic in accordance with federal regulations. It is anticipated that the ORF ATCT will sufficiently serve the Airport throughout the forecast horizon.

## 4.6 SURFACE TRANSPORTATION AND PARKING REQUIREMENTS

This section presents the projections of future airline passenger, car rental, and ORF employee parking needs, based on the forecast presented in **Chapter 3 (Forecasts of Aviation Activity)**, as well as a summary of the anticipated future changes in the ORF parking inventory. Projected enplanement growth by year (base year to PAL 4) was applied to existing (2017) peak on-airport public and employee parking accumulations to project future parking need. Information provided by ORF was used to determine the magnitude and timing of changes to the existing parking inventory.

### 4.6.1 Passenger Parking Demand Projections

Beginning with the Master Plan enplanement projections from the base year to PAL 4, existing peak parking utilization was increased in line with enplanement growth; however, a five percent reduction in parking demand in the base year was assumed, based on an increase in the use of ride-sharing services such as Uber, Lyft and other car services. **Table 4-91** presents the results of the parking projections from the base year through PAL 4. At the current enplanement level of about 1.8 million passengers, the parking system requires a total capacity of approximately 5,400 parking spaces. At 2.8 million enplanements, the demand for parking is projected to reach almost 8,000 spaces.

### 4.6.2 Parking Supply Changes

While parking demand is projected to increase in the future as enplanements grow, several projects will also impact the supply of parking owned and controlled by ORF. These known projects will ultimately increase the total supply of parking from 8,598 to 8,976 spaces.

The proposed projects include the removal of Lot D for construction of a new garage. That new garage will be completed in 2021, providing 2,612 public parking and 596 employee spaces. Once the employees are transferred to Garage D, the Employee lot will be eliminated, and Garages B and C will be closed for rehabilitation. In 2022, the rehabilitation will be completed, and the garages will reopen with the loss of 100 total spaces. Once Garages B and C reopen, the Long-

term lot will be permanently closed with a loss of 2,052 spaces. **Table 4-93** summarizes the changes in parking inventory by user group and year.

**Table 4-91 – Projected Parking Needs**

| Year | Master Plan Enplanement Projections | Peak Utilization of NAA Public Parking | Peak Utilization of Rental Car Parking | Peak Utilization of CAA Employee Parking | Total Peak Utilization of ORF Parking |
|---|---|---|---|---|---|
| **2017 (actual)** | 1,672,024 | 3,999 | 636 | 258 | 4,893 |
| **Base** | 1,857,487 | 4,443 | 707 | 287 | 5,436 |
| **PAL 1** | 2,115,424 | 4,807 | 805 | 326 | 5,938 |
| **PAL 2** | 2,376,990 | 5,401 | 904 | 367 | 6,672 |
| **PAL 3** | 2,622,848 | 5,959 | 998 | 405 | 7,362 |
| **PAL 4** | 2,834,623 | 6,441 | 1,078 | 437 | 7,956 |

Source: DESMAN.

**Table 4-92 – Projected Parking Inventory**

| Year | Location | Spaces Lost | Spaces Gained | User Group |
|---|---|---|---|---|
| **2019** | Loss of Lot D for Construction | 82 | 0 | Public Parking |
| **2021** | Garage D | 0 | 2,612 | Public Parking |
| | | 0 | 596 | Employee Parking |
| **2021** | Loss of Employee Lot | 596 | 0 | Employee Parking |
| **2021** | Rehab Garages B and C | 2,223 | 0 | Public Parking |
| **2022** | Finish Garages B and C | 0 | 2,123 | Public Parking |
| **2022** | Loss of Long-Term Lot | 2,052 | 0 | Public Parking |
| **Total** | | **4,953** | **5,331** | **Net +378** |

Source: DESMAN.

**Table 4-93 – Projected Parking Inventory by Type of User**

| | Location | Regular | Disabled | Authorized | Rental Car | Total by Year | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | 2018 | 2019 | 2020 | 2021 | 2022 |
| **A** | **Garage A** | 2,535 | 37 | 0 | 636 | 3,208 | 3,208 | 3,208 | 3,208 | 3,208 |
| | **Short-Term* | 275 | 7 | 0 | 0 | 282 | *282* | 282 | 282 | 282 |
| | **Long-Term* | 2,260 | 30 | 0 | 0 | 2,290 | 2,290 | 2,290 | 2,290 | 2,290 |
| | **Rental Cars* | 0 | 0 | 0 | 636 | 636 | 636 | 636 | 636 | 636 |
| **B** | **Garage B** | 1,090 | 21 | 2 | 0 | 1,113 | 1,113 | 1,113 | 0 | 1,063 |
| **C** | **Garage C** | 1,089 | 21 | 0 | 0 | 1,110 | 1,110 | 1,110 | 0 | 1,060 |
| **D** | **Lot/Garage D** | 72 | 4 | 6 | 0 | 82 | 0 | 0 | 3,208 | 3,208 |
| **E** | **Long-Term Lot** | 1,999 | 42 | 11 | 0 | 2,052 | 2,052 | 2,052 | 2,052 | 0 |
| **F** | **Departures North** | 146 | 6 | 0 | 0 | 152 | 152 | 152 | 152 | 152 |
| **G** | **Departures South** | 171 | 6 | 0 | 0 | 177 | 177 | 177 | 177 | 177 |
| **H** | **North-Permit Only** | 103 | 5 | 0 | 0 | 108 | 108 | 108 | 108 | 108 |
| **I** | **Employee Lot** | 580 | 12 | 4 | 0 | 596 | 596 | 596 | 0 | 0 |
| **Total** | | **7,785** | **154** | **23** | **636** | **8,598** | **8,516** | **8,516** | **8,905** | **8,976** |

Source: DESMAN.

### 4.6.3 Future Adequacy of the ORF Parking Inventory

The projected growth of parking demand was overlaid onto the projected parking supply by user group from the base year through PAL 4. For planning purposes, our target occupancy was 90 percent of available spaces. This accounted for the practical capacity of a parking system such as unused ADA spaces, vehicles parking over the lines, and the last few spaces in a parking facility

which may be hard to find. Only when enplanements exceed 2.75 million assuming no further increase in non-drive mode split would public parking demand exceed the target of 90 percent peak occupancy.

As shown in **Table 4-94,** based on observed peak utilization of current parking demand, the public parking demand in the base year of 4,442 spaces will increase to 6,441 in PAL 4. Similarly, rental car space demand will increase from 707 to 1,078 spaces and employee demand will increase from 287 vehicles to 437. It has been noted that during certain employee shift changes, peaks may reach 596 spaces.

This analysis demonstrated that, in total, there will be an adequate number of parking spaces available to accommodate the projected enplanements; however, there may be a need to convert excess long-term spaces to car rental spaces if growth occurs as expected.

**Table 4-95** provides a further breakdown of supply and distribution of demand over the 20-year period. For each user group, the existing supply and demand were identified. The planned changes, both additions and subtractions, were added to the existing supply and the projected demand was calculated based on the growth of enplanements. The reserved spaces were assumed to remain constant at 110 and were considered 100 percent occupied throughout the 20-year study period. For each of the user groups shown in the table, the supply of parking in the base year and PAL 4 was identified, the demand was projected, and the surplus/deficit was calculated. As discussed previously, based on the current parking plans and the projected enplanements, there will be adequate parking available to accommodate the demand. As discussed previously, based on the current parking plans and the projected enplanements, there will be adequate public parking available to accommodate the demand; however, during the course of the planning period, rental car demand will exceed capacity.

**Table 4-94 – Projected Adequacy of the ORF Parking Inventory**

| Year | Passenger Projections | Peak Util. of ORF Public Parking | Projected ORF Public Parking Inventory | Anticipated Peak Public Surplus/(Deficit) | Peak Util. of Rental Car Parking | Projected ORF Rental Car Inventory | Anticipated Peak Rental Car Parking Surplus/(Deficit) |
|---|---|---|---|---|---|---|---|
| **2017 (actual)** | 1,672,024 | 3,999 | 7,366 | 3,367 | 636 | 636 | 0 |
| **Base** | 1,857,487 | 4,442 | 7,366 | 2,924 | 707 | 636 | (71) |
| **PAL 1** | 2,115,424 | 4,807 | 7,491 | 2,684 | 805 | 636 | (169) |
| **PAL 2** | 2,376,990 | 5,401 | 7,491 | 2,090 | 904 | 636 | (268) |
| **PAL 3** | 2,622,848 | 5,959 | 7,491 | 1,532 | 998 | 636 | (362) |
| **PAL 4** | 2,834,623 | 6,441 | 7,491 | 1,050 | 1,078 | 636 | (442) |

| Year | Passenger Projections | Projected ORF Employee Parking Inventory | Peak Util. of ORF Employee Parking | Anticipated Peak Employee Parking Surplus/(Deficit) |
|---|---|---|---|---|
| **2017 (actual)** | 1,672,024 | 596 | 258 | 338 |
| **Base** | 1,857,487 | 596 | 287 | 309 |
| **PAL 1** | 2,115,424 | 596 | 326 | 270 |
| **PAL 2** | 2,376,990 | 596 | 367 | 229 |
| **PAL 3** | 2,622,848 | 596 | 405 | 191 |
| **PAL 4** | 2,834,623 | 596 | 437 | 159 |

[Tables Continued on Next Page]

**Table 4-94 – Projected Adequacy of the ORF Parking Inventory (Continued)**

| Year | Passenger Projections | Projected ORF Total Parking Inventory | Anticipated Total Peak Surplus/(Deficit) | Net Change in ORF Inventory vs. 2017 | Total Peak Utilization of ORF Parking |
|---|---|---|---|---|---|
| **2017 (actual)** | 1,672,024 | 8,598 | 3,705 | 0 | 4,893 |
| **Base** | 1,857,487 | 8,598 | 3,162 | 0 | 5,436 |
| **PAL 1** | 2,115,424 | 8,723 | 2,785 | 125 | 5,938 |
| **PAL 2** | 2,376,990 | 8,723 | 2,051 | 0 | 6,672 |
| **PAL 3** | 2,622,848 | 8,723 | 1,361 | 0 | 7,362 |
| **PAL 4** | 2,834,623 | 8,723 | 768 | 0 | 7,956 |

Source: DESMAN.

**Table 4-95 – Summary of Projected Parking Needs by User Group**

| User Group | Base Year Supply | Base Year Demand | Base Year Surplus | PAL 4 Supply | PAL 4 Demand | PAL 4 Surplus |
|---|---|---|---|---|---|---|
| Short Term | 592 | 190 | 402 | 592 | 290 | 302 |
| Long Term | 6,510 | 4,055 | 2,455 | 6,635 | 5,906 | 729 |
| ADA | 154 | 88 | 66 | 154 | 134 | 20 |
| Reserved | 110 | 110 | 0 | 110 | 110 | 0 |
| Rental Car | 636 | 707 | (71) | 636 | 1078 | (442) |
| Employee | 596 | 287 | 309 | 596 | 437 | 159 |
| **Total** | **8,598** | **5,436** | **3,162** | **8,723** | **7,956** | **768** |

Source: DESMAN

### 4.6.4 Future Capacity of ORF Curb front

The projected growth of curb front activity for both passenger cars and bus/rideshare vehicles were overlaid onto the existing curb front dimensions by location and user group from the base year through PAL 4. The current useable curb front lengths are shown in **Table 4-96** and are illustrated in **Figure 4-31**. The table summarizes separately the existing curb fronts on the departure and arrivals buildings and separately for cars and bus/rideshare. It should be noted that there are small variations in length due to the locations of cross walk and turning radii. The table also acknowledges that in the three-lane roadway configuration, the curb lane is the primary drop-off lane, the middle lane is the overflow lane, and the outside lane is reserved for through traffic. The current curb front occupancy ranges from 20 percent to 45 percent.

**Table 4-96 – Current Useable Curb Front Length**

| Curb front | Cars & Shuttles | Usable Curb front Length (ft.) | | Total Usable Length | Second Lane Length | Total Usable Length |
|---|---|---|---|---|---|---|
| | | North | South | | | |
| Departures | Cars | 377 | 288 | 665 | 500 | 1,165 |
| | Shuttles | 266 | 244 | 510 | 400 | 910 |
| Arrivals | Cars | 688 | 0 | 688 | 500 | 1,188 |
| | Shuttles | 688 | 0 | 688 | 0 | 688 |

| Curb front | Cars & Shuttles | Current Curb Front Occupancy | Occupancy Incl. Second Lane | Occupancy with 5% shift in rideshare | Base Year Curb Front Occupancy (Base Year) | Peak Design Condition 2x Avg. |
|---|---|---|---|---|---|---|
| Departures | Cars | 40% | 23% | 22% | 22% | 43% |
| | Shuttles | 20% | 11% | 13% | 13% | 25% |
| Arrivals | Cars | 45% | 26% | 25% | 25% | 50% |
| | Shuttles | 20% | 20% | 22% | 22% | 45% |

Source: DESMAN.


The observed occupancies are also summarized for each curb front. It is reported that there are short periods of time during peak departure periods when the immediate curb front, generally immediately in front of the entrance doors, when cars are stacked up or double parked. Based on the existing configuration of the separated departures curbside lanes on each side of the Departures building, individual airline peaking characteristics often cause off-peak period congestion on the curbside based on the fleet mix of the aircraft and the airlines operating the flight during these times. For example, should Delta, Frontier, and Allegiant have flights during the same period, with the make-up of the passengers on Frontier and Allegiant commonly having a higher number of leisure passengers on larger planes (i.e., +/- 177 seats), and the tickets counters on the south departure curbside, congestion is common during these periods. This results in drivers dwelling at the curb front for longer than necessary.

Based on the infrastructure and operational characteristics of the Departures curbside (i.e., passengers can utilize north and south curbsides, curb lane length is constrained, etc.) for the purposes of this Study, the curbside lane was shown and calculated as total length. Additionally, since there was no use of the overflow lane during the field observations conducted for this Study, the current occupancy was factored to include the use of the overflow lane. As such, it is recommended that the departure lanes be actively managed during peak times. Ambassadors, attendants, or police point control should be used to direct drivers to spread out over the length of the curb front and, when necessary, direct them to the overflow lanes.

Factoring the overflow lane, which would be used during busy times, has typical occupancy ranges that are between 11 percent and 26 percent. As with the parking projection, it was assumed that rideshare would increase 5 percent over the near future (see **Table 4-96**). The base year occupancy in the automobile lanes decreases slightly, while the occupancy in the rideshare lanes increases. Recognizing the seasonality of airport enplanements, the base year (2018) occupancy was adjusted to reflect that the peak design condition generally is twice the typical or average condition (see **Table 4-96**). Even during peak times, the occupancy of the lanes is a maximum of 50 percent or less at current enplanements.

The current design day conditions for each category were projected based on the Master Plan enplanement projections. As shown in **Table 4-97**, the existing curb front occupancy would increase from existing levels to no more than 61 percent for bus/rideshare lanes and to no more than 72 percent for auto lanes. Based on the existing curb front lengths, there will be adequate capacity to accommodate projected enplanements through PAL 4. As new flights are added, some departures may conflict and create a “microburst” of activity. During the short periods when drop-off for several departing flights overlap, point control, either by attendants or police, can direct traffic on the curb front. The point control staff will help to spread the concentration of drop-off motorists along the curb front and will be able to encourage drivers to move along and not dwell unnecessarily at the curb front. If the problem persists or the flight schedules become more heavily concentrated, the outer curb front could be utilized during peak periods. It is not believed that a physical solution, such as adding additional curb length, will be necessary.

**Figure 4-31 – Existing Curb Front Layout**




Source: DESMAN

**Table 4-97 – Projected Curb Needs**

| Year | Enplanement Projections | Peak Utilization of Departures Curb Front | | Peak Utilization of Arrivals Curb Front | |
|---|---|---|---|---|---|
| | | Private Cars | Bus/Rideshare | Private Cars | Bus/Rideshare |
| **2017 (actual)** | 1,672,024 | 43% | 25% | 50% | 45% |
| **Base** | 1,857,487 | 48% | 28% | 55% | 49% |
| **PAL 1** | 2,115,424 | 52% | 29% | 54% | 46% |
| **PAL 2** | 2,376,990 | 59% | 33% | 60% | 52% |
| **PAL 3** | 2,622,848 | 65% | 36% | 67% | 57% |
| **PAL 4** | 2,834,623 | 70% | 39% | 72% | 61% |

Source: DESMAN.

### 4.6.5 Curbside Management Plan

Based on the projection of curbside activity, the existing curb front will be adequate to accommodate the projected needs; however, as enplanements increase, there may be short "microbursts" of activity when several planes land or take off in a short period of time. During these peak activity periods, it may be desirable to have a curbside management plan ready. At many airports this includes a combination of ambassadors to help direct patrons to and from the curb and the terminal, as well as traffic directors to insure smooth traffic flow for both passenger cars and taxi/transportation network companies (TNCs). The need for this service should be monitored over time.

### 4.6.6 Rental Car Ready/Return Parking

As previously discussed, current rental car operations consist of two separate facilities; a ready and return area in Garage A and an off-site QTA maintenance facility located west of Airport property on Military Highway. The rental car companies' return lot was previously located on Airport Road, adjacent to the long-term lot; however, the Airport recently completed the process of converting the second floor of Garage A to a return facility where passengers drop-off vehicles. The current drop-off lot has been eliminated. As discussed previously, the combined rental car facility will be adequate to accommodate the projected enplanements.

### 4.6.7 Rental Car Vehicle Storage and Maintenance Facilities

Rental car vehicle storage and maintenance is situated off airport property on Military Highway. Currently, there are no plans to relocate or expand the facility; however, if the long-term surface lot is displaced for terminal facility needs, there may be a need for additional customer parking in Garage A. If so, consideration should be given to relocating the Rental Car QTA and fueling facilities in an alternate location. Additionally, there are no current plans to relocate or expand the facilities along Military Highway due to capacity or necessary improvements associated with inadequate facility requirements. There has been considerable thought to operational justification of the relocations of all QTA facilities into a consolidated QTA facility in proximity to the terminal. With the rental ready/return and passenger pick-up now located in Garage A, considerable increased trips via the rental car companies to and from the ready/return and QTA has put a strain on the terminal roadway system from a capacity and operational safety perspective. As such, it is recommended, when practical, to consider a consolidated QTA in proximity to the terminal buildings where feasible.

### 4.6.8 Commercial Vehicles and TNC Staging Area

The current TNC lot is located in the old rental car return lot. The lot contains more than two acres and can accommodate more than 250 vehicles. The taxi waiting area is located on Airport Road adjacent to the existing long-term lot. It can accommodate approximately 25 taxis and provides a small service building. Between 2016 and 2017, total TNC traffic increased 76 percent to an average of just under 50 trips per hour during the peak month (December). Assuming that TNCs grow in proportion to enplanements, TNC traffic would grow to about 70 per hour. This can easily be accommodated in the existing lot. There is continuing discussion regarding when TNCs' share of the market will level out, and at whose expense; taxis/limos or parkers. Given the distances that passengers and employees are traveling to get to the Airport, it is expected that price will limit the growth of TNCs at the Airport. Given the uncertainties of projected demand, it is recommended that a combined taxi, TNC, limo waiting area be developed at ORF to accommodate 100 to 125 vehicles. As discussed in **Section 4.6.1**, TNC operations are expected to decrease parking demand by approximately five percent in the base year due to an increase in the use of ride-sharing services; however, TNC activity is not expected to impact public parking in the future, as public parking demand is projected to increase and, thus, is being accounted for in future parking considerations.

## 4.7 ACCESS ROADWAYS AND CIRCULATION

The Airport is served with access roads and connections to regional highways and Interstate 64. The Airport's grounds provide public access to both the arrivals and departures buildings as well as access to parking facilities.

### 4.7.1 Regional Access

The regional access system based on I-64 via Norview Avenue and Robin Hood Road has substantial capacity to accommodate an increase in enplanements. These roads, together with Route 192 (Azalea Garden Road), will continue to provide easy access to and from the Airport for passengers and employees; however, as enplanements increase and more vehicles are traveling to the Airport from the Interstate system, consideration should be given to improving the access to and from the east on I-64 (this includes the majority of travelers to and from points south, east and west).

### 4.7.2 Local Access

The primary local access road for most passengers and employees is Norview Avenue which provides four lanes between the Airport and I-64. Traffic on Norview is controlled by traffic signals at Rt. 192, Military Highway, a shopping center, and the Interstate 64 ramps. The existing turn lanes at key intersections provide a good level of service for existing peak hour traffic and enough capacity to accommodate the growth in enplanements at Norfolk International Airport; however, since Norview Avenue passes through a residential neighborhood between Military Highway and Azalea Garden Road, it can be expected that there would be increasing complaints from the neighborhood about airport traffic. If the neighborhood is to remain in place over the long term, consideration should be given to providing more direct access to the Airport from I-64.

In addition, Azalea Garden Road provides a secondary exit from the Airport to the north to Rt. 170 and to the southwest to Military Highway and points beyond. The Robin Hood Road

interchange with I-64 provides an alternative entrance to the Airport from the south and via I-264 from Virginia Beach and Portsmouth. As enplanements increase, consideration should be given to improvement of the interchange at Robin Hood Road to provide full access to and from the east with direct access along Robin Hood Road and Airport Road to the terminal.

### 4.7.3 Circulation

More than 4.5 lane miles of circulation roadways, in addition to the curb front loading lanes, effectively distribute circulating traffic throughout the Airport. The existing configuration can accommodate the projected increase in enplanements. If the terminal buildings are significantly reconstructed or expanded, it will be appropriate to review the resulting configuration to ensure that the circulation roadways will not be reduced to a level that will be unable to accommodate projected traffic flows.

### 4.7.4 Parking Cashier Plaza Requirements

The existing cashier plaza contains nine exit lanes (four set up for cashiers and five automated pay stations which accept prepayments and pay in lane), which are adequate to accommodate 1,400 vehicle per hour. This represents approximately 18 percent of the parking capacity, which exceeds the target to accommodate 15 percent of long-term capacity and 100 percent of the short-term capacity in the peak hour. Since the automated lanes have almost twice the capacity of the cashiered lanes over time, more of the cashiered lanes can be converted to prepaid/pay in lane (if demand dictates).

### 4.7.5 High Capacity Transit (BRT or Light Rail) Route

Hampton Roads Transit (HRT) is exploring the options to expand the existing Tides light rail system from downtown to the Naval Station Norfolk. As a part of the environmental review process that began in the summer of 2019, HRT commenced a Draft Environmental Impact Statement (DEIS) on an eastern corridor where a transit technology/mode (BRT or Light Rail) and a locally preferred alternative (LPA) or route will be selected. The Naval Station Norfolk DEIS, also known as the Naval Station Norfolk Transit Corridor Project, is anticipated to conclude by the end of 2021.

The eastern route will likely travel along the Military Highway corridor and stop at intermediary destinations in Norfolk, continuing to the end destination of Naval Station Norfolk. This route could be configured to approach or enter the Airport, depending on the feasibility of a connection and environmental impacts. If an effective connection is provided to the Airport, the high capacity transit system has the potential to provide alternative access for employees and visitors to Norfolk, Virginia.

# 5 AIRPORT DEVELOPMENT CONCEPTS

To satisfy the facility requirements identified in **Chapter 4**, numerous concepts, site configurations, and development options were created and reviewed for the various components of the Airport. In many circumstances, multiple alternatives were identified, but eliminated early in the planning process from further consideration. The concepts deemed most reasonable to support the long-term operational sustainability of the Airport were identified and carried forward in the evaluation.

This chapter includes separate concepts and configurations for runways, taxiways, passenger terminal facilities, air cargo, general aviation, and support facilities. The number of potential recommendations is substantial; however, it is emphasized that although projects may be desired, they may not necessarily be financially or environmentally feasible. As such, recommendations presented within this chapter were further modified or narrowed during the financial planning components of the Master Plan Study. The overall effort refined the final strategy into actionable recommended projects for implementation in phases.

## 5.1 CONCEPT EVALUATION

Regardless of timeframe or activity level, the overarching principles guiding facility recommendations are to provide an elevated level of customer service and promote regional economic wellbeing while accommodating the evolving business model of the airlines and airport tenants. For some functional areas, such as the airfield, the logical recommendations were distinctly apparent as they are driven largely by Federal Aviation Administration (FAA) design standards as well as by existing infrastructure and available property. In contrast, improvements related to the passenger terminal buildings and vehicle parking have variability in their configuration. This is due to potential financing and implementation challenges, and their influence on surrounding Airport facilities.

During the identification of facility requirements, it became evident that the Master Plan would not consist of all-encompassing or competing alternatives for development of the Airport. Rather, the concepts and alternatives presented consist of a series of separate improvements that are assembled into the overall strategy. As such, individual components were reviewed and recommended separately to develop the preferred improvements program.

## 5.2 CURRENT AIRFIELD COMPLIANCES AND DEFICIENCIES

Norfolk International Airport (ORF) currently operates two runways (Runway 5/23 and Runway 14/32), each having unique capabilities and constraints. Each runway was evaluated based on its operational requirements, with the identified improvements provided below. To identify the best methods for improving airfield operations with regard to the runway infrastructure, it was important to evaluate the strengths and weaknesses of closing Runway 14/32 and/or the addition of a secondary runway (i.e., parallel Runway 5R/23L).

To satisfy operational efficiency, access to and from the runways, improvements and expansions to the associated taxiway systems, and FAA design standards were also identified. Concepts

relating to runway standards and deficiencies are presented in **Sections 5.2.1** and **5.2.2**, while taxiway standards and deficiencies are discussed in **Section 5.2.3**.

### 5.2.1 Runway 5/23

***Design Standards Satisfied***

Based on the demands outlined in **Chapter 4, Section 4.3.1**, the current length, width, Runway Object Free Zone (ROFZ), and Runway Protection Zones (RPZs) of the primary runway (Runway 5/23) are adequate and are anticipated to remain adequate throughout the forecast period; therefore, it is recommended that these fundamentals of Runway 5/23 be maintained throughout the planning period. No development alternatives are needed for these elements.

***Design Standards Needing Improvements***

Although many attributes of Runway 5/23 meet FAA design criteria, some features do not, including: the runway shoulders, safety areas, object free areas, and the blast pads.

- Runway Shoulders – When evaluating runway designs standards in **Chapter 4**, it was determined that Runway 5/23 does not meet the 25-foot shoulder requirement, with the current shoulders measuring zero to 15 feet. It is recommended that pavement be added to both sides of the runway to meet the 25-foot requirement.
- Runway Safety Area (RSA) – The Runway 5/23 RSA width contains a drainage structure located near the intersection with Taxiway 'A'. Furthermore, portions of the RSA do not meet the transverse grading requirements. Per FAA design criteria, transverse grades should be -1.5 percent to -3.0 percent away from the runway shoulder edge and beyond the runway ends; however, the existing grades are 0.7 percent to 2.0 percent. It is recommended these areas be graded to meet FAA design criteria and that the RSA is widened where necessary.
- Runway Object Free Area (ROFA) – The ROFA design standard for Runway Design Code (RDC) III and IV is 800 feet wide, centered about the runway centerline, and extends 1,000 feet beyond each runway end. Currently, the Runway 5/23 ROFA contains portions of the glideslope shelter and antenna. To address this condition, it is recommended that the glideslope shelter and antenna be relocated if feasible. If future relocation is not feasible, based on potential costs or airfield infrastructure design requirements that impact the potential for relocation, the Airport should seek an FAA Modification of Standards (MOS).
- Runway Blast Pads – Conformance to FAA design criteria requires that 200-foot wide by 200-foot length blast pads be placed symmetrically at the end of each RDC IV runway. At present, the blast pads on each runway end have a deficient width of only 150 feet. It is recommended that the blast pads be widened to meet the design criteria.

**Chapter 4** provides additional details regarding FAA design standards.

### 5.2.2 Runway 14/32

***Design Standards Satisfied***

Based on the requirements outlined within **Chapter 4, Section 4.3.1**, the current runway width, RSA, ROFZ, and RPZ of the crosswind runway (Runway 14/32) are adequate throughout the forecast period; therefore, these fundamentals of Runway 14/32 would be maintained as long as the Runway remains in operation. No development alternatives are needed for these elements.

***Design Standards Needing Improvements***

Although many attributes of Runway 14/32 meet FAA design criteria, the runway shoulders and ROFA are deficient.

- Runway Shoulders – Runway 14/32 currently lacks the required 25-foot paved shoulders. If the Runway 14/32 was retained for RDC III or IV, 25-foot shoulders would be added.
- ROFA – The ROFA design standard for RDC III and IV is 800 feet wide, centered about the runway centerline, and extends 1,000 feet beyond each runway end. Currently, the ROFA contains part of Robin Hood Road and the airport access road. As mentioned in **Chapter 4**, Runway 14/32 would be considered A-I or B-II moving forward. If Runway 14/32 remains in operation, the ROFA is still impacted by public roads.

Efforts Necessary to Meet FAA Design Standards (if retained)

In 2014, NAA completed a Study evaluating Runway 14/32 and what measures would be necessary to bring the runway into compliance with FAA standards. The results of the Study concluded that, if Runway 14/32 is to stay operational, the Authority has two options: 1) upgrade Runway 14/32 by extending the overall length to meet the needs and requirements, or 2) downgrade the runway by shortening and possibly limiting aircraft weights so the final compliant runway fits within the Airport's existing property.

Each option was further analyzed to determine what actions would be required to achieve compliance, followed by a cost estimate. The cost estimates included administration fees, preliminary expenses, land/structures/right-of-way, architectural engineering basic fees, project inspection fees, relocation expenses and payments, demolition and removal costs, construction and project improvement costs, and miscellaneous fees.

To upgrade the runway and bring Runway 14/32 into compliance based on critical aircraft, the estimated cost would be $25,200,000; however, to bring the runway into compliance by reducing the size of critical aircraft and by keeping improvements within the Airport's property, associated improvements costs were estimated at approximately $7,500,000 (assuming a B-I/B-II runway).

See **Appendix M** for the complete Runway 14/32 analysis.

Note: As discussed below in **Section 5.3.3**, based on the costs of maintaining Runway 14/32 in either scenario and on its limited use, it is recommended that this runway be closed in PAL 1 to avoid any additional costs. The environmental assessment associated with the closure of the runway will begin prior to the runway closure. In addition, the closure of Runway 14/32 will free up much-needed on-airport land areas that will allow the Authority to pursue additional aeronautical development. The closure of Runway 14/32 will also allow the Authority to prioritize projects to bring Runway 5/23 to FAA standards based on need and financial feasibility.

### 5.2.3 Taxiways

***Design Standards Satisfied***

The taxiway system at ORF was evaluated and compared to FAA standards for taxiway designs based on the Airport's Taxiway Design Group (TDG 5) (see **Section 4.3.3**). Based on FAA standards, the following items are satisfactory:

- Width: All taxiways
- Shoulders (30 feet): Taxiway 'V'
- Distance of taxiway centerlines from objects: Taxiways 'A', 'J', and 'F'
- Taxiway Safety Area (TSA): All taxiways
- Taxiway Object Free Area (TOFA): Taxiways 'A', 'J', and 'V'
- Taxiway Fillets: All taxiways, except for Taxiway 'C'

***Design Standards Needing Improvements***

Although many attributes of ORF's taxiway system meet FAA design criteria, some features do not, including the following:

- Shoulders: Neither Taxiway 'A' or 'F' have shoulders, while the shoulders for Taxiways 'C' and 'J' are less than the required width and unpaved.
- Distance of taxiway centerlines from objects: Taxiways 'C' and 'F'
  - Result of access roads impeding the TOFA (near the Runway 23 end)
- TOFA: Taxiways 'C' and 'F'
  - An MOS is required if objects are not be relocated outside the TOFA.
- Taxiway Fillets: Taxiway 'C'
  - Revised pavement geometry is necessary to meet standards.

## 5.3 AIRFIELD DEVELOPMENT CONCEPTS

This section identifies and evaluates potential runway and taxiway improvements that will enhance the overall safety, efficiency, reliability, and capacity of the airfield at ORF. Aircraft flows between the runway system and various functional areas (e.g., terminal area, air cargo, and general aviation) have been considered. Runway and taxiway concepts were developed through qualitative review of the following considerations:

- Construction and operating costs
- Operational changes and considerations
- Construction impacts, including ease of phasing and construction
- Airfield delays and other operational factors
- Capacity, safety, and reliability considerations
- Airspace considerations

- Environmental considerations
- Community acceptance

As discussed within previous section of the Master Plan, the goal is to plan for a safe and operationally efficient airfield. This can be accomplished by meeting the following objectives:

- Adhere to FAA design standards, reducing/eliminating Modifications of Standards
- Accommodate all existing and projected users
- Provide sufficient airfield capacity to meet demand, while minimizing airfield delays
- Reduce runway crossings (particularly in the middle third of runway) to improve safety
- Reduce risk of pilot confusion
    - Reducing the number of taxiways intersecting at a single location
    - Eliminating acute angle intersections
    - Increasing the pilot's situational awareness (proper signage and marking)
    - Avoiding wide expanses of pavement
    - Increasing visibility
- Determine the ultimate Airport Layout

### 5.3.1 Initial Runway Alternatives

ORF currently operates a two-runway system, each with unique capabilities and constraints. Both runways were evaluated based on previously outlined criteria. In total, 16 runway alternatives were initially evaluated, as listed in **Table 5-1**. Runway alternatives considered various issues, including displaced threshold locations on the primary runway (Runway 5/23), improvements to or closure of the crosswind runway (Runway 14/32), and various options for a new secondary parallel runway; which would be designated Runway 5R/23L. The purpose of evaluating the new secondary parallel runway within the alternatives considered is to protect the associated air space and land use for future infrastructure development. Previous studies also considered this need at ORF. The following runway alternatives include refinements of past concepts and additional layouts based on present and forecasted needs. It is noted that the justification for a secondary parallel runway has not been accepted by the FAA at this time but remains a strong ultimate goal of the Airport beyond the 20-year planning horizon.

**Table 5-1 – Initial Runway Alternatives**

| Alternative | Description | Length | Width | ARC | Visibility Minimums | TSS # (FAA EB 99) | Parallel Rwy | Parallel Txy | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | CL Separation | CL Separation | TDG |
| **Runway 5/23** | | | | | | | | | |
| 1 | Relocate 5 Threshold | 9,001' | 150' | D-IV | < 3/4 Mile | 5 - 34:1 | - | - | - |
| **Runway 14/32** | | | | | | | | | |
| 2 | Reconfigure 14/32 | 4,876' | 100' | B-II | ≥ 1 Mile | 4 - 20:1 | - | 240' | 3 |
| 3 | Close 14/32 | - | - | - | - | - | - | - | - |
| **New Parallel Runway (Runway 5R/23L)** | | | | | | | | | |
| 4 | 9,001' - 400' Offset | 9,001' | 150' | D-IV | < 3/4 Mile | 5 - 34:1 | 400' | - | - |
| 5 | 9,001' - 876' Offset | 9,001' | 150' | D-IV | < 3/4 Mile | 5 - 34:1 | 876' | 400' | 5 |
| 6 | 7,900' | 7,900' | 150' | C-III | < 3/4 Mile | 5 - 34:1 | 876' | 400' | 3 |
| 7 | 7,200' | 7,200' | 150' | C-III | < 3/4 Mile | 5 - 34:1 | 876' | 400' | 3 |
| 8 | 6,000', 34:1 | 6,000' | 150' | C-III | < 3/4 Mile | 5 - 34:1 | 876' | 400' | 3 |
| 9 | 6,000', 20:1 | 6,000' | 150' | C-II | ≥ 3/4 Mile | 4 - 20:1 | 876' | 300' | 3 |
| 10 | 5,500', 34:1 | 5,500' | 150' | C-II | < 3/4 Mile | 5 - 34:1 | 876' | 400' | 3 |
| 11 | 4,876', 20:1 | 4,876 | 100' | B-II | ≥ 1 Mile | 4 - 20:1 | 876' | 240' | 3 |
| **Additional Runway Alternatives** | | | | | | | | | |
| 12A | 5,500’ with EMAS | 5,500’ | 100’ | C-II | ≥ 3/4 Mile | 4 - 20:1 | 876' | 300’ | 3 |
| 12B | 5,500’ with EMAS | 5,500’ | 100’ | C-II | ≥ 1 Mile | 4 - 20:1 | 876' | 300’ | 3 |
| 13A | Runway Realignment | 7,500’ | 100’ | | | | | | |
| 13B | Runway Shift West | 7,900’ | 100’ | | | | | | |
| 14 | Rotated Runway | 5,500’ | 100’ | | | | | | |

Note: The new runway (5R/23L) would be parallel to the current runway (Runway 5/23), which would become Runway 5L/23R.
Source: CHA, 2019.

### 5.3.2 Eliminated Runway Alternatives

Through thorough evaluation and multiple work sessions and discussions with the Authority, 16 overall Runway alternatives were evaluated for consideration, based upon extensive planning considerations. These alternatives were subsequently presented to the Airport Board for consideration. Based upon these work sessions and Board review, it was determined that the following 11 alternatives listed within **Table 5-1** are not preferable and do not require further consideration:

- Alternative 1: Relocate Runway 5 Threshold
- Alternative 4: 9,001’, Offset: 400’ (Commercial Operations)
- Alternative 5: 9,001’, Offset: 876’ (Commercial Operations)
- Alternative 6: 7,900’ (Commercial Operations)
- Alternative 7: 7,200’ (Commercial Operations)
- Alternative 9: 6,000’, ARC C-II (20:1)
- Alternative 10: 5,500’, ARC C-II (34:1)
- Alternative 12A: 5,500’, ARC C-II, with EMAS, 3/4-mile visibility minimum
- Alternative 13A: Runway Realignment

- Alternative 13B: Runway Shift
- Alternative 14: Rotated Runway

**Appendix N** contains further detail and illustrations regarding the alternatives not chosen for further consideration.

### 5.3.3 Runway Alternatives for Further Consideration

Of the initial 16 alternatives, five have been recommended for further consideration, with each briefly discussed and illustrated throughout the subsequent sections.

***Runway 14/32 Alternatives***

Alternative 2: Reconfigure Runway 14/32

This alternative (**Figure 5-1**) would retain Runway 14/32 throughout the planning period. The runway was reviewed for standards for commercial operations and large jet aircraft (Airport Reference Code [ARC] C-III) and for lighter general aviation activity (ARC B-II). To provide the RSA and ROFA required for ARC C-III, the Accelerate to Stop Distance Available (ASDA) and Landing Distance Available (LDA) would remain below 4,000 feet for Runway 32 due to the limited property available, making this option impractical. If the Runway was designed for lighter (i.e., non-commercial) aircraft with ARC B-II and improved with a full-length parallel taxiway, all declared distances would be over 4,500 feet. This length would satisfy runway requirements for piston and turboprop aircraft, as well as for some small light jets.

However, there are several airspace and facilities to the northwest and southeast of the runway that may hinder further development. Additional improvements on the Runway 32 end impacts potential GA development necessary to accommodate future GA demand. Additionally, development is restricted on the Runway 14 end, which impacts the the expansion of the cargo facilities necessary to accommodate existing and future demand. Finally, based on runway length, and location of runway ends relative to user (GA operators) the runway usage remains very low (less than one percent of Airport operations, as described in **Chapter 4 – Facility Requirements**).

In terms of airspace, there are several non-compatible land uses within the Runway 14 RPZ. Although reducing the Runway ARC to B-II will reduce the RPZ size, some non-compatible uses, including residential owned land, and sections of Norview Ave and Azalea Garden Drive would still remain. **Table 5-2** lists the opportunities and constraints for Runway Alternative 2.

**Table 5-2 – Alternative 2: Reconfigure Runway 14/32**

| Opportunities | Constraints |
|---|---|
| ✈ Retains crosswind coverage for light general aviation aircraft<br>✈ Provides improved parallel taxiway | ✈ Design standards hinders usage by general aviation jets and commercial aircraft<br>✈ Requires parallel taxiway relocation and extension<br>✈ Occupies critical airport property that could be used for other facilities<br>✈ Airspace limitations (north/south traffic) and conflicts with surrounding facilities |

Source: CHA, 2019.

Alternative 3: Close Runway 14/32


This alternative (**Figure 5-2**) would permanently close Runway 14/32 and enable redevelopment of the property for expanded airport facilities. Runway 14/32 can only effectively serve piston aircraft and is used infrequently. (More detail regarding usage of Runway 14/32 is provided in **Chapter 3, Table 4-7: Runway Usage**). Furthermore, even with a runway extension the surrounding regional airspace would render commercial activity on this orientation difficult. As such, with very limited benefit, there is a strong case for this alternative; therefore, it was also advanced for additional consideration. **Table 5-3** lists the opportunities and constraints for Runway Alternative 3.

**Table 5-3 – Alternative 3: Close Runway 14/32**

| Opportunities | Constraints |
|---|---|
| ✈ Recaptures airport property to expand critical aviation facilities<br>✈ Avoids airspace conflicts with surrounding facilities<br>✈ Eliminates some operational conflicts and safety concerns | ✈ Reduces crosswind coverage for light General Aviation aircraft |

Source: CHA, 2019.

Note: Crosswind coverage is provided in Chapter 2 (Section 2.7.2) and in Chapter 4 (Section 4.3.1).




File: V:\PROJECTS\ANYVK4\33370\CADD\FIGURES\ALTERNATIVES\RUNWAY ALTERNATIVES\3 - EXHT-ORF-14-32 OPEN WITH FULL PARALLEL.DWG Saved: 7/24/2019 12:09:53 PM Plotted: 7/24/2019 12:15:20 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE


GRAPHIC SCALE
(FEET)
0 400 800

| DECLARED DISTANCES RUNWAY 14 | | |
|---|---|---|
| | EXISTING C-III | PROPOSED B-II |
| TORA | 4,876' | 4,876' |
| TODA | 4,876' | 4,876' |
| ASDA | 4,876' | 4,876' |
| LDA | 4,301' | 4,576' |

| DECLARED DISTANCES RUNWAY 32 | | |
|---|---|---|
| | EXISTING C-III | PROPOSED B-II |
| TORA | 4,876' | 4,876' |
| TODA | 4,876' | 4,876' |
| ASDA | 3,876' | 4,576' |
| LDA | 3,876' | 4,576' |

**Figure 5-1**
**Reconfigure Runway 14-32**

20:1 TSS , B-II Runway
Alternative 2




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE
(FEET)
0 300 600

**Figure 5-2**
**Close Runway 14-32**
Alternative 3

File: V:\PROJECTS\ANYVK4\33370\CADD\FIGURES\ALTERNATIVES\RUNWAY ALTERNATIVES\4 – EXHIBIT-ORF-14-32 CLOSED.DWG Saved: 7/24/2019 2:51:26 PM Plotted: 7/24/2019 2:54:26 PM Current User: Harris, Jackson LastSavedBy: 5451

***Proposed Parallel Runway 5R/23L Alternatives***

Each of the following three alternatives proposes a new parallel runway to the existing primary Runway 5/23. As such, the parallel runway's purposes are individually unique to each alternative, and effectively would be designated Runway 5R/23L. Although **Chapter 4** discussed and found airfield capacity and wind coverage on Runway 5/23 to be adequate, it did not address the potential functionality and operational efficiency of providing an alternative landing service to Runway 5/23 from a general aviation perspective (see **Chapter 1 – Airport Inventory** and **Chapter 4 – Facility Requirements** for discussion regarding operational factors and inefficient impacts of the existing airfield infrastructure).

Currently, smaller general aviation aircraft originating from the FBO and GA area must cross the active primary runway for multiple purposes. In order for GA aircraft to depart Runway 23, they must cross the primary at Taxiway 'A', 'G', or 'F' before entering Taxiway 'C' and taxiing to the Runway 23 end. This may cause operational inefficiencies and safety concerns co-mingling smaller GA piston aircraft with large commercial and cargo service airliners. Similarly, when the airfield is under northerly operations, GA aircraft must exit the runway to the opposite (west side) side of the airfield from the GA area, taxi back and cross the primary runway before taxiing to the FBO and/or GA area. Additionally, in order to deice, GA jets must cross the primary and enter the terminal apron (where the only deicing operations and deicing pad on the airfield is located).

Although the airfield capacity provided by a parallel runway is not required during the planning period covered by this Master Plan Update, these alternatives are included in an effort to identify adequate ways to accommodate all current users and future demand in an efficient, safe, and feasible manner. These alternatives pursue economic feasibility, constructability, and sustainability to improve the airfield of ORF into the future. Planning considerations made for these alternatives included limiting environmental impacts, limiting operational impacts to the Little Creek Bay Naval Installation, and preserving future airspace surrounding the Airport for development in the future.

<u>Parallel Runway – Coordination Between NAA & the United States Navy</u>

At the commencement of the Master Plan Update, a Planning Advisory Committee (PAC) which included the Navy was established for the purpose of providing guidance and advice on technical and local issues. As part of the PAC, NAA has been in discussions with the US Navy regarding the potential for a new parallel runway (Runway 5R/23L). Discussions covered several design iterations of the parallel runway, including a full-length parallel runway, a shortened parallel runway, and a new realigned runway. As a result of these discussions, the US Navy issued a letter to NAA indicating their concern for impacts to Naval training activity resulting from any parallel runway alternative. It is understood by NAA that there are potential impacts to current and future Navy operations. However, it should be noted that the potential for a parallel runway is a long-term, rather than a short-term, goal of the Authority. Therefore, the Authority and the US Navy will continue to be in coordination on airfield development at the Airport after the conclusion of the current Master Plan Update.

Alternative 8: Runway 5R/23L – 6,000 Feet, ARC C-III

This alternative (**Figure 5-3**) includes building a new parallel runway 876 feet east of the existing Runway 5/23. The new runway would be 6,000 feet in length and 150 feet in width, providing the greatest length without physically impacting adjacent Lake Whitehurst. This runway concept would be capable of serving up to C-III aircraft. Constraints to this alternative include penetration to the Runway 5L glideslope critical area, potentially requiring its relocation[29].

Accompanying the parallel runway would be a full-length parallel taxiway capable of accommodating aircraft up to TDG 3. This taxiway would be 50 feet wide and provide 400 feet of separation from the runway. As shown in **Figure 5-3**, Lake Whitehurst would impede the TOFA, TSA, and RSA. To minimize airspace and obstruction considerations, both runway ends would include displaced thresholds, reducing landing distance to 5,000 or 5,500 feet. The US Navy has indicated their concern for impacts to Naval training activity for this and any parallel runway alternative.

This concept warranted further consideration and was used as the foundation for the remaining derivative alternatives of various lengths and approach capabilities. **Table 5-4** lists the opportunities and constraints for Runway Alternative 8.

**Table 5-4 – Alternative 8: Runway 5R/23L (6,000', ARC C-III)**

| Opportunities | Constraints |
|---|---|
| ✈ Provides secondary runway for General Aviation airport users<br>✈ Avoids impacts to VORTAC<br>✈ 876' separation enables simultaneous VFR operations<br>✈ No direct physical impacts to Lake Whitehurst (however some wetland impacts will occur)<br>✈ Greater height over Little Creek Naval Base | ✈ Length limits usage by most commercial operations<br>✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and General Aviation parking apron)<br>✈ RPZ impacts to commercial buildings Potential Impact to Naval training activity |

Source: CHA, 2019.

Alternative 11: Runway 5R/23L – 4,876 Foot, ARC B-II

This alternative (**Figure 5-4**) illustrates the shortest parallel runway concept, providing the existing length of Runway 14/32 at 4,876 feet. The purpose of this concept is to replace the crosswind runway with a parallel runway. At this length, an ARC of B-II is appropriate with a taxiway offset of only 240 feet. A one-mile visibility minimum results in a steeper 20:1 threshold surface. This minimalist concept would reduce costs and impacts but would not accommodate the full general aviation corporate jet fleet. Larger aircraft would often taxi across the new runway to use the longer length of the primary runway. Nevertheless, with the lowest costs and impacts, this concept was advanced for further consideration. **Table 5-5** lists the opportunities and constraints for Runway Alternative 11.

[29] It should be noted that this constraint would be present for the other parallel runway alternatives with the same runway to runway offset.

**Table 5-5 – Alternative 11: Runway 5R/23L (Length: 4,876', ARC B-II)**

| Opportunities | Constraints |
|---|---|
| ✈ Lower cost General Aviation runway for non-jet aircraft<br>✈ No impacts to airport support facilities<br>✈ No impacts to Lake Whitehurst<br>✈ No VOR impacts<br>✈ Allows for 876-foot simultaneous runway operations | ✈ Runway use limited to propeller and light jet aircraft<br>✈ Potential Impact to Naval training activity |

Source: CHA, 2019.

Alternative 12B: Runway 5R/23L – 5,500 Foot, ARC C-II


Alternative 12B (**Figure 5-5**) is also intended to be a modest approach to providing a capable parallel runway, and thus, includes a 5,500-foot length and 100-foot width. To keep costs and potential impacts at a minimum, this concept adds an aircraft arresting system, known as an Engineered Materials Arresting System (EMAS), at both ends of the runway. The EMAS beds eliminate the requirement for an RSA beyond the "stop-end" of the runway, with only a 600-foot long RSA on the approach end. As such, the RSA impacts to Lake Whitehurst are avoided, requiring little filling or grading overall. The ARC C-II design includes a 300-foot runway-taxiway offset. A 600-foot runway displacement is included on Runway 5R to avoid building and object obstructions.

Alternative 12B depicts one-mile visibility minimum, which results in a reduced width of the RPZ that is clear of all buildings. It also has a steeper 20:1 threshold surface. Due to its minimum impacts, Alternative 12B was advanced for potential implementation. **Table 5-6** lists the opportunities and constraints for Runway Alternative 12B, and **Appendix N** lists the differences between Alternatives 12A and 12B.

**Table 5-6 – Alternative 12B: Runway 5R/23L (Length: 5,500', ARC C-II)**

| Opportunities | Constraints |
|---|---|
| ✈ Provides secondary runway for General Aviation airport users<br>✈ Avoids impacts to VORTAC<br>✈ 876' separation enables simultaneous VFR operations<br>✈ No impacts to Lake Whitehurst<br>✈ No wetland impacts | ✈ Length restricts usage by commercial operations<br>✈ Potential Impact to Naval training activity |

Source: CHA, 2019.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)


0 500 1000

| DECLARED DISTANCES PROPOSED RUNWAY 5R-23L | | |
|---|---|---|
| | RUNWAY 5R | RUNWAY 23L |
| TORA | 6,000' | 6,000' |
| TODA | 6,000' | 6,000' |
| ASDA | 6,000' | 6,000' |
| LDA | 5,000' | 5,500' |

NOTE: COMMERCIAL TAKEOFFS ARE RESTRICTED ON 5R DUE TO LOCATION OF EXISTING 5L GLIDESLOPE CRITICAL AREA.

**Figure 5-3**
**Proposed 5R-23L - 6,000'**
34:1 TSS , C-III Runway
180' SHIP HEIGHTS
Alternative 8

File: V:\PROJECTS\ANYX4\33370\CADD\FIGURES\ALTERNATIVES\RUNWAY ALTERNATIVES\9 - EXHIT-ORF-CONCEPT 5B2 - 6,000' 23 TSS - 34701.DWG Saved: 8/21/2019 4:31:52 PM Plotted: 8/21/2019 4:37:18 PM Current User: Harris, Jackson LastSavedBy: 5451




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)


0 500 1000

| DECLARED DISTANCES PROPOSED RUNWAY 5R-23L | | |
|---|---|---|
| | RUNWAY 5R | RUNWAY 23L |
| TORA | 4,876' | 4,876' |
| TODA | 4,876' | 4,876' |
| ASDA | 4,876' | 4,876' |
| LDA | 3,876' | 4,876' |

**Figure 5-4**
**Proposed 5R-23L - 4,876'**

20:1 TSS , B-II Runway
180' SHIP HEIGHTS
Alternative 11

File: V:\PROJECTS\ANY\X41333701\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\12 - EXHIT-ORF-CONCEPT 5A1 - 4,876' 23 TSS - 20101.DWG Saved: 7/9/2019 11:57:15 AM Plotted: 7/9/2019 11:59:39 AM Current User: Abney, Nikki LastSavedBy: 5835




File: V:\PROJECTS\ANY\X4\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\13B - EXHIT-ORF-CONCEPT - 5,500 100 FT WIDE.DWG Saved: 7/9/2019 1:20:58 PM Plotted: 7/9/2019 1:22:54 PM Current User: Abney, Nikki LastSavedBy: 5835

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

| DECLARED DISTANCES PROPOSED RUNWAY 5R-23L | | |
|---|---|---|
| | RUNWAY 5R | RUNWAY 23L |
| TORA | 5,500' | 5,500' |
| TODA | 5,500' | 5,500' |
| ASDA | 5,500' | 5,500' |
| LDA | 4,900' | 5,500' |

**Figure 5-5**
**Proposed 5R-23L**
**5,500' With EMAS At Both Ends**

20:1 TSS , C-II Runway
Not Lower than 1 Mile Visibility
Alternative 12B

### 5.3.4 Taxiway Alternatives

Aircraft ground movement at ORF is supported by a system of taxiways providing access to all portions of the airfield. Nevertheless, portions of the taxiway system are considered non-standard with regard to current FAA design standards or are such that an improved configuration could reduce the risk of pilot confusion and thus a runway incursion. The following taxiway alternatives were developed with the aforementioned considerations and adherence to all FAA design standards.

It is important to note that with each concept, focus was given to the portions of the taxiway system west of the existing Runway 5/23; therefore, the conceptualized taxiway system supporting the potential parallel Runway 5R/23L remains the same throughout each alternative with a TDG 3 full-length parallel taxiway. **Table 5-6** lists the opportunities and constraints for all taxiway alternatives.

***Taxiway Alternative 1***

Taxiway Alternative 1 (**Figure 5-6**) addresses the variable separation distance between Taxiway 'C' and Runway 5/23. Taxiway 'C' is currently designated as TDG 5, requiring a minimum taxiway to runway centerline distance of 400 feet; however, the current separation of Taxiway 'C' ranges from 400 feet at the Runway 5 end to over 600 feet at the Runway 23 end. While this distance provides an added separation margin, it also reduces the available non-movement space near the southeasternmost gates of Terminal Concourse B, requiring aircraft push-back into the Taxiway 'C' environment; therefore, Taxiway Alternative 1 illustrates a parallel Taxiway 'C' offset of 400 feet from the Runway 5 end to Taxiway 'H'.

Additionally, Taxiway Alternative 1 illustrates the conversion of the Runway 14/32 pavement (from Runway 5/23 northeastward) into a new TDG 3 taxiway (relocated Taxiway 'D'). This conversion of pavement allows for continued ingress/egress to the cargo area and for potential aeronautical development along the taxiway. If necessary, the taxiway can be shortened to accommodate the realignment of Robin Hood Road and the expansion of the cargo facility.

Lastly, Taxiway Alternative 1 shows the removal and update of taxiways that would be either no longer required or are non-standard. Specifically, this concept shows a realignment of Taxiway 'F' to meet current FAA taxiway design geometry. As a result of this realignment, this concept also shows a relocation of Taxiway 'E' to provide improved access. Although this concept shows the removal of Taxiway 'G', a pavement corridor is reserved for an Aircraft Rescue and Fire Fighting (ARFF) access road between the existing firefighting station and the southern portion of the airfield.

***Taxiway Alternative 2***

Taxiway Alternative 2 (**Figure 5-7**) shows similar concepts to address non-standard taxiway conditions and improved design geometry. While Taxiway Alternative 1 shows a Taxiway 'C' offset of 400 feet from the Runway 5 end to Taxiway 'H', this concept shows the offset distance throughout the full length of the taxiway. This full-length offset of 400 feet does not require a turn north of Taxiway 'H' and is compliant with current FAA taxiway geometry; however, this configuration impacts the existing Runway 23 glide slope antennae and PAPI, requiring relocation of both NAVAID systems. As a result of these relocations, a portion of Lake Whitehurst east of the Runway 23 end would require filling and grading in order to provide sufficient ground to

accommodate reinstallation and operation of both systems, as well as to provide access roads. Significant environmental permitting and coordination would be required prior to moving the NAVAIDs.

***Taxiway Alternative 3***

Similar to Taxiway Alternative 1, Taxiway Alternative 3 (**Figure 5-8**) shows a partially realigned offset of Taxiway 'C' from the Runway 5 end to Taxiway 'H', along with the conversion of the Runway 14/32 pavement (from Runway 5/23 northward) into a new TDG 3 taxiway; however, this concept adds a new TDG 5 partial-length parallel taxiway east of Runway 5/23 from the end of Runway 5 to the realigned portion (as discussed in Taxiway Alternative 2) of Taxiway 'E', terminating prior to Lake Whitehurst to avoid filling a portion of the lake.

To accommodate the parallel taxiway, relocation of both the VORTAC and Runway 5 glide slope antenna would be required.

**Table 5-7 – Taxiway Alternatives**

| Alternative | Opportunities | Constraints |
|---|---|---|
| **Alternative 1: Partial Realignment of Taxiway C** | ✈ Realignment of Taxiway C to 400' offset improves the separation from Concourse B | ✈ Taxiway C retains existing curves near Runway 23 end |
| | ✈ Partial taxiway realignment avoids impact to Runway 23 Glideslope | ✈ Does not provide full-length standard parallel taxiway |
| | ✈ Conversion of Runway 14/32 to Taxiway expands area for air cargo apron | ✈ |
| | ✈ Removes non-standard conditions (direct apron to runway access) | |
| | | |
| **Alternative 2: Full Realignment of Taxiway C** | ✈ Full Realignment removes all curves in Taxiway C centerline | ✈ Taxiway C realignment near Runway 23 requires relocation of Glideslope and PAPI |
| | ✈ Realignment improves separation from Concourse B | ✈ Substantial environmental impacts to Lake Whitehurst |
| | ✈ Conversion of Runway 14/32 to Taxiway expands area for air cargo apron | |
| | | |
| **Alternative 3: Extension of Taxiway J** | ✈ Improves operational flexibility | ✈ Requires relocation of VORTAC |
| | ✈ Provides additional runway exits | ✈ Taxiway J cannot be extended to full parallel without impacts to Lake Whitehurst |

Source: CHA, 2019.

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 400 800

## LEGEND

- Future Airfield Pavement
- Future Parallel Runway

RELOCATED TAXIWAY 'D'

INSTALL HMI PVMT. (TYP.)

REMOVE EX. TAXIWAY PVMT. (TYP.)

PAINT RUNWAY MARKINGS (TYP.)

RECONFIGURED TAXIWAY 'C'

EXISTING RUNWAY '5L-23R'

FUT. ARFF ACCESS ROAD

V A C B G H E C J G F

**Figure 5-6**

Taxiway Alternative 1

File: V:\PROJECTS\ANY\K43\33370\CADD\FIGURES\ALTERNATIVES\TAXIWAY ALTERNATIVES\ORF-TW-ALT 1.DWG Saved: 7/16/2019 1:52:20 PM Plotted: 8/12/2019 3:08:44 PM Current User: French, Adam LastSavedBy: 5451

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

RELOCATED TAXIWAY 'D'

RECONFIGURED TAXIWAY 'C'

EXISTING RUNWAY '5L-23R'

REMOVE EX. TAXIWAY PVMT. (TYP.)

PAINT RUNWAY MARKINGS (TYP.)

INSTALL HMI PVMT. (TYP.)

GLIDESLOPE CRITICAL AREA

LAND REQUIRED

RELOCATE GLIDE SLOPE & AWOS

NEW GLIDE SLOPE AREA

FUT. ARFF ACCESS ROAD

A B C E G H J V

GRAPHIC SCALE (FEET)

0 500 1000

## LEGEND

- Future Airfield Pavement
- Future Parallel Runway

**Figure 5-7**

Taxiway Alternative 2

File: V:\PROJECTS\ANY\K43\33370\CADD\FIGURES\ALTERNATIVES\TAXIWAY ALTERNATIVES\ORF-TW-ALT 2.DWG Saved: 7/24/2019 8:39:02 AM Plotted: 8/12/2019 3:23:22 PM Current User: French, Adam LastSavedBy: 4571

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 400 800

## LEGEND

- Future Airfield Pavement
- Future Parallel Runway

RELOCATED TAXIWAY 'D'

REMOVE EX. TAXIWAY PVMT. (TYP.)

RECONFIGURED TAXIWAY 'C'

EXISTING RUNWAY '5L-23R'

NEW TAXIWAY

RELOCATE GLIDESLOPE

INSTALL HMI PVMT. (TYP.)

PAINT RUNWAY MARKINGS (TYP.)

RELOCATE VORTAC

FUT. ARFF ACCESS ROAD

**Figure 5-8**

Taxiway Alternative 3

File: v:\PROJECTS\ANY\K4\33370\CADD\FIGURES\ALTERNATIVES\TAXIWAY ALTERNATIVES\ORF-TW-ALT 3.DWG Saved: 7/16/2019 1:45:45 PM Plotted: 8/12/2019 3:27:35 PM Current User: French, Adam LastSavedBy: 5451

## 5.4 PASSENGER TERMINAL FACILITY ALTERNATIVES

The preliminary passenger terminal facility concepts for ORF were developed to satisfy the identified facility requirements throughout the 20-year planning period (**Chapter 4**, **Section 4.4**). Each concept incorporates the new or replacement facilities within the footprint of the existing terminal complex. In each alternative, the existing and proposed parking garages are retained, as is the 2002 arrivals building; however, several concepts consider the possibility of developing a two-level terminal facility with upper- and lower-level roadways along with a two-level departures/arrivals building (i.e., headhouse). This two-level concept would have baggage claim functions on the lower level and would call for repurposing the arrivals building as a ground transportation center (GTC) on the lower-level and airport administrative offices on the upper mezzanine level, with the potential for future infrastructure improvements to the second level with renovation as needed for administrative repurposing. Other than the Status Quo Alternative, all of the terminal concepts include substantial changes to the concourses, gates, security screening, ticketing, concessions, access roadways and other facilities, as described below.

Based on discussions with the Norfolk Airport Authority (NAA) management staff and Board Members, the preliminary terminal alternatives were refined, with the selection of a recommended concept. The ultimate plan was organized to include several phases, based on Planning Activity Levels (PALs) following a long-term implementation program.

### 5.4.1 Status Quo Alternative

The main departure terminal and Concourses A and B were originally constructed in 1974. Over the past 45 years, the NAA has continuously maintained these facilities, including several renovations in the past five years to upgrade the main lobby (i.e., atrium), concourses, airline gate areas, restrooms, concessions, and security checkpoints, and additional renovations are in the design phase. Thus, the Status Quo Alternative includes continuous improvements and renovations of existing facilities, but without any major new or replacement facilities.


It is noted that without expansion of concourses, gates, post-security concessions, out-bound baggage processors, and other facilities, current problem areas will persist, and the level of passenger service will continually decline as activity grows. At a minimum, with the addition of some airline gates (potentially through an extension of Concourse A), the existing passenger terminal could continue to operate through the planning period, although all of the current shortcomings will become heightened to the detriment of the passenger experience and operational efficiency.

### 5.4.2 2009 Master Plan Alternative

The previous Airport Master Plan developed an incremental terminal recommendation that retained the existing building layout and internal configuration and included expansion of gates and associated facilities through the addition of a third concourse (Concourse C). This layout utilized the area of the long-term surface parking lot for the location of the additional concourse. This alternative was a simple and low-cost expansion option that maximized use of existing facilities; however, several shortcomings were apparent, including the need for a third security checkpoint and taxilane/push-back conflicts between the concourses. The following exhibit

(**Figure 5-9**) from the 2009 Master Plan provides a graphic depiction of this concept, and **Table 5-8** summarizes the 2009 passenger terminal alternative.

**Figure 5-9 – 2009 Passenger Terminal Alternative**




Source: CHA, 2019.

**Table 5-8 – 2009 Passenger Terminal Facility Summary**

| General Layout | |
|---|---|
| Retain the existing terminal layout including the departure and arrivals building, curbside and circulation, but expand the number of gates, hold rooms, and post-security concessions by adding a third concourse. | |
| **Advantages** | **Disadvantages** |
| ✈ Low capital costs<br>✈ Ease of construction phasing; virtually no impact to passenger activity<br>✈ Provides adequate number of gates and added space for related services. | ✈ Requires addition of a third security checkpoint. Issues with TSA staffing and duplication of facilities<br>✈ Results in separation and some duplication of all post-security facilities, services, and concessions<br>✈ Reduced flexibility for airline gate utilization and operations<br>✈ No improvements or expansion of other needed facilities (e.g., out-bound baggage)<br>✈ Existing deficiencies remain in passenger circulation<br>✈ Retains split facilities for the ticketing hall and curb side drop-off, with associated passenger confusion<br>✈ Retains the overly complex roadway layout, see Figure 5-10. |

Source: CHA, 2019.


Due to the disadvantages of the 2009 Terminal Alternative, four new concepts were developed as part of this Master Plan and are subsequently discussed and illustrated below.

### 5.4.3 Passenger Terminal Facility Alternative 1

Passenger Terminal Facility Alternative 1 (**Figure 5-11**) addresses pre-security configuration issues of the current terminal complex. In particular, the split ticketing halls are combined and relocated to the west side of the departure building, facing the arrival building. This enables reconfiguration of the terminal roadways with an efficient parallel alignment with the arrivals building's curbside. The new departure curbside will provide greater overall length, with adjacent short-term parking serving both arrivals and departures.

Relocation of the ticketing halls enable redevelopment of the lower level of the departure building for expansion of the outbound baggage make-up facilities to serve all three concourses. TSA security would be consolidated into a single checkpoint that is located on the eastern half of the atrium area. As is the case with the Status Quo Alternative, the previous Airport Master Plan developed an incremental terminal recommendation that retained the existing building layout and internal configuration, and included gates, and associated facilities through the addition of a third concourse (Concourse C). This layout utilizes the area of the long-term surface parking lot for the location of the additional concourse, with expansion of Terminal Concourse A. This alternative is a simple and low-cost expansion option that maximizes use of existing facilities; however, several shortcomings are apparent, including long walking distances and taxilane/push-back conflicts between the concourses. **Figure 5-11** provides a graphic depiction of this concept, while **Table 5-9** summarizes Passenger Terminal Alternative 1.


### Figure 5-10 – Existing Terminal Curbside Layout




### Table 5-9 – Passenger Terminal Facility Alternative 1 Summary

| General Layout | |
|---|---|
| Builds upon the 2009 terminal layout with three concourses, and retention of the arrival building. The departure building is modified to relocate and consolidation of the ticketing halls, security screening checkpoint, and departure curbside, expansion of outbound baggage make-up facilities, and improve vehicular circulation. | |
| **Advantages** | **Disadvantages** |
| ✈ Modest capital costs through retention of several existing facilities<br>✈ Ease of construction phasing with minor impacts to passenger activity<br>✈ Provides adequate additional facilities for all terminal requirements, including outbound baggage<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing hall and curbside drop-off (reduces passenger confusion)<br>✈ Eliminates overly complex roadway layout<br>✈ Eliminates the need for a third security checkpoint. | ✈ Results in separation and potential duplication of all post-security facilities, services, and concessions<br>✈ Reduced flexibility for airline gate utilization and operations<br>✈ Retains existing long walking distances to baggage claim and parking garages |

Source: CHA, 2019.




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Concessions
- Airline
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement
- Removal/Demolition

**Figure 5-11**
Terminal Facility
Alternative 1


### 5.4.4 Passenger Terminal Facility Alternative 2A

The goal of Passenger Terminal Facility Alternative 2A (**Figure 5-12**) is to retain the benefits of Alternative 1, while removing its disadvantages. To achieve this goal, Passenger Terminal Facility Alternative 2A includes the same improvements to the departure building's vehicular circulation, and parking as Alternative 1; however, this alternative would completely replace existing Concourses A and B with a new consolidated north-south concourse to house all gates and a centralized security checkpoint and concession core. Alternative 2A assumes that the departures and arrivals function will continue to be separated. As such, the arrivals building is proposed to remain as the baggage claim facility on the lower level; however, in order to provide increased consolidated space for airport administrative functions, the mezzanine level would be used. **Table 5-10** summarizes the Passenger Terminal Facility Alternative 2A.

**Table 5-10 – Passenger Terminal Facility Alternative 2A Summary**

| General Layout | |
|---|---|
| Includes the development of a new departures building, curbside, and circulation. All existing gates are replaced with a large new contact gate concourse and centralized security checkpoint and concessions core. Arrivals building will continue to function as is with the addition of airport administrative offices on the second level. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates the security checkpoint, improves TSA staffing and eliminates duplicate facilities<br>✈ Enables a new central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility for airline gate utilization and operations<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing halls and curbside drop-off (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout | ✈ High capital costs, with substantial new facilities<br>✈ Moderately difficult construction phasing with impact to passenger activity<br>✈ Retains long walking distances to baggage claim and parking garages |

Source: CHA, 2019.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Concessions
- Airline
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement
- Removal/Demolition

**Figure 5-12**
Terminal Facility
Alternative 2A

File: V:\PROJECTS\ANY\X4\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL ALTERNATIVES\TERMINAL_ALT2A.DWG Saved: 7/24/2019 10:06:40 AM Plotted: 8/22/2019 2:23:27 PM Current User: Harris, Jackson LastSavedBy: 5451


### 5.4.5 Passenger Terminal Facility Alternative 2B

The goal of Passenger Terminal Facility Alternative 2B (**Figure 5-13**) is to retain the benefits of Alternative 2A, while consolidating passenger and baggage processing functions and roadway/curbside activities into a single consolidated facility. To achieve this goal, Passenger Terminal Facility Alternative 2B includes the same improvements to the concourse and gate area; however, it would completely replace the departures and arrivals buildings and vehicular circulation roadway system. In order to do this, a two-level roadway system would be constructed to serve a new two-level terminal building. The upper level of this building would house the departures and out-bound baggage make-up functions and the lower level will accommodate the in-bound baggage and baggage claim facilities. Alternative 2B calls for repurposing the arrivals building as a new GTC on the lower level, with the second level use to house an expanded airport administrative office area. As in Alternative 2A, this alternative would completely replace existing Concourses A and B with a new consolidated north-south concourse to house all gates, with a centralized security checkpoint and concessions core. **Table 5-11** summarizes the Passenger Terminal Facility Alternative 2B.

**Table 5-11 – Passenger Terminal Facility Alternative 2B Summary**

| General Layout | |
|---|---|
| Includes the development of a new consolidated passenger and baggage processing facility with a two-level building and support roadway/curbside system. All existing gates are replaced with a large new contact gate concourse and centralized security checkpoint and concessions core. Arrivals building will be repurposed as a ground transportation center and will also provide area for airport administrative offices on the second level. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates the security checkpoint, improves TSA staffing and eliminates duplicate facilities<br>✈ Enables a new central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility for airline gate utilization and operations<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing and arrivals halls (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout<br>✈ Provides a new GTC to house all ground transportation functions | ✈ Higher capital costs, with substantial new facilities and a reconfigured GTC/administrative building<br>✈ Highly difficult construction phasing with impact to passenger and tenant activity<br>✈ Retains long walking distance to parking garages |

Source: CHA, 2019.




File: V:\PROJECTS\ANY\K4\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL_ALTERNATIVES\TERMINAL_ALT2B.DWG Saved: 7/30/2019 10:00:30 AM Plotted: 8/22/2019 2:28:45 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Concessions
- Airline - Ticketing
- Airline - Baggage Claim
- Ground Transportation
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement
- Removal/Demolition

**Figure 5-13**
Terminal Facility
Alternative 2B


### 5.4.6 Passenger Terminal Facility Alternative 3A

Passenger Terminal Facility Alternative 3A (**Figure 5-14**) is a derivative of Alternative 2A that provides for additional gate expansion (beyond what is needed during the planning period) in a configuration that may reduce passenger walking distances. The concept includes the centralized security checkpoint and up to four concourses surrounded by a central concessions core. The layout would incorporate development of two double-loaded concourses, with ultimate expansion of two additional single-loaded piers. Alternatively, the concept could include partial development of all four concourses, with expansion as needed. As shown in the figure, up to 42 gates could be accommodated. **Table 5-12** summarizes the Passenger Terminal Facility Alternative 3A.

**Table 5-12 – Passenger Terminal Facility Alternative 3A Summary**

| General Layout | |
|---|---|
| Includes the development of a new departures building, curbside, and circulation. All existing gates are replaced with a large new contact gate concourse, but with greater expansion capability on four concourses. Includes a centralized security checkpoint and concessions core. Arrivals building will continue to function as is with the addition of airport administrative offices on the second level. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates security checkpoint, improves TSA staffing and eliminates duplicate facilities<br>✈ Enable central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility and expandability for airline gate utilization and operations<br>✈ Potential to reduce passenger walking distances between the security screening checkpoint and concourse gates/holdroom areas<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing halls and curbside drop-off (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout | ✈ High capital costs, with substantial new facilities<br>✈ Moderately difficult construction phasing with impact to passenger activity<br>✈ Four concourses will result in duplication of concessions and operational functions<br>✈ Multiple concourses may result in complex signage and passenger confusion.<br>✈ Retains long walking distances between the concourse gates/holdrooms/security screening checkpoint and the parking garage/baggage claim areas. |

Source: CHA, 2019.




File: V:\PROJECTS\ANY\K41\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL ALTERNATIVES\TERMINAL_ALT3A.DWG Saved: 8/22/2019 1:38:18 PM Plotted: 8/22/2019 1:56:07 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Concessions
- Airline
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement
- Future Building Expansion
- Removal/Demolition

**Figure 5-14**
Terminal Facility
Alternative 3A


### 5.4.7 Passenger Terminal Facility Alternative 3B

The goal of Passenger Terminal Facility Alternative (**Figure 5-15**) is to retain the benefits of Alternative 3A, while consolidating passenger and baggage processing functions and roadway/curbside activities into a single consolidated facility. To achieve this goal, Passenger Terminal Facility Alternative 3B includes the same improvements to the concourse and gate area as Alternative 3A; however, it would completely replace the departures and arrivals buildings and vehicular circulation roadway system. In order to do this, a two-level roadway system would be constructed to serve a new two-level terminal building. The upper level of this building would house the departures and out-bound baggage make-up functions and the lower level will accommodate the in-bound baggage and baggage claim facilities. Alternative 3B calls for repurposing the arrivals building as a new GTC on the lower level, with the second level used to house an expanded airport administrative office area. As in Alternative 3A, this alternative would completely replace existing Concourses A and B, with a new consolidated north-south concourse to house all gates and provide additional gates beyond what is needed in the 20-year planning horizon. This concept also incorporates a centralized security checkpoint and concessions core. **Table 5-13** summarizes the Passenger Terminal Facility Alternative 3B.

**Table 5-13 – Passenger Terminal Facility Alternative 3B Summary**

| General Layout | |
|---|---|
| Includes the development of a new consolidated passenger and baggage processing facility with a two-level building and support roadway/curbside system. All existing gates are replaced with a large new contact gate concourse and centralized security checkpoint and concessions core. Arrivals building will be repurposed as a ground transportation center and will also provide area for airport administrative offices on the second level. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates the security checkpoint, improves TSA staffing and eliminates duplicate facilities<br>✈ Enables a new central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility and future expandability for airline gate utilization and operations<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing and arrivals halls (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout<br>✈ Provides an expanded area for airport administrative offices<br>✈ Provides a new GTC to house all ground transportation functions | ✈ Higher capital costs, with substantial new facilities and a reconfigured GTC/administrative building<br>✈ Highly difficult construction phasing with impact to passenger and tenant activity<br>✈ Four concourses will result in duplication of concessions and operational functions<br>✈ Multiple concourses may result in complex signage and passenger confusion.<br>✈ Retains long walking distance to parking garages |

Source: CHA, 2019.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Concessions
- Airline - Ticketing
- Airline - Baggage Claim
- Ground Transportation
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement
- Removal/Demolition

**Figure 5-15**
Terminal Facility
Alternative 3B

File: V:\PROJECTS\ANY\K41\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL ALTERNATIVES\TERMINAL_ALT3B.DWG Saved: 8/22/2019 1:45:04 PM Plotted: 8/22/2019 1:52:40 PM Current User: Harris, Jackson LastSavedBy: 5451


### 5.4.8 Passenger Terminal Facility Alternative 4A

Passenger Terminal Facility Alternative 4A (**Figure 5-16**) is a derivative of Alternatives 1, 2A, and 3A that provides for additional gate expansion (beyond that needed throughout the planning period); however, due to the split concourse configuration, Alternative 4A increases walking distances between gates and to the headhouse but reduces distances from the headhouse to arrivals and parking This concept includes the centralized security checkpoint and two double-loaded concourses (one to the north and one to the south). It also provides five contact gates at its central core. This central portion of the terminal also serves as a central concessions core area and supports a consolidated security screening checkpoint. The layout would incorporate development of up to 10 remote aircraft parking positions that can support overnight parking and/or four deicing lanes. Alternatively, the concept could include partial development of a third central concourse, with expansion as needed. **Table 5-14** summarizes the Passenger Terminal Facility Alternative 4A.

**Table 5-14 – Passenger Terminal Facility Alternative 4A Summary**

| General Layout | |
|---|---|
| Includes a new and improved departure building, curbside, and centralized security checkpoint, but with greater expansion capability on two concourses. The new departures building that will house all ticketing and out-bound baggage functions and is moved closer to the arrivals building, and an overhead canopy is provided. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates security checkpoint and improves TSA staffing<br>✈ Enable central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility and expandability for airline gate utilization and operations<br>✈ Combines split facilities for the ticketing halls and curbside drop-off (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout | ✈ High capital costs, with substantial new facilities<br>✈ Moderately difficult construction phasing with impact to passenger activity<br>✈ Two concourses will result in duplication of concessions and operational functions<br>✈ Increases walking distances between gates and to arrivals building and parking given the extension lengths of the concourses |

Source: CHA, 2019.




File: V:\PROJECTS\ANY\K4\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL ALTERNATIVES\TERMINAL_ALT4A.DWG Saved: 8/7/2019 1:57:55 PM Plotted: 8/22/2019 2:09:23 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 125 250

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Airline - Ticketing
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement

**Figure 5-16**
Terminal Facility
Alternative 4A


### 5.4.9 Passenger Terminal Facility Alternative 4B

The goal of Passenger Terminal Facility Alternative (**Figure 5-17**) is to retain the benefits of Alternative 4A, while consolidating passenger and baggage processing functions and roadway/curbside activities into a single consolidated facility. To achieve this goal, Passenger Terminal Facility Alternative 4B includes the same improvements to the concourse and gate area as Alternative 4A; however, it would completely replace the departures and arrivals buildings and vehicular circulation roadway system. In order to do this, a two-level roadway system would be constructed to serve a new two-level terminal building. The upper level of this building would house the departures and out-bound baggage make-up functions and the lower level will accommodate the in-bound baggage and baggage claim facilities. Alternative 4B calls for repurposing the arrivals building as a new GTC on the lower level with the second level to house airport administrative office area. This alternative would completely replace existing Concourses A and B, with two new consolidated double-loaded concourses, one to the north and one to the south of the headhouse, along with a centralized security checkpoint and concessions core. In addition, 5 contact gates are located in the central portion of the terminal facility. Alternative 4B meets the 20-year gate requirements and provides expansion capabilities for a third central concourse beyond what is needed in the 20-year planning horizon. **Table 5-15** summarizes the Passenger Terminal Facility Alternative 4B.

**Table 5-15 – Passenger Terminal Facility Alternative 4B Summary**

| General Layout | |
|---|---|
| Includes the development of a new consolidated passenger and baggage processing facility with a two-level building and support roadway/curbside system. All existing gates are replaced with two new contact gate concourses and centralized security checkpoint and concessions core. Arrivals building will be repurposed as a ground transportation center and will also provide area for airport administrative offices on the second level. | |
| **Advantages** | **Disadvantages** |
| ✈ Provides adequate additional facilities for all terminal requirements<br>✈ Consolidates the security checkpoint and improves TSA staffing<br>✈ Enables a new central FIS facility below an expanded security checkpoint<br>✈ Provides passenger access to all post-security facilities, services, and concessions<br>✈ Maximizes flexibility and future expandability for airline gate utilization and operations<br>✈ Combines split facilities for the ticketing and arrivals halls (reduces passenger confusion)<br>✈ Eliminates the overly complex roadway layout<br>✈ Provides an expanded area for airport administrative offices<br>✈ Provides a new GTC to house all ground transportation functions | ✈ Higher capital costs, with substantial new facilities and a reconfigured GTC/administrative building<br>✈ Highly difficult construction phasing with impact to passenger and tenant activity<br>✈ Two concourses will result in duplication of concessions and operational functions<br>✈ Increases walking distances between gates and parking garages |

Source: CHA, 2019.




File: V:\PROJECTS\VANYX4\33370\CADD\FIGURES\ALTERNATIVES\TERMINAL ALTERNATIVES\TERMINAL_ALT4B.DWG Saved: 8/7/2019 1:59:23 PM Plotted: 8/22/2019 2:13:55 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 125 250

## LEGEND

- Existing Facility
- Circulation/Holdroom
- Airline - Ticketing
- Airline - Baggage Claim
- Security/Regulatory
- New Apron/Airfield Pavement
- New Landside Pavement

**Figure 5-17**
Terminal Facility
Alternative 4B

## 5.5 LANDSIDE COMMERCIAL DEVELOPMENT OPTIONS

Should the Airport's parking capacity become constrained, the area southwest of the new Robin Hood Road/Norview Road intersection can be developed for additional long-term parking, along with a new employee parking lot to the southeast of the intersection (as identified in the previous Airport Master Plan). As detailed within **Chapter 3**, even with the loss of the existing long-term parking lot, passenger parking is adequate throughout the forecast period with the development and construction of Garage D. As previously described, with the new Passenger Facility Terminal options presented in **Section 5.4**, additional parking locations become available in proximity to the Terminal front, resulting in additional parking for temporary or emergency purposes in the event construction phasing impacts existing parking capacity; however, should the Airport require additional parking, these two areas are potential locations for a future surface parking lot and are illustrated within **Figure 5-18**. **Table 5-16** summarizes all Landside Commercial Development Options.

***Landside Commercial Development***

With the potential closure of Runway 14/32 and realignment of Robin Hood Road, considerable land for redevelopment would become available. Several opportunities are presented throughout these alternatives for various options on the land use of these available properties. This alternative presents potential non-aeronautical opportunities within this area.


***Commercial Retail/Cell Phone Lot/Gas Station***

One option is to develop a commercial retail station along the eastern corner of the new Robin Hood Road and Norview Road intersection. This commercial center has the potential to house a consolidated gas station, thus providing a partnership opportunity with terminal concessionaires for an external food court option along with a potential location for a more robust cell phone/passenger wait lot. This concept is a growing trend amongst heavily trafficked airports and provides a potential opportunity for increased revenue generation.

**Table 5-16 – Landside Commercial Development Options**

| General Layout | |
|---|---|
| Includes commercial retail/concessions, cell phone lot, and gas station | |
| **Opportunities** | **Constraints** |
| ✈ Revenue generation<br>✈ Passenger convenience<br>✈ Consolidation of new gas station, cell phone lot, "courtyard"<br>✈ Provides opportunities for new partnership with concessionaires<br>✈ Potential overflow or emergency parking | ✈ Utilizes area with potential for airside connectivity<br>✈ Potential parking for employees and/or temporary staging lots are pushed further from the Terminal<br>✈ Requires realignment of Robin Hood Road and Norview Avenue/Airport Road |

Source: CHA, 2019.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Future Building
- Future Landside Pavement

**Figure 5-18**
Landside Commercial Development Options

File: V:\PROJECTS\ANY\K41\33370\CADD\FIGURES\ALTERNATIVES\OTHER ALTERNATIVES\COMMERCIAL DEVELOPMENT_NEW.DWG Saved: 10/15/2019 2:58:03 PM Plotted: 10/17/2019 3:01:16 PM Current User: Harris, Jackson LastSavedBy: 5451

## 5.6 SUPPORT FACILITIES DEVELOPMENT CONCEPTS

### 5.6.1 Rental Car Concessions Alternatives

The Facility Requirements analysis in **Chapter 4**, **Section 4.6**, identified sufficient short- and long-term vehicle parking spaces for ORF throughout the planning horizon; however, the analysis further identified a growing deficit of rental car spaces during peak periods, including a need for approximately 450 additional spaces by PAL 4. This additional capacity can be accommodated in various ways including physical capacity increases, consolidation of rental car operations, and relocating off-site rental car activities nearer to the Airport's terminal itself.

As discussed in **Chapter 2** and **Chapter 4**, rental car companies currently have off-site Quick Turnaround (QTA) facilities along Military Highway, resulting in unnecessary rental car throughput (i.e., rental car companies moving overflow and vehicles requiring maintenance) along the terminal curbsides, Norview Ave., and Airport/Robin Hood Road, and expenditures for rental car companies maintaining off-site facilities. As such, there has been a need identified to decrease rental car traffic or separate rental car activity from passenger/pedestrian activity along the Airport's roads and consolidate rental car functions in proximity to the Airport terminal; therefore, concepts have been developed that provide additional rental car space to accommodate growing demand through consolidated QTA facilities or through the development of a Consolidated Rental Car Facility (CONRAC).

It is important to note, that although these alternatives show potential structures to accommodate rental car activity, for planning purposes the overarching goal is the preservation of land to accommodate these activities. As demand changes, the physical structures necessary to accommodate the activity will change; therefore, three potential layouts were developed for a QTA and two potential layouts for a CONRAC facility. All QTA Alternatives are depicted in **Figure 5-19** and all CONRAC alternatives are presented in **Figure 5-20**. **Table 5-17** summarizes both the QTA and CONRAC alternatives.

***QTA Alternatives***

Alternative 1 - Consolidated QTA

QTA Alternative 1 shows a new rental car QTA facility along the western portion of the airfield nearby the existing Runway 14 end. The construction of a consolidated QTA area/facility provides easy access to all rental car operations for both passengers and rental car employees and reduces the need for vehicle transport to/from airport property. In this concept, Robin Hood Road is realigned (but is not necessary), providing increased connectivity to Military Highway. While this location preserves the area adjacent to the existing long-term and (Transportation Network Company) TNC parking lots (e.g., *Uber*, *Lyft*, etc.), the location of the QTA facility is dependent upon closure of Runway 14/32.

Alternative 2 - Consolidated QTA

Similar to Alternative 1, QTA Alternative 2 shows a new QTA facility at the existing Runway 14 end. The location shown in Alternative 2 allows for development of a new QTA facility without the need for immediate realignment Robin Hood Road. This concept does require some degree of reconstruction of the existing Airport Road and access to/from Robin Hood Road; however, this location limits full aeronautical or non-aeronautical (i.e., parking, retail commercial, etc.)

development potential of the area, as this location east of the Robin Hood Road realignment has access to the airfield.

Alternative 3A – Consolidated QTA

QTA Alternative 3 depicts the repurposing of the existing employee parking lot for a new consolidated QTA facility capable of supporting rental car vehicle parking/storage needs, as well housing for maintenance services. This concept requires a longer shuttle of rental cars to/from the Airport along Robin Hood Road but limits the potential throughput of rental vehicles along the arrivals or departures curbsides and eliminates the use of Norview Avenue as a potential rental car route.

Alternative 3B - Dedicated QTA

QTA Alternative 3 shows the repurposing of the existing employee parking lot into a dedicated QTA facility. For the purposes of the physical make-up of this location, a consolidated single-structure QTA is not feasible; however, this concept allows for a more cost-effective solution by providing a dedicated area for rental car operations without the need for construction of a parking garage. Like Alternative 3A, this concept requires a longer shuttle of rental cars to/from the Airport along Robin Hood Road while limiting the potential throughput of rental vehicles along the arrivals or departures curbsides and eliminating the use of Norview Avenue as a potential rental car route.

***CONRAC Alternatives***

A need for consolidated rental car facilities has been identified. This need can be met by consolidating the QTA facilities located along Military Highway into a permanent structure, which could possibly be located on the Airport. Typically, a CONRAC provides a full service on-stop location for all rental car activities, including ready return, QTA, overflow storage, and rental pick-up (including rental car counters). Such a facility is most commonly attached to the terminal in some fashion, providing access for arriving passengers.

CONRAC facility sizing varies from airport to airport based upon demand for rental car services, the presence of a GTC, etc.; however, several design considerations exist and, thus, the facility should be sized accordingly to accommodate the existing and future needs of the rental car companies. When developing a CONRAC facility, it is important to account for safety of the employees and the general public, convenience to the rental car agencies and customers, efficient operational capabilities, operational sustainability, and cost efficiency. For the purposes of this Study, two locations for a CONRAC were identified, and the facility sizing of each location were independent of each other.

Alternative 1 – Consolidated CONRAC and QTA

This alternative proposes the construction of a CONRAC and QTA facility west of Airport Road, nearby the taxi queue area. This facility would consolidate all rental car functions and operations, with a pedestrian access bridge that would be constructed across Airport Road to connect the CONRAC facility with the existing Arrivals building. Access into and out of the CONRAC facility would be via Robin Hood Road and Airport Road, thus, preventing interference and congestion of the Terminal Loop. Based on industry standard facility sizing, it is expected that this CONRAC would accommodate all rental car vehicles and operations across five levels, sufficiently accommodating all current and future demand at the Airport; however, it is important to note

that facility sizing may change prior to any future planning. Thus, the purpose of this alternative is for the preservation of space sufficient to accommodate such a facility.

This site for the CONRAC has the potential to accommodate the CONRAC itself, additional parking along Robin Hood Road, and space for a potential commercial/retail development at the corner of Robin Hood Road and Norview Ave., as well as potentially housing a gas station/convenience store and food options with a cell phone lot for passengers, visitors and the general public.

Alternative 2 – CONRAC Only


This alternative suggests a replacement of Garages B and C to support a CONRAC facility. For the purposes of the sizing of this facility, the current spacing of Garages B and C provide more than adequate width required for a potential CONRAC, thus decreasing the requirement to accommodate additional floors for rental purposes. As such, an opportunity within this alternative suggests the potential for additional floors within this CONRAC facility for passenger parking, which continues to provide adequate capacity for public parking on the Airport. The lower floors would be dedicated to QTA, rental car ready and return parking; preventing interference with existing public parking within the garages. Customers would be able to access the facility via ingress and egress points currently in place. Although this option would provide the necessary space for CONRAC activity, QTA operations within the lower level of this space would be difficult. In addition, rental car vehicular access would impede the Airport's Terminal Loop, potentially resulting in congestion during peak periods.

The positioning of the facility would also allow space for future commercial development, such as those shown in **Figure 5-18**.

**Table 5-17 – Rental Car Alternatives (QTA and/or CONRAC)**

| Alternative | Opportunities | Constraints |
|---|---|---|
| QTA Development | ✈ Runway 14/32 end provides sufficient space for either consolidated or dedicated QTA facility | ✈ QTA development near existing Runway 14 end dependent upon runway closure and realignment of Robin Hood Road |
| | ✈ Existing employee lot provides immediate space for consolidation or dedicated QTA facility | ✈ Building within existing long-term lot limits development of future terminal facilities within the existing area |
| Consolidated CONRAC and QTA | ✈ Prevent interference and congestion of the Terminal Loop | ✈ Require relocation of the existing taxi queuing area |
| | ✈ Ingress/Egress points in place (Airport Road) | ✈ Maintenance cost for pedestrian access bridge |
| CONRAC (Not QTA) | ✈ Does not require building an entirely new facility | ✈ No space for QTA activity, thus requiring a QTA elsewhere |
| | ✈ Avoids interference with existing public parking | ✈ Rental car traffic will still impede the Airport's Terminal Loop |
| | ✈ Ingress/Egress points in place (to the terminal facilities and by roadway) | - |

Source: CHA, 2019.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)

0 250 500

**LEGEND**

- Future Landside Pavement
- Future Building

**Figure 5-19**
QTA Alternatives




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 100 200

## LEGEND

- Future Building
- Future Landside Pavement

**Figure 5-20**

CONRAC Alternatives

File: V:\PROJECTS\ANYX4\333370\CADD\FIGURES\ALTERNATIVES\OTHER ALTERNATIVES\CONRAC.DWG Saved: 10/15/2019 3:00:33 PM Plotted: 10/15/2019 3:03:25 PM Current User: Harris, Jackson LastSavedBy: 5451

### 5.6.2 Air Cargo Facilities Alternatives

As described in **Chapter 4**, **Section 4.5.2**, air cargo facilities at ORF are currently undersized to adequately accommodate the existing level of cargo activity, both by physical footprint and functionality, as leaseholds and processors are separated for each cargo operator. Based on the facility requirements calculations, cargo operations currently exceed maximum capacity by approximately 10 percent during peak periods. The dedicated air cargo apron is currently sufficient in size and capable of supporting up to four widebody aircraft and one single-engine turboprop aircraft with angled parking; however, by PAL 1, it is forecasted that there will be a need for one additional cargo aircraft parking position, with a deficit of approximately 3,450 square yards (SY). This deficit may grow to over 19,000 SY by PAL 4. Furthermore, the existing 88,000 square feet (SF) of cargo processing building space does not meet the current need of approximately 97,000 SF, with demand forecasted to grow to over 143,800 SF by PAL 4.

During the development of the alternatives, future transition of cargo fleet mixes was incorporated as air cargo operators transition to new and converted B767-300 aircraft with decreased operations of A300 and B757 airframes. Based on these observations and the projected growth of cargo operations over the forecast period, three conceptual air cargo facility alternatives were identified for evaluation.

***North Cargo/MRO Area Alternative 1***

The North Cargo/MRO Area Alternative 1 (**Figure 5-21**) shows an approximate 56,000 SF cargo facility northeast of the current facilities, improving the physical footprint of cargo infrastructure and allowing consolidation of processors. This alternative further depicts area dedicated to loading and unloading activity on the landside of the newly proposed facility, as well as parking for ground-cargo vehicles and cargo operator employee parking.

This concept would shift Taxiway 'V' approximately 114 feet northeast, providing additional space for aircraft parking and improved functionality. By shifting the taxiway, cargo operators would have the ability to park widebody aircraft perpendicular to the present facilities rather than the current angled configuration. In addition to parking reorientation, the apron would sufficiently accommodate up to five B767-300 aircraft and two Cessna 208 Caravans.

Additional apron space will be required to accommodate the shifted taxiway, as well as for aircraft parking at the additional processing facility. Apron parking at the depicted cargo facility would accommodate two to three B767-300 aircraft. In addition to cargo activity, MRO activity can also be supported within the development area, with space for two MRO facilities (approximately 85,000 SF each). In total, approximately 74,030 SY of airfield pavement is recommended to support the shifted taxiway, as well as to support parking for up to three ADG IV aircraft deicing positions to be utilized by cargo and commercial operators (see **Section 5.6.5**). The additional pavement and infrastructure repurposes the pavement currently serving as Runway 14/32, lowering developmental costs. This alternative is cost-effective due to the reuse of existing pavement and retention of existing cargo buildings and apron, rather than razing and replacing current facilities. **Table 5-18** summarizes the North Cargo/MRO Area Alternative 1.

**Table 5-18 – North Cargo/MRO Area Alternative 1 Summary**

| General Layout | |
|---|---|
| Incremental Expansion of existing Air Cargo facilities. | |
| **Opportunities** | **Constraints** |
| ✈ Accommodates relocation of Robin Hood Road.<br>✈ Provide locations for additional infrastructure needed throughout the planning period<br>✈ Maintains existing air cargo facilities<br>✈ Repurposes Runway 14/32 for apron/taxiway<br>✈ Includes locations for MRO facilities<br>✈ Does not infringe upon long-term surface parking lot<br>✈ Lowest cost of the air cargo concepts | ✈ Requires closure of Runway 14/32<br>✈ Layout is limited to a single taxilane, resulting in potential for some apron congestion/delay |

Source: CHA,2019.

***North Cargo/MRO Area Alternative 2***

North Cargo/MRO Area Alternative 2 (**Figure 5-22**) shows razing of the existing cargo buildings for improved functionality and best-use of the developable area. As such, two new cargo facilities are incorporated, providing a minimum of approximately 56,000 SF of total space. The largest of the two facilities (located northeast of the current building) would serve as a dedicated cargo sort facility, with vehicular parking to the north (landside) and an aircraft parking apron to the south (airside). The aircraft parking apron would utilize the pavement and infrastructure currently used for cargo related vehicular parking, aiding in cost efficiency. The new apron would measure approximately 100,000 SY and could support up to 10 cargo aircraft, allowing cargo operators more options and flexibility when processing freight. The smaller facility shown would also have dedicated apron space capable of supporting up to two B767-300s. To allow for the development of the new cargo buildings and apron space, it is necessary to shift Taxiway 'V' approximately 400 feet to the west, converting the pavement currently used for a runway (Runway 14/32) to use as a taxiway, thus lowering costs.

Similar to the first development concept, this alternative also provides the option for the development of two MROs to the east of the shifted taxiway, enabling increased utilization of the available developable area. **Table 5-19** summarizes the North Cargo/MRO Area Alternative 2.

**Table 5-19 – North Cargo/MRO Area Alternative 2 Summary**

| General Layout | |
|---|---|
| Redevelopment of existing Air Cargo facilities | |
| **Opportunities** | **Constraints** |
| ✈ Accommodates relocation of Robin Hood Road.<br>✈ Provide locations for additional infrastructure beyond that needed during the Planning Period<br>✈ Repurposes Runway 14/32 for future Taxiway<br>✈ Includes locations for MRO facilities<br>✈ Includes separate taxiway access to each component to improve efficiency | ✈ Requires closure of Runway 14/32<br>✈ Requires replacement of existing air cargo buildings<br>✈ Highest cost of the alternative concepts |

Source: CHA, 2019.

***North Cargo/MRO Area Alternative 3***

Similar to Alternative 2, North Cargo/MRO Area Alternative 3 (**Figure 5-23**) depicts razing the current cargo facilities and constructing two new facilities to satisfy long-term requirements, with one facility being dedicated to cargo sort activities. A new aircraft parking apron for the sort facility would be necessary, measuring approximately 100,000 SY and capable of supporting up to 10 B767-300 aircraft. The apron would repurpose existing pavement to decrease developmental costs. The smaller cargo facility's apron would also repurpose pavement from Runway 14/32 and would provide parking for up to three B767-300 aircraft. Landside parking and areas for loading and unloading activities would be provided to the west of each newly constructed cargo facility, again repurposing some existing pavement. Roadway access from the proposed Robin Hood Road realignment would serve these new facilities.

In addition, Alternative 3 provides the option of building two new MRO facilities on the southwest side of the developable area, along with a single apron for joint-use operations with the MRO facility operators. An access road is shown to allow for entry from the proposed cargo drive to the proposed Robin Hood Road realignment. The locations of the recommended roadways will maintain the separation of cargo and MRO activities from FAA equipment and non-airport related businesses (i.e., the existing catering company) adjacent to the developable area. The location of the roadways also allows for the repurposing of existing infrastructure (i.e., cargo-related vehicle parking and loading/loading space) used by cargo operators. **Table 5-20** summarizes the North Cargo/MRO Area Alternative 3.

**Table 5-20 – North Cargo/MRO Area Alternative 3 Summary**

| General Layout | |
|---|---|
| Major Buildout Air Cargo facilities | |
| **Advantages** | **Disadvantages** |
| ✈ Accommodates relocation of Robin Hood Road.<br>✈ Provide locations for additional infrastructure needed throughout the Planning Period<br>✈ Repurposes Runway 14/32 for future Taxiway<br>✈ Includes locations for MRO facilities<br>✈ Does not infringe upon long-term surface parking lot | ✈ Requires closure of Runway 14/32<br>✈ Requires replacement of existing air cargo buildings<br>✈ Occupies space of the existing long-term lot the potential future terminal facilities |

Source: CHA, 2019.

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

Future Non-Aeronautical Development

Loading / Unloading

Air Cargo Facility

Deicing Apron

Fuel Facility

GRAPHIC SCALE (FEET)

0 200 400


## LEGEND

- Future Airfield Pavement
- Future Landside Pavement
- Future Building
- Pavement Removal

**Figure 5-21**
North Cargo Area -
Alternative 1

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE




GRAPHIC SCALE (FEET)

0 150 300

## LEGEND

- Future Airfield Pavement
- Future Landside Pavement
- Future Building
- Pavement Removal

**Figure 5-22**
North Cargo Area - Alternative 2

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

Future Non-Aeronautical Development Area

Future Non-Aeronautical Development / Cell-Phone Waiting Lot

Additional Cargo Facilities

Loading / Unloading

Cargo Sort Facility

MRO Facilities

GRAPHIC SCALE (FEET)

0 150 300

## LEGEND

- Future Airfield Pavement
- Future Landside Pavement
- Future Building
- Pavement Removal

**Figure 5-23**
North Cargo Area - Alternative 3

### 5.6.3 General Aviation Facilities Alternatives

General Aviation (GA) activity at ORF represents approximately 31 percent of total annual airport operations and includes various types of private, corporate, and business aircraft flights. GA services and facilities are accommodated by Signature Flight Support, which is located along the southern portion of the airport and currently the Airport's only Fixed Based Operator (FBO).

The following discusses the existing GA infrastructure as well as potential concepts to accommodate forecasted demand and future buildout, as identified in **Sections 4.3.4** and **4.5.1**. Note that each concept was developed with the presumed closure of Runway 14/32, although certain portions of each could occur prior.

***General Aviation Alternative 1***

General Aviation Area Alternative 1 (**Figure 5-24**) depicts an option to accommodate forecasted apron and hangar demand while requiring minimal construction of additional infrastructure to support future development. This concept depicts a northeasterly expansion of the current GA apron by approximately 29,000 SY. The southern portion of the expansion would support a TDG 2 taxilane to provide access as well as ingress/egress for additional expansion. Although more space than currently forecasted is depicted, the expansion accommodates apron parking for 12 ADG II aircraft and allows for phased development.

Southeast of the GA apron expansion, General Aviation Area Alternative 1 depicts two bulk hangars (150' x 200'), each providing 30,000 SF of aircraft storage. Similar to the GA apron expansion, this concept allows for phased development northeast of the FBO building (Building 20) and along the existing TDG 2 taxilane. Since the development would occur outside of the airside secure limits, vehicle parking/access and associated security measures would likely be required.

This concept also depicts several portions of existing taxiway to be either removed or repurposed. As such, a new taxiway providing TDG 3 access to the Ground Runup Enclosure (GRE) is shown. This taxiway would also provide access to potential corporate hangar development located northwest of the FAA Aircraft Traffic Control facility. Lastly, this concept depicts several areas capable of accommodating future aeronautical and/or non-aeronautical development. As stated, this concept requires closure of Runway 14/32, but other existing facilities (i.e., the GRE, ATCT, fuel farm, ASR, etc.) are all retained. **Table 5-21** summarizes the General Aviation Alternative 1.

**Table 5-21 – General Aviation Alternative 1 Summary**

| General Layout | |
|---|---|
| Northeasterly expansion of the current GA facilities serviced by existing FBO | |
| **Opportunities** | **Constraints** |
| ✈ Minimal additional infrastructure required to accommodate development<br>✈ Sufficient apron parking and aircraft storage space for short-term demand<br>✈ Accommodates phased development to accommodate all long-term requirements<br>✈ Retains existing airport support facilities and access road | ✈ Requires closure of Runway 14/32<br>✈ Northeasterly apron expansion may be limited by construction of TDG 3 taxiway to GRE |

Source: CHA, 2019.

### *General Aviation Alternative 2*

Similar to Alternative 1, General Aviation Alternative 2 (**Figure 5-25**) depicts an option to accommodate forecasted hangar and apron space with the option for future expansion. Alternative 2, however, assumes the addition of a second FBO servicing additional apron space and aircraft storage located along the proposed Runway 5R/23L eastern corridor.

The GA apron expansion depicted (approximately 36,400 SY) accommodates parking for 16 ADG II aircraft, and a TDG 2 taxilane is shown along the eastern portion of the apron expansion for increased connectivity. Additionally, two bulk hangars (200' x 100') are shown providing a total of 40,000 SF of aircraft storage.

Differing from the first alternative, Alternative 2 depicts a potential second FBO nearby the existing fuel farm, which would be relocated in this concept. As part of this concept, an itinerant apron expansion is shown southeast of the proposed Runway 5R/23L. Although Alterative 2 depicts various bulk hangar sizes, this area provides sufficient space for a variety of hangars and types depending upon demand. This concept also shows preservation of the GRE along with taxiway/runway access. Additionally, the proposed corporate hangar development northeast of the FAA Air Traffic Control facility would likely require access to the apron expansion. Similar to Alternative 1, several areas capable of accommodating future aeronautical and/or non-aeronautical development are shown. Lastly, this concept assumes the redevelopment of Taxiway 'F'. **Table 5-22** summarizes the General Aviation Alternative 2.

**Table 5-22 – General Aviation Alternative 2 Summary**

| General Layout | |
|---|---|
| Addition of a second Fixed Base Operator (FBO) servicing additional apron space and aircraft storage located along the proposed Runway 5R/23L eastern corridor | |
| **Opportunities** | **Constraints** |
| ✈ Sufficient apron parking and aircraft storage space for short-term demand<br>✈ Accommodates phased development to accommodate all long-term requirement<br>✈ Provides frontage and separation between FBOs<br>✈ Maintains uninterrupted GA layout across proposed Runway 5R/23L eastern corridor<br>✈ Retains existing airport support facilities and access road | ✈ Requires closure of Runway 14/32<br>✈ Additional infrastructure required (replaced Taxiway 'F')<br>✈ Ultimate buildout dependent upon establishment of second FBO<br>✈ Additional vehicle access to eastern corridor required |

Source: CHA, 2019.

### *Additional Measures for Consideration*

Three T-hangar buildings are currently located in the general aviation area at ORF. The buildings are adequate in terms of function; however, spacing between the T-hangar buildings is limited, with some areas only providing approximately 25 feet for maneuverability. Future consideration may be given to the replacement of the existing T-hangars with box hangars, if demand requires; therefore, the need and demand for the T-hangars should be closely monitored for demand throughout the planning horizon.

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 400 800

## LEGEND

- Future Airfield Pavement
- Future Landside Pavement
- Future Building
- Pavement Removal

*FBO Facility*

*Future Aeronautical Development*

*Recommended Land Acquisition*

*Land Use Compatible Development*

*Potential Corporate Hangar Development*

*T-Hangar Realignment & Removal*

*Future Aeronautical Development*

*GA FIS Facility*

**Figure 5-24**
General Aviation Area
Alternative 1

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 200 400


## LEGEND

- Future Airfield Pavement
- Future Landside Pavement
- Future Building
- Pavement Removal

**Figure 5-25**
General Aviation Area
Alternative 2

### 5.6.4 Aviation Fueling Facilities Alternatives

The existing Jet-A fuel farm is located north of the Air Traffic Control Tower and includes four aboveground Jet-A fuel tanks with storage capacities of 210,000-gallons per tank. From the fuel farm, fuel is pumped via underground pipeline to a dispensing location north of the ARFF facility where it is transferred to fuel trucks for dispensing to aircraft.



Source: Google Earth.

The Airport maintains the Jet-A fuel farm, dispensing facility, and underground fuel piping system. The functionality of the existing facility was evaluated in **Chapter 4**, **Section 4.5.4**. Due to the age and condition of the fueling system, it is near the end of its useful life and the Airport is experiencing increasing operations and maintenance costs for upkeep of the system; therefore, in an effort to consolidate the fueling system, **Figure 5-26** depicts two potential locations for a new consolidated Jet-A fuel farm.

Both alternatives assume that the Jet-A fuel storage and upload will be located within a consolidated area, thus eliminating the need for an underground pipeline. With each location, environmental permitting would be required, as well as the decommissioning and demolition of the existing system.

Alterative 1 depicts a location within the existing rental car overflow parking lot. This location allows for quick access of fuel deliveries along with airside connectivity to commercial and cargo aircraft; however, relocation of the rental car overflow parking lot may be required.

Alternative 2 shows expansion of the existing fuel dispensing facility to also include Jet-A storage. This location reuses a portion of the fueling system currently in place and minimizes impacts to existing infrastructure. Access for fuel tanker trucks may be difficult and is shared with the terminal access road. The overall size of this site is limited.

With the potential relocation of Robin Hood road, additional locations are possible that provide both landside and airside access.

NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 250 500




**Figure 5-26**
Fuel / Glycol Storage Facility Alternatives

### 5.6.5 Aircraft Deicing Facilities Alternatives

Commercial Aircraft deicing operations at ORF are confined to the main terminal apron, and the cargo apron on the west side of the airfield. The Airport's main deicing facility/pad is located on the northeast side of the main terminal apron and consists of four ADG IV deicing positions, which are utilized on a first-come-first-serve basis.




Source: Google Earth.

Deicing facilities were previously evaluated in **Section 4.5.5**. As discussed, NAA has a long-term goal of developing a centralized deicing area, complete with a built-in runoff collection system. **Figure 5-27** depicts two deicing alternative locations.

The remote terminal deicing apron location shows an area for three ADG IV deicing positions along the northwestern edge of Taxiway C and on a portion of the current Runway 14/32, which is presumed closed for this alternative. As this location is not a part of the Passenger Terminal apron, a deicing fluid (i.e., glycol) drainage system would be required, however, deicing would be served by mobile trucks and deicing equipment, as impacts to terminal area operations may hinder the likelihood any permanent deicing equipment. This location is respective of Cargo Alternative 1 (**Figure 5-21**), which currently depicts cargo facility development within the area, and would provide a consolidated commercial/cargo deicing location. Based on ingress and egress requirements for the taxilanes associated with the terminal gates, the overall length of the deicing bays is more than adequate for single use and may be simultaneously occupied with two aircraft. The over space is a dual use with RON capability at night with positions for up to six RON aircraft.

The Terminal Alterative 4 deicing apron location shows an area southwest of the existing deicing pad. This alternative depicts three ADG IV aircraft deicing positions and is respective of Passenger Terminal Alternative 4 (**Figure 5-16** and **Figure 5-17**). This location allows for utilization of existing apron space and aircraft ingress/egress nearby the terminal gates. Similar to the remote deicing facility, lane length is more than adequate for single aircraft use and may be utilized by up to two aircraft per lane at a time for simultaneous use, therefore increasing the overall deicing capacity at the Airport. Additionally, during non-deicing periods the area can accommodate up to six remain overnight (RON) aircraft.




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 150 300

**Figure 5-27**

Deicing Apron Alternatives

### 5.6.6 Airfield Maintenance Facilities Alternatives

The NAA airfield maintenance facilities are currently located on the southeast end of the airfield and consist of a 40,000 SF facility that houses the snow removal equipment and a 6,000 SF facility for sand storage and airport maintenance and utility vehicles. According to the NAA, and as discussed in **Section 4.5.7**, these buildings are at capacity and do not account for the most recent FAA guidance within FAA AC 150/5220/18A, *Buildings for Storage and maintenance of Airport Snow and Ice Control Equipment and Materials*; therefore, **Figure 5-28** depicts several alternate locations for additional airfield maintenance facilities. Note that with each location, the potential exists for either complete facility relocation or establishment of a secondary airfield maintenance site, depending on need or location.

***Airfield Maintenance Alterative 1***

Alternative 1 shows an expanded maintenance facility directly northwest of the existing. This location provides consolidation of all airport maintenance resources within a dedicated area. A disadvantage to this concept is the impact to the existing ARFF training area, which is shown relocated southward.

***Airfield Maintenance Alterative 2***

Alternative 2 shows an expanded area southeast of the GA apron. This location provides quick access to both the airfield and Miller Store Road with the ability for expansion; however, this area is dependent upon closure of Runway 14/32 and is ideal space for future aeronautical and/or aeronautical-related development. Proximity to the FBO terminal building could be considered an aesthetic disadvantage.

***Airfield Maintenance Alterative 3***

Alternative 3 is also dependent upon closure of Runway 14/32. Although less of an impact to future aeronautical and/or aeronautical-related development, this location may also be dependent upon potential relocation of the GRE facility.


***Airfield Maintenance Alterative 4***

Alternative 4 takes advantage of the undeveloped wooded area to the north of the existing fuel farm. This area provides connectivity to the airfield and Miller Store Road but would require land acquisition and site clearing prior to development. **Table 5-23** summarizes the Airfield Maintenance Alternatives.

**Table 5-23 – Airfield Maintenance Alternatives**

| Opportunities | Constraints |
|---|---|
| ✈ Existing facility can be retained, allowing for smaller addition(s) to supplement space needs<br>✈ Sufficient locations throughout airfield allow for total relocation or for a secondary airfield maintenance site | ✈ Partial or total relocation within existing Runway 32 approach area limits potential aeronautical and/or aeronautical-related development<br>✈ Proximity to the FBO terminal building could be considered an aesthetic disadvantage |

Source: CHA, 2019.




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 250 500

**LEGEND**

- Future Airfield Pavement
- Future Building

**Figure 5-28**

Airfield Maintenance Alternatives

## 5.7 RECOMMENDED DEVELOPMENT PLAN SUMMARY

Based on the review of the Airport's goals and objectives, as well as the needs and constraints identified in this Chapter and in previous Chapters, specific alternatives were identified as the most reasonable to form the recommended development plan for ORF. This plan improves the safety, operational efficiency, and functionality of the airfield while incorporating all necessary facilities. This section provides a summary of the major concepts in support of the short- and long-term operation of the Airport.

As mentioned previously, there are a substantial number of areas on the Airport that were evaluated and have recommended improvement concepts. It should be emphasized that this is a long-term plan and that some desired improvements may not be financially or environmentally feasible. Prior to implementation of some of the proposed development projects, an Environmental Assessment (EA) or Environmental Impact Statement (EIS) would be required in accordance with regulations covered under the National Environmental Policy Act (NEPA).

A summary of the advantages and disadvantages of each recommended alternative or concept is presented in **Table 5-24**, while the recommended plan for ORF is illustrated in **Figure 5-29**.

### 5.7.1 Airside Development

***Runway 14/32 Closure***

Based on the evaluations of airfield development concepts and the limited use of Runway 14/32, it is recommended that the runway be decommissioned in PAL 1. It was determined that the highest and best use of the land that the runway occupies is redevelopment for industrial and corporate/GA activity to accommodate existing and future demand in terms of cargo and GA activity.

***Runway 5/23 Standardization***

It is recommended that Runway 5/23 be brought up to FAA standards as set forth in AC 150/5300-13A, *Airport Design*, in PAL 1 and PAL 2. This includes building out the runway's shoulders and blast pads, relocating obstructions within the ROFA and ROFZ, and grading the RSAs. It is further recommended that the land within the RPZs for Runway 5 and Runway 23 be acquired to maintain operational safety of the airport and to ensure compatibility.

***Taxiway 'C' Partial Realignment***

In PAL 1, the recommended partial realignment of Taxiway 'C' addresses the variable separation distance between the taxiway and Runway 5/23. Taxiway 'C' is currently designated as TDG 5, requiring a minimum taxiway to runway centerline distance of 400 feet; however, the current separation of Taxiway 'C' ranges from 400 feet at the Runway 5 end to over 600 feet at the Runway 23 end. While this distance provides an added separation margin, it also reduces the available non-movement space near the southeasternmost gates of Terminal Concourse B, requiring aircraft push-back into the Taxiway 'C' environment; therefore, this concept recommends a parallel Taxiway 'C' offset of 400 feet from the Runway 5 end to Taxiway 'H'.

***West Airfield Taxiway Improvements***

Taxiway Alternative 1 illustrates the conversion of the Runway 14/32 pavement (from Runway 5/23 northeastward) into a new TDG 3 taxiway (relocated Taxiway 'D') during PAL 1. This

conversion of pavement allows for continued ingress/egress to the cargo area and for potential aeronautical development along the taxiway. If necessary, the taxiway can be shortened to accommodate the realignment of Robin Hood Road and the expansion of the cargo facility.

Lastly, this concept recommends the removal and update of taxiways that would be either no longer required or are non-standard. Specifically, this concept shows a realignment of Taxiway 'F' to meet current FAA taxiway design geometry. As a result of this realignment, this concept also shows a relocation of Taxiway 'E' to provide improved access. Although this concept shows the removal of Taxiway 'G', a pavement corridor is reserved for an Aircraft Rescue and Fire Fighting (ARFF) access road between the existing firefighting station and the southern portion of the airfield.

***Parallel Runway 5R/23L***

Beyond the 20-year planning horizon, a parallel ARC C-II runway (measuring 5,500 feet long and 100 feet wide) is recommended 876 feet south of the existing runway (Runway 5/23), while providing a 300-foot runway-taxiway separation. The existing runway would receive a new designation of Runway 5L/23R and the new parallel runway would be designated as Runway 5R/23L. To eliminate the requirement for an RSA beyond the "stop-end" of the runway (with only a 600-foot long RSA on the approach end) and to lesson environmental impacts, an EMAS would be installed at each runway end. The Authority's preferred alternative includes mitigation measures that would need to be reviewed and approved by the FAA during a future environmental and design effort for Runway 5R/23L. Furthermore, a 600-foot runway displacement avoids building and object obstructions.

The ultimate goal is to extend Runway 5R/23L an additional 3,501 feet and widen by an additional 50 feet, thus providing an ultimate length and width of 9,001 feet and 150 feet, respectively. The extension would eliminate the need of EMAS beds. The ultimate build-out of the parallel runway would accommodate most aircraft operations at ORF, while also segregating general aviation from commercial activity.

### 5.7.2 Passenger Terminal Facility Development

Passenger Terminal Facility Alternative 1 addresses pre-security configuration issues of the current terminal complex. In particular, the split ticketing halls are combined and relocated to the west side of the departure building, facing the arrival building during PAL 4. This enables reconfiguration of the terminal roadways with an efficient parallel alignment with the arrivals building's curbside. The new departure curbside will provide greater overall length, with adjacent short-term parking serving both arrivals and departures.

Relocation of the ticketing halls enable redevelopment of the lower level of the departure building for expansion of the outbound baggage make-up facilities to serve all three concourses. TSA security would be consolidated into a single checkpoint that is located on the eastern half of the atrium area. As is the case with the Status Quo Alternative, the previous Airport Master Plan developed an incremental terminal recommendation that retained the existing building layout and internal configuration, and included gates, and associated facilities through the addition of a third concourse (Concourse C). This layout utilizes the area of the long-term surface parking lot for the location of the additional concourse, with expansion of Terminal Concourse A. This alternative is a simple and low-cost expansion option that maximizes use of existing facilities;

however, several shortcomings are apparent, including long walking distances and taxilane/push-back conflicts between the concourses.

### 5.7.3 Landside Commercial Development or Airfield Maintenance Facilities Relocation

The land made available through the closure of Runway 14/32 and the realignment of Robin Hood Road can be developed for either commercial use or for aeronautical use. If reserved for commercial purposes, recommended facilities and uses include commercial retail and concessions, a cell phone lot, and a gas station. If the land is opted for aeronautical uses, it is recommended that the current functions of airfield maintenance be relocated to this site.

### 5.7.4 Support Facilities Development

***Rental Car Facilities***

During PAL 2, it is recommended that the existing employee parking lot be repurposed for use as a consolidated QTA facility. The facility should provide enough space to support rental car parking and storage needs, as well as maintenance services, throughout the short- and medium-term.

In PAL 4, it is recommended that a CONRAC facility replace the lower level of Parking Garages B and C; however, the facility would still allow for passenger parking on levels not being used for rental car functions.

***North Cargo Facility***

Development of an additional cargo facility is recommended in PAL 2 to the northeast of the current cargo facilities, thus repurposing land made available through the future closure of Runway 14/32. The new facility would improve the footprint of cargo infrastructure and would allow for consolidation of processors. It is further recommended that an area dedicated to loading and unloading of cargo be provided landside, as well as parking for ground-cargo vehicles and cargo operator employee parking. To accommodate the new facility and to provide adequate apron space, it is recommended that Taxiway 'V' be shifted approximately 114 feet to the northeast; however, repurposing the pavement currently serving as Runway 14/32 will be necessary to support the additional apron space required to accommodate the shifted taxiway.

***General Aviation Facilities Expansion***

In PAL 1, it is recommended that two 150 feet by 200 feet bulk hangars be constructed in the GA area, with each hangar providing 30,000 SF of aircraft storage. In PAL 2, the GA apron should be expanded approximately 29,000 SY to the northeast (while still retaining existing facilities such as the GRE, ATCT, fuel farm, ASR, etc.), with the southern portion of the expansion supporting a TDG-2 taxilane.

A new taxiway providing TDG 3 access to the GRE is also recommended, requiring the removal or repurposing of existing taxiways. The taxiway would also be capable of providing access to potential corporate hangar development located northwest of the FAA ATC facility.

***Aviation Fueling Facilities Relocation***

During PAL 1, it is recommended that the current fuel farm be decommissioned, followed by demolition, and that a consolidated Jet-A storage and upload facility be constructed in the existing rental car overflow parking lot.

***Remote Terminal Deicing Apron***

After determining the recommended plan for future cargo development, the deicing apron alternatives were re-evaluated and the remote terminal deicing apron alternative chosen to represent the recommended deicing apron alternative. This location is preferred opposed to the terminal deicing apron, as the location is compatible with all the previously evaluated terminal alternatives and does not impede future development within the terminal area. In addition, the remote terminal deicing apron will include a built-in runoff collection system, while also allowing for use and ease of access for both commercial and cargo operators.


During PAL 2, the remote terminal deicing apron would be developed east of the existing cargo area and directly south of the recommended cargo facility, assuming the closure of Runway 14/32 (as recommended in **Section 5.7.1**), and would be capable of supporting three ADG IV deicing positions. The overall length of the deicing bays should be adequate for single use during deicing activities but should be capable of accommodating up to two aircraft per position at night, thus supporting up to six RON aircraft.

**Table 5-24 – Recommended Development Plan**

| Recommended Alternative/Concept | Opportunities | Constraints |
|---|---|---|
| **Airfield Development** | | |
| **Runway 14/32 Closure** (Alternative 3) | ✈ Recaptures airport property to expand critical aviation facilities<br>✈ Avoids airspace conflicts with surrounding facilities | ✈ Reduces crosswind coverage for light General Aviation aircraft |
| **Parallel Runway 5R/23L (Initial Development)** (Alternative 12B) 5,500' x 100', ARC C-II EMAS at Both Ends Offset 876' 20:1 TSS, Visibility ≥ 1 Mile | ✈ Provides secondary runway for GA airport users<br>✈ Avoids impacts to VORTAC<br>✈ 876' separation enables simultaneous VFR operations<br>✈ No impacts to Lake Whitehurst<br>✈ No wetland impacts | ✈ Length restricts usage by commercial operations<br>✈ Potential Impact to Naval training activity |
| **Parallel Runway 5R/23L (Ultimate Development)** (Alternative 5) 9,001' x 150', ARC D-IV Offset 876' 34:1 TSS | ✈ Provides secondary runway for operational flexibility<br>✈ Proposed length accommodates all commercial activity<br>✈ Avoids impacts to VORTAC<br>✈ 876' separation enables simultaneous VFR operations | ✈ Impacts to Lake Whitehurst<br>✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and GA parking apron)<br>✈ Significant construction costs<br>✈ Approach/departure overfly Little Creek Naval Base |
| **Taxiway 'C' Partial Realignment** (Alternative 1) | ✈ Realignment of Taxiway C to 400' offset improves the separation from Concourse B<br>✈ Partial taxiway realignment avoids impact to Runway 23 Glideslope<br>✈ Conversion of Runway 14/32 to Taxiway expands area for air cargo apron<br>✈ Removes non-standard conditions (direct apron to runway access) | ✈ Taxiway C retains existing curves near Runway 23 end<br>✈ Does not provide full-length standard parallel taxiway |
| **Terminal Facility Development** | | |
| **Terminal Expansion** (Alternative 1) | ✈ Modest capital costs through retention of several existing facilities | ✈ Results in separation and potential duplication of all post-security facilities, services, and concessions |

| Recommended Alternative/Concept | Opportunities | Constraints |
|---|---|---|
| | ✈ Ease of construction phasing with minor impacts to passenger activity<br>✈ Provides adequate additional facilities for all terminal requirements, including outbound baggage<br>✈ Removes deficiencies in passenger circulation<br>✈ Combines split facilities for the ticketing hall and curbside drop-off (reduces passenger confusion)<br>✈ Eliminates overly complex roadway layout<br>✈ Eliminates the need for a third security checkpoint | ✈ Reduces flexibility for airline gate utilization and operations<br>✈ Retains existing long walking distances to baggage claim and parking garages |
| **Landside Commercial Development** | | |
| **Commercial Retail/Cell Phone Lot/Gas Station** | ✈ Revenue generation<br>✈ Passenger convenience<br>✈ Consolidation of new gas station, cell phone lot, "courtyard"<br>✈ Provides opportunities for new partnership with concessionaires<br>✈ Potential overflow or emergency parking | ✈ Utilizes area with potential for airside connectivity<br>✈ Potential parking for employees and/or temporary staging lots are pushed farther from the terminal<br>✈ Requires realignment of Robin Hood Road and Norview Avenue/Airport Road |
| **Support Facilities Development** | | |
| **Rental Car Consolidated QTA** (Alternative 3A) | ✈ Consolidates rental car vehicle parking/storage and maintenance services<br>✈ Limits potential throughput of rental vehicles along the arrivals and departures curbsides<br>✈ Eliminates use of Norview Avenue as a potential rental car route | ✈ Requires longer shuttle of rental cars to/from the Airport along Robin Hood Road |
| **Rental Car CONRAC Facility** (Alternative 2, but Excludes QTA) | ✈ Does not require building an entirely new facility<br>✈ Avoids interference with existing public parking<br>✈ Ingress/Egress points in place (to the terminal facilities and by roadway) | ✈ No space for QTA activity, thus requiring a QTA elsewhere<br>✈ Rental car traffic will still impede the Airport's Terminal Loop |
| **North Cargo Facility** (Alternative 1, but Excludes MRO) | ✈ Accommodates relocation of Robin Hood Road<br>✈ Provides locations for additional infrastructure needed throughout the planning period<br>✈ Maintains existing air cargo facilities<br>✈ Repurposes Runway 14/32 for apron/taxiway | ✈ Requires closure of Runway 14/32<br>✈ Layout is limited to single taxilane, resulting in potential for some apron congestion/delay |

| Recommended Alternative/Concept | Opportunities | Constraints |
|---|---|---|
| | ✈ Does not infringe upon long-term surface parking lot<br>✈ Lowest cost of the air cargo concepts | |
| **GA Facilities Expansion** (Alternative 1) | ✈ Minimal additional infrastructure required to accommodate development<br>✈ Sufficient apron parking and aircraft storage space for short-term demand<br>✈ Accommodates phased development to accommodate all long-term requirements<br>✈ Retains existing airport support facilities and access road<br>✈ | ✈ Requires closure of Runway 14/32<br>✈ Northeasterly apron expansion may be limited by construction of TDG 3 taxiway to GRE |
| **Aviation Fueling Facilities Relocation** (Alternative 1) | ✈ Jet-A storage and upload located in a consolidated location, thus eliminating the need for an unground pipe<br>✈ Allows for quick access of fuel deliveries<br>✈ Allows for airside connectivity to commercial and cargo aircraft | ✈ Requires environmental permitting<br>✈ Requires decommissioning and demolition of the existing fueling system<br>✈ May require relocation of the rental car overflow parking lot |
| **Remote Terminal Deicing Apron** (Alternative 1) | ✈ Consists of three ADG IV deicing positions<br>✈ Provides a consolidated commercial/cargo deicing location<br>✈ Deicing bays may be utilized as single use or may be simultaneously occupied with two aircraft<br>✈ Over space allows for dual use with RON capability at night (up to six RON aircraft) | ✈ Dependent on closure of Runway 14/32<br>✈ Requires installation of a deicing fluid (i.e., glycol) drainage system<br>✈ Deicing services must be via mobile trucks and mobile equipment, as impacts to terminal area operations hinder the likelihood of permanent deicing equipment |
| **Airfield Maintenance Facilities Relocation** | Further Consideration Needed | Further Consideration Needed |




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

## LEGEND

- PAL 1 Development/Demolition
- PAL 2 Development/Demolition
- PAL 3 Development/Demolition
- PAL 4 Development/Demolition
- Future Development/Demolition (Beyond Planning Period)
- Future Development Area
- Property Line

**Figure 5-29**
Recommended Plan

# 6 ENVIRONMENTAL OVERVIEW

This section provides a preliminary assessment of the environmental factors existing on and around the Norfolk International Airport (ORF). This review was conducted in accordance with the FAA Orders 5050.4B, *National Environmental Policy Act (NEPA) Implementing Instructions for Airport Actions* and 1050.1F, *Environmental Impacts: Policies and Procedures*. This review does not provide a complete investigation sufficient for obtaining environmental permits or compliance with environmental documentation as required by the National Environmental Policy Act (NEPA). A review of existing GIS data, coordination with relevant environmental regulatory agencies and a field walk-over were conducted to develop this overview of the environmental resources.

The purpose of this review was to identify the environmental resources that may affect future development at the Airport and to identify those environmental issues that may require additional environmental analysis prior to implementation of future projects. The environmental impact categories discussed in this overview are:

- Air Quality
- Biological Resources (Including Fish, Wildlife, and Plants)
- Climate
- Coastal Resources
- Department of Transportation Act, Section 4(f)
- Farmlands
- Hazardous Materials, Solid Waste, and Pollution Prevention
- Historical, Architectural, Archeological, and Cultural Resources
- Land Use
- Natural Resources and Energy Supply
- Socioeconomic, Environmental Justice, and Children's Environmental Health and Safety Risks
- Visual Effects (Including Light Emissions)
- Water Resources (Including Wetlands, Floodplains, Surface Waters, Groundwater, and Wild and Scenic Rivers)

## 6.1 AIR QUALITY

The Clean Air Act Amendments (CAAA) of 1990 required the EPA to set National Ambient Air Quality Standards (NAAQS) for six "criteria" pollutants considered harmful to public health and the environment. The NAAQS identified two types of air quality standards: primary and secondary. Primary standards provide public health protection, including protecting the health of "sensitive" populations, such as asthmatics, children, and the elderly. Secondary standards were established to provide public welfare protection, including protection against impaired

visibility and damage to animals, soils, crops, vegetation, and buildings. The six "criteria air pollutants" that were established by EPA to protect public health and welfare include:

- Ozone (O3)
- Carbon monoxide (CO)
- Particulates (PM10 and PM2.5)
- Sulfur dioxide (SO2)
- Nitrogen dioxide (NO2)
- Lead (Pb)

The Commonwealth of Virginia established the Air Pollution Control Board to establish general administrative and air quality program provisions that support the Regulations for the Control and Abatement of Air Pollution and the provisions of the federal Clean Air Act. This program is administered through six regions throughout the Commonwealth of Virginia. Norfolk International Airport lies within the Tidewater Region. As of 2017, the Tidewater Region was in attainment with all six EPA criteria air pollutants, which includes the City of Norfolk. Previously, this area had been in non-attainment with the 1-hour and 8-hour ozone levels. This designation was revoked in 2007, and the City of Norfolk has been re-designated as a maintenance area for these two criteria.

No air quality modeling was conducted as part of this Study. If proposed developments require air quality modeling, it would be conducted during preparation of additional environmental documentation (and before construction). The results of the air quality modeling should be evaluated to determine whether the proposed activity may contribute to significant 1-hour or 8-hour ozone levels.

## 6.2 BIOLOGICAL RESOURCES (INCLUDING FISH, WILDLIFE, AND PLANTS)

Information regarding biotic communities at the Airport was obtained through a review of the Natural Heritage Data Explorer (NHDE) of the Virginia Department of Conservation and Recreation, screening through the U.S. Fish & Wildlife Service's (USFWS) Information Planning and Conservation (IPaC) System, and a general field walkover.

A large portion of the Airport consists of impervious surfaces such as asphalt, concrete, or buildings. Significant acreage with the Air Operations Area (AOA) is comprised of managed turf adjacent to runways, taxiways and apron areas. These areas provide minimal ecological diversity and show extensive habitat fragmentation.

Intact biotic communities that remain within the Airport include both emergent and forested wetlands (see **Section 6.14**), urban woodlands and open water areas. While no specific critical habitat designations are applicable for the Airport Property (see below), such habitats can support a range of wildlife, including reptiles, amphibians, mammals, song birds and wading birds. For both security purposes and to prevent large mammals, such as deer and coyote, from traversing the runways, the Airport maintains fencing around the airfield.

For implementation of the airfield recommendations, a more detailed environmental analysis would be conducted to assess potential impacts to biotic communities, including quantifying acreages of potential sand barren habitat to be disturbed and identifying mitigation measures to address that loss.

### 6.2.1 Threatened and Endangered Species

The Endangered Species Act of 1973 (ESA) provides for listing, conservation, and recovery of endangered and threatened species of plants and wildlife. Section 7(a)(2) of the ESA states that federal agencies shall ensure the actions it authorizes, funds, or carries out are not likely to jeopardize the continued existence of a listed species or result in a destruction or adverse modification of designated critical habitat. Section 9 of the ESA prohibits the take of listed species. Take is defined in the ESA as "to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect." The definition of harm also includes adverse habitat modifications. Federal actions that could result in a take must be coordinated under Section 7.

Similar to the biotic communities previously discussed, threatened and endangered species that may or are known to occur within the project area were identified through queries of the Virginia Department of Game and Inland Fisheries Fish and Wildlife Information Service (VaFWIS), screening through the USFWS IPaC system, and a review of the Natural Heritage Data Explorer (NHDE) of the Virginia Department of Conservation and Recreation.

***Federally Listed Species***

The IPaC report prepared as part of this overview identified only one federally listed species as potentially occurring at the Airport: The Northern Long-eared Bat (*Myotis septentrionalis*); however, the IPaC report indicated that no critical habitat for this species is found at the Airport.

With respect to the Northern Long-eared Bat, the Final 4(d) rule, issued on January 14, 2016, prohibits an incidental take that may occur from tree removal activities within 150 feet of known occupied maternity roost tree(s) during the "pup season" (generally June 1 to July 31). The 4(d) rule also prohibits an incidental take that may occur from tree removal activities within ¼ mile of a hibernation site, year-round. The nearest known maternity roost tree is located 12.8 miles to the southeast of the Airport. The nearest known hibernacula is located over 180 miles to the northwest of the Airport.

The USFWS IPaC report also identified the following 16 migratory birds as having distributional ranges that overlap the project area:

- American Oystercatcher (*Haematopus palliatus*)
- Bald Eagle (*Haliaeetus leucocephalus*)
- Black Skimmer (*Rynchops niger*)
- Clapper Rail (*Rallus crepitans*)
- Dunlin (*Calidris alpine articola*)
- Gull-billed Tern (*Gelochelidon nilotica*)
- Least Tern (*Sterna antillarum*)

- Prairie Warbler (*Dendroica discolor*)
- Prothonotary Warbler (*Protonotaria citrea*)
- Purple Sandpiper (*Calidris maritima*)
- Red-headed Woodpecker (*Melenerpes erythrocephalus*)
- Red-throated Loon (*Gavia stellata*)
- Ruddy Turnstone (*Arenaria interpres morinella*)
- Rusty Blackbird (*Euphagus carolinus*)
- Semipalmated Sandpiper (*Calidris pusilla*)
- Willet (*Tringa semipalmata*)

Closer to implementation of specific airfield recommendations, more detailed environmental analysis would be conducted, including consultation with USFWS, confirmation of existing species within the project area, an evaluation of potential impacts to those species and habitat areas, and, if appropriate, mitigation measures to address adverse impacts.

***State-Listed Species***

A review of VaFWIS data revealed that fifteen vertebrates, four invertebrates, and four vascular plant species listed as endangered, threatened, and special concern species occur, or formerly within three miles of the Airport. A species-specific evaluation of the available occurrence data indicated that only four state listed avian species and two reptile species of concern occur within the City of Norfolk, and consequently may potentially be found on Airport property. These species are the Eastern Black Rail (*Laterallus jamaicensis jamaicensis*), the Gull-billed Tern (*Gelochelidon nilotica*), the Peregrine Falcon (*Falco peregrinus*), the Loggerhead Shrike (*Lanius ludovicianus*), the Northern Diamond-backed Terrapin (*Malaclemys terrapin terrapin*), and the Spotted Turtle (*Clemmys guttata*).

Of the four state-listed bird species, only the Eastern Black Rail[30] would have specific habitat requirements met within the Airport property. The existing emergent and scrub-shrub wetland habitats could potentially provide this species with both foraging and nesting opportunities. The remaining state listed bird species may potentially be found on or near the Airport but are unlikely to rely upon Airport property for nesting habitat.

The two, state species of concern, the Northern Diamond-backed Terrapin and the Spotted Turtle, are both aquatic turtle species. As Lake Whitehurst is classified as an Impaired Water for aquatic species, the usage of that water body by such species, while possible, is unlikely.

The review of the NHDE indicated no state listed plant species likely to naturally occur within the Airport or adjacent areas. This does not include specimen plants that may exist within the adjacent Norfolk Botanical Garden.

[30] The Eastern Black Rail is proposed for federal listing of endangered species.

A more detailed environmental analysis would be conducted prior to implementation of the airfield recommendations, including formal consultation with the Virginia Department of Game and Inland Fisheries and Virginia Department of Conservation and Recreation, potential field surveys to determine the presence/absence of any listed species, and an evaluation of potential impacts to those species and habitat areas. If appropriate, mitigation measures to address adverse impacts would be pursued.

## 6.3 CLIMATE

Although the FAA has not established a significance threshold for climate, an Environmental Assessment will be required to determine what impacts are present, and mitigation measures will be identified to limit the significance of those impacts. As discussed in **Chapter 3,** operations at ORF are projected to increase during the 20-year planning period. The higher frequency of operations in conjunction with increased fuel consumption may result in a higher level of gas emissions with the possibility to negatively impact the air quality. The EA will be conducted independently of this Study but prior to implementing new development.

## 6.4 COASTAL RESOURCES

The National Oceanic and Atmospheric Administration (NOAA) regulations (15 CFR Part 930) require an analysis of any action affecting the coastal areas along the Atlantic and Gulf Coasts. The Virginia DEQ administers the Virginia Coast Zone Management Program, established in 1986, which administers enforceable laws, regulations and policies that protect the coastal resources of Virginia, foster sustainable use of coastal resources and coordinate the management of coastal lands to ensure sustainable development while minimizing resource use conflicts by promoting informed, science-based decision making. The Airport does lie within the Hampton Roads Planning District of the Virginia Coastal Zone.

This will require that any federal action (including decision making and project funding) that has a reasonably foreseeable effect on any land or water use or natural resource of the coastal zone must be consistent with the enforceable policies of the Virginia Coastal Zone Management Program. This includes both direct and indirect effects. Any proposed project at the Airport will require coordination with the Virginia DEQ to ensure compliance with the enforceable policies (which include Fisheries Management, Subaqueous Lands Management, Wetlands Management, Dunes Management, Non-point Source Pollution Control, Point Source Pollution Control, Shoreline Sanitation, Air Pollution Control, and Coastal Lands Management). Given the location of the Airport and the non-tidal nature of the surrounding aquatic resources (lake and wetlands), some of these policies are not likely to apply.

## 6.5 DEPARTMENT OF TRANSPORTATION ACT, SECTION 4(F)

Pursuant to Section 303 of the U.S. Department of Transportation (Section 4(f)), programs or projects requiring the use of any publicly-owned land, including public parks, recreation areas, wildlife or waterfowl refuge areas, and historic sites (including traditional cultural properties) of national, state, or local significance shall not be approved by the Secretary of Transportation unless there is no feasible and prudent alternative to the use of such land, and such program includes all possible planning to minimize harm.

Based on a review of the surrounding area, two such facilities exist. Lake Whitehurst, which provides recreational opportunities, surrounds the Airport on three sides. Additionally, the Norfolk Botanical Gardens (also known as Azalea Gardens) lies directly adjacent to the airport property just to the north of the terminal area.

Future projects at ORF should be evaluated for potential impacts to these resources as part of the required environmental documentation under NEPA. Impacts to Lake Whitehurst would require a detailed review under Section 303.

## 6.6 FARMLANDS

The Farmland Protection Policy Act (FPPA) limits the conversion of significant agricultural lands to non-agricultural uses as a result of federal actions (7 USC § 4201, et seq.). The determination of whether farmlands are subject to FPPA requirements is based on soil type; thus, the land does not have to be actively used for agriculture. Farmland subject to FPPA requirements can be pastureland, forested, or other land types, but not open water or developed urban or transportation areas. The FPPA regulates four types of farmland soils:

- Prime Farmland;
- Unique Farmland;
- Farmland of Statewide Importance; and
- Farmland of Local Importance.


The evaluation is based upon soils identified by the Natural Resources Conservation Services (NRCS). Prime farmland is defined by the NRCS as “land that has the best combination of physical and chemical characteristics” for agriculture. This includes land with these characteristics used for livestock or timber production but not land that is already urbanized or used for water storage. Unique farmland is defined as “land other than prime farmland that is used for production of specific high-value food and fiber crops,” with such crops defined by the Secretary of Agriculture. Farmland of statewide or local importance is farmland other than prime or unique farmland that “is used for the production of food, feed, fiber, forage or oilseed crops.”

No portion of the Airport is designated prime farmland or the other regulated categories.

## 6.7 HAZARDOUS MATERIALS, SOLID WASTE, AND POLLUTION PREVENTION

The available GIS resources from the EPA were reviewed, indicating a total of eight locations with existing or historic permits under the Resource Conservation and Recovery Act (RCRA). RCRA creates the framework for the proper management of hazardous and non-hazardous solid waste.

## Figure 6-1 – Existing or Historical Permits Under the RCRA



Of these eight locations, five were located on or adjacent to airport property (**Figure 6-1**). The first corresponds to Norfolk International Airport itself, classified as a Conditionally Exempt Small Quantity Generator, including both Norfolk Airport Authority (NAA) and the Transportation Security Administration (TSA) activities. Covered activities include the bulb crusher used by the Airport Authority to recycle spent fluorescent bulbs and the generation of potentially ignitable, corrosive, or reactive waste at the TSA checkpoint.

Two of the directly adjacent locations correspond to air cargo operators at ORF (FedEx and UPS), which are classified as Conditionally Exempt Small Quantity Generators. This designation covers the use of solvents and ignitable waste as part of the service and delivery operations. A third location corresponds to Piedmont Airlines, classified as a Small Quantity Generator of similar materials to the shipping companies. The fifth location represents an FAA facility classified as a Conditionally Exempt Small Quantity Generator of ignitable waste.

The remaining three locations correspond to Arai Americans, Inc (a Small Quantity Generator of ignitable waste and solvents associated with automobile parts manufacturing), TCS Materials Ferry Road Plant (a ready-mix concrete manufacturer) and AEPCO Marine Inc. (A Small Quantity Generator of solvents associated with paint manufacturing).

A search of all available EPA compliance databases was conducted, which demonstrated that as of 2018, all identified facilities comply with the applicable environmental regulations.

Typical of airport facilities, ORF does have potential sources of hazardous material that are generated at the Airport. These include:

- Above-ground storage tanks (ASTs)
- Underground storage tanks (USTs)
- Transformers
- Glycol and deicing
- Buckeye jet fuel pipeline
- Sewage pump areas
- Indoor and outdoor floor/ground drains
- Elevators
- Spills on taxiways, roadways, and parking lots
- Waste storage

Modifications to the existing airport facilities should be evaluated for the potential to generate additional hazardous materials; however, it is not expected that any recommended projects would produce wastes that could not be properly mitigated and addressed. In the case that hazardous waste is encountered during soil disturbing activities, mitigation will be addressed in accordance will all state and federal requirements.

A *Recycling, Reuse, and Waste Reduction Plan* has been established to further evaluate methods of mitigating and controlling hazardous waste, with emphasis on municipal solid waste, construction and demolition debris, compostables, and deplaned waste. See **Appendix O**.

## 6.8 HISTORIC, ARCHITECTURAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES

Under the National Historic Preservation Act of 1966 and the Archaeological and Historic Preservation Act of 1974, federal undertakings, such as the actions included in the Master Plan Update, are subject to Section 106 review to ensure that properties or data having historic, scientific, prehistoric, archaeological or paleontological significance are surveyed, recovered or preserved.

The Virginia Cultural Information System (V-CRIS) of the Virginia Department of Historic Resources was queried in order to identify federally and state-listed resources in the project area. The GIS review identified three potentially historic sites near the project area (**Figure 6-2**).

- Robin Hood Road Bridge, DHR ID 122-5005, located along Robin Hood Road along the southwest perimeter of the airport. This bridge was constructed in 1944.
- Norfolk Azalea Garden/Norfolk Botanical Garden, DHR ID 122-1007, located immediately to the north of the existing airport terminal. First established in 1938, this facility lies at 6700 Azalea Garden Road.
- Little Creek Amphibious Naval Base Historic District, DHR ID 134-0999 – approximately 0.35 miles to the northeast of the Airport.

**Figure 6-2 – Historical Resources**




Of these three resources, only the Norfolk Botanical Garden is listed on both the Virginia Landmarks Register (VLR #06-01-2005) and the National Historic Register of Places (NHRP #08-17-2005).

Prior to implementation of specific airfield recommendations, a more detailed environmental review, including DHR consultation, would be conducted to confirm existing resources and assess any potential effects. During the Environmental Assessment (EA), recognized tribes for this area will have to be consulted. The identified resources above are not likely to be impacted by Master Plan recommendations.

## 6.9 LAND USE

The Norfolk International Airport owns over a thousand acres of property, or approximately two square miles. The Airport is located predominately within the City of Norfolk, with the southeastern portions of the airport in the City of Virginia Beach. While the Airport is predominately surrounded by compatible land use, there are some locations north, west and southwest of the Airport with residential neighborhoods.

### 6.9.1 General Land Use

As shown in the Land Use illustration (**Figure 6-3**), the property surrounding the Airport is very diverse.

- Immediately north of the Airport is the Norfolk Botanical Garden and portions of Lake Whitehurst
- Northeast of the Airport is the location of the US Navy Joint Expeditionary Base Little Creek, as well as the open water areas of Little Creek Harbor and Lake Whitehurst. This location is beneath the final approach of Runway 23. Avigation easements have been established to accommodate aircraft flyovers of the Little Creek Harbor. The Runway Protection Zone (RPZ) of Runway 23 extends over Route 60 and Amphibious Drive onto the base property. The land use within the RPZ mostly includes open space, storage areas, and parking facilities.
- To the southeast of the Airport is an industrial area within the City of Virginia Beach.
- Directly south is a mixed-use area of Virginia Beach known as Burton Station. This area includes dozens of airport parcels that were acquired to protect the Runway 32 approach. **Figure 6-4** illustrates these parcels in greater detail. **Table 6-1** provides information on the acquisition history. Also, in this location is the new Norfolk Premium Outlets shopping mall, industrial uses, and scattered residential development.
- Southwest of the Airport, across Interstate 64 in the City of Norfolk, the mixed land uses include business/office development, industrial, commercial uses along Military Highway, and some residential areas. This location is beneath the final approach of Runway 5. Due to the displaced threshold on Runway 5, the RPZ extends only up to Interstate 64 and does not contain airport or other buildings. As shown in **Figure 6-6**, the Airport has acquired properties in this location adjacent to Robin Hood Road. These properties are currently used for airport employee parking or remain as open space.
- Lastly, the majority of the area to the west and northwest of the Airport is residential, including areas along Norview Avenue, the primary entrance route to the Airport, and Azalea Garden Road (Route 192). As shown in **Figure 6-3** and **Figure 6-5**, this location includes the final approach to Runway 14. As such, some parcels at the intersection of Norview Avenue and Azalea Garden Road were acquired by the Airport in the past to protect the Runway 14 approach. These parcels remain as undeveloped open space.

As shown, the primary airport property includes a continuous area of over 1,000 acres, and contains the Airport's airfield, terminal area, and other aeronautical facilities. All of this property is critical to the Airport and is retained in the Airport's recommended plan.

As discussed above, there are three additional areas of airport property that were acquired more recently and are located beyond the primary airport boundary for the approaches to Runway 5, 14, and 32. These locations were acquired specifically to protect the critical airspace and the Runway Protection Zones against incompatible land use. These three locations have been referred to as non-aeronautical property because they do not contain airport development, are

all located beyond the operational areas, and are outside the airport perimeter fence. These three locations are discussed below.

**Table 6-1 – Parcel Acquisition History**

| Grant Number | Grant Description | Parcel Numbers |
|---|---|---|
| **Runway 32 (Approach End)** | | |
| 4 | Acquire Land for Noise Compatibility within 75 DNL | 78 |
| 5 | Acquire Land for Approaches | 79 |
| 6 | Acquire Land for Approaches | 80, 81, 82, 83, 84, 85, 86, 87, 88, 90 |
| 10 | Acquire Land for Approaches | 89 |
| 14 | Acquire ARFF Vehicle | 57, 61, 62, 63 |
| 16 | Acquire Land for Approaches | 100, 101 |
| 19 | Acquire Land for Approaches | 128 |
| 21 | Acquire Land for Approaches | 108, 110, 111, 114, 121, 122, 123, 124, 143, 144 |
| 27 | Acquire Land for Noise Compatibility within 75 DNL | 116, 117, 118, 119, 120 |
| 41 | Acquire Land for Approaches | 130, 159 |
| N/A | N/A | 55, 59, 64, 91, 95, 102, 106, 107, 109, 112, 125, 129, 131, 145 |
| **Runway 14 (Approach End)** | | |
| 5 | Acquire Land for Approaches | 53, 54 |

Source: NAA, CHA, 2020.

### 6.9.2 South Property

| Future Land Use | |
|---|---|
| ☐ | Retain for Aviation Related Development |
| ☐ | Retain for Non-Aviation Related Development |
| ☑ | Release or Sell Property |

The largest of these areas of non-aeronautical property is to the south of the Airport. The Authority owns over 60 parcels totaling over 50 acres beyond the Runway 32 end, generally known as Burton Station within the City of Virginia Beach; and thus, is subject to the City of Virginia Beach zoning regulations. These parcels are primarily zoned for Light Industrial use, with the southern portion adjacent to residential zoning. The area of Burton Station is largely industrial, including an Industrial Park and the recently opened Norfolk Premium Outlets commercial development. Virginia Beach has conducted initial re-development planning for this area that included the parcels owned by the airport. The City views the location as an important growth area for mixed use economic development.

The Airport Master Plan's recommendations include the proposed permanent closure of the infrequently used Runway 14/32. This has a significant positive effect on the potential development of the Burton Station area, which the City considers a strategic growth area with concepts for revitalization. The 50+ acres of non-aeronautical airport property will no longer be required to protect the airspace and RPZ of Runway 32. As such, the Master Plan recommends releasing all of these parcels for compatible development.

The release of airport property that is no longer needed is referred to by the FAA as 'disposal of surplus property.' The Burton Station properties will fall into this category, which requires a formal process to sell the properties to another party. There are many options for the disposal of the various parcels including:

- Individual parcel sale(s) to private parties or developers
- Bundling and consolidating into larger tracks of land for sale
- Property swaps, where the Airport acquires properties that may be contiguous to the airport boundary, in exchange for non-aeronautical parcels of equal value
- Public-private partnerships (P3) for lease or sale, and associated redevelopment
- Working directly with economic development agencies and/or the City of Virginia Beach for the sale of individual or groups of parcels.

The Master Plan recommends that the logical physical division line between the aeronautical and non-aeronautical properties would be Miller Store Road. Parcels to the north of the road would be permanently retained for airport use. Property south of Miller Store Road can be release and resold.

As all of the surplus non-aeronautical properties were acquired with a mixture of FAA, State, and Airport funds, the basic federal requirements for disposal are summarized below:

FAA Land Release – The Airport coordinates with the FAA to prepare a "Land Release" document, which provides the justification and documentation needed for FAA approval to dispose of the properties. The disposal can include a long-term lease or outright sale of the parcels. In this case, it is recommended that sale in fee is appropriate for these parcels.

Environmental Review –The FAA would typically require an environmental review consistent with NEPA practices in order to evaluate the potential impacts of the property redevelopment; however, regulatory changes in 2018 may enable the sale of the properties without environmental study as the parcels are not currently in airport use or directly accessible from the airport. This determination is made by FAA Headquarters, but would be coordinated through the FAA Washington Airports District Office (ADO).

Fair Market Appraisals – The value of the properties must be determined independently by state-licensed land appraisers, and the property sale must be at the determined fair market value. All applicable value considerations, such as property condition, zoning, current use, comparable local sales, etc. are considered in this process. If appropriate, a second appraisal and review appraisal may be conducted to reach a negotiated sale price.

Retention of Avigation Easements – The sale of airport property typically requires the Airport to retain a permanent easement on the property that protects the airport from development of incompatible land use. Examples include permanent height restrictions that prevent development of radio towers that could impact the overlying airspace and use restrictions preventing development of landfills or other facilities that may attract large numbers of birds (i.e., airport wildlife hazards). Note that existing zoning on these properties already include both height and land use restrictions. Thus, such easements may not result in any further restrictions.

Return of Federal & State Funding – Finally, it is noted that as these properties were acquired with public funds, the sales revenue cannot be retained by the Airport. Rather, the FAA and Airport complete a process that requires the airport to return the federal and state portions of

the property sales revenue (or apply the revenue to a future FAA funded project). As such, the process may be revenue-neutral to the Airport.

As the overall land release process is detailed, many airport sponsors will hire an agent to assist with the process, similar to hiring consultants to implement other airport programs. Following the approval of the Master Plan, it is recommended that the Airport meet with Virginia Beach to discuss their interest in the Burton Station properties and develop an action plan. Following the disposal of the property, the Airport would update their formal Airport Layout Plan and Property Map on file with the FAA.

### 6.9.3 North/Northwest Property

| Future Land Use | |
|---|---|
| ☐ | Retain for Aviation Related Development |
| ☐ | Retain for Non-Aviation Related Development |
| ☑ | Release or Sell Property |

The Authority owns a few large parcels totaling approximately 15 acres to the north/northwest of the airfield beyond the Runway 14 end within in the City of Norfolk. These parcels are zoned for Open Space Preservation and single-family residential. The current land use is open space and woods. Although undeveloped, on City mapping this location is listed as Airport Gateway Park. Similar to the non-aeronautical properties to the south, these parcels are no longer needed for airspace protection to Runway 14 as that runway is recommended for permanent closure. Disposal through sale in fee of these 15 acres is recommended; however, based on the City Zoning, these parcels do not have development potential. Airport uses, including for cell phone parking lot, remote parking, or a gas station are not compatible with the zoning or adjacent homes. Nevertheless, the same FAA disposal process is required, with sale at the fair market value; however, based on the limited potential, the appraised value of these parcels would be low.

Upon approval of the Master Plan, it is recommended that the Airport discuss these properties with the City of Norfolk, or perhaps an independent preservation organization, who may be interested in obtaining ownership in fee. In this circumstance, the FAA would be consulted to determine if the property could be donated for long-term preservation as transfer of the property would have a public benefit of open space preservation.


In addition to the potential public benefits of the land releases to the Cities of Norfolk, Virginia Beach, or other parties, the Airport will also benefit as it would no longer have responsibility for property maintenance, security, or insurance. Parcels would be sold “as is”, with the forthcoming improvements at the discretion of the new owner(s) and applicable regulations.

### 6.9.4 West/Southwest Property

| Future Land Use | |
|---|---|
| ☑ | Retain for Aviation Related Development |
| ☑ | Retain for Non-Aviation Related Development |
| ☐ | Release or Sell Property |

The third area of non-aeronautical property includes five parcels totaling approximately 17 acres west of the airfield near Runway 5, and along Robin Hood Road in the City of Norfolk. This property extends out to Military Highway (Route 165) and included former commercial and residential uses. The property was acquired to protect the approach to Runway 5 and ensure compatibly land use.

In recent years, a portion of these parcels were redeveloped into temporary airport employee parking, which requires the airport to run shuttles to and from the terminal complex. Existing zoning includes a mixture of Open Space Preservation, Corridor Commercial, Single-Family Residential, and General Airport. With exception of the open space, which includes wetlands and environmentally sensitive property, ideally the remainder of the property would be rezoned to General Airport. The Master Plan's recommendations include use of this property for expanded airport landside facilities including parking, rental car facilities, or airport-related commercial use. As such, these properties are recommended for permanent airport property and may be considered as aeronautical property. Thus, the property will be retained by the Authority.




# NORFOLK INTERNATIONAL AIRPORT

## MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000


## LEGEND

- Airport Property Boundary
- Parcel Delineation
- Non-Aeronautical Airport Property
- Municipal Boundary

## LAND USE

- Officespace
- Residential
- Multi-family Residential
- Commercial
- Military Base
- Parks/Recreation/Greenspace
- Industrial & Institutional
- Agricultural
- Schools & Hospitals

**Figure 6-3**
Non-Aeronautical Airport Property




**LEGEND**


- Airport Property Boundary
- Parcel Delineation
- Non Aeronautical Airport Property

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

**Figure 6-4**

Non-Aeronautical Airport Property (South)





**LEGEND**

- Airport Property Boundary
- Parcel Delineation
- Non Aeronautical Airport Property

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

**Figure 6-5**
Non-Aeronautical Airport Property (North)




**LEGEND**

- Airport Property Boundary
- Parcel Delineation
- Non Aeronautical Airport Property

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

**Figure 6-6**
Non-Aeronautical Airport Property (West)

## 6.10 NATURAL RESOURCES AND ENERGY SUPPLY

As shown in **Appendix P**, an *Energy Efficiency Assessment* was conducted to evaluate current utility infrastructure, with an emphasis on electricity, natural gas, and propane, for usage and consumption. Energy conservation measures such as solar photovoltaic arrays, wind turbines, and cogeneration were also evaluated.

In regard to the Master Plan Update, the recommended projects consist primarily of standard upgrades to existing infrastructure at the Airport; therefore, development will not likely have regional impacts on natural resources and energy supply.

## 6.11 NOISE AND COMPATIBLE LAND USE

As shown in the FAA-approved forecasts (**Chapter 3**), air traffic is projected to increase during the 20-year planning period; therefore, it is likely that noise levels will also increase. To date, NAA has completed noise evaluations, and further studies will be coordinated separate from this Master Plan to determine if the future noise levels negatively impact the area surrounding the Airport.

As discussed in **Section 6.9**, a land use analysis was also conducted that evaluated the property near the Airport for compatible land use.

## 6.12 SOCIOECONOMICS, ENVIRONMENTAL JUSTICE, AND CHILDREN'S ENVIRONMENTAL HEALTH AND SAFETY RISKS

Socioeconomics, environmental justice, and children's environmental health and safety risks were not evaluated during the Master Plan Update. Rather, they will be evaluated during a separate Environmental Assessment for significant projects at the Airport; however, most of the anticipated development projects are anticipated to have little to no effect on the previously mentioned matters, as the projects are on airport-owned property and no property acquisitions or new runways are expected within the planning horizon.

## 6.13 VISUAL EFFECTS (INCLUDING LIGHT EMISSIONS)

All improvements to existing infrastructure are within the Airport's existing property line and do not include projects consisting of new lighting systems or the construction of a new runway.

## 6.14 WATER RESOURCES


### 6.14.1 Wetlands

Wetlands at the Airport are regulated and protected under both federal and state regulatory programs. U.S. Department of Transportation Order 5660.1A, *Preservation of the Nation's Wetlands*, implements Executive Order 11990, *Protection of Wetlands*. The U.S. Army Corps of Engineers (USACE) administers Section 404 of the Clean Water Act (CWA) (33 CFR 320-332) which regulates discharges of fill into wetlands and waters of the United States. Wetlands as defined in 33 CFR Part 328 are *"those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas."* The Virginia Water Protection Permit

Program (VWP) of the Virginia Department of Environmental Quality serves as Virginia's Section 401 certification program of federal Section 404 permits issued by the USACE. The VWP regulates activities in both tidal and non-tidal wetlands, including non-tidal wetlands that may not fall under federal jurisdiction but are still considered waters of the state.

In order to identify wetlands occurring within the Airport Property, data available online through the National Wetlands Inventory (NWI) mapper was reviewed. A field walkover of the Airport was also conducted to confirm the potential presence of the wetlands indicated on the NWI. Wetland boundaries were not formally delineated as part of this Study. It is anticipated that prior to initiating specific projects, a current wetland delineation would be required to determine federal and state regulated wetland boundaries.

**Figure 6-7 – NWI Wetland Map**



A number of wetlands occur on the Airport. Based upon available information, and observations during the field walkover, all of the wetland areas are non-tidal wetlands. Based on information obtained (other than Lake Whitehurst), on-airport wetlands are primarily forested and dominated by red maples and northern spice bush. The largest contiguous wetlands occur at the end of Runway 23 associated with Lake Whitehurst and are comprised of a mosaic of wetland types (**Figure 6-8**). Emergent, scrub/shrub and forested wetland areas were observed, adjacent to and surrounding the open water area of Lake Whitehurst. Additional wetland areas are also present at the end of Runway 5, including emergent and forested wetlands (**Figure 6-9**).

**Figure 6-8 – Runway 23 Wetland Detail**






**Figure 6-9 – Runway 5 Wetland Detail**




## 6.14.2 Floodplains

Executive Order 11988, *Floodplain Management*, defines floodplains as "the lowland and relatively flat areas adjoining inland and coastal waters including flood prone areas of offshore islands", including the area that would be inundated by a 100-year flood. A 100-year floodplain is an area that has a 1 percent chance of being flooded in any given year (Zone AE). A 500-year floodplain is an area that has a 0.2 percent chance of being flooded in any given year.

## Figure 6-10 – Floodplain Map



Both 100 and 500-year floodplains are present on the Airport in connection with Lake Whitehurst and the nearby Chesapeake Bay Estuary.

Based on the foregoing, the projects recommended in the master plan are not anticipated to impact floodplains; however, prior to implementation, project-specific environmental documentation would be prepared to document existing floodplains in the area and evaluate potential for impacts. If it is determined that a proposed action would occur within the 100-year floodplain, compliance with applicable state and federal flood and stormwater management standards must be demonstrated.

### 6.14.3 Wild and Scenic Rivers

Through the National Wild and Scenic Rivers Act of 1968 (16 U.S.C 1271), rivers can be federally designated as wild and scenic if they contain remarkable scenic, recreational, or fish and wildlife related values. Such rivers are granted protection under the Act and must be evaluated as part of the NEPA process. Based upon a review of the National Wild and Scenic Rivers System, Virginia has no designated Wild and Scenic Rivers.

### 6.14.4 Water Quality

Water quality standards applicable to the Airport were established under the federal Clean Water Act (CWA) and the Virginia State Water Control Law and the Groundwater Management Act of 1992. Together, these regulations include requirements for controlling discharges into surface water and groundwater, develop waste treatment management plans and practices, and establish federal permitting requirements for discharges (CWA Section 402) and dredged and fill materials (CWA Section 404). Existing surface water and groundwater quality at the Airport are described below.

***Surface Water***

Surface water features on and in the immediate vicinity of the Airport include a network of drainage features, wetlands and open water that comprise the Lake Whitehurst Reservoir. Existing wetlands are described in subsequent sections. Surface waters on the airport flow, either through stormwater drainage systems or concentrated drainage channels, into Lake Whitehurst.

Lake Whitehurst is classified as an Impaired (Category 5A) Water by the Virginia DEQ. This designation represents the poor ability of the lake to support aquatic life (due to high levels of chlorophyll-a and phosphorus, and low levels of dissolved oxygen) and a restriction on the consumption of fish removed from the lake (due to the presence of PCBs and mercury in fish tissue). Lake Whitehurst was first listed as an Impaired Water in 2006, with additional listings added in 2008 and 2010.

Any future projects that would potentially add additional impervious surface would increase the potential for runoff from the Airport into nearby surface water. Prior to implementation of these improvements, more detailed documentation would be required to more specifically quantify the additional impervious surface area and assess resulting impacts to surface water. Drainage improvements would be required to minimize stormwater runoff and associated potential for adverse impacts to surface waters. These improvements should be included in the project design and fully evaluated in the project-specific environmental documentation to be conducted closer

to the time of construction. If such elements are incorporated, it is not anticipated that the proposed projects would result in adverse impacts to surface water quality.




***Groundwater***

The Virginia Department of Environmental Quality administers the Groundwater Characterization Program, which assesses groundwater availability and ambient groundwater quality to inform management decisions in legislatively designated Groundwater Management Areas. The Airport lies within the Eastern Virginia Groundwater Management Area.

At the level of effort for this overview, no specific information on groundwater quality in the immediate vicinity of ORF was available. Any proposed projects would be evaluated closer to implementation, when more details are available, in a project-specific environmental document to determine potential impacts.

***Stormwater***

ORF holds an existing Virginia Pollution Discharge Elimination System (VPDES) permit (permit #VA0089737), which is the state-administered program regulating the discharge of stormwater from an industrial facility. As an airport, ORF is classified as a minor industrial facility and must comply with the Virginia Pollution Discharge Elimination System Permit Regulation (9VAC25-31-190). This includes compliance with all effluent standards mandated by the Clean Water Act through the proper operation and maintenance of all facilities and systems of treatment and control which are installed or used by the permittee to achieve compliance with the conditions of the permit. ORF is also required to monitor the existing stormwater discharges from the Airport for the effluents of concern and report those to the Virginia Department of Environmental Quality (DEQ).

Any modifications to the drainage system or modifications to physical facilities at the Airport which would result in a change to either the quantity or potential quality of stormwater discharge from the airport should be communicated to the Virginia DEQ to determine if the existing permit would require modification or reissue.

In general, new airfield or major terminal projects would trigger the need to address water quality and associated permitting. General maintenance and minor projects typically do not affect water quality.

## 6.15 SUMMARY

Projects recommended in the master plan are anticipated to have some impacts on the environment, with concerns generally focused on water quality, biotic communities, threatened and endangered species, and wetlands. As noted under each of the resource-specific sections, before implementation of some of the proposed development projects, an Environmental Assessment (EA) or Environmental Impact Statement (EIS) would be required to identify existing conditions at that time, determine impacts on each resource, and if appropriate, identity mitigation measures to address adverse impacts. Once project details are available, if appropriate under NEPA, Categorical Exclusion(s) or Environmental Assessment(s) will be prepared in accordance with FAA guidance. Based on past studies and the types of projects recommended in the master plan, it is anticipated that impacts can be successfully mitigated allowing implementation of the recommended plan.

# 7 FINANCIAL PLAN

This chapter presents the description of the airport capital improvement program (ACIP) and the resulting financial projections for the Norfolk International Airport (ORF). The ACIP was developed under the assumption that various demand-based indicators, such as annual operations, annual passenger enplanements, and based aircraft grow in-line with the aviation demand forecast presented in the ORF Master Plan **Chapter 3**.

ORF is operated by the Norfolk Airport Authority (Authority). The Authority was established in 1948 as a political subdivision of the Commonwealth of Virginia. The Authority's Fiscal Year (FY) ends June 30. The ACIP was prepared for four planning activity levels (PALs): PAL 1 (FY 2020 through FY 2023), PAL 2 (FY 2024 through FY 2028), PAL 3 (FY 2029 through FY 2033), and PAL 4 (FY 2034 through FY 2038). Due to the uncertainty of capital needs, funding availability, and financial metrics past a 10-year time frame, financial projections were only developed for PAL 1 and PAL 2. Master plans are typically prepared every five to seven years. As a result, an updated master plan would be prepared for ORF during the PAL 2 timeframe, thus producing more accurate project forecasts for the PAL 3 and PAL 4 timeframe.

The FY 2019 numbers included in this Chapter reflect the amounts presented in the Authority's Basic Financial Statements (2019 Financial Statements), and the FY 2020 numbers reflect the Authority's 2020 budget approved by the Board of Commissioners (the Board) in May 2019 (FY 2020 Budget). All financial tables are included at the end of this Chapter.

## 7.1 ACTIVITY FORECAST

**Table 7-1** presents the activity forecast used to develop the financial plan. The enplanement and operation forecast for FY 2020 through FY 2038 reflect the amounts included in ORF's Master Plan **Chapter 3**, **Table 3-31**. Since the forecast was prepared prior to December 2018, the FY 2018 and FY 2019 enplanements and operations in **Table 7-1** reflect actual versus forecast.

As shown in the table, enplanements are forecast to grow at a compound annual growth rate (CAGR) of 2.5 percent from FY 2018 through FY 2038, and operations are forecast to grow at a CAGR of 1.4 percent for the same period. The FY 2020 budgeted landed weight decreases from the FY 2019 actual amount since the budget was prepared prior to actual results. Since landed weight was not forecast in **Table 3-31** but is necessary to calculate the landing fee for the financial forecast, the FY 2021 through FY 2038 landed weights were assumed to grow with the annual percent growth in operations shown in **Table 3-31**.

## 7.2 CAPITAL PROGRAM AND COST SUMMARIES

All airports receiving federal Airport Improvement Program (AIP) funding are required to maintain a current ACIP with the Federal Aviation Administration (FAA), which identifies projects to be undertaken at an airport over a specified period of time. The Authority's ACIP includes the projects recommended in **Chapter 6** of this Master Plan.

**Table 7-2** presents the recommended ACIP and its corresponding cost estimates, which were based on a planning level of detail, for PAL 1 and PAL 2. While accurate for master planning purposes, actual project costs will likely vary from these planning estimates once project design and engineering estimates are developed. The cost estimates presented in the table are presented in 2020 dollars and include contingencies, design costs and construction management costs. As shown in the table, the ACIP for PAL 1 and PAL 2 is estimated at approximately $411.8 million.

## 7.3 CAPITAL PROGRAM FUNDING SOURCES

**Table 7-3** presents the ACIP's estimated funding sources for PAL 1 and PAL 2. The following sections describe the amount of funding available from these sources.

### 7.3.1 AIP Grants

Grants administered by the FAA through the AIP are a critical capital funding source to implement the projects recommended in the ACIP. Passenger entitlement grants are allocated to airports by a formula based on enplanements, cargo entitlement grants are allocated based on historical landed weight market share, and discretionary grants are allocated in accordance with FAA guidelines. FAA grants are subject to annual Congressional appropriation. The AIP expires periodically, and federal reauthorization is required to continue. In October 2018, Congress passed a five-year reauthorization bill for the FAA — the FAA Reauthorization Act of 2018.

The U.S. DOT classifies ORF as a small hub airport; therefore, the AIP formula stipulates that ORF is entitled to receive 90 percent in federal funding for AIP-eligible projects. AIP funds can be used for most improvement needs, but not operating costs; however, AIP funds are typically not available for revenue-generating projects, so for the purpose of this analysis, AIP funds were not assumed for revenue-generating projects.

As shown on **Table 7-3**, AIP grants were estimated to be approximately $86.5 million from FY 2020 through FY 2028. Of this amount, approximately $55.0 million was assumed to be funded with passenger entitlement grants, approximately $1.5 million was assumed to be funded with cargo entitlement grants, and $30 million with discretionary grants. The annual application of the AIP grants to the eligible portions of the ACIP is presented in **Table 7-4** and is described in greater detail in the following subsections.

***Entitlement Grants***

Entitlement funds are distributed through grants by a formula based on the number of enplanements at individual airports and the amount of landed weight of arriving cargo at individual airports for the most recent federal fiscal year. In cases where entitlement funds are not used during the current federal fiscal year, these funds are redistributed to other airport sponsors as discretionary funds in the next federal fiscal year. **Table 7-5** presents ORF's AIP passenger entitlement calculation. As shown in the table, it is estimated that ORF will receive approximately $45.9 million in passenger entitlement AIP grants from FY 2020 through FY 2028.

ORF also receives cargo entitlement grants. In FY 2019, the FAA apportioned total entitlements of $3.2 billion, of which 3.5 percent is allotted for cargo entitlements, or $112 million. This amount is then allocated to airports on a pro-rata basis according to an airport's share of total U.S. cargo landed weight. In FY 2017, ORF's cargo landed weight was 0.15 percent of total U.S.

landed weight; therefore, ORF was apportioned $165,000 in cargo entitlements in FY 2019. This amount is forecast to increase with the growth in landed weight presented in **Table 7-1**. As shown on **Table 7-4**, it is estimated that ORF will receive approximately $1.5 million in cargo entitlement AIP grants from FY 2020 through FY 2028.

***Discretionary Grants***

At the beginning of each federal fiscal year, the FAA sets aside the amount of discretionary funds to cover the Letter of Intent (LOI) payment schedules. The total discretionary funds in all LOIs subject to future obligation are limited to approximately 50 percent of the forecast discretionary funds available for that purpose. The authorizing statute directs the FAA to allocate certain discretionary funding to specific airport types and set aside categories such as noise, reliever airports, military airport program and projects relating to capacity, safety, security and noise; however, the FAA has some discretion in funding specific projects within these discretionary funding set-aside categories. The FAA approves discretionary funds for use on specific projects, after consideration of project priority and other selection criteria.

As shown on **Table 7-2**, approximately $30 million in discretionary funds are assumed to fund a portion of the $103.0 million design and construction of Runway 5/23. Since the Authority has not yet received FAA approval for these funds, it is possible that it will not receive these funds. If the Authority does not receive this discretionary funding, it will need to identify alternative funding sources, delay the projects until funding sources become available, or cancel the projects. A possible alternative funding source in PAL 1 and PAL 2, if the discretionary funds are not approved, is the Authority's General Reserve Fund balance, which is discussed in greater detail in **Section 7.5.5 Pro Forma Cash Flow.**

As shown on **Table 7-2**, of the $411.8 million total project costs, approximately $255.8 million is eligible for AIP grants; however, as shown in **Table 7-4**, only $77.5 million is available in AIP passenger entitlements, cargo entitlements, and discretionary funds. This shortfall in funding will need to be recovered in other funding sources, which are discussed in greater detail in the remainder of this section.

### 7.3.2 State Grants

The Code of Virginia §58.1-638 *Disposition of state sales and use tax revenue* created in the Department of the Treasury a special non-reverting fund which is part of the Transportation Trust Fund and is known as the Commonwealth Airport Fund (CAF). The Commonwealth Transportation Board per §58.1-638 annually allocates 2.4 percent of the Transportation Trust Fund for the CAF. These funds are allocated by the Commonwealth Transportation Board to the Virginia Aviation Board (VAB). Funds are then allocated by the VAB to any Virginia airport which is owned by the Commonwealth, a governmental subdivision thereof, or a private entity to which the public has access for the purposes enumerated in Code of Virginia §5.1-2.16 or is owned or leased by the Metropolitan Washington Airports Authority.

The CAF is then used through entitlement and discretionary funds, to provide funding for planning and engineering projects that focus on airport facility development. In general, these projects include master plan and airport layout plan studies, environmental studies, land acquisition, airside facility design and construction, and terminal building design and construction.

The maximum amount an airport can receive from CAF entitlement funds is $2 million annually, which is what ORF has historically received. As shown on **Table 7-4**, this analysis assumed ORF will continue to receive $2 million annually from CAF for a total of $28.7 million in state entitlement grants through PAL 2. FY 2021 state entitlements are greater than the $2 million maximum annual entitlement due to the anticipated reimbursement of state entitlement funds which were used to fund previous capital projects. The Authority has received authorization from the FAA to utilize passenger facility charge (PFC) revenue for this reimbursement.

In addition to entitlement funds, CAF has approximately $8 million annually that is applied on a discretionary basis. This analysis assumed that ORF will receive discretionary state grants in the amount of $5 million in FY 2022, FY 2023, and FY 2024, for a total of $15 million, to fund the reconstruction of Runway 5/23. If the Authority does not receive approval for this funding, it will need to identify alternative funding sources, delay the projects until funding sources become available, or cancel the projects.

### 7.3.3 Third Party

Many airports use private third-party investment when the planned improvements will primarily be used by a private business or other organization. Such projects are not ordinarily eligible for federal funding. Projects of this kind typically include cargo facilities, hangars, FBO facilities, fuel storage, exclusive aircraft parking aprons, industrial aviation use facilities, non-aviation office/ commercial/industrial developments, and similar projects. Private development proposals are considered by an airport on a case-by-case basis. Often, airport funds for infrastructure, preliminary site work, and site access are required to facilitate privately developed projects on airport property.

This analysis assumed the Authority will fund all projects, and therefore, no third-party funding was included; however, certain projects may be considered for third party financing such as the cargo facility expansion totaling $26.5 million in FY 2025, the relocation of the fuel farm totaling $40 million in FY 2026, and the general aviation hangar construction totaling $22 million in FY 2028.

### 7.3.4 Local Funds

As shown in **Table 7-3**, approximately $137.9 million in PFC revenue (excluding financing costs), $12.2 million in customer facility charge (CFC) revenue, and $131.1 million in ORF revenue (excluding financing costs) is required to fund the remaining costs of the ACIP. These funding sources are described in greater detail in the following sub-sections.

***Passenger Facility Charges***

PFCs are authorized by Title 14 of the Code of Federal Regulations, Part 158 and are administered by the FAA. PFCs collected from qualified enplaned passengers are used to fund eligible projects. An airport operator can impose a PFC of $1, $2, $3, $4 or $4.50 per eligible, enplaned passenger. Once a PFC is imposed, it is included as part of the ticket price paid by passengers enplaning at the airport, collected by the airlines and remitted to the airport operator, less an allowance for airline processing expenses. The PFC legislation stipulates that if a medium to large hub airport institutes a PFC of $1, $2, or $3, they must forego 50 percent of their AIP entitlement funds. This increases to 75 percent if they charge a $4 or $4.50 PFC. Since ORF is designated by the FAA as a small hub airport, it does not have to forego any of its annual AIP entitlement funds.

Projects that are eligible for PFC funding include those that preserve or enhance the capacity, safety or security of the air transportation system, reduce noise or mitigate noise effects, or furnish opportunities for enhanced competition between or among air carriers. PFCs cannot be used for revenue-generating facilities at airports, such as restaurants and other concession space, rental car facilities, public parking facilities or construction of exclusively leased space or facilities.

The Authority currently has three open PFC applications all having approval to collect a $4.50 per enplaned passenger fee. PFC Application #14-04-C-00-ORF is fully funded but not yet closed out, PFC Application #18-05-C-00-ORF is forecast to be fully funded in FY 2020, and PFC Application #19-06-C-00-ORF expires on April 1, 2023. This expiration date was determined based on ORF's Terminal Area Forecast for enplanements dated February 2019 (TAF). The TAF has a CAGR of 1.8 percent from FY 2019 through FY 2022 compared to the Master Plan enplanement forecast included in **Table 3-31** of 3 percent for the same time period. As a result of the higher enplanement growth rate, PFC revenues are estimated to be available for future eligible projects in FY 2022.

**Table 7-6** presents the PFC calculation for ORF, as well as the annual funding plan for these revenues. As shown in the table, approximately $77.8 million in PFCs are estimated to be collected during the projection period. This amount increases to approximately $92.2 million when combined with $14.4 million of PFCs the Authority has in its PFC Fund as of June 30, 2019. Approximately $10 million of this PFC revenue is committed to fund PFC Application #18-05-C-00-ORF and $15.8 million is committed to fund PFC Application #19-06-C-00-ORF, with the $66.4 million remaining being available to fund the ACIP on a pay-go and leveraged basis.

As shown in **Table 7-3**, $137.9 million in PFCs are needed to fund the ACIP, of which $19.4 million is assumed to be funded on a pay-go basis and, due to a difference in the timing of the project spend versus the receipt of PFC revenues, $118.5 million was assumed to be funded with general airport revenue bonds (GARBs). While this analysis did not make any recommendations on the type of debt structure ORF needs to undertake, it did assume the following:

- Thirty-year GARB issuances in 2022 and 2025 to fund the PFC eligible portions of the ACIP.
- Five percent interest rate.
- The funding of a debt service reserve equaling maximum annual debt service.

These assumptions translate into GARB issuances with a total construction fund deposit of $118.5 million, which is all for airfield projects, at a par amount of $128.3 million. **Table 7-7** presents the debt service that results from the future PFC-eligible GARB issuances. As shown in the table, PFC-eligible debt service totals approximately $43.6 million through PAL 2 and approximately $250.4 million through the term of the bonds. These GARB issuances would commit the majority of PFC revenues through FY 2054; however, the Authority's PFC capacity would become available prior to 2054 if actual enplanements are better than forecasted and if the PFC collection rate is increased from the current $4.50 per enplaned passenger fee.

***Customer Facility Charges***

In September 1999, the Authority approved a CFC to be charged by the rental car companies to their customers. This CFC is collected by the rental car companies to cover the costs of on-airport

rental car facilities, including all costs associated with ready/return facilities, parking facilities, and a shuttle bus service (1999 Resolution). According to the 1999 Resolution, the CFC is calculated annually based on the estimated cost of operating the rental car facilities and is collected from rental car customers using the airport facilities and remitted 100 percent to the Authority by the rental car operators. The initial CFC was estimated to be between $0.70 and $1.00 per transaction/rental, increasing to $1.03 in FY 2018. In May 2018, the Board approved a resolution, which authorized the Authority's staff to set a CFC rate to fund future capital projects. As a result, the CFC was increased to $2.00 per transaction day effective July 29, 2018. The rental car companies are obligated to collect the CFC through July 31, 2023, which can be extended by mutual agreement of the Authority and the rental car companies.

**Table 7-8** presents the CFC calculation for ORF, as well as the annual funding plan for these revenues. As shown in the table, $28.7 million in CFCs were assumed to be collected through PAL 2, of which $12.2 million is needed to fund the CFC-eligible portions of the ACIP on a pay-go basis, $11.3 million is used to fund rental car operating expenses, and $3.4 million to fund the CFC-eligible debt service related to the Series 2019 Bond.

***Authority Funds***

ORF generates revenue through parking, rental cars, terminal concessions, land rents, and airline revenues. These revenues are used to cover maintenance and operating expenses and debt service obligations at ORF. As shown on **Table 7-3**, approximately $131.1 in Authority funds (excluding financing costs) are required to fund the remainder of the ACIP. This amount was forecast to be funded through a combination of pay-go funds and GARBs, which are described in greater detail in **Section 7.5 Financial Feasibility**.

## 7.4 AUTHORITY'S ACCOUNTING STRUCTURE

The Authority was established in 1948 as a political subdivision of the Commonwealth of Virginia and has the full responsibility for ORF's operation, maintenance, and development. The Authority is governed by the Board of at least seven but not more than nine members appointed for four-year terms by the City Council. The Authority has a management staff headed by the Executive Director who is appointed by the Board.

Under Section 601 of the Master Indenture, Rate Covenant, the Authority shall continuously own, control, operate, and maintain ORF in an efficient and economical manner and on a revenue producing basis and shall at all times prescribe, fix, maintain, and collect rates, fees, and other charges for the services and facilities furnished by ORF fully sufficient at all times:

- For 100 percent of the Operating Expenses and for the accumulation in the Revenue Fund of a reasonable reserve therefor; and
- Such Net Revenues for General Revenues in each Fiscal Year:
  - Will equal at least 125 percent of the Debt Service Requirement on all Revenue Obligations secured by General Revenues then Outstanding;
  - Will enable the Authority to make all required payments, if any, into the Debt Service Reserve Account and the Rebate Fund and on any Contract or Other Airport Obligation;

- Will enable the Authority to accumulate an amount to be held in the Renewal and Extension Fund, which in the judgment of the Authority is adequate to meet the costs of major renewals, replacements, repairs, additions, betterments, and improvements to ORF, necessary to keep the same in good operating condition or as is required by any governmental agency having jurisdiction over the ORF; and
- Will remedy all deficiencies in required payments into any of the funds and accounts mentioned in the Indenture from prior Fiscal Years.

The Airline Agreements extend through June 30, 2021 and shall be automatically renewed for two additional terms of one year each unless either party gives notice of its intent to terminate 90 days prior to the end of the then current term. The Signatory Airlines include American, Delta, Southwest, and United. FedEx and UPS are not signatory to the Airline Agreement but pay signatory landing fees since they meet the minimum number of flights required to pay the signatory rates. Allegiant and Frontier are the only Non-Signatory Airlines operating at ORF. Article 7 of the Airline Agreements describes the method for the calculation of the rents, fees and charges of the Signatory Airlines for the use of facilities, rights, licenses, and privileges to operate at ORF, which is a compensatory rate-setting methodology with a revenue-sharing mechanism. Non-signatory airlines pay a fee that is 1.25 times higher than the rates paid by the Signatory Airlines. The Airline Agreement also permits the Authority to increase the Landing Fee Rate and Terminal Rental Rate to meet the Rate Covenant. Although the Airline Agreements will expire during the forecast period, the rate-setting methodologies outlined in the current Airline Agreements were assumed to be extended throughout the forecast period.

## 7.5 FINANCIAL FEASIBILITY

This section of the financial analysis presents the projected operating expenses, debt service, and revenues resulting from the daily operation of the Authority. In addition, the funding of the ACIP was layered into the projections to determine if it is feasible for the Authority to undertake the program in the FY 2020 through FY 2028 planning period.

### 7.5.1 Operating Expenses

The Authority's financial statements were prepared using the economic resources measurement focus and the accrual basis of accounting. Operating expenses include salaries and fringe benefit costs, maintenance and repairs, security, utilities, professional services, administrative, payments to the City, and other operating expenses. Interest expense and financing costs are reported as non-operating expenses.

The FY 2019 operating expenses reflect the actual expenses presented in the 2019 Financial Statements and the FY 2020 operating expenses reflect the FY 2020 Budget. **Table 7-9** presents operating expenses by line item and cost center for FY 2019 through FY 2028.

As shown in the table, operating expenses were approximately $33.5 million in FY 2019 and are budgeted to increase 8.3 percent, primarily as a result of maintenance and repairs and administrative services, to approximately $36.3 million in FY 2020. Operating expenses are forecast to be approximately $40.0 million in FY 2028, reflecting a CAGR of 1.2 percent from FY 2020 through FY 2028. Operating expenses were projected based on the following:

- A review of historical trends and the anticipated effects of inflation assumed at 1.4 percent annually, reflecting the most recent 10-year average of the South Region Consumer Price Index (CPI).
- A reduction of $600,000 in 2022 to reflect the decommissioning of the employee parking lot shuttle buses since the employees will be parking in the garages upon parking garage D's completion.
- Increases in the City Payment of $150,000 every five years based on the Authority's agreement with the City. This agreement expires in 2024; however, this analysis assumed that the City Payments will continue and increase per the existing agreement.

### 7.5.2 Debt Service

The Authority currently has two outstanding debt obligations: Series 2011A-C Bonds and Series 2019 Bonds. As shown in **Table 7-10**, annual outstanding debt service is approximately $4.2 million in FY 2020, increasing to a high of $8.5 million in FY 2024.

As shown in **Table 7-3**, $131.1 million in Authority funds is needed to fund the ACIP, of which $31.2 million was assumed to be funded on a pay-go basis and, due to a difference in the timing of the project spend versus the availability of General Reserve funds, $99.9 million was assumed to be funded with GARBs. While this analysis did not make any recommendations on the type of debt structure ORF needs to undertake, it did assume the following:

- Thirty-year GARB issuances in 2021 and 2025 to fund the ACIP.
- Five percent interest rate.
- Two-year capitalized interest period.
- The funding of a debt service reserve equaling maximum annual debt service.

**Table 7-11** presents the debt service that results from the future GARB issuances. As shown in the table, the total construction fund deposit of $99.9 million at a par amount of $121.3 million. The resulting debt service totals approximately $20.1 million through PAL 2 and approximately $224.6 million through the term of the bonds. The 2021 GARB issuance were assumed to fund ground transportation and general aviation projects and the 2025 GARB issuance were assumed to fund cargo and general aviation projects; therefore, neither bond issuance is funded through airline rates and charges.

### 7.5.3 Capital Improvement Amortization

As shown in **Table 7-3**, approximately $31.2 million in Authority funds are required to fund the remainder of the ACIP on a pay-go basis. According to the Airline Agreements, only airfield, terminal, and an allocation of administrative projects can be recovered through airline rates and charges. As a result, approximately $26.6 million of the Authority-funded projects can be recovered through airline rates and charges. **Table 7-12** presents the estimated amortization for these projects, which totals approximately $3.8 million in FY 2028. The projects are amortized over their useful life at 3%, reflecting the Revenue Bond Index as of January 30, 2020 rounded up.

### 7.5.4 Operating Revenues

Major sources of operating revenue at ORF are derived from non-airline and airline sources. Non-airline revenues accounted for 75.9 percent of ORF's revenues in FY 2019 and include parking, rental car revenues, terminal concessions, FBO fees, land rents, maintenance hangar rentals, cargo rentals, and other operating revenues.

Airline revenues accounted for 24.1 percent of ORF's operating revenue in FY 2019 and included revenues generated primarily from airline landing fees and terminal rentals. As previously discussed, the existing airline agreements expire on June 30, 2021. The methodologies outlined in the current airline agreements were assumed to be in place throughout the forecast period.

**Table 7-13** presents the airline rates and charges at ORF for FY 2020 through FY 2028. As shown in the table, the maximum airline cost per enplanement (CPE) in PAL 1 is $5.74 in FY 2023 and in PAL 2 is $6.00 in FY 2024.

**Table 7-14** presents operating revenues for FY 2019 through FY 2028. As shown, operating revenues were approximately $41.2 million in FY 2019 and budgeted to be $44.8 million in FY 2020, reflecting an 8.7 percent increase, primarily due to an increase in parking and landing fee revenues due to a rate increase. Operating revenues are forecast to increase to approximately $65.6 million in FY 2028, reflecting a CAGR of 4.9 percent from FY 2020 to FY 2028. FY 2021 through FY 2028 operating revenues are projected based on the following:

- Historical trends, lease provisions, and inflation.
- Revenues from parking, terminal concessions, and rental cars are projected to increase with prospective enplanement growth.
- It was assumed that the Authority would renegotiate concession leases that expire during the planning period with terms and conditions that would implement changes in rate structures and business practices, as necessary, to maintain positive financial performance.
- The employee parking monthly fee is estimated to increase from $20 per month to $30 in FY 2022 since the employees will be parking in a garage instead of the surface lot.
- Once the parking garage D is complete in FY 2022, the Authority intends on instituting premium parking programs that could potentially increase parking revenues. Also, there will be a slight increase in available parking spaces that may increase revenues. After 2022, additional parking revenues are forecasted to grow with enplanements.
- Parking rates were assumed to increase $1.00 in FY 2022 to coincide with the completion of parking garage D and then every five years thereafter.
- Air cargo and general aviation terminal rentals were increased in FY 2027 to reflect additional rent anticipated once the new facilities are complete. The revenue increase is equal to the debt service required to fund those facilities.

### 7.5.5 Pro Forma Cash Flow

**Table 7-15** presents the pro forma cash flow of ORF for the planning period, based on the projection of operating revenues, operating expenses, and debt service discussed previously. As shown in the table, the Authority has sufficient funds for its portion of the ACIP through PAL 2.

As previously discussed, the Authority's Master Indenture requires that net revenues available for debt service be at least 125 percent of debt service. **Table 7-16** presents the debt service coverage calculation. As shown in the table, the Authority satisfies the debt service coverage test in PAL 1 and PAL 2.

**Table 7-16** also presents the days cash on hand for ORF. Days cash on hand is the number of days that an organization can continue to pay its operating expenses given the amount of cash available. The Authority's days cash on hand in FY 2019 was 310 days. As shown in the table, the Authority has a minimum of 272 and an average of 300 days cash on hand in PAL 1 and a minimum of 356 and an average of 488 days cash on hand in PAL 2.

This analysis assumed that approximately $30 million in AIP discretionary grants and $15 million in state discretionary grants will fund the ACIP. If the Authority does not receive approval for these funds, it will need to identify alternative funding sources, delay the projects until funding sources become available, or cancel the projects. As shown in **Table 7-15**, the Authority is forecast to have approximately $85.6 million in General Reserve Funds by the end of PAL 2. These funds could be used to bridge any gap that may occur due to the receipt of less discretionary funding.

## 7.6 SUMMARY

The financial feasibility of future projects will be determined by existing and future leases, funding levels and participation rates of federal grant programs, the availability of PFC and CFC revenues and other funding sources, bonding capacity and the ability to generate internal cash flow from operations at ORF.

The financial projections were prepared on the basis of available information and assumptions set forth in this Chapter. It is believed that such information and assumptions provide a reasonable basis for the projections to the level of detail appropriate for planning purposes. Some of the assumptions used to develop the projections may not be realized, and unanticipated events or circumstances may occur; therefore, the actual results will vary from those projected, and such variations could be material.

If actual results are less favorable than the forecast, the Authority may need additional grants, PFCs, CFCs, and Authority funds to fund the ACIP as it is presented; therefore, as the Authority has done in the past, it should continue to monitor its financial situation to determine which projects should be undertaken and when. In addition, the Authority should review and evaluate current leases and service incentives to enhance revenues and provide financial solvency, while improving the facilities.

The actual need for facilities is most appropriately established by airport activity levels rather than a specified date. For example, projections were made as to when the terminal expansions may be needed at ORF. In reality, the timeframe in which the development is needed may be

substantially different. Actual demand may be slower to develop than expected. On the other hand, high levels of demand may establish the need to accelerate the development. Although every effort was made in this planning process to conservatively estimate when facility development may be needed, aviation demand will dictate when facility improvements need to be delayed or accelerated.

**Table 7-1 – Activity Forecast**
**(in 000s)**

| Fiscal Year | Enplanements | | Operations | | Landed Weight (a) | Change |
|---|---|---|---|---|---|---|
| | Per Table 3-31 | % Change | Per Table 3-31 | % Change | | |
| **2018(b)** | 1,741.1 | -- | 74.8 | -- | 2,308.8 | -- |
| **2019(b)** | 1,927.1 | 10.7% | 78.0 | 4.3% | 2,689.3 | 16.5% |
| **Forecast** | | | | | | |
| **2020** | 2,038.2 | 5.8% | 78.7 | 0.8% | 2,551.4 | -5.1% |
| **2021** | 2,072.3 | 1.7% | 79.3 | 0.8% | 2,572.6 | 0.8% |
| **2022** | 2,104.7 | 1.6% | 80.0 | 0.8% | 2,594.1 | 0.8% |
| **2023** | 2,115.4 | 0.5% | 80.1 | 0.1% | 2,614.2 | 0.8% |
| **2024** | 2,168.2 | 2.5% | 81.2 | 1.5% | 2,617.4 | 0.1% |
| **2025** | 2,220.8 | 2.4% | 82.4 | 1.4% | 2,656.0 | 1.5% |
| **2026** | 2,273.2 | 2.4% | 83.6 | 1.4% | 2,694.4 | 1.4% |
| **2027** | 2,325.3 | 2.3% | 84.7 | 1.4% | 2,732.2 | 1.4% |
| **2028** | 2,377.0 | 2.2% | 85.9 | 1.4% | 2,770.5 | 1.4% |
| **2029** | 2,428.3 | 2.2% | 87.0 | 1.2% | 2,808.3 | 1.4% |
| **2030** | 2,479.3 | 2.1% | 88.0 | 1.2% | 2,843.0 | 1.2% |
| **2031** | 2,528.7 | 2.0% | 89.0 | 1.2% | 2,877.4 | 1.2% |
| **2032** | 2,576.4 | 1.9% | 90.0 | 1.1% | 2,910.8 | 1.2% |
| **2033** | 2,622.8 | 1.8% | 91.0 | 1.1% | 2,943.0 | 1.1% |
| **2034** | 2,667.8 | 1.7% | 92.4 | 1.6% | 2,974.9 | 1.1% |
| **2035** | 2,711.4 | 1.6% | 93.8 | 1.5% | 3,021.5 | 1.6% |
| **2036** | 2,753.7 | 1.6% | 95.2 | 1.5% | 3,067.8 | 1.5% |
| **2037** | 2,794.8 | 1.5% | 96.6 | 1.5% | 3,113.5 | 1.5% |
| **2038** | 2,834.6 | 1.4% | 98.0 | 1.4% | 3,158.6 | 1.5% |
| **CAGR (2018 - 2038)** | **2.5%** | | **1.4%** | | **1.6%** | |

(a) The FY 2020 landed weight amount reflects the amount included in the FY 2020 Budget. Since landed weight is not forecast in Table 3-31, FY 2021 through FY 2038 is forecast to grow based on the growth in operations.
(b) FY 2018 and FY 2019 reflect actual results; and therefore, do not match the amounts in Table 3-31.
Source: DKMG, CHA, 2020.

## Table 7-2 – ACIP and Funding Sources
## (in 000s)

| Project | Fiscal Year | Cost Center | Project Costs | Inflated | 90% Eligibility | Funding Sources | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | AIP Grants | | | State | | Third Party | Authority | | | | | | Total |
| | | | | | | Entitlement | | Discretionary | Entitlement | Discretionary | | PFCs | | CFC | General Reserve | | | |
| | | | | | | Passenger | Cargo | | | | | Pay-Go | GARBs | | GARBs | Direct Expense (a) Amort in Rate Base | Direct Expense (a) Non-rate base | |
| **PAL 1 (2020-2023)** | | | | | | | | | | | | | | | | | | |
| Airfield Signage Replacement (Design & Constr) | 2020 | Airfield | $2,500 | $2,500 | $2,250 | $2,250 | $0 | $0 | $250 | $0 | $0 | $0 | $0 | $0 | $0 | $0 | $0 | $2,500 |
| Txwy 'C' South Reconstruct (Design) | 2020 | Airfield | 1,500 | 1,500 | 1,350 | 1,350 | 0 | 0 | 150 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,500 |
| Property Purchase - Gurley Street (3 Parcels) | 2020 | Airfield | 525 | 525 | 473 | 473 | 0 | 0 | 53 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 525 |
| Property Purchase - Barrs Road | 2020 | Airfield | 750 | 750 | 675 | 675 | 0 | 0 | 75 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 750 |
| Pavement Management Plan Update | 2020 | Airfield | 250 | 250 | 225 | 225 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 250 |
| Continuous Friction Measuring Equipment (Purchase) | 2020 | Airfield | 70 | 70 | 63 | 0 | 0 | 0 | 56 | 0 | 0 | 0 | 0 | 0 | 0 | 14 | 0 | 70 |
| Intersection Impr-Departures Blvd & LT W Exit (Design) | 2020 | Grnd Trans | 500 | 500 | 450 | 0 | 0 | 0 | 400 | 0 | 0 | 0 | 0 | 0 | 0 | 100 | 0 | 500 |
| Rnwy 5/23 Outer Pavement Mill & Overlay (Design) | 2020 | Airfield | 250 | 250 | 225 | 0 | 0 | 0 | 200 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 0 | 250 |
| Fire Protection in Departures Basement (Design) | 2020 | Fire | 250 | 250 | 0 | 0 | 0 | 0 | 200 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 0 | 250 |
| Water Main into Departures Tml (Design & Constr) | 2020 | Terminal | 250 | 250 | 225 | 0 | 0 | 0 | 200 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 0 | 250 |
| Field Maintenance High Bay Heating | 2020 | Airfield | 150 | 150 | 135 | 0 | 0 | 0 | 120 | 0 | 0 | 0 | 0 | 0 | 0 | 30 | 0 | 150 |
| Departures Terminal Ticket Lobby Seating | 2020 | Terminal | 100 | 100 | 0 | 0 | 0 | 0 | 80 | 0 | 0 | 0 | 0 | 0 | 0 | 20 | 0 | 100 |
| Field Maintenance Mechanic Truck | 2020 | Airfield | 70 | 70 | 63 | 0 | 0 | 0 | 56 | 0 | 0 | 0 | 0 | 0 | 0 | 14 | 0 | 70 |
| Long Term East Repairs-Departures South (Constr) | 2020 | Grnd Trans | 500 | 500 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 500 | 0 | 500 |
| Garage B & C Repairs (Design & Constr) | 2020 | Grnd Trans | 300 | 300 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 300 | 0 | 300 |
| Fuel Farm Expansion-AvGas for GA, Close old GA Farm | 2020 | Airfield | 750 | 750 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 750 | 750 |
| Concourse Stairwell Refurbishment (Design & Constr) | 2020 | Terminal | 600 | 600 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 600 | 600 |
| Arrivals Terminal & Fire Station Fire Alarm Upgrade | 2020 | Fire | 400 | 400 | 360 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 400 | 400 |

| Project | Fiscal Year | Cost Center | Project Costs | Inflated | 90% Eligibility | Funding Sources | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | AIP Grants | | | State | | Third Party | Authority | | | | | | Total |
| | | | | | | Entitlement | | Discretionary | | | | PFCs | | CFC | General Reserve | | | |
| | | | | | | Passenger | Cargo | | Entitlement | Discretionary | | Pay-Go | GARBs | | GARBs | Direct Expense (a) Amort in Rate Base | Direct Expense (a) Non-rate base | |
| Doors for Departures Main Lobby & Admin Elevator Hall | 2020 | Terminal | 150 | 150 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 150 | 150 |
| Work Station & Server Upgrades/Replacement | 2020 | Terminal | 150 | 150 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 150 | 150 |
| Concourse Digital Message Signs | 2020 | Terminal | 120 | 120 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 120 | 120 |
| Parking Lot South Generator - Replacement | 2020 | Grnd Trans | 80 | 80 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 0 | 80 |
| Conference Room IT Upgrades | 2020 | Terminal | 80 | 80 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 80 |
| Fire Department & Field Maintenance Bunk Area Study | 2020 | Fire | 60 | 60 | 54 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 60 | 60 |
| Human Resources Information System | 2020 | Admin | 130 | 130 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 130 | 0 | 130 |
| Janitorial Department Ride On Floor Equipment | 2020 | Terminal | 50 | 50 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 50 |
| Txwy C South Reconstruct & Txwy V Rehab (Constr) | 2021 | Airfield | 11,000 | 11,000 | 9,900 | 9,900 | 0 | 0 | 1,100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11,000 |
| Rnwy 5/23 Standardization - Design | 2021 | Airfield | 3,000 | 3,000 | 2,700 | 2,700 | 0 | 0 | 300 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3,000 |
| Closure of Rnwy 14/32-Environ Study & Design | 2021 | Airfield | 300 | 300 | 270 | 270 | 0 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 300 |
| West Airfield Txwy Impr (North/South)-Prelim P&D | 2021 | Airfield | 1,750 | 1,750 | 1,575 | 1,575 | 0 | 0 | 175 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,750 |
| Intersection Impr-Departures Blvd & LT W Exit (Constr) | 2021 | Grnd Trans | 6,000 | 6,000 | 5,400 | 0 | 0 | 0 | 4,800 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,200 | 6,000 |
| Rnwy 5/23 Outer Pavement Mill & Overlay (Constr) | 2021 | Airfield | 3,500 | 3,500 | 3,150 | 0 | 0 | 0 | 2,275 | 383 | 0 | 0 | 0 | 0 | 0 | 842 | 0 | 3,500 |
| Fire Protection in Departures Basement (Constr) | 2021 | Fire | 600 | 600 | 0 | 0 | 0 | 0 | 480 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 120 | 600 |
| Ticket Lobby Improvements (Constr) | 2021 | Terminal | 4,000 | 4,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4,000 | 0 | 4,000 |
| Interior Wayfinding Impr (Constr) | 2021 | Terminal | 2,000 | 2,000 | 0 | 0 | 0 | 0 | 1,600 | 0 | 0 | 0 | 0 | 0 | 0 | 400 | 0 | 2,000 |
| ARFF & SRE Sleeping Quarters Impr (Design & Constr) | 2021 | Fire | 1,000 | 1,000 | 900 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,000 | 1,000 |
| Garage A, B, C Rehabilitation (Design & Constr) | 2021 | Grnd Trans | 10,000 | 10,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 10,000 | 0 | 0 | 10,000 |
| Corporate Hangar (Constr) | 2021 | Other | 3,000 | 3,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3,000 | 0 | 0 | 3,000 |

| Project | Fiscal Year | Cost Center | Project Costs | Inflated | 90% Eligibility | Funding Sources | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | AIP Grants | | | State | | Third Party | Authority | | | | | | Total |
| | | | | | | Entitlement | | Discretionary | Entitlement | Discretionary | | PFCs | | CFC | General Reserve | | | |
| | | | | | | Passenger | Cargo | | | | | Pay-Go | GARBs | | GARBs | Direct Expense (a) Amort in Rate Base | Direct Expense (a) Non-rate base | |
| Design Development for Departures Terminal (Design) | 2021 | Terminal | 1,000 | 1,000 | 0 | 900 | 0 | 0 | 100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,000 |
| Arrivals North Stair Tower Elevator (Constr) | 2021 | Terminal | 750 | 750 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 167 | 0 | 583 | 0 | 750 |
| Arrivals Terminal Restrooms (Constr) | 2021 | Terminal | 2,500 | 2,500 | 0 | 0 | 0 | 0 | 2,000 | 0 | 0 | 0 | 0 | 0 | 0 | 500 | 0 | 2,500 |
| Rnwy 5/23 Standardization-Constr Ph 1 | 2022 | Airfield | 30,000 | 30,000 | 27,000 | 5,000 | 0 | 10,000 | 2,000 | 5,000 | 0 | 3,400 | 0 | 0 | 0 | 4,600 | 0 | 30,000 |
| Closure of Rnwy 14/32 (Design) | 2022 | Airfield | 1,500 | 1,500 | 1,350 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,500 | 0 | 1,500 |
| Misc Airside & Landside Maintenance & Equipment | 2022 | Admin | 3,000 | 3,000 | 2,700 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3,000 | 0 | 3,000 |
| Txwy C Mid-Field South Txwy A to B (Design & Constr) | 2022 | Airfield | 18,000 | 18,000 | 16,200 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 18,000 | 0 | 0 | 0 | 0 | 18,000 |
| Rnwy 5/23 Standardization-Constr Ph 2 | 2023 | Airfield | 40,000 | 40,000 | 36,000 | 5,000 | 0 | 10,000 | 2,000 | 5,000 | 0 | 8,000 | 10,000 | 0 | 0 | 0 | 0 | 40,000 |
| Closure of Rnwy 14/32 (Constr) | 2023 | Airfield | 7,500 | 7,500 | 6,750 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 7,500 | 0 | 0 | 0 | 0 | 7,500 |
| Txwy C Mid-Field North Txwy B E (Design & Constr) | 2023 | Airfield | 13,000 | 13,000 | 11,700 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13,000 | 0 | 0 | 0 | 0 | 13,000 |
| Misc Airside & Landside Maintenance & Equipment | 2023 | Admin | 3,000 | 3,000 | 2,700 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3,000 | 0 | 3,000 |
| **Total PAL 1 (2020-2023)** | | | **$176,935** | **$176,935** | **$134,843** | **$30,318** | **$0** | **$20,000** | **$18,725** | **$10,383** | **$0** | **$11,400** | **$48,500** | **$167** | **$13,000** | **$19,763** | **$4,680** | **$176,935** |
| **PAL 2 (2024-2028)** | | | | | | | | | | | | | | | | | | |
| Txwy C North Rehabilitation (Final Design & Constr) | 2024 | Airfield | $3,000 | $3,000 | $2,700 | $2,700 | $0 | $0 | $0 | $0 | $0 | $0 | $0 | $0 | $0 | $300 | $0 | $3,000 |
| Rnwy 5/23 Standardization-Constr Ph 3 | 2024 | Airfield | 30,000 | 30,000 | 27,000 | 5,000 | 0 | 10,000 | 2,000 | 5,000 | 0 | 8,000 | 0 | 0 | 0 | 0 | 0 | 30,000 |
| Misc Airside & Landside Maintenance & Equipment | 2024 | Admin | 2,500 | 2,500 | 2,250 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2,500 | 0 | 2,500 |
| Cargo Apron Improvements | 2025 | Cargo | 31,200 | 31,200 | 28,080 | 0 | 1,540 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 29,660 | 0 | 0 | 31,200 |
| Cargo Facility Expansion | 2025 | Cargo | 26,500 | 26,500 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 26,500 | 0 | 0 | 26,500 |
| Misc Airside & Landside Maintenance & Equipment | 2025 | Admin | 2,500 | 2,500 | 2,250 | 0 | 0 | 0 | 2,000 | 0 | 0 | 0 | 0 | 0 | 0 | 500 | 0 | 2,500 |
| Deicing Apron with Glycol Recovery System | 2026 | Airfield | 39,000 | 39,000 | 35,100 | 5,000 | 0 | 0 | 2,000 | 0 | 0 | 0 | 32,000 | 0 | 0 | 0 | 0 | 39,000 |
| Relocated Fuel Facility | 2026 | Airfield | 40,000 | 40,000 | 0 | 2,000 | 0 | 0 | 0 | 0 | 0 | 0 | 38,000 | 0 | 0 | 0 | 0 | 40,000 |
| Misc Airside & Landside Maintenance & Equipment | 2026 | Admin | 2,500 | 2,500 | 2,250 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2,500 | 0 | 2,500 |
| QTA Facility (Repurpose Employee Lot) | 2027 | Grnd Trans | 12,000 | 12,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12,000 | 0 | 0 | 0 | 12,000 |
| Misc Airside & Landside Maintenance & Equipment | 2027 | Admin | 2,500 | 2,500 | 2,250 | 0 | 0 | 0 | 2,000 | 0 | 0 | 0 | 0 | 0 | 0 | 500 | 0 | 2,500 |

| Project | Fiscal Year | Cost Center | Project Costs | Inflated | 90% Eligibility | Funding Sources | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | AIP Grants | | | State | | Third Party | Authority | | | | | | Total |
| | | | | | | Entitlement | | Discretionary | Entitlement | Discretionary | | PFCs | | CFC | General Reserve | | | |
| | | | | | | Passenger | Cargo | | | | | Pay-Go | GARBs | | GARBs | Direct Expense (a) Amort in Rate Base | Direct Expense (a) Non-rate base | |
| General Aviation Apron Improvements | 2028 | GA | 18,700 | 18,700 | 16,830 | 5,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13,700 | 0 | 0 | 18,700 |
| General Aviation Hangar Construction | 2028 | GA | 22,000 | 22,000 | 0 | 5,000 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 17,000 | 0 | 0 | 22,000 |
| Misc Airside & Landside Maintenance & Equipment | 2028 | Admin | 2,500 | 2,500 | 2,250 | 0 | 0 | 0 | 2,000 | 0 | 0 | 0 | 0 | 0 | 0 | 500 | 0 | 2,500 |
| **Total PAL 2 (2024-2028)** | | | **$234,900** | **$234,900** | **$120,960** | **$24,700** | **$1,540** | **$10,000** | **$10,000** | **$5,000** | **$0** | **$8,000** | **$70,000** | **$12,000** | **$86,860** | **$6,800** | **$0** | **$234,900** |
| **Total PAL 1 and PAL 2** | | | **$411,835** | **$411,835** | **$255,803** | **$55,018** | **$1,540** | **$30,000** | **$28,725** | **$15,383** | **$0** | **$19,400** | **$118,500** | **$12,167** | **$99,860** | **$26,563** | **$4,680** | **$411,835** |
| | | | | | | **$86,557** | | | **$44,108** | | | **$137,900** | | | **$131,104** | | | |

(a) Capital expenditures in the airfield and terminal are included the airline rate base through amortization (see Table 7-12).

Source: DKMG, CHA, project costs

### Table 7-3 – ACIP Funding Sources by Year
### (in 000s)

| Year | Project Costs | Funding Sources | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | AIP Grants | | | State | | Third Party | Authority | | | | | | Total |
| | | | | | | | | PFCs | | CFC | General Reserve | | | |
| | | Entitlement | | Discretionary | Entitlement | Discretionary | | Pay-Go | GARBs | | GARBs | Direct Expense (a) | | |
| | | Passenger | Cargo | | | | | | | | | Amort in Rate Base | Non rate base | |
| **2020** | $10,535.00 | $4,972.50 | $0.00 | $0.00 | $1,864.50 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $1,338.00 | $2,360.00 | $10,535.00 |
| **2021** | $50,400.00 | $15,345.00 | $0.00 | $0.00 | $12,860.00 | $383.00 | $0.00 | $0.00 | $0.00 | $166.67 | $13,000.00 | $6,325.33 | $2,320.00 | $50,400.00 |
| **2022** | $52,500.00 | $5,000.00 | $0.00 | $10,000.00 | $2,000.00 | $5,000.00 | $0.00 | $3,400.00 | $18,000.00 | $0.00 | $0.00 | $9,100.00 | $0.00 | $52,500.00 |
| **2023** | $63,500.00 | $5,000.00 | $0.00 | $10,000.00 | $2,000.00 | $5,000.00 | $0.00 | $8,000.00 | $30,500.00 | $0.00 | $0.00 | $3,000.00 | $0.00 | $63,500.00 |
| **Total PAL 1** | **$176,935.00** | **$30,317.50** | **$0.00** | **$20,000.00** | **$18,724.50** | **$10,383.00** | **$0.00** | **$11,400.00** | **$48,500.00** | **$166.67** | **$13,000.00** | **$19,763.33** | **$4,680.00** | **$176,935.00** |
| **2024** | $35,500.00 | $7,700.00 | $0.00 | $10,000.00 | $2,000.00 | $5,000.00 | $0.00 | $8,000.00 | $0.00 | $0.00 | $0.00 | $2,800.00 | $0.00 | $35,500.00 |
| **2025** | $60,200.00 | $0.00 | $1,539.60 | $0.00 | $2,000.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $56,160.40 | $500.00 | $0.00 | $60,200.00 |
| **2026** | $81,500.00 | $7,000.00 | $0.00 | $0.00 | $2,000.00 | $0.00 | $0.00 | $0.00 | $70,000.00 | $0.00 | $0.00 | $2,500.00 | $0.00 | $81,500.00 |
| **2027** | $14,500.00 | $0.00 | $0.00 | $0.00 | $2,000.00 | $0.00 | $0.00 | $0.00 | $0.00 | $12,000.00 | $0.00 | $500.00 | $0.00 | $14,500.00 |
| **2028** | $43,200.00 | $10,000.00 | $0.00 | $0.00 | $2,000.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $30,700.00 | $500.00 | $0.00 | $43,200.00 |
| **Total PAL 2** | **$234,900.00** | **$24,700.00** | **$1,539.60** | **$10,000.00** | **$10,000.00** | **$5,000.00** | **$0.00** | **$8,000.00** | **$70,000.00** | **$12,000.00** | **$86,860.40** | **$6,800.00** | **$0.00** | **$234,900.00** |
| **Total** | **$411,835.00** | **$55,017.50** | **$1,539.60** | **$30,000.00** | **$28,724.50** | **$15,383.00** | **$0.00** | **$19,400.00** | **$118,500.00** | **$12,166.67** | **$99,860.40** | **$26,563.33** | **$4,680.00** | **$411,835.00** |
| | | **$86,557.10** | | | **$44,107.50** | | | **$137,900.00** | | | **$99,860.40** | **$31,243.33** | | |
| | | | | | | | | | | | **$131,103.73** | | | |

(a) Capital expenditures in the airfield and terminal are included the airline rate base through amortization (see Table 7-12).
Source: DKMG, CHA, 2020.

### Table 7-4 – Application of AIP and State Grants
### (in 000s)

| | Source Table | Total | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| AIP Grants | | | | | | | | | | | |
| Entitlement (a) | 7-5 | $45,930.94 | $4,771.13 | $4,957.08 | $5,068.18 | $5,102.29 | $5,134.68 | $5,145.42 | $5,198.17 | $5,250.80 | $5,303.20 |
| Discretionary | | $30,000.00 | $0.00 | $0.00 | $10,000.00 | $10,000.00 | $10,000.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Cargo (b) | | $1,539.60 | $165.00 | $166.40 | $167.80 | $169.10 | $169.30 | $171.80 | $174.30 | $176.70 | $179.20 |
| **Total AIP grants** | | **$77,470.54** | **$4,936.13** | **$5,123.48** | **$15,235.98** | **$15,271.39** | **$15,303.98** | **$5,317.22** | **$5,372.47** | **$5,427.50** | **$5,482.40** |
| State Grants | | | | | | | | | | | |
| Entitlement (c) | | $28,724.50 | $1,864.50 | $12,860.00 | $2,000.00 | $2,000.00 | $2,000.00 | $2,000.00 | $2,000.00 | $2,000.00 | $2,000.00 |
| Discretionary | | $15,383.00 | $0.00 | $383.00 | $5,000.00 | $5,000.00 | $5,000.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **Total state grants** | | **$44,107.50** | **$1,864.50** | **$13,243.00** | **$7,000.00** | **$7,000.00** | **$7,000.00** | **$2,000.00** | **$2,000.00** | **$2,000.00** | **$2,000.00** |
| **Total available grants** | | **$121,578.04** | **$6,800.63** | **$18,366.48** | **$22,235.98** | **$22,271.39** | **$22,303.98** | **$7,317.22** | **$7,372.47** | **$7,427.50** | **$7,482.40** |
| **Cumulative** | | | | **$25,167.11** | **$47,403.08** | **$69,674.47** | **$91,978.45** | **$99,295.67** | **$106,668.14** | **$114,095.64** | **$121,578.04** |
| **Beginning balance** | | **$13,336.95** | **$13,336.95** | **$13,300.58** | **$3,079.06** | **$3,315.03** | **$3,586.42** | **$1,190.40** | **$4,968.02** | **$3,340.49** | **$8,767.99** |
| **Plus: available grants** | | **$121,578.04** | **$6,800.63** | **$18,366.48** | **$22,235.98** | **$22,271.39** | **$22,303.98** | **$7,317.22** | **$7,372.47** | **$7,427.50** | **$7,482.40** |
| **Less: CIP Funded with AIP grants** | | | | | | | | | | | |
| **Entitlement-passenger** | **7-2** | **(55,017.50)** | **(4,972.50)** | **(15,345.00)** | **(5,000.00)** | **(5,000.00)** | **(7,700.00)** | **0.00** | **(7,000.00)** | **0.00** | **(10,000.00)** |
| **Entitlement-cargo** | **7-2** | **(1,539.60)** | **0.00** | **0.00** | **0.00** | **0.00** | **0.00** | **(1,539.60)** | **0.00** | **0.00** | **0.00** |
| **Discretionary** | **7-2** | **(30,000.00)** | **0.00** | **0.00** | **(10,000.00)** | **(10,000.00)** | **(10,000.00)** | **0.00** | **0.00** | **0.00** | **0.00** |
| **Less: CIP Funded with state grants** | | | | | | | | | | | |
| **Entitlement** | **7-2** | **(28,724.50)** | **(1,864.50)** | **(12,860.00)** | **(2,000.00)** | **(2,000.00)** | **(2,000.00)** | **(2,000.00)** | **(2,000.00)** | **(2,000.00)** | **(2,000.00)** |
| **Discretionary** | **7-2** | **(15,383.00)** | **0.00** | **(383.00)** | **(5,000.00)** | **(5,000.00)** | **(5,000.00)** | **0.00** | **0.00** | **0.00** | **0.00** |
| **Ending balance** | | **4,250.39** | **13,300.58** | **3,079.06** | **3,315.03** | **3,586.42** | **1,190.40** | **4,968.02** | **3,340.49** | **8,767.99** | **4,250.39** |

(a) A two-year lag is assumed to reflect the time needed to compile annual enplanement data and complete the grant application and approval process.
b) In federal fiscal year 2019, the FAA apportioned total entitlements of $3.2 billion, of which 3.5% is allotted for cargo entitlements, or $112 million. This amount is then allocated to airports on a pro-rata basis according to an airport's share of total U.S. cargo landed weight. In federal fiscal year 2017, ORF's cargo landed weight was 0.15% of total U.S. landed weight, therefore, ORF was apportioned $165,000 in cargo entitlements in federal fiscal year 2019. This amount is forecast to increase with the growth in landed weight presented in Table 7-1.
(c) FY 2021 state entitlements are greater than the $2 million maximum due to the reimbursement of past state grants with PFC revenue.
Source: DKMG, CHA, 2020.

### Table 7-5 – Calculation of AIP Entitlements
### (in 000s)

| | Source Table | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Enplanements | 7-1 | 2,038.2 | 2,072.3 | 2,104.7 | 2,115.4 | 2,168.2 | 2,220.8 | 2,273.2 | 2,325.3 | 2,377.0 |
| FAA Formula (a) | | | | | | | | | | |
| $7.80 for 1st 50,000 Enpl | | $390.00 | $390.00 | $390.00 | $390.00 | $390.00 | $390.00 | $390.00 | $390.00 | $390.00 |
| $5.20 for next 50,000 Enpl | | $260.00 | $260.00 | $260.00 | $260.00 | $260.00 | $260.00 | $260.00 | $260.00 | $260.00 |
| $2.60 for next 400,000 Enpl | | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 | $1,040.00 |
| $0.65 for next 500,000 Enpl | | $325.00 | $325.00 | $325.00 | $325.00 | $325.00 | $325.00 | $325.00 | $325.00 | $325.00 |
| $0.50 for the remaining Enpl | | $519.09 | $536.14 | $552.34 | $557.71 | $584.09 | $610.40 | $636.60 | $662.66 | $688.50 |
| Total Calculated Entitlements | | $2,534.09 | $2,551.14 | $2,567.34 | $2,572.71 | $2,599.09 | $2,625.40 | $2,651.60 | $2,677.66 | $2,703.50 |
| **Calculated Entitlement x 2 (b)** | | **$5,068.18** | **$5,102.29** | **$5,134.68** | **$5,145.42** | **$5,198.17** | **$5,250.80** | **$5,303.20** | **$5,355.32** | **$5,406.99** |
| **Entitlements (c)** | | **$4,771.13** | **$4,957.08** | **$5,068.18** | **$5,102.29** | **$5,134.68** | **$5,145.42** | **$5,198.17** | **$5,250.80** | **$5,303.20** |
| **Cumulative** | | | | | **$19,898.67** | **$25,033.35** | **$30,178.77** | **$35,376.94** | **$40,627.74** | **$45,930.94** |

(a) The FAA formula is defined in 49 United States Code § 47114.
(b) In any fiscal year in which the total amount available under 49 United States Code § 48103 is $3.2 billion or more, the amount apportioned to a sponsor shall be increased by doubling the amount that would otherwise be apportioned.
(c) A two-year lag is assumed to reflect the time needed to compile annual enplanement data and complete the grant application and approval process.
Source: DKMG, CHA, 2020.

### Table 7-6 – Application of PFCs
### (in 000s)

| | Source Table | Total | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Enplanements | 7-1 | | 2,038.2 | 2,072.3 | 2,104.7 | 2,115.4 | 2,168.2 | 2,220.8 | 2,273.2 | 2,325.3 | 2,377.0 |
| % of enplanements revenue producing | | | 90.0% | 90.0% | 90.0% | 90.0% | 90.0% | 90.0% | 90.0% | 90.0% | 90.0% |
| Enplanements for PFC | | | 1,834.4 | 1,865.1 | 1,894.2 | 1,903.9 | 1,951.4 | 1,998.7 | 2,045.9 | 2,092.8 | 2,139.3 |
| Net PFC charge (a) | | | 4.39 | 4.39 | 4.39 | 4.39 | 4.39 | 4.39 | 4.39 | 4.39 | 4.39 |
| PFC revenue | | | 8,053.00 | 8,188.00 | 8,316.00 | 8,358.00 | 8,566.00 | 8,774.00 | 8,981.00 | 9,187.00 | 9,391.00 |
| Cumulative | | | | 16,241.00 | 24,557.00 | 32,915.00 | 41,481.00 | 50,255.00 | 59,236.00 | 68,423.00 | 77,814.00 |
| **Balance in PFC Account as of 6/30/18** | | **$14,359.29** | **$14,359.29** | **$0.00** | **$4,818.11** | **$6,317.41** | **$3,258.72** | **$408.03** | **$834.02** | **$1,467.02** | **$2,306.02** |
| **Plus: PFC revenue** | | **$77,814.00** | **$8,053.00** | **$8,188.00** | **$8,316.00** | **$8,358.00** | **$8,566.00** | **$8,774.00** | **$8,981.00** | **$9,187.00** | **$9,391.00** |
| **Less: committed PFCs** | | | | | | | | | | | |
| **PFC App #18-05-C-00-ORF** | **7-2** | **($10,000.00)** | **($10,000.00)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** |
| **PFC App #19-06-C-00-ORF** | **7-2** | **($15,782.18)** | **($12,412.29)** | **($3,369.90)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** |
| **Less: CIP funded with PFC pay-go** | **7-2** | **($19,400.00)** | **$0.00** | **$0.00** | **($3,400.00)** | **($8,000.00)** | **($8,000.00)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** |
| **Less: PFC eligible debt service** | **7-7** | **($43,642.09)** | **$0.00** | **$0.00** | **($3,416.69)** | **($3,416.69)** | **($3,416.69)** | **($8,348.00)** | **($8,348.00)** | **($8,348.00)** | **($8,348.00)** |
| **Ending balance** | | **$3,349.02** | **$0.00** | **$4,818.11** | **$6,317.41** | **$3,258.72** | **$408.03** | **$834.02** | **$1,467.02** | **$2,306.02** | **$3,349.02** |

(a) The PFC formula is defined in 49 United States Code § 40117. PFC of $4.50 less airline collection fee of $0.11.
Source: DKMG, CHA, 2020.

### Table 7-7 – PFC-Eligible Debt Service
### (in 000s)

| Fiscal Year | Source Table | Series 2022 Bonds | | | Series 2025 Bonds | | | Total | | | Cumulative |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Principal | Interest | Total | Principal | Interest | Total | Principal | Interest | Total | |
| **2020** | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **2021** | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **2022** | | $790.55 | $2,626.15 | $3,416.69 | $0.00 | $0.00 | $0.00 | $790.55 | $2,626.15 | $3,416.69 | $3,416.69 |
| **2023** | | $830.07 | $2,586.62 | $3,416.69 | $0.00 | $0.00 | $0.00 | $830.07 | $2,586.62 | $3,416.69 | **$6,833.39** |
| **2024** | | $871.58 | $2,545.12 | $3,416.69 | $0.00 | $0.00 | $0.00 | $871.58 | $2,545.12 | $3,416.69 | $10,250.08 |
| **2025** | | $915.16 | $2,501.54 | $3,416.69 | $1,140.99 | $3,790.32 | $4,931.31 | $2,056.15 | $6,291.85 | $8,348.00 | $18,598.08 |
| **2026** | | $960.91 | $2,455.78 | $3,416.69 | $1,198.04 | $3,733.27 | $4,931.31 | $2,158.96 | $6,189.05 | $8,348.00 | $26,946.08 |
| **2027** | | $1,008.96 | $2,407.73 | $3,416.69 | $1,257.95 | $3,673.36 | $4,931.31 | $2,266.90 | $6,081.10 | $8,348.00 | $35,294.08 |
| **2028** | | $1,059.41 | $2,357.29 | $3,416.69 | $1,320.84 | $3,610.47 | $4,931.31 | $2,380.25 | $5,967.75 | $8,348.00 | **$43,642.09** |
| **Total through PAL 2** | | **$6,436.63** | **$17,480.22** | **$23,916.85** | **$4,917.83** | **$14,807.41** | **$19,725.24** | **$11,354.46** | **$32,287.63** | **$43,642.09** | |
| **Remaining years** | | $46,086.31 | $32,497.62 | $78,583.93 | $70,888.48 | $57,325.56 | $128,214.04 | $116,974.80 | $89,823.18 | $206,797.97 | |
| **Total debt service** | | $52,522.94 | $49,977.84 | $102,500.78 | $75,806.31 | $72,132.97 | $147,939.28 | $128,329.25 | $122,110.81 | $250,440.06 | |
| **Construction fund** | **7-2** | **$48,500.00** | | | **$70,000.00** | | | **$118,500.00** | | | |
| **Par amount** | | **$52,522.94** | | | **$75,806.31** | | | **$128,329.25** | | | |

Source: DKMG, CHA, 2020.

## Table 7-8 – Application of CFCs
## (in 000s)

| | Source Table | Total | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Enplanements | 7-1 | | 2,038.2 | 2,072.3 | 2,104.7 | 2,115.4 | 2,168.2 | 2,220.8 | 2,273.2 | 2,325.3 | 2,377.0 |
| % O&D of enplanements | | | 97.0% | 97.0% | 97.0% | 97.0% | 97.0% | 97.0% | 97.0% | 97.0% | 97.0% |
| Total O&D enplanements | | | $1,977.03 | $2,010.12 | $2,041.54 | $2,051.96 | $2,103.13 | $2,154.18 | $2,205.00 | $2,255.56 | $2,305.68 |
| % visiting passengers (a) | | | $0.37 | $0.37 | $0.37 | $0.37 | $0.37 | $0.37 | $0.37 | $0.37 | $0.37 |
| Total visiting passengers | | | $731.50 | $743.74 | $755.37 | $759.23 | $778.16 | $797.05 | $815.85 | $834.56 | $853.10 |
| Total transactions | | | $384.75 | $391.19 | $397.30 | $399.33 | $409.29 | $419.22 | $429.12 | $438.95 | $448.71 |
| % of visiting passengers renting cars (b) | | | $0.53 | $0.53 | $0.53 | $0.53 | $0.53 | $0.53 | $0.53 | $0.53 | $0.53 |
| Average days per rental | | | $3.86 | $3.86 | $3.86 | $3.86 | $3.86 | $3.86 | $3.86 | $3.86 | $3.86 |
| Transaction days (c) | | | $1,483.30 | $1,508.12 | $1,531.70 | $1,539.52 | $1,577.90 | $1,616.21 | $1,654.34 | $1,692.27 | $1,729.87 |
| CFC per transaction day | | | $2.00 | $2.00 | $2.00 | $2.00 | $2.00 | $2.00 | $2.00 | $2.00 | $2.00 |
| CFC revenue | | | $2,967.00 | $3,016.00 | $3,063.00 | $3,079.00 | $3,156.00 | $3,232.00 | $3,309.00 | $3,384.00 | $3,460.00 |
| Cumulative | | | | $5,983.00 | $9,046.00 | $12,125.00 | $15,281.00 | $18,513.00 | $21,822.00 | $25,206.00 | $28,666.00 |
| **Balance in CFC Account as of 6/30/19** | | **$187.60** | **$187.60** | **$1,969.81** | **$3,618.14** | **$5,283.14** | **$6,584.66** | **$7,946.51** | **$9,367.51** | **$10,849.16** | **$388.65** |
| **Plus: CFC revenue** | | **$28,666.00** | **$2,967.00** | **$3,016.00** | **$3,063.00** | **$3,079.00** | **$3,156.00** | **$3,232.00** | **$3,309.00** | **$3,384.00** | **$3,460.00** |
| **Less: CFC eligible debt service** | | | | | | | | | | | |
| **Series 2019 Bonds** | **7-10** | **($3,430.58)** | **$0.00** | **$0.00** | **($180.00)** | **($542.48)** | **($542.15)** | **($542.00)** | **($541.36)** | **($541.50)** | **($541.09)** |
| **Less: CIP funded with CFC pay-go** | **7-2** | **($12,166.67)** | **$0.00** | **($166.67)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **($12,000.00)** | **$0.00** |
| **Less: rental car operating expenses** | | **($11,268.78)** | **($1,184.78)** | **($1,201.00)** | **($1,218.00)** | **($1,235.00)** | **($1,252.00)** | **($1,269.00)** | **($1,286.00)** | **($1,303.00)** | **($1,320.00)** |
| **Ending balance** | | **$1,987.56** | **$1,969.81** | **$3,618.14** | **$5,283.14** | **$6,584.66** | **$7,946.51** | **$9,367.51** | **$10,849.16** | **$388.65** | **$1,987.56** |

(a) Per Table 3 of Characteristics of Passengers Using Norfolk International Airport 2017, prepared by Bonney & Company.
(b) Based on the average of FY 2016 through FY 2019.
(c) Transaction days are forecasted with enplanement growth.
Source: DKMG, CHA, 2020.

## Table 7-9 – Operating Expenses (in 000s)

| | Actual 2019 | PAL 1 2020 | PAL 1 2021 | PAL 1 2022 | PAL 1 2023 | PAL 2 2024 | PAL 2 2025 | PAL 2 2026 | PAL 2 2027 | PAL 2 2028 |
|---|---|---|---|---|---|---|---|---|---|---|
| **Summary by line item** | | | | | | | | | | |
| Salaries and fringe benefits | $17,041.38 | $17,791.75 | $18,041.00 | $18,293.00 | $18,549.00 | $18,808.00 | $19,071.00 | $19,338.00 | $19,609.00 | $19,882.00 |
| Maintenance and repairs | $2,993.53 | $3,706.40 | $3,758.00 | $3,810.00 | $3,863.00 | $3,917.00 | $3,972.00 | $4,027.00 | $4,083.00 | $4,140.00 |
| Payment to City (a) | $2,500.00 | $2,500.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,800.00 | $2,800.00 | $2,800.00 |
| Other expenses | | | | | | | | | | |
| Security and other services | $3,957.95 | $4,303.76 | $4,363.00 | $4,424.00 | $4,485.00 | $4,547.00 | $4,611.00 | $4,676.00 | $4,742.00 | $4,808.00 |
| Utilities | $2,780.34 | $2,791.22 | $2,829.00 | $2,868.00 | $2,907.00 | $2,947.00 | $2,988.00 | $3,030.00 | $3,073.00 | $3,117.00 |
| Professional services, administrative, advertising, insurance, sanitation, etc. | $4,211.60 | $5,179.58 | $5,251.00 | $5,324.00 | $5,398.00 | $5,472.00 | $5,548.00 | $5,625.00 | $5,705.00 | $5,785.00 |
| Increase due to terminal expansion (b) | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Decommissioning of shuttle buses (c) | $0.00 | $0.00 | $0.00 | ($600.00) | ($608.00) | ($617.00) | ($626.00) | ($635.00) | ($644.00) | ($653.00) |
| **Total Operating Expenses** | **$33,484.81** | **$36,272.71** | **$36,892.00** | **$36,769.00** | **$37,244.00** | **$37,724.00** | **$38,214.00** | **$38,861.00** | **$39,368.00** | **$39,879.00** |
| **Summary by cost center** | | | | | | | | | | |
| Airfield | $2,556.22 | $2,085.20 | $2,114.00 | $2,144.00 | $2,175.00 | $2,206.00 | $2,238.00 | $2,270.00 | $2,302.00 | $2,335.00 |
| Terminal | $4,624.57 | $4,664.50 | $4,730.00 | $4,796.00 | $4,862.00 | $4,930.00 | $4,998.00 | $5,068.00 | $5,139.00 | $5,211.00 |
| Ground Transportation | $6,105.38 | $6,672.14 | $6,765.00 | $6,260.00 | $6,348.00 | $6,436.00 | $6,525.00 | $6,616.00 | $6,710.00 | $6,805.00 |
| Other | $0.00 | $172.56 | $175.00 | $178.00 | $181.00 | $184.00 | $187.00 | $190.00 | $193.00 | $196.00 |
| Total direct | $13,286.17 | $13,594.40 | $13,784.00 | $13,378.00 | $13,566.00 | $13,756.00 | $13,948.00 | $14,144.00 | $14,344.00 | $14,547.00 |
| Maintenance - Field | $1,509.72 | $1,341.25 | $1,360.00 | $1,379.00 | $1,398.00 | $1,417.00 | $1,437.00 | $1,457.00 | $1,477.00 | $1,497.00 |
| Maintenance - Building | $1,581.05 | $1,584.75 | $1,607.00 | $1,630.00 | $1,653.00 | $1,676.00 | $1,700.00 | $1,724.00 | $1,748.00 | $1,773.00 |
| Janitorial | $2,239.28 | $2,343.60 | $2,376.00 | $2,408.00 | $2,441.00 | $2,474.00 | $2,508.00 | $2,543.00 | $2,578.00 | $2,613.00 |
| Police | $5,389.47 | $5,562.14 | $5,640.00 | $5,718.00 | $5,798.00 | $5,880.00 | $5,963.00 | $6,047.00 | $6,132.00 | $6,217.00 |
| Fire | $3,168.76 | $3,054.20 | $3,096.00 | $3,138.00 | $3,180.00 | $3,223.00 | $3,267.00 | $3,312.00 | $3,358.00 | $3,404.00 |
| Administrative | $3,810.35 | $6,292.37 | $6,379.00 | $6,468.00 | $6,558.00 | $6,648.00 | $6,741.00 | $6,834.00 | $6,931.00 | $7,028.00 |
| Payment to City | $2,500.00 | $2,500.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,650.00 | $2,800.00 | $2,800.00 | $2,800.00 |
| Total indirect | $20,198.64 | $22,678.31 | $23,108.00 | $23,391.00 | $23,678.00 | $23,968.00 | $24,266.00 | $24,717.00 | $25,024.00 | $25,332.00 |
| **Total Operating Expenses** | **$33,484.81** | **$36,272.71** | **$36,892.00** | **$36,769.00** | **$37,244.00** | **$37,724.00** | **$38,214.00** | **$38,861.00** | **$39,368.00** | **$39,879.00** |
| **% Change** | | **8.3%** | **1.7%** | **-0.3%** | **1.3%** | **1.3%** | **1.3%** | **1.7%** | **1.3%** | **1.3%** |
| **CAGR from 2020** | | | | | **0.9%** | | | | | **1.2%** |
| **Allocation of indirect for rates & charges** | | | | | | | | | | |
| Airfield | | $5,755.83 | $5,852.56 | $5,958.68 | $6,034.64 | $6,111.58 | $6,191.03 | $6,293.92 | $6,375.81 | $6,457.97 |
| Terminal | | $11,463.85 | $11,646.87 | $11,865.02 | $12,021.96 | $12,180.79 | $12,343.60 | $12,539.18 | $12,706.53 | $12,874.54 |
| Ground Transportation | | $4,855.41 | $4,990.51 | $4,939.94 | $4,987.23 | $5,034.55 | $5,083.23 | $5,220.30 | $5,270.86 | $5,321.50 |
| Other | | $603.22 | $618.06 | $627.36 | $634.17 | $641.08 | $648.14 | $663.60 | $670.80 | $677.98 |
| **Total indirect** | | **$22,678.31** | **$23,108.00** | **$23,391.00** | **$23,678.00** | **$23,968.00** | **$24,266.00** | **$24,717.00** | **$25,024.00** | **$25,332.00** |

(a) Increases in the City Payment of $150,000 every five years based on the Authority's agreement with the City. This agreement expires in 2024; however, this analysis assumes that the City Payments will continue and increase per the existing agreement.
(b) Operating expenses are projected to increase in PAL 3 and PAL 4 to account for the maintenance and operation of the new and expanded terminal facilities.
(c) A reduction of $600,000 in 2022 to reflect the decommissioning of the employee parking lot shuttle buses since the employees will be parking in the garages upon parking garage D's completion.
Sources: Authority's Basic Financial Statements for FY ended June 30, 2019, Authority's budget for FY 2020, DKMG Consulting LLC (FY 2021 - FY 2038), CHA, 2020.

## Table 7-10 – Outstanding Debt Service Requirement
## (in 000s)

| | Actual | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | 2019 | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Series 2011A | $2,120.93 | $2,127.85 | $2,119.53 | $2,117.90 | $2,124.20 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Series 2011B (a) | $893.21 | $891.28 | $891.51 | $899.34 | $899.51 | $876.60 | $871.48 | $605.49 | $0.00 | $0.00 |
| Series 2011C | $1,204.59 | $1,204.59 | $1,204.59 | $1,204.59 | $1,204.59 | $3,520.21 | $3,513.59 | $3,510.96 | $3,506.96 | $3,517.03 |
| Series 2019 Bonds (b) | $0.00 | $0.00 | $0.00 | $1,360.88 | $4,101.38 | $4,098.88 | $4,097.75 | $4,092.88 | $4,094.00 | $4,090.88 |
| **Total Debt Service** | **$4,218.73** | **$4,223.72** | **$4,215.63** | **$5,582.70** | **$8,329.68** | **$8,495.69** | **$8,482.81** | **$8,209.33** | **$7,600.96** | **$7,607.91** |
| | | | | | | | | | | |
| **Summary by funding source** | | | | | | | | | | |
| Summary for debt service coverage (c) | | | | | | | | | | |
| Authority funded | $3,102.49 | $4,223.72 | $4,215.63 | $5,402.70 | $7,787.20 | $7,953.54 | $7,940.81 | $7,667.97 | $7,059.46 | $7,066.82 |
| CFC eligible | $0.00 | $0.00 | $0.00 | $180.00 | $542.48 | $542.15 | $542.00 | $541.36 | $541.50 | $541.09 |
| PFC eligible | | | | | | | | | | |
| Series 2019 Bonds (d) | $1,116.24 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **Total** | **$4,218.73** | **$4,223.72** | **$4,215.63** | **$5,582.70** | **$8,329.68** | **$8,495.69** | **$8,482.81** | **$8,209.33** | **$7,600.96** | **$7,607.91** |
| Summary for airline rates and charges (c) | | | | | | | | | | |
| Authority funded | | | | | | | | | | |
| Airfield | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Terminal | $1,444.42 | $1,457.80 | $1,489.11 | $1,491.21 | $1,504.75 | $1,499.87 | $1,228.95 | $607.85 | $608.32 | $608.72 |
| Ground transportation | $1,713.39 | $2,820.59 | $2,798.75 | $6,756.33 | $6,564.58 | $6,562.55 | $6,560.11 | $6,563.38 | $6,564.52 | $6,566.66 |
| CFC eligible | $0.00 | $0.00 | $0.00 | $180.00 | $542.48 | $542.15 | $542.00 | $541.36 | $541.50 | $541.09 |
| PFC eligible | $1,116.24 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **Total** | **$4,274.05** | **$4,278.39** | **$4,287.86** | **$8,427.54** | **$8,611.81** | **$8,604.56** | **$8,331.06** | **$7,712.59** | **$7,714.34** | **$7,716.48** |

(a) A portion of the Series 2011B Bond debt service is PFC eligible and was approved in PFC Application #2.
(b) The Series 2019 Bond Debt Service is shown net of capitalized interest.
(c) For the calculation of debt service coverage, the principal and interest payments are the sum of July of the prior calendar year and January of the current calendar year. For the calculation of airline rate and charges, the principal and interest payments are the sum of January and July of the current year.
(d) The maximum PFC eligibility for PFC Application #2 was reached for the Series 2011B Bonds through the PFC contribution made in FY 2019. Since no PFC contributions were made in FY 2018, the remaining PFC eligibility amount applied in FY 2019 to achieve full eligibility was greater than the Series 2011B Bond debt service payment for that year.
Source: Authority records, DKMG, CHA, 2020.

### Table 7-11 – Future Debt Service Requirement
### (in 000s)

| Fiscal Year | Source Table | Series 2021 Bonds | | | Series 2025 Bonds | | | Total | | | Allocation to Cost Centers | | | | | | | Cumulative |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Principal | Interest (a) | Total | Principal | Interest (a) | Total | Principal | Interest (a) | Total | Airfield | Terminal | Ground Trans | Other | Cargo | General Aviation | Total | |
| **2020** | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **2021** | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **2022** | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| **2023** | | $270.32 | $765.02 | $1,035.34 | $0.00 | $0.00 | $0.00 | $270.32 | $765.02 | $1,035.34 | $0.00 | $0.00 | $796.42 | $238.92 | $0.00 | $0.00 | $1,035.34 | **$1,035.34** |
| **2024** | | $283.84 | $751.92 | $1,035.76 | $0.00 | $0.00 | $0.00 | $283.84 | $751.92 | $1,035.76 | $0.00 | $0.00 | $796.74 | $239.02 | $0.00 | $0.00 | $1,035.76 | $2,071.10 |
| **2025** | | $298.03 | $738.17 | $1,036.20 | $0.00 | $0.00 | $0.00 | $298.03 | $738.17 | $1,036.20 | $0.00 | $0.00 | $797.07 | $239.12 | $0.00 | $0.00 | $1,036.20 | $3,107.30 |
| **2026** | | $312.93 | $723.72 | $1,036.66 | $0.00 | $0.00 | $0.00 | $312.93 | $723.72 | $1,036.66 | $0.00 | $0.00 | $797.43 | $239.23 | $0.00 | $0.00 | $1,036.66 | $4,143.95 |
| **2027** | | $328.58 | $708.56 | $1,037.14 | $1,806.18 | $5,111.53 | $6,917.70 | $2,134.75 | $5,820.09 | $7,954.84 | $0.00 | $0.00 | $797.80 | $239.34 | $4,472.71 | $2,445.00 | $7,954.84 | $12,098.79 |
| **2028** | | $345.01 | $692.64 | $1,037.65 | $1,896.48 | $5,024.01 | $6,920.49 | $2,241.49 | $5,716.64 | $7,958.14 | $0.00 | $0.00 | $798.19 | $239.46 | $4,474.51 | $2,445.98 | $7,958.14 | **$20,056.93** |
| **Total through PAL 2** | | **1,838.71** | **4,380.03** | **6,218.74** | **3,702.66** | **10,135.53** | **13,838.19** | **5,541.37** | **14,515.56** | **20,056.93** | **0.00** | **0.00** | **4,783.64** | **1,435.09** | **8,947.21** | **4,890.98** | **20,056.93** | |
| **Remaining years** | | 13,948.80 | 9,075.60 | 23,024.40 | 101,782.68 | 79,769.16 | 181,551.85 | 115,731.49 | 88,844.76 | 204,576.25 | 0.00 | 0.00 | 17,711.08 | 5,313.32 | 117,384.04 | 64,167.81 | 204,576.25 | |
| **Total debt service** | | 15,787.51 | 13,455.63 | 29,243.14 | 105,485.34 | 89,904.70 | 195,390.04 | 121,272.85 | 103,360.32 | 224,633.18 | 0.00 | 0.00 | 22,494.72 | 6,748.42 | 126,331.25 | 69,058.79 | 224,633.18 | |
| **Construction fund** | **7-2** | **13,000.00** | | | **86,860.40** | | | **99,860.40** | | | | | | | | | | |
| **Par amount** | | **15,787.51** | | | **105,485.34** | | | **121,272.85** | | | | | | | | | | |

(a) Net of capitalized interest.
Source: DKMG, CHA, 2020.

### Table 7-12 – Capital Improvement Amortization
### (in 000s)

| | Source Table | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| **CIP to be Amortized** | | | | | | | | | | |
| **Project costs** | **7-2** | **$1,338.00** | **$6,325.33** | **$9,100.00** | **$3,000.00** | **$2,800.00** | **$500.00** | **$2,500.00** | **$500.00** | **$500.00** |
| **Cumulative** | **7-2** | | | | **$19,763.33** | | | | | **$6,800.00** |
| **Amortization** | | | | | | | | | | |
| Prior year amortization | | $1,391.39 | $1,253.35 | $1,129.68 | $1,053.94 | $1,040.85 | $865.80 | $817.83 | $808.13 | $793.85 |
| CIP amortization (a) | | $0.00 | $0.00 | $156.85 | $898.38 | $1,965.17 | $2,316.87 | $2,645.11 | $2,703.73 | $2,996.80 |
| **Total amortization** | | **$1,391.39** | **$1,253.35** | **$1,286.53** | **$1,952.32** | **$3,006.02** | **$3,182.66** | **$3,462.94** | **$3,511.86** | **$3,790.65** |
| **Amortization by cost center** | | | | | | | | | | |
| Direct cost centers | | | | | | | | | | |
| Airfield | | $164.59 | $127.66 | $148.57 | $234.62 | $1,060.84 | $1,148.20 | $1,238.16 | $1,249.75 | $1,333.16 |
| Terminal | | $884.45 | $799.95 | $814.41 | $1,394.15 | $1,504.40 | $1,492.60 | $1,587.76 | $1,605.55 | $1,703.24 |
| Ground Transportation | | $339.55 | $322.95 | $320.77 | $320.77 | $438.00 | $541.86 | $637.02 | $656.56 | $754.25 |
| Other | | $2.79 | $2.79 | $2.79 | $2.79 | $2.79 | $0.00 | $0.00 | $0.00 | $0.00 |
| **Total amortization** | | **$1,391.39** | **$1,253.35** | **$1,286.53** | **$1,952.32** | **$3,006.02** | **$3,182.66** | **$3,462.94** | **$3,511.86** | **$3,790.65** |
| **% Change** | | | **-9.9%** | **2.6%** | **51.8%** | **54.0%** | **5.9%** | **8.8%** | **1.4%** | **7.9%** |

(a) Amortization begins when project is placed into service, which is assumed to be two years after the project start date. The projects are amortized over their useful life at 3%, reflecting the Revenue Bond Index as of January 30, 2020 rounded up.
Source: Autohrity's budget for FY 2020

## Table 7-13 – Airline Rates and Charges

| | Source Table | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| **Landing Fee Rate** | | | | | | | | | | |
| Operating Expenses | | | | | | | | | | |
| Direct | 7-9 | $2,085.20 | $2,114.00 | $2,144.00 | $2,175.00 | $2,206.00 | $2,238.00 | $2,270.00 | $2,302.00 | $2,335.00 |
| Indirect | 7-9 | $5,755.83 | $5,852.56 | $5,958.68 | $6,034.64 | $6,111.58 | $6,191.03 | $6,293.92 | $6,375.81 | $6,457.97 |
| Debt Service Requirement | | | | | | | | | | |
| Outstanding | 7-10 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Future | 7-11 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Amortization | 7-12 | $164.59 | $127.66 | $148.57 | $234.62 | $1,060.84 | $1,148.20 | $1,238.16 | $1,249.75 | $1,333.16 |
| Total requirement | | $8,005.62 | $8,094.22 | $8,251.24 | $8,444.26 | $9,378.42 | $9,577.23 | $9,802.09 | $9,927.57 | $10,126.14 |
| Landed weight | 7-1 | $2,551.35 | $2,572.60 | $2,594.11 | $2,614.22 | $2,617.39 | $2,656.00 | $2,694.35 | $2,732.21 | $2,770.53 |
| **Signatory landing fee rate** | | **$3.14** | **$3.15** | **$3.18** | **$3.23** | **$3.58** | **$3.61** | **$3.64** | **$3.63** | **$3.65** |
| Non-signatory landing fee rate | | $3.92 | $3.93 | $3.98 | $4.04 | $4.48 | $4.51 | $4.55 | $4.54 | $4.57 |
| Landing fee revenue | | | | | | | | | | |
| Signatory | | $6,643.03 | $6,716.55 | $6,846.85 | $7,007.01 | $7,782.17 | $7,947.14 | $8,133.73 | $8,237.85 | $8,402.63 |
| Cargo and non-signatory | | $1,061.27 | $1,377.67 | $1,404.40 | $1,437.25 | $1,596.25 | $1,630.09 | $1,668.36 | $1,689.72 | $1,723.51 |
| Total landing fee revenue | | $7,704.30 | $8,094.22 | $8,251.24 | $8,444.26 | $9,378.42 | $9,577.23 | $9,802.09 | $9,927.57 | $10,126.14 |
| **Terminal Rental Rate** | | | | | | | | | | |
| Operating Expenses | | | | | | | | | | |
| Direct | 7-9 | $4,664.50 | $4,730.00 | $4,796.00 | $4,862.00 | $4,930.00 | $4,998.00 | $5,068.00 | $5,139.00 | $5,211.00 |
| Indirect | 7-9 | $11,463.85 | $11,646.87 | $11,865.02 | $12,021.96 | $12,180.79 | $12,343.60 | $12,539.18 | $12,706.53 | $12,874.54 |
| Debt Service Requirement | | | | | | | | | | |
| Outstanding | 7-10 | $1,457.80 | $1,489.11 | $1,491.21 | $1,504.75 | $1,499.87 | $1,228.95 | $607.85 | $608.32 | $608.72 |
| Future | 7-11 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Amortization | | $884.45 | $799.95 | $814.41 | $1,394.15 | $1,504.40 | $1,492.60 | $1,587.76 | $1,605.55 | $1,703.24 |
| Less telephone reimbursements | 7-14 | ($40.00) | ($41.00) | ($42.00) | ($43.00) | ($44.00) | ($45.00) | ($46.00) | ($47.00) | ($48.00) |
| Net requirement | | $18,430.60 | $18,624.94 | $18,924.64 | $19,739.86 | $20,071.06 | $20,018.15 | $19,756.79 | $20,012.39 | $20,349.50 |
| Total useable terminal space | | $485.89 | $485.89 | $485.89 | $485.89 | $485.89 | $485.89 | $485.89 | $485.89 | $485.89 |
| **Terminal Rental Rate** | | **$37.93** | **$38.33** | **$38.95** | **$40.63** | **$41.31** | **$41.20** | **$40.66** | **$41.19** | **$41.88** |
| Airline leased space | | $125.45 | $125.45 | $125.45 | $125.45 | $125.45 | $125.45 | $125.45 | $125.45 | $125.45 |
| Terminal rental revenue | | $4,758.48 | $4,808.65 | $4,886.03 | $5,096.51 | $5,182.01 | $5,168.36 | $5,100.88 | $5,166.87 | $5,253.90 |
| **Airline cost per enplanement** | | | | | | | | | | |
| Landing fee revenue | | $6,643.03 | $6,716.55 | $6,846.85 | $7,007.01 | $7,782.17 | $7,947.14 | $8,133.73 | $8,237.85 | $8,402.63 |
| Terminal rental revenue | | $4,758.48 | $4,808.65 | $4,886.03 | $5,096.51 | $5,182.01 | $5,168.36 | $5,100.88 | $5,166.87 | $5,253.90 |
| Telephone reimbursement | 7-14 | $40.00 | $41.00 | $42.00 | $43.00 | $44.00 | $45.00 | $46.00 | $47.00 | $48.00 |
| Less: airline's share of surplus revenue | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Total | | $11,441.51 | $11,566.20 | $11,774.87 | $12,146.52 | $13,008.19 | $13,160.50 | $13,280.60 | $13,451.72 | $13,704.53 |
| Enplaned passengers | 7-1 | $2,038.18 | $2,072.29 | $2,104.68 | $2,115.42 | $2,168.17 | $2,220.80 | $2,273.20 | $2,325.32 | $2,376.99 |
| **Airline cost per enplaned passengers** | | **$5.61** | **$5.58** | **$5.59** | **$5.74** | **$6.00** | **$5.93** | **$5.84** | **$5.78** | **$5.77** |

(a) Reflects the years when future debt service comes online.
Source: DKMG, CHA, 2020

## Table 7-14 – Operating Revenues (in 000s)

| | Source Table | Actual 2019 | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Parking | | | | | | | | | | | |
| Public parking | | $16,689.3 | $17,950.0 | $18,250.0 | $18,535.0 | $18,630.0 | $19,095.0 | $19,559.0 | $20,020.0 | $20,479.0 | $20,934.0 |
| Employee & limo parking (a) | | $237.8 | $234.5 | $238.0 | $361.5 | $367.0 | $372.0 | $377.0 | $382.0 | $387.0 | $392.0 |
| Additional parking revenues | | | | | | | | | | | |
| Due to enhanced parking amenities (b) | | $0.0 | $0.0 | $0.0 | $232.8 | $234.0 | $240.0 | $246.0 | $252.0 | $258.0 | $264.0 |
| Due to rate increase (c) | | $0.0 | $0.0 | $0.0 | $2,605.0 | $2,618.0 | $2,683.0 | $2,749.0 | $2,813.0 | $5,755.0 | $5,883.0 |
| Total parking | | $16,927.1 | $18,184.5 | $18,488.0 | $21,734.3 | $21,849.0 | $22,390.0 | $22,931.0 | $23,467.0 | $26,879.0 | $27,473.0 |
| % Change | | | 7.4% | 1.7% | 17.6% | 0.5% | 2.5% | 2.4% | 2.3% | 14.5% | 2.2% |
| Landing fees | | $6,175.57 | $7,704.30 | $8,094.22 | $8,251.24 | $8,444.26 | $9,378.42 | $9,577.23 | $9,802.09 | $9,927.57 | $10,126.14 |
| % Change | | | 24.8% | 5.1% | 1.9% | 2.3% | 11.1% | 2.1% | 2.3% | 1.3% | 2.0% |
| Rent | | | | | | | | | | | |
| Airline space rent | | $3,767.61 | $4,758.48 | $4,808.65 | $4,886.03 | $5,096.51 | $5,182.01 | $5,168.36 | $5,100.88 | $5,166.87 | $5,253.90 |
| Building rent | | $1,133.71 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 | $1,165.72 |
| Fuel farm rent | | $278.28 | $300.00 | $304.20 | $308.50 | $312.80 | $317.20 | $321.60 | $326.10 | $330.70 | $335.30 |
| Air cargo terminal | | $232.16 | $210.00 | $213.00 | $216.00 | $219.00 | $222.00 | $225.00 | $228.00 | $231.00 | $234.00 |
| Passenger loading bridge loan | | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 | $106.04 |
| Common use gates | | $0.00 | $100.00 | $100.00 | $100.00 | $100.00 | $100.00 | $100.00 | $100.00 | $100.00 | $100.00 |
| Other | | $859.99 | $839.70 | $852.00 | $863.00 | $875.00 | $887.00 | $899.00 | $911.00 | $923.00 | $935.00 |
| Increase due to new cargo building rentals (d) | 7-11 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $4,472.71 | $4,474.51 |
| Increase due to new GA hangar rentals (d) | 7-11 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $2,445.00 | $2,445.98 |
| Total rent | | $6,377.79 | $7,479.93 | $7,549.61 | $7,645.29 | $7,875.06 | $7,979.97 | $7,985.71 | $7,937.73 | $14,941.03 | $15,050.45 |
| % Change | | | 17.3% | 0.9% | 1.3% | 3.0% | 1.3% | 0.1% | -0.6% | 88.2% | 0.7% |
| Rental car | | $7,246.77 | $7,000.00 | $7,098.00 | $7,197.00 | $7,298.00 | $7,400.00 | $7,504.00 | $7,609.00 | $7,716.00 | $7,824.00 |
| % Change | | | -3.4% | 1.4% | 1.4% | 1.4% | 1.4% | 1.4% | 1.4% | 1.4% | 1.4% |
| Concessions | | | | | | | | | | | |
| Food services | | $1,468.55 | $1,800.00 | $1,830.00 | $1,859.00 | $1,868.00 | $1,915.00 | $1,961.00 | $2,007.00 | $2,053.00 | $2,099.00 |
| Newsstand | | $1,107.74 | $950.00 | $966.00 | $981.00 | $986.00 | $1,011.00 | $1,036.00 | $1,060.00 | $1,084.00 | $1,108.00 |
| Fixed base operator | | $360.84 | $330.00 | $335.00 | $340.00 | $345.00 | $350.00 | $355.00 | $360.00 | $365.00 | $370.00 |
| Advertising | | $233.82 | $250.00 | $254.00 | $258.00 | $259.00 | $265.00 | $271.00 | $277.00 | $283.00 | $289.00 |
| Catering | | $103.85 | $115.00 | $117.00 | $119.00 | $120.00 | $123.00 | $126.00 | $129.00 | $132.00 | $135.00 |
| Other | | $55.17 | $53.00 | $54.00 | $55.00 | $55.00 | $56.00 | $57.00 | $58.00 | $59.00 | $60.00 |
| Increase due to new concession space (e) | | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Total concessions | | $3,329.96 | $3,498.00 | $3,556.00 | $3,612.00 | $3,633.00 | $3,720.00 | $3,806.00 | $3,891.00 | $3,976.00 | $4,061.00 |
| % Change | | | 5.0% | 1.7% | 1.6% | 0.6% | 2.4% | 2.3% | 2.2% | 2.2% | 2.1% |
| Other | | | | | | | | | | | |
| Ground transportation revenues | | $937.89 | $855.00 | $868.00 | $881.00 | $885.00 | $906.00 | $927.00 | $948.00 | $968.00 | $988.00 |
| Reimbursements - telephones | | $38.88 | $40.00 | $41.00 | $42.00 | $43.00 | $44.00 | $45.00 | $46.00 | $47.00 | $48.00 |
| Other | | $187.08 | $44.00 | $45.00 | $46.00 | $47.00 | $48.00 | $49.00 | $50.00 | $51.00 | $52.00 |
| Total other | | $1,163.85 | $939.00 | $954.00 | $969.00 | $975.00 | $998.00 | $1,021.00 | $1,044.00 | $1,066.00 | $1,088.00 |
| % Change | | | -19.3% | 1.6% | 1.6% | 0.6% | 2.4% | 2.3% | 2.3% | 2.1% | 2.1% |
| **Total operating revenue** | | **$41,221.03** | **$44,805.73** | **$45,739.83** | **$49,408.83** | **$50,074.32** | **$51,866.39** | **$52,824.94** | **$53,750.82** | **$64,505.60** | **$65,622.59** |
| **% Change** | | | **8.7%** | **2.1%** | **8.0%** | **1.3%** | **3.6%** | **1.8%** | **1.8%** | **20.0%** | **1.7%** |
| **CAGR from 2020** | | | | | | **3.8%** | | | | | **4.9%** |

(a) The employee parking monthly fee is estimated to increase from $20 per month to $30 in FY 2022 since the employees will be parking in a garage instead of the surface lot.
(b) Once the Parking Garage D is complete, the Authority intends on instituting premium parking programs that could potentially increase parking revenues. Also, there will be a slight increase in available parking spaces that may increase revenues. After 2022, additional parking revenues are forecasted to grow with enplanements.
(c) Assumes a $1.00 rate increase in FY 2022 to coincide with the completion of parking garage D and then every five years thereafter.
(d) Air cargo and general aviation terminal rentals are increased in FY 2027 to reflect additional rent anticipated once the new facilities are complete. The revenue increase is equal to the debt service required to fund those facilities.
(e) Increased concession revenues due to the new concession space resulting from the terminal expansion.
Sources: Authority's Basic Financial Statements for FY ended June 30, 2019, Authority's budget for FY 2020, DKMG Consulting LLC (FY 2021 - FY 2038), CHA, 2020.

### Table 7-15 – Pro Forma Cash Flow
### (in 000s)

| | Source Table | Total | Actual 2019 | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| Operating revenues | 7-14 | | $41,221.03 | $44,805.73 | $45,739.83 | $49,408.83 | $50,074.32 | $51,866.39 | $52,824.94 | $53,750.82 | $64,505.60 | $65,622.59 |
| Non-operating revenues | | | $6,213.98 | $5,753.50 | $5,805.00 | $5,854.00 | $5,872.00 | $5,951.00 | $6,029.00 | $6,108.00 | $6,185.00 | $6,263.00 |
| General Revenues | | | $47,435.02 | $50,559.23 | $51,544.83 | $55,262.83 | $55,946.32 | $57,817.39 | $58,853.94 | $59,858.82 | $70,690.60 | $71,885.59 |
| Less: Operating Expenses | 7-9 | | ($33,484.81) | ($36,272.71) | ($36,892.00) | ($36,769.00) | ($37,244.00) | ($37,724.00) | ($38,214.00) | ($38,861.00) | ($39,368.00) | ($39,879.00) |
| Net Revenues | | | $13,950.21 | $14,286.52 | $14,652.83 | $18,493.83 | $18,702.32 | $20,093.39 | $20,639.94 | $20,997.82 | $31,322.60 | $32,006.59 |
| Less: Debt Service Requirement | 7-10 | | | | | | | | | | | |
| Outstanding debt service | | | ($4,218.73) | ($4,223.72) | ($4,215.63) | ($5,582.70) | ($8,329.68) | ($8,495.69) | ($8,482.81) | ($8,209.33) | ($7,600.96) | ($7,607.91) |
| Plus: PFC-eligible debt service | | | $1,116.24 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Future debt service | | | $0.00 | $0.00 | $0.00 | $0.00 | ($1,035.34) | ($1,035.76) | ($1,036.20) | ($1,036.66) | ($7,954.84) | ($7,958.14) |
| Total Debt Service Requirement | | | ($3,102.49) | ($4,223.72) | ($4,215.63) | ($5,582.70) | ($9,365.02) | ($9,531.45) | ($9,519.01) | ($9,245.98) | ($15,555.80) | ($15,566.04) |
| Less: VRA Loan Payments (a) | | | ($92.29) | ($92.29) | ($15.38) | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 | $0.00 |
| Transfer to the General Reserve Fund | | | $10,755.43 | $9,970.52 | $10,421.82 | $12,911.13 | $9,337.31 | $10,561.95 | $11,120.93 | $11,751.84 | $15,766.79 | $16,440.55 |
| Cumulative | | | | | $20,392.34 | $33,303.47 | $42,640.77 | $53,202.72 | $64,323.65 | $76,075.49 | $91,842.28 | $108,282.83 |
| **General Reserve Fund** | | | | | | | | | | | | |
| **Beginning balance (balance as of 6/30/19)** | | **$26,973.42** | | **$26,973.42** | **$30,818.50** | **$30,594.98** | **$32,406.11** | **$36,743.42** | **$42,505.37** | **$51,126.30** | **$58,378.14** | **$71,644.93** |
| **Plus: Transfer from the Revenue Fund** | | **$108,282.83** | | **$9,970.52** | **$10,421.82** | **$12,911.13** | **$9,337.31** | **$10,561.95** | **$11,120.93** | **$11,751.84** | **$15,766.79** | **$16,440.55** |
| **Less: Authority funded CIP** | | | | | | | | | | | | |
| **Amortized in the rate base** | **7-2** | **($26,563.33)** | | **($1,338.00)** | **($6,325.33)** | **($9,100.00)** | **($3,000.00)** | **($2,800.00)** | **($500.00)** | **($2,500.00)** | **($500.00)** | **($500.00)** |
| **Non-rate base** | **7-2** | **($4,680.00)** | | **($2,360.00)** | **($2,320.00)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** |
| **Less: transfer to State Grant fund** | | | | | | | | | | | | |
| **Annual amount** | | **($18,000.00)** | | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** | **($2,000.00)** |
| **Virginia State Block Grant (b)** | | **($427.44)** | | **($427.44)** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** | **$0.00** |
| **Ending balance** | | **$85,585.47** | | **$30,818.50** | **$30,594.98** | **$32,406.11** | **$36,743.42** | **$42,505.37** | **$51,126.30** | **$58,378.14** | **$71,644.93** | **$85,585.47** |

(a) The Virginia Resources Authority (VRA) made a loan to the Authority in Feburary 2001 to fund the construction related to Hangar 4 and ground support equipment shop.
(b) The Commonwealth of Virginia made a loan to the Authority in 2009 to finance the site work project to accommodate parking garage D.
Source: DKMG, CHA, 2020.

### Table 7-16 – Debt Service Coverage and Days Cash on Hand
### (in 000s)

| | Source Table | PAL 1 | | | | PAL 2 | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 |
| **Calculation of debt service coverage ratio** | | | | | | | | | | |
| Net Revenues | 7-15 | $14,286.52 | $14,652.83 | $18,493.83 | $18,702.32 | $20,093.39 | $20,639.94 | $20,997.82 | $31,322.60 | $32,006.59 |
| Total Debt Service Requirement | 7-15 | $4,223.72 | $4,215.63 | $5,582.70 | $9,365.02 | $9,531.45 | $9,519.01 | $9,245.98 | $15,555.80 | $15,566.04 |
| **Debt service coverage ratio** | | **338.2%** | **347.6%** | **331.3%** | **199.7%** | **210.8%** | **216.8%** | **227.1%** | **201.4%** | **205.6%** |
| **Days cash on hand** | | | | | | | | | | |
| Current year unrestricted cash & equivalents | 7-15 | $26,973.42 | $30,818.50 | $30,594.98 | $32,406.11 | $36,743.42 | $42,505.37 | $51,126.30 | $58,378.14 | $71,644.93 |
| Total O&M Expenses | 7-9 | $36,272.71 | $36,892.00 | $36,769.00 | $37,244.00 | $37,724.00 | $38,214.00 | $38,861.00 | $39,368.00 | $39,879.00 |
| Ratio | | 0.74 | 0.84 | 0.83 | 0.87 | 0.97 | 1.11 | 1.32 | 1.48 | 1.80 |
| Number of days | | 366 | 365 | 365 | 365 | 366 | 365 | 365 | 365 | 366 |
| **Days cash on hand** | | **272** | **305** | **304** | **318** | **356** | **406** | **480** | **541** | **658** |
| **Average** | | | | | **300** | | | | | **488** |

Source: DKMG, CHA, 2020.

# 8 AIRPORT LAYOUT PLAN

This chapter presents the Airport Layout Plan (ALP) for the recommended developments at Norfolk International Airport (ORF). The ALP illustrates the recommended future airport facilities, airspace, and serves as the official development plan for the Airport. A number of additional drawings that illustrate surrounding airspace and land use support the ALP. The combined set of drawings is termed the ALP Drawing Set. This chapter contains the Summary of the Recommended Plan, the 20-year Airport Capital Improvement Plan (ACIP), and a description of the ALP drawing set.

## 8.1 SUMMARY OF RECOMMENDATION PLAN

**Figures 5-29** in **Chapter 5** presented the overall recommended airport developments for ORF. The plan includes recommendations for airfield, passenger terminal, landside, general aviation (GA), and air cargo development, which have been organized into three implementation phases: short-term, mid-term, and long-term.

It should be noted that potential obstructions for removal/relocation (i.e., tree clearings, utility poles, etc.) and property acquisitions were not shown in the **Chapter 5** figures, as they occur beyond the property of the Airport; however, these potential projects are included in the recommendations.

***PAL 1 (0-5 Years, 2020-2023)***

- Airfield Signage Replacement (To Be Complete in Summer 2020)
- Runway 5/23 Standardization – Phase 1 & 2 Construction (i.e., 25-foot shoulders, grade RSAs, widen blast pads, etc.)[31]
- Runway 5/23 Outer Pavement Mill & Overlay
- Taxiway 'C' Mid-Field North/South Reconstruction
- Taxiway 'V' Rehabilitation
- Closure of Runway 14/32 (Reserve Land for Future Commercial or Aeronautical Use)
- Corporate Hangar Construction (Two, Each at 150 ft. x 200 ft.)
- Fuel Farm Expansion [Add 10,000 Gallons AvGas for General Aviation (GA); Close Old Fuel Farm]
- ARFF Sleeping Quarters Improvements and Fire Alarm Upgrade
- Terminal (Interior) Wayfinding Improvements
- Ticket Lobby Improvements
- Misc. Departures Terminal Improvements (i.e., fire protection, water main, etc.)

[31] Projects currently underway to bring Runway 5/23 to FAA standards.

- Misc. Arrivals Terminal Improvements (i.e., fire alarm upgrade, elevators, restrooms, etc.)
- Misc. Concourse Improvements (i.e., refurbish stairwell, etc.)
- Intersection Improvements – Departures Boulevard & Long-Term West Exit
- Garage B & C Repairs/Garage A, B, & C Rehabilitation (5,400 Parking Spaces)
- Misc. Parking Improvements (i.e., replace generator, etc.)
- Property Acquisition – Gurley Street (Three Parcels)
- Property Acquisition – Barrs Road

***PAL 2 (5-10 Years, 2024-2028)***

- Taxiway 'C' North Rehabilitation
- Runway 5/23 Standardization – Phase 3 Construction
- Construction of a New Cargo Facility Measuring Approximately 56,000 SF (i.e., facility, landside area dedicated to loading and unloading of cargo, parking for ground-cargo vehicles and cargo operator employees, etc.) and shift Taxiway 'V' (Approximately 114 ft. northeast)
- Develop a Remote Terminal Apron (Approximately 74,000 SY) for Deicing Operations; Include a Glycol Recovery System
- Relocate Fuel Facility in the Previous Rental Car Overflow Lot [Minimum of 600,000 Gallon Storage Capacity plus AvGas for General Aviation (GA); Close Old Fuel Farm]
- Repurpose Old Employee Lot as a Consolidated Quick Turnaround (QTA) Facility
- Expand the GA Apron Approximately 29,000 SY

***PAL 3 (10-15 Years, 2029-2033)***

- Convert the Lower Levels of Garage B & C into a New Consolidated Rental Car (CONRAC) Facility

***PAL 4 (15-20 Years, 2034-2038)***

- Combine the Split Ticketing Halls and Relocate to the West Side of the Departures Building
- Reconfigure Terminal Roadways
- Expand Outbound Baggage Facilities
- Develop the Land Made Available Through the Closure of Runway 14/32 for either Commercial or Aeronautical Use (Approximately 45 acres to the northwest and approximately 19 acres to the southeast)

***Beyond the 20-Year Planning Horizon***

- Construct New Runway (9,001 ft. x 150 ft.) – Runway 5R/23L

The projects listed above include new facilities and property acquisition. Throughout the planning period, numerous rehabilitation projects and facility upgrades, both airside and landside, will also

be pursued by ORF but are not all listed above; however, they are included in the Airport Capital Improvement Plan (ACIP) (see **Chapter 7**).

## 8.2 AIRPORT LAYOUT PLAN

The ALP drawings illustrate all development projects identified for ORF throughout the 20-year planning horizon. Upon approval by the Federal Aviation Administration (FAA), the ALP becomes the official planning document for the Airport. The FAA requires that all new airport facilities be consistent with the ALP. As such, keeping the drawings accurate and up to date is a high priority. FAA policy requires that the ALP be updated at least every five to ten years.

Although the ALP is the only drawing that is signed by the FAA, it is part of a larger drawing set that includes the sheets listed below.

**Table 8-1 – ALP Drawing Index**

| SHEET INDEX | |
|---|---|
| SHEET No. | DESCRIPTION |
| 1 | TITLE SHEET |
| 2 | AIRPORT DATA SHEET 1 |
| 3 | AIRPORT DATA SHEET 2 |
| 4 | EXISTING AIRPORT LAYOUT PLAN |
| 5 | FUTURE AIRPORT LAYOUT PLAN BY PLANNING ACTIVITY LEVEL (PAL) |
| 6 | PASSENGER TERMINAL AREA PLAN |
| 7 | CARGO AREA PLAN |
| 8 | GENERAL AVIATION AREA PLAN |
| 9 | AIRSPACE PLAN |
| 10 | AIRSPACE OBSTRUCTIONS AND DETAILS |
| 11 | RUNWAY 5 (FUTURE RUNWAY 5L) INNER APPROACH |
| 12 | RUNWAY 23 (FUTURE RUNWAY 23R) INNER APPROACH |
| 13 | RUNWAY 5 APPROACH OBSTRUCTIONS 1 |
| 14 | RUNWAY 5 APPROACH OBSTRUCTIONS 2 |
| 15 | RUNWAY 5 APPROACH OBSTRUCTIONS 3 |
| 16 | RUNWAY 23 APPROACH OBSTRUCTIONS 1 |
| 17 | RUNWAY 23 APPROACH OBSTRUCTIONS 2 |
| 18 | RUNWAY 14 APPROACH |
| 19 | RUNWAY 32 APPROACH |
| 20 | RUNWAY 14 APPROACH OBSTRUCTION 1 |
| 21 | RUNWAY 14 APPROACH OBSTRUCTION 2 |

| SHEET INDEX | |
|---|---|
| SHEET No. | DESCRIPTION |
| 22 | RUNWAY 14 APPROACH OBSTRUCTION 3 |
| 23 | RUNWAY 14 APPROACH OBSTRUCTION 4 |
| 24 | RUNWAY 32 APPROACH OBSTRUCTION 1 |
| 25 | RUNWAY 32 APPROACH OBSTRUCTION 2 |
| 26 | RUNWAY 32 APPROACH OBSTRUCTION 3 |
| 27 | FUTURE RUNWAY 5R INNER APPROACH |
| 28 | FUTURE RUNWAY 23L INNER APPROACH |
| 29 | FUTURE RUNWAY 5R APPROACH OBSTRUCTION TABLES - 1 |
| 30 | FUTURE RUNWAY 5R APPROACH OBSTRUCTION TABLES - 2 |
| 31 | FUTURE RUNWAY 23L APPROACH OBSTRUCTION TABLES |
| 32 | LAND USE MAP |
| 33 | AIRPORT PROPERTY INVENTORY MAP |
| 34 | PROPERTY DATA TABLES |
| 35 | Future Airport Layout Plan |

The Norfolk Airport Authority ('NAA' or 'the Authority') and the FAA maintain full size copies of the final approved ALP Set. Each of the drawings is described below in the subsequent sections.

### 8.2.1 Existing and Future/Ultimate Airport Layout Plan

The first drawing sheet of the drawing set is the Existing Airport Layout. This sheet depicts the Airport as it exists today. The drawing identifies all key FAA airfield design standards [e.g. Runway Safety Areas (RSA), Object Free Areas (OFA), Runway Protection Zones (RPZ), etc.] and illustrates all landside facilities.

Next, the Future and Ultimate (or proposed) ALPs include all features of the Existing ALP, as well as all proposed facilities, airfield improvements, and recommendations. These drawings are reviewed by several offices within the FAA for consistency with airport design standards, flight procedures, airspace, and environmental requirements. Approval indicates the FAA's endorsement of the proposed project types and locations, but development may still be predicated upon environmental approvals and demand/capacity justification.

It should be noted that projects illustrated on the ALP do not commit the Airport Authority to pursue their development nor does it ensure that FAA funding will be available. The projects are intended to depict the maximum build-out of the Airport within the planning period. Also note that the FAA considers ALP approval to 'condition', pending environmental review under the National Environmental Policy Act (NEPA).

The ALP drawings were prepared in accordance with the FAA design standards for Airport Reference Code (ARC) D-IV, which includes commercial jet aircraft such as the Boeing 737-900 and Airbus 300. ORF's primary runway (Runway 5/23) currently satisfies FAA design standards for ARC D-IV. The secondary or crosswind runway (Runway 14/32) primarily serves small, GA aircraft. Although Runway 14/32 was categorized as a C-III runway in the previous 2008 Airport Master Plan, current operations now indicate that the runway is an A-I, with the Cirrus SR22 being the critical aircraft for the runway. The future and ultimate ALPs for ORF depict the closure of Runway 14/32 within the 20-year planning horizon.

The following publications were used during the drawing preparation:

- FAA Advisory Circular 150/5300-13A, *Airport Design*
- FAA Advisory Circular 150/5070-6B, *Airport Master Plans*
- Title 14 Code of Federal Regulations (CFR) Part 77, *Safe, Efficient Use, and Preservation of the Navigable Airspace*

As a large amount of information is contained on the ALP drawing, additional charts and tables relating to the ALP were placed on preceding sheets (Airport Data Sheet 1 & Airport Data Sheet 2) to reduce clutter. The data sheets for ORF include the following information: Airport Data, Windrose Diagrams & Condition Observations, Runway Design Standards, Runway Data, Taxiway Data, Departure Surfaces, Runway Safety Area Data, Modification of Standards, Threshold Siting Surfaces (TSS), and Abbreviations.

As shown in the ALP drawing, the existing airport property extends out beyond the runway ends to include the majority of RPZ; however, Runway ends 5L, 23R, and 5R each have a small area of the RPZ that is off-airport. The Runway 5L RPZ extends over public roadways (i.e., Robin Hood Road, Interstate 64, etc.), while the Runway 23 RPZ extends over land military-owned land. Office space and industrial land use properties are located within the future Runway 5R RPZ. The NAA should review these locations and consider acquisition if such parcels become available for sale. Until property becomes available, the NAA can look into acquiring easements or long-term leases to control land uses.

### 8.2.2 Airspace Plan

The next several sheets of the ALP drawing set illustrate the airspace requirements described in

Title 14 CFR Part 77, *Safe, Efficient Use, and Preservation of the Navigable Airspace*. Part 77.19 identifies a series of geometric planes (i.e., imaginary surfaces) that extend outward and upward from civil airports' runways and define the obstruction clearing requirements. These surfaces identify the maximum acceptable height of objects by defining three-dimensional areas surrounding all sides of the airfield. When an object penetrates an imaginary surface, it is considered an airspace obstruction, and all obstructions are treated as potential hazards to air navigation (unless a FAA aeronautical study determines otherwise).

***Imaginary Surfaces***

The height and dimensions of the imaginary surfaces are determined by the airfield and runway end elevations, the type of aircraft using the facilities, and the availability of instrument approaches to the runway ends (approach type and visibility minimums). The first sheet of the Airspace Plan provides an overall depiction of these surfaces. For ORF, the specific surfaces are described below.

Primary Surface

The primary surface is longitudinally centered on each runway and extends 200 feet beyond the runway ends. Based on the precision instrument approaches, the width of the primary surface for Runway 5 and Runway 23, as well as the future parallel runway (Runway 5R/23L), is 1,000 feet. Because Runways 14 and 32 are non-precision runways with more than ¾ statute mile visibility minimums, the primary surface for the crosswind runway is 500 feet.

The elevation of the primary surface is equal to the elevation of the nearest point of a runway centerline. Note that the highest point of the primary surface determines the official airport elevation (i.e., for ORF: 26.4 feet above mean sea level).

Horizontal Surface

The horizontal surface consists of the horizontal plane 150 feet above the Airport's elevation of 26.4 feet mean sea level (MSL); therefore, the horizontal surface at ORF is situated 176.40 feet above MSL. The shape of the surface is created using radial arcs of 10,000 feet from the ends of the primary surface of the existing and future runways at ORF, connected by lines tangent to the arcs.

Conical Surface

The conical surface extends outward and upward from the periphery of the horizontal surface at a slope of 20 to 1, for a horizontal distance of 4,000 feet. At ORF, the elevation of the outer edge of the conical surface is 376.40 feet above MSL.

Approach Surface

Approach surfaces are longitudinally centered on the runway centerlines and extend outward and upward from the ends of the primary surfaces. The inner edge of the approach surface is the same width as the primary surface and extends uniformly to a designated width dependent on the type of runway (i.e., utility, civil, visual, precision, non-precision, etc.). The approach surface extends for a horizontal distance at a specified slope, also dependent upon whether the runway is a visual, non-precision instrument, or a precision instrument runway. For ORF, the dimensions and slopes of the existing approach surfaces are listed in **Table 8-2**, while the future and ultimate approach surface characteristics are listed in **Table 8-3**.

**Table 8-2 – Approach Surface Dimensions (Existing)**

| Runway End | Inner Width (Ft.) | Outer Width (Ft.) | Length (Ft.) | Slope |
|---|---|---|---|---|
| Runway 5 (Precision) | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |
| Runway 23 (Precision) | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |
| Runway 14 (Non-Precision) | 500 | 4,000 | 10,000 | 34:1 |
| Runway 32 (Non-Precision) | 500 | 4,000 | 10,000 | 34:1 |

Source: CHA, 2020.

**Table 8-3 – Approach Surface Dimensions (Future & Ultimate)**

| Runway End | Inner Width (Ft.) | Outer Width (Ft.) | Length (Ft.) | Slope |
|---|---|---|---|---|
| Runway 5L (Precision) - Future/Ultimate | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |
| Runway 23R (Precision) - Future/Ultimate | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |
| Runway 5R (Precision) - Future | 500 | 4,000 | 10,000 | 34:1 |
| Runway 23L (Precision) - Future | 500 | 4,000 | 10,000 | 34:1 |
| Runway 5R (Precision) - Ultimate | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |
| Runway 23L (Precision) - Ultimate | 1,000 | 16,000 | 10,000 (+40,000) | 50:1 (40:1) |

Source: CHA, 2020.

Transitional Surface

Transitional surfaces extend outward and upward at right angles from the sides of the primary and approach surfaces at a slope of 7 to 1 (7:1), with the transitional surfaces terminating at the overlying horizontal surface.

The overall Airspace Plan illustrates the full dimensions of the Part 77 surfaces and obstructions located within the outer portions of the approach, horizontal, and conical surfaces. These drawings use a small scale, as they depict a large area extending approximately 9.5 miles from the runway ends.

***Airspace Obstructions and Details***

Following the overview of the airspace is a sheet providing a data table detailing obstructions to the airspace. These include objects such as trees, utility poles, light poles, etc. As shown in ORF's Airspace Obstructions and Details sheet, the horizontal and transitional surfaces are obstructed.

***Inner Approach and Approach Obstructions Drawings***

The approach surface is illustrated in greater detailed at the ends of each runway in a two sets of drawings titled Inner Approach and Approach Obstructions. By definition, the inner portion of the surface extends outward to the point where the approach reaches 100 feet above the runway end elevation. These sheets illustrate approach obstructions in a level of detail to identify specific objects, such tree, poles, and building penetrations. As common to most airports, the drawings identify several penetrations to the surrounding airspace.

### 8.2.3 Passenger Terminal Area Plan

The Passenger Terminal Area Plan illustrates the existing and future terminal building(s), parking, access, and apron area. The facilities depicted are identical to that depicted on the ALP, but at a larger scale and in greater detail. Highlights of the proposed new facilities on the Passenger Terminal Area Plan include:

- Reconfigured Concourse 'A'
- Reconfigured Concourse 'B'
- New Concourse 'C'
- Expansion of the Terminal Building
- Expansion of the Terminal Apron
- New Hourly Parking Lot
- New Departures Curbside Roadway
- Reconfigure Terminal Access Roadway
- New Cell Phone Waiting Lot

The construction of the new and expanded terminal facilities will be conducted via a phased approach, thus limiting impacts to passenger activity. Financial planning and financing will be required when undertaking each phased approach; therefore, availability of funding will also affect the timing and ultimate level of development.

### 8.2.4 Cargo Area Plan

The Cargo Area Plan illustrates the existing air cargo buildings, dedicated apron space, parking, and access, as well as a proposed new air cargo sort facility and associated aircraft apron and landside vehicular parking areas. To accommodate the new facility and to provide adequate apron space, Taxiway 'V' will shift approximately 114 feet to the northeast, which is also depicted in this Plan.

The plan further depicts areas not directly associated with, but whose layouts affect the Cargo Area Plan (i.e., new fuel/glycol storage facility, airline deicing apron, airport access road reconfiguration, etc.).

### 8.2.5 General Aviation Area Plan

The General Aviation Area Plan illustrates the existing ground run-up enclosure (GRE), GA terminal building, corporate/box hangars, T-hangars, aircraft maintenance hangar, and Fixed-Base Operator (FBO) maintenance shop, as well as FAA facilities (i.e., support building and air traffic control tower).

The Plan also depicts proposed facilities, including one box hangar measuring approximately 30,000 square feet (SF) and one box hangar measuring approximately 22,500 SF on the western side of the GA area, as well as two T-hangar units to be rebuilt. In addition, proposed corporate hangars and associated apron space is depicted on the eastern side of the GA area. The Plan further depicts a GA apron expansion (which includes tie-down positions), as well as the reconfigured taxiway and runway access from the GA facilities.

### 8.2.6 Land Use Map

As discussed in **Chapter 6 (Section 6.9**, ***Land Use*)**, the land surrounding the airport contains a diverse mix of uses, including: office space, residential, multi-family residential, commercial, military, parks/recreation/greenspace, industrial, agricultural, schools, and hospitals. Airport development has the potential to impact sensitive areas such as residences, schools, churches, etc.; however, airports are typically considered to be compatible with commercial, industrial, and agricultural activities. The Land Use Map sheet depicts the surrounding land use and associated zoning for Virginia Beach, Virginia and the City of Norfolk.

### 8.2.7 Airport Property Map / Data Tables

The final sheets of the ALP set are the Airport Property Map and Property Data Tables. The Airport Property Map drawing is often called the "Exhibit A" because the property map is a required attachment for FAA grant applications, and is attached as Exhibit A.

The primary purpose of this drawing and the associated data tables is to provide information indicating how various tracts of airport property were acquired (i.e., federal programs, local funds only, etc.). The map helps the FAA identify the current and future aeronautical uses of properties acquired with federal funds. The map also identifies each location that is proposed or planned for ultimate acquisition. An "Exhibit A" is for illustration purposes and does not constitute a property boundary survey or other legal documentation.

# APPENDIX A – HISTORICAL DATA SETS

### Table A-1– Socioeconomic Factors

| Fiscal Year | Population (000) | Employment (000) | Income ($) |
|---|---|---|---|
| **2008** | 1,839.3 | 1,123.0 | 37,255 |
| **2009** | 1,844.6 | 1,088.5 | 36,975 |
| **2010** | 1,856.3 | 1,074.2 | 37,187 |
| **2011** | 1,862.8 | 1,074.9 | 38,565 |
| **2012** | 1,873.9 | 1,078.3 | 39,961 |
| **2013** | 1,881.2 | 1,086.0 | 39,822 |
| **2014** | 1,892.0 | 1,094.6 | 40,807 |
| **2015** | 1,898.8 | 1,112.5 | 42,291 |
| **2016** | 1,909.9 | 1,126.6 | 43,447 |
| **2017** | 1,922.5 | 1,140.6 | 44,649 |

Source: Woods & Poole Economics, Inc., CHA, 2018.

### Table A-2 – Commercial Activity

| Fiscal Year | Enplanements | Operations | Scheduled Seats | Average Seats Per Departure | Load Factors |
|---|---|---|---|---|---|
| **2008** | 1,841,881 | 63,716 | 5,069,307 | 79.6 | 72.9% |
| **2009** | 1,740,349 | 58,477 | 4,634,004 | 79.2 | 75.2% |
| **2010** | 1,697,663 | 57,038 | 4,629,310 | 81.2 | 73.7% |
| **2011** | 1,658,696 | 57,614 | 4,642,508 | 80.6 | 71.8% |
| **2012** | 1,669,997 | 55,522 | 4,559,278 | 82.1 | 73.5% |
| **2013** | 1,615,283 | 53,259 | 4,552,460 | 85.5 | 71.3% |
| **2014** | 1,534,316 | 47,070 | 3,900,974 | 82.9 | 79.1% |
| **2015** | 1,499,400 | 43,469 | 3,591,391 | 82.6 | 83.8% |
| **2016** | 1,603,159 | 47,273 | 4,008,096 | 84.8 | 80.4% |
| **2017** | 1,672,024 | 47,195 | 4,241,674 | 89.8 | 79.0% |

Source: NAA, CHA, 2018.

### Table A-3 – FAA TAFs: Enplanements

| Fiscal Year | National | Regional | | | State |
|---|---|---|---|---|---|
| | | RIC | PHF | PGV | |
| **2008** | 747,466,798 | 1,760,914 | 512,799 | 49,453 | 4,618,145 |
| **2009** | 695,488,533 | 1,666,022 | 492,548 | 58,238 | 4,441,971 |
| **2010** | 702,818,621 | 1,639,557 | 508,668 | 60,544 | 4,404,345 |
| **2011** | 722,926,202 | 1,597,152 | 527,549 | 63,124 | 4,358,236 |
| **2012** | 731,053,513 | 1,583,114 | 365,600 | 61,524 | 4,226,369 |
| **2013** | 734,336,521 | 1,583,315 | 273,414 | 59,300 | 4,070,466 |
| **2014** | 753,529,877 | 1,647,904 | 265,197 | 60,281 | 4,070,499 |
| **2015** | 786,384,586 | 1,718,820 | 208,304 | 57,550 | 4,057,875 |
| **2016** | 822,586,152 | 1,763,247 | 200,223 | 50,044 | 4,222,748 |
| **2017** | 846,556,739 | 1,799,021 | 198,229 | 49,851 | 4,369,186 |

Source: NAA, CHA, 2018.

### Table A-4 – ORF's Percent Market Shares: Enplanements

| Fiscal Year | National Market Share | State Market Share | Regional Market Share |
|---|---|---|---|
| **2008** | 0.2% | 7.4% | 44.2% |
| **2009** | 0.3% | 7.2% | 44.0% |
| **2010** | 0.2% | 7.0% | 43.5% |
| **2011** | 0.2% | 6.8% | 43.1% |
| **2012** | 0.2% | 6.8% | 45.4% |
| **2013** | 0.2% | 6.6% | 45.7% |
| **2014** | 0.2% | 6.3% | 43.7% |
| **2015** | 0.2% | 5.9% | 43.0% |
| **2016** | 0.2% | 6.1% | 44.3% |
| **2017** | 0.2% | 6.2% | 44.8% |
| **Average** | **0.2%** | **6.64%** | **44.2%** |

Source: NAA, CHA, 2018.

### Table A-5 – ORF's General Aviation and Military Activity

| Fiscal Year | General Aviation Operations | | | | Military Operations | | |
|---|---|---|---|---|---|---|---|
| | Itinerant | Civil | With Cargo | Without Cargo | Itinerant | Local | Total |
| **2008** | 34,385 | 11,553 | 45,938 | 43,266 | 774 | 7,004 | 7,778 |
| **2009** | 28,160 | 7,719 | 35,879 | 33,439 | 714 | 1,860 | 2,574 |
| **2010** | 28,477 | 5,558 | 34,035 | 31,423 | 523 | 873 | 1,396 |
| **2011** | 29,012 | 4,274 | 33,286 | 30,664 | 738 | 370 | 1,108 |
| **2012** | 27,062 | 3,152 | 30,214 | 27,832 | 1,364 | 79 | 1,443 |
| **2013** | 24,534 | 2,491 | 27,025 | 24,502 | 786 | 461 | 1,247 |
| **2014** | 25,154 | 4,091 | 29,245 | 26,847 | 1,130 | 203 | 1,333 |
| **2015** | 24,225 | 1,488 | 25,713 | 22,532 | 567 | 343 | 910 |
| **2016** | 24,265 | 1,943 | 26,208 | 23,230 | 595 | 13 | 608 |
| **2017** | 23,636 | 1,157 | 24,793 | 22,364 | 508 | 92 | 600 |

Source: Signature, NAA, CHA, 2018.

# APPENDIX B – NATIONAL TAF AND PROJECTED ENPLANEMENTS[32]

## Table B-1 – National TAF and Projected Enplanements

| Fiscal Year | TAF (National) | TAF (ORF) | Historical Trends | | Market Shares | | | | Regressions | | | | | | Air Service | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 5-Year | 10-Year | Average National | Static State | Static Regional | Adjusted Static Regional | Population Based | Employment Based | Income Based | Population-Income Based | Employment-Income Based | Population-Income-Employment Based | Short-Term | Med- to Long-Term |
| **2017** | 846,556,739 | 1,652,323 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 | 1,672,024 |
| **2018** | 887,027,038 | 1,815,241 | 1,683,609 | 1,655,925 | 1,953,884 | 1,723,608 | 1,816,656 | 1,812,627 | 1,513,586 | 1,657,072 | 1,524,971 | 1,546,545 | 1,585,688 | 1,575,919 | 1,857,487 | 1,857,487 |
| **2019** | 927,374,941 | 2,008,565 | 1,695,275 | 1,639,981 | 2,042,760 | 1,804,097 | 2,056,552 | 2,089,768 | 1,482,420 | 1,658,013 | 1,492,895 | 1,534,810 | 1,568,428 | 1,564,254 | 2,003,360 | 2,003,360 |
| **2020** | 951,340,881 | 2,047,023 | 1,707,021 | 1,624,190 | 2,095,551 | 1,859,352 | 2,103,128 | 2,142,823 | 1,451,136 | 1,658,949 | 1,456,981 | 1,536,042 | 1,543,929 | 1,555,429 | 2,038,176 | 2,038,176 |
| **2021** | 973,596,970 | 2,084,292 | 1,718,849 | 1,608,551 | 2,144,575 | 1,922,509 | 2,147,528 | 2,192,905 | 1,419,764 | 1,659,884 | 1,417,650 | 1,548,883 | 1,513,171 | 1,549,288 | 2,072,287 | 2,072,287 |
| **2022** | 995,029,034 | 2,116,656 | 1,730,758 | 1,593,063 | 2,191,784 | 1,980,779 | 2,186,663 | 2,237,442 | 1,388,284 | 1,660,821 | 1,373,932 | 1,576,653 | 1,474,471 | 1,546,667 | 2,104,678 | 2,104,678 |
| **2023** | 1,015,797,464 | 2,147,644 | 1,742,750 | 1,577,724 | 2,237,531 | 2,035,945 | 2,224,870 | 2,281,421 | 1,356,750 | 1,661,755 | 1,326,358 | 1,617,702 | 1,428,578 | 1,547,086 | 2,115,424 | 2,234,279 |
| **2024** | 1,035,068,887 | 2,177,805 | 1,754,826 | 1,562,533 | 2,279,981 | 2,081,165 | 2,261,767 | 2,323,698 | 1,325,157 | 1,662,685 | 1,274,706 | 1,672,798 | 1,375,030 | 1,550,688 | 2,168,171 | 2,316,173 |
| **2025** | 1,054,043,471 | 2,206,080 | 1,766,984 | 1,547,488 | 2,321,777 | 2,120,940 | 2,296,861 | 2,364,245 | 1,293,635 | 1,663,609 | 1,218,334 | 1,744,694 | 1,312,639 | 1,558,275 | 2,220,800 | 2,397,883 |
| **2026** | 1,073,017,630 | 2,233,911 | 1,779,228 | 1,532,588 | 2,363,572 | 2,158,473 | 2,331,610 | 2,404,530 | 1,262,251 | 1,664,531 | 1,157,959 | 1,831,150 | 1,242,797 | 1,569,437 | 2,273,199 | 2,479,237 |
| **2027** | 1,092,560,588 | 2,263,883 | 1,791,556 | 1,517,831 | 2,406,620 | 2,195,140 | 2,369,311 | 2,448,419 | 1,231,036 | 1,665,444 | 1,093,805 | 1,931,508 | 1,165,685 | 1,583,904 | 2,325,316 | 2,560,152 |
| **2028** | 1,112,650,527 | 2,294,704 | 1,803,969 | 1,503,217 | 2,450,873 | 2,231,077 | 2,407,978 | 2,493,366 | 1,200,085 | 1,666,352 | 1,025,523 | 2,047,371 | 1,080,783 | 1,602,247 | 2,376,990 | 2,640,381 |
| **2029** | 1,133,320,175 | 2,325,437 | 1,816,468 | 1,488,743 | 2,496,402 | 2,266,561 | 2,446,872 | 2,538,795 | 1,169,334 | 1,667,255 | 953,017 | 2,178,812 | 987,939 | 1,624,425 | 2,428,333 | 2,720,094 |
| **2030** | 1,154,378,676 | 2,357,212 | 1,829,054 | 1,474,408 | 2,542,789 | 2,302,098 | 2,488,029 | 2,587,476 | 1,138,820 | 1,668,151 | 876,794 | 2,324,206 | 888,031 | 1,650,058 | 2,479,279 | 2,799,192 |
| **2031** | 1,175,949,046 | 2,391,205 | 1,841,728 | 1,460,212 | 2,590,302 | 2,337,685 | 2,531,108 | 2,637,832 | 1,109,233 | 1,669,041 | 797,541 | 2,483,899 | 782,253 | 1,679,981 | 2,528,677 | 2,875,886 |
| **2032** | 1,197,790,347 | 2,425,236 | 1,854,489 | 1,446,152 | 2,638,413 | 2,372,788 | 2,574,518 | 2,688,756 | 1,080,627 | 1,669,923 | 714,480 | 2,660,825 | 669,219 | 1,714,987 | 2,576,438 | 2,950,038 |
| **2033** | 1,219,740,641 | 2,458,050 | 1,867,338 | 1,432,228 | 2,686,764 | 2,407,453 | 2,617,059 | 2,739,097 | 1,052,830 | 1,670,798 | 627,038 | 2,856,304 | 547,830 | 1,755,160 | 2,622,848 | 3,022,093 |
| **2034** | 1,242,112,645 | 2,492,239 | 1,880,276 | 1,418,437 | 2,736,043 | 2,442,369 | 2,661,048 | 2,790,944 | 1,025,896 | 1,671,666 | 534,673 | 3,072,452 | 417,129 | 1,801,095 | 2,667,816 | 3,091,910 |
| **2035** | 1,264,545,129 | 2,526,083 | 1,893,305 | 1,404,780 | 2,785,456 | 2,477,090 | 2,704,005 | 2,841,200 | 999,796 | 1,672,529 | 436,131 | 3,313,540 | 274,947 | 1,853,867 | 2,711,393 | 3,159,566 |
| **2036** | 1,287,208,236 | 2,559,371 | 1,906,423 | 1,391,254 | 2,835,377 | 2,512,082 | 2,748,216 | 2,894,181 | 974,459 | 1,673,388 | 333,123 | 3,573,294 | 124,400 | 1,911,876 | 2,753,696 | 3,225,245 |
| **2037** | 1,310,024,370 | 2,592,636 | 1,919,632 | 1,377,858 | 2,885,635 | 2,547,100 | 2,793,020 | 2,948,255 | 949,866 | 1,674,244 | 226,612 | 3,848,278 | -32,666 | 1,974,331 | 2,794,755 | 3,288,992 |
| **2038** | 1,333,057,375 | 2,627,295 | 1,932,933 | 1,364,591 | 2,936,370 | 2,582,498 | 2,839,646 | 3,004,495 | 925,988 | 1,675,099 | 116,000 | 4,140,458 | -197,307 | 2,041,693 | 2,834,623 | 3,350,889 |
| **AAGR 2018-2038** | **2.1%** | **1.9%** | **0.7%** | **-1.0%** | **2.1%** | **2.0%** | **2.3%** | **2.6%** | **-2.4%** | **0.1%** | **-12.1%** | **5.0%** | **-9.9%** | **1.3%** | **2.1%** | **3.0%** |
| **Growth 2018-2038** | **50.3%** | **44.7%** | **14.8%** | **-17.6%** | **50.3%** | **49.8%** | **56.3%** | **65.8%** | **-38.8%** | **1.1%** | **-92.4%** | **167.7%** | **-112.4%** | **29.6%** | **52.1%** | **80.4%** |
| **% Above TAF (ORF)** | **-** | **-** | **1.2%** | **36.5%** | **-26.4%** | **-48.1%** | **11.8%** | **-1.7%** | **8.1%** | **14.4%** | **-64.8%** | **-36.2%** | **-95.6%** | **57.6%** | **7.9%** | **27.5%** |

Source: FAA 2018 TAF, NAA, CHA, 2019.

[32] Note: Projected enplanements take into consideration recently announced, as well as potential, non-stop service routes from ORF throughout the forecast horizon.

# APPENDIX C – REGRESSIONS[33]

## *A. Socioeconomic Regressions*

- Input Variables (All data inputs were for 2008-2017)
  - Independent Variables: Data pertaining to what the regression base is (ex, population data for the Population Based Regression), Dependent Variable: Always Enplanements
- See **Appendix B** for Regression Results

**Table C-1 – Socioeconomic Regression Calculations**

**Population Based Regression**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.691373306 |
| **R Square** | **0.48** |
| Adjusted R Square | 0.41274668 |
| Standard Error | 75590.2777 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 1 | 41857580913 | 41857580913 | 7.32558385 | 0.02679954 |
| Residual | 8 | 45711120663 | 5713890083 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | 6258612.841 | 1701700.218 | 3.677858635 | 0.00623838 | 2334485.101 | 10182740.58 | 2334485.101 | 10182740.58 |
| X Variable 1 | -2452.093837 | 905.9744792 | -2.70658158 | 0.02679954 | -4541.274733 | -362.9129421 | -4541.274733 | -362.9129421 |

**Employment Based Regression**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.016969827 |
| **R Square** | **0.00** |
| Adjusted R Square | -0.124676028 |
| Standard Error | 104608.4867 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 1 | 25217600.1 | 25217600.1 | 0.002304464 | 0.962889191 |
| Residual | 8 | 87543483975 | 10942935497 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | 1576459.977 | 1600531.282 | 0.984960428 | 0.353491286 | -2114371.778 | 5267291.731 | -2114371.778 | 5267291.731 |
| X Variable 1 | 69.83882807 | 1454.829122 | 0.048004832 | 0.962889191 | -3285.003143 | 3424.6808 | -3285.003143 | 3424.6808 |

**Income Regression**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.599749806 |
| **R Square** | **0.36** |
| Adjusted R Square | 0.279662309 |
| Standard Error | 83718.46756 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 1 | 31498447085 | 31498447085 | 4.494140056 | 0.066831572 |
| Residual | 8 | 56070254490 | 7008781811 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | 2529242.858 | 414050.7205 | 6.108533888 | 0.000286763 | 1574440.184 | 3484045.532 | 1574440.184 | 3484045.532 |
| X Variable 1 | -21.84677628 | 10.30538117 | -2.119938692 | 0.066831572 | -45.61102789 | 1.917475319 | -45.61102789 | 1.917475319 |

**Population-Income Regression**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.801833099 |
| **R Square** | **0.64** |
| Adjusted R Square | 0.540918123 |
| Standard Error | 66834.12623 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 2 | 56301098574 | 28150549287 | 6.302173051 | 0.027202566 |
| Residual | 7 | 31267603002 | 4466800429 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | 16912707.69 | 6112918.192 | 2.766715856 | 0.027825417 | 2457953.081 | 31367462.29 | 2457953.081 | 31367462.29 |
| X Variable 1 | -9757.477882 | 4140.824218 | -2.356409586 | 0.050607915 | -19548.97125 | 34.01548494 | -19548.97125 | 34.01548494 |
| X Variable 2 | 76.47469881 | 42.52845066 | 1.798200913 | 0.115187336 | -24.08910701 | 177.0385046 | -24.08910701 | 177.0385046 |

**Employment-Income Regression**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.818737332 |
| **R Square** | **0.67** |
| Adjusted R Square | 0.576139625 |
| Standard Error | 64219.15833 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 2 | 58699999498 | 29349999749 | 7.116703677 | 0.020571891 |
| Residual | 7 | 28868702078 | 4124100297 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | -124870.5181 | 1081149.983 | -0.115497868 | 0.911293939 | -2681383.987 | 2431642.951 | -2681383.987 | 2431642.951 |
| X Variable 1 | 3072.715891 | 1196.437924 | 2.568220071 | 0.037104064 | 243.5897601 | 5901.842022 | 243.5897601 | 5901.842022 |
| X Variable 2 | -39.94376766 | 10.58980332 | -3.771908358 | 0.006965532 | -64.98467341 | -14.90286191 | -64.98467341 | -14.90286191 |

**Population-Employment-Income**

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.84369935 |
| **R Square** | **0.71** |
| Adjusted R Square | 0.567742891 |
| Standard Error | 64852.13419 |
| Observations | 10 |

| ANOVA | | | | | |
|---|---|---|---|---|---|
| - | *df* | *SS* | *MS* | *F* | *Significance F* |
| Regression | 3 | 62333905720 | 20777968573 | 4.940313849 | 0.046318568 |
| Residual | 6 | 25234795855 | 4205799309 | - | - |
| Total | 9 | 87568701576 | | - | - |

| - | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | 8412714.452 | 9249522.175 | 0.909529627 | 0.398132958 | -14220050.97 | 31045479.88 | -14220050.97 | 31045479.88 |
| X Variable 1 | -5163.502956 | 5554.971624 | -0.929528233 | 0.388482898 | -18756.02886 | 8429.022944 | -18756.02886 | 8429.022944 |
| X Variable 2 | 2000.572684 | 1670.393864 | 1.197665249 | 0.276210037 | -2086.733859 | 6087.879227 | -2086.733859 | 6087.879227 |
| X Variable 3 | 18.40086983 | 63.67251065 | 0.288992371 | 0.782312365 | -137.4001511 | 174.2018907 | -137.4001511 | 174.2018907 |

Source: NAA, CHA, 2018.

[33] Note: Projected enplanements take into consideration recently announced, as well as potential, non-stop service routes from ORF throughout the forecast horizon.

### *B. Air Service Regressions*

**Table C-2 – Air Service Regression Calculations**

| Short-Term Air Service: Population Based Regression | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| ***Regression Statistics*** | | | **ANOVA** | | | | | |
| Multiple R | 0.927878484 | | - | *df* | *SS* | *MS* | *F* | *Significance F* |
| **R Square** | 0.86 | | Regression | 1 | 31688979343 | 31688979343 | 18.57628903 | 0.022997266 |
| Adjusted R Square | 0.814611308 | | Residual | 3 | 5117649595 | 1705883198 | | |
| Standard Error | 41302.3389 | | Total | 4 | 36806628938 | | | |
| Observations | 5 | | | | | | | |
| **-** | ***Coefficients*** | ***Standard Error*** | ***t Stat*** | ***P-value*** | ***Lower 95%*** | ***Upper 95%*** | ***Lower 95.0%*** | ***Upper 95.0%*** |
| Intercept | -6068715.791 | 2004534.63 | -3.304519553 | 0.0455788 | -13003347.71 | -244700.0529 | -13003347.71 | -244700.0529 |
| X Variable 1 | 4094.010385 | 1022.365361 | 4.310021929 | 0.022997266 | 1152.79426 | 7660.039993 | 1152.79426 | 7660.039993 |
| **Medium- to Long-Term Air Service: Population Based Regression** | | | | | | | | |
| ***Regression Statistics*** | | | **ANOVA** | | | | | |
| Multiple R | 0.949441091 | | - | *df* | *SS* | *MS* | *F* | *Significance F* |
| **R Square** | 0.90 | | Regression | 1 | 4.6744E+11 | 4.6744E+11 | 73.167501 | 2.68889E-05 |
| Adjusted R Square | 0.889118183 | | Residual | 8 | 51109074259 | 6388634282 | | |
| Standard Error | 79928.9327 | | Total | 9 | 5.18549E+11 | | | |
| Observations | 10 | | | | | | | |
| **-** | ***Coefficients*** | ***Standard Error*** | ***t Stat*** | ***P-value*** | ***Lower 95%*** | ***Upper 95%*** | ***Lower 95.0%*** | ***Upper 95.0%*** |
| Intercept | -10472204.34 | 1434932.436 | -7.298046983 | 8.40462E-05 | -13781164.47 | -7163244.205 | -13781164.47 | -7163244.205 |
| X Variable 1 | 6356.254769 | 743.0913143 | 8.553800384 | 2.68889E-05 | 4642.683126 | 8069.826413 | 4642.683126 | 8069.826413 |

Source: FAA 2018 TAF, NAA, CHA, 2019.

# APPENDIX D – GENERAL AVIATION FORECASTS

## *A. Based Aircraft Forecast Methodologies*

### Table D-1 – TAF Based Growth Scenario

| Fiscal Year | TAF | TAF Based Growth | Percent Difference from TAF |
|---|---|---|---|
| **2017** | 95 | 87 | -8.4% |
| **2018** | 96 | 89 | -7.3% |
| **2019** | 99 | 90 | -9.1% |
| **2020** | 100 | 92 | -8.0% |
| **2021** | 102 | 93 | -8.8% |
| **2022** | 104 | 95 | -8.7% |
| **2023** | 106 | 97 | -8.5% |
| **2024** | 108 | 98 | -9.3% |
| **2025** | 110 | 100 | -9.1% |
| **2026** | 112 | 102 | -8.9% |
| **2027** | 114 | 104 | -8.8% |
| **2028** | 116 | 106 | -8.6% |
| **2029** | 118 | 107 | -9.3% |
| **2030** | 120 | 109 | -9.2% |
| **2031** | 122 | 111 | -9.0% |
| **2032** | 124 | 113 | -8.9% |
| **2033** | 126 | 115 | -8.7% |
| **2034** | 128 | 117 | -8.6% |
| **2035** | 130 | 119 | -8.5% |
| **2036** | 132 | 121 | -8.3% |
| **2037** | 134 | 124 | -7.5% |
| **2038** | 136 | 126 | -7.4% |
| **AAGR 2018-2038** | **1.8%** | **1.8%** | - |
| **Growth 2018-2038** | **42.1%** | **42.1%** | - |

Source: FAA 2018 TAF, Signature, NAA, CHA, 2019.

**FAA Aerospace Forecast Scenario**

### Table D-2 – FAA National Average Annual Growth Rates for GA Aircraft

| Fiscal Year | Single Engine | Multi-Engine Piston | Turbo-Prop | Jet | Rotor-craft |
|---|---|---|---|---|---|
| AAGR 2018-2023 | -0.8% | -0.3% | -0.4% | 2.4% | 1.9% |
| AAGR 2023-2028 | -1.1% | -0.4% | 1.8% | 2.2% | 1.8% |
| AAGR 2028-2033 | -1.1% | -0.5% | 2.6% | 2.1% | 1.8% |
| AAGR 2033-2038 | -1.1% | -0.7% | 3.4% | 2.5% | 2.2% |
| **AAGR 2018-2038** | **-1.0%** | **-0.4%** | **1.7%** | **2.2%** | **1.8%** |

Source: FAA Aerospace Forecast FY 2018-2038, CHA, 2018.

## Table D-3 – FAA Aerospace Forecast

| Fiscal Year | Single Engine | Multi-Engine Piston | Turbo-Prop | Jet | Rotor-craft | Military | Total Based Aircraft |
|---|---|---|---|---|---|---|---|
| **2017** | 46 | 10 | 9 | 20 | 2 | 0 | 87 |
| **2018** | 46 | 10 | 9 | 20 | 2 | 0 | 87 |
| **2019** | 45 | 10 | 9 | 21 | 2 | 0 | 87 |
| **2020** | 45 | 10 | 9 | 21 | 2 | 0 | 87 |
| **2021** | 45 | 10 | 9 | 22 | 2 | 0 | 87 |
| **2022** | 44 | 10 | 9 | 23 | 2 | 0 | 88 |
| **2023** | 44 | 10 | 9 | 23 | 2 | 0 | 88 |
| **2024** | 43 | 10 | 9 | 24 | 2 | 0 | 88 |
| **2025** | 43 | 10 | 9 | 24 | 2 | 0 | 88 |
| **2026** | 42 | 10 | 9 | 25 | 2 | 0 | 88 |
| **2027** | 42 | 10 | 9 | 25 | 2 | 0 | 89 |
| **2028** | 42 | 10 | 10 | 26 | 2 | 0 | 89 |
| **2029** | 41 | 10 | 10 | 26 | 2 | 0 | 89 |
| **2030** | 41 | 10 | 10 | 27 | 3 | 0 | 90 |
| **2031** | 40 | 10 | 10 | 27 | 3 | 0 | 90 |
| **2032** | 40 | 9 | 11 | 28 | 3 | 0 | 91 |
| **2033** | 39 | 9 | 11 | 29 | 3 | 0 | 91 |
| **2034** | 39 | 9 | 11 | 29 | 3 | 0 | 92 |
| **2035** | 39 | 9 | 12 | 30 | 3 | 0 | 92 |
| **2036** | 38 | 9 | 12 | 31 | 3 | 0 | 93 |
| **2037** | 38 | 9 | 13 | 32 | 3 | 0 | 94 |
| **2038** | 37 | 9 | 13 | 32 | 3 | 0 | 95 |
| **AAGR 2018-2038** | **-1.0%** | **-0.5%** | **1.9%** | **2.3%** | **1.9%** | **0.0%** | **0.4%** |
| **Growth 2018-2038** | **-18.3%** | **-8.8%** | **44.6%** | **58.1%** | **46.3%** | **0.0%** | **8.8%** |

Source: FAA Aerospace Forecast FY 2018-2038, Signature, CHA, 2018.

## Additional Methodologies

### Table D-4 – Market Share Scenario

| Fiscal Year | Market Share | | |
|---|---|---|---|
| | Static National | Static State | Static Regional |
| **2017** | 87 | 87 | 87 |
| **2018** | 88 | 87 | 88 |
| **2019** | 88 | 88 | 89 |
| **2020** | 89 | 89 | 89 |
| **2021** | 90 | 89 | 90 |
| **2022** | 91 | 90 | 91 |
| **2023** | 91 | 91 | 92 |
| **2024** | 92 | 91 | 92 |
| **2025** | 93 | 91 | 93 |
| **2026** | 94 | 92 | 94 |
| **2027** | 94 | 93 | 94 |
| **2028** | 95 | 93 | 95 |
| **2029** | 96 | 94 | 96 |
| **2030** | 97 | 94 | 97 |
| **2031** | 97 | 95 | 97 |
| **2032** | 98 | 95 | 98 |
| **2033** | 99 | 96 | 99 |
| **2034** | 100 | 96 | 99 |
| **2035** | 100 | 97 | 100 |
| **2036** | 101 | 97 | 101 |
| **2037** | 102 | 98 | 102 |
| **2038** | 103 | 99 | 102 |
| **AAGR 2018-2038** | **0.8%** | **0.6%** | **0.8%** |
| **Growth 2018-2038** | **17.3%** | **12.8%** | **16.6%** |

Source: FAA 2018 TAF, Signature, CHA, 2018.

### *B. GA Operations Forecast Methodologies*

**Table D-5 – OPBA Scenario**

| Fiscal Year | Based Aircraft | Itinerant GA | Local GA | Total GA Operations | OPBA |
|---|---|---|---|---|---|
| **2017** | 87 | 21,207 | 1,157 | 22,364 | 257 |
| **2018** | 89 | 21,583 | 1,178 | 22,760 | 257 |
| **2019** | 90 | 21,965 | 1,198 | 23,164 | 257 |
| **2020** | 92 | 22,355 | 1,220 | 23,574 | 257 |
| **2021** | 93 | 22,751 | 1,241 | 23,992 | 257 |
| **2022** | 95 | 23,154 | 1,263 | 24,418 | 257 |
| **2023** | 97 | 23,565 | 1,286 | 24,850 | 257 |
| **2024** | 98 | 23,982 | 1,308 | 25,291 | 257 |
| **2025** | 100 | 24,408 | 1,332 | 25,739 | 257 |
| **2026** | 102 | 24,840 | 1,355 | 26,195 | 257 |
| **2027** | 104 | 25,280 | 1,379 | 26,660 | 257 |
| **2028** | 106 | 25,729 | 1,404 | 27,132 | 257 |
| **2029** | 107 | 26,185 | 1,429 | 27,613 | 257 |
| **2030** | 109 | 26,649 | 1,454 | 28,103 | 257 |
| **2031** | 111 | 27,121 | 1,480 | 28,601 | 257 |
| **2032** | 113 | 27,602 | 1,506 | 29,108 | 257 |
| **2033** | 115 | 28,091 | 1,533 | 29,624 | 257 |
| **2034** | 117 | 28,589 | 1,560 | 30,149 | 257 |
| **2035** | 119 | 29,096 | 1,587 | 30,683 | 257 |
| **2036** | 121 | 29,611 | 1,616 | 31,227 | 257 |
| **2037** | 124 | 30,136 | 1,644 | 31,780 | 257 |
| **2038** | 126 | 30,670 | 1,673 | 32,344 | 257 |

Source: Signature, CHA, 2018.

## Table D-6 – Market Share Scenario

| Fiscal Year | Static National | | | Static State | | | Static Regional | | |
|---|---|---|---|---|---|---|---|---|---|
| | Itinerant GA | Local GA | Total GA Operations | Itinerant GA | Local GA | Total GA Operations | Itinerant GA | Local GA | Total GA Operations |
| **2017** | 21,207 | 1,157 | 22,364 | 21,207 | 1,157 | 22,364 | **21,207** | **1,157** | **22,364** |
| **2018** | 21,418 | 1,180 | 22,598 | 21,251 | 1,178 | 22,428 | **21,029** | **1,163** | **22,192** |
| **2019** | 21,527 | 1,193 | 22,720 | 21,295 | 1,191 | 22,486 | 20,879 | 1,171 | 22,050 |
| **2020** | 21,600 | 1,197 | 22,797 | 21,339 | 1,198 | 22,537 | 20,956 | 1,176 | 22,132 |
| **2021** | 21,673 | 1,201 | 22,875 | 21,383 | 1,205 | 22,588 | 21,035 | 1,181 | 22,216 |
| **2022** | 21,747 | 1,205 | 22,952 | 21,428 | 1,212 | 22,640 | 21,114 | 1,186 | 22,300 |
| **2023** | 21,821 | 1,210 | 23,031 | 21,472 | 1,220 | 22,692 | **21,194** | **1,192** | **22,385** |
| **2024** | 21,896 | 1,214 | 23,110 | 21,517 | 1,227 | 22,744 | 21,275 | 1,197 | 22,472 |
| **2025** | 21,972 | 1,219 | 23,191 | 21,561 | 1,235 | 22,796 | 21,356 | 1,202 | 22,559 |
| **2026** | 22,050 | 1,223 | 23,273 | 21,606 | 1,243 | 22,849 | 21,439 | 1,208 | 22,647 |
| **2027** | 22,129 | 1,228 | 23,356 | 21,651 | 1,251 | 22,902 | 21,523 | 1,214 | 22,736 |
| **2028** | 22,208 | 1,232 | 23,441 | 21,696 | 1,259 | 22,955 | **21,608** | **1,219** | **22,827** |
| **2029** | 22,289 | 1,237 | 23,527 | 21,741 | 1,268 | 23,008 | 21,694 | 1,225 | 22,919 |
| **2030** | 22,371 | 1,242 | 23,613 | 21,786 | 1,276 | 23,062 | 21,779 | 1,231 | 23,009 |
| **2031** | 22,455 | 1,247 | 23,701 | 21,831 | 1,285 | 23,116 | 21,865 | 1,236 | 23,101 |
| **2032** | 22,539 | 1,252 | 23,791 | 21,876 | 1,294 | 23,170 | 21,952 | 1,242 | 23,195 |
| **2033** | 22,625 | 1,257 | 23,882 | 21,921 | 1,304 | 23,225 | **22,041** | **1,248** | **23,289** |
| **2034** | 22,712 | 1,262 | 23,974 | 21,967 | 1,313 | 23,280 | 22,131 | 1,254 | 23,385 |
| **2035** | 22,801 | 1,267 | 24,068 | 22,012 | 1,323 | 23,335 | 22,222 | 1,261 | 23,482 |
| **2036** | 22,891 | 1,272 | 24,163 | 22,058 | 1,332 | 23,391 | 22,314 | 1,267 | 23,581 |
| **2037** | 22,982 | 1,278 | 24,260 | 22,104 | 1,342 | 23,446 | 22,408 | 1,273 | 23,681 |
| **2038** | 23,075 | 1,283 | 24,358 | 22,150 | 1,353 | 23,502 | **22,502** | **1,280** | **23,782** |
| **AAGR 2018-2038** | **0.4%** | **0.4%** | **0.4%** | **0.21%** | **0.70%** | **0.23%** | **0.3%** | **0.5%** | **0.3%** |
| **Growth 2018-2038** | **7.7%** | **8.8%** | **7.8%** | **4.23%** | **14.88%** | **4.79%** | **7.0%** | **10.1%** | **7.2%** |

Note: Excludes Military Operations.
Source: FAA 2018 TAF, NAA, CHA, 2019.

### *C. Recommended GA Forecast and Based Aircraft*

**Table D-7 – Recommended GA Forecast**

| Fiscal Year | Based Aircraft | Operations | | | | Total GA Operations |
|---|---|---|---|---|---|---|
| | | Itinerant | Local | Total Civil | Military | |
| **2017** | 87 | 21,207 | 1,157 | 22,364 | 600 | 22,964 |
| **2018** | 89 | 21,583 | 1,178 | 22,760 | 600 | 23,360 |
| **2019** | 90 | 21,965 | 1,198 | 23,164 | 600 | 23,764 |
| **2020** | 92 | 22,355 | 1,220 | 23,574 | 600 | 24,174 |
| **2021** | 93 | 22,751 | 1,241 | 23,992 | 600 | 24,592 |
| **2022** | 95 | 23,154 | 1,263 | 24,418 | 600 | 25,018 |
| **2023** | 97 | 23,565 | 1,286 | 24,850 | 600 | 25,450 |
| **2024** | 98 | 23,982 | 1,308 | 25,291 | 600 | 25,891 |
| **2025** | 100 | 24,408 | 1,332 | 25,739 | 600 | 26,339 |
| **2026** | 102 | 24,840 | 1,355 | 26,195 | 600 | 26,795 |
| **2027** | 104 | 25,280 | 1,379 | 26,660 | 600 | 27,260 |
| **2028** | 106 | 25,729 | 1,404 | 27,132 | 600 | 27,732 |
| **2029** | 107 | 26,185 | 1,429 | 27,613 | 600 | 28,213 |
| **2030** | 109 | 26,649 | 1,454 | 28,103 | 600 | 28,703 |
| **2031** | 111 | 27,121 | 1,480 | 28,601 | 600 | 29,201 |
| **2032** | 113 | 27,602 | 1,506 | 29,108 | 600 | 29,708 |
| **2033** | 115 | 28,091 | 1,533 | 29,624 | 600 | 30,224 |
| **2034** | 117 | 28,589 | 1,560 | 30,149 | 600 | 30,749 |
| **2035** | 119 | 29,096 | 1,587 | 30,683 | 600 | 31,283 |
| **2036** | 121 | 29,611 | 1,616 | 31,227 | 600 | 31,827 |
| **2037** | 124 | 30,136 | 1,644 | 31,780 | 600 | 32,380 |
| **2038** | 126 | 30,670 | 1,673 | 32,344 | 600 | 32,944 |
| **AAGR 2018-2038** | **1.8%** | **0.0%** | **0.0%** | **1.8%** | **0.0%** | **1.7%** |
| **Growth 2018-2038** | **42.1%** | **0.0%** | **0.0%** | **42.1%** | **0.0%** | **41.0%** |

Source: FAA 2018 TAF, Signature, NAA, CHA, 2019.

### Table D-8 – Based Aircraft by Aircraft Type

| Fiscal Year | Single Engine | Multi-Engine Piston | Turbo-Prop | Jet | Rotorcraft | Total |
|---|---|---|---|---|---|---|
| **2017** | 46 | 10 | 9 | 20 | 2 | 87 |
| **2018** | 46 | 10 | 10 | 21 | 2 | 89 |
| **2019** | 46 | 10 | 10 | 22 | 2 | 90 |
| **2020** | 46 | 10 | 10 | 24 | 2 | 92 |
| **2021** | 46 | 10 | 11 | 24 | 2 | 93 |
| **2022** | 47 | 10 | 11 | 25 | 2 | 95 |
| **2023** | 47 | 10 | 11 | 26 | 3 | 97 |
| **2024** | 47 | 10 | 11 | 27 | 3 | 98 |
| **2025** | 47 | 10 | 11 | 28 | 3 | 99 |
| **2026** | 48 | 10 | 12 | 29 | 3 | 102 |
| **2027** | 48 | 10 | 12 | 30 | 3 | 103 |
| **2028** | 48 | 11 | 13 | 31 | 3 | 106 |
| **2029** | 48 | 11 | 13 | 32 | 3 | 107 |
| **2030** | 48 | 11 | 14 | 33 | 3 | 109 |
| **2031** | 49 | 11 | 14 | 34 | 3 | 111 |
| **2032** | 49 | 11 | 14 | 36 | 3 | 113 |
| **2033** | 49 | 11 | 15 | 37 | 3 | 115 |
| **2034** | 50 | 11 | 15 | 38 | 3 | 117 |
| **2035** | 50 | 12 | 15 | 39 | 3 | 119 |
| **2036** | 50 | 12 | 16 | 40 | 3 | 121 |
| **2037** | 51 | 12 | 16 | 41 | 4 | 124 |
| **2038** | 51 | 12 | 17 | 42 | 4 | 126 |

Source: Signature, NAA, CHA, 2018.

# APPENDIX E – AIRPORT-PROVIDED DATA

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 10/01/2016 To: 10/31/2016

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 10/01/16 | 65 | 64 | 42 | 5 | 176 | 0 | 0 | 0 | 176 |
| 10/02/16 | 66 | 83 | 33 | 0 | 182 | 0 | 0 | 0 | 182 |
| 10/03/16 | 71 | 88 | 23 | 1 | 183 | 0 | 0 | 0 | 183 |
| 10/04/16 | 72 | 90 | 50 | 2 | 214 | 0 | 0 | 0 | 214 |
| 10/05/16 | 72 | 96 | 56 | 0 | 224 | 0 | 0 | 0 | 224 |
| 10/06/16 | 81 | 81 | 32 | 0 | 194 | 0 | 0 | 0 | 194 |
| 10/07/16 | 77 | 76 | 34 | 0 | 187 | 0 | 0 | 0 | 187 |
| 10/08/16 | 60 | 48 | 10 | 0 | 118 | 0 | 0 | 0 | 118 |
| 10/09/16 | 45 | 45 | 15 | 2 | 107 | 0 | 0 | 0 | 107 |
| 10/10/16 | 77 | 82 | 33 | 3 | 195 | 0 | 0 | 0 | 195 |
| 10/11/16 | 80 | 73 | 49 | 3 | 205 | 0 | 0 | 0 | 205 |
| 10/12/16 | 79 | 79 | 73 | 3 | 234 | 0 | 0 | 0 | 234 |
| 10/13/16 | 80 | 84 | 50 | 4 | 218 | 0 | 0 | 0 | 218 |
| 10/14/16 | 78 | 80 | 58 | 3 | 219 | 0 | 0 | 0 | 219 |
| 10/15/16 | 67 | 55 | 66 | 0 | 188 | 16 | 0 | 16 | 204 |
| 10/16/16 | 71 | 81 | 66 | 0 | 218 | 0 | 0 | 0 | 218 |
| 10/17/16 | 78 | 76 | 54 | 0 | 208 | 0 | 0 | 0 | 208 |
| 10/18/16 | 80 | 75 | 72 | 3 | 230 | 0 | 0 | 0 | 230 |
| 10/19/16 | 82 | 80 | 64 | 0 | 226 | 0 | 0 | 0 | 226 |
| 10/20/16 | 79 | 73 | 83 | 0 | 235 | 0 | 0 | 0 | 235 |
| 10/21/16 | 87 | 80 | 56 | 1 | 224 | 0 | 0 | 0 | 224 |
| 10/22/16 | 67 | 57 | 34 | 0 | 158 | 0 | 0 | 0 | 158 |
| 10/23/16 | 70 | 72 | 59 | 0 | 201 | 0 | 0 | 0 | 201 |
| 10/24/16 | 77 | 74 | 36 | 0 | 187 | 0 | 0 | 0 | 187 |
| 10/25/16 | 76 | 76 | 66 | 0 | 218 | 0 | 0 | 0 | 218 |
| 10/26/16 | 76 | 86 | 72 | 1 | 235 | 0 | 0 | 0 | 235 |
| 10/27/16 | 80 | 73 | 64 | 2 | 219 | 0 | 0 | 0 | 219 |
| 10/28/16 | 82 | 79 | 50 | 0 | 211 | 0 | 0 | 0 | 211 |
| 10/29/16 | 68 | 58 | 67 | 0 | 193 | 48 | 0 | 48 | 241 |
| 10/30/16 | 71 | 62 | 36 | 1 | 170 | 0 | 0 | 0 | 170 |
| 10/31/16 | 75 | 57 | 29 | 0 | 161 | 0 | 0 | 0 | 161 |
| Total | 2289 | 2283 | 1532 | 34 | 6138 | 64 | 0 | 64 | 6202 |

Database Range: 09/09/16 1412 - 11/10/16 1511Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 90 days on 02/08/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 11/10/2016

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 11/01/2016 To: 11/30/2016

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 11/01/16 | 82 | 80 | 49 | 4 | 215 | 0 | 0 | 0 | 215 |
| 11/02/16 | 85 | 83 | 56 | 1 | 225 | 0 | 0 | 0 | 225 |
| 11/03/16 | 81 | 77 | 74 | 0 | 232 | 0 | 0 | 0 | 232 |
| 11/04/16 | 95 | 63 | 56 | 0 | 214 | 0 | 0 | 0 | 214 |
| 11/05/16 | 78 | 43 | 138 | 0 | 259 | 32 | 0 | 32 | 291 |
| 11/06/16 | 77 | 66 | 73 | 0 | 216 | 0 | 0 | 0 | 216 |
| 11/07/16 | 82 | 61 | 52 | 1 | 196 | 0 | 0 | 0 | 196 |
| 11/08/16 | 78 | 54 | 45 | 0 | 177 | 0 | 0 | 0 | 177 |
| 11/09/16 | 91 | 60 | 46 | 4 | 201 | 0 | 0 | 0 | 201 |
| 11/10/16 | 91 | 72 | 53 | 0 | 216 | 0 | 0 | 0 | 216 |
| 11/11/16 | 92 | 64 | 88 | 0 | 244 | 4 | 0 | 4 | 248 |
| 11/12/16 | 73 | 48 | 53 | 6 | 180 | 14 | 0 | 14 | 194 |
| 11/13/16 | 77 | 53 | 61 | 1 | 192 | 16 | 0 | 16 | 208 |
| 11/14/16 | 85 | 54 | 37 | 0 | 176 | 0 | 0 | 0 | 176 |
| 11/15/16 | 87 | 68 | 59 | 0 | 214 | 0 | 0 | 0 | 214 |
| 11/16/16 | 92 | 65 | 73 | 0 | 230 | 0 | 0 | 0 | 230 |
| 11/17/16 | 90 | 68 | 71 | 0 | 229 | 0 | 0 | 0 | 229 |
| 11/18/16 | 95 | 62 | 77 | 3 | 237 | 0 | 0 | 0 | 237 |
| 11/19/16 | 72 | 35 | 58 | 0 | 165 | 6 | 0 | 6 | 171 |
| 11/20/16 | 77 | 62 | 31 | 0 | 170 | 22 | 0 | 22 | 192 |
| 11/21/16 | 91 | 61 | 34 | 0 | 186 | 0 | 0 | 0 | 186 |
| 11/22/16 | 86 | 74 | 53 | 2 | 215 | 0 | 0 | 0 | 215 |
| 11/23/16 | 90 | 63 | 57 | 0 | 210 | 0 | 0 | 0 | 210 |
| 11/24/16 | 53 | 38 | 11 | 0 | 102 | 0 | 0 | 0 | 102 |
| 11/25/16 | 71 | 43 | 33 | 0 | 147 | 0 | 0 | 0 | 147 |
| 11/26/16 | 94 | 53 | 44 | 0 | 191 | 0 | 0 | 0 | 191 |
| 11/27/16 | 80 | 64 | 52 | 0 | 196 | 12 | 0 | 12 | 208 |
| 11/28/16 | 87 | 68 | 60 | 0 | 215 | 48 | 0 | 48 | 263 |
| 11/29/16 | 93 | 53 | 44 | 0 | 190 | 0 | 0 | 0 | 190 |
| 11/30/16 | 94 | 69 | 32 | 0 | 195 | 0 | 0 | 0 | 195 |
| Total | 2519 | 1824 | 1670 | 22 | 6035 | 154 | 0 | 154 | 6189 |

Database Range: 10/05/16 1926 - 12/06/16 2025Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 64 days on 02/08/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 12/6/2016

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 12/01/2016 To: 12/31/2016

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 12/01/16 | 92 | 69 | 57 | 1 | 219 | 0 | 0 | 0 | 219 |
| 12/02/16 | 84 | 81 | 66 | 0 | 231 | 0 | 0 | 0 | 231 |
| 12/03/16 | 64 | 40 | 60 | 0 | 164 | 12 | 0 | 12 | 176 |
| 12/04/16 | 67 | 63 | 27 | 6 | 163 | 0 | 0 | 0 | 163 |
| 12/05/16 | 81 | 68 | 41 | 5 | 195 | 0 | 0 | 0 | 195 |
| 12/06/16 | 87 | 67 | 36 | 0 | 190 | 0 | 0 | 0 | 190 |
| 12/07/16 | 85 | 72 | 46 | 2 | 205 | 0 | 0 | 0 | 205 |
| 12/08/16 | 86 | 80 | 43 | 0 | 209 | 10 | 0 | 10 | 219 |
| 12/09/16 | 84 | 81 | 56 | 0 | 221 | 0 | 0 | 0 | 221 |
| 12/10/16 | 78 | 36 | 37 | 0 | 151 | 16 | 0 | 16 | 167 |
| 12/11/16 | 60 | 61 | 46 | 2 | 169 | 0 | 0 | 0 | 169 |
| 12/12/16 | 84 | 61 | 21 | 0 | 166 | 0 | 0 | 0 | 166 |
| 12/13/16 | 87 | 67 | 59 | 0 | 213 | 0 | 0 | 0 | 213 |
| 12/14/16 | 85 | 75 | 39 | 6 | 205 | 0 | 0 | 0 | 205 |
| 12/15/16 | 85 | 75 | 35 | 4 | 199 | 0 | 0 | 0 | 199 |
| 12/16/16 | 81 | 63 | 52 | 0 | 196 | 0 | 0 | 0 | 196 |
| 12/17/16 | 99 | 32 | 11 | 0 | 142 | 0 | 0 | 0 | 142 |
| 12/18/16 | 72 | 48 | 21 | 0 | 141 | 0 | 0 | 0 | 141 |
| 12/19/16 | 88 | 63 | 32 | 0 | 183 | 0 | 0 | 0 | 183 |
| 12/20/16 | 87 | 65 | 63 | 0 | 215 | 2 | 0 | 2 | 217 |
| 12/21/16 | 82 | 58 | 65 | 1 | 206 | 0 | 0 | 0 | 206 |
| 12/22/16 | 86 | 57 | 99 | 0 | 242 | 22 | 0 | 22 | 264 |
| 12/23/16 | 86 | 54 | 48 | 0 | 188 | 10 | 0 | 10 | 198 |
| 12/24/16 | 70 | 39 | 11 | 0 | 120 | 0 | 0 | 0 | 120 |
| 12/25/16 | 56 | 28 | 14 | 0 | 98 | 0 | 0 | 0 | 98 |
| 12/26/16 | 78 | 52 | 39 | 0 | 169 | 0 | 0 | 0 | 169 |
| 12/27/16 | 82 | 67 | 28 | 0 | 177 | 0 | 0 | 0 | 177 |
| 12/28/16 | 83 | 57 | 51 | 2 | 193 | 12 | 0 | 12 | 205 |
| 12/29/16 | 80 | 59 | 23 | 0 | 162 | 0 | 0 | 0 | 162 |
| 12/30/16 | 84 | 55 | 32 | 0 | 171 | 0 | 0 | 0 | 171 |
| 12/31/16 | 63 | 43 | 58 | 0 | 164 | 4 | 0 | 4 | 168 |
| Total | 2486 | 1836 | 1316 | 29 | 5667 | 88 | 0 | 88 | 5755 |

Database Range: 11/30/16 1430 - 01/31/17 1428Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 8 days on 02/08/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 1/31/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 01/01/2017 To: 01/31/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 01/01/17 | 65 | 49 | 37 | 0 | 151 | 0 | 0 | 0 | 151 |
| 01/02/17 | 77 | 67 | 20 | 0 | 164 | 0 | 0 | 0 | 164 |
| 01/03/17 | 88 | 52 | 21 | 0 | 161 | 0 | 0 | 0 | 161 |
| 01/04/17 | 93 | 56 | 47 | 0 | 196 | 0 | 0 | 0 | 196 |
| 01/05/17 | 89 | 53 | 47 | 0 | 189 | 0 | 0 | 0 | 189 |
| 01/06/17 | 76 | 60 | 28 | 0 | 164 | 10 | 0 | 10 | 174 |
| 01/07/17 | 3 | 3 | 0 | 0 | 6 | 0 | 0 | 0 | 6 |
| 01/08/17 | 60 | 51 | 29 | 1 | 141 | 0 | 0 | 0 | 141 |
| 01/09/17 | 86 | 68 | 25 | 4 | 183 | 0 | 0 | 0 | 183 |
| 01/10/17 | 74 | 71 | 34 | 0 | 179 | 0 | 0 | 0 | 179 |
| 01/11/17 | 82 | 72 | 41 | 0 | 195 | 0 | 0 | 0 | 195 |
| 01/12/17 | 82 | 62 | 55 | 2 | 201 | 6 | 0 | 6 | 207 |
| 01/13/17 | 80 | 69 | 38 | 15 | 202 | 0 | 0 | 0 | 202 |
| 01/14/17 | 62 | 37 | 24 | 0 | 123 | 12 | 0 | 12 | 135 |
| 01/15/17 | 60 | 49 | 22 | 0 | 131 | 0 | 0 | 0 | 131 |
| 01/16/17 | 77 | 68 | 31 | 0 | 176 | 0 | 0 | 0 | 176 |
| 01/17/17 | 76 | 58 | 34 | 1 | 169 | 0 | 0 | 0 | 169 |
| 01/18/17 | 80 | 64 | 47 | 0 | 191 | 0 | 0 | 0 | 191 |
| 01/19/17 | 82 | 68 | 64 | 1 | 215 | 16 | 0 | 16 | 231 |
| 01/20/17 | 80 | 77 | 34 | 0 | 191 | 0 | 0 | 0 | 191 |
| 01/21/17 | 59 | 41 | 17 | 0 | 117 | 0 | 0 | 0 | 117 |
| 01/22/17 | 66 | 58 | 13 | 0 | 137 | 0 | 0 | 0 | 137 |
| 01/23/17 | 75 | 49 | 29 | 0 | 153 | 0 | 0 | 0 | 153 |
| 01/24/17 | 76 | 68 | 55 | 0 | 199 | 0 | 0 | 0 | 199 |
| 01/25/17 | 80 | 76 | 78 | 0 | 234 | 20 | 0 | 20 | 254 |
| 01/26/17 | 86 | 66 | 31 | 0 | 183 | 0 | 0 | 0 | 183 |
| 01/27/17 | 80 | 70 | 43 | 0 | 193 | 0 | 0 | 0 | 193 |
| 01/28/17 | 58 | 48 | 96 | 0 | 202 | 46 | 0 | 46 | 248 |
| 01/29/17 | 64 | 73 | 33 | 0 | 170 | 0 | 0 | 0 | 170 |
| 01/30/17 | 74 | 62 | 45 | 2 | 183 | 0 | 0 | 0 | 183 |
| 01/31/17 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | 2190 | 1765 | 1118 | 26 | 5099 | 110 | 0 | 110 | 5209 |

Database Range: 11/30/16 1428 - 01/31/17 1427Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 8 days on 02/08/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 1/31/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 02/01/2017 To: 02/28/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 02/01/17 | 81 | 67 | 41 | 0 | 189 | 8 | 4 | 12 | 201 |
| 02/02/17 | 82 | 65 | 54 | 7 | 208 | 24 | 0 | 24 | 232 |
| 02/03/17 | 79 | 78 | 60 | 0 | 217 | 0 | 0 | 0 | 217 |
| 02/04/17 | 60 | 41 | 81 | 0 | 182 | 28 | 0 | 28 | 210 |
| 02/05/17 | 61 | 48 | 22 | 1 | 132 | 10 | 0 | 10 | 142 |
| 02/06/17 | 74 | 68 | 53 | 2 | 197 | 4 | 0 | 4 | 201 |
| 02/07/17 | 76 | 63 | 35 | 9 | 183 | 10 | 0 | 10 | 193 |
| 02/08/17 | 84 | 74 | 43 | 2 | 203 | 0 | 0 | 0 | 203 |
| 02/09/17 | 80 | 44 | 27 | 4 | 155 | 0 | 0 | 0 | 155 |
| 02/10/17 | 79 | 74 | 34 | 5 | 192 | 0 | 0 | 0 | 192 |
| 02/11/17 | 57 | 51 | 37 | 1 | 146 | 16 | 0 | 16 | 162 |
| 02/12/17 | 71 | 54 | 27 | 4 | 156 | 0 | 0 | 0 | 156 |
| 02/13/17 | 77 | 64 | 25 | 5 | 171 | 0 | 0 | 0 | 171 |
| 02/14/17 | 74 | 68 | 47 | 7 | 196 | 0 | 0 | 0 | 196 |
| 02/15/17 | 79 | 68 | 36 | 0 | 183 | 20 | 0 | 20 | 203 |
| 02/16/17 | 80 | 65 | 33 | 1 | 179 | 0 | 0 | 0 | 179 |
| 02/17/17 | 89 | 61 | 60 | 15 | 225 | 10 | 0 | 10 | 235 |
| 02/18/17 | 60 | 45 | 99 | 1 | 205 | 42 | 0 | 42 | 247 |
| 02/19/17 | 73 | 52 | 50 | 0 | 175 | 18 | 0 | 18 | 193 |
| 02/20/17 | 80 | 64 | 58 | 0 | 202 | 0 | 0 | 0 | 202 |
| 02/21/17 | 85 | 60 | 46 | 0 | 191 | 0 | 0 | 0 | 191 |
| 02/22/17 | 86 | 55 | 56 | 1 | 198 | 0 | 0 | 0 | 198 |
| 02/23/17 | 83 | 66 | 45 | 2 | 196 | 2 | 0 | 2 | 198 |
| 02/24/17 | 85 | 70 | 64 | 0 | 219 | 0 | 0 | 0 | 219 |
| 02/25/17 | 67 | 47 | 60 | 2 | 176 | 28 | 0 | 28 | 204 |
| 02/26/17 | 71 | 62 | 55 | 0 | 188 | 0 | 0 | 0 | 188 |
| 02/27/17 | 79 | 65 | 26 | 0 | 170 | 0 | 0 | 0 | 170 |
| 02/28/17 | 81 | 60 | 30 | 0 | 171 | 0 | 0 | 0 | 171 |
| Total | 2133 | 1699 | 1304 | 69 | 5205 | 220 | 4 | 224 | 5429 |

Database Range: 01/12/17 1603 - 03/15/17 1502Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 90 days on 06/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 3/15/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 03/01/2017 To: 03/31/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 03/01/17 | 90 | 57 | 36 | 0 | 183 | 0 | 0 | 0 | 183 |
| 03/02/17 | 88 | 58 | 36 | 4 | 186 | 40 | 0 | 40 | 226 |
| 03/03/17 | 85 | 64 | 35 | 5 | 189 | 16 | 0 | 16 | 205 |
| 03/04/17 | 61 | 55 | 74 | 0 | 190 | 18 | 0 | 18 | 208 |
| 03/05/17 | 69 | 59 | 52 | 2 | 182 | 12 | 0 | 12 | 194 |
| 03/06/17 | 81 | 65 | 41 | 2 | 189 | 0 | 0 | 0 | 189 |
| 03/07/17 | 88 | 60 | 32 | 0 | 180 | 0 | 0 | 0 | 180 |
| 03/08/17 | 86 | 64 | 37 | 5 | 192 | 0 | 0 | 0 | 192 |
| 03/09/17 | 85 | 65 | 46 | 0 | 196 | 0 | 0 | 0 | 196 |
| 03/10/17 | 81 | 63 | 31 | 0 | 175 | 14 | 0 | 14 | 189 |
| 03/11/17 | 61 | 70 | 59 | 2 | 192 | 26 | 0 | 26 | 218 |
| 03/12/17 | 67 | 56 | 43 | 1 | 167 | 6 | 0 | 6 | 173 |
| 03/13/17 | 74 | 60 | 39 | 0 | 173 | 0 | 0 | 0 | 173 |
| 03/14/17 | 60 | 23 | 15 | 0 | 98 | 0 | 0 | 0 | 98 |
| 03/15/17 | 75 | 78 | 25 | 0 | 178 | 0 | 0 | 0 | 178 |
| 03/16/17 | 85 | 69 | 48 | 0 | 202 | 6 | 0 | 6 | 208 |
| 03/17/17 | 88 | 68 | 56 | 1 | 213 | 0 | 0 | 0 | 213 |
| 03/18/17 | 61 | 47 | 34 | 0 | 142 | 4 | 0 | 4 | 146 |
| 03/19/17 | 70 | 62 | 43 | 0 | 175 | 10 | 0 | 10 | 185 |
| 03/20/17 | 80 | 67 | 75 | 2 | 224 | 0 | 0 | 0 | 224 |
| 03/21/17 | 81 | 67 | 44 | 1 | 193 | 0 | 0 | 0 | 193 |
| 03/22/17 | 83 | 67 | 29 | 2 | 181 | 0 | 0 | 0 | 181 |
| 03/23/17 | 86 | 67 | 50 | 4 | 207 | 17 | 0 | 17 | 224 |
| 03/24/17 | 77 | 79 | 52 | 0 | 208 | 0 | 0 | 0 | 208 |
| 03/25/17 | 63 | 57 | 65 | 0 | 185 | 24 | 0 | 24 | 209 |
| 03/26/17 | 68 | 62 | 47 | 1 | 178 | 22 | 0 | 22 | 200 |
| 03/27/17 | 79 | 66 | 38 | 0 | 183 | 0 | 0 | 0 | 183 |
| 03/28/17 | 90 | 66 | 33 | 0 | 189 | 0 | 0 | 0 | 189 |
| 03/29/17 | 84 | 63 | 54 | 1 | 202 | 0 | 0 | 0 | 202 |
| 03/30/17 | 83 | 61 | 72 | 0 | 216 | 0 | 0 | 0 | 216 |
| 03/31/17 | 85 | 58 | 20 | 0 | 163 | 0 | 0 | 0 | 163 |
| Total | 2414 | 1923 | 1361 | 33 | 5731 | 215 | 0 | 215 | 5946 |

Database Range: 01/31/17 1635 - 04/03/17 1533Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 71 days on 06/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 4/3/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 04/01/2017 To: 04/30/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 04/01/17 | 61 | 52 | 73 | 0 | 186 | 22 | 0 | 22 | 208 |
| 04/02/17 | 69 | 59 | 70 | 0 | 198 | 0 | 0 | 0 | 198 |
| 04/03/17 | 79 | 66 | 35 | 3 | 183 | 0 | 0 | 0 | 183 |
| 04/04/17 | 80 | 63 | 32 | 1 | 176 | 0 | 0 | 0 | 176 |
| 04/05/17 | 71 | 74 | 48 | 0 | 193 | 0 | 0 | 0 | 193 |
| 04/06/17 | 85 | 56 | 23 | 2 | 166 | 0 | 0 | 0 | 166 |
| 04/07/17 | 71 | 72 | 38 | 0 | 181 | 0 | 0 | 0 | 181 |
| 04/08/17 | 51 | 55 | 59 | 0 | 165 | 16 | 0 | 16 | 181 |
| 04/09/17 | 65 | 78 | 47 | 0 | 190 | 8 | 0 | 8 | 198 |
| 04/10/17 | 76 | 79 | 50 | 3 | 208 | 0 | 0 | 0 | 208 |
| 04/11/17 | 86 | 73 | 61 | 2 | 222 | 14 | 0 | 14 | 236 |
| 04/12/17 | 82 | 74 | 66 | 4 | 226 | 0 | 0 | 0 | 226 |
| 04/13/17 | 86 | 81 | 65 | 2 | 234 | 0 | 0 | 0 | 234 |
| 04/14/17 | 84 | 77 | 35 | 3 | 199 | 0 | 10 | 10 | 209 |
| 04/15/17 | 57 | 67 | 21 | 0 | 145 | 8 | 0 | 8 | 153 |
| 04/16/17 | 66 | 71 | 39 | 0 | 176 | 0 | 0 | 0 | 176 |
| 04/17/17 | 78 | 83 | 32 | 0 | 193 | 0 | 0 | 0 | 193 |
| 04/18/17 | 83 | 73 | 56 | 8 | 220 | 0 | 0 | 0 | 220 |
| 04/19/17 | 81 | 70 | 29 | 0 | 180 | 0 | 0 | 0 | 180 |
| 04/20/17 | 84 | 71 | 59 | 4 | 218 | 0 | 0 | 0 | 218 |
| 04/21/17 | 85 | 69 | 65 | 2 | 221 | 0 | 0 | 0 | 221 |
| 04/22/17 | 60 | 64 | 25 | 1 | 150 | 0 | 0 | 0 | 150 |
| 04/23/17 | 69 | 66 | 27 | 1 | 163 | 0 | 0 | 0 | 163 |
| 04/24/17 | 83 | 71 | 12 | 2 | 168 | 0 | 0 | 0 | 168 |
| 04/25/17 | 84 | 59 | 54 | 2 | 199 | 0 | 0 | 0 | 199 |
| 04/26/17 | 86 | 70 | 55 | 2 | 213 | 0 | 0 | 0 | 213 |
| 04/27/17 | 84 | 72 | 87 | 1 | 244 | 11 | 0 | 11 | 255 |
| 04/28/17 | 83 | 77 | 25 | 4 | 189 | 10 | 14 | 24 | 213 |
| 04/29/17 | 62 | 62 | 35 | 3 | 162 | 0 | 0 | 0 | 162 |
| 04/30/17 | 71 | 70 | 47 | 2 | 190 | 0 | 0 | 0 | 190 |
| Total | 2262 | 2074 | 1370 | 52 | 5758 | 89 | 24 | 113 | 5871 |

Database Range: 03/14/17 1325 - 05/15/17 1322Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 29 days on 06/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 5/15/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 05/01/2017 To: 05/31/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 05/01/17 | 83 | 75 | 29 | 0 | 187 | 0 | 0 | 0 | 187 |
| 05/02/17 | 88 | 70 | 48 | 5 | 211 | 2 | 6 | 8 | 219 |
| 05/03/17 | 86 | 71 | 70 | 3 | 230 | 0 | 0 | 0 | 230 |
| 05/04/17 | 91 | 76 | 72 | 1 | 240 | 22 | 0 | 22 | 262 |
| 05/05/17 | 88 | 59 | 24 | 0 | 171 | 0 | 0 | 0 | 171 |
| 05/06/17 | 67 | 55 | 38 | 2 | 162 | 0 | 0 | 0 | 162 |
| 05/07/17 | 73 | 71 | 58 | 3 | 205 | 0 | 0 | 0 | 205 |
| 05/08/17 | 85 | 72 | 45 | 6 | 208 | 0 | 0 | 0 | 208 |
| 05/09/17 | 88 | 66 | 56 | 7 | 217 | 0 | 0 | 0 | 217 |
| 05/10/17 | 85 | 70 | 62 | 6 | 223 | 0 | 0 | 0 | 223 |
| 05/11/17 | 89 | 77 | 77 | 6 | 249 | 0 | 0 | 0 | 249 |
| 05/12/17 | 89 | 72 | 45 | 0 | 206 | 0 | 0 | 0 | 206 |
| 05/13/17 | 68 | 61 | 35 | 0 | 164 | 0 | 0 | 0 | 164 |
| 05/14/17 | 72 | 73 | 31 | 1 | 177 | 14 | 0 | 14 | 191 |
| 05/15/17 | 82 | 65 | 58 | 1 | 206 | 0 | 0 | 0 | 206 |
| 05/16/17 | 86 | 73 | 62 | 2 | 223 | 0 | 0 | 0 | 223 |
| 05/17/17 | 89 | 71 | 59 | 5 | 224 | 0 | 0 | 0 | 224 |
| 05/18/17 | 85 | 67 | 80 | 3 | 235 | 0 | 0 | 0 | 235 |
| 05/19/17 | 89 | 67 | 75 | 3 | 234 | 4 | 0 | 4 | 238 |
| 05/20/17 | 65 | 61 | 35 | 3 | 164 | 0 | 0 | 0 | 164 |
| 05/21/17 | 74 | 66 | 48 | 3 | 191 | 0 | 0 | 0 | 191 |
| 05/22/17 | 81 | 63 | 29 | 2 | 175 | 0 | 0 | 0 | 175 |
| 05/23/17 | 89 | 74 | 25 | 2 | 190 | 0 | 0 | 0 | 190 |
| 05/24/17 | 85 | 72 | 31 | 1 | 189 | 0 | 0 | 0 | 189 |
| 05/25/17 | 88 | 52 | 52 | 1 | 193 | 0 | 0 | 0 | 193 |
| 05/26/17 | 93 | 78 | 70 | 2 | 243 | 0 | 0 | 0 | 243 |
| 05/27/17 | 62 | 65 | 34 | 0 | 161 | 0 | 0 | 0 | 161 |
| 05/28/17 | 71 | 64 | 28 | 1 | 164 | 12 | 0 | 12 | 176 |
| 05/29/17 | 75 | 65 | 34 | 1 | 175 | 0 | 0 | 0 | 175 |
| 05/30/17 | 82 | 52 | 36 | 0 | 170 | 0 | 0 | 0 | 170 |
| 05/31/17 | 87 | 66 | 63 | 6 | 222 | 0 | 0 | 0 | 222 |
| Total | 2535 | 2089 | 1509 | 76 | 6209 | 54 | 6 | 60 | 6269 |

Database Range: 04/14/17 1831 - 06/15/17 1829Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 90 days on 09/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 6/15/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 06/01/2017 To: 06/30/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 06/01/17 | 91 | 65 | 69 | 3 | 228 | 0 | 0 | 0 | 228 |
| 06/02/17 | 85 | 77 | 55 | 0 | 217 | 0 | 0 | 0 | 217 |
| 06/03/17 | 62 | 69 | 42 | 2 | 175 | 0 | 0 | 0 | 175 |
| 06/04/17 | 73 | 76 | 49 | 3 | 201 | 0 | 0 | 0 | 201 |
| 06/05/17 | 80 | 67 | 35 | 0 | 182 | 0 | 0 | 0 | 182 |
| 06/06/17 | 86 | 80 | 51 | 2 | 219 | 0 | 0 | 0 | 219 |
| 06/07/17 | 86 | 67 | 47 | 4 | 204 | 0 | 0 | 0 | 204 |
| 06/08/17 | 88 | 74 | 60 | 1 | 223 | 0 | 0 | 0 | 223 |
| 06/09/17 | 85 | 78 | 80 | 0 | 243 | 0 | 0 | 0 | 243 |
| 06/10/17 | 77 | 67 | 59 | 0 | 203 | 0 | 0 | 0 | 203 |
| 06/11/17 | 80 | 67 | 52 | 0 | 199 | 0 | 0 | 0 | 199 |
| 06/12/17 | 85 | 70 | 55 | 1 | 211 | 0 | 0 | 0 | 211 |
| 06/13/17 | 89 | 72 | 51 | 0 | 212 | 0 | 0 | 0 | 212 |
| 06/14/17 | 90 | 76 | 68 | 3 | 237 | 0 | 0 | 0 | 237 |
| 06/15/17 | 85 | 96 | 62 | 1 | 244 | 0 | 0 | 0 | 244 |
| 06/16/17 | 88 | 70 | 41 | 0 | 199 | 0 | 0 | 0 | 199 |
| 06/17/17 | 82 | 66 | 40 | 0 | 188 | 0 | 0 | 0 | 188 |
| 06/18/17 | 80 | 68 | 30 | 3 | 181 | 0 | 0 | 0 | 181 |
| 06/19/17 | 100 | 48 | 42 | 1 | 191 | 0 | 0 | 0 | 191 |
| 06/20/17 | 95 | 70 | 43 | 1 | 209 | 0 | 0 | 0 | 209 |
| 06/21/17 | 88 | 75 | 50 | 0 | 213 | 0 | 0 | 0 | 213 |
| 06/22/17 | 87 | 86 | 83 | 13 | 269 | 8 | 0 | 8 | 277 |
| 06/23/17 | 88 | 74 | 57 | 3 | 222 | 0 | 0 | 0 | 222 |
| 06/24/17 | 81 | 59 | 30 | 0 | 170 | 0 | 0 | 0 | 170 |
| 06/25/17 | 86 | 72 | 57 | 0 | 215 | 0 | 0 | 0 | 215 |
| 06/26/17 | 84 | 74 | 42 | 2 | 202 | 0 | 0 | 0 | 202 |
| 06/27/17 | 87 | 72 | 63 | 2 | 224 | 0 | 0 | 0 | 224 |
| 06/28/17 | 94 | 74 | 73 | 2 | 243 | 16 | 6 | 22 | 265 |
| 06/29/17 | 90 | 80 | 66 | 1 | 237 | 0 | 0 | 0 | 237 |
| 06/30/17 | 90 | 72 | 61 | 0 | 223 | 0 | 0 | 0 | 223 |
| Total | 2562 | 2161 | 1613 | 48 | 6384 | 24 | 6 | 30 | 6414 |

Database Range: 05/09/17 1947 - 07/10/17 1945Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 65 days on 09/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 7/10/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 07/01/2017 To: 07/31/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 07/01/17 | 82 | 60 | 23 | 0 | 165 | 0 | 0 | 0 | 165 |
| 07/02/17 | 73 | 59 | 40 | 0 | 172 | 0 | 0 | 0 | 172 |
| 07/03/17 | 70 | 58 | 32 | 2 | 162 | 0 | 0 | 0 | 162 |
| 07/04/17 | 69 | 69 | 27 | 0 | 165 | 0 | 0 | 0 | 165 |
| 07/05/17 | 78 | 73 | 56 | 1 | 208 | 0 | 0 | 0 | 208 |
| 07/06/17 | 84 | 72 | 55 | 0 | 211 | 0 | 0 | 0 | 211 |
| 07/07/17 | 90 | 73 | 47 | 0 | 210 | 0 | 0 | 0 | 210 |
| 07/08/17 | 81 | 59 | 42 | 0 | 182 | 0 | 0 | 0 | 182 |
| 07/09/17 | 89 | 68 | 55 | 0 | 212 | 0 | 0 | 0 | 212 |
| 07/10/17 | 79 | 67 | 30 | 0 | 176 | 0 | 0 | 0 | 176 |
| 07/11/17 | 87 | 79 | 46 | 0 | 212 | 0 | 0 | 0 | 212 |
| 07/12/17 | 85 | 74 | 60 | 6 | 225 | 0 | 0 | 0 | 225 |
| 07/13/17 | 90 | 64 | 47 | 0 | 201 | 0 | 0 | 0 | 201 |
| 07/14/17 | 97 | 78 | 57 | 2 | 234 | 0 | 0 | 0 | 234 |
| 07/15/17 | 74 | 71 | 33 | 0 | 178 | 0 | 0 | 0 | 178 |
| 07/16/17 | 84 | 72 | 51 | 4 | 211 | 0 | 0 | 0 | 211 |
| 07/17/17 | 81 | 67 | 47 | 1 | 196 | 0 | 0 | 0 | 196 |
| 07/18/17 | 90 | 82 | 51 | 2 | 225 | 0 | 0 | 0 | 225 |
| 07/19/17 | 85 | 81 | 56 | 0 | 222 | 0 | 0 | 0 | 222 |
| 07/20/17 | 86 | 88 | 50 | 1 | 225 | 0 | 0 | 0 | 225 |
| 07/21/17 | 91 | 87 | 77 | 4 | 259 | 0 | 0 | 0 | 259 |
| 07/22/17 | 80 | 64 | 44 | 6 | 194 | 10 | 0 | 10 | 204 |
| 07/23/17 | 102 | 70 | 59 | 0 | 231 | 0 | 0 | 0 | 231 |
| 07/24/17 | 76 | 74 | 51 | 0 | 201 | 0 | 0 | 0 | 201 |
| 07/25/17 | 86 | 86 | 49 | 8 | 229 | 0 | 0 | 0 | 229 |
| 07/26/17 | 87 | 90 | 65 | 11 | 253 | 0 | 6 | 6 | 259 |
| 07/27/17 | 85 | 90 | 69 | 0 | 244 | 0 | 0 | 0 | 244 |
| 07/28/17 | 85 | 71 | 54 | 0 | 210 | 4 | 0 | 4 | 214 |
| 07/29/17 | 79 | 70 | 27 | 0 | 176 | 0 | 0 | 0 | 176 |
| 07/30/17 | 84 | 69 | 44 | 2 | 199 | 0 | 0 | 0 | 199 |
| 07/31/17 | 81 | 80 | 55 | 0 | 216 | 0 | 0 | 0 | 216 |
| Total | 2590 | 2265 | 1499 | 50 | 6404 | 14 | 6 | 20 | 6424 |

Database Range: 06/02/17 1447 - 08/03/17 1446Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 41 days on 09/13/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 8/3/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 08/01/2017 To: 08/31/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 08/01/17 | 88 | 82 | 51 | 4 | 225 | 0 | 0 | 0 | 225 |
| 08/02/17 | 92 | 64 | 35 | 1 | 192 | 4 | 0 | 4 | 196 |
| 08/03/17 | 89 | 78 | 57 | 0 | 224 | 0 | 0 | 0 | 224 |
| 08/04/17 | 78 | 67 | 48 | 0 | 193 | 2 | 0 | 2 | 195 |
| 08/05/17 | 79 | 68 | 44 | 0 | 191 | 0 | 0 | 0 | 191 |
| 08/06/17 | 86 | 77 | 66 | 0 | 229 | 0 | 0 | 0 | 229 |
| 08/07/17 | 77 | 82 | 29 | 0 | 188 | 0 | 0 | 0 | 188 |
| 08/08/17 | 89 | 79 | 52 | 0 | 220 | 0 | 0 | 0 | 220 |
| 08/09/17 | 86 | 87 | 50 | 0 | 223 | 0 | 0 | 0 | 223 |
| 08/10/17 | 85 | 91 | 60 | 2 | 238 | 0 | 0 | 0 | 238 |
| 08/11/17 | 89 | 73 | 45 | 5 | 212 | 0 | 0 | 0 | 212 |
| 08/12/17 | 78 | 63 | 21 | 0 | 162 | 0 | 0 | 0 | 162 |
| 08/13/17 | 93 | 64 | 58 | 2 | 217 | 0 | 0 | 0 | 217 |
| 08/14/17 | 82 | 88 | 54 | 0 | 224 | 0 | 0 | 0 | 224 |
| 08/15/17 | 88 | 75 | 56 | 4 | 223 | 0 | 0 | 0 | 223 |
| 08/16/17 | 86 | 75 | 71 | 0 | 232 | 0 | 0 | 0 | 232 |
| 08/17/17 | 86 | 77 | 86 | 1 | 250 | 14 | 0 | 14 | 264 |
| 08/18/17 | 97 | 74 | 49 | 3 | 223 | 0 | 0 | 0 | 223 |
| 08/19/17 | 77 | 60 | 36 | 0 | 173 | 6 | 0 | 6 | 179 |
| 08/20/17 | 79 | 77 | 38 | 0 | 194 | 20 | 0 | 20 | 214 |
| 08/21/17 | 80 | 74 | 52 | 0 | 206 | 0 | 0 | 0 | 206 |
| 08/22/17 | 91 | 80 | 59 | 0 | 230 | 0 | 0 | 0 | 230 |
| 08/23/17 | 90 | 76 | 52 | 2 | 220 | 0 | 0 | 0 | 220 |
| 08/24/17 | 88 | 84 | 74 | 1 | 247 | 0 | 0 | 0 | 247 |
| 08/25/17 | 108 | 77 | 46 | 0 | 231 | 0 | 0 | 0 | 231 |
| 08/26/17 | 71 | 56 | 62 | 0 | 189 | 18 | 0 | 18 | 207 |
| 08/27/17 | 77 | 79 | 45 | 1 | 202 | 0 | 0 | 0 | 202 |
| 08/28/17 | 81 | 74 | 34 | 12 | 201 | 0 | 0 | 0 | 201 |
| 08/29/17 | 97 | 72 | 14 | 0 | 183 | 0 | 0 | 0 | 183 |
| 08/30/17 | 85 | 82 | 54 | 4 | 225 | 0 | 0 | 0 | 225 |
| 08/31/17 | 88 | 81 | 74 | 4 | 247 | 0 | 0 | 0 | 247 |
| Total | 2660 | 2336 | 1572 | 46 | 6614 | 64 | 0 | 64 | 6678 |

Database Range: 07/11/17 1427 - 09/11/17 1425Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - **Password expires THIS WEEK on 09/13/2017**

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 9/11/2017

Norfolk ATCT CountOps - Tower Historical Airport Operations Count

Page 1 of 1

## Tower Daily Airport Operations (-1) Count

☐ New Format ☐ Display Manual Count ONLY

Selected Date From: 09/01/2017 To: 09/30/2017

Display: ORF Save Airport

View/Refresh Home

| ORF | Itinerant | | | | | Local | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|
| Date | AC | AT | GA | MI | Total | Civil | Military | Total | |
| 09/01/17 | 90 | 80 | 41 | 1 | 212 | 0 | 0 | 0 | 212 |
| 09/02/17 | 73 | 58 | 16 | 0 | 147 | 0 | 0 | 0 | 147 |
| 09/03/17 | 58 | 68 | 65 | 0 | 191 | 8 | 0 | 8 | 199 |
| 09/04/17 | 72 | 77 | 44 | 0 | 193 | 0 | 0 | 0 | 193 |
| 09/05/17 | 83 | 69 | 58 | 0 | 210 | 0 | 0 | 0 | 210 |
| 09/06/17 | 79 | 83 | 31 | 0 | 193 | 0 | 0 | 0 | 193 |
| 09/07/17 | 80 | 78 | 67 | 0 | 225 | 0 | 0 | 0 | 225 |
| 09/08/17 | 81 | 89 | 50 | 0 | 220 | 18 | 0 | 18 | 238 |
| 09/09/17 | 65 | 57 | 40 | 1 | 163 | 12 | 0 | 12 | 175 |
| 09/10/17 | 67 | 72 | 35 | 0 | 174 | 0 | 0 | 0 | 174 |
| 09/11/17 | 69 | 72 | 24 | 2 | 167 | 0 | 0 | 0 | 167 |
| 09/12/17 | 80 | 82 | 31 | 2 | 195 | 16 | 0 | 16 | 211 |
| 09/13/17 | 85 | 90 | 42 | 1 | 218 | 0 | 0 | 0 | 218 |
| 09/14/17 | 86 | 83 | 44 | 1 | 214 | 0 | 0 | 0 | 214 |
| 09/15/17 | 90 | 89 | 57 | 3 | 239 | 3 | 0 | 3 | 242 |
| 09/16/17 | 68 | 63 | 45 | 0 | 176 | 0 | 0 | 0 | 176 |
| 09/17/17 | 71 | 82 | 42 | 1 | 196 | 0 | 0 | 0 | 196 |
| 09/18/17 | 85 | 84 | 43 | 0 | 212 | 0 | 0 | 0 | 212 |
| 09/19/17 | 83 | 78 | 24 | 3 | 188 | 0 | 0 | 0 | 188 |
| 09/20/17 | 81 | 78 | 83 | 0 | 242 | 2 | 2 | 4 | 246 |
| 09/21/17 | 87 | 83 | 66 | 0 | 236 | 0 | 0 | 0 | 236 |
| 09/22/17 | 90 | 85 | 50 | 0 | 225 | 0 | 30 | 30 | 255 |
| 09/23/17 | 65 | 56 | 57 | 0 | 178 | 0 | 0 | 0 | 178 |
| 09/24/17 | 69 | 82 | 40 | 0 | 191 | 0 | 0 | 0 | 191 |
| 09/25/17 | 83 | 83 | 39 | 0 | 205 | 0 | 0 | 0 | 205 |
| 09/26/17 | 89 | 83 | 38 | 2 | 212 | 0 | 0 | 0 | 212 |
| 09/27/17 | 83 | 91 | 37 | 1 | 212 | 0 | 0 | 0 | 212 |
| 09/28/17 | 85 | 87 | 64 | 4 | 240 | 2 | 14 | 16 | 256 |
| 09/29/17 | 88 | 88 | 77 | 0 | 253 | 0 | 0 | 0 | 253 |
| 09/30/17 | 67 | 65 | 35 | 1 | 168 | 0 | 0 | 0 | 168 |
| Total | 2352 | 2335 | 1385 | 23 | 6095 | 61 | 46 | 107 | 6202 |

Database Range: 08/22/17 1300 - 10/23/17 1258Z

Request Your Interim or Annual Validation Spreadsheet Here
Please report any problems with this web interface here.
Click here for CountOps support information.
Logged in as fm - Password expires in 48 days on 12/10/2017

http://orf.countops.faa.gov:5806/TowerApoDash1CountFromSummaryPage 10/23/2017

# APPENDIX F – ORF SCHEDULING DATA

## Table F-1 – ORF Scheduling Data

| ARRIVALS | | | | | DEPARTURES | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Origin | Flight Number | Arrival Time | Airline | Aircraft | Destination | Flight Number | Departure Time | Airline | Aircraft |
| MSP | 3474 | 00:11:00 | DL | CR9 | LGA | 3634 | 05:25:00 | AA | ERD |
| ATL | 2095 | 00:22:00 | DL | M90 | DCA | 5520 | 05:29:00 | AA | CR2 |
| MDW | 2255 | 01:10:00 | WN | 73H | ATL | 2557 | 05:40:00 | DL | M90 |
| BOS | 5387 | 08:05:00 | DL | CR9 | MDW | 1480 | 05:40:00 | WN | 73H |
| TPA | ---- | --:--:-- | F9 | A320 | CLT | 5532 | 05:47:00 | AA | CR7 |
| EWR | 4918 | 08:21:00 | UA | ERJ | PHL | 5546 | 06:00:00 | AA | CR7 |
| CLT | 5045 | 08:57:00 | AA | CR7 | LGA | 5021 | 06:00:00 | DL | CR9 |
| BWI | 1418 | 09:10:00 | WN | 73W | EWR | 4016 | 06:00:00 | UA | ERJ |
| ORD | 1892 | 09:13:00 | UA | 739 | IAD | 1443 | 06:20:00 | UA | 73G |
| PHL | 5008 | 09:15:00 | AA | ER4 | BWI | 1222 | 06:25:00 | WN | 73W |
| ATL | 1113 | 09:19:00 | DL | M88 | IAH | 6160 | 06:46:00 | UA | E7W |
| IAD | 6018 | 09:32:00 | UA | CR7 | ATL | 1183 | 07:00:00 | DL | 757 |
| DCA | 5104 | 09:36:00 | AA | CR2 | MIA | 4706 | 07:06:00 | AA | E75 |
| SFB | 626 | 09:48:00 | G4 | M80 | DFW | 1615 | 07:10:00 | AA | M82 |
| JFK | 3437 | 09:55:00 | DL | CR9 | CLT | 1917 | 07:17:00 | AA | 319 |
| LGA | 5701 | 09:59:00 | AA | CR2 | ORD | 1637 | 07:25:00 | UA | 738 |
| ORD | 2973 | 10:10:00 | AA | CR2 | DTW | 6245 | 07:30:00 | DL | CR7 |
| LGA | 5266 | 10:17:00 | DL | CRJ | JFK | 5203 | 07:33:00 | DL | CRJ |
| CLT | 837 | 10:26:00 | AA | 319 | ORD | 3682 | 07:53:00 | AA | CR7 |
| DTW | 6278 | 10:35:00 | DL | CR7 | PHL | 5088 | 08:10:00 | AA | CR7 |
| MCO | 2114 | 10:55:00 | WN | 73W | DEN | 2273 | 08:15:00 | UA | 319 |
| DFW | 2274 | 11:01:00 | AA | M82 | ATL | 1252 | 08:20:00 | DL | 757 |
| MIA | 3817 | 11:05:00 | AA | ER4 | MSP | 3498 | 08:40:00 | DL | CR9 |
| BWI | 127 | 11:40:00 | WN | 73W | EWR | 4925 | 08:51:00 | UA | ERJ |
| ATL | 2074 | 11:51:00 | DL | M90 | TPA | ---- | --:--:-- | F9 | A320 |
| LGA | 5087 | 11:54:00 | DL | CR9 | LGA | 3344 | 09:11:00 | AA | ERD |
| DCA | 5226 | 12:22:00 | AA | CR2 | CLT | 5045 | 09:27:00 | AA | CR7 |
| LGA | 3970 | 13:03:00 | AA | ERD | PHL | 5008 | 09:44:00 | AA | ER4 |
| EWR | 4919 | 13:03:00 | UA | ERJ | BWI | 2310 | 09:45:00 | WN | 73W |
| CLT | 676 | 13:07:00 | AA | 319 | ATL | 1113 | 10:00:00 | DL | M88 |
| PHL | 4865 | 13:08:00 | AA | ER4 | ORD | 2249 | 10:18:00 | UA | 739 |
| FLL | 1758 | 13:18:00 | G4 | 320 | DCA | 5101 | 10:24:00 | AA | CR2 |
| PHX | ---- | --:--:-- | F9 | A320 | IAD | 6018 | 10:25:00 | UA | CR7 |
| IAD | 1144 | 13:52:00 | UA | 738 | JFK | 3510 | 10:30:00 | DL | CR9 |
| ATL | 2141 | 14:21:00 | DL | M88 | SFB | 627 | 10:33:00 | G4 | M80 |
| DFW | 320 | 14:23:00 | AA | M82 | ORD | 2973 | 10:40:00 | AA | CR2 |
| DTW | 5166 | 14:33:00 | DL | CR9 | LGA | 5297 | 10:47:00 | DL | CRJ |
| PHL | 4895 | 14:35:00 | AA | ER4 | LGA | 5702 | 10:50:00 | AA | CR2 |
| LGA | 5324 | 14:37:00 | DL | CRJ | CLT | 837 | 11:06:00 | AA | 319 |
| BWI | 2374 | 14:50:00 | WN | 73W | DTW | 6278 | 11:10:00 | DL | CR7 |
| ORD | 4511 | 14:52:00 | UA | CR7 | MCO | 1972 | 11:30:00 | WN | 73W |
| ORD | 3782 | 15:35:00 | AA | CR7 | DFW | 2274 | 11:41:00 | AA | M82 |
| CLT | 5447 | 16:01:00 | AA | CR2 | MIA | 3817 | 11:41:00 | AA | ER4 |
| ATL | 2206 | 16:04:00 | DL | M88 | BWI | 2329 | 12:10:00 | WN | 73W |
| JFK | 5142 | 16:34:00 | DL | CRJ | LGA | 5103 | 12:30:00 | DL | CR9 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| EWR | 4998 | 16:34:00 | UA | ERJ | ATL | 2074 | 12:31:00 | DL | M90 |
| MDW | 1756 | 16:45:00 | WN | 73W | CLT | 5610 | 12:47:00 | AA | CR2 |
| CLT | 867 | 16:58:00 | AA | 319 | JFK | 3846 | 13:28:00 | AA | ERD |
| MIA | 3367 | 17:21:00 | AA | ER4 | PHL | 4865 | 13:34:00 | AA | ER4 |
| BWI | 479 | 17:30:00 | WN | 73W | EWR | 4948 | 13:35:00 | UA | ERJ |
| DTW | 6281 | 17:36:00 | DL | CR7 | CLT | 676 | 13:47:00 | AA | 319 |
| ORD | 4516 | 17:39:00 | UA | CR7 | FLL | 1759 | 14:03:00 | G4 | 320 |
| JFK | 3390 | 17:41:00 | AA | ERD | IAD | 1618 | 14:45:00 | UA | 738 |
| LGA | 4073 | 17:43:00 | DL | CRJ | PHL | 4895 | 15:00:00 | AA | ER4 |
| ATL | 1378 | 17:49:00 | DL | M88 | ATL | 2141 | 15:01:00 | DL | M88 |
| PHL | 5124 | 17:56:00 | AA | CR7 | DTW | 5166 | 15:08:00 | DL | CR9 |
| LGA | 3874 | 18:31:00 | AA | ERD | LGA | 5319 | 15:10:00 | DL | CRJ |
| IAD | 6025 | 18:31:00 | UA | CR7 | BWI | 205 | 15:20:00 | WN | 73W |
| EWR | 3505 | 18:33:00 | UA | E70 | ORD | 4536 | 15:30:00 | UA | CR7 |
| CLT | 5694 | 19:06:00 | AA | CR9 | DFW | 320 | 15:35:00 | AA | M82 |
| LGA | 5261 | 19:16:00 | DL | CR9 | ORD | 3782 | 16:07:00 | AA | CR7 |
| ATL | 1685 | 19:19:00 | DL | M88 | ATL | 2206 | 16:46:00 | DL | M88 |
| PHL | 5268 | 19:41:00 | AA | CR7 | JFK | 3345 | 17:04:00 | DL | CRJ |
| DCA | 5367 | 20:29:00 | AA | CR2 | EWR | 4962 | 17:05:00 | UA | ERJ |
| CLT | 5369 | 20:59:00 | AA | CR7 | MDW | 2569 | 17:15:00 | WN | 73W |
| ORD | 658 | 21:13:00 | UA | 73G | DCA | 5510 | 17:18:00 | AA | CR2 |
| JFK | 3749 | 21:41:00 | AA | ERD | CLT | 867 | 17:38:00 | AA | 319 |
| ATL | 1247 | 21:43:00 | DL | 757 | BWI | 460 | 18:05:00 | WN | 73W |
| ORD | 4104 | 21:52:00 | AA | CR7 | JFK | 3390 | 18:08:00 | AA | ERD |
| PHL | 5692 | 21:56:00 | AA | CR7 | DTW | 6281 | 18:11:00 | DL | CR7 |
| IAH | 6247 | 22:17:00 | UA | E7W | MIA | 3367 | 18:13:00 | AA | ER4 |
| DTW | 6187 | 22:29:00 | DL | CR7 | LGA | 5312 | 18:20:00 | DL | CRJ |
| DFW | 2587 | 22:33:00 | AA | M82 | ATL | 1378 | 18:30:00 | DL | M88 |
| LGA | 3513 | 22:46:00 | AA | ERD | ORD | 4545 | 18:30:00 | UA | CR7 |
| ATL | 2275 | 23:00:00 | DL | 757 | PHL | 5124 | 18:36:00 | AA | CR7 |
| DEN | 2272 | 23:08:00 | UA | 319 | LGA | 3874 | 18:56:00 | AA | ERD |
| JFK | 5315 | 23:25:00 | DL | CRJ | EWR | 3628 | 19:10:00 | UA | E70 |
| EWR | 4266 | 23:30:00 | UA | ERJ | PHX | ---- | --:--:-- | F9 | A320 |
| CLT | 1938 | 23:34:00 | AA | 319 | IAD | 6025 | 19:45:00 | UA | CR7 |
| BWI | 1096 | 23:35:00 | WN | 73W | CLT | 5694 | 19:54:00 | AA | CR9 |
| IAD | 1807 | 23:36:00 | UA | 738 | BOS | 5402 | 19:57:00 | DL | CR9 |
| MIA | 4714 | 23:56:00 | AA | E75 | ATL | 1685 | 19:59:00 | DL | M88 |

Note: Schedule for a standard Friday in July (2018).
Source: FlightAware, CHA, 2018.

# APPENDIX G – FAA REQUIRED APPENDICES[34]

***FAA Appendix B***

**Summarizing and Documenting Airport Planning Forecasts**

**Table G-1 – Forecast Levels and Growth Rates**

| Specified Base Year: 2017 | Forecast Levels | | | | | | Average Annual Compound Growth Rates | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Base Year Level | Base Year + 1-Year | Base Year + 6-Years | Base Year + 11-Years | Base Year + 16-Years | Base Year + 21-Years | Base Year to + 1 | Base Year to + 6 | Base Year to +11 | Base Year to +16 | Base Year to +21 |
| **Passenger Enplanements** | | | | | | | | | | | |
| Air Carrier | 1,672,024 | 1,857,487 | 2,115,424 | 2,376,990 | 2,622,848 | 2,834,623 | 11.1% | 4.0% | 3.2% | 2.9% | 2.5% |
| **Operations** | | | | | | | | | | | |
| **Itinerant** | - | - | - | - | - | - | - | - | - | - | - |
| Air Carrier | 47,195 | 48,986 | 51,889 | 55,177 | 57,488 | 61,430 | 3.8% | 1.6% | 1.4% | 1.2% | 1.3% |
| General Aviation (Includes Cargo) | 23,636 | 24,058 | 26,284 | 28,715 | 31,372 | 34,274 | 1.8% | 1.8% | 1.8% | 1.8% | 1.8% |
| Military | 508 | 508 | 508 | 508 | 508 | 508 | 0.0% | 0.0% | 0.0% | 0.0% | 0.0% |
| **Local** | - | - | - | - | - | - | - | - | - | - | - |
| General Aviation | 1,157 | 1,178 | 1,286 | 1,404 | 1,533 | 1,673 | 1.8% | 1.8% | 1.8% | 1.8% | 1.8% |
| Military | 92 | 92 | 92 | 92 | 92 | 92 | 0.0% | 0.0% | 0.0% | 0.0% | 0.0% |
| **TOTAL OPERATIONS** | **72,588** | **74,821** | **80,058** | **85,896** | **90,992** | **97,978** | **3.1%** | **1.6%** | **1.5%** | **1.4%** | **1.4%** |
| **Peak Hour Operations** | 20 | 21 | 22 | 23 | 24 | 26 | 3.8% | 1.6% | 1.4% | 1.2% | 1.3% |
| **Cargo/mail (enplaned + deplaned tons)** | 119,634 | 121,903 | 133,910 | 147,101 | 161,590 | 177,506 | 1.9% | 1.9% | 1.9% | 1.9% | 1.9% |
| **Based Aircraft** | | | | | | | | | | | |
| Single Engine (Non-jet) | 46 | 46 | 47 | 48 | 49 | 51 | 0.0% | 0.4% | 0.4% | 0.4% | 0.5% |
| Multi Engine (Non-jet) | 10.00 | 10 | 10 | 11 | 11 | 12 | 0.0% | 0.0% | 0.9% | 0.6% | 0.9% |
| Turbo-Prop | 9.00 | 10 | 11 | 13 | 15 | 17 | 11.1% | 3.4% | 3.4% | 3.2% | 3.1% |
| Jet Engine | 20.00 | 21 | 26 | 31 | 37 | 42 | 5.0% | 4.5% | 4.1% | 3.9% | 3.6% |
| Helicopter | 2.00 | 2 | 3 | 3 | 3 | 4 | 0.0% | 7.0% | 3.8% | 2.6% | 3.4% |
| **TOTAL** | **87** | **89** | **97** | **106** | **115** | **126** | **2.3%** | **1.8%** | **1.8%** | **1.8%** | **1.8%** |

Source: FAA 2018 TAF, Signature, NAA, CHA, 2019.

**Table G-2 – Operational Factors**

| Specified Base Year: 2017 | Base Year Level | Base Year + 1-Year | Base Year + 6-Years | Base Year + 11-Years | Base Year + 16-Years | Base Year + 21-Years |
|---|---|---|---|---|---|---|
| Average Aircraft Size (Seats) - Air Carrier | 89.8 | 96.0 | 100.5 | 104.6 | 109.4 | 109.6 |
| Average enplaning load factor - Air Carrier | 79.0 | 79.5 | 81.1 | 82.4 | 83.4 | 84.2 |
| GA operations per based aircraft | 257 | 257 | 257 | 257 | 257 | 257 |

Source: FAA 2018 TAF, Signature, NAA, CHA, 201**9.**

[34] Note: The projected enplanements and operations that are found within the FAA Required Appendices take into consideration recently announced, as well as potential, non-stop service routes from ORF throughout the forecast horizon.

***FAA Appendix C***

**Table G-3 – Comparing Airport Planning and TAF Forecasts**

| Specified Base Year: 2017 | Year | Airport Forecast | TAF | AF/TAF (% Difference) |
|---|---|---|---|---|
| **Passenger Enplanements** | | | | |
| Base Year Level | **2017** | 1,672,024 | 1,652,323 | 1.2% |
| Base Year + 1-Year | **2018** | 1,857,487 | 1,815,241 | 2.3% |
| Base Year + 6-Years | **2023** | 2,115,424 | 2,147,644 | -1.5% |
| Base Year + 11-Years | **2028** | 2,376,990 | 2,294,704 | 3.6% |
| Base Year + 16-Years | **2033** | 2,622,848 | 2,458,050 | 6.7% |
| Base Year + 21-Years | **2038** | 2,834,623 | 2,627,295 | 7.9% |
| **Commercial Operations[35]** | | | | |
| Base Year Level | **2017** | 47,195 | 53,716 | -12.1% |
| Base Year + 1-Year | **2018** | 48,986 | 55,898 | -11.0% |
| Base Year + 6-Years | **2023** | 51,889 | 57,203 | -16.1% |
| Base Year + 11-Years | **2028** | 55,177 | 60,832 | -16.0% |
| Base Year + 16-Years | **2033** | 57,488 | 65,055 | -18.2% |
| Base Year + 21-Years | **2038** | 61,430 | 69,436 | -18.1% |
| **Total Operations[36]** | | | | |
| Base Year Level | **2017** | 72,588 | 72,785 | -0.3% |
| Base Year + 1-Year | **2018** | 74,821 | 72,073 | 4.0% |
| Base Year + 6-Years | **2023** | 80,058 | 77,872 | 2.9% |
| Base Year + 11-Years | **2028** | 85,896 | 81,749 | 5.2% |
| Base Year + 16-Years | **2033** | 90,992 | 86,330 | 5.3% |
| Base Year + 21-Years | **2038** | 97,978 | 91,083 | 7.6% |

Source: FAA 2018 TAF, Signature, NAA, CHA, 2019.

[35] Commercial Operations TAF = Air Carrier + Air Taxi & Commuter Operations

[36] Total Operations includes Commercial, Cargo, Military, and GA Operations.

# APPENDIX H – NEW AIR SERVICE ROUTE ANNOUNCEMENTS

FRONTIER
LOW FARES DONE RIGHT

TRAVEL DEAL

Travel Advisory

## Frontier Airlines Continues to Make Flying More Affordable: Adds Another 15 Routes With Fares as low as $39

June 05, 2018

Share

DENVER – Delivering on its mission to deliver low fares nationwide, today Frontier Airlines announced service on 15 new routes. Frontier will bring the most new routes to San Diego International Airport (SAN) with a total of five. Las Vegas sees three new routes and Austin, Las Vegas, Orlando and San Antonio will each see the addition of two new routes. To celebrate the addition of these new destinations, Frontier is offering special introductory fares as low as $39 available now at FlyFrontier.com.

"These additional fifteen routes are the latest evidence of Frontier's commitment to make air travel more affordable across the United States," said Daniel Shurz, senior vice president of commercial for Frontier Airlines. "We're offering not only amazing low fares, but a reliable and friendly service that allows customers to customize their travel experience to their needs and budget. This empowers more people than ever to fly. This is what our Low Fares Done Right philosophy is all about."

Highlights of this announcement:

-Now serving 31 destinations to/from **Austin, Texas** with the addition of service to/from **Louisville, KY** and **Orange County, Calif.**

-Now serving 27 destinations to/from **Las Vegas** with the addition of new service to/from **Calgary, Canada**,**Norfolk, VA and Spokane,Wash.**.

-Now serving 39 destinations to/from **Orlando** with the resumption of service to/from **Pittsburgh** and new daily service to **Ontario, Calif**.

-Now serving twelve destinations to/from **San Diego** with the addition of new service to/from **Cleveland, Indianapolis, Milwaukee, Pittsburgh** and **Raleigh/Durham**.

-Now serving 25 destinations to/from **San Antonio, Texas** with the addition of service to/from **Orange County** and **Salt Lake City**.

-Growing service from **Calgary, Canada**, now serving two destinations with service to **Denver** and **Las Vegas**.

**Summary of New Service**

**LAS VEGAS (LAS) to/from NORFOLK (ORF)**

**F9 1629** Depart LAS: 6:40 a.m. Arrive ORF: 2:29 p.m.

**F9 1628** Depart ORF: 9:00 p.m. Arrive LAS: 11:21 p.m.

Aircraft: Airbus A320

Frequency: Tuesday, Thursday, Sunday

Service Start: August, 14

Media Information:
720.374.4560
media@flyfrontier.com

**FRONTIER AIRLINES ANNNOUNCES NEW SERVICE FROM NORFOLK, VA**
**NEW LOW-FARE, NON-STOP FLIGHTS TO DENVER and ORLANDO, FLA.**
**Fares as low as $39**

NORFOLK, VA. – Low-Cost carrier, Frontier Airlines announced new low-cost, non-stop flights from Norfolk International Airport (ORF) to Denver International Airport (DEN) and Orlando International Airport (MCO). Select connections will be available in Denver and Orlando to cities across the Frontier network. The airline announced the new route today at an event with airport officials. Service will begin in August and to celebrate these flights, Frontier is offering special intro one-way fares as low as $39 which are available now at flyfrontier.com

"We are proud to bring our unique brand of Low Fares Done Right to Norfolk," said Jonathan Freed, Director of Corporate Communications for Frontier Airlines. "Frontier's new flights to Denver and Orlando will make air travel more accessible and affordable for everyone in Norfolk and the surrounding area. We look forward to making it easier for people to fly, and for people to fly more often."

Robert Bowen, Norfolk Airport Authority executive director states "Frontier Airlines' entrance into the Norfolk market is a statement of confidence in the region. Year-over-year passenger traffic at Norfolk International Airport has increased in 33 of the last 34 months. Frontier's low fares to Denver and Orlando, both popular markets, will be embraced by local travelers."

Blythe Scott, chairman of the Norfolk Airport Authority board of commissioners comments, "Frontier Airlines is welcomed at Norfolk International Airport and is further evidence of the resurgence in demand for affordable air service in the community."

"We are excited to welcome Frontier Airlines to Norfolk International Airport." said Norfolk Mayor Kenny Alexander, "Our airport is continuing its remarkable momentum with the addition of new routes and carriers. Not only are we expanding destinations, we are also providing affordable travel options for residents of Hampton Roads."

Summary of New Service:

**DENVER (DEN) to/from NORFOLK (ORF)**
**F9 1459** Depart DEN: 6:05 a.m. Arrive ORF: 11:30 a.m.
**F9 273** Depart ORF: 6 p.m. Arrive DEN: 8:08 p.m.
Aircraft: Airbus A320
Frequency: Thursday, Sunday
Service Start: August, 12

Media Information:
720.374.4560
media@flyfrontier.com

**ORLANDO (MCO) to/from NORFOLK (ORF)**
**F9 273** Depart MCO: 3:15 p.m. Arrive ORF: 5:10 p.m.
**F9 1459** Depart ORF: 12:20 p.m. Arrive MCO: 2:25 p.m.
Aircraft: Airbus A320
Frequency: Thursday, Sunday
Service Start: August, 12

Frontier is focused on offering customers real choice and the ability to customize their travel to their needs and budget. For example, customers can purchase travel options like bags and seat selections either a la carte or in one low-priced bundle called the WORKSsm. The Works bundle is considered one of the best values in the industry and offers customers full refundability, a carry-on bag, a checked bag, the best available seat (including exit rows and Stretch seating), waived change fees and priority boarding for as low as $59 each way. The Works is only available at FlyFrontier.com.

Frontier flies one of the youngest fleets in the industry, the Airbus A320 Family of nearly 80 jet aircraft. With nearly 200 new planes on order, Frontier will continue to grow to deliver on the mission of providing affordable travel across America. Frontier's young fleet also ensures that the company will continue to keep fares low and that customers will enjoy a pleasant and reliable experience flying with the airline.

**About Frontier Airlines:**

Frontier Airlines is committed to delivering 'Low Fares Done Right' to nearly 90 cities in the United States, Canada, Dominican Republic and Mexico on more than 300 daily flights. Headquartered in Denver, Frontier Airlines is the proud recipient of the Federal Aviation Administration's 2016 Diamond Award for maintenance excellence and was named the industry's most fuel-efficient airline by The International Council on Clean Transportation (ICCT) as a result of superior technology and operational efficiencies.

Media Information:
720.374.4560
media@flyfrontier.com

## *About Intro Fare Offer:

Fares must be purchased by 11:59 pm Eastern time on May 9, 2018 for nonstop travel. Travel is valid Aug. 12, 2018 through Nov. 14, 2018. Fares are valid Tuesdays and Wednesdays unless otherwise specified below:

Travel from **Florida** is valid Tuesday through Friday. Travel to **Florida** is valid Sunday through Wednesday.

Travel from **Denver** is valid Tuesday through Thursday and Saturday. Travel to **Denver** is valid Monday through Wednesday and Saturday.

Fares are one way and do not require roundtrip purchase.

Discount Den fares are only available at FlyFrontier.com to members of Discount Den.

| | | | |
|---|---|---|---|
| DEN | to/from | ORF | 79 |
| MCO | to/from | ORF | 39 |

NORFOLK INTERNATIONAL AIRPORT
**Media Contact: Charles Braden**
**Director of Market Development**
**757-857-3351**

## FOR IMMEDIATE RELEASE:

# Frontier Airlines to Provide Nonstop Norfolk to Phoenix and Tampa Air Service

**NORFOLK, VA. – (August 8, 2018)** – Frontier Airlines has announced that it will begin nonstop air service from Norfolk International Airport to Phoenix, Arizona and Tampa, Florida effective November 17, 2018. Seasonal service will be offered Wednesdays and Saturdays via 180-seat Airbus A320 aircraft.

Norfolk Airport Authority executive director Robert Bowen states "This new nonstop service provides our local community needed access to Phoenix and Tampa at an extremely affordable price." Local travelers will enjoy Frontier's signature "low fares done right" and convenient schedules to these popular destinations. Both Phoenix and Tampa are ranked among Norfolk's top 20 destinations in terms of passenger demand.

Both Phoenix and Tampa are available for sale now on FlyFrontier.com:

| **Depart** | **Arrive** |
|---|---|
| Norfolk 7:35PM | Phoenix 11:02PM |
| Phoenix 7:25AM | Norfolk 1:53PM |
| | |
| **Depart** | **Arrive** |
| Norfolk 9:09AM | Tampa 11:15AM |
| Tampa 6:23AM | Norfolk 8:19AM |

###

*Norfolk International Airport (ORF) is the major airport serving Coastal Virginia and Northeast North Carolina with air service provided by Allegiant, American, Delta, Frontier, Southwest, United and their regional airline partners. Together they provide nonstop access to 26 major airports (includes year-round and seasonal service), most of which are international gateways, allowing convenient access to global destinations. According to the FAA, Norfolk International Airport's passenger activity is ranked in the top 15% of commercial service airports in the United States with nearly 3.4 million scheduled passengers served in 2017.*

# ALLEGIANT ARRIVES IN NORFOLK WITH THE ONLY LOW-COST, NONSTOP SERVICE TO 3 DESTINATIONS IN FLORIDA

Click to tweet: .@Allegiant connects @NorfolkAirport with 3 destinations in #Florida with a fare everyone can afford! @VisitFlorida #GetAway #YourWay

**NORFOLK, Va.** June 20, 2017 — **Allegiant** (NASDAQ: ALGT) today announces the only low-cost, nonstop service connecting Norfolk, Virginia to three destinations in Florida: Fort Lauderdale, Orlando / Sanford and Tampa / St. Pete. **There is no better time to get away your way, with one-way fares on the new routes as low as $39.***

"We're thrilled to announce that we are bringing our unique brand of ultra-low-cost, convenient travel to Norfolk," said Lukas Johnson, Allegiant senior vice president of commercial. "We know that Norfolk-area travelers are eager to have a convenient connection to all that Florida has to offer, and we are excited to offer nonstop service at a fare that everyone can afford."

The new flights announced today from **Norfolk International Airport (ORF)** include:

1. **Tampa / St. Pete, Florida** via St. Pete-Clearwater International Airport (PIE) – begins Oct. 4, 2017 with fares as low as $39*

2. **Orlando / Sanford, Florida** via Orlando Sanford International Airport (SFB) – begins Nov. 17, 2017 with fares as low as $39*

3. **Fort Lauderdale, Florida** via Fort Lauderdale-Hollywood International Airport (FLL) – begins Nov. 17, 2017 with fares as low as $39*

Robert Bowen, airport authority executive director says, "We are gratified that Allegiant has chosen Norfolk International Airport to serve southeastern Virginia. Their air service will add many affordably-priced vacation destinations for our community."

Allegiant offers a unique option to Norfolk area travelers with low base fares and savings on rental cars, hotels and activity and attraction tickets. Travelers can book their entire vacation with Allegiant for less.

***About the introductory one-way fares:**
Seats are limited. Price includes taxes and fees. Fares are one way and not available on all flights. Flights must be purchased by June 22, 2017 for travel by Feb. 13, 2018. See Allegiant.com for details. For optional services and baggage fees, please visit Allegiant.com. Additional restrictions may apply.

**Allegiant®**
Las Vegas-based Allegiant (NASDAQ: ALGT) is focused on linking travelers in small cities to world-class leisure destinations. The airline offers industry-low fares on an all-jet fleet while also offering other travel-related products such as hotel rooms and rental cars. All can be purchased only through the company website, Allegiant.com. Beginning with one aircraft and one route in 1999, the company has grown to over 80 aircraft and more than 300 routes across the country with base airfares less than half the cost of the average domestic roundtrip ticket. For downloadable press kit, including photos, visit: http://gofly.us/iiFa303wrtF.

###

**Allegiant Media Contact**
Phone: 702-800-2020
Email: mediarelations@allegiantair.com

# ALLEGIANT ANNOUNCES NEW NONSTOP SERVICE TO JACKSONVILLE WITH FARES AS LOW AS $49

Click to Tweet: .@Allegiant announces nonstop service from @NorfolkAirport to @JAXAirport with fares everyone can afford. #GetAway #YourWay

**NORFOLK, Va.** April 3, 2018 — **Allegiant** (NASDAQ: ALGT) today announces new nonstop service from Norfolk to Jacksonville, Florida via Jacksonville International Airport (JAX) beginning June 14, 2018. **There is no better time to get away your way, with one-way fares on the new routes as low as $49.***

“Allegiant is excited to offer Norfolk travelers their only ultra-low-cost, nonstop option to visit Jacksonville,” said Lukas Johnson, Allegiant senior vice president of commercial. “The Norfolk community has been very supportive of us since we first began flying here last year, and we’re pleased to be able to provide them with convenient, friendly service to enjoy all that this sunny destination has to offer.”

The new seasonal service will operate twice weekly from Norfolk International Airport (ORF) to Jacksonville International Airport (JAX). With this addition, Allegiant will offer nonstop service to four cities in Florida from ORF: Fort Lauderdale, Jacksonville, Orlando / Sanford and Tampa / St. Pete. Flight days, times and the lowest fares can be found only at Allegiant.com.

“The addition of nonstop service from Norfolk to Jacksonville by Allegiant will be welcoming news for many travelers,” said Robert Bowen, Norfolk Airport Authority executive director. “The natural military ties between our two communities, as well as a Florida vacation destination makes this news very exciting.”

Allegiant offers a unique option to Norfolk-area travelers with low base fares and savings on rental cars and hotels. Travelers can book their entire vacation with Allegiant for less.

***About the introductory one-way fares:**
Seats are limited. Price includes taxes and fees. Fares are one way and not available on all flights. Flights must be purchased by April 4, 2018 for travel by Aug. 13, 2018. For more details, optional services and baggage fees, please visit Allegiant.com. Additional restrictions may apply.

**Allegiant®**
Las Vegas-based Allegiant (NASDAQ: ALGT) is focused on linking travelers to world-class leisure destinations. The airline offers industry-low fares on an all-jet fleet while also offering other travel-related products such as hotel rooms and rental cars. All can be purchased only through the company website, Allegiant.com. Beginning with one aircraft and one route in 1999, the company has grown to over 80 aircraft and more than 300 routes across the country with base airfares less than half the cost of the average domestic roundtrip ticket. For downloadable press kit, including photos, visit: http://gofly.us/ToZT30iauev.

###

**Allegiant Public Relations**
Phone: 725-221-9937
Email: communications@allegiantair.com
#

#

# ALLEGIANT ANNOUNCES NEW NONSTOP SERVICE TO NORFOLK FROM 2 CITIES WITH FARES AS LOW AS $49* EACH WAY

**NORFOLK, Va.** Jan. 15, 2019 — **Allegiant** (NASDAQ: ALGT) today announces two new nonstop routes to Norfolk from two cities in Ohio: Cincinnati and Cleveland. **To celebrate, the company is offering fares on the new routes as low as $49* each way.**

"We're excited to announce yet another expansion in Norfolk," said Drew Wells, Allegiant vice president of planning and revenue. "We're sure folks in Cincinnati and Cleveland will be thrilled to take advantage of these convenient, ultra-low-cost, nonstop flights to enjoy Virginia Beach and the Outer Banks."

The new seasonal routes to **Norfolk International Airport (ORF)** include:

1. **Cincinnati, Ohio** via Cincinnati / Northern Kentucky International Airport (CVG) – beginning June 7, 2019 with fares as low as $49* each way.

2. **Cleveland, Ohio** via Cleveland Hopkins International Airport (CLE) – beginning June 7, 2019 with fares as low as $49* each way.

The new nonstop routes will operate twice-weekly and will bring nearly 4,000 passengers to the Virginia Beach and Outer Banks areas annually, contributing to visitor spending in the local economy. Flight days, times and the lowest fares can be found only at Allegiant.com.

Robert Bowen, Norfolk Airport Authority executive director states, "Both Cincinnati and Cleveland are high tourist origins for our region. Allegiant's new service from these cities into Norfolk International Airport will have a direct local economic impact on lodging, dining and other services."

Allegiant offers a unique option to Virginia Beach-bound travelers with low base airfare and savings on rental cars. Travelers can book their entire vacation with Allegiant for less.

***About the introductory fares:**
Price displayed reflects purchase of a roundtrip itinerary and includes taxes, carrier charges & government fees. Seats and dates are limited and fares are not available on all flights. Flights must be purchased by Jan. 16, 2019 for travel by Aug. 13, 2019. Fare rules, routes and schedules are subject to change without notice. Optional baggage charges and additional restrictions may apply. For more details, optional services and baggage fees, please visit Allegiant.com.

**Allegiant®**
Las Vegas-based Allegiant (NASDAQ: ALGT) is focused on linking travelers to world-class leisure destinations. The airline offers industry-low fares on an all-jet fleet while also offering other travel-related products such as hotel rooms and rental cars. All can be purchased only through the company website, Allegiant.com. Beginning with one aircraft and one route in 1999, the company has grown to over 80 aircraft and more than 300 routes across the country with base airfares less than half the cost of the average domestic roundtrip ticket. For downloadable press kit, including photos, visit: http://gofly.us/iiFa303wrtF.

###

#
**Allegiant Public Relations**
Phone: 725-221-9937
Email: communications@allegiantair.com
#

NORFOLK INTERNATIONAL AIRPORT

**Media Contact: Charles Braden**
**Director of Market Development**
**757-857-3351**

## FOR IMMEDIATE RELEASE:

# United Airlines to Provide Nonstop Norfolk to Denver Air Service

**NORFOLK, VA. – (January 8, 2018)** – United Airlines has announced that it will begin year-round daily nonstop air service from Norfolk International Airport to Denver, Colorado effective June 8, 2018. The service will be operated on 128-seat Airbus A319 aircraft with dual class service and an affordable fare structure.

Norfolk Airport Authority executive director Robert Bowen states "This new nonstop service provides our local community needed access to Denver and also offers greater west coast and pacific reach through United's Denver hub. We are gratified that United has selected Norfolk for this service expansion." Local travelers will have convenient access to over 50 destinations via the Denver hub. According to the FAA, Denver is Norfolk's 9th ranked market in terms of passenger demand.

The Norfolk to Denver service which begins June 8, 2018 is available for sale now on United.com and scheduled as follows:

| Depart | Arrive |
|---|---|
| Norfolk 8:00 A.M. | Denver 10:08 A.M. |
| Denver 5:45 P.M. | Norfolk 11:10 P.M. |

###

*Norfolk International Airport (ORF) is the major airport serving Coastal Virginia and Northeast North Carolina with air service provided by Allegiant, American, Delta, Southwest, United and their regional airline partners. Together they provide nonstop access to 22 major airports (includes year-round and seasonal service), most of which are international gateways, allowing convenient access to global destinations. According to the FAA, Norfolk International Airport's passenger activity is ranked in the top 15% of commercial service airports in the United States with over 3.2 million scheduled passengers served in 2016.*

NORFOLK INTERNATIONAL AIRPORT

**Media Contact: Charles Braden**
**Director of Market Development**
**757-857-3351**

## FOR IMMEDIATE RELEASE:

# SOUTHWEST AIRLINES TO EXPAND SUMMER 2019 SERVICE FROM NORFOLK INTERNATIONAL AIRPORT

**NORFOLK, Va. – (November 15, 2018)** – Southwest Airlines will add new nonstop service from Norfolk International Airport (ORF) to Nashville, TN and San Diego, CA on June 9, 2019. The airline has just released the June 9 – August 5 schedule and it is now on sale at Southwest.com.

Flights to both cities are summer seasonal service and will be operated on the weekends with the following schedule:

| **Service to Nashville (BNA) Operates on Saturday and Sunday** | |
|---|---|
| Depart ORF at 6:15 P.M. | Arrive BNA at 7:10 P.M. |
| Depart BNA at 11:40 A.M. | Arrive ORF at 2:30 P.M. |

| **Service to San Diego (SAN) Operates on Sunday** | |
|---|---|
| Depart ORF at 12:40 P.M. | Arrive SAN at 3:00 P.M. |
| Depart SAN at 3:45 P.M. | Arrive ORF at 11:50 P.M. |

Robert Bowen, Norfolk Airport Authority executive director states, “We welcome this wonderful news. San Diego is a popular destination for our region with close ties to the military community. The return of the previously served Nashville route will also be well received.” In addition to the service above, Southwest will also return the summer weekend nonstop service to Denver, CO.

###

*Norfolk International Airport (ORF) is the major airport serving Coastal Virginia and Northeast North Carolina with air service provided by Allegiant, American, Delta, Frontier, Southwest, United and their regional airline partners. Together they provide nonstop access to 26 major airports (includes year-round and seasonal service), most of which are international gateways, allowing convenient access to global destinations. According to the FAA, Norfolk International Airport’s passenger activity is ranked in the top 13% of commercial service airports in the United States with nearly 3.4 million scheduled passengers served in 2017.*

# APPENDIX I – AIRLINE SCHEDULES (JULY 2017)

Aviation DataMiner

| From : 07/01/2017 | | Airport : NORFOLK INTERNATIONAL ( ORF ) | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| To : 07/31/2017 | | SCHEDULED DEPARTURES | | | | | | | | | | | | | |
| Destination | Flight No | Date From | Date To | Dep Time | Arr Time | Sys Carrier | Op Carrier | Aircraft | Mon | Tue | Wed | Thu | Fri | Sat | Sun |
| ATL | | | | | | | | | | | | | | | |
| | 2557 | 7/10/2017 | 7/13/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/12/2017 | 7/20/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/19/2017 | 7/20/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/19/2017 | 7/21/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/24/2017 | 7/27/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/26/2017 | 8/3/2017 | 05:45:00 | 07:21:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 2557 | 7/1/2017 | 7/6/2017 | 06:00:00 | 07:42:00 | DL | DL | M88 | | | | | | X | |
| | 2557 | 7/8/2017 | 7/13/2017 | 06:00:00 | 07:42:00 | DL | DL | M88 | | | | | | X | |
| | 2557 | 7/9/2017 | 7/13/2017 | 06:00:00 | 07:44:00 | DL | DL | M88 | | | | | | | X |
| | 2557 | 7/15/2017 | 7/20/2017 | 06:00:00 | 07:42:00 | DL | DL | M88 | | | | | | X | |
| | 2557 | 7/16/2017 | 7/20/2017 | 06:00:00 | 07:44:00 | DL | DL | M88 | | | | | | | X |
| | 2557 | 7/22/2017 | 7/22/2017 | 06:00:00 | 07:42:00 | DL | DL | M88 | | | | | | X | |
| | 2557 | 7/23/2017 | 7/27/2017 | 06:00:00 | 07:44:00 | DL | DL | M88 | | | | | | | X |
| | 2557 | 7/29/2017 | 8/3/2017 | 06:00:00 | 07:42:00 | DL | DL | M88 | | | | | | X | |
| | 2557 | 7/30/2017 | 8/3/2017 | 06:00:00 | 07:44:00 | DL | DL | M88 | | | | | | | X |
| | 1183 | 7/1/2017 | 7/6/2017 | 07:00:00 | 08:42:00 | DL | DL | 757 | X | X | | | | X | X |
| | 1183 | 7/5/2017 | 7/6/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | X | X | X | X | | X |
| | 1183 | 7/5/2017 | 7/13/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | X | X | X | X | | X |
| | 1183 | 7/8/2017 | 7/13/2017 | 07:00:00 | 08:42:00 | DL | DL | 757 | | | | | | X | |
| | 1183 | 7/12/2017 | 7/20/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | X | X | X | X | | X |
| | 1183 | 7/15/2017 | 7/20/2017 | 07:00:00 | 08:42:00 | DL | DL | 757 | | | | | | X | |
| | 1183 | 7/19/2017 | 7/20/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | X | X | X | X | | X |
| | 1183 | 7/19/2017 | 7/21/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | X | X | X | X | | X |
| | 1183 | 7/22/2017 | 7/22/2017 | 07:00:00 | 08:42:00 | DL | DL | 757 | | | | | | X | |
| | 1183 | 7/23/2017 | 7/27/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | | X | X | X | | X |
| | 1183 | 7/25/2017 | 7/27/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | | X | | | | | |
| | 1183 | 7/26/2017 | 8/3/2017 | 07:00:00 | 08:43:00 | DL | DL | 757 | X | | X | X | X | | X |
| | 1183 | 7/29/2017 | 8/3/2017 | 07:00:00 | 08:42:00 | DL | DL | 757 | | | | | | X | |
| | 1252 | 7/1/2017 | 7/1/2017 | 08:05:00 | 09:46:00 | DL | DL | M88 | | | | | | X | |
| | 1252 | 7/8/2017 | 7/13/2017 | 08:05:00 | 09:45:00 | DL | DL | 757 | | | | | | X | |
| | 1252 | 7/15/2017 | 7/20/2017 | 08:05:00 | 09:45:00 | DL | DL | 757 | | | | | | X | |
| | 1252 | 7/22/2017 | 7/22/2017 | 08:05:00 | 09:45:00 | DL | DL | 757 | | | | | | X | |
| | 1252 | 7/29/2017 | 8/3/2017 | 08:05:00 | 09:45:00 | DL | DL | 757 | | | | | | X | |
| | 1252 | 7/2/2017 | 7/4/2017 | 08:15:00 | 09:54:00 | DL | DL | 757 | | X | | | | | X |
| | 1252 | 7/3/2017 | 7/3/2017 | 08:15:00 | 09:54:00 | DL | DL | 757 | X | | | | | | |
| | 1252 | 7/5/2017 | 7/6/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | X | X | X | X | | X |
| | 1252 | 7/5/2017 | 7/13/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | X | X | X | X | | X |
| | 1252 | 7/10/2017 | 7/13/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | X | | | | | | |
| | 1252 | 7/12/2017 | 7/20/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | X | X | X | X | | X |
| | 1252 | 7/17/2017 | 7/20/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | X | | | | | | |
| | 1252 | 7/19/2017 | 7/20/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | X | X | X | X | | X |
| | 1252 | 7/19/2017 | 7/21/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | X | X | X | X | | X |
| | 1252 | 7/23/2017 | 7/27/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | | X | X | X | | X |
| | 1252 | 7/24/2017 | 7/27/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | X | X | | | | | |
| | 1252 | 7/26/2017 | 8/3/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | | | X | X | X | | X |
| | 1252 | 7/31/2017 | 8/3/2017 | 08:15:00 | 09:56:00 | DL | DL | 757 | X | X | | | | | |
| | 1113 | 7/3/2017 | 7/4/2017 | 09:45:00 | 11:26:00 | DL | DL | M88 | X | X | | | | | |
| | 1113 | 7/5/2017 | 7/6/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | | | X | X | X | | |
| | 1113 | 7/5/2017 | 7/7/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | | | X | X | X | | |
| | 1113 | 7/10/2017 | 7/13/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/12/2017 | 7/20/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/19/2017 | 7/20/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/19/2017 | 7/21/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/24/2017 | 7/27/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/26/2017 | 8/3/2017 | 09:45:00 | 11:28:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 1113 | 7/2/2017 | 7/2/2017 | 10:29:00 | 12:13:00 | DL | DL | M88 | | | | | | | X |
| | 1113 | 7/9/2017 | 7/13/2017 | 10:29:00 | 12:16:00 | DL | DL | M88 | | | | | | | X |
| | 1113 | 7/16/2017 | 7/20/2017 | 10:29:00 | 12:16:00 | DL | DL | M88 | | | | | | | X |
| | 1113 | 7/23/2017 | 7/27/2017 | 10:29:00 | 12:16:00 | DL | DL | M88 | | | | | | | X |
| | 1113 | 7/30/2017 | 8/3/2017 | 10:29:00 | 12:16:00 | DL | DL | M88 | | | | | | | X |
| | 1113 | 7/1/2017 | 7/6/2017 | 10:39:00 | 12:23:00 | DL | DL | M88 | | | | | | X | |
| | 1113 | 7/8/2017 | 7/13/2017 | 10:39:00 | 12:23:00 | DL | DL | M88 | | | | | | X | |
| | 1113 | 7/15/2017 | 7/20/2017 | 10:39:00 | 12:23:00 | DL | DL | M88 | | | | | | X | |
| | 1113 | 7/22/2017 | 7/22/2017 | 10:39:00 | 12:23:00 | DL | DL | M88 | | | | | | X | |
| | 1113 | 7/29/2017 | 8/3/2017 | 10:39:00 | 12:23:00 | DL | DL | M88 | | | | | | X | |
| | 2074 | 7/2/2017 | 7/4/2017 | 12:25:00 | 14:10:00 | DL | DL | M88 | X | X | | | | | X |
| | 2074 | 7/5/2017 | 7/6/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | | | X | X | X | | |
| | 2074 | 7/5/2017 | 7/7/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | | | X | X | X | | |
| | 2074 | 7/9/2017 | 7/13/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/12/2017 | 7/20/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/19/2017 | 7/20/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/19/2017 | 7/21/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/23/2017 | 7/27/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/26/2017 | 8/3/2017 | 12:25:00 | 14:13:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2074 | 7/1/2017 | 7/6/2017 | 12:29:00 | 14:14:00 | DL | DL | M88 | | | | | | X | |
| | 2074 | 7/8/2017 | 7/13/2017 | 12:29:00 | 14:14:00 | DL | DL | M88 | | | | | | X | |
| | 2074 | 7/15/2017 | 7/20/2017 | 12:29:00 | 14:14:00 | DL | DL | M88 | | | | | | X | |
| | 2074 | 7/22/2017 | 7/22/2017 | 12:29:00 | 14:14:00 | DL | DL | M88 | | | | | | X | |
| | 2074 | 7/29/2017 | 8/3/2017 | 12:29:00 | 14:14:00 | DL | DL | M88 | | | | | | X | |
| | 2141 | 7/1/2017 | 7/1/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | X | X | | | | X | X |
| | 2141 | 7/2/2017 | 7/6/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | X | X | | | | X | X |
| | 2141 | 7/5/2017 | 7/6/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2141 | 7/5/2017 | 7/13/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2141 | 7/8/2017 | 7/13/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | | | | | | X | |
| | 2141 | 7/12/2017 | 7/18/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2141 | 7/15/2017 | 7/20/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | | | | | | X | |
| | 2141 | 7/19/2017 | 7/19/2017 | 14:25:00 | 16:12:00 | DL | DL | M90 | | | X | | | | |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 2141 | 7/19/2017 | 7/19/2017 | 14:25:00 | 16:12:00 | DL | DL | M90 | | | X | | | | |
| | 2141 | 7/19/2017 | 7/20/2017 | 14:25:00 | 16:12:00 | DL | DL | M90 | | | X | | | | |
| | 2141 | 7/20/2017 | 7/21/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | | X | X | | X |
| | 2141 | 7/22/2017 | 7/22/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | | | | | | X | |
| | 2141 | 7/23/2017 | 7/27/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | | X | | | X |
| | 2141 | 7/26/2017 | 7/28/2017 | 14:25:00 | 16:12:00 | DL | DL | M90 | | | X | | X | | |
| | 2141 | 7/26/2017 | 7/27/2017 | 14:25:00 | 16:12:00 | DL | DL | M90 | | | X | | X | | |
| | 2141 | 7/27/2017 | 8/3/2017 | 14:25:00 | 16:12:00 | DL | DL | M88 | X | X | X | X | | | X |
| | 2141 | 7/29/2017 | 8/3/2017 | 14:25:00 | 16:10:00 | DL | DL | M88 | | | | | | X | |
| | 2206 | 7/1/2017 | 7/6/2017 | 16:35:00 | 18:23:00 | DL | DL | M88 | | | | | | X | |
| | 2206 | 7/5/2017 | 7/13/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/5/2017 | 7/6/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/8/2017 | 7/13/2017 | 16:35:00 | 18:23:00 | DL | DL | M88 | | | | | | X | |
| | 2206 | 7/12/2017 | 7/20/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/15/2017 | 7/20/2017 | 16:35:00 | 18:23:00 | DL | DL | M88 | | | | | | X | |
| | 2206 | 7/19/2017 | 7/20/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/19/2017 | 7/21/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/22/2017 | 7/22/2017 | 16:35:00 | 18:23:00 | DL | DL | M88 | | | | | | X | |
| | 2206 | 7/23/2017 | 7/27/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/26/2017 | 8/3/2017 | 16:35:00 | 18:25:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 2206 | 7/29/2017 | 8/3/2017 | 16:35:00 | 18:23:00 | DL | DL | M88 | | | | | | X | |
| | 321 | 7/2/2017 | 7/4/2017 | 18:25:00 | 20:14:00 | DL | DL | M88 | X | X | | | | | X |
| | 321 | 7/5/2017 | 7/13/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 321 | 7/5/2017 | 7/6/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 321 | 7/12/2017 | 7/20/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 321 | 7/16/2017 | 7/20/2017 | 18:25:00 | 20:16:00 | DL | DL | M90 | | | | | | | X |
| | 321 | 7/19/2017 | 7/20/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 321 | 7/19/2017 | 7/21/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | |
| | 321 | 7/23/2017 | 7/23/2017 | 18:25:00 | 20:16:00 | DL | DL | M90 | | | | | | | X |
| | 321 | 7/24/2017 | 7/27/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 321 | 7/26/2017 | 8/3/2017 | 18:25:00 | 20:16:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/5/2017 | 7/13/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/5/2017 | 7/6/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/12/2017 | 7/20/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/19/2017 | 7/20/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/19/2017 | 7/21/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/23/2017 | 7/27/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| | 1685 | 7/26/2017 | 8/3/2017 | 19:55:00 | 21:43:00 | DL | DL | M88 | X | X | X | X | X | | X |
| **BWI** | | | | | | | | | | | | | | | |
| | 1560 | 6/28/2017 | 7/6/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | | | X | X | X | | |
| | 1560 | 7/5/2017 | 7/13/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1560 | 7/12/2017 | 7/20/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1560 | 7/19/2017 | 7/20/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1560 | 7/19/2017 | 7/27/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1560 | 7/26/2017 | 8/3/2017 | 06:00:00 | 06:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1560 | 7/3/2017 | 7/3/2017 | 06:05:00 | 07:00:00 | WN | WN | 73W | X | | | | | | |
| | 2864 | 7/1/2017 | 7/6/2017 | 06:35:00 | 07:30:00 | WN | WN | 73W | | | | | | X | |
| | 2864 | 7/8/2017 | 7/13/2017 | 06:35:00 | 07:30:00 | WN | WN | 73W | | | | | | X | |
| | 2864 | 7/15/2017 | 7/20/2017 | 06:35:00 | 07:30:00 | WN | WN | 73W | | | | | | X | |
| | 2864 | 7/22/2017 | 7/27/2017 | 06:35:00 | 07:30:00 | WN | WN | 73W | | | | | | X | |
| | 2864 | 7/29/2017 | 8/3/2017 | 06:35:00 | 07:30:00 | WN | WN | 73W | | | | | | X | |
| | 4824 | 7/4/2017 | 7/4/2017 | 06:35:00 | 07:30:00 | WN | WN | 73C | | X | | | | | |
| | 3946 | 7/2/2017 | 7/6/2017 | 07:00:00 | 07:55:00 | WN | WN | 73H | | | | | | | X |
| | 3946 | 7/9/2017 | 7/13/2017 | 07:00:00 | 07:55:00 | WN | WN | 73H | | | | | | | X |
| | 3946 | 7/16/2017 | 7/20/2017 | 07:00:00 | 07:55:00 | WN | WN | 73H | | | | | | | X |
| | 3946 | 7/23/2017 | 7/27/2017 | 07:00:00 | 07:55:00 | WN | WN | 73H | | | | | | | X |
| | 3946 | 7/30/2017 | 8/3/2017 | 07:00:00 | 07:55:00 | WN | WN | 73H | | | | | | | X |
| | 4551 | 7/1/2017 | 7/6/2017 | 10:05:00 | 11:00:00 | WN | WN | 73W | | | | | | X | |
| | 4551 | 7/8/2017 | 7/13/2017 | 10:05:00 | 11:00:00 | WN | WN | 73W | | | | | | X | |
| | 4551 | 7/15/2017 | 7/20/2017 | 10:05:00 | 11:00:00 | WN | WN | 73W | | | | | | X | |
| | 4551 | 7/22/2017 | 7/27/2017 | 10:05:00 | 11:00:00 | WN | WN | 73W | | | | | | X | |
| | 4551 | 7/29/2017 | 8/3/2017 | 10:05:00 | 11:00:00 | WN | WN | 73W | | | | | | X | |
| | 1068 | 7/2/2017 | 7/2/2017 | 10:40:00 | 11:35:00 | WN | WN | 73W | | | | | | | X |
| | 1068 | 7/9/2017 | 7/13/2017 | 10:40:00 | 11:35:00 | WN | WN | 73W | | | | | | | X |
| | 1068 | 7/16/2017 | 7/20/2017 | 10:40:00 | 11:35:00 | WN | WN | 73W | | | | | | | X |
| | 1068 | 7/23/2017 | 7/27/2017 | 10:40:00 | 11:35:00 | WN | WN | 73W | | | | | | | X |
| | 1068 | 7/30/2017 | 8/3/2017 | 10:40:00 | 11:35:00 | WN | WN | 73W | | | | | | | X |
| | 632 | 6/28/2017 | 7/6/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | | X | X | X | X | | |
| | 632 | 7/3/2017 | 7/3/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | | | | | | |
| | 632 | 7/5/2017 | 7/13/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 632 | 7/12/2017 | 7/20/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 632 | 7/19/2017 | 7/20/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 632 | 7/19/2017 | 7/27/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 632 | 7/26/2017 | 8/3/2017 | 12:00:00 | 12:55:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 2394 | 7/1/2017 | 7/6/2017 | 12:25:00 | 13:20:00 | WN | WN | 73W | | | | | | X | |
| | 2394 | 7/8/2017 | 7/13/2017 | 12:25:00 | 13:20:00 | WN | WN | 73W | | | | | | X | |
| | 2394 | 7/15/2017 | 7/20/2017 | 12:25:00 | 13:20:00 | WN | WN | 73W | | | | | | X | |
| | 2394 | 7/22/2017 | 7/27/2017 | 12:25:00 | 13:20:00 | WN | WN | 73W | | | | | | X | |
| | 2394 | 7/29/2017 | 8/3/2017 | 12:25:00 | 13:20:00 | WN | WN | 73W | | | | | | X | |
| | 1370 | 7/2/2017 | 7/6/2017 | 12:35:00 | 13:30:00 | WN | WN | 73W | | | | | | | X |
| | 1370 | 7/9/2017 | 7/13/2017 | 12:35:00 | 13:30:00 | WN | WN | 73W | | | | | | | X |
| | 1370 | 7/16/2017 | 7/20/2017 | 12:35:00 | 13:30:00 | WN | WN | 73W | | | | | | | X |
| | 1370 | 7/23/2017 | 7/27/2017 | 12:35:00 | 13:30:00 | WN | WN | 73W | | | | | | | X |
| | 1370 | 7/30/2017 | 8/3/2017 | 12:35:00 | 13:30:00 | WN | WN | 73W | | | | | | | X |
| | 563 | 6/28/2017 | 7/6/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | | | X | X | X | | |
| | 563 | 7/5/2017 | 7/13/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 563 | 7/12/2017 | 7/20/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 563 | 7/19/2017 | 7/27/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 563 | 7/19/2017 | 7/20/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 563 | 7/26/2017 | 8/3/2017 | 14:45:00 | 15:40:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 1234 | 7/3/2017 | 7/3/2017 | 15:05:00 | 16:00:00 | WN | WN | 73C | X | | | | | | |
| | 4167 | 7/2/2017 | 7/6/2017 | 15:15:00 | 16:10:00 | WN | WN | 73W | | | | | | | X |
| | 4167 | 7/9/2017 | 7/13/2017 | 15:15:00 | 16:10:00 | WN | WN | 73W | | | | | | | X |
| | 4167 | 7/16/2017 | 7/20/2017 | 15:15:00 | 16:10:00 | WN | WN | 73W | | | | | | | X |
| | 4167 | 7/23/2017 | 7/27/2017 | 15:15:00 | 16:10:00 | WN | WN | 73W | | | | | | | X |
| | 4167 | 7/30/2017 | 8/3/2017 | 15:15:00 | 16:10:00 | WN | WN | 73W | | | | | | | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1223 | 7/4/2017 | 7/4/2017 | 16:05:00 | 17:00:00 | WN | WN | 73W | | X | | | | | |
| | 137 | 7/3/2017 | 7/3/2017 | 16:25:00 | 17:20:00 | WN | WN | 73W | X | | | | | | |
| | 137 | 6/28/2017 | 7/6/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | | | X | X | X | | |
| | 137 | 7/5/2017 | 7/13/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 137 | 7/12/2017 | 7/20/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 137 | 7/19/2017 | 7/20/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 137 | 7/19/2017 | 7/27/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 137 | 7/26/2017 | 8/3/2017 | 16:30:00 | 17:25:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 332 | 7/4/2017 | 7/4/2017 | 17:05:00 | 18:05:00 | WN | WN | 73W | | X | | | | | |
| | 4363 | 7/2/2017 | 7/6/2017 | 17:40:00 | 18:40:00 | WN | WN | 73W | | | | | | | X |
| | 4363 | 7/9/2017 | 7/13/2017 | 17:40:00 | 18:40:00 | WN | WN | 73W | | | | | | | X |
| | 4363 | 7/16/2017 | 7/20/2017 | 17:40:00 | 18:40:00 | WN | WN | 73W | | | | | | | X |
| | 4363 | 7/23/2017 | 7/27/2017 | 17:40:00 | 18:40:00 | WN | WN | 73W | | | | | | | X |
| | 4363 | 7/30/2017 | 8/3/2017 | 17:40:00 | 18:40:00 | WN | WN | 73W | | | | | | | X |
| | 268 | 6/28/2017 | 7/6/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | | X | X | X | X | | |
| | 268 | 7/5/2017 | 7/13/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 268 | 7/12/2017 | 7/20/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 268 | 7/19/2017 | 7/27/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 268 | 7/19/2017 | 7/20/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 268 | 7/26/2017 | 8/3/2017 | 18:35:00 | 19:35:00 | WN | WN | 73C | X | X | X | X | X | | |
| | 5819 | 7/1/2017 | 7/6/2017 | 18:35:00 | 19:35:00 | WN | WN | 73W | | | | | | X | |
| | 5819 | 7/8/2017 | 7/13/2017 | 18:35:00 | 19:35:00 | WN | WN | 73W | | | | | | X | |
| | 5819 | 7/15/2017 | 7/20/2017 | 18:35:00 | 19:35:00 | WN | WN | 73W | | | | | | X | |
| | 5819 | 7/22/2017 | 7/27/2017 | 18:35:00 | 19:35:00 | WN | WN | 73W | | | | | | X | |
| | 5819 | 7/29/2017 | 8/3/2017 | 18:35:00 | 19:35:00 | WN | WN | 73W | | | | | | X | |
| **CLT** | | | | | | | | | | | | | | | |
| | 1978 | 7/8/2017 | 7/13/2017 | 05:25:00 | 06:42:00 | AA | AA | 319 | | | | | | X | |
| | 1978 | 7/15/2017 | 7/20/2017 | 05:25:00 | 06:42:00 | AA | AA | 319 | | | | | | X | |
| | 1978 | 7/22/2017 | 7/27/2017 | 05:25:00 | 06:42:00 | AA | AA | 319 | | | | | | X | |
| | 1978 | 7/29/2017 | 8/3/2017 | 05:25:00 | 06:42:00 | AA | AA | 319 | | | | | | X | |
| | 5073 | 6/29/2017 | 7/6/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5073 | 7/5/2017 | 7/13/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/12/2017 | 7/12/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/13/2017 | 7/20/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/19/2017 | 7/20/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/19/2017 | 7/27/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/26/2017 | 7/26/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 5073 | 7/27/2017 | 8/3/2017 | 05:25:00 | 06:34:00 | AA | 16 | CR9 | X | X | X | X | X | | X |
| | 1823 | 6/29/2017 | 7/6/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | X | X | X | X | |
| | 1823 | 7/3/2017 | 7/3/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | | | | | | |
| | 1823 | 7/4/2017 | 7/4/2017 | 07:15:00 | 08:40:00 | AA | AA | 320 | | X | | | | | |
| | 1823 | 7/5/2017 | 7/13/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1823 | 7/12/2017 | 7/20/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1823 | 7/19/2017 | 7/20/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1823 | 7/19/2017 | 7/27/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1823 | 7/26/2017 | 7/26/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1823 | 7/27/2017 | 8/3/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1935 | 7/2/2017 | 7/2/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | | | | | X |
| | 1935 | 7/9/2017 | 7/13/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | | | | | X |
| | 1935 | 7/16/2017 | 7/20/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | | | | | X |
| | 1935 | 7/23/2017 | 7/27/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | | | | | X |
| | 1935 | 7/30/2017 | 7/30/2017 | 07:15:00 | 08:40:00 | AA | AA | 319 | | | | | | | X |
| | 5222 | 7/8/2017 | 7/13/2017 | 07:15:00 | 08:34:00 | AA | 16 | CR9 | | | | | | X | |
| | 5222 | 7/15/2017 | 7/20/2017 | 07:15:00 | 08:34:00 | AA | 16 | CR9 | | | | | | X | |
| | 5222 | 7/22/2017 | 7/27/2017 | 07:15:00 | 08:34:00 | AA | 16 | CR9 | | | | | | X | |
| | 5222 | 7/29/2017 | 8/3/2017 | 07:15:00 | 08:34:00 | AA | 16 | CR9 | | | | | | X | |
| | 5252 | 6/29/2017 | 7/4/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | | X | X | X | X |
| | 5252 | 7/5/2017 | 7/13/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/5/2017 | 7/6/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/12/2017 | 7/12/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/13/2017 | 7/20/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/19/2017 | 7/27/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/19/2017 | 7/20/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/26/2017 | 7/26/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5252 | 7/27/2017 | 8/3/2017 | 09:25:00 | 10:50:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 616 | 7/2/2017 | 7/6/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | | | | | | X |
| | 616 | 7/9/2017 | 7/13/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | | | | | | X |
| | 616 | 7/16/2017 | 7/20/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | | | | | | X |
| | 616 | 7/23/2017 | 7/27/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | | | | | | X |
| | 616 | 7/30/2017 | 8/3/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | | | | | | X |
| | 1970 | 6/29/2017 | 7/6/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | | X | X | X | X | | |
| | 1970 | 7/5/2017 | 7/13/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1970 | 7/12/2017 | 7/20/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1970 | 7/19/2017 | 7/20/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1970 | 7/19/2017 | 7/27/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1970 | 7/26/2017 | 7/26/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 1970 | 7/27/2017 | 8/3/2017 | 11:05:00 | 12:26:00 | AA | AA | 319 | X | X | X | X | X | | |
| | 5368 | 7/1/2017 | 7/6/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | | | | | | X | |
| | 5368 | 7/8/2017 | 7/13/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | | | | | | X | |
| | 5368 | 7/15/2017 | 7/20/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | | | | | | X | |
| | 5368 | 7/22/2017 | 7/27/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | | | | | | X | |
| | 5368 | 7/29/2017 | 8/3/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | | | | | | X | |
| | 5501 | 7/3/2017 | 7/3/2017 | 11:05:00 | 12:25:00 | AA | 16 | CR9 | X | | | | | | |
| | 4130 | 6/29/2017 | 7/4/2017 | 12:10:00 | 13:31:00 | AA | ZW | CR2 | X | X | | X | X | X | X |
| | 4130 | 7/5/2017 | 7/6/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4130 | 7/5/2017 | 7/13/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4130 | 7/12/2017 | 7/20/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4130 | 7/19/2017 | 7/20/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4130 | 7/19/2017 | 7/27/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4130 | 7/26/2017 | 8/3/2017 | 12:35:00 | 13:56:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 5240 | 6/29/2017 | 7/6/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/5/2017 | 7/13/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/12/2017 | 7/12/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/13/2017 | 7/20/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/19/2017 | 7/27/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/19/2017 | 7/20/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 5240 | 7/26/2017 | 7/26/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5240 | 7/27/2017 | 8/3/2017 | 13:45:00 | 15:05:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5278 | 7/1/2017 | 7/1/2017 | 17:46:00 | 19:10:00 | AA | 16 | CR2 | | | | | | X | |
| | 5558 | 6/29/2017 | 7/4/2017 | 17:46:00 | 19:10:00 | AA | 16 | CR2 | X | X | | X | X | | X |
| | 5083 | 7/5/2017 | 7/6/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/5/2017 | 7/13/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/12/2017 | 7/12/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/13/2017 | 7/20/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/19/2017 | 7/27/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/19/2017 | 7/20/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/26/2017 | 7/26/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5083 | 7/27/2017 | 8/3/2017 | 17:50:00 | 19:13:00 | AA | 16 | CR7 | X | X | X | X | X | | |
| | 5441 | 7/8/2017 | 7/13/2017 | 17:50:00 | 19:14:00 | AA | 16 | CR2 | | | | | | X | |
| | 5441 | 7/15/2017 | 7/20/2017 | 17:50:00 | 19:14:00 | AA | 16 | CR2 | | | | | | X | |
| | 5441 | 7/22/2017 | 7/27/2017 | 17:50:00 | 19:14:00 | AA | 16 | CR2 | | | | | | X | |
| | 5441 | 7/29/2017 | 8/3/2017 | 17:50:00 | 19:14:00 | AA | 16 | CR2 | | | | | | X | |
| | 5103 | 6/29/2017 | 7/1/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | | | | X | X | X | |
| | 5103 | 7/2/2017 | 7/4/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | | | | | X |
| | 5103 | 7/5/2017 | 7/6/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/5/2017 | 7/13/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/12/2017 | 7/12/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/13/2017 | 7/20/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/19/2017 | 7/20/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/19/2017 | 7/27/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/26/2017 | 7/26/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| | 5103 | 7/27/2017 | 8/3/2017 | 19:55:00 | 21:13:00 | AA | 16 | CR9 | X | X | X | X | X | X | X |
| **DCA** | | | | | | | | | | | | | | | |
| | 4123 | 6/29/2017 | 7/6/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | | | | X | X | | |
| | 4123 | 7/5/2017 | 7/5/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | | | X | | | | |
| | 4123 | 7/5/2017 | 7/5/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | | | X | | | | |
| | 4123 | 7/6/2017 | 7/13/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4123 | 7/12/2017 | 7/20/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4123 | 7/19/2017 | 7/20/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4123 | 7/19/2017 | 7/27/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4123 | 7/26/2017 | 7/26/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4123 | 7/27/2017 | 8/3/2017 | 05:30:00 | 06:31:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 3433 | 7/9/2017 | 7/13/2017 | 06:50:00 | 07:56:00 | AA | MQ | ER4 | | | | | | | X |
| | 3433 | 7/16/2017 | 7/20/2017 | 06:50:00 | 07:56:00 | AA | MQ | ER4 | | | | | | | X |
| | 3433 | 7/23/2017 | 7/27/2017 | 06:50:00 | 07:56:00 | AA | MQ | ER4 | | | | | | | X |
| | 3433 | 7/30/2017 | 8/3/2017 | 06:50:00 | 07:56:00 | AA | MQ | ER4 | | | | | | | X |
| | 3433 | 7/2/2017 | 7/2/2017 | 07:50:00 | 09:00:00 | AA | MQ | ER4 | | | | | | | X |
| | 4126 | 6/29/2017 | 7/6/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | | X | X | X | X | X | |
| | 4126 | 7/5/2017 | 7/13/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | X | X | X | X | X | X | |
| | 4126 | 7/12/2017 | 7/20/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | X | X | X | X | X | X | |
| | 4126 | 7/19/2017 | 7/20/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | X | X | X | X | X | X | |
| | 4126 | 7/19/2017 | 7/27/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | X | X | X | X | X | X | |
| | 4126 | 7/26/2017 | 8/3/2017 | 08:20:00 | 09:27:00 | AA | ZW | CR2 | X | X | X | X | X | X | |
| | 4128 | 7/2/2017 | 7/6/2017 | 09:45:00 | 10:57:00 | AA | ZW | CR2 | | | | | | | X |
| | 4128 | 7/9/2017 | 7/13/2017 | 09:45:00 | 10:57:00 | AA | ZW | CR2 | | | | | | | X |
| | 4128 | 7/16/2017 | 7/20/2017 | 09:45:00 | 10:57:00 | AA | ZW | CR2 | | | | | | | X |
| | 4128 | 7/23/2017 | 7/27/2017 | 09:45:00 | 10:57:00 | AA | ZW | CR2 | | | | | | | X |
| | 4128 | 7/30/2017 | 8/3/2017 | 09:45:00 | 10:57:00 | AA | ZW | CR2 | | | | | | | X |
| | 4274 | 6/29/2017 | 7/6/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | | X | X | X | X | | |
| | 4274 | 7/3/2017 | 7/3/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | | | | | | |
| | 4274 | 7/5/2017 | 7/13/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4274 | 7/12/2017 | 7/20/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4274 | 7/19/2017 | 7/27/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4274 | 7/19/2017 | 7/20/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4274 | 7/26/2017 | 8/3/2017 | 12:00:00 | 13:06:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4134 | 7/1/2017 | 7/6/2017 | 13:15:00 | 14:27:00 | AA | ZW | CR2 | | | | | | X | |
| | 4134 | 7/8/2017 | 7/13/2017 | 13:15:00 | 14:27:00 | AA | ZW | CR2 | | | | | | X | |
| | 4134 | 7/15/2017 | 7/20/2017 | 13:15:00 | 14:27:00 | AA | ZW | CR2 | | | | | | X | |
| | 4134 | 7/22/2017 | 7/27/2017 | 13:15:00 | 14:27:00 | AA | ZW | CR2 | | | | | | X | |
| | 4134 | 7/29/2017 | 8/3/2017 | 13:15:00 | 14:27:00 | AA | ZW | CR2 | | | | | | X | |
| | 5369 | 7/1/2017 | 7/6/2017 | 15:20:00 | 16:30:00 | AA | 16 | CR2 | | | | | | X | |
| | 5369 | 7/8/2017 | 7/13/2017 | 15:20:00 | 16:30:00 | AA | 16 | CR2 | | | | | | X | |
| | 5369 | 7/15/2017 | 7/20/2017 | 15:20:00 | 16:30:00 | AA | 16 | CR2 | | | | | | X | |
| | 5369 | 7/22/2017 | 7/27/2017 | 15:20:00 | 16:30:00 | AA | 16 | CR2 | | | | | | X | |
| | 5369 | 7/29/2017 | 8/3/2017 | 15:20:00 | 16:30:00 | AA | 16 | CR2 | | | | | | X | |
| | 4232 | 6/29/2017 | 7/4/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | | X | | X | X | | |
| | 4232 | 7/5/2017 | 7/6/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4232 | 7/5/2017 | 7/13/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4232 | 7/12/2017 | 7/20/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4232 | 7/19/2017 | 7/20/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4232 | 7/19/2017 | 7/27/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4232 | 7/26/2017 | 8/3/2017 | 19:59:00 | 21:08:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| **DEN** | | | | | | | | | | | | | | | |
| | 4249 | 7/1/2017 | 7/6/2017 | 17:20:00 | 19:20:00 | WN | WN | 73H | | | | | | X | |
| | 4249 | 7/8/2017 | 7/13/2017 | 17:20:00 | 19:20:00 | WN | WN | 73H | | | | | | X | |
| | 4249 | 7/15/2017 | 7/20/2017 | 17:20:00 | 19:20:00 | WN | WN | 73H | | | | | | X | |
| | 4249 | 7/22/2017 | 7/27/2017 | 17:20:00 | 19:20:00 | WN | WN | 73H | | | | | | X | |
| | 4249 | 7/29/2017 | 8/3/2017 | 17:20:00 | 19:20:00 | WN | WN | 73H | | | | | | X | |
| | 5169 | 7/2/2017 | 7/6/2017 | 18:25:00 | 20:25:00 | WN | WN | 73W | | | | | | | X |
| | 5169 | 7/9/2017 | 7/13/2017 | 18:25:00 | 20:25:00 | WN | WN | 73W | | | | | | | X |
| | 5169 | 7/16/2017 | 7/20/2017 | 18:25:00 | 20:25:00 | WN | WN | 73W | | | | | | | X |
| | 5169 | 7/23/2017 | 7/27/2017 | 18:25:00 | 20:25:00 | WN | WN | 73W | | | | | | | X |
| | 5169 | 7/30/2017 | 8/3/2017 | 18:25:00 | 20:25:00 | WN | WN | 73W | | | | | | | X |
| **DFW** | | | | | | | | | | | | | | | |
| | 1099 | 6/29/2017 | 7/6/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 1099 | 7/5/2017 | 7/13/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 1099 | 7/12/2017 | 7/20/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 1099 | 7/19/2017 | 7/27/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 1099 | 7/19/2017 | 7/20/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 1099 | 7/26/2017 | 8/3/2017 | 07:05:00 | 09:21:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 294 | 6/29/2017 | 7/4/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | | X | X | X | X |
| | 294 | 7/5/2017 | 7/13/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 294 | 7/5/2017 | 7/6/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 294 | 7/12/2017 | 7/20/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 294 | 7/19/2017 | 7/20/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 294 | 7/19/2017 | 7/27/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| | 294 | 7/26/2017 | 8/3/2017 | 15:15:00 | 17:29:00 | AA | AA | M82 | X | X | X | X | X | X | X |
| **DTW** | | | | | | | | | | | | | | | |
| | 3435 | 7/5/2017 | 7/6/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/5/2017 | 7/13/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/12/2017 | 7/20/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/19/2017 | 7/20/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/19/2017 | 7/21/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/24/2017 | 7/27/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3435 | 7/26/2017 | 8/3/2017 | 07:15:00 | 09:13:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 6228 | 7/9/2017 | 7/13/2017 | 07:15:00 | 09:13:00 | DL | G7 | CR7 | | | | | | | X |
| | 6228 | 7/16/2017 | 7/20/2017 | 07:15:00 | 09:13:00 | DL | G7 | CR7 | | | | | | | X |
| | 6228 | 7/23/2017 | 7/27/2017 | 07:15:00 | 09:13:00 | DL | G7 | CR7 | | | | | | | X |
| | 6228 | 7/30/2017 | 8/3/2017 | 07:15:00 | 09:13:00 | DL | G7 | CR7 | | | | | | | X |
| | 3435 | 7/3/2017 | 7/3/2017 | 09:00:00 | 10:54:00 | DL | 9E | CRJ | X | | | | | | |
| | 3612 | 7/2/2017 | 7/2/2017 | 09:00:00 | 10:54:00 | DL | 9E | CRJ | | | | | | | X |
| | 3435 | 7/1/2017 | 7/1/2017 | 09:20:00 | 11:09:00 | DL | 9E | CRJ | | | | | | X | |
| | 3435 | 7/15/2017 | 7/20/2017 | 09:20:00 | 11:09:00 | DL | 9E | CRJ | | | | | | X | |
| | 3435 | 7/22/2017 | 7/22/2017 | 09:20:00 | 11:09:00 | DL | 9E | CRJ | | | | | | X | |
| | 3435 | 7/29/2017 | 7/29/2017 | 09:20:00 | 11:09:00 | DL | 9E | CRJ | | | | | | X | |
| | 4183 | 7/4/2017 | 7/4/2017 | 09:20:00 | 11:11:00 | DL | 9E | CRJ | | X | | | | | |
| | 3435 | 7/8/2017 | 7/8/2017 | 09:30:00 | 11:19:00 | DL | 9E | CRJ | | | | | | X | |
| | 4582 | 7/6/2017 | 7/6/2017 | 11:00:00 | 12:55:00 | DL | OO | CR7 | | | | X | | | |
| | 4582 | 7/7/2017 | 7/7/2017 | 11:00:00 | 12:55:00 | DL | OO | CR9 | | | | | X | | |
| | 4582 | 7/5/2017 | 7/5/2017 | 11:02:00 | 12:55:00 | DL | OO | CR9 | | | X | | | | |
| | 4582 | 7/5/2017 | 7/5/2017 | 11:02:00 | 12:55:00 | DL | OO | CR9 | | | X | | | | |
| | 3529 | 7/9/2017 | 7/13/2017 | 11:10:00 | 13:05:00 | DL | OO | CR7 | | | | | | | X |
| | 3529 | 7/16/2017 | 7/20/2017 | 11:10:00 | 13:05:00 | DL | OO | CR7 | | | | | | | X |
| | 3529 | 7/23/2017 | 7/27/2017 | 11:10:00 | 13:05:00 | DL | OO | CR7 | | | | | | | X |
| | 3529 | 7/30/2017 | 8/3/2017 | 11:10:00 | 13:05:00 | DL | OO | CR7 | | | | | | | X |
| | 4582 | 7/10/2017 | 7/13/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 4582 | 7/12/2017 | 7/20/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 4582 | 7/19/2017 | 7/20/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 4582 | 7/19/2017 | 7/21/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 4582 | 7/24/2017 | 7/27/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 4582 | 7/26/2017 | 8/3/2017 | 11:10:00 | 13:05:00 | DL | OO | CR9 | X | X | X | X | X | | |
| | 3324 | 7/3/2017 | 7/3/2017 | 12:30:00 | 14:29:00 | DL | 9E | CRJ | X | | | | | | |
| | 6301 | 7/2/2017 | 7/2/2017 | 12:30:00 | 14:29:00 | DL | G7 | CR9 | | | | | | | X |
| | 3324 | 7/4/2017 | 7/4/2017 | 12:40:00 | 14:39:00 | DL | 9E | CRJ | | X | | | | | |
| | 6224 | 7/5/2017 | 7/13/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/5/2017 | 7/6/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/12/2017 | 7/20/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/19/2017 | 7/20/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/19/2017 | 7/21/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/23/2017 | 7/27/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6224 | 7/26/2017 | 8/3/2017 | 14:45:00 | 16:43:00 | DL | G7 | CR7 | X | X | X | X | X | | X |
| | 6304 | 7/1/2017 | 7/1/2017 | 17:00:00 | 19:02:00 | DL | G7 | CR9 | | | | | | X | |
| | 6304 | 7/4/2017 | 7/4/2017 | 17:00:00 | 19:03:00 | DL | G7 | CR9 | | X | | | | | |
| | 6304 | 7/8/2017 | 7/13/2017 | 17:00:00 | 19:02:00 | DL | G7 | CR9 | | | | | | X | |
| | 6304 | 7/15/2017 | 7/20/2017 | 17:00:00 | 19:02:00 | DL | G7 | CR9 | | | | | | X | |
| | 6304 | 7/22/2017 | 7/22/2017 | 17:00:00 | 19:02:00 | DL | G7 | CR9 | | | | | | X | |
| | 6304 | 7/29/2017 | 8/3/2017 | 17:00:00 | 19:02:00 | DL | G7 | CR9 | | | | | | X | |
| | 3379 | 7/2/2017 | 7/2/2017 | 17:10:00 | 19:13:00 | DL | 9E | CRJ | | | | | | | X |
| | 6304 | 7/3/2017 | 7/3/2017 | 17:20:00 | 19:23:00 | DL | G7 | CR9 | X | | | | | | |
| | 6304 | 7/5/2017 | 7/12/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | | | |
| | 6304 | 7/5/2017 | 7/6/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | | | |
| | 6304 | 7/6/2017 | 7/13/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | | X | | X | | | X |
| | 6304 | 7/12/2017 | 7/20/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | X | | |
| | 6304 | 7/13/2017 | 7/20/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | | X | | X | | | X |
| | 6304 | 7/19/2017 | 7/20/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | X | | |
| | 6304 | 7/19/2017 | 7/21/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | X | | |
| | 6304 | 7/20/2017 | 7/20/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | | X | | X | | | X |
| | 6304 | 7/23/2017 | 7/27/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | | X | | X | | | X |
| | 6304 | 7/24/2017 | 7/27/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | X | | |
| | 6304 | 7/26/2017 | 8/3/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | X | | X | | X | | |
| | 6304 | 7/27/2017 | 8/3/2017 | 17:55:00 | 19:47:00 | DL | G7 | CR9 | | X | | X | | | X |
| | 6304 | 7/7/2017 | 7/7/2017 | 18:00:00 | 19:52:00 | DL | G7 | CR9 | | | | | X | | |
| **EWR** | | | | | | | | | | | | | | | |
| | 4866 | 7/5/2017 | 7/5/2017 | 06:00:00 | 07:30:00 | UA | C5 | ERJ | | | X | | | | |
| | 4866 | 7/5/2017 | 7/5/2017 | 06:00:00 | 07:30:00 | UA | C5 | ERJ | | | X | | | | |
| | 3593 | 7/3/2017 | 7/4/2017 | 06:06:00 | 07:36:00 | UA | YX | E7W | X | X | | | | | |
| | 3593 | 7/2/2017 | 7/6/2017 | 06:10:00 | 07:40:00 | UA | YX | E7W | | | | | | | X |
| | 3593 | 7/9/2017 | 7/13/2017 | 06:10:00 | 07:40:00 | UA | YX | E7W | | | | | | | X |
| | 3593 | 7/16/2017 | 7/20/2017 | 06:10:00 | 07:40:00 | UA | YX | E7W | | | | | | | X |
| | 3593 | 7/23/2017 | 7/27/2017 | 06:10:00 | 07:40:00 | UA | YX | E7W | | | | | | | X |
| | 3593 | 7/30/2017 | 8/3/2017 | 06:10:00 | 07:40:00 | UA | YX | E7W | | | | | | | X |
| | 3613 | 7/7/2017 | 7/7/2017 | 06:10:00 | 07:40:00 | UA | YX | E70 | | | | | X | | |
| | 4866 | 7/6/2017 | 7/13/2017 | 06:10:00 | 07:40:00 | UA | C5 | ERJ | X | X | X | X | | X | |
| | 4866 | 7/12/2017 | 7/20/2017 | 06:10:00 | 07:40:00 | UA | C5 | ERJ | X | X | X | X | X | X | |
| | 4866 | 7/19/2017 | 7/27/2017 | 06:10:00 | 07:40:00 | UA | C5 | ERJ | X | X | X | X | X | X | |
| | 4866 | 7/19/2017 | 7/20/2017 | 06:10:00 | 07:40:00 | UA | C5 | ERJ | X | X | X | X | X | X | |
| | 4866 | 7/26/2017 | 8/3/2017 | 06:10:00 | 07:40:00 | UA | C5 | ERJ | X | X | X | X | X | X | |
| | 4430 | 7/16/2017 | 7/16/2017 | 08:00:00 | 09:30:00 | UA | EV | ERJ | | | | | | | X |
| | 4430 | 7/1/2017 | 7/2/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | | | | | | X | X |
| | 4430 | 7/5/2017 | 7/13/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | X |
| | 4430 | 7/5/2017 | 7/6/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | X |
| | 4430 | 7/12/2017 | 7/20/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | |
| | 4430 | 7/19/2017 | 7/27/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | X |
| | 4430 | 7/19/2017 | 7/20/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | X |
| | 4430 | 7/26/2017 | 8/3/2017 | 08:05:00 | 09:35:00 | UA | EV | ERJ | X | X | X | X | X | X | X |
| | 4420 | 7/4/2017 | 7/4/2017 | 10:25:00 | 11:54:00 | UA | EV | ERJ | | X | | | | | |
| | 4420 | 7/2/2017 | 7/6/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | | | X |
| | 4420 | 7/5/2017 | 7/13/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | | | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 4420 | 7/11/2017 | 7/13/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | | X | | | | | |
| | 4420 | 7/12/2017 | 7/20/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | X | | X |
| | 4420 | 7/18/2017 | 7/20/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | | X | | | | | |
| | 4420 | 7/19/2017 | 7/20/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | X | | X |
| | 4420 | 7/19/2017 | 7/27/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | X | | X |
| | 4420 | 7/25/2017 | 7/27/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | | X | | | | | |
| | 4420 | 7/26/2017 | 8/3/2017 | 10:36:00 | 12:05:00 | UA | EV | ERJ | X | | X | X | X | | X |
| | 4841 | 7/1/2017 | 7/1/2017 | 10:36:00 | 12:05:00 | UA | C5 | ERJ | | | | | | X | |
| | 4903 | 7/8/2017 | 7/13/2017 | 10:36:00 | 12:05:00 | UA | C5 | ERJ | | | | | | X | |
| | 4903 | 7/15/2017 | 7/20/2017 | 10:36:00 | 12:05:00 | UA | C5 | ERJ | | | | | | X | |
| | 4903 | 7/22/2017 | 7/27/2017 | 10:36:00 | 12:05:00 | UA | C5 | ERJ | | | | | | X | |
| | 4903 | 7/29/2017 | 7/29/2017 | 10:36:00 | 12:05:00 | UA | C5 | ERJ | | | | | | X | |
| | 4981 | 7/7/2017 | 7/7/2017 | 10:38:00 | 12:30:00 | UA | C5 | DH2 | | | | | X | | |
| | 4421 | 7/5/2017 | 7/13/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | | | |
| | 4421 | 7/5/2017 | 7/6/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | | | |
| | 4421 | 7/12/2017 | 7/20/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 4421 | 7/19/2017 | 7/27/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 4421 | 7/19/2017 | 7/20/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 4421 | 7/26/2017 | 8/3/2017 | 14:15:00 | 15:49:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 4869 | 7/2/2017 | 7/2/2017 | 14:15:00 | 16:18:00 | UA | C5 | DH2 | | | | | | | X |
| | 4869 | 7/9/2017 | 7/13/2017 | 14:15:00 | 16:18:00 | UA | C5 | DH2 | | | | | | | X |
| | 4869 | 7/16/2017 | 7/20/2017 | 14:15:00 | 16:18:00 | UA | C5 | DH2 | | | | | | | X |
| | 4869 | 7/23/2017 | 7/27/2017 | 14:15:00 | 16:18:00 | UA | C5 | DH2 | | | | | | | X |
| | 4869 | 7/30/2017 | 8/3/2017 | 14:15:00 | 16:18:00 | UA | C5 | DH2 | | | | | | | X |
| | 4969 | 7/7/2017 | 7/7/2017 | 14:20:00 | 16:23:00 | UA | C5 | DH2 | | | | | X | | |
| | 4869 | 7/3/2017 | 7/3/2017 | 14:21:00 | 16:24:00 | UA | C5 | DH2 | X | | | | | | |
| | 4421 | 7/1/2017 | 7/1/2017 | 14:25:00 | 15:59:00 | UA | EV | ERJ | | | | | | X | |
| | 3653 | 7/4/2017 | 7/4/2017 | 14:30:00 | 16:04:00 | UA | YX | E70 | | X | | | | | |
| | 3732 | 7/8/2017 | 7/13/2017 | 14:30:00 | 16:04:00 | UA | YX | E70 | | | | | | X | |
| | 3732 | 7/15/2017 | 7/20/2017 | 14:30:00 | 16:04:00 | UA | YX | E70 | | | | | | X | |
| | 3732 | 7/22/2017 | 7/27/2017 | 14:30:00 | 16:04:00 | UA | YX | E70 | | | | | | X | |
| | 3732 | 7/29/2017 | 8/3/2017 | 14:30:00 | 16:04:00 | UA | YX | E70 | | | | | | X | |
| | 4815 | 7/5/2017 | 7/6/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/5/2017 | 7/13/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/12/2017 | 7/20/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/19/2017 | 7/27/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/19/2017 | 7/20/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/26/2017 | 8/3/2017 | 17:10:00 | 18:40:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4815 | 7/1/2017 | 7/1/2017 | 17:15:00 | 18:45:00 | UA | C5 | ERJ | | | | | | X | |
| | 4381 | 7/2/2017 | 7/2/2017 | 17:19:00 | 18:49:00 | UA | EV | ERJ | | | | | | | X |
| | 4815 | 7/3/2017 | 7/4/2017 | 17:19:00 | 19:15:00 | UA | C5 | DH2 | X | X | | | | | |
| | 4815 | 7/8/2017 | 7/8/2017 | 17:19:00 | 19:15:00 | UA | C5 | DH2 | | | | | | X | |
| | 4815 | 7/22/2017 | 7/27/2017 | 17:19:00 | 19:15:00 | UA | C5 | DH2 | | | | | | X | |
| | 4815 | 7/29/2017 | 8/3/2017 | 17:19:00 | 19:15:00 | UA | C5 | DH2 | | | | | | X | |
| | 4815 | 7/15/2017 | 7/15/2017 | 17:28:00 | 19:24:00 | UA | C5 | DH2 | | | | | | X | |
| | 4815 | 7/9/2017 | 7/13/2017 | 17:30:00 | 19:00:00 | UA | C5 | ERJ | | | | | | | X |
| | 4815 | 7/16/2017 | 7/20/2017 | 17:30:00 | 19:00:00 | UA | C5 | ERJ | | | | | | | X |
| | 4815 | 7/23/2017 | 7/27/2017 | 17:30:00 | 19:00:00 | UA | C5 | ERJ | | | | | | | X |
| | 4815 | 7/30/2017 | 7/30/2017 | 17:30:00 | 19:00:00 | UA | C5 | ERJ | | | | | | | X |
| | 3416 | 7/9/2017 | 7/13/2017 | 19:00:00 | 20:35:00 | UA | YX | E70 | | | | | | | X |
| | 3416 | 7/16/2017 | 7/20/2017 | 19:00:00 | 20:35:00 | UA | YX | E70 | | | | | | | X |
| | 3416 | 7/23/2017 | 7/27/2017 | 19:00:00 | 20:35:00 | UA | YX | E70 | | | | | | | X |
| | 3416 | 7/30/2017 | 7/30/2017 | 19:00:00 | 20:35:00 | UA | YX | E70 | | | | | | | X |
| | 3827 | 7/1/2017 | 7/6/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | | | X | X | X | X | |
| | 3827 | 7/5/2017 | 7/13/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 3827 | 7/12/2017 | 7/20/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 3827 | 7/19/2017 | 7/20/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 3827 | 7/19/2017 | 7/27/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 3827 | 7/26/2017 | 8/3/2017 | 19:05:00 | 20:40:00 | UA | EV | ERJ | X | X | X | X | X | | |
| | 3827 | 7/2/2017 | 7/6/2017 | 19:14:00 | 20:49:00 | UA | EV | ERJ | X | | | | | X | X |
| | 3827 | 7/8/2017 | 7/13/2017 | 19:14:00 | 20:49:00 | UA | EV | ERJ | | | | | | X | |
| | 3827 | 7/15/2017 | 7/20/2017 | 19:14:00 | 20:49:00 | UA | EV | ERJ | | | | | | X | |
| | 3827 | 7/22/2017 | 7/27/2017 | 19:14:00 | 20:49:00 | UA | EV | ERJ | | | | | | X | |
| | 3827 | 7/29/2017 | 8/3/2017 | 19:14:00 | 20:49:00 | UA | EV | ERJ | | | | | | X | |
| **IAD** | | | | | | | | | | | | | | | |
| | 1472 | 7/1/2017 | 7/1/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | | | | X | |
| | 1472 | 7/2/2017 | 7/2/2017 | 06:20:00 | 07:18:00 | UA | UA | 739 | | | | | | | X |
| | 1472 | 7/3/2017 | 7/6/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | X | | | X | X | X | |
| | 1472 | 7/4/2017 | 7/4/2017 | 06:20:00 | 07:18:00 | UA | UA | 739 | | X | | | | | |
| | 1472 | 7/5/2017 | 7/6/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/5/2017 | 7/13/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/6/2017 | 7/13/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | X | X | | X | X | X | |
| | 1472 | 7/9/2017 | 7/13/2017 | 06:20:00 | 07:17:00 | UA | UA | 739 | | | | | | | X |
| | 1472 | 7/12/2017 | 7/20/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/13/2017 | 7/20/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | X | X | | X | X | X | |
| | 1472 | 7/16/2017 | 7/20/2017 | 06:20:00 | 07:17:00 | UA | UA | 739 | | | | | | | X |
| | 1472 | 7/19/2017 | 7/27/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/19/2017 | 7/20/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/20/2017 | 7/27/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | X | X | | X | X | X | |
| | 1472 | 7/23/2017 | 7/23/2017 | 06:20:00 | 07:17:00 | UA | UA | 739 | | | | | | | X |
| | 1472 | 7/26/2017 | 8/3/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | | | X | | | | |
| | 1472 | 7/27/2017 | 8/3/2017 | 06:20:00 | 07:17:00 | UA | UA | 320 | X | X | | X | X | X | |
| | 1472 | 7/30/2017 | 7/30/2017 | 06:20:00 | 07:17:00 | UA | UA | 739 | | | | | | | X |
| | 237 | 7/2/2017 | 7/6/2017 | 10:30:00 | 11:30:00 | UA | UA | 739 | | | | | | | X |
| | 237 | 7/9/2017 | 7/13/2017 | 10:30:00 | 11:30:00 | UA | UA | 739 | | | | | | | X |
| | 237 | 7/16/2017 | 7/20/2017 | 10:30:00 | 11:30:00 | UA | UA | 739 | | | | | | | X |
| | 237 | 7/23/2017 | 7/27/2017 | 10:30:00 | 11:30:00 | UA | UA | 739 | | | | | | | X |
| | 237 | 7/30/2017 | 8/3/2017 | 10:30:00 | 11:30:00 | UA | UA | 739 | | | | | | | X |
| | 4748 | 7/1/2017 | 7/4/2017 | 10:30:00 | 11:30:00 | UA | AX | ER4 | | X | | | | X | |
| | 4970 | 7/5/2017 | 7/6/2017 | 10:30:00 | 11:38:00 | UA | C5 | DH2 | | | X | X | X | X | |
| | 4970 | 7/5/2017 | 7/8/2017 | 10:30:00 | 11:38:00 | UA | C5 | DH2 | | | X | X | X | X | |
| | 4970 | 7/10/2017 | 7/13/2017 | 10:30:00 | 11:30:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4970 | 7/12/2017 | 7/20/2017 | 10:30:00 | 11:30:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4970 | 7/15/2017 | 7/20/2017 | 10:30:00 | 11:38:00 | UA | C5 | DH2 | | | | | | X | |
| | 4970 | 7/19/2017 | 7/27/2017 | 10:30:00 | 11:30:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4970 | 7/19/2017 | 7/20/2017 | 10:30:00 | 11:30:00 | UA | C5 | ERJ | X | X | X | X | X | | |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 4970 | 7/22/2017 | 7/27/2017 | 10:30:00 | 11:38:00 | UA | C5 | DH2 | | | | | | X | |
| | 4970 | 7/26/2017 | 8/3/2017 | 10:30:00 | 11:30:00 | UA | C5 | ERJ | X | X | X | X | X | | |
| | 4970 | 7/29/2017 | 8/3/2017 | 10:30:00 | 11:38:00 | UA | C5 | DH2 | | | | | X | X | |
| | 6254 | 7/3/2017 | 7/3/2017 | 10:30:00 | 11:30:00 | UA | YV | CR7 | X | | | | | | |
| | 249 | 7/3/2017 | 7/3/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | | | | | |
| | 249 | 7/4/2017 | 7/6/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | X | X | | | | |
| | 249 | 7/5/2017 | 7/13/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | X | | X | | |
| | 249 | 7/6/2017 | 7/13/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | | X | | | |
| | 249 | 7/11/2017 | 7/13/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | X | | | | | |
| | 249 | 7/12/2017 | 7/19/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | X | | X | | |
| | 249 | 7/13/2017 | 7/20/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | | X | | | |
| | 249 | 7/18/2017 | 7/20/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | X | | | | | |
| | 249 | 7/19/2017 | 7/19/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | X | | | | |
| | 249 | 7/19/2017 | 7/19/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | X | | | | |
| | 249 | 7/20/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | | X | | | |
| | 249 | 7/21/2017 | 7/21/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | | | X | | |
| | 249 | 7/24/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | | | | | |
| | 249 | 7/25/2017 | 7/25/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | X | | | | | |
| | 249 | 7/26/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | X | | X | | |
| | 249 | 7/26/2017 | 7/28/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | X | | X | | |
| | 249 | 7/27/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | | | | X | | | |
| | 249 | 7/31/2017 | 7/31/2017 | 14:50:00 | 15:47:00 | UA | UA | 320 | X | | | | | | |
| | 6148 | 7/1/2017 | 7/6/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | X | |
| | 6148 | 7/2/2017 | 7/6/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | | X |
| | 6148 | 7/8/2017 | 7/8/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | X | |
| | 6148 | 7/9/2017 | 7/13/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | | X |
| | 6148 | 7/15/2017 | 7/15/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | X | |
| | 6148 | 7/16/2017 | 7/20/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | | X |
| | 6148 | 7/22/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | X | |
| | 6148 | 7/23/2017 | 7/27/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | | X |
| | 6148 | 7/29/2017 | 8/3/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | X | |
| | 6148 | 7/30/2017 | 8/3/2017 | 14:50:00 | 15:47:00 | UA | YV | CR7 | | | | | | | X |
| | 6174 | 7/23/2017 | 7/23/2017 | 19:40:00 | 20:40:00 | UA | YV | CR7 | | | | | | | X |
| | 6174 | 7/23/2017 | 7/23/2017 | 19:40:00 | 20:40:00 | UA | YV | CR7 | | | | | | | X |
| | 4683 | 7/15/2017 | 7/15/2017 | 19:45:00 | 20:45:00 | UA | AX | ER4 | | | | | | X | |
| | 6064 | 7/1/2017 | 7/1/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | | | | | | X | |
| | 6174 | 7/4/2017 | 7/4/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | X | | | | | |
| | 6174 | 7/5/2017 | 7/13/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/5/2017 | 7/6/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/8/2017 | 7/8/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | | | | | X | |
| | 6174 | 7/9/2017 | 7/13/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | | | | | | X |
| | 6174 | 7/12/2017 | 7/20/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/16/2017 | 7/16/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | | | | | | X |
| | 6174 | 7/19/2017 | 7/27/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/19/2017 | 7/20/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/22/2017 | 7/22/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | | | | | X | |
| | 6174 | 7/26/2017 | 8/3/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | X | X | X | X | X | | |
| | 6174 | 7/29/2017 | 8/3/2017 | 19:45:00 | 20:45:00 | UA | YV | E7W | | | | | | X | |
| | 6174 | 7/30/2017 | 7/30/2017 | 19:45:00 | 20:45:00 | UA | YV | CR7 | | | | | | | X |
| **IAH** | | | | | | | | | | | | | | | |
| | 3924 | 7/3/2017 | 7/6/2017 | 06:00:00 | 08:13:00 | UA | EV | ERJ | X | | | | | | X |
| | 3924 | 7/9/2017 | 7/13/2017 | 06:00:00 | 08:13:00 | UA | EV | ERJ | | | | | | | X |
| | 3924 | 7/16/2017 | 7/20/2017 | 06:00:00 | 08:13:00 | UA | EV | ERJ | | | | | | | X |
| | 3924 | 7/23/2017 | 7/27/2017 | 06:00:00 | 08:13:00 | UA | EV | ERJ | | | | | | | X |
| | 3924 | 7/30/2017 | 7/30/2017 | 06:00:00 | 08:13:00 | UA | EV | ERJ | | | | | | | X |
| | 5492 | 7/4/2017 | 7/4/2017 | 06:00:00 | 08:05:00 | UA | OO | CR7 | | X | | | | | |
| | 6060 | 7/1/2017 | 7/6/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | | | | X | X | X | X |
| | 6060 | 7/6/2017 | 7/13/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | X | X | X | X | X | X | |
| | 6060 | 7/12/2017 | 7/20/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | X | X | X | X | X | X | |
| | 6060 | 7/19/2017 | 7/27/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | X | X | X | X | X | X | |
| | 6060 | 7/19/2017 | 7/20/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | X | X | X | X | X | X | |
| | 6060 | 7/26/2017 | 8/3/2017 | 06:00:00 | 08:13:00 | UA | YV | E7W | X | X | X | X | X | X | |
| | 6060 | 7/5/2017 | 7/5/2017 | 06:10:00 | 08:23:00 | UA | YV | E7W | | | X | | | | |
| | 6060 | 7/5/2017 | 7/5/2017 | 06:10:00 | 08:23:00 | UA | YV | E7W | | | X | | | | |
| **JFK** | | | | | | | | | | | | | | | |
| | 3303 | 7/1/2017 | 7/1/2017 | 06:08:00 | 07:28:00 | DL | 9E | CRJ | | | | | | X | |
| | 3303 | 7/2/2017 | 7/2/2017 | 06:08:00 | 07:29:00 | DL | 9E | CRJ | | | | | | | X |
| | 3303 | 7/8/2017 | 7/13/2017 | 06:08:00 | 07:28:00 | DL | 9E | CRJ | | | | | | X | |
| | 3303 | 7/15/2017 | 7/20/2017 | 06:08:00 | 07:28:00 | DL | 9E | CRJ | | | | | | X | |
| | 3303 | 7/22/2017 | 7/22/2017 | 06:08:00 | 07:28:00 | DL | 9E | CRJ | | | | | | X | |
| | 3303 | 7/29/2017 | 8/3/2017 | 06:08:00 | 07:28:00 | DL | 9E | CRJ | | | | | | X | |
| | 3303 | 7/3/2017 | 7/6/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/5/2017 | 7/13/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/12/2017 | 7/20/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/19/2017 | 7/20/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/19/2017 | 7/21/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/23/2017 | 7/27/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3303 | 7/26/2017 | 8/3/2017 | 07:00:00 | 08:25:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3364 | 7/1/2017 | 7/6/2017 | 13:50:00 | 15:18:00 | AA | MQ | ER4 | | | | | | X | |
| | 3364 | 7/8/2017 | 7/13/2017 | 13:50:00 | 15:18:00 | AA | MQ | ER4 | | | | | | X | |
| | 3364 | 7/15/2017 | 7/20/2017 | 13:50:00 | 15:18:00 | AA | MQ | ER4 | | | | | | X | |
| | 3364 | 7/22/2017 | 7/27/2017 | 13:50:00 | 15:18:00 | AA | MQ | ER4 | | | | | | X | |
| | 3364 | 7/29/2017 | 8/3/2017 | 13:50:00 | 15:18:00 | AA | MQ | ER4 | | | | | | X | |
| | 4276 | 6/29/2017 | 7/6/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4276 | 7/5/2017 | 7/13/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4276 | 7/12/2017 | 7/20/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4276 | 7/19/2017 | 7/20/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4276 | 7/19/2017 | 7/27/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4276 | 7/26/2017 | 8/3/2017 | 13:55:00 | 15:19:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 3514 | 7/8/2017 | 7/13/2017 | 16:40:00 | 18:14:00 | DL | 9E | CRJ | | | | | | X | |
| | 3514 | 7/15/2017 | 7/20/2017 | 16:40:00 | 18:14:00 | DL | 9E | CRJ | | | | | | X | |
| | 3514 | 7/22/2017 | 7/22/2017 | 16:40:00 | 18:14:00 | DL | 9E | CRJ | | | | | | X | |
| | 3514 | 7/29/2017 | 7/29/2017 | 16:40:00 | 18:14:00 | DL | 9E | CRJ | | | | | | X | |
| | 3514 | 7/3/2017 | 7/3/2017 | 17:05:00 | 18:39:00 | DL | 9E | CRJ | X | | | | | | |
| | 3514 | 7/2/2017 | 7/2/2017 | 17:06:00 | 18:40:00 | DL | 9E | CRJ | | | | | | | X |
| | 3514 | 7/1/2017 | 7/1/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | | | | | | X | |
| | 3514 | 7/4/2017 | 7/6/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 3514 | 7/5/2017 | 7/13/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3514 | 7/12/2017 | 7/20/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3514 | 7/19/2017 | 7/20/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3514 | 7/19/2017 | 7/21/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3514 | 7/23/2017 | 7/27/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3514 | 7/26/2017 | 8/3/2017 | 17:16:00 | 18:50:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| **LGA** | | | | | | | | | | | | | | | |
| | 3433 | 6/29/2017 | 7/6/2017 | 06:05:00 | 07:28:00 | AA | MQ | ER4 | | X | | X | X | | |
| | 3433 | 7/6/2017 | 7/13/2017 | 06:05:00 | 07:28:00 | AA | MQ | ER4 | X | X | | X | X | | |
| | 3433 | 7/13/2017 | 7/20/2017 | 06:05:00 | 07:28:00 | AA | MQ | ER4 | X | X | | X | X | | |
| | 3433 | 7/20/2017 | 7/27/2017 | 06:05:00 | 07:28:00 | AA | MQ | ER4 | X | X | | X | X | | |
| | 3433 | 7/27/2017 | 8/3/2017 | 06:05:00 | 07:28:00 | AA | MQ | ER4 | X | X | | X | X | | |
| | 3441 | 7/5/2017 | 7/6/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/5/2017 | 7/13/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/12/2017 | 7/20/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/19/2017 | 7/20/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/19/2017 | 7/21/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/24/2017 | 7/27/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3441 | 7/26/2017 | 8/3/2017 | 06:05:00 | 07:34:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 4178 | 6/29/2017 | 7/6/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | |
| | 4178 | 7/5/2017 | 7/13/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4178 | 7/12/2017 | 7/20/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4178 | 7/19/2017 | 7/20/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4178 | 7/19/2017 | 7/27/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4178 | 7/26/2017 | 8/3/2017 | 09:01:00 | 10:30:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 3441 | 7/1/2017 | 7/6/2017 | 09:15:00 | 10:40:00 | DL | 9E | CRJ | | | | | | X | |
| | 3441 | 7/8/2017 | 7/13/2017 | 09:15:00 | 10:40:00 | DL | 9E | CRJ | | | | | | X | |
| | 3441 | 7/15/2017 | 7/20/2017 | 09:15:00 | 10:40:00 | DL | 9E | CRJ | | | | | | X | |
| | 3441 | 7/22/2017 | 7/22/2017 | 09:15:00 | 10:40:00 | DL | 9E | CRJ | | | | | | X | |
| | 3441 | 7/29/2017 | 8/3/2017 | 09:15:00 | 10:40:00 | DL | 9E | CRJ | | | | | | X | |
| | 3969 | 7/2/2017 | 7/2/2017 | 09:15:00 | 10:41:00 | DL | 9E | CRJ | | | | | | | X |
| | 3969 | 7/4/2017 | 7/4/2017 | 09:15:00 | 10:41:00 | DL | 9E | CRJ | | X | | | | | |
| | 3969 | 7/3/2017 | 7/3/2017 | 09:20:00 | 10:45:00 | DL | 9E | CRJ | X | | | | | | |
| | 3969 | 7/5/2017 | 7/6/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/5/2017 | 7/13/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/12/2017 | 7/20/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/19/2017 | 7/20/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/19/2017 | 7/21/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/23/2017 | 7/27/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3969 | 7/26/2017 | 8/3/2017 | 10:15:00 | 11:48:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3364 | 6/29/2017 | 7/6/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | X | | X | X | | X |
| | 3364 | 7/3/2017 | 7/5/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | X | | X | | | | |
| | 3364 | 7/5/2017 | 7/13/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | | X | | | | |
| | 3364 | 7/6/2017 | 7/13/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | X | X | | X | X | | X |
| | 3364 | 7/12/2017 | 7/20/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | | X | | | | |
| | 3364 | 7/13/2017 | 7/20/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | X | X | | X | X | | X |
| | 3364 | 7/19/2017 | 7/27/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | | X | | | | |
| | 3364 | 7/19/2017 | 7/20/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | | X | | | | |
| | 3364 | 7/20/2017 | 7/27/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | X | X | | X | X | | X |
| | 3364 | 7/26/2017 | 7/26/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | | | X | | | | |
| | 3364 | 7/27/2017 | 8/3/2017 | 12:30:00 | 14:00:00 | AA | MQ | ER4 | X | X | | X | X | | X |
| | 3975 | 7/5/2017 | 7/13/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/5/2017 | 7/6/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/12/2017 | 7/20/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/19/2017 | 7/20/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/19/2017 | 7/21/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/23/2017 | 7/27/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3975 | 7/26/2017 | 8/3/2017 | 12:30:00 | 14:15:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3494 | 7/2/2017 | 7/4/2017 | 15:15:00 | 16:59:00 | DL | 9E | CRJ | | X | | | | | X |
| | 3494 | 7/3/2017 | 7/3/2017 | 15:15:00 | 17:00:00 | DL | 9E | CRJ | X | | | | | | |
| | 3788 | 7/1/2017 | 7/6/2017 | 15:20:00 | 16:50:00 | AA | MQ | ER4 | | | | | | X | |
| | 3788 | 7/8/2017 | 7/13/2017 | 15:20:00 | 16:50:00 | AA | MQ | ER4 | | | | | | X | |
| | 3788 | 7/15/2017 | 7/20/2017 | 15:20:00 | 16:50:00 | AA | MQ | ER4 | | | | | | X | |
| | 3788 | 7/22/2017 | 7/27/2017 | 15:20:00 | 16:50:00 | AA | MQ | ER4 | | | | | | X | |
| | 3788 | 7/29/2017 | 8/3/2017 | 15:20:00 | 16:50:00 | AA | MQ | ER4 | | | | | | X | |
| | 3494 | 7/1/2017 | 7/6/2017 | 15:40:00 | 17:23:00 | DL | 9E | CRJ | | | | | | X | |
| | 3494 | 7/8/2017 | 7/13/2017 | 15:40:00 | 17:23:00 | DL | 9E | CRJ | | | | | | X | |
| | 3494 | 7/15/2017 | 7/20/2017 | 15:40:00 | 17:23:00 | DL | 9E | CRJ | | | | | | X | |
| | 3494 | 7/22/2017 | 7/22/2017 | 15:40:00 | 17:23:00 | DL | 9E | CRJ | | | | | | X | |
| | 3494 | 7/29/2017 | 8/3/2017 | 15:40:00 | 17:23:00 | DL | 9E | CRJ | | | | | | X | |
| | 3494 | 7/5/2017 | 7/13/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3494 | 7/5/2017 | 7/6/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | |
| | 3494 | 7/9/2017 | 7/9/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | | | | | | | X |
| | 3494 | 7/12/2017 | 7/20/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3494 | 7/19/2017 | 7/20/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3494 | 7/19/2017 | 7/21/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3494 | 7/23/2017 | 7/27/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3494 | 7/26/2017 | 8/3/2017 | 16:20:00 | 17:58:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3443 | 7/5/2017 | 7/6/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/5/2017 | 7/13/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/12/2017 | 7/20/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/19/2017 | 7/20/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/19/2017 | 7/27/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/26/2017 | 7/26/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 7/27/2017 | 8/3/2017 | 18:25:00 | 20:01:00 | AA | MQ | ER4 | X | X | X | X | X | | |
| | 3443 | 6/29/2017 | 7/4/2017 | 18:30:00 | 20:01:00 | AA | MQ | ER4 | X | X | | X | X | | |
| | 3397 | 7/9/2017 | 7/13/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3397 | 7/12/2017 | 7/20/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3397 | 7/19/2017 | 7/20/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3397 | 7/19/2017 | 7/21/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3397 | 7/23/2017 | 7/27/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3397 | 7/26/2017 | 8/3/2017 | 18:55:00 | 20:33:00 | DL | 9E | CRJ | X | X | X | X | X | | X |
| | 3443 | 7/2/2017 | 7/6/2017 | 18:59:00 | 20:30:00 | AA | MQ | ER4 | | | | | | | X |
| | 3443 | 7/9/2017 | 7/13/2017 | 18:59:00 | 20:30:00 | AA | MQ | ER4 | | | | | | | X |
| | 3443 | 7/16/2017 | 7/20/2017 | 18:59:00 | 20:30:00 | AA | MQ | ER4 | | | | | | | X |
| | 3443 | 7/23/2017 | 7/27/2017 | 18:59:00 | 20:30:00 | AA | MQ | ER4 | | | | | | | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 3443 | 7/30/2017 | 8/3/2017 | 18:59:00 | 20:30:00 | AA | MQ | ER4 | | | | | | | X |
| **MCO** | | | | | | | | | | | | | | | |
| | 4732 | 7/1/2017 | 7/6/2017 | 09:20:00 | 11:10:00 | WN | WN | 73C | | | | | | X | |
| | 4732 | 7/8/2017 | 7/13/2017 | 09:20:00 | 11:10:00 | WN | WN | 73C | | | | | | X | |
| | 4732 | 7/15/2017 | 7/20/2017 | 09:20:00 | 11:10:00 | WN | WN | 73C | | | | | | X | |
| | 4732 | 7/22/2017 | 7/27/2017 | 09:20:00 | 11:10:00 | WN | WN | 73C | | | | | | X | |
| | 4732 | 7/29/2017 | 8/3/2017 | 09:20:00 | 11:10:00 | WN | WN | 73C | | | | | | X | |
| | 1755 | 6/28/2017 | 7/6/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | | | X | X | X | | |
| | 1755 | 7/4/2017 | 7/4/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | | X | | | | | |
| | 1755 | 7/5/2017 | 7/13/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1755 | 7/12/2017 | 7/20/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1755 | 7/19/2017 | 7/20/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1755 | 7/19/2017 | 7/27/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1755 | 7/26/2017 | 8/3/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 5441 | 7/3/2017 | 7/3/2017 | 09:50:00 | 11:40:00 | WN | WN | 73W | X | | | | | | |
| | 1253 | 7/2/2017 | 7/6/2017 | 11:50:00 | 13:40:00 | WN | WN | 73C | | | | | | | X |
| | 1253 | 7/9/2017 | 7/13/2017 | 11:50:00 | 13:40:00 | WN | WN | 73C | | | | | | | X |
| | 1253 | 7/16/2017 | 7/20/2017 | 11:50:00 | 13:40:00 | WN | WN | 73C | | | | | | | X |
| | 1253 | 7/23/2017 | 7/23/2017 | 11:50:00 | 13:40:00 | WN | WN | 73C | | | | | | | X |
| | 1253 | 7/30/2017 | 8/3/2017 | 11:50:00 | 13:40:00 | WN | WN | 73W | | | | | | | X |
| | 2489 | 7/1/2017 | 7/6/2017 | 15:35:00 | 17:25:00 | WN | WN | 73H | | | | | | X | |
| | 2489 | 7/8/2017 | 7/13/2017 | 15:35:00 | 17:25:00 | WN | WN | 73H | | | | | | X | |
| | 2489 | 7/15/2017 | 7/20/2017 | 15:35:00 | 17:25:00 | WN | WN | 73H | | | | | | X | |
| | 2489 | 7/22/2017 | 7/27/2017 | 15:35:00 | 17:25:00 | WN | WN | 73H | | | | | | X | |
| | 2489 | 7/29/2017 | 8/3/2017 | 15:35:00 | 17:25:00 | WN | WN | 73H | | | | | | X | |
| **MDW** | | | | | | | | | | | | | | | |
| | 1348 | 6/28/2017 | 7/6/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | | X | X | X | X | | |
| | 1348 | 7/3/2017 | 7/3/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | | | | | | |
| | 1348 | 7/5/2017 | 7/13/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/12/2017 | 7/20/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/19/2017 | 7/27/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/19/2017 | 7/20/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/26/2017 | 8/3/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/19/2017 | 7/20/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 1348 | 7/26/2017 | 8/3/2017 | 05:30:00 | 06:35:00 | WN | WN | 73H | X | X | X | X | X | | |
| | 730 | 7/2/2017 | 7/6/2017 | 06:30:00 | 07:35:00 | WN | WN | 73W | | | | | | | X |
| | 730 | 7/9/2017 | 7/13/2017 | 06:30:00 | 07:35:00 | WN | WN | 73W | | | | | | | X |
| | 730 | 7/16/2017 | 7/20/2017 | 06:30:00 | 07:35:00 | WN | WN | 73W | | | | | | | X |
| | 730 | 7/23/2017 | 7/27/2017 | 06:30:00 | 07:35:00 | WN | WN | 73W | | | | | | | X |
| | 730 | 7/30/2017 | 8/3/2017 | 06:30:00 | 07:35:00 | WN | WN | 73W | | | | | | | X |
| | 1247 | 7/1/2017 | 7/6/2017 | 07:05:00 | 08:10:00 | WN | WN | 73H | | | | | | X | |
| | 1247 | 7/8/2017 | 7/13/2017 | 07:05:00 | 08:10:00 | WN | WN | 73H | | | | | | X | |
| | 1247 | 7/15/2017 | 7/20/2017 | 07:05:00 | 08:10:00 | WN | WN | 73H | | | | | | X | |
| | 1247 | 7/22/2017 | 7/27/2017 | 07:05:00 | 08:10:00 | WN | WN | 73H | | | | | | X | |
| | 1247 | 7/29/2017 | 8/3/2017 | 07:05:00 | 08:10:00 | WN | WN | 73H | | | | | | X | |
| | 2515 | 7/1/2017 | 7/6/2017 | 13:15:00 | 14:20:00 | WN | WN | 73W | | | | | | X | |
| | 2515 | 7/8/2017 | 7/13/2017 | 13:15:00 | 14:20:00 | WN | WN | 73W | | | | | | X | |
| | 2515 | 7/15/2017 | 7/20/2017 | 13:15:00 | 14:20:00 | WN | WN | 73W | | | | | | X | |
| | 2515 | 7/22/2017 | 7/27/2017 | 13:15:00 | 14:20:00 | WN | WN | 73W | | | | | | X | |
| | 2515 | 7/29/2017 | 8/3/2017 | 13:15:00 | 14:20:00 | WN | WN | 73W | | | | | | X | |
| | 3694 | 7/2/2017 | 7/6/2017 | 17:00:00 | 18:10:00 | WN | WN | 73W | | | | | | | X |
| | 3694 | 7/9/2017 | 7/13/2017 | 17:00:00 | 18:10:00 | WN | WN | 73W | | | | | | | X |
| | 3694 | 7/16/2017 | 7/20/2017 | 17:00:00 | 18:10:00 | WN | WN | 73W | | | | | | | X |
| | 3694 | 7/23/2017 | 7/27/2017 | 17:00:00 | 18:10:00 | WN | WN | 73W | | | | | | | X |
| | 3694 | 7/30/2017 | 8/3/2017 | 17:00:00 | 18:10:00 | WN | WN | 73W | | | | | | | X |
| | 1052 | 7/3/2017 | 7/3/2017 | 17:25:00 | 18:30:00 | WN | WN | 73W | X | | | | | | |
| | 1052 | 6/28/2017 | 7/6/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | | | X | X | X | | |
| | 1052 | 7/5/2017 | 7/13/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1052 | 7/12/2017 | 7/20/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1052 | 7/19/2017 | 7/27/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1052 | 7/19/2017 | 7/20/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 1052 | 7/26/2017 | 8/3/2017 | 17:30:00 | 18:35:00 | WN | WN | 73W | X | X | X | X | X | | |
| | 4916 | 7/4/2017 | 7/4/2017 | 17:45:00 | 18:50:00 | WN | WN | 73W | | X | | | | | |
| | 5759 | 7/1/2017 | 7/6/2017 | 19:50:00 | 20:55:00 | WN | WN | 73W | | | | | | X | |
| | 5759 | 7/8/2017 | 7/13/2017 | 19:50:00 | 20:55:00 | WN | WN | 73W | | | | | | X | |
| | 5759 | 7/15/2017 | 7/20/2017 | 19:50:00 | 20:55:00 | WN | WN | 73W | | | | | | X | |
| | 5759 | 7/22/2017 | 7/27/2017 | 19:50:00 | 20:55:00 | WN | WN | 73W | | | | | | X | |
| | 5759 | 7/29/2017 | 8/3/2017 | 19:50:00 | 20:55:00 | WN | WN | 73W | | | | | | X | |
| **MIA** | | | | | | | | | | | | | | | |
| | 3769 | 6/29/2017 | 7/6/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3769 | 7/5/2017 | 7/13/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3769 | 7/12/2017 | 7/20/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3769 | 7/19/2017 | 7/20/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3769 | 7/19/2017 | 7/27/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3769 | 7/26/2017 | 8/3/2017 | 07:00:00 | 09:25:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 6/28/2017 | 7/6/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 7/5/2017 | 7/13/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 7/12/2017 | 7/20/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 7/19/2017 | 7/20/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 7/19/2017 | 7/27/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3796 | 7/26/2017 | 8/3/2017 | 13:25:00 | 15:57:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| **MSP** | | | | | | | | | | | | | | | |
| | 4706 | 7/2/2017 | 7/6/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | | X | X | | X |
| | 4706 | 7/6/2017 | 7/13/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/12/2017 | 7/20/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/19/2017 | 7/20/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/19/2017 | 7/21/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/23/2017 | 7/27/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/26/2017 | 8/3/2017 | 06:00:00 | 08:03:00 | DL | OO | CR9 | X | X | X | X | X | | X |
| | 4706 | 7/1/2017 | 7/6/2017 | 06:15:00 | 08:15:00 | DL | OO | CR9 | | | | | | X | |
| | 4706 | 7/8/2017 | 7/13/2017 | 06:15:00 | 08:15:00 | DL | OO | CR9 | | | | | | X | |
| | 4706 | 7/15/2017 | 7/20/2017 | 06:15:00 | 08:15:00 | DL | OO | CR9 | | | | | | X | |
| | 4706 | 7/22/2017 | 7/22/2017 | 06:15:00 | 08:15:00 | DL | OO | CR9 | | | | | | X | |
| | 4706 | 7/29/2017 | 8/3/2017 | 06:15:00 | 08:15:00 | DL | OO | CR9 | | | | | | X | |
| **ORD** | | | | | | | | | | | | | | | |
| | 287 | 7/1/2017 | 7/1/2017 | 06:35:00 | 07:51:00 | UA | UA | 739 | | | | | | X | |
| | 287 | 7/2/2017 | 7/2/2017 | 06:35:00 | 07:51:00 | UA | UA | 739 | | | | | | | X |
| | 287 | 7/3/2017 | 7/6/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | X | |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 287 | 7/5/2017 | 7/13/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | X | |
| | 287 | 7/9/2017 | 7/13/2017 | 06:35:00 | 07:50:00 | UA | UA | 320 | | | | | | X | X |
| | 287 | 7/12/2017 | 7/20/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | | |
| | 287 | 7/15/2017 | 7/20/2017 | 06:35:00 | 07:50:00 | UA | UA | 320 | | | | | | X | X |
| | 287 | 7/19/2017 | 7/20/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | | X |
| | 287 | 7/19/2017 | 7/27/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | | X |
| | 287 | 7/22/2017 | 7/22/2017 | 06:35:00 | 07:50:00 | UA | UA | 320 | | | | | | X | |
| | 287 | 7/26/2017 | 8/3/2017 | 06:35:00 | 07:50:00 | UA | UA | 319 | X | X | X | X | X | X | X |
| | 2920 | 6/29/2017 | 7/6/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/5/2017 | 7/13/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/12/2017 | 7/12/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/13/2017 | 7/20/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/19/2017 | 7/20/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/19/2017 | 7/27/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/26/2017 | 7/26/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2920 | 7/27/2017 | 8/3/2017 | 08:00:00 | 09:20:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 498 | 7/3/2017 | 7/3/2017 | 10:11:00 | 11:29:00 | UA | UA | 739 | X | | | | | | |
| | 498 | 7/6/2017 | 7/6/2017 | 10:13:00 | 11:30:00 | UA | UA | 739 | | | | X | | | |
| | 498 | 7/13/2017 | 7/20/2017 | 10:13:00 | 11:29:00 | UA | UA | 739 | | | | X | | | |
| | 498 | 7/20/2017 | 7/20/2017 | 10:13:00 | 11:29:00 | UA | UA | 739 | | | | X | | | |
| | 498 | 7/27/2017 | 7/27/2017 | 10:13:00 | 11:29:00 | UA | UA | 739 | | | | X | | | |
| | 498 | 7/1/2017 | 7/1/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | X | |
| | 498 | 7/2/2017 | 7/2/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | | X |
| | 498 | 7/4/2017 | 7/4/2017 | 10:14:00 | 11:31:00 | UA | UA | 320 | | X | | | | | |
| | 498 | 7/5/2017 | 7/13/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | X | X | | X | | |
| | 498 | 7/5/2017 | 7/6/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | X | X | | X | | |
| | 498 | 7/8/2017 | 7/8/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | X | |
| | 498 | 7/9/2017 | 7/9/2017 | 10:14:00 | 11:32:00 | UA | UA | 738 | | | | | | | X |
| | 498 | 7/10/2017 | 7/13/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | | | | | | |
| | 498 | 7/12/2017 | 7/20/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | X | X | | X | | |
| | 498 | 7/15/2017 | 7/20/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | X | |
| | 498 | 7/16/2017 | 7/20/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | | X |
| | 498 | 7/17/2017 | 7/17/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | | | | | | |
| | 498 | 7/16/2017 | 7/20/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | | X |
| | 498 | 7/17/2017 | 7/17/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | | | | | | |
| | 498 | 7/19/2017 | 7/20/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | X | X | | X | | |
| | 498 | 7/19/2017 | 7/27/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | X | X | | X | | |
| | 498 | 7/22/2017 | 7/27/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | X | |
| | 498 | 7/23/2017 | 7/27/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | | X |
| | 498 | 7/26/2017 | 8/3/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | X | X | X | | X | | |
| | 498 | 7/29/2017 | 8/3/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | X | |
| | 498 | 7/30/2017 | 8/3/2017 | 10:14:00 | 11:32:00 | UA | UA | 739 | | | | | | | X |
| | 3829 | 7/5/2017 | 7/13/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3829 | 7/5/2017 | 7/6/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3829 | 7/12/2017 | 7/20/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3829 | 7/19/2017 | 7/27/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3829 | 7/19/2017 | 7/20/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 3829 | 7/26/2017 | 8/3/2017 | 10:41:00 | 12:10:00 | AA | MQ | ER4 | X | X | X | X | X | X | X |
| | 5486 | 7/2/2017 | 7/6/2017 | 11:47:00 | 13:08:00 | UA | OO | E7W | | | | | | | X |
| | 5486 | 7/9/2017 | 7/13/2017 | 11:47:00 | 13:08:00 | UA | OO | E7W | | | | | | | X |
| | 5486 | 7/16/2017 | 7/20/2017 | 11:47:00 | 13:08:00 | UA | OO | E7W | | | | | | | X |
| | 5486 | 7/23/2017 | 7/27/2017 | 11:47:00 | 13:08:00 | UA | OO | E7W | | | | | | | X |
| | 5486 | 7/30/2017 | 8/3/2017 | 11:47:00 | 13:08:00 | UA | OO | E7W | | | | | | | X |
| | 3566 | 7/1/2017 | 7/1/2017 | 13:44:00 | 15:05:00 | UA | YX | E70 | | | | | | X | |
| | 3987 | 7/8/2017 | 7/13/2017 | 13:44:00 | 15:05:00 | UA | EV | ERJ | | | | | | X | |
| | 3987 | 7/15/2017 | 7/20/2017 | 13:44:00 | 15:05:00 | UA | EV | ERJ | | | | | | X | |
| | 3987 | 7/22/2017 | 7/27/2017 | 13:44:00 | 15:05:00 | UA | EV | ERJ | | | | | | X | |
| | 3987 | 7/29/2017 | 8/3/2017 | 13:44:00 | 15:05:00 | UA | EV | ERJ | | | | | | X | |
| | 2887 | 6/29/2017 | 7/6/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/5/2017 | 7/13/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/12/2017 | 7/12/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/13/2017 | 7/20/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/19/2017 | 7/20/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/19/2017 | 7/27/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/26/2017 | 7/26/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 2887 | 7/27/2017 | 8/3/2017 | 16:10:00 | 17:32:00 | AA | OO | CR7 | X | X | X | X | X | X | X |
| | 1801 | 7/16/2017 | 7/16/2017 | 16:53:00 | 18:13:00 | UA | UA | 739 | | | | | | | X |
| | 1801 | 7/2/2017 | 7/2/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | | | | X |
| | 1801 | 7/3/2017 | 7/3/2017 | 16:59:00 | 18:22:00 | UA | UA | 320 | X | | | | | | |
| | 1801 | 7/4/2017 | 7/6/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | X | | | | | |
| | 1801 | 7/5/2017 | 7/6/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | X | | X | | X | | |
| | 1801 | 7/5/2017 | 7/10/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | X | | X | | X | | |
| | 1801 | 7/6/2017 | 7/13/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | X | | | |
| | 1801 | 7/8/2017 | 7/8/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | | | X | |
| | 1801 | 7/9/2017 | 7/9/2017 | 16:59:00 | 18:22:00 | UA | UA | 320 | | | | | | | X |
| | 1801 | 7/11/2017 | 7/13/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | X | | | | | |
| | 1801 | 7/12/2017 | 7/12/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/12/2017 | 7/12/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/13/2017 | 7/20/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | X | | | |
| | 1801 | 7/14/2017 | 7/19/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | X | | |
| | 1801 | 7/15/2017 | 7/15/2017 | 16:59:00 | 18:22:00 | UA | UA | 320 | | | | | | X | |
| | 1801 | 7/17/2017 | 7/20/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | X | | | | | | |
| | 1801 | 7/18/2017 | 7/20/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | X | | | | | |
| | 1801 | 7/19/2017 | 7/19/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/19/2017 | 7/19/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/20/2017 | 7/27/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | X | | | |
| | 1801 | 7/21/2017 | 7/21/2017 | 16:59:00 | 18:22:00 | UA | UA | 320 | | | | | X | | |
| | 1801 | 7/22/2017 | 7/22/2017 | 16:59:00 | 18:22:00 | UA | UA | 320 | | | | | | X | |
| | 1801 | 7/24/2017 | 7/27/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | X | | | | | | |
| | 1801 | 7/25/2017 | 7/25/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | X | | | | | |
| | 1801 | 7/26/2017 | 7/26/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/26/2017 | 7/26/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | | | |
| | 1801 | 7/27/2017 | 7/27/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | X | | | |
| | 1801 | 7/28/2017 | 8/3/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | X | | X | | |
| | 1801 | 7/29/2017 | 7/29/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | | | | | | X | |
| | 1801 | 7/31/2017 | 8/3/2017 | 16:59:00 | 18:22:00 | UA | UA | 319 | X | | | X | | | |
| | 1801 | 7/1/2017 | 7/1/2017 | 17:05:00 | 18:25:00 | UA | UA | 738 | | | | | | X | |
| | 1801 | 7/30/2017 | 7/30/2017 | 17:05:00 | 18:23:00 | UA | UA | 320 | | | | | | | X |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1801 | 7/23/2017 | 7/23/2017 | 17:18:00 | 18:35:00 | UA | UA | 739 | | | | | | | X |
| **PHL** | | | | | | | | | | | | | | | |
| | 4104 | 6/29/2017 | 7/6/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | | X | X | X | X | X | |
| | 4104 | 7/5/2017 | 7/13/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4104 | 7/12/2017 | 7/20/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4104 | 7/19/2017 | 7/20/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4104 | 7/19/2017 | 7/27/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4104 | 7/26/2017 | 8/3/2017 | 06:15:00 | 07:19:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 6/29/2017 | 7/6/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 7/5/2017 | 7/13/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 7/12/2017 | 7/20/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 7/19/2017 | 7/20/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 7/19/2017 | 7/27/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4185 | 7/26/2017 | 8/3/2017 | 08:35:00 | 09:47:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4237 | 6/29/2017 | 7/6/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | | X | X | X | X | X | X |
| | 4237 | 7/5/2017 | 7/13/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4237 | 7/12/2017 | 7/20/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4237 | 7/19/2017 | 7/27/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4237 | 7/19/2017 | 7/20/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4237 | 7/26/2017 | 8/3/2017 | 11:05:00 | 12:12:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 6/29/2017 | 7/4/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | | X | X | X | X |
| | 4167 | 7/5/2017 | 7/6/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 7/5/2017 | 7/13/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 7/12/2017 | 7/20/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 7/19/2017 | 7/27/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 7/19/2017 | 7/20/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4167 | 7/26/2017 | 8/3/2017 | 13:10:00 | 14:21:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 6/29/2017 | 7/4/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | | X | X | X | X |
| | 4119 | 7/5/2017 | 7/13/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 7/5/2017 | 7/6/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 7/12/2017 | 7/20/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 7/19/2017 | 7/27/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 7/19/2017 | 7/20/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4119 | 7/26/2017 | 8/3/2017 | 15:41:00 | 16:50:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 6/29/2017 | 7/4/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | | X | X | X | X |
| | 4212 | 7/5/2017 | 7/13/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 7/5/2017 | 7/6/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 7/12/2017 | 7/20/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 7/19/2017 | 7/20/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 7/19/2017 | 7/27/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4212 | 7/26/2017 | 8/3/2017 | 17:38:00 | 18:43:00 | AA | ZW | CR2 | X | X | X | X | X | X | X |
| | 4195 | 6/29/2017 | 7/6/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | | X | X | X | X | | |
| | 4195 | 7/5/2017 | 7/13/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4195 | 7/12/2017 | 7/20/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4195 | 7/19/2017 | 7/27/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4195 | 7/19/2017 | 7/20/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | X | X | X | X | X | | X |
| | 4195 | 7/26/2017 | 8/3/2017 | 18:10:00 | 19:16:00 | AA | ZW | CR2 | X | X | X | X | X | | X |


# APPENDIX J – FAA AC 150/5060-5 AIRPORT CAPACITY AND DELAY

### *A. Table 3-1 (ASV Weighting Factors)*

Table 3-1. ASV Weighting Factors

| Percent of Maximum capacity | Weighting Factors | | | |
|---|---|---|---|---|
| | VFR | IFR | | |
| | | Mix Index (0-20) | Mix Index (21-50) | Mix Index (51-180) |
| 91+ | 1 | 1 | 1 | 1 |
| 81-90 | 5 | 1 | 3 | 5 |
| 66-80 | 15 | 2 | 8 | 15 |
| 51-65 | 20 | 3 | 12 | 20 |
| 0-50 | 25 | 4 | 16 | 25 |

### *B. Figure 3-2 (Runway-Use Diagrams)*



12/1/95

AC 150/5060-5 CHG 2




Figure 3-2. Runway-use diagrams

***C. Figure 3-3***





FIGURE 3-3, HOURLY CAPACITY OF RUNWAY-USE DIAGRAM NOS.: 1,54 FOR VFR CONDITIONS.

***D. Figure 3***





FIGURE 3-43. HOURLY CAPACITY OF RUNWAY-USE DIAGRAM NOS. 1, 54 FOR IFR CONDITIONS.

# APPENDIX K – AIRPORT WEATHER DATA: PROVIDED BY NOAA'S NATIONAL CLIMATE DATA CENTER (NCDC)

| 2009-2018 | Visibility (Miles) | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **1,341** | | | | | | | | | | | | | | | | | 1 | | | 2 | | | | 4 | | 2 | | 7 | | | 8 | | 4 | | 1 | 2 | | | 5 | | | 185 |
| **1,372** | | | | | | | | | | | 1 | | 1 | | | | 1 | | | 3 | | 1 | | 6 | | 3 | | 5 | | | 2 | | 8 | | | 6 | | | 3 | | | 206 |
| **1,402** | | | | | | | | | | | | | | | | | | | | | | 1 | | 2 | | 3 | | 4 | | | 4 | | 4 | | | 6 | | | 5 | | | 177 |
| **1,433** | | | | | | | | | 1 | | | | | | | | 1 | | | 2 | | 2 | | 4 | | 4 | | 4 | | | 3 | | 7 | | | 4 | | | 6 | | | 184 |
| **1,463** | | | | | | | | | | | | | 1 | | | | | | | 1 | | 2 | | 3 | | 7 | | 6 | | | 4 | | 9 | | | 5 | | | 2 | | | 207 |
| **1,470** | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **1,494** | | | | | | | | | | | | | 1 | | 3 | | | | | 1 | | 1 | | 2 | | 2 | | 2 | | | 5 | | 6 | | | | | | 7 | | | 173 |
| **1,500** | | | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **1,524** | | | | | | | | | 2 | | 1 | | | | | | 1 | | | 2 | | 3 | | 6 | | 12 | | 14 | | | 13 | | 23 | | | 23 | | | 28 | | | 724 |
| **1,676** | | | | | | | | | | | | | 1 | | 1 | | | | | 3 | | 4 | | 8 | | 10 | | 15 | | | 14 | | 21 | | | 24 | | | 33 | | 2 | 697 |
| **1,800** | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **1,829** | | | | | 1 | | | | 1 | | | | | | 1 | | | | | 5 | | 7 | | 8 | | 18 | | 13 | | | 18 | | 37 | | | 23 | | | 27 | | | 1056 |
| **1,981** | | | | | | | | | 1 | | | | | | 1 | | 1 | | | 2 | | 3 | | 3 | | 4 | | 13 | | | 11 | | 16 | | | 12 | | | 23 | | | 679 |
| **2,100** | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **2,134** | | | | | | | | | | | 1 | | 1 | | | | 1 | | | 1 | | 3 | | 7 | | 10 | | 20 | | | 17 | | 27 | | | 33 | | | 31 | | | 972 |
| **2,286** | 1 | | | | | | 1 | | | | | | | | 1 | | 2 | | | 1 | | 2 | | 3 | | 8 | | 9 | | | 9 | | 16 | | | 14 | | | 26 | | | 587 |
| **2,438** | | | | | 5 | | | | | | 1 | | | | 1 | | 1 | | | 1 | | 1 | | 7 | | 7 | | 9 | | | 13 | | 19 | | | 16 | | | 14 | | | 788 |
| **2,591** | | | | | 1 | | | | | | | | | | 2 | | | | | | | 2 | | 1 | | 4 | | 11 | | | 8 | | 8 | | | 14 | | | 9 | | | 468 |
| **2,700** | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **2,743** | | | | | 2 | | | | | | | | | | 1 | | | | | | | 2 | | 8 | | 7 | | 11 | | | 13 | | 17 | | | 20 | | | 21 | | 2 | 792 |
| **2,896** | | | | | | | | | | | | | | | | | | | | 1 | | 3 | | 6 | | 2 | | 7 | | | 10 | | 9 | | | 7 | | | 10 | | | 479 |
| **3,048** | | | | | 1 | | | | | | 2 | | | | 1 | | | | | 4 | | | | 4 | | 6 | | 12 | | | 24 | | 32 | | | 33 | | | 28 | | | 1164 |
| **3,353** | | | | | | | | | | | | | | | | | | | | 1 | | 1 | | 2 | | 8 | | 20 | | | 12 | | 30 | | | 26 | | | 38 | | | 1021 |
| **3,600** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 |
| **3,658** | | | | | | | | | | | | | | | | | | | | | | | | 2 | | 8 | | 14 | | | 18 | | 47 | | | 31 | | | 35 | | | 1421 |
| **6,096** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 |
| **22,000** | | | | | 4 | 1 | 12 | | 18 | 3 | 14 | 1 | 17 | | 14 | 1 | 27 | 4 | | 34 | 3 | 26 | 8 | 77 | 24 | 120 | 42 | 243 | 69 | | 341 | 121 | 501 | 119 | | 595 | 162 | 4 | 801 | 7988 | 28 | 54058 |
| **99,999** | 2 | 1 | | 28 | 1 | 42 | 5 | 53 | 3 | 81 | 1 | 37 | | 91 | 2 | 45 | 1 | 154 | 1 | 2 | 124 | 4 | 242 | | 292 | 1 | 307 | 1 | 308 | | | 408 | 1 | 355 | | 1 | 432 | | 1 | 16990 | 26 | 65 |

# APPENDIX L – TFMSC/DISTRIBUTED OPSNET DATA (2018)

# OPSNET Operations Prorated By TFMS Report

From 01/2018 To 12/2018 | Airport=ORF

| # | Date | Airport | Departure | | | | Arrival | | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | AC+AT | GA | MIL | Total | AC+AT | GA | MIL | Total | |
| 1 | Jan-18 | ORF - Norfolk | 1,979 | 483 | 18 | 2,480 | 1,957 | 464 | 13 | 2,434 | 4,914 |
| 2 | Feb-18 | ORF - Norfolk | 2,003 | 575 | 27 | 2,605 | 1,977 | 560 | 13 | 2,550 | 5,155 |
| 3 | Mar-18 | ORF - Norfolk | 2,144 | 669 | 36 | 2,849 | 2,125 | 646 | 23 | 2,794 | 5,643 |
| 4 | Apr-18 | ORF - Norfolk | 2,216 | 633 | 32 | 2,881 | 2,193 | 614 | 25 | 2,832 | 5,713 |
| 5 | May-18 | ORF - Norfolk | 2,459 | 699 | 47 | 3,205 | 2,438 | 675 | 37 | 3,150 | 6,355 |
| 6 | Jun-18 | ORF - Norfolk | 2,445 | 793 | 62 | 3,300 | 2,419 | 769 | 54 | 3,242 | 6,542 |
| 7 | Jul-18 | ORF - Norfolk | 2,533 | 673 | 19 | 3,225 | 2,511 | 656 | 14 | 3,181 | 6,406 |
| 8 | Aug-18 | ORF - Norfolk | 2,589 | 821 | 36 | 3,446 | 2,557 | 802 | 28 | 3,387 | 6,833 |
| 9 | Sep-18 | ORF - Norfolk | 2,455 | 627 | 26 | 3,108 | 2,432 | 608 | 13 | 3,053 | 6,161 |
| 10 | Oct-18 | ORF - Norfolk | 2,539 | 756 | 88 | 3,383 | 2,516 | 732 | 82 | 3,330 | 6,713 |
| 11 | Nov-18 | ORF - Norfolk | 2,450 | 683 | 29 | 3,162 | 2,423 | 669 | 16 | 3,108 | 6,270 |
| 12 | Dec-18 | ORF - Norfolk | 2,478 | 578 | 34 | 3,090 | 2,445 | 562 | 18 | 3,025 | 6,115 |
| **OPSNET Total :** | | | **28,290** | **7,990** | **454** | **36,734** | **27,993** | **7,757** | **336** | **36,086** | **72,820** |
| **TFMS Total * :** | | | **28,021** | **4,749** | **149** | **32,919** | **23,667** | **4,323** | **121** | **28,111** | **61,030** |
| **TFMS % Of OPSNET * :** | | | **99.05** | **59.44** | **32.82** | **89.61** | **84.55** | **55.73** | **36.01** | **77.9** | **83.81** |

* - Does not include TFMS records if Userclass = O-Other or is missing and does not include TFMS records missing specific times (hour = NA).

Report created on Thu Nov 21 16:32:31 EST 2019

Sources: Traffic Flow Management System Counts (TFMSC), Aviation System Performance Metrics (ASPM)

# OPSNET Operations Prorated By TFMS Report

From 08/2018 To 08/2018 | Airport=ORF

| # | Date | Airport | Hour | Departure | | | | Arrival | | | | Total Operations |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | AC+AT | GA | MIL | Total | AC+AT | GA | MIL | Total | |
| 1 | Aug-18 | ORF - Norfolk | 0 | 21 | 20 | 23 | 64 | 37 | 7 | 20 | 64 | 128 |
| 2 | Aug-18 | ORF - Norfolk | 1 | 1 | 2 | 0 | 3 | 12 | 2 | 0 | 14 | 17 |
| 3 | Aug-18 | ORF - Norfolk | 2 | 1 | 0 | 1 | 2 | 1 | 1 | 0 | 2 | 4 |
| 4 | Aug-18 | ORF - Norfolk | 4 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 |
| 5 | Aug-18 | ORF - Norfolk | 5 | 98 | 12 | 8 | 118 | 2 | 3 | 5 | 10 | 128 |
| 6 | Aug-18 | ORF - Norfolk | 6 | 162 | 25 | 0 | 187 | 32 | 5 | 0 | 37 | 224 |
| 7 | Aug-18 | ORF - Norfolk | 7 | 237 | 86 | 0 | 323 | 24 | 11 | 0 | 35 | 358 |
| 8 | Aug-18 | ORF - Norfolk | 8 | 182 | 65 | 0 | 247 | 101 | 54 | 1 | 156 | 403 |
| 9 | Aug-18 | ORF - Norfolk | 9 | 140 | 60 | 1 | 201 | 230 | 41 | 0 | 271 | 472 |
| 10 | Aug-18 | ORF - Norfolk | 10 | 223 | 66 | 1 | 290 | 108 | 61 | 0 | 169 | 459 |
| 11 | Aug-18 | ORF - Norfolk | 11 | 178 | 67 | 0 | 245 | 146 | 60 | 0 | 206 | 451 |
| 12 | Aug-18 | ORF - Norfolk | 12 | 133 | 41 | 1 | 175 | 148 | 49 | 0 | 197 | 372 |
| 13 | Aug-18 | ORF - Norfolk | 13 | 147 | 40 | 0 | 187 | 105 | 57 | 0 | 162 | 349 |
| 14 | Aug-18 | ORF - Norfolk | 14 | 99 | 64 | 0 | 163 | 187 | 55 | 0 | 242 | 405 |
| 15 | Aug-18 | ORF - Norfolk | 15 | 195 | 50 | 0 | 245 | 108 | 91 | 0 | 199 | 444 |
| 16 | Aug-18 | ORF - Norfolk | 16 | 88 | 77 | 0 | 165 | 153 | 88 | 0 | 241 | 406 |
| 17 | Aug-18 | ORF - Norfolk | 17 | 127 | 67 | 0 | 194 | 204 | 62 | 0 | 266 | 460 |
| 18 | Aug-18 | ORF - Norfolk | 18 | 186 | 12 | 1 | 199 | 162 | 64 | 1 | 227 | 426 |
| 19 | Aug-18 | ORF - Norfolk | 19 | 146 | 29 | 0 | 175 | 151 | 30 | 0 | 181 | 356 |
| 20 | Aug-18 | ORF - Norfolk | 20 | 138 | 13 | 0 | 151 | 84 | 19 | 1 | 104 | 255 |
| 21 | Aug-18 | ORF - Norfolk | 21 | 64 | 8 | 0 | 72 | 114 | 21 | 0 | 135 | 207 |
| 22 | Aug-18 | ORF - Norfolk | 22 | 14 | 13 | 0 | 27 | 162 | 15 | 0 | 177 | 204 |
| 23 | Aug-18 | ORF - Norfolk | 23 | 8 | 4 | 0 | 12 | 286 | 6 | 0 | 292 | 304 |
| **OPSNET Total :** | | | | **2,589** | **821** | **36** | **3,446** | **2,557** | **802** | **28** | **3,387** | **6,833** |
| **TFMS Total * :** | | | | **2,572** | **469** | **4** | **3,045** | **2,149** | **432** | **4** | **2,585** | **5,630** |
| **TFMS % Of OPSNET * :** | | | | **99.34** | **57.13** | **11.11** | **88.36** | **84.04** | **53.87** | **14.29** | **76.32** | **82.39** |

* - Does not include TFMS records if Userclass = O-Other or is missing and does not include TFMS records missing specific times (hour = NA).

Report created on Thu Nov 21 16:42:34 EST 2019

Sources: Traffic Flow Management System Counts (TFMSC), Aviation System Performance Metrics (ASPM)

# OPSNET Operations Prorated By TFMS Report

From 08/2018 To 08/2018 | Airport=ORF
(Daily Averages)

| # | Date | Airport | Hour | Departure AC+AT | Departure GA | Departure MIL | Departure Total | Arrival AC+AT | Arrival GA | Arrival MIL | Arrival Total | Total Operations |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Aug-18 | ORF - Norfolk | 0 | 1 | 0 | 1 | 3 | 1 | 0 | 0 | 3 | 6 |
| 2 | Aug-18 | ORF - Norfolk | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 2 |
| 3 | Aug-18 | ORF - Norfolk | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 2 |
| 4 | Aug-18 | ORF - Norfolk | 4 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 |
| 5 | Aug-18 | ORF - Norfolk | 5 | 3 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 4 |
| 6 | Aug-18 | ORF - Norfolk | 6 | 5 | 0 | 0 | 6 | 1 | 0 | 0 | 1 | 7 |
| 7 | Aug-18 | ORF - Norfolk | 7 | 7 | 2 | 0 | 10 | 0 | 0 | 0 | 1 | 11 |
| 8 | Aug-18 | ORF - Norfolk | 8 | 5 | 2 | 0 | 7 | 3 | 1 | 0 | 5 | 13 |
| 9 | Aug-18 | ORF - Norfolk | 9 | 4 | 1 | 0 | 6 | 7 | 1 | 0 | 8 | 15 |
| 10 | Aug-18 | ORF - Norfolk | 10 | 7 | 2 | 0 | 9 | 3 | 1 | 0 | 5 | 14 |
| 11 | Aug-18 | ORF - Norfolk | 11 | 5 | 2 | 0 | 7 | 4 | 1 | 0 | 6 | 14 |
| 12 | Aug-18 | ORF - Norfolk | 12 | 4 | 1 | 0 | 5 | 4 | 1 | 0 | 6 | 12 |
| 13 | Aug-18 | ORF - Norfolk | 13 | 4 | 1 | 0 | 6 | 3 | 1 | 0 | 5 | 11 |
| 14 | Aug-18 | ORF - Norfolk | 14 | 3 | 2 | 0 | 5 | 6 | 1 | 0 | 7 | 13 |
| 15 | Aug-18 | ORF - Norfolk | 15 | 6 | 1 | 0 | 7 | 3 | 2 | 0 | 6 | 14 |
| 16 | Aug-18 | ORF - Norfolk | 16 | 2 | 2 | 0 | 5 | 4 | 2 | 0 | 7 | 13 |
| 17 | Aug-18 | ORF - Norfolk | 17 | 4 | 2 | 0 | 6 | 6 | 2 | 0 | 8 | 14 |
| 18 | Aug-18 | ORF - Norfolk | 18 | 6 | 0 | 0 | 6 | 5 | 2 | 0 | 7 | 13 |
| 19 | Aug-18 | ORF - Norfolk | 19 | 4 | 0 | 0 | 5 | 4 | 0 | 0 | 5 | 11 |
| 20 | Aug-18 | ORF - Norfolk | 20 | 4 | 0 | 0 | 4 | 2 | 0 | 0 | 3 | 8 |
| 21 | Aug-18 | ORF - Norfolk | 21 | 2 | 0 | 0 | 2 | 3 | 0 | 0 | 4 | 6 |
| 22 | Aug-18 | ORF - Norfolk | 22 | 0 | 0 | 0 | 0 | 5 | 0 | 0 | 5 | 6 |
| 23 | Aug-18 | ORF - Norfolk | 23 | 0 | 0 | 0 | 0 | 9 | 0 | 0 | 9 | 9 |
| **OPSNET Total :** | | | | **85.75914905** | **27.03015255** | **2.000132422** | **114.789434** | **84.67173049** | **26.64377086** | **1.221568939** | **112.5370703** | **227.3265043** |
| **TFMS Total * :** | | | | **84.46228481** | **15.26208883** | **0.129032258** | **99.8534059** | **71.40894777** | **14.51677923** | **0.129032258** | **86.05475926** | **185.9081652** |
| **TFMS % Of OPSNET * :** | | | | **98.49** | **56.46** | **6.45** | **86.99** | **84.34** | **54.48** | **10.56** | **76.47** | **81.78** |

* - Does not include TFMS records if Userclass = O-Other or is missing and does not include TFMS records missing specific times (hour = NA).

Report created on Thu Nov 21 16:47:18 EST 2019
Sources: Traffic Flow Management System Counts (TFMSC), Aviation System Performance Metrics (ASPM)

# APPENDIX M – RUNWAY 14/32 RSA EVALUATION

## I. INTRODUCTION

Delta Airport Consultants has developed concepts to bring Runway 14-32 into compliance with FAA standards. These are in addition to, and supplemental to, options considered in the Master Plan completed in October 2008.

There are two general directions that can be taken to bring the runway into compliance:

- "Upgrade" Runway 14-32 by extending the overall length to meet the needs and requirements as presented in the Master Plan.

- "Downgrade" Runway 14-32 by shortening and possibly limiting aircraft weights so the final compliant runway fits within the existing airport property.

## II. EXISTING CONDITION

To determine the existing conditions of Runway 14-32, a review of the most recent Airport Layout Plan and the most recent instrument approaches were reviewed (see Appendix A). Using these sources, the current design requirements were determined based on FAA Advisory Circular 150/5300-13A Airport Design. Table 1 presents a summary of both existing and required criteria for Runway 14-32; substandard criteria are highlighted in yellow. Exhibit 1 presents the existing conditions of Runway 14-32 with non-standard criteria highlighted.


# TABLE 1
# NON-STANDARD DESIGN CRITERIA
# RUNWAY 14-32

**RUNWAY 14-32 EXISTING CONDITIONS VERSUS FAA REQUIRED DESIGN STANDARDS**

Source: Table A7-9 Runway design standards matrix, C/D/E - III FAA AC 150/5300-13A

| ITEM | DIM [1] | Runway 14 | | Runway 32 | |
|---|---|---|---|---|---|
| | | Existing Not Lower than 1 mile | Required Not Lower than 1 mile | Existing Not Lower than 1 mile | Required Not Lower than 1 mile |
| **RUNWAY DESIGN** | | | | | |
| Runway Length - Departure | A | 4,875 ft | 5,600 ft | 4,875 ft | 5,600 ft |
| Runway Length - Arrival | | 4,662 ft | 4,850 ft | 4,875 ft | 4,850 ft |
| Runway width * | B | 150 ft | 100 ft | 150 ft | 100 ft |
| Shoulder Width | | 0 ft | 25 ft | 0 ft | 25 ft |
| Blast Pad Width | | 150 ft | 200 ft | 0 ft | 200 ft |
| Crosswind Component | | 16 knots | 16 knots | 16 knots | 16 knots |
| **RUNWAY PROTECTION** | | | | | |
| Runway Safety Area (RSA) | | | | | |
| Length beyond departure end | R | 1,000 ft | 1,000 ft | 41 ft | 1,000 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | C | 500 ft | 500 ft | 500 ft | 500 ft |
| Runway Object Free Area (ROFA) | | | | | |
| Length beyond runway end | R | 935 ft | 1,000 ft | 41 ft | 1,000 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | Q | 800 ft | 800 ft | 800 ft | 800 ft |
| Runway Obstacle Free Zone (ROFZ) | | | | | |
| Length | | 5,166 ft | | 5,166 ft | |
| Width | | 400 ft | | 400 ft | |
| Precision Obstacle Free Zone (POFZ) | | | | | |
| Length | | N/A | N/A | N/A | 200 ft |
| Width | | N/A | N/A | N/A | 800 ft |
| Approach Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | Not clear of | 1,700 ft | 2,500 ft |
| Inner Width | U | 500 ft | bldgs and | 1,000 ft | 1,000 ft |
| Outer Width | V | 1,010 ft | other non- | 1,510 ft | 1,750 ft |
| Acres | | 29.465 | compatible | 48.978 | 78.914 |
| Departure Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1,700 ft | 1,700 ft | Not clear of |
| Inner Width | U | 500 ft | 500 ft | 500 ft | bldgs and |
| Outer Width | V | 1,010 ft | 1,010 ft | 1,010 ft | other non- |
| Acres | | 29.465 | 29.465 | 29.465 | compatible |
| **RUNWAY SEPARATION** | | | | | |
| *Runway centerline to:* | | | | | |
| Parallel runway centerline | H | N/A | | | |
| Holding Position | | 250 ft | 250 ft | 250 ft | 250 ft |
| Parallel taxiway/taxilane centerline | D | 399 ft | 400 ft | 399 ft | 400 ft |
| Aircraft parking area | G | 500 ft | > 500 ft | 500 ft | > 500 ft |
| Helicopter touchdown pad | | N/A | | | |

* Runway width for design of 150,000 pounds or less is 100 feet, over 150,000 pounds width is 150 feet.




# EXISTING CONDITIONS
## NORFOLK INTERNATIONAL AIRPORT

www.deltaairport.com

| DRAWN BY: | PJW | CHECKED BY: | JCL | SCALE: | 1" = 600' | DATE: | JUNE 2014 |
|---|---|---|---|---|---|---|---|

**EXHIBIT**
**1**

N:\14051\04 CAD\Exhibits\14051 RW 14-32 Ex Conditions.dwg, L1, 6/25/2014 8:54:19 AM, mrm

DRAWING: 14051 RW 14-32 Ex Conditions.dwg LAYOUT: L1

## III. "UPGRADE" RUNWAY 14-32

### Scenario A: Bring Runway 14-32 into Compliance based on Critical Aircraft

Based on the most recent Airport Layout Plan, the critical aircraft for Runway 14-32 is a Boeing 737-700. A review of the aircraft performance characteristics from Boeing indicates a critical runway length for a Boeing 737-700 as 5,600 feet. It is important to note that a runway length of 5,600 feet would serve the most critical aircraft for Runway 14-32 while Runway 5-23 would still be considered the primary runway. To be a fully functional alternative runway to Runway 5-23, its overall length would have to be 6,500 feet. This scenarios does not meet that requirement.

Table 2 presents the existing conditions and the required design criteria to bring Runway 14-32 into compliance with the extension to 5,600 feet. Generally, runway extensions could be accommodated by extending in one or both directions. However, extending to the northwest (on the Runway 14 end) would require filling a portion of Lake Whitehurst, relocation of Norview Avenue, and the acquisition of a church and several homes. Therefore, for this report, an extension to the southeast was assumed to be the more viable option.

Actions required to accomplish a runway extension include:

1. To bring runway safety area up to criteria, shift the end of Runway 14 by 959 feet to the southeast.

2. To bring the runway object free area into compliance, an additional shift of the runway by approximately 15 feet (974 feet total) is required to move the security fence outside of the ROFA. Note that the master plan indicated that this shift would be 980 feet. While there is a slight difference (attributed to the level of information available), it validates the general length of shift required. The difference of 6 feet is negligible at this level of effort.

3. To obtain the required runway length of 5,600 feet, extend the overall runway pavement by 725 feet.

4. The shift of the runway by 974 feet in Items 1 and 2 above, resolves the non-compatible land use within the Runway 14 RPZ.

5. Reduce runway width to 100 feet (aircraft weight less than 150,000 lbs)

6. Include a new full parallel taxiway and associated taxiway connectors.

The results of these actions are presented on Exhibit 2. Highlights of this option include:

A. While roads are not permitted within RPZ's, this criteria is relatively new and it is assumed that the FAA would accept Norview Avenue located within the Runway

14 RPZ. However, all roads within the new Runway 32 RPZ would be prohibited.

B. All criteria associated with the Runway 14 end have been brought up to standard and issues mitigated.

C. New impacts are created on the Runway 32 end as follows:

1. Closure or relocations of Miller Store Road, Tim Road, Burton Station Road and Drum Lane
2. Relocation of railroad and a spur
3. Acquisition and relocation of office space (5840 Burton Station Road) – non compatible use within the RPZ
4. Acquisition and relocation of several residences
5. Possible acquisition and relocation of one or two hotels (Comfort Inn and Wingate)
6. Likely impacts to golf course associated with tree removal and option associated with the road and railroad relocations.
7. Possible obstruction issues with development and utilities along Northampton Blvd.
8. Likely several other issues that are not immediately known due to the level of this effort.

Costs to accomplish Scenario A are difficult to fully assess at this time. However, a reasonable effort has been completed to identify the scope of items that would have to be addressed and where possible, costs have been assigned. This cost summary can be found in Table 3.

6/25/14

N

RUNWAY 5-23

RUNWAY 14-32 (5,600' x 100')

1000' RSA

1000' RSA

ROFA

RSA

RPZ

974' SHIFT
(ROFA CONTROL)

TIM RD

DRUM LN

HOTELS

BURTON STATION RD

RESIDENTIAL AREA

OFFICE

NORVIEW AVE

MILLER STORE RD

NORTHHAMPTON BLVD

800 0 800 1600

SCALE: 1"=800' FEET

www.deltaairport.com

# SCENARIO A
## NORFOLK INTERNATIONAL AIRPORT

| DRAWN BY: | PJW | CHECKED BY: | JCL | SCALE: | 1" = 800' | DATE: | JUNE 2014 |
|---|---|---|---|---|---|---|---|

EXHIBIT
2

N:\14051\04 CAD\Exhibits\14051 RW 14-32 Scenario A2.dwg, L1, 6/25/2014 8:50:15 AM, mrm

DRAWING: 14051 RW 14-32 Scenario A2.dwg LAYOUT: L1

# TABLE 2
# DESIGN STANDARDS SCENARIO A
# C-III DESIGN STANDARDS

**RUNWAY 14-32 EXISTING CONDITIONS VERSUS FAA REQUIRED DESIGN STANDARDS**

Source: Table A7-9 Runway design standards matrix, C/D/E - III FAA AC 150/5300-13A

| ITEM | DIM [1] | Runway 14 | | Runway 32 | |
|---|---|---|---|---|---|
| | | Existing Not Lower than 1 mile | Required Not Lower than 1 mile | Existing Not Lower than 1 mile | Required Not Lower than 1 mile |
| **RUNWAY DESIGN** | | | | | |
| Runway Length - Departure | A | 4,875 ft | 5,600 ft | 4,875 ft | 5,600 ft |
| Runway Length - Arrival | | 4,662 ft | 5,600 ft | 4,875 ft | 5,600 ft |
| Runway width * | B | 150 ft | 100 ft | 150 ft | 100 ft |
| Shoulder Width | | 0 ft | 25 ft | 0 ft | 25 ft |
| Blast Pad Width | | 150 ft | 200 ft | 0 ft | 200 ft |
| Crosswind Component | | 16 knots | 16 knots | 16 knots | 16 knots |
| **RUNWAY PROTECTION** | | | | | |
| Runway Safety Area (RSA) | | | | | |
| Length beyond departure end | R | 1,000 ft | 1,000 ft | 41 ft | 1,000 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | C | 500 ft | 500 ft | 500 ft | 500 ft |
| Runway Object Free Area (ROFA) | | | | | |
| Length beyond runway end | R | 935 ft | 1,000 ft | 41 ft | 1,000 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | Q | 800 ft | 800 ft | 800 ft | 800 ft |
| Runway Obstacle Free Zone (ROFZ) | | | | | |
| Length | | 5,166 ft | 6,000 ft | 5,166 ft | 6,000 ft |
| Width | | 400 ft | 400 ft | 400 ft | 400 ft |
| Precision Obstacle Free Zone (POFZ) | | | | | |
| Length | | N/A | N/A | N/A | N/A |
| Width | | N/A | N/A | N/A | N/A |
| Approach Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1,700 ft | 1,700 ft | 1,700 ft |
| Inner Width | U | 500 ft | 500 ft | 1,000 ft | 500 ft |
| Outer Width | V | 1,010 ft | 1,010 ft | 1,510 ft | 1,010 ft |
| Acres | | 29.465 | 29.465 | 29.465 | 29.465 |
| Departure Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1,700 ft | 1,700 ft | 1,700 ft |
| Inner Width | U | 500 ft | 500 ft | 500 ft | 500 ft |
| Outer Width | V | 1,010 ft | 1,010 ft | 1,010 ft | 1,010 ft |
| Acres | | 29.465 | 29.465 | 29.465 | 29.465 |
| **RUNWAY SEPARATION** | | | | | |
| *Runway centerline to:* | | | | | |
| Parallel runway centerline | H | N/A | | | |
| Holding Position | | 250 ft | 250 ft | 250 ft | 250 ft |
| Parallel taxiway/taxilane centerline | D | 399 ft | 400 ft | 399 ft | 400 ft |
| Aircraft parking area | G | 500 ft | 500 ft | 500 ft | 500 ft |
| Helicopter touchdown pad | | N/A | | | |

* Runway width for design of 150,000 pounds or less is 100 feet, over 150,000 pounds width is 150 feet.

# TABLE 3
# PROJECT COST SUMMARY SCENARIO A

| Classification | | Budget Amount |
|---|---|---|
| **Administration** | | |
| Miscellaneous costs | | $10,000.00 |
| | **Subtotal** | **$10,000.00** |
| **Preliminary expense** | | |
| Master Plan Update | | $250,000.00 |
| Obstruction Study | | $125,000.00 |
| Environmental Impact Statement | | $1,500,000.00 |
| Appraisals, EDDA, Surveys (prelim land items) | | $50,000.00 |
| | **Subtotal** | **$1,925,000.00** |
| **Land, structures, right-of-way** | | |
| Office building acquisistion and demolition | | Pending |
| Hotel acquisition and demolition | | Pending |
| Residential acquisistion and demolition | | Pending |
| Golf course acquistion and replacement lands | | Pending |
| | **Subtotal** | **$0.00** |
| **Architectural engineering basic fees** | | |
| Preliminary Design, Airfield | | $500,000.00 |
| Final Design, Airfield | | $1,500,000.00 |
| Preliminary Design roadway system modifications | | Pending |
| Final Design roadway system modifications | | Pending |
| Preliminary Design railroad relocations | | Pending |
| Final Design railroad relocations | | Pending |
| | **Subtotal** | **$2,000,000.00** |
| **Project inspection fees** | | |
| CO Phase Services, Airfield | | $900,000.00 |
| CO Phase Services, roadway system modifciations | | Pending |
| CO Phase Services, railroad relocations | | Pending |
| | **Subtotal** | **$900,000.00** |
| **Relocation expense** | | |
| Moving expenses for businesses and homes | | Pending |
| | **Subtotal** | **$0.00** |
| **Relocation payment to individuals and businesses** | | |
| | | Pending |
| | **Subtotal** | **$0.00** |
| **Demolition and removal** | | |
| Houses, office bldg, hotels | | Pending |
| | **Subtotal** | **$0.00** |
| **Construction and project improvement cost** | | |
| Runway and Taxiway | | $20,400,000.00 |
| Relocate Miller Store Road | | Pending |
| Relocate Burton Station Road | | Pending |
| Relocate Tim Road | | Pending |
| Relocate Railroads | | Pending |
| | **Subtotal** | **$20,400,000.00** |
| **Miscellaneous cost** | | |
| | | Pending |
| | **Subtotal** | **$0.00** |
| **TOTAL** | | **$25,235,000.00** |
| **SAY** | | **$25,200,000.00** |

**Note that several items are not included as they are difficult to estimate at this level. Items that would be within the scope of the project, but have no value assigned are identified as "pending"**

**Scenario B: Bring Runway 14-32 into compliance by Reducing size of Critical Aircraft and keeping improvements within airport boundaries**

The concept of this Scenario is to "fit" a usable runway within the existing airport boundaries. To accomplish, it is assumed that a "downgrade" of the runway will be required. This "downgrade" would reduce the approach speed and critical aircraft wing span.

Two concepts were developed for Scenario B

1. Bring Runway 14-32 into full compliance
2. Bring Runway 14-32 into compliance with most criteria; however, assume that the FAA would allow a waiver to exist for roads within the RPZ as this is an existing condition.

Concept B1 results in a runway length of approximately 3,200 feet long and is shown on Exhibit 3. Concept B2 results in a runway length of approximately 4,150 feet long and is shown on Exhibit 4. Design criteria are presented on Tables 4 and 6 while Project Cost Summaries are presented in Tables 5 and 7.

The result of adopting either scenario has to bring into question the usefulness of the runway for Norfolk International Airport. Runway lengths less than 4,200 feet generally accommodate only light single and twin engine aircraft. In addition, there are costs that would be expended to "downgrade" the runway: reducing the runway width, relocation of all edge and end lights, adjustment of tie-ins to existing pavements, and the development of new approaches based on new runway ends.

Should one of the Scenario B concepts be considered, it would be beneficial to reduce the runway design criteria to Group II (wing spans up to 79 feet) vs. the Group III (wing spans up to 118 feet) that was used in the overall evaluation. The Group II design standard is more realistic for runway lengths less than 4,200 feet long. Using Group II standards would provide for additional runway length potential or open up more space within the airport boundary as the safety area requirements are reduced.

6/25/14

RUNWAY PROTECTION ZONE NOT LOWER THAN 1 MILE APPROACH VISIBILITY (MIN.) (500' X 700' X 1000')

RUNWAY PROTECTION ZONE NOT LOWER THAN 1 MILE APPROACH VISIBILITY (MIN.) (500' X 700' X 1000')

RUNWAY 5-23

600'

800'

300'

200'

ROFA

RPZ

RSA

RUNWAY 14-32 (3,200' x 100')

14

23

# SCENARIO B1
## NORFOLK INTERNATIONAL AIRPORT

EXHIBIT
3

www.deltaairport.com

| DRAWN BY: | PJW | CHECKED BY: | JCL | SCALE: | 1" = 600' | DATE: | JUNE 2014 |
|---|---|---|---|---|---|---|---|

DRAWING: 14051 RW 14-32 Scenario B1.dwg LAYOUT: L1

N:\14051\04 CAD\Exhibits\14051 RW 14-32 Scenario B1.dwg, L1, 6/25/2014 8:45:32 AM, mrm

# TABLE 4
# DESIGN STANDARDS SCENARIO B1
# A/B – III DESIGN STANDARDS

**RUNWAY 14-32 EXISTING CONDITIONS VERSUS FAA REQUIRED DESIGN STANDARDS**


Source: Table A7-9 Runway design standards matrix, C/D/E - III FAA AC 150/5300-13A

| ITEM | DIM [1] | Runway 14 | | Runway 32 | |
|---|---|---|---|---|---|
| | | Existing Not Lower than 1 mile | Required Not Lower than 1 mile | Existing Not Lower than 1 mile | Required Not Lower than 1 mile |
| **RUNWAY DESIGN** | | | | | |
| Runway Length - Departure | A | 4,875 ft | 3,200 ft | 4,875 ft | 3,200 ft |
| Runway Length - Arrival | | 4,662 ft | 3,200 ft | 4,875 ft | 3,200 ft |
| Runway width | B | 150 ft | 100 ft | 150 ft | 100 ft |
| Shoulder Width | | 0 ft | 10 ft | 0 ft | 10 ft |
| Blast Pad Width | | 150 ft | 95 ft | 0 ft | 95 ft |
| Crosswind Component | | 16 knots | 13 knots | 16 knots | 13 knots |
| **RUNWAY PROTECTION** | | | | | |
| Runway Safety Area (RSA) | | | | | |
| Length beyond departure end | R | 1,000 ft | 600 ft | 41 ft | 600 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | C | 500 ft | 300 ft | 500 ft | 300 ft |
| Runway Object Free Area (ROFA) | | | | | |
| Length beyond runway end | R | 935 ft | 600 ft | 41 ft | 600 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | Q | 800 ft | 800 ft | 800 ft | 800 ft |
| Runway Obstacle Free Zone (ROFZ) | | | | | |
| Length | | 5,166 ft | 4,400 ft | 5,166 ft | 4,400 ft |
| Width | | 400 ft | 400 ft | 400 ft | 400 ft |
| Precision Obstacle Free Zone (POFZ) | | | | | |
| Length | | N/A | N/A | N/A | N/A |
| Width | | N/A | N/A | N/A | N/A |
| Approach Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1000 ft | 1,700 ft | 1000 ft |
| Inner Width | U | 500 ft | 500 ft | 1,000 ft | 500 ft |
| Outer Width | V | 1,010 ft | 700 ft | 1,510 ft | 700 ft |
| Acres | | 29.465 | 13.77 | 48.978 | 13.77 |
| Departure Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1000 ft | 1,700 ft | 1000 ft |
| Inner Width | U | 500 ft | 500 ft | 500 ft | 500 ft |
| Outer Width | V | 1,010 ft | 700 ft | 1,010 ft | 700 ft |
| Acres | | 29.465 | 13.77 | 29.465 | 13.77 |
| **RUNWAY SEPARATION** | | | | | |
| *Runway centerline to:* | | | | | |
| Parallel runway centerline | H | N/A | | | |
| Holding Position | | 250 ft | 200 ft | 250 ft | 200 ft |
| Parallel taxiway/taxilane centerline | D | 399 ft | 300 ft | 399 ft | 300 ft |
| Aircraft parking area | G | 500 ft | 400 ft | 500 ft | 400 ft |
| Helicopter touchdown pad | | N/A | | | |

# TABLE 5
# PROJECT COST SUMMARY SCENARIO B1

| Classification | | Budget Amount |
|---|---|---|
| **Administration** | | |
| Miscellaneous costs | | $10,000.00 |
| | **Subtotal** | **$10,000.00** |
| **Preliminary expense** | | |
| Master Plan Update | | $250,000.00 |
| Obstruction Study | | $0.00 |
| Environmental Evaluation (Level unknown) | | $200,000.00 |
| Appraisals, EDDA, Surveys (prelim land items) | | $0.00 |
| | **Subtotal** | **$450,000.00** |
| **Land, structures, right-of-way** | | |
| None | | None |
| | **Subtotal** | **$0.00** |
| **Architectural engineering basic fees** | | |
| Preliminary Design, Airfield | | $75,000.00 |
| Final Design, Airfield | | $450,000.00 |
| Preliminary Design roadway system modifications | | None |
| Final Design roadway system modifications | | None |
| Preliminary Design railroad relocations | | None |
| Final Design railroad relocations | | None |
| | **Subtotal** | **$525,000.00** |
| **Project inspection fees** | | |
| CO Phase Services, Airfield | | $400,000.00 |
| CO Phase Services, roadway system modifciations | | None |
| CO Phase Services, railroad relocations | | None |
| | **Subtotal** | **$400,000.00** |
| **Relocation expense** | | |
| Moving expenses for businesses and homes | | None |
| | **Subtotal** | **$0.00** |
| **Relocation payment to individuals and businesses** | | |
| | | None |
| | **Subtotal** | **$0.00** |
| **Demolition and removal** | | |
| | | In construction cost |
| | **Subtotal** | **$0.00** |
| **Construction and project improvement cost** | | |
| Runway and Taxiway | | $6,100,000.00 |
| Relocate Miller Store Road | | None |
| Relocate Burton Station Road | | None |
| Relocate Tim Road | | None |
| Relocate Railroads | | None |
| | **Subtotal** | **$6,100,000.00** |
| **Miscellaneous cost** | | |
| | | Pending |
| | **Subtotal** | **$0.00** |
| **TOTAL** | | **$7,485,000.00** |
| **SAY** | | **$7,500,000.00** |

**Note that several items are not included as they are difficult to estimate at this level. Items that would be within the scope of the project, but have no value assigned are identified as "pending"**




# SCENARIO B2
## NORFOLK INTERNATIONAL AIRPORT

www.deltaairport.com

| DRAWN BY: | PJW | CHECKED BY: | JCL | SCALE: | 1" = 600' | DATE: | JUNE 2014 |
|---|---|---|---|---|---|---|---|

EXHIBIT
4

DRAWING: 14051 RW 14-32 Scenario B2.dwg LAYOUT: L1

N:\14051\04 CAD\Exhibits\14051 RW 14-32 Scenario B2.dwg, L1, 6/25/2014 8:49:28 AM, mrm

# TABLE 6
# DESIGN STANDARDS SCENARIO B2
# A/B – III DESIGN STANDARDS

**RUNWAY 14-32 EXISTING CONDITIONS VERSUS FAA REQUIRED DESIGN STANDARDS**

Source: Table A7-9 Runway design standards matrix, C/D/E - III FAA AC 150/5300-13A

| ITEM | DIM [1] | Runway 14 | | Runway 32 | |
|---|---|---|---|---|---|
| | | Existing Not Lower than 1 mile | Required Not Lower than 1 mile | Existing Not Lower than 1 mile | Required Not Lower than 1 mile |
| **RUNWAY DESIGN** | | | | | |
| Runway Length - Departure | A | 4,875 ft | 4,150 | 4,875 ft | 4,150 |
| Runway Length - Arrival | | 4,662 ft | 4,150 | 4,875 ft | 4,150 |
| Runway width | B | 150 ft | 100 ft | 150 ft | 100 ft |
| Shoulder Width | | 0 ft | 10 ft | 0 ft | 10 ft |
| Blast Pad Width | | 150 ft | 95 ft | 0 ft | 95 ft |
| Crosswind Component | | 16 knots | 13 knots | 16 knots | 13 knots |
| **RUNWAY PROTECTION** | | | | | |
| Runway Safety Area (RSA) | | | | | |
| Length beyond departure end | R | 1,000 ft | 600 ft | 41 ft | 600 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | C | 500 ft | 300 ft | 500 ft | 300 ft |
| Runway Object Free Area (ROFA) | | | | | |
| Length beyond runway end | R | 935 ft | 600 ft | 41 ft | 600 ft |
| Length prior to threshold | P | 254 ft | 600 ft | 600 ft | 600 ft |
| Width | Q | 800 ft | 800 ft | 800 ft | 800 ft |
| Runway Obstacle Free Zone (ROFZ) | | | | | |
| Length | | 5,166 ft | 5,350 ft | 5,166 ft | 5,350 ft |
| Width | | 400 ft | 400 ft | 400 ft | 400 ft |
| Precision Obstacle Free Zone (POFZ) | | | | | |
| Length | | N/A | N/A | N/A | N/A |
| Width | | N/A | N/A | N/A | N/A |
| Approach Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1000 ft | 1,700 ft | 1000 ft |
| Inner Width | U | 500 ft | 500 ft | 1,000 ft | 500 ft |
| Outer Width | V | 1,010 ft | 700 ft | 1,510 ft | 700 ft |
| Acres | | 29.465 | 13.77 | 48.978 | 13.77 |
| Departure Runway Protection Zone (RPZ) | | | | | |
| Length | L | 1,700 ft | 1000 ft | 1,700 ft | 1000 ft |
| Inner Width | U | 500 ft | 500 ft | 500 ft | 500 ft |
| Outer Width | V | 1,010 ft | 700 ft | 1,010 ft | 700 ft |
| Acres | | 29.465 | 13.77 | 29.465 | 13.77 |
| **RUNWAY SEPARATION** | | | | | |
| *Runway centerline to:* | | | | | |
| Parallel runway centerline | H | N/A | | | |
| Holding Position | | 250 ft | 200 ft | 250 ft | 200 ft |
| Parallel taxiway/taxilane centerline | D | 399 ft | 300 ft | 399 ft | 300 ft |
| Aircraft parking area | G | 500 ft | 400 ft | 500 ft | 400 ft |
| Helicopter touchdown pad | | N/A | | | |


# TABLE 7
# PROJECT COST SUMMARY SCENARIO B2

| Classification | | Budget Amount |
|---|---|---|
| **Administration** | | |
| Miscellaneous costs | | $10,000.00 |
| | **Subtotal** | **$10,000.00** |
| **Preliminary expense** | | |
| Master Plan Update | | $250,000.00 |
| Obstruction Study | | $0.00 |
| Environmental Impact Statement | | $200,000.00 |
| Appraisals, EDDA, Surveys (prelim land items) | | $0.00 |
| | **Subtotal** | **$450,000.00** |
| **Land, structures, right-of-way** | | None |
| | **Subtotal** | **$0.00** |
| **Architectural engineering basic fees** | | |
| Preliminary Design, Airfield | | $75,000.00 |
| Final Design, Airfield | | $450,000.00 |
| Preliminary Design roadway system modifications | | None |
| Final Design roadway system modifications | | None |
| Preliminary Design railroad relocations | | None |
| Final Design railroad relocations | | None |
| | **Subtotal** | **$525,000.00** |
| **Project inspection fees** | | |
| CO Phase Services, Airfield | | $400,000.00 |
| CO Phase Services, roadway system modifciations | | None |
| CO Phase Services, railroad relocations | | None |
| | **Subtotal** | **$400,000.00** |
| **Relocation expense** | | |
| Moving expenses for businesses and homes | | None |
| | **Subtotal** | **$0.00** |
| **Relocation payment to individuals and businesses** | | |
| | | None |
| | **Subtotal** | **$0.00** |
| **Demolition and removal** | | |
| | | Incl. in construction |
| | **Subtotal** | **$0.00** |
| **Construction and project improvement cost** | | |
| Runway and Taxiway | | $6,100,000.00 |
| Relocate Miller Store Road | | None |
| Relocate Burton Station Road | | None |
| Relocate Tim Road | | None |
| Relocate Railroads | | None |
| | **Subtotal** | **$6,100,000.00** |
| **Miscellaneous cost** | | |
| | | Pending |
| | **Subtotal** | **$0.00** |
| **TOTAL** | | **$7,485,000.00** |
| **SAY** | | **$7,500,000.00** |

**Note that several items are not included as they are difficult to estimate at this level. Items that would be within the scope of the project, but have no value assigned are identified as "pending"**

**Appendix A**

Airport Layout Plan (1)
Approach Procedures (4)




## AIRPORT DATA TABLE

| | |
|---|---|
| Airport Elevation (MSL) | 27.2' |
| Airport Reference Point (NAD 83) | |
| Latitude | 36° 53' 40.80" N |
| Longitude | 76° 12' 04.50" W |
| Mean Max Temperature of Hottest Month | 87° |
| Airport Terminal Area Navaids | ILS, GPS, VOR/DME Rotating Beacon |
| Magnetic Variation | 10.7° W |
| Date of Magnetic Variation | March 2007 |
| NPIAS Service Level | Primary (P) |
| State Service Level | Commercial Service (CM) |
| Wind Coverage Crosswind Component | |
| VMC | 100% |
| IMC | 99.9% |
| All Weather | 100% |
| Airport Reference Code | D-IV |
| Design Aircraft | Boeing 757-200 |
| Taxiway Lighting | MITL |
| Taxiway Marking | Centerline |

## FACILITIES TABLE

| # | Facility Name | # | Facility Name |
|---|---|---|---|
| 1 | Main Terminal Complex | 18 | FAA Support Building |
| 2 | Automobile Parking Garage | 19 | FAA ASR-9 Radar |
| 3 | Airfield Lighting Vault | 20 | G.A. Terminal and Hangar Facility C-1 |
| 4 | Tilturator | 21 | Hangar C-2 |
| 5 | Airfield Building and Baggage Claim | 22 | Hangar C-2 |
| 6 | Aircraft Rescue and Firefighting Station | 23 | T-Hangar Building #1 |
| 7 | ARFF Storage Building | 24 | T-Hangar Building #2 |
| 8 | Air Cargo Building | 25 | T-Hangar Building #3 |
| 9 | Air Cargo Building | 26 | Aircraft Maintenance Hangar |
| 10 | Catering Facility | 27 | Airfield Maintenance Facility |
| 11 | FAA Remote Communications Facility (RTR) | 28 | General Aviation Fuel Farm |
| 12 | Rental Car Return Building | 29 | ARFF Training Facility |
| 13 | FAA Support Building | 30 | Hangar C-5 |
| 14 | FAA Airport Traffic Control Tower | 31 | Hangar C-2 |
| 15 | Fuel Farm | 32 | Hangar C-4 |
| 16 | Former FAA Support Building (Abandoned) | 33 | FBO Maintenance Shop |
| 17 | Ground Run-up Enclosure (GRE) | 34 | Airfield Maintenance Building |

## ALL WEATHER WIND ROSE




## IMC WIND ROSE




## ALL WEATHER COVERAGE

| CROSSWIND COMPONENT | RUNWAY 5-23 | RUNWAY 14-32 | COMBINED |
|---|---|---|---|
| 10.5 KNOTS | 96.4% | 79.0% | 99.2% |
| 13 KNOTS | 99.0% | 89.0% | 99.8% |
| 16 KNOTS | 99.8% | 95.1% | 100.0% |
| 20 KNOTS | 100.0% | 99.1% | 100.0% |

## VMC WEATHER COVERAGE

| CROSSWIND COMPONENT | RUNWAY 5-23 | RUNWAY 14-32 | COMBINED |
|---|---|---|---|
| 10.5 KNOTS | 96.5% | 79.1% | 99.2% |
| 13 KNOTS | 99.0% | 89.0% | 99.8% |
| 16 KNOTS | 99.8% | 95.2% | 100.0% |
| 20 KNOTS | 100.0% | 99.2% | 100.0% |

## IMC WEATHER COVERAGE

| CROSSWIND COMPONENT | RUNWAY 5-23 | RUNWAY 14-32 | COMBINED |
|---|---|---|---|
| 10.5 KNOTS | 94.7% | 79.2% | 97.7% |
| 13 KNOTS | 97.6% | 87.4% | 99.3% |
| 16 KNOTS | 99.3% | 94.4% | 99.8% |
| 20 KNOTS | 99.8% | 98.2% | 100.0% |

WIND DATA SOURCE: SURFACE AIRWAY HOURLY DATA (TD-3280) FOR JANUARY 1, 1997 THROUGH DECEMBER 31, 2006 FROM NATIONAL CLIMATIC DATA CENTER

## RUNWAY DATA TABLE

| RUNWAY DATA | Runway 5 | Runway 23 | Runway 14 | Runway 32 |
|---|---|---|---|---|
| Effective Gradient (%) | 0.02 | | 0.03 | |
| Maximum Grade Change | 0.02 | | 0.03 | |
| Wind Coverage (%) | | | | |
| All Weather | 100.0% (20 knots) | | 100.0% (20 knots) | |
| IMC | 100.0% (20 knots) | | 100.0% (20 knots) | |
| Max. Elevation (MSL) | 27.2' | | 25.1' | |
| Runway Length | 9,001' | | 4,875' | |
| Runway Width | 150' | | 150' | |
| Displaced Threshold | 1,000' | 0' | 213' | 0' |
| Usable Runway Length* | 9,001' | 9,001' | 4,875' | 4,875' |
| Surface Type | Asphalt, Concrete, Grooved | | Asphalt, Grooved | |
| Pavement Strength | | | | |
| Single Wheel | 150,000 lbs. | | 75,000 lbs. | |
| Dual Wheel | 200,000 lbs. | | 100,000 lbs. | |
| Dual Tandem | 350,000 lbs. | | N/A | |
| Double Dual Tandem | 475,000 lbs. | | N/A | |
| Approach Surface Slope | 50:1 (Precision) | | 34:1 (Non-Precision) | |
| Approach Minimums | 200'-1/2 | 321'-3/4 | 420'-1 | 440'-1 |
| Visual Approach Aids | MALSR, PAPI | | REIL, PAPI | |
| Instrument Approach Aids | ILS-CAT I, VOR/DME, GPS | | VOR, DME, GPS | |
| Runway Lighting | HIRL | | MIRL | |
| Runway Marking | Precision | | Non-Precision | |
| Airport Reference Code (ARC) | D-IV | | C-III | |
| Critical Aircraft | Boeing 757-200 | | Boeing 737-700 | |
| Runway Object Free Area (ROFA) | | | | |
| Length Beyond Runway | 933' | 1,000' | 1,000' | 41' |
| Width | 800' | 800' | 800' | 800' |
| Runway Safety Area (RSA) | | | | |
| Length Beyond Runway | 933' | 1,000' | 1,000' | 41' |
| Width | 500' | 500' | 500' | 500' |
| Runway Object Free Zone (ROFZ) | 9,401' x 400' | | 5,166' x 400' | |
| FAR Part 77 Category | D-IV | | C-III | |
| Runway End Coordinates (NAD 83) | | | | |
| Latitude | 36°53'07.57" N | 36°54'19.44" N | 36°53'48.66" N | 36°53'16.92" N |
| Longitude | 76°12'31.38" W | 76°11'21.99" W | 76°12'43.76" W | 76°11'56.52" W |
| Runway End Elevations (MSL) | 18.8' | 19.2' | 19.2' | 22.7' |
| Displaced Threshold Elevation (MSL) | 21.9' | N/A | 19.3' | N/A |
| Line of Sight Violations | N/A | N/A | N/A | N/A |

* Lengths shown reflect total physical runway length. See declared distances table for detailed operational runway lengths

N/A = Not Applicable

## DECLARED DISTANCES

| Runway End ID | TORA | TODA | ASDA | LDA | LDA Approach End RSA Length | LDA Stop End RSA Length | ASDA Stop End RSA Length | Date of Approval |
|---|---|---|---|---|---|---|---|---|
| 5 | 9,001' | 9,001' | 8,938' | 7,936' | 2,000' | 1,000' | 1,000' | |
| 23 | 9,001' | 9,001' | 9,001' | 9,001' | 933' | 1,000' | 1,000' | |
| 14 | 4,875' | 4,875' | 4,875' | 4,662' | 244' | 1,000' | 1,000' | |
| 32 | 4,875' | 4,875' | 4,875' | 4,875' | 1,000' | 41' | 41' | |

ASDA = ACCELERATE-STOP DISTANCE AVAILABLE
TODA = TAKEOFF DISTANCE AVAILABLE
TORA = TAKEOFF RUN AVAILABLE
LDA = LANDING DISTANCE AVAILABLE

## LEGEND

| | |
|---|---|
| Runway Safety Area (RSA) | |
| Runway Object Free Area (ROFA) | |
| Runway Object Free Zone (ROFZ) | |
| Runway Protection Zone (RPZ) | |
| Taxiway Object Free Area (TOFA) | |
| Runway Visibility Zone | |
| Airport Pavement | |
| Airport Reference Point | |
| Airport Buildings | |
| Airport Property Line | |
| Railroad | |
| Fence | |
| Roads | |
| Ground Elevation Contours | 20 |
| Windsock [1] | |
| Obstruction Light | |
| Rotating Beacon | |

[1] Exact location not surveyed

## MODIFICATION OF STANDARDS

| No. | Standard Modified | FAA Standards / Existing Condition | Proposed Action | Reference/Comment | Date Approved |
|---|---|---|---|---|---|
| 1 | Runway 5 glide slope critical area | Critical area should be cleared of objects that could cause signal reflections / Localizer equipment building located within critical area at south end of Runway 5-23 | None | Approved by the FAA in previous ALP | |
| 2 | Runway visibility zone | An unobstructed view should be provided between intersecting runways / Aircraft parked at Gates B28 and B29 can obstruct view | Provide 24-hour ATCT/Close Runway 14-32 after construction of Runway 5R-23L | Approved by the FAA in previous ALP | |
| 3 | Runway 14 Runway Protection Zone (RPZ) | RPZ should be cleared of objects and certain land uses / Buildings inside RPZs at east and west ends of Runway 14-32 | Close Runway 14-32 after construction of Runway 5R-23L | | |
| 4 | Runway 14-32 Runway Safety Area (RSA) | 1,000' x 500' RSA should be cleared, graded, and free of objects / RSA at west end of Runway 14-32 does not meet standards | Close Runway 14-32 after construction of Runway 5R-23L | | |
| 5 | Runway 23 Runway Protection Zone (RPZ) | RPZ should be cleared of objects and certain land uses / Building at fishing facility is inside RPZ beyond north end of Runway 5-23 | Remove building from RPZ | | |
| 6 | Runway 5-23 Runway Object Free Area (ROFA) | 1,000' x 800' ROFA should be cleared of objects protruding above RSA edge elevation / ROFA at north end of Runway 5-23 contains fence and service road | None | Approved by the FAA in previous ALP | |

1"=400'
SCALE
400 0 400 800
FEET

| VA DEPT. OF AVIATION | | FEDERAL AVIATION ADMINISTRATION | | NORFOLK INTERNATIONAL AIRPORT | |
|---|---|---|---|---|---|
| PENDING | | PENDING | | PENDING | |
| APPROVED | DATE | APPROVED | DATE | APPROVED | DATE |

| NO. | REVISIONS | APP. | DATE |
|---|---|---|---|

# EXISTING AIRPORT LAYOUT PLAN


NORFOLK INTERNATIONAL AIRPORT
NORFOLK, VIRGINIA


JACOBS CONSULTANCY


TALBERT&BRIGHT ENGINEERS & PLANNERS CONSULTANTS


| | | | |
|---|---|---|---|
| DRAWN BY: | NTM/SEA | SCALE: | 1"=400' |
| CHECKED BY: | JAW/CJO | DATE: | JUNE 2008 |

SHEET 2 OF 9


NORFOLK, VIRGINIA
AL-291 (FAA)
13290
RNAV (GPS) RWY 14
NORFOLK INTL (ORF)
APP CRS 137°
Rwy Idg 4662
TDZE 25
Apt Elev 26
DME/DME RNP-0.3 NA.
Helicopter visibility reduction below ¾ SM NA.
MISSED APPROACH: Climb to 2000 via 137° course to WARIV WP then left turn direct JIMMY WP and hold.
ATIS 127.15
NORFOLK APP CON 118.9 353.7
NORFOLK TOWER 120.8 257.8
GND CON 121.9
CLNC DEL 118.5
HARCUM HCM
CAPE CHARLES CCV
Procedure NA for arrivals at CCV VORTAC on V1-139 Northeast bound and arrivals at DEEMS on V1 Southwest bound.
(IAF) CUBEL
JIMMY
4 NM
(IF) FIDAR
(FAF) JADEX
(IAF) HAMKI
WARIV
MSA RW14 25 NM
2300
DEEMS ORF 13 RADAR
ELEV 26
TDZE 25
137° to RW14
TWR 165
TDZ/CL Rwy 5
REIL Rwys 14 and 32
HIRL Rwy 5-23
MIRL Rwy 14-32
Procedure Turn NA
3.04°
TCH 35
5.6 NM
4.5 NM
CATEGORY
LNAV MDA
CIRCLING
NORFOLK, VIRGINIA
Orig-C 22AUG13
36°54'N - 76°12'W
NORFOLK INTL (ORF)
RNAV (GPS) RWY 14
NE-3, 01 MAY 2014 to 29 MAY 2014
NE-3, 01 MAY 2014 to 29 MAY 2014


NORFOLK, VIRGINIA
AL-291 (FAA)
13290
VOR/DME RWY 14
NORFOLK INTL (ORF)
VORTAC ORF 116.9 Chan 116
APP CRS 129°
Rwy Idg 4662
TDZE 25
Apt Elev 26
Helicopter visibility reduction below ¾ SM NA.
MISSED APPROACH: Climbing left turn to 2000 via ORF R-041 to JIMMY Int/11.8 DME and hold.
ATIS 127.15
NORFOLK APP CON 118.9 353.7
NORFOLK TOWER 120.8 257.8
GND CON 121.9
CLNC DEL 118.5
108.8 HCM Chan 25
JIMMY ORF 11.8
R-134
221°
041°
R-041
R-309
FLAPS ORF 10
1400
129°
(5)
CHIMP ORF 5
228
141
196
173
163
60
174
148
511
556
544
539
1282
1245
NORFOLK 116.9 ORF Chan 116
MSA ORF 25 NM
180°
1800
270°
2300
NE-3, 01 MAY 2014 to 29 MAY 2014
NE-3, 01 MAY 2014 to 29 MAY 2014
RADAR REQUIRED
ELEV 26
D
TDZE 25
2000
JIMMY
ORF R-041
FLAPS ORF 10
CHIMP ORF 5
2000
129°
1400
2.90°
TCH 35
ORF 0.6
5 NM
4.4 NM
129° 4.4 NM from FAF
85±
165±
117
128±
121±
9001 X 150
4875 X 150
TWR 165
23
32
5
CATEGORY | A | B | C | D
S-14 | 460-1 435 (500-1) | | 460-1¼ 435 (500-1¼) | 460-1½ 435 (500-1½)
CIRCLING | 520-1 494 (500-1) | | 540-1½ 514 (600-1½) | 580-2 554 (600-2)
TDZ/CL Rwy 5
REIL Rwys 14 and 32
HIRL Rwy 5-23
MIRL Rwy 14-32
NORFOLK, VIRGINIA
Amdt 2F 22AUG13
36°54′ N - 76°12′ W
NORFOLK INTL (ORF)
VOR/DME RWY 14


NORFOLK, VIRGINIA
AL-291 (FAA)
13290
APP CRS 317°
Rwy Idg 4875
THRE 22
Apt Elev 27
RNAV (GPS) RWY 32
NORFOLK INTL (ORF)
DME/DME RNP-0.3 NA. Helicopter visibility reduction below ¾ SM NA. Circling to Rwy 14 NA at night.
MISSED APPROACH: Climb to 2000 direct CERIN and on track 047° to JIMMY and hold.
ATIS 127.15
NORFOLK APP CON 118.9 353.7
NORFOLK TOWER 120.8 257.8
GND CON 121.9
CLNC DEL 118.5
CAPE CHARLES CCV
JIMMY
221°
041°
4 NM
188° (29.1)
2000
Procedure NA for arrivals at CCV VORTAC on V1-139 northeast bound.
047° (11.9)
228
196
141
163
CERIN
173
60
RW32
174
148
180
(FAF) EVAPE
511
(IAF) JEBAT
556
539
544
1245
1300
317° (5.2)
2000
227° (5)
MSA RW32 25 NM
2300
(IF) FAMEX
2000
047° (5)
(IAF) HELBA
Procedure NA for arrivals at SUNNS on V139 southwest bound.
SUNNS
2000
056° (25.7)
NE-3, 01 MAY 2014 to 29 MAY 2014
NE-3, 01 MAY 2014 to 29 MAY 2014
ELEV 27
D
THRE 22
2000
CERIN
trk 047°
JIMMY
FAMEX
EVAPE
2.3 NM to RW32
317°
2000
RW32
1300
3.06°
TCH 35
2.3 NM
1.5 NM
5.2 NM
85±
165±
117
128±
121±
TWR 165
9001 X 150
4875 X 150
317° to RW32
TDZ/CL Rwy 5
REIL Rwys 14 and 32
HIRL Rwy 5-23
MIRL Rwy 14-32
CATEGORY A B C D
LNAV MDA 440-1 418 (500-1) 440-1⅛ 418 (500-1⅛)
CIRCLING 520-1 493 (500-1) 540-1½ 513 (600-1½) 580-2 553 (600-2)
NORFOLK, VIRGINIA
Orig-C 17OCT13
36°54'N - 76°12'W
NORFOLK INTL (ORF)
RNAV (GPS) RWY 32


NORFOLK, VIRGINIA
AL-291 (FAA)
13290
VOR/DME RWY 32
NORFOLK INTL (ORF)
VORTAC ORF 116.9 Chan 116
APP CRS 326°
Rwy Idg 4875
TDZE 25
Apt Elev 26
Visibility reduction by helicopters NA.
MISSED APPROACH: Climbing right turn to 2000 via ORF R-041 to JIMMY Int/11.8 DME and hold.
ATIS 127.15
NORFOLK APP CON 118.9 353.7
NORFOLK TOWER 120.8 257.8
GND CON 121.9
CLNC DEL 118.5
108.8 HCM Chan 25
R-134
JIMMY ORF 11.8
221°
041°
R-041
NORFOLK 116.9 ORF Chan 116
CAJIN ORF 4
SECTS ORF 9
MSA ORF 25 NM
180°
1800
270°
2300
R-146
326°
(5)
RADAR REQUIRED
ELEV 26
D
TDZE 25
TWR 165
TDZ/CL Rwy 5
REIL Rwys 14 and 32
HIRL Rwy 5-23
MIRL Rwy 14-32
326° 3.8 NM from FAF
2000
ORF R-041
JIMMY
ORF 0.2
3.07°
TCH 35
3.8 NM
5 NM
1300
1600
CATEGORY
A
B
C
D
S-32
460-1 435 (500-1)
460-1¼ 435 (500-1¼)
460-1½ 435 (500-1½)
CIRCLING
520-1 494 (500-1)
540-1½ 514 (600-1½)
580-2 554 (600-2)
NORFOLK, VIRGINIA
Amdt 4E 18NOV10
36°54'N - 76°12'W
NORFOLK INTL (ORF)
VOR/DME RWY 32
NE-3, 01 MAY 2014 to 29 MAY 2014
NE-3, 01 MAY 2014 to 29 MAY 2014

**Appendix B**

Engineer's opinion of Probable construction cost (3)

**ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST**
**PRELIMINARY - SCENARIO A**

**RUNWAY 14-32 COMPLIANCE EVALUATION**

NORFOLK INTERNATIONAL AIRPORT
VIRGINIA

DATE:

| DESCRIPTION | UNIT | QUANTITY | UNIT PRICE | TOTAL AMOUNT |
|---|---|---|---|---|
| MOBILIZATION | LS | 1 | $ 1,100,000.00 | $ 1,100,000 |
| PAVEMENT REMOVAL | SY | 85,000 | $ 7.50 | $ 637,500 |
| MISCELLANEOUS DEMOLITION | LS | 1 | $ 75,000.00 | $ 75,000 |
| UNCLASSIFIED EXCAVATION | CY | 125,000 | $ 10.00 | $ 1,250,000 |
| MUCK EXCAVATION | CY | 12,500 | $ 25.00 | $ 312,500 |
| CEMENT TREATED SUBGRADE (12") | SY | 62,300 | $ 8.00 | $ 498,400 |
| EROSION AND SEDIMENT CONTROL | LS | 1 | $ 500,000.00 | $ 500,000 |
| CEMENT TREATED BASE COURSE (8") | SY | 62,300 | $ 25.00 | $ 1,557,500 |
| BITUMINOUS SURFACE COURSE | TN | 21,500 | $ 125.00 | $ 2,687,500 |
| GROUND STABILIZATION FABRIC | SY | 62,300 | $ 2.00 | $ 124,600 |
| AIRFIELD TRAFFIC CONTROL (CLOSED MARKERS, ETC) | LS | 1 | $ 100,000.00 | $ 100,000 |
| PAVEMENT MARKING | SF | 85,000 | $ 3.50 | $ 297,500 |
| GROOVING | SY | 49,600 | $ 1.25 | $ 62,000 |
| DRAINAGE (10% OF PAVING AND EARTHWORK | LS | 1 | $ 650,000.00 | $ 650,000 |
| SEEDING | AC | 175 | $ 1,250.00 | $ 218,750 |
| MULCHING | AC | 175 | $ 1,250.00 | $ 218,750 |
| CABLE TRENCH AND CONDUIT | LF | 12,000 | $ 6.00 | $ 72,000 |
| #6 BARE CU COUNTERPOISE | LF | 12,000 | $ 1.75 | $ 21,000 |
| 1/C, #8, 5KV, FAA TYPE "C" CABLE | LF | 24,000 | $ 1.50 | $ 36,000 |
| NEW AIRFIELD SIGNS | EA | 20 | $ 6,500.00 | $ 130,000 |
| NEW DISTANCE REMAINING SIGNS | EA | 5 | $ 7,500.00 | $ 37,500 |
| NEW TH LIGHTS | EA | 16 | $ 1,300.00 | $ 20,800 |
| NEW MIRLS | EA | 56 | $ 1,300.00 | $ 72,800 |
| MISC MITLS AT TIE-INS | EA | 12 | $ 1,300.00 | $ 15,600 |
| PULL CAN PLAZAS | EA | 8 | $ 7,500.00 | $ 60,000 |
| MISCELLANEOUS - 20% | LS | 1 | $ 2,000,000.00 | $ 2,000,000 |
| | | | **ESTIMATED CONSTRUCTION COST:** | $ 12,755,700 |
| | | | **SAY** | $ 12,750,000 |
| PARALLEL TAXIWAY 60% of RW | LS | 1 | | $ 7,653,420 |
| **TOTAL CONSTRUCITON COST FOR AIRFIELD ONLY** | | | | **$ 20,400,000** |

**ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST**
**PRELIMINARY - SCENARIO B1 - 3,200 FEET**

**RUNWAY 14-32 COMPLIANCE EVALUATION**

NORFOLK INTERNATIONAL AIRPORT
VIRGINIA

DATE:

| DESCRIPTION | UNIT | QUANTITY | UNIT PRICE | TOTAL AMOUNT |
|---|---|---|---|---|
| MOBILIZATION | LS | 1 | $ 350,000.00 | $ 350,000 |
| PAVEMENT REMOVAL | SY | 46,000 | $ 7.50 | $ 345,000 |
| MISCELLANEOUS DEMOLITION | LS | 1 | $ 75,000.00 | $ 75,000 |
| PAVEMENT SURFACE MILLING | SY | 35,600 | $ 6.00 | $ 213,600 |
| OFFSITE BORROW (TO FILL PAVEMENT REMOVAL) | CY | 46,000 | $ 15.00 | $ 690,000 |
| MUCK EXCAVATION | CY | 4,600 | $ 25.00 | $ 115,000 |
| CEMENT TREATED SUBGRADE (12") | SY | 0 | | $ - |
| EROSION AND SEDIMENT CONTROL | LS | 1 | $ 200,000.00 | $ 200,000 |
| CEMENT TREATED BASE COURSE (8") | SY | 0 | $ 22.50 | $ - |
| BITUMINOUS SURFACE COURSE | TN | 6,200 | $ 120.00 | $ 744,000 |
| GROUND STABILIZATION FABRIC | SY | 0 | $ 2.00 | $ - |
| AIRFIELD TRAFFIC CONTROL (CLOSED MARKERS, ETC) | LS | 1 | $ 50,000.00 | $ 50,000 |
| PAVEMENT MARKING | SF | 11,000 | $ 3.50 | $ 38,500 |
| GROOVING | SY | 0 | $ 1.25 | $ - |
| DRAINAGE (10% OF PAVING AND EARTHWORK) | LS | 1 | $ 150,000.00 | $ 150,000 |
| SEEDING | AC | 10 | $ 1,250.00 | $ 12,500 |
| MULCHING | AC | 10 | $ 1,250.00 | $ 12,500 |
| CABLE TRENCH AND CONDUIT | LF | 6,600 | $ 6.00 | $ 39,600 |
| #6 BARE CU COUNTERPOISE | LF | 6,600 | $ 1.75 | $ 11,550 |
| 1/C, #8, 5KV, FAA TYPE "C" CABLE | LF | 12,900 | $ 1.50 | $ 19,350 |
| NEW AIRFIELD SIGNS | EA | 10 | $ 5,000.00 | $ 50,000 |
| NEW DISTANCE REMAINING SIGNS | EA | 0 | $ 7,500.00 | $ - |
| NEW TH LIGHTS | EA | 16 | $ 1,300.00 | $ 20,800 |
| NEW MIRLS | EA | 32 | $ 1,300.00 | $ 41,600 |
| MISC MITLS AT TIE-INS | EA | 12 | $ 1,200.00 | $ 14,400 |
| PULL CAN PLAZAS | EA | 4 | $ 3,500.00 | $ 14,000 |
| MISCELLANEOUS - 20% | LS | 1 | $ 600,000.00 | $ 600,000 |
| | | | **ESTIMATED CONSTRUCTION COST:** | $ 3,807,400 |
| | | | **SAY** | $ 3,900,000 |
| PARALLEL TAXIWAY 60% of RW | LS | 1 | | $ 2,340,000 |
| **TOTAL CONSTRUCITON COST FOR AIRFIELD ONLY** | | | | **$ 6,100,000** |

**ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST**
**PRELIMINARY - SCENARIO B2 - 4,150 FEET**

**RUNWAY 14-32 COMPLIANCE EVALUATION**

NORFOLK INTERNATIONAL AIRPORT
VIRGINIA

DATE: June 24, 2014

| DESCRIPTION | UNIT | QUANTITY | UNIT PRICE | TOTAL AMOUNT |
|---|---|---|---|---|
| MOBILIZATION | LS | 1 | $ 350,000.00 | $ 350,000 |
| PAVEMENT REMOVAL | SY | 12,100 | $ 7.50 | $ 90,750 |
| MISCELLANEOUS DEMOLITION | LS | 1 | $ 50,000.00 | $ 50,000 |
| PAVEMENT SURFACE MILLING | SY | 69,200 | $ 6.00 | $ 415,200 |
| OFFSITE BORROW (TO FILL PAVEMENT REMOVAL) | CY | 12,100 | $ 15.00 | $ 181,500 |
| MUCK EXCAVATION | CY | 1,200 | $ 25.00 | $ 30,000 |
| CEMENT TREATED SUBGRADE (12") | SY | 0 | | $ - |
| EROSION AND SEDIMENT CONTROL | LS | 1 | $ 100,000.00 | $ 100,000 |
| CEMENT TREATED BASE COURSE (8") | SY | 0 | $ 22.50 | $ - |
| BITUMINOUS SURFACE COURSE | TN | 12,000 | $ 120.00 | $ 1,440,000 |
| GROUND STABILIZATION FABRIC | SY | 0 | $ 2.00 | $ - |
| AIRFIELD TRAFFIC CONTROL (CLOSED MARKERS, ETC) | LS | 1 | $ 50,000.00 | $ 50,000 |
| PAVEMENT MARKING | SF | 12,000 | $ 3.50 | $ 42,000 |
| GROOVING | SY | 0 | $ 1.25 | $ - |
| DRAINAGE (10% OF PAVING AND EARTHWORK) | LS | 1 | $ 175,000.00 | $ 175,000 |
| SEEDING | AC | 8 | $ 1,250.00 | $ 10,000 |
| MULCHING | AC | 8 | $ 1,250.00 | $ 10,000 |
| CABLE TRENCH AND CONDUIT | LF | 8,500 | $ 6.00 | $ 51,000 |
| #6 BARE CU COUNTERPOISE | LF | 8,500 | $ 1.75 | $ 14,875 |
| 1/C, #8, 5KV, FAA TYPE "C" CABLE | LF | 15,200 | $ 1.50 | $ 22,800 |
| NEW AIRFIELD SIGNS | EA | 10 | $ 5,000.00 | $ 50,000 |
| NEW DISTANCE REMAINING SIGNS | EA | 0 | $ 7,500.00 | $ - |
| NEW TH LIGHTS | EA | 16 | $ 1,300.00 | $ 20,800 |
| NEW MIRLS | EA | 42 | $ 1,300.00 | $ 54,600 |
| MISC MITLS AT TIE-INS | EA | 12 | $ 1,200.00 | $ 14,400 |
| PULL CAN PLAZAS | EA | 4 | $ 3,500.00 | $ 14,000 |
| MISCELLANEOUS - 20% | LS | 1 | $ 600,000.00 | $ 600,000 |
| | | | **ESTIMATED CONSTRUCTION COST:** | $ 3,786,925 |
| | | | **SAY** | $ 3,790,000 |
| PARALLEL TAXIWAY 60% of RW | LS | 1 | | $ 2,274,000 |
| **TOTAL CONSTRUCITON COST FOR AIRFIELD ONLY** | | | | **$ 6,100,000** |

# APPENDIX N – ELIMINATED RUNWAY ALTERNATIVES

**Table N-1 – Eliminated Runway Alternatives Summary**

| Alternative | Opportunities | Constraints |
|---|---|---|
| **Alternative 1: Relocate Runway 5 Threshold** | ✈ Captures full length of runway for landing on Runway 5 (current Landing Distance Available is adequate for all aircraft operations) | ✈ Cost and impact of relocating approach lighting system and navigational aids (glideslope, PAPIs, runway markings) |
| | - | ✈ Off-airport tree removal required |
| **Alternative 4: 9,000' Offset: 400'** | ✈ Provides secondary runway for operational flexibility | ✈ 400' separation does not permit simultaneous operations |
| | ✈ Proposed length accommodates all commercial activity | ✈ Overlapping Runway Object Free Areas (ROFAs) |
| | ✈ Avoids impacts to existing landside facilities | ✈ Requires relocation or decommissioning of VORTAC |
| | | ✈ Environmental impacts to Lake Whitehurst |
| | | ✈ Significant construction costs |
| | | ✈ Approach/departure overfly Little Creek Naval Base |
| **Alternative 5: 9,000' Offset: 876'** | ✈ Provides secondary runway for operational flexibility | ✈ Impacts to Lake Whitehurst |
| | ✈ Proposed length accommodates all commercial activity | ✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and GA parking apron) |
| | ✈ Avoids impacts to VORTAC | ✈ Significant construction costs |
| | ✈ 876' separation enables simultaneous VFR operations | ✈ Approach/departure overfly Little Creek Naval Base |
| **Alternative 6: 7,900' and 7,200' Offset: 876'** | ✈ Provides secondary runway for operational flexibility | ✈ Impacts to Lake Whitehurst |
| | ✈ Proposed length accommodates all or most commercial activity | ✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and GA parking apron) |
| | ✈ Avoids impacts to VORTAC | ✈ Approach/departure overfly Little Creek Naval Base |
| | ✈ 876' separation enables simultaneous VFR operations | |
| | ✈ Reduces costs and impacts due to shorter runway lengths (7,900' or 7,200') | |

*Table continued on next page*

*Table continued from previous page*

| Alternative | Opportunities | Constraints |
|---|---|---|
| **Alternative 7: 6,000', ARC-C-II (20:1)** | ✈ Provides secondary runway for GA airport users | ✈ Length limits usage by most commercial operations |
| | ✈ Avoids impacts to VORTAC | ✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and GA parking apron) |
| | ✈ 876' separation enables simultaneous VFR operations | ✈ Higher IFR visibility minimums |
| | ✈ No direct impacts to Lake Whitehurst (however some wetland impacts will occur) | |
| | ✈ No RPZ impacts | |
| | ✈ Greater height over Little Creek Naval Base | - |
| **Alternative 10: 5,500', ARC C-II (34:1)** | ✈ Provides secondary runway for GA airport users | ✈ Length restricts usage by all commercial operations |
| | ✈ Avoids impacts to VORTAC | ✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, and GA parking apron) |
| | ✈ 876' separation enables simultaneous VFR operations | ✈ RPZ impacts to commercial buildings |
| | ✈ No direct impacts to Lake Whitehurst (however some wetland impacts will occur) | |
| | ✈ Greater height over Little Creek Naval Base | |
| **Alternative 12A: 5,500', ARC C-II EMAS 3/4-Mile Visibility Minimum** | ✈ Provides secondary runway for GA airport users | ✈ Length restricts usage by commercial operations |
| | ✈ Avoids impacts to VORTAC | ✈ Impacts to on-airport facilities (airport maintenance and ARFF training facilities) |
| | ✈ 876' separation enables simultaneous VFR operations | ✈ RPZ impacts to commercial buildings |
| | ✈ No impacts to Lake Whitehurst | |
| | ✈ No wetland impacts | |
| | ✈ Provides separation of fleet mix (commercial and GA) | ✈ Relocation of existing airfield maintenance buildings |
| | ✈ Provides secondary runway for operational flexibility | ✈ Impacts on several GA hangars, the MRO facility, the itinerant parking apron, and the ARFF training area |
| | ✈ Provides more developable land on the east side of the airfield | ✈ Difficult construction phasing |

*Table continued on next page*

*Table continued from previous page*

| Alternative | Opportunities | Constraints |
|---|---|---|
| **Alternative 13A: Runway Realignment to 3-21 Orientation** | ✈ Avoids flyovers of Little Creek Naval Base | ✈ Reduced primary runway length (7,500') to accommodate safety areas |
| | ✈ Reduced impact to Little Creek Bay operations box | ✈ Complete reconstruction of airfield |
| | ✈ Standard full-length parallel taxiway option for primary and potential parallel runway | ✈ Reduced terminal apron space |
| | ✈ Provides the opportunity to reuse the existing primary runway as a full-length mid-field parallel taxiway | ✈ Substantial costs |
| | | ✈ Impacts to on-airport facilities (airport maintenance facilities, ARFF training facility, MRO hangar, GA hangar facilities and GA parking apron) |
| | | ✈ Requires filling a portion of Lake Whitehurst |
| | | ✈ Relocation of runway NAVAIDs |
| | | ✈ Realignment over residential area |
| **Alternative 13B: Runway Shift 400' West** | ✈ Limits flyovers of Little Creek Naval Base | ✈ Runway length shortened to 7,900' |
| | ✈ Provides more developable land on the east airfield for potential cargo relocation and expansion and GA facility expansion | ✈ Complete reconstruction of airfield |
| | | ✈ Substantial costs |
| | | ✈ Closure of secondary airport access route Robin Hood Road |
| | | ✈ Requires removal of 6 gates on Concourse B and RON parking |
| | | ✈ Removal of air cargo building and employee lot |
| | | ✈ Requires filling a portion of Lake Whitehurst |
| | | ✈ Relocation of runway NAVAIDs, VORTAC |
| | | ✈ Relocation of the existing ARFF station, ARFF storage building, and airport triturator |
| **Alternative 14: Secondary Runway** | ✈ Limits operations over Little Creek Naval Base | ✈ Substantial cost |
| | ✈ Provides separation of fleet mix (commercial and GA) | ✈ Relocation of existing airfield maintenance buildings |
| | ✈ Provides secondary runway for operational flexibility | ✈ Impacts on several GA hangars, the MRO facility, the itinerant parking apron, and the ARFF training area |
| | ✈ Provides more developable land on the east side of the airfield | ✈ Difficult construction phasing |

Source: CHA, 2019.

RELOCATED THRESHOLD SITING SURFACE 34:1 (#5)

RELOCATE THRESHOLD 1,000'

RELOCATE THRESHOLD LIGHTS

RELOCATE MALSR

PAINT RUNWAY MARKINGS

EXISTING DISPLACED THRESHOLD

RELOCATE GLIDE SLOPE

RUNWAY '5-23'

TAXIWAY 'C'

TAXIWAY 'J'

ROBIN HOOD RD.

APPROACH RPZ

RPZ

LOCALIZER

LOCALIZER SHELTER

N. MILITARY HWY-165

NORFOLK SOUTHERN RR

INTERSTATE 64

MILLER STORE RD.

ACADEMY DR.

HENNEMAN DR.

ELLSMERE AVE.

ALMEDA AVE.

SIGMON ST.

KILMER LN.

ELIZABETH AVE.

E. PRINCESS ANNE RD.

COWAND DR.

WRIGHT DR.

AIRPORT RD.

1,000

| DECLARED DISTANCES EXISTING | | |
|---|---|---|
| | RUNWAY 5 | RUNWAY 23 |
| TORA | 9,001' | 9,001' |
| TODA | 9,001' | 9,001' |
| ASDA | 8,809' | 8,995' |
| LDA | 7,809' | 8,995' |

| DECLARED DISTANCES PROPOSED THRESHOLD RELOCATIONS | | |
|---|---|---|
| | RUNWAY 5 | RUNWAY 23 |
| TORA | 6,860' | 9,001' |
| TODA | 6,860' | 9,001' |
| ASDA | 8,809' | 8,995' |
| LDA | 8,809' | 8,060' |

LEGEND:

- ANTENNA
- BUILDING
- BUSH
- COMMUNICATION TOWER
- CRANE
- POLE
- LIGHT POLE
- UTILITY POLE
- RUNWAY LIGHT
- SIGN
- NON-COMM TOWER
- TREE
- UTILITY BOX
- ROAD R-123
- 123 P77 SURFACE PENETRATION
- 123 P77 OBJECT WITHIN 10 OF P77

GRAPHIC SCALE (FEET)

0 100 200 400

HORIZONTAL

0 20

VERTICAL

EXISTING GROUND RUNWAY C/L PROFILE EXTENDED

INTERSTATE 64 (17' VEHICLE HEIGHT TYP.)

RELOCATED THRESHOLD SITING SURFACE 34:1 (#5)

RELOCATE THRESHOLD 1,000'

EXIST. RUNWAY 5 THRESHOLD ELEV = 20.59

1,000' THRESHOLD RELOCATION

200'

| NO. | DATE | REVISION | BY | CK. | APPR. |
|---|---|---|---|---|---|

DESIGNED BY XX
DRAWN BY XXXX
REVIEWED BY XXXX
APPROVED BY
SCALE
100 0 200
SCALE:

CHA design/construction solutions
CHA Consulting, Inc.
4080 Lafayette Center Drive #210A
Chantilly, Virginia 20151
703-230-0300
www.chaconsulting.com


NORFOLK INTERNATIONAL AIRPORT

PROJECT NAME
MASTER PLAN UPDATE

SHEET TITLE
(Figure N-1) Alternative 1: RELOCATE RUNWAY 5 THRESHOLD 34:1 TSS, DIV RUNWAY

JOB NO. 33370
DATE _____ 2018
FILE NAME
REV. NO.
DWG. NO.

File: V:\PROJECTS\MKY\A33370\CADD\FIGURES\MKY-ALP-ALT01thru10-MASTER ALTERNATIVES\Y-2 - EXH1-DRF-01 5-23 thru LDA OPS $DESIGNER$ Date: 3/6/2018 2:39:38 PM $USER$ $DESIGNER$




File: V:\PROJECTS\ANY\K41\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\5 - EXHIT-ORF-9001' WITH 400' OFF.DWG Saved: 7/8/2019 4:11:01 PM Plotted: 7/9/2019 11:28:42 AM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)

0 500 1000

**Figure N-2**
**Proposed 5R-23L - 9,001'**
34:1 TSS , D-IV Runway
180' SHIP HEIGHTS
Alternative 4

NORFOLK INTERNATIONAL AIRPORT


MASTER PLAN UPDATE




GRAPHIC SCALE (FEET)

0 750 1500

**Figure N-3**
**PROPOSED 5R-23L - 9,001'**
34:1 TSS , D-IV Runway
180' SHIP HEIGHTS
Alternative 5




File: v:\PROJECTS\ANY\X4\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\7 — EXHIT-ORF-CONCEPT B 7,900'.DWG Saved: 7/9/2019 11:01:15 AM Plotted: 7/9/2019 11:24:15 AM Current User: Abney, Nikki LastSavedBy: 5451


**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

**Figure N-4**
**Proposed 5R-23L - 7,900'**
34:1 TSS , C-III Runway
180' SHIP HEIGHTS
Alternative 6




**NORFOLK INTERNATIONAL AIRPORT**


MASTER PLAN UPDATE

**Figure N-5**
**Proposed 5R-23L - 7,200'**
34:1 TSS , C-III Runway
180' SHIP HEIGHTS
Alternative 7

File: V:\PROJECTS\ANY\K41\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\8 – EXH1-08F-CONCEPT A 7,200'.DWG Saved: 7/9/2019 11:18:28 AM Plotted: 7/9/2019 11:20:38 AM Current User: Abney, Nikki LastSavedBy: 5835

NORFOLK INTERNATIONAL AIRPORT


MASTER PLAN UPDATE




GRAPHIC SCALE (FEET)

0 500 1000

**Figure N-6**
**Proposed 5R-23L - 6,000'**
20:1 TSS , C-II Runway
180' SHIP HEIGHTS
Alternative 9




NORFOLK INTERNATIONAL AIRPORT

MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)

0 500 1000

| DECLARED DISTANCES PROPOSED RUNWAY 5R-23L | | |
|---|---|---|
| | RUNWAY 5R | RUNWAY 23L |
| TORA | 5,500' | 5,500' |
| TODA | 5,500' | 5,500' |
| ASDA | 5,500' | 5,500' |
| LDA | 4,500' | 5,500' |

**Figure N-7**
**Proposed 5R-23L - 5,500'**
34:1 TSS , C-II Runway
180' SHIP HEIGHTS
Alternative 10

File: V:\PROJECTS\ANY\X4\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\11 - EXHIT-ORF-CONCEPT 5A2 - 5,500' 23 TSS-34TO1.DWG Saved: 7/9/2019 11:52:03 AM Plotted: 7/9/2019 11:54:01 AM Current User: Abney, Nikki LastSavedBy: 5835




File: V:\PROJECTS\ANY\K43\33370\CADD\FIGURES\AIRFIELD ALTERNATIVES\RUNWAY ALTERNATIVES\13A - EXHIT-ORF-CONCEPT - 5,500 100 FT WIDE.DWG Saved: 7/9/2019 12:16:28 PM Plotted: 7/9/2019 1:19:11 PM Current User: Abney, Nikki LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**


MASTER PLAN UPDATE


GRAPHIC SCALE (FEET)

0 500 1000

| DECLARED DISTANCES PROPOSED RUNWAY 5R-23L | | |
|---|---|---|
| | RUNWAY 5R | RUNWAY 23L |
| TORA | 5,500' | 5,500' |
| TODA | 5,500' | 5,500' |
| ASDA | 5,500' | 5,500' |
| LDA | 4,900' | 5,500' |

**Figure N-8**
**Proposed 5R-23L**
**5,500' With EMAS At Both Ends**
20:1 TSS , C-II Runway
Not Lower than 3/4 Mile Visibility
Alternative 12A


LAND REQUIRED
RPZ
RSA
ROFA
TOFA
RPZ
RPZ
RPZ




**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)


0 500 1000

## LEGEND

- Future Airfield Pavement
- Future Runway

**Figure N-10**
**Runway Shift 400'**
Proposed Runway 5R/23L - 7,900'
Alternative 13B

File: V:\PROJECTS\ANY\K4\33370\CADD\FIGURES\ALTERNATIVES\RUNWAY ALTERNATIVES\PDH ALTERNATIVES\SHIFTED VERSION REDUCE TOTAL LENGTH OF 5L-23R.DWG Saved: 7/24/2019 3:23:28 PM Plotted: 7/25/2019 10:33:26 AM Current User: French, Adam LastSavedBy: 4571




File: V:\PROJECTS\ANY\K4\33370\CADD\FIGURES\ALTERNATIVES\RUNWAY ALTERNATIVES\13A – EXIT-ORF-CONCEPT-WITH ROTATED RUNWAY.DWG Saved: 8/21/2019 4:41:56 PM Plotted: 8/21/2019 4:47:06 PM Current User: Harris, Jackson LastSavedBy: 5451

**NORFOLK INTERNATIONAL AIRPORT**

MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)

0 500 1000

**Figure N-11**
**ROTATED 5'500' RUNWAY**
Alternative 14

# APPENDIX O – RECYCLING, REUSE, & WASTE REDUCTION PLAN

NORFOLK INTERNATIONAL AIRPORT

# Airport Master Plan:
# Recycling, Reuse, and Waste Reduction Plan



*Prepared by:*

CHA
design/construction solutions

***3 Winners Circle***

***Albany, NY 12205***

***Phone: (518) 453-4500***

*June 2019*

# TABLE OF CONTENTS

1 Recycling, Reuse, and Waste Reduction Plan ..... 1-1
1.1 Airport Description ..... 1-1
1.2 Types of Airport Waste ..... 1-1
1.3 Airport Buildings ..... 1-4
1.4 Existing Program ..... 1-5
1.4.1 Infrastructure ..... 1-6
1.4.2 Waste Collection ..... 1-8
1.4.3 Recycling, Reuse, and Waste Reduction Efforts ..... 1-8
1.5 Waste Management Contracts ..... 1-9
1.5.1 Waste & Recycling Contracts ..... 1-10
1.5.2 Tenant Leases ..... 1-10
1.6 Waste Audit ..... 1-10
1.6.1 Solid Waste Material ..... 1-10
1.6.2 Recycled Material Audit ..... 1-11
1.7 Recycling Feasibility ..... 1-11
1.8 Cost Savings & Revenue Generation ..... 1-12
1.9 Recommendations ..... 1-13
1.9.1 Future Recycling Program ..... 1-13
1.9.2 Reduce Waste to Landfills ..... 1-14
1.9.3 Education & Outreach ..... 1-16
1.9.4 Conclusion ..... 1-16

# LIST OF FIGURES

Figure 1-1 – Airport Waste Streams ..... 1-3

# LIST OF TABLES

Table 1-1 – Airport Waste Management Areas ..... 1-5
Table 1-2 – Waste Management Procedures at ORF ..... 1-9
Table 1-3 – Monthly Waste Removal Costs ..... 1-10

# 1 RECYCLING, REUSE, AND WASTE REDUCTION PLAN

The U.S. Congress passed the Federal Aviation Administration (FAA) Modernization and Reform Act (FMRA) in 2012. The law included several changes to the Airport Improvement Program (AIP), two of which related to recycling, reuse, and waste reduction at airports. Section 132(b) of the FMRA expanded the definition of airport planning to include, "*developing a plan for recycling and minimizing the generation of airport solid waste, consistent with applicable State and local recycling laws, including the cost of a waste audit*." Section 133 of the FMRA added a provision requiring airports that are preparing a master plan to address issues relating to solid waste recycling at the airport. This includes:

- The feasibility of solid waste recycling at the airport;
- Minimizing the generation of solid waste at the airport;
- Operation and maintenance requirements;
- Review of waste management contracts;
- The potential for cost savings or the generation of revenue

As defined by Congress, "recycling" refers to any program, practice, or opportunity to reduce the amount of waste disposed in a landfill. This includes reuse and waste reduction, as well as the recycling of materials. The FAA issued a memorandum on September 30, 2014 to provide guidance on preparing airport recycling, reuse, and waste reduction plans as an element of airport master plans within a sustainability document or as a standalone document. The guidance is mandatory when preparing an airport master plan. The purpose of this Study, which is concurrent with the Master Plan Update, is to review the Norfolk Airport Authority's (NAA) current recycling, reuse, and waste program, and to provide guidance on ways to reduce waste and improve recycling and reuse at Norfolk International Airport (ORF) in compliance with the FAA's guidance.

## 1.1 AIRPORT DESCRIPTION

ORF, which is classified as a small hub primary airport, is located one mile east of I-64 (Norview Ave exit 279), eight miles northeast of downtown Norfolk, VA.; 20 miles west of the Virginia Beach Oceanfront; and 45 miles southeast of Williamsburg, VA. The airport is owned and operated by the Norfolk Airport Authority (NAA). NAA is a political subdivision of the Commonwealth of Virginia and is an independent agency of the City of Norfolk. The Authority is governed by a Board of Commissioners consisting of up to nine members appointed by Norfolk City Council for four-year terms, as well as an Executive Director that manages routine operations at the Airport. Additional facility information is presented in **Chapter 1** of the Master Plan Study.

## 1.2 TYPES OF AIRPORT WASTE

The focus of this plan will be on municipal solid waste, which generally consists of everyday items used and then thrown out and legally disposed of in a landfill or equivalent state-permitted facility. When referring to municipal solid waste, the FAA guidance includes construction and demolition debris, organic compostable material (food and yard waste), and deplaned waste;

however, the guidance does not include other types of solid wasted such as hazardous waste, "universal waste" (i.e., batteries, fluorescent bulbs, and other electronics), and industrial waste.

The following are the four primary types of municipal waste generated at airports:

- Municipal Solid Waste (MSW) – MSW includes common inorganic waste such as aluminum and steel, glass bottles and containers, plastic bottles and containers, packaging, newspapers, and other paper products.
- Construction & Demolition (C&D) Debris – This includes any non-hazardous solid waste from land clearing, excavation, or other type of construction demolition and/or renovation of buildings, roads, and utilities. C&D debris may include concrete, wood, metals, drywall, carpet, plastics, pipes, and salvaged building components.
- Compostables – These are sometimes referred to as "food" or "green" waste. They include trees, shrubs, grass clippings, leaves, weeds, and small branches, as well as food that is not consumed or generated during food preparation activities but discarded.
- Deplaned Wasted – These are items that are removed from the passenger aircraft, which can include bottles and cans, newspapers and other mixed papers, plastic cups and utensils, food waste, magazines, and paper towels.


This plan will focus on the MSW listed above that can be recycled or disposed of in a landfill. This plan does not address the management of other types of waste, specifically hazardous waste, universal waste (batteries, fluorescent light bulbs, etc.), or industrial waste (used solvents, etc.), It should also be noted that any waste deplaned from international flights is regulated by separate laws.

Waste management at an airport includes many components and can be quite complex. For instance, ORF has various tenants, agreements, differing operational requirements, and disposal processes that all contribute to the waste stream at the Airport. According the FAA's September 30, 2014 guidance, an airport's waste management is broken down into three main areas:

- Areas where an airport has direct control over the waste stream (e.g., public spaces, office space, main terminal, and airfield);
- Areas where an airport does not have direct control over the waste steam, but can influence waste management (e.g., tenants and aircraft deplaned waste); and
- Areas where an airport has no control over the waste stream (i.e., areas where the airport does not own or leases to private or government entity).

In addition, the FAA's 2013 Recycling Synthesis identified seven main airport waste streams: terminals, airfields, cargo hangars, aircraft, airport construction, flight kitchens, and administrative offices (see **Figure 1-1**). The main generators of waste at the Airport are tenants, the main passenger terminal building, and the airfield. The airfield generates waste typically during construction projects, and waste materials can range from runway concrete or asphalt to lighting and signage.

**Figure 1-1 – Airport Waste Streams**




Source: FAA. (2013). *Recycling, Reuse and Waste Reduction at Airports-A Synthesis Document*.

## 1.3 AIRPORT BUILDINGS

NAA is responsible for numerous buildings and associated infrastructure and has direct control of waste management in several buildings at ORF; however, it doesn't have direct control over several others. Pursuant to the FAA's guidance on airport recycling, areas that NAA has direct control or influence should be included in the recycling, reuse, and waste reduction plan. Any buildings and areas that NAA does not have direct control may be excluded.

The terminal facility at ORF is separated into an Arrivals Terminal and a Main Passenger Terminal. The main passenger terminal is approximately 400,000-square-feet and houses all airline ticket counters, two airline concourses with 22 gates, and various retail and food concessions. Gate A1 is configured with US Customs and Border Protection facility requirements to allow the processing and handling of international flights. The NAA administrative offices, police and security offices, and conference facilities, are also located in the main passenger terminal.

The arrivals terminal is a 243,000-square-foot facility that contains the baggage claim facilities for arriving passengers and the ground transportation facilities to accommodate rental car operations, taxis, shuttle service and transportation network providers. The second-level mezzanine serves as the connection between the arrivals and main departures terminal buildings via the pedestrian bridge. NAA has control over waste management in space devoted for NAA staff offices and conference rooms, as well as space where other NAA employees work such as maintenance staff, Aircraft Rescue Fire Fighting (ARFF) staff, and other public employees. The NAA-influenced areas include the numerous leased areas in terminal buildings with airlines, food service providers, and rental car companies. **Table 1-1** summarizes the buildings and areas at ORF under control or influence of the NAA. The areas highlighted in red will be the main areas of focus for this plan.

**Table 1-1 – Airport Waste Management Areas**

| NAA Control | NAA Influence | No NAA Control or Influence |
|---|---|---|
| NAA Offices (Main Terminal Complex – Bldg. #1) | Main Terminal Complex – NAA & Airlines | FAA Support Building (Bldg. #13 & 18) |
| Parking Areas (Garage, Long-term & Short-term Lots, and employee parking – Bldg. #2, 35, and 36) | Arrivals Building & Baggage Claim – NAA & Airlines | FAA ATCT (Bldg. #14) |
| Airfield Maintenance Facility & Airfield Maintenance (Bldg. #27 & 34) | Terminal Restaurants & Retail Areas | TSA Offices & Checkpoints |
| Fuel Farm (Bldg. #15) | Airline Space within Terminal – baggage claim & handling, office space, hold rooms, passenger gates, and ticket counters | FIS Facility – US Customs & Border Protection |
| Aircraft Rescue & Firefighting Station, Storage Building, and Training Facility (Bldg. #6, 7, & 29) | Car Rental Facilities – Avis/Budget; Enterprise/Alamo/National; Hertz/Dollar/Thrifty | |
| NAA building maintenance areas including storage & and office space | Airline Catering & Flight Kitchen (Bldg. # 10) | |
| Non-leased terminal space for utilities | Air Cargo Building (Bldg. #8 & 9) | |
| Ground Run Up Enclosure (Bldg. #17) | GA Terminal & Hangar Facility C-1 (Bldg. #20) | |
| | Air Cargo – Fed Ex (Bldg. #8); UPS (Bldg. #9) | |
| | Hangars (Bldg. #21-25 & 30-32) | |

Source: Airport Master Plan Update – Building Diagram, CHA, 2019.

## 1.4 EXISTING PROGRAM

NAA currently has an undefined recycling program. Although the Airport recycles materials, it does not have specific policies or goals. The Airport has a contract with Waste Management and TFC Recycling for its recycling and waste hauling needs. According to NAA, some of the drivers and challenges to having an official plan and policy in place are:

- Interest of tenants to participate;
- Additional bulk collection points;
- The large number of trash receptacles/size of existing receptacles;
- Recyclable way finding

The challenges of sufficient staff to implement a comprehensive plan and to police compliance is also an issue. NAA is a lean organization and would have difficulty implementing and enforcing new policies with current staffing levels.

### 1.4.1 Infrastructure

Waste and recycling infrastructure are a critical part of waste management. The waste management infrastructure used by NAA includes recycling bins, garbage cans, dumpsters, and compactors. Inside the arrivals and main terminal, there are a wide of variety of trash and recycling receptacles with a myriad of different colors and styles. There are two main areas where trash and recycling are collected: at the main terminal and arrivals terminal. There are three additional trash dumpsters at various locations around the airport. These are described in more detail in the following sections.

***Recycling Bins & Garbage Cans***

The Airport has a wide variety of recycling bins and garbage cans throughout their facility, which are described below:

- NAA Administrative Areas – In the NAA administrative areas, employees have individual recycling bins and garbage cans in their offices and also have access to containers in common areas, such as meeting rooms and restrooms.
- Concourse A & B – There are a wide variety of separate garbage and recycling bins located throughout the passenger areas in Concourses A and B in the Main Terminal Building. These silver, 55-gallon containers were introduced in 2011 and are emptied by NAA janitorial staff numerous times throughout the day.






- Main Terminal Area – In the main terminal area between the pedestrian bridge the TSA checkpoint, there are smaller blank receptacles that are connected with both trash and recycling. According to NAA janitorial staff, these have issues, as the top of the receptacle is geared for bottles and cans only b/c of its small opening.





- TSA Checkpoint – Located at the TSA Checkpoints are dual receptacles for trash and recycling. Interviews with NAA staff indicated these receptacles perform the best as far as collection and ease of removal and replacing bags and contents.





- Curbside & Ticketing – The curbside and airline ticketing have decorative trash cans that are similar to the receptacles in the walkway between terminals. There also seemed to be less recycling only receptacles in this area.





- Dumpsters & Compactors – Dumpsters/compactors are positioned on airport property in five locations. The main terminal and the arrivals terminal each have one 30-yard dumpster/compactor for MSW and one 8-cubic yard dumpster for recycling. There are three other dumpsters for trash only located at the Robin Hood Lift Station (4 yards), the Field Maintenance Building (8 yards) and the Transportation Network Companies (TNC) Staging Lot (8 yards).






### 1.4.2 Waste Collection

Waste is collected in several different manners across the airport. Currently, NAA has two contracts for waste removal off-site. TFC Recycling is responsible for collecting the trash and recycling from the 30-yard dumpster/compactor and the 8-yard recycling dumpster each located at the Arrivals terminal and Main terminal. The 30-yard dumpsters are collected every Monday, Wednesday, and Friday while the two 8-yard recycling dumpsters are collected on Tuesdays and Thursdays. The recycling is processed at the TFC facility while the trash is sent to a waste to energy facility owned and operated by Wheelabrator Technologies.

Waste Management is responsible for collecting the three dumpsters located at the Field Maintenance Building, the Robin Hood Lift Station, and the TNC Staging Area. Although not confirmed, this waste is most likely being taken to a landfill.

### 1.4.3 Recycling, Reuse, and Waste Reduction Efforts

As previously stated, NAA currently has an undefined recycling program. Although recycling receptacles are located throughout the airport, albeit in a wide variety of ways, NAA does not have set goals or policies.

***NAA Administrative Offices & Terminal Area***

NAA employees located in the terminal administrative offices currently recycle office paper, newspapers, and magazines; cardboard; plastic bottles; and printer/toner cartridges. To further advance NAA's commitment to reducing waste, they recently purchased a "bulb crusher" to crush old incandescent lighting and recycle the glass. Other on-going efforts are discussed in the following subsections. All the waste collected by TFC is processed and sent to a waste to energy facility.

***Green Waste & Construction Debris***

NAA manages waste generated by landscaping and construction activities, universal waste, and hazardous waste. During construction and major infrastructure projects at the airport, NAA requires contractors to remove C&D waste, such as asphalt, concrete, aggregate, and other materials wherever possible, but at this time does not require them to re-use. Green waste from landscaping activities is collected on site (and stored adjacent to the Field Maintenance Building). Specific uses of this decomposed material have not been identified to date.

***Tenant Efforts***

The tenants at ORF fall into three primary categories: Airlines, Rental Car Companies, and Vendors. The one outlier to these categories is the USO facility located in the main terminal. Each category of tenant and their recycling efforts are discussed below

- Airlines – Three of the airlines that service ORF (American Airlines, Southwest Airlines and Allegiant Airlines) provided information about their existing recycling efforts. None of the three airlines currently utilize the existing airport recycling program for either office waste or deplaned MSW. This is primarily due to internal company policies that govern how MSW generated onboard the aircraft is handled. Both American and Southwest separate aluminum cans onboard the aircraft, which are then retained onboard until the aircraft returns to a designated hub airport. Allegiant Airlines do not require their cabin crew to separate the MSW generated onboard the aircraft. All of the airlines utilize the existing

NAA disposal facilities, with co-mingled deplaned waste deposited in the trash compactor.

- Rental Car Companies – The waste generated in the leased office space for Rental Car Companies and at ticket counters for all three airlines is also currently co-mingled. Existing waste receptacles in these locations are emptied by contracted janitorial services (not NAA staff) and deposited in the ORF trash compactor.
- Vendors/Restaurants – The Vendors currently co-mingle all waste (with the exception of cardboard) which is removed by contracted janitorial services and deposited in the ORF trash compactor.
- USO Facility: The USO facility located in the main terminal is serviced by NAA staff and does separate recyclable materials from the remainder of the generated trash. The disposal of these materials follows the standard waste disposal procedures practiced by NAA.

A descriptions of the waste collection procedures are listed in **Table 1-2** by waste source.

**Table 1-2 – Waste Management Procedures at ORF**

| Waste Source | Waste Management Procedures |
|---|---|
| Arrivals Terminal (Pre-Security excluding concessions) | There are numerous trash and recycling receptables throughout this area, although receptacle types differ in appearance. Trash & recycling receptables located in the check-in and pre-security areas are collected and transported by NAA's janitorial service to the 30-yard trash dumpster/compactor and 8-yard recycling dumpster at the Arrivals Terminal. Both of these dumpsters are collected by TFC Recycling. There was no recycling receptables located on the curbside. |
| Main Terminal (Post Security) | Individual 55-gallon receptables (one each for recycling and trash) are located through the concourses with one each at every gate and scattered throughout the general circulation areas. This waste is also collected by NAA janitorial staff and taken to the Main Terminal 30-yard trash dumpster/compactor and 8-yard recycling dumpster, which is also collected by TFC. Deplaned waste is handled by the airlines but is transported to the same dumpsters. |
| Concessions | Waste from concession activities is not handled by NAA. All waste is co-mingled and disposed of in the NAA trash compactor. Cardboard is separated and placed in NAA's cardboard compactor. |
| Airfield | Landscape waste is generally stockpiled in a quasi-compost area near the Field Maintenance Building. Most other construction waste is specified in construction documents to be handled by the contractor. Glycol used for de-icing operations is collected through the use of recovery trucks to meet required stormwater discharge and FAA requirements. |
| Field Maintenance Area | No recycling; Trash is collected in an 8-yard dumpster that is taken by Waste Management. Waste oil collection tanks are provided and utilized. |

Source: NAA, CHA (Site-Visit), 2019.

## 1.5 WASTE MANAGEMENT CONTRACTS

The FMRA requires a review of exiting waste management contracts to address solid waste recycling at an airport. The purpose of this exercise is to potentially identify opportunities to improve recycling scope and efficiency.

### 1.5.1 Waste & Recycling Contracts

According to NAA, dumpster and trash removal services at ORF (NAA managed spaces) have been with the same companies for over 15 years. Waste Management is currently handling the trash removal for the three dumpsters not located at the terminals. TFC, who also has been under contract with NAA over the same time period, handles the two 30-yard trash dumpsters at the terminals. TFC is also responsible for the two 8-yard recycling dumpsters at each terminal building.

The actual waste hauler contracts were not readily available for review; however, NAA provided a year's-worth of costs incurred to remove waste and recycling. NAA's primary waste collection contractor, TFC Recycling, collects waste on a scheduled basis and charges by weight. NAA's additional waste collection contractor, Waste Management, collects waste on a scheduled basis and charges by collection (pull). **Table 1-3** shows the monthly waste hauler fees broken out by vendor and month. In 2018, NAA averaged $2,085 a month in costs for Waste Management's services and approximately $7,300 for TFC Recycling.

**Table 1-3 – Monthly Waste Removal Costs**

| Month | Waste Management | TFC Recycling |
|---|---|---|
| January | $2,118.73 | $6,329.22 |
| February | $2,004.73 | $6,503.71 |
| March | $2,004.73 | $6,813.52 |
| April | $1,997.56 | $7,122.66 |
| May | $2,323.94 | $7,261.14 |
| June | $2,034.89 | $7,665.37 |
| July | $2,029.98 | $8,073.53 |
| August | $2,027.57 | $8,703.22 |
| September | $2,373.62 | $6,716.85 |
| October | $2,033.65 | $8,258.68 |
| November | $2,046.95 | $6,903.51 |
| December | $2,034.89 | $7,250.11 |

Source: NAA, CHA, 2019.

### 1.5.2 Tenant Leases

NAA is responsible for managing tenant leases in the terminal buildings as well as outlying facilities. According to NAA, tenant leases do not currently require participation in any airport recycling program or standalone recycling and waste management efforts.

## 1.6 WASTE AUDIT

CHA contracted with TFC Recycling to conduct a solid waste and a recycling audit. These visual audits, completed on February 5 and 11 2019, were on the material in the TFC dumpsters at the main terminal.

### 1.6.1 Solid Waste Material

During the solid waste audit, material was collected from the 30-yard dumpsters located at the Main terminal. The container held waste materials that had been collected over the course of one week. This solid waste included trash from both terminal buildings (both pre- and post-security); the concessions, the airlines deplaned waste, and trash from the airlines gate area. The visual audit revealed waste accounted for approximately 70% of the trash materials found in the

dumpster while other recyclables accounted for 30%. A breakdown of the waste by percentage was :

- Cardboard – 4%
- Paper (mixed office) – 1%
- Aluminum – 5%
- Plastic – 15%
- Glass – 5%
- MSW – 70%

### 1.6.2 Recycled Material Audit

The recycled material was collected from the two 8-yard dumpsters located at the two terminals. Fibers (carboard) accounted for 95% of the recyclable materials collected, while non-recyclables (e.g., non-compostable food waste, disposable food containers, other waste, etc) accounted for the remaining 5% of the recyclable materials collected.

## 1.7 RECYCLING FEASIBILITY

The enthusiasm of the NAA staff and the ORF tenants to commit to an official program is a major success factor in any recycling plan. Without the commitment of resources such as funding, labor and time, space, and access to secure areas, a recycling program will struggle to succeed. There are established Federal, State, and local guidelines that ensure appropriate waste handling and disposal. This section identifies some of these guidelines.

***Federal***

The U.S. Environmental Protection Agency (EPA) and the FAA establish the guidelines and that regulate solid waste. EPA guidelines that affect waste handling at the Airport include the Resource Conservation and Recovery Act (RCRA), which describes the proper waste management procedures and programs mandated by Congress. The RCRA established a national framework for waste management procedures, including both non-hazardous solid waste as well as hazardous waste. The laws and guidelines authorized by the RCRA are monitored by state officials to ensure that all federal guidelines are followed by local entities. All waste produced at ORF fall under the regulations established by the RCRA. The Act establishes guidelines for the safe disposal of materials including landfill material acceptance of industrial waste, their location, and proper mitigation guidelines for contamination cleanup.

As described earlier, the FMRA included planning requirements for recycling and waste minimization when completing a new airport master plan; therefore, NAA is required to address solid waste as part of an airport master planning project. The FAA also provides guidance and report format on airport waste and recycling in the September 2014 memo.

***State***

The Virginia Department of Environmental Quality (DEQ) oversees solid waste management at the state level, along with the Virginia Waste Management Board under the Virginia Waste Management Act. The provisions of this act set the standards for siting, design, construction, operation, closure and post-closure care of solid waste management facilities. Both companies

that provide waste hauling services for NAA utilize facilities that are permitted under these regulations. An initiative of the DEQ, the Virginia Environmental Excellence Program (VEEP) was established to encourage superior environmental performance. VEEP drives environmental excellence by encouraging facilities and organizations within the Commonwealth that have strong environmental records to go above and beyond their legal requirements. The goal of this voluntary program is to encourage facilities and organizations within the State of Virginia to incorporate environmental sustainability into their management procedures.

***Local***

The City of Norfolk has developed and implemented a series of initiatives titled Norfolk's Green Scene. Norfolk's Green Scene is an environmental hub that provides Norfolk residents with access to all things Green. "Norfolk strives to be a premier waterfront community that creates a positive, regenerative effect on its environment, avoids detrimental environmental impacts, and thrives economically and culturally." The goals of this initiative include the enhancement of the efficient use and protection of natural resources by reducing and recycling waste.

***Community***

Waste and recycling projects at other airports have confirmed that passengers have an interest in recycling. Based on the area's recycling programs, area residents have many opportunities to recycle and are familiar with general recycling practices. As has been previously discussed, the City of Norfolk has a commitment to reducing and recycling waste. Passengers and employees who recycle at home or at other businesses around Virginia are likely to expect ORF to have a recycling program and participate in that program. The use of the currently available recycling receptacles at ORF is an example.

Despite NAA not having a formal recycling plan, the Airport does recycle, which is conducted on a voluntary basis. This plan has reviewed existing facilities and practices and conducted a visual waste audit; therefore, NAA can begin to identify opportunities to increase recycling efforts through the recommendations later in this plan.

## 1.8 COST SAVINGS & REVENUE GENERATION

The costs associated with a recycling program are dependent on available infrastructure, material markets, and the type of waste generated. These costs often include capital costs for containers, landfill tipping fees, hauling costs, material rebates, and labor. Generally, demonstrated reductions in costs are an important part of ensuring the viability and success of an airport's recycling and waste reduction efforts. As a result, the FMRA requires an evaluation of the potential cost savings and revenue generation opportunities for an Airport Recycling, Reuse, and Waste Reduction Plan.

NAA's primary waste collection contractor, TFC Recycling, collects waste on a scheduled basis and charges by weight. Based on the past year's charges for dumpster and compactor trash removal services, NAA expects to pay approximately $438,000 over the next five years associated with TFC's services. NAA's additional waste collection contractor, Waste Management, collects waste on a scheduled basis and charges by collection (pull). Based on the past year's charges for dumpster trash removal services, NAA expects to pay approximately $125,156 over the next five years for Waste Management's services.

Reducing the volume of waste generated from all applicable areas under the influence of NAA would reduce costs by decreasing the number, frequency and tonnage of required pickups. In addition, the existing contracts are not structured to reduce costs by diverting materials to recycling. However; should a new fee structure be implemented for recycling collection versus waste collection, it is possible that NAA could achieve a financial benefit from diversion to recycling.

Source separated recyclable materials are potential revenue generators through rebates or credits from the collection companies. Rebates, credits, and similar programs would have to be negotiated in the next round of contracts for these services. If NAA is interested in receiving income from recyclable materials, two key elements need to be considered:

1) how to incentivize the waste haulers support for recycling instead of penalizing them through reduced waste payments, and
2) how this revenue would be credited to the various organizations responsible for waste management and recycling at ORF.

## 1.9 RECOMMENDATIONS

This section presents some recommendations for NAA, including waste reduction, reuse, and recycling strategies, based on the information presented in previous sections of this document. There are recommended strategies for reduction and reuse and for recycling and composting. This section also describes the containers and bins as well as the signage and labeling to lead to increased participation in recycling and reduce contamination.

### 1.9.1 Future Recycling Program

According to the EPA, recycling waste items to be processed into raw materials to make new products is the second most preferred waste management strategy after waste reduction. The FAA guidance expects an Airport's recycling, reuse, and waste reduction plan to document, at a minimum, the facility's existing program to recycle paper, plastic bottles, aluminum cans, and plastic cups. As discussed previously, recycling of these materials is carried out to various degrees at ORF.

***Mixed Recycling***

The current recycling stream at ORF allows for the recycling of co-mingled plastics, glass and aluminum. This program should be expanded into tenant spaces. Additionally, more uniform recycling containers should be explored for all public areas (both secure and unsecure) throughout the terminal to show a consistent message to all passengers. These should replace the current myriad of collection container styles located throughout ORF.

NAA should maintain the use of the glass crusher to permit the recycling of light bulbs and evaluate the feasibility of expanding this to include the contract janitorial companies that serve the various tenants within the facility. This could also be utilized for glass construction debris associated with future projects.

***Other Recyclables***

As other recyclable materials are identified in ORF's waste stream and occur in a consistent and significant quantity in the future, NAA should work with its employees, airlines, tenants, and

janitorial and waste hauling contractors to design and implement strategies to separate, collect, and process these materials.

### 1.9.2 Reduce Waste to Landfills

Waste reduction is the most environmentally preferred waste management strategy. It is recommended that NAA focus on moving materials up the waste management hierarchy as a key strategy in reducing the facility's environmental impacts. It is also recommended that NAA evaluate the following reduction and reuse strategies to determine which, if any, are feasible and prudent for implementation at ORF.

- Increase the percentage of waste destined for waste to energy generation, as opposed to landfill disposal. This would require re-negotiating existing contracts or potentially eliminating and/or consolidating all waste and recycling services to one vendor.
- Install liquid collection stations.
- Encourage employee and passenger reuse of durable water bottles by refilling at drinking fountains
- Evaluate the possibility of a pre-consumer food composting program
- Collect and donate unopened food, beverage, and toiletry items subject to TSA restrictions
- Set NAA 's printers and copiers to default to double-sided printing

***Waste to Energy***

As discussed previously, all of the waste currently hauled under contract with TFC Recycling is destined for disposal at a waste to energy facility located in the local area and operated by Wheelabrator Technologies. This represents a significant diversion from landfill disposal and is reflective of NAA's commitment. NAA should investigate the feasibility of sending a greater percentage of the overall waste stream at ORF to this facility which would require re-negotiating Waste Management's contract or only utilizing TFC as the sole provider of waste removal.

***Liquids Collection***

Evaluations of the waste collection procedures found that garbage cans and recycling containers located in the security queuing areas and other non-sterile areas receive a significant amount of liquids due to TSA restrictions. Liquids add significant weight to the waste stream, contaminate other materials like paper, and may be rejected by a recycler, which will result in them being landfilled. Liquid collection stations are becoming more common at Airports around the country to combat liquids in the waste and recycling streams.

It is recommended that NAA evaluate installing liquid collection stations in security queuing areas to capture the liquids discarded here. Liquid collection stations can both reduce the weight of the waste stream generated in these areas and protect recyclable materials. These stations should be co-located with recycling bins so passengers can recycle the plastic bottles, aluminum cans and other containers they do not wish to retain and refill.

Liquid collection stations also encourage passengers to empty their reusable and disposable water bottles and refill them in the sterile area after clearing screening. A liquid collection station

also acts as a final reminder to passengers about to enter the screening area that liquids greater than 3.3 fluid ounces are not allowed through screening, and thereby expedite the screening process by encouraging the removal of prohibited liquids from carry-on luggage.

Liquid collection stations are available from various manufacturers and can also be fabricated in-house. These stations require maintenance and servicing, specifically emptying into a designated drain. Stations should include signs indicating that passengers can empty their beverage containers and keep them to refill after they pass through security at water fountains located throughout the terminal.

The use of liquid collection stations would require custodial staff and contractor time to empty these containers on a regular basis and deal with any issues, such as spills. Case studies from other airports show that the time required for staff to empty these stations is offset by the reduction in time dealing with liquids in the trash bags, which can contribute greatly to their weight.

It would be important to locate the liquid collection stations within the security screening queuing areas and with designated access to custodial stations with floor drains to allow for them to be emptied easily and quickly.

Liquid collection stations also provide a benefit to housekeeping staff. Without liquid collection, bags need to be emptied more frequently so that they do not exceed comfortable or safe handling weights. Diverting liquids to a collection station from the waste or recycling stream can reduce the overall weight of waste and recycling bags, which can reduce the frequency at which bags need to be emptied. Diverting the liquids will also reduce the need to reinforce the bags (double bag) to address the extra weight and potential for leaks.

***Food Waste***

According to industry case studies, food waste is a major component of the waste stream at an Airport, on average about 35 percent. The potential implementation of a food composting program at ORF could result in significant waste reduction. Composting of food waste at ORF is largely dependent on the availability of a local composting facility or other organization interested in accepting this material. If a composting facility or other organization is found or established in the Norfolk area, NAA should evaluate implementing composting at ORF. In a terminal, pre-consumer food waste (waste generated by food preparation activities) is generally easier to compost because restaurant employees are at a facility more frequently and on a more regular basis than passengers, so they are easier to train and educate on composting practices and requirements. The specific items accepted by a composting facility are dependent on that facility's design and the process used to break down the waste; some facilities accept all food waste (including meat and bones and breads) while others accept only vegetables and fruit.

One option for easing into composting gradually is to first implement a composting program for coffee grounds generated by restaurants in the terminals. Coffee grounds have a pleasant odor, are easily identifiable (therefore easy to separate), are typically uncontaminated by other materials, and are generated in a predictable manner and quantity. Once tenants are comfortable composting coffee grounds, other materials can be added by name (banana peels,

apple cores, etc.) and/or by type (fruits, vegetables, etc.) until all food waste appropriate for composting is included.

***Donation of Food, Beverages, and Toiletries***

It is recommended that NAA investigate the feasibility of collecting unopened bottles of water, other beverages, food and toiletries that are restricted from carry-on luggage and donating them to a local charity or other organization. These items can be very heavy and add weight to the waste stream in the queuing area or TSA operation screening.

In compliance with TSA requirements, these items may need to be collected prior to the security checkpoint queuing area. Collection of these items would require containers at the security checkpoints and management by NAA staff to store the items until the receiving organization could collect them. Coordination between NAA and the designated receiving organization will be needed. The existing presence of a USO facility within the airport could facilitate this. Additionally, information from a TSA representative may be required to assist with coordination on the location and details of this collection program.

### 1.9.3 Education & Outreach

To complement existing waste and recycling signage, it is recommended that NAA work to improve terminal messaging for passengers by providing consistent instructions for recycling at ORF. Providing clear instructional signage at the recycling stations/recycling bins can improve passenger participation and reduce the amount of contamination into recycling collection points. As discussed earlier, this would also include consolidating the design of both the waste and recycling receptacles, so they are consistent throughout the terminal and passengers are not confused as to what type of material goes into what bin.




It is also recommended that NAA provide simple training for employees, airlines, and tenants that explains NAA's existing recycling efforts. The format of training could be as simple as an email, newsletters, or flyer etc. The training should include reminders about the materials that are accepted and information about some of the positive effects the program is having to reduce and reuse at ORF.

### 1.9.4 Conclusion

NAA has an existing voluntary recycling program, but no policies and procedures in place. However; the findings in this plan show there are opportunities to increase recycling efforts. By

implementing these recommendations, NAA could then set goals and implement policies (both for Airport staff and its tenants). Additionally, if NAA implements measures to ensure the ORF waste stream is not contaminated and made contract modifications to allow all solid waste and trash be taken to the waste to energy facility, the Airport could divert landfill materials and see increased and quantifiable cost savings.

# APPENDIX P – ENERGY EFFICIENCY ASSESSMENT

NORFOLK INTERNATIONAL AIRPORT

# Airport Master Plan: Energy Efficiency Assessment



*Prepared by:*


CHA
design/construction solutions

***3 Winners Circle***

***Albany, NY 12205***

***Phone: (518) 453-4500***


*February 2019*

# TABLE OF CONTENTS

Executive Summary ..... a
1 Energy Efficiency Assessment ..... 1-1
1.1 Utility Analysis ..... 1-1
1.1.1 Utility Rate Descriptions ..... 1-4
1.2 Building and System Descriptions ..... 1-4
1.2.1 Building 1: Main Terminal complex (Departures) ..... 1-4
1.2.2 Building 5: Arrivals Terminal ..... 1-10
1.2.3 Building 3: Airfield Lighting Vault (AFLV) ..... 1-12
1.2.4 Building 4: Triturator ..... 1-13
1.2.5 Building 34: Airfield Maintenance Storage (Snow Removal) ..... 1-14
1.2.6 Building 6: Aircraft rescue and firefighting (ARFF) Station ..... 1-14
1.2.7 Building 17: Ground Run-Up Enclosure (GRE) ..... 1-16
1.2.8 Building 27: Airfield Maintenance Facility ..... 1-16
1.2.9 Building 12: TNC Staging ..... 1-18
1.2.10 Building 2: Automobile Parking Garage ..... 1-18
1.2.11 Building 8 and 9: Air Cargo Buildings (UPS & Fedex) ..... 1-19
1.2.12 Building 36: Short-Term Parking Lot ..... 1-20
1.2.13 Building 35: Long-Term Parking Lot ..... 1-20
1.2.14 Building 15: Fuel Farm ..... 1-21
1.2.15 Building 7: ARFF Storage building ..... 1-21
2 Energy Conservation ..... 2-1
2.1 Energy Conservation Measures ..... 2-1
2.1.1 Building Envelope ECMs ..... 2-1
2.1.2 Mechanical Equipment ECMs ..... 2-3
2.1.3 Domestic Hot Water ECMs ..... 2-8
2.1.4 Kitchen ECMs ..... 2-9
2.1.5 Control System ECMs ..... 2-10
2.1.6 Lighting/Electrical System ECMs ..... 2-12
2.2 Operations and Maintenance Opportunities ..... 2-14
2.2.1 O&M-1: AHU HW/CHW Coil Cleaning and Replacement ..... 2-14

2.2.2 O&M-2: Jetway Bridge Infiltration ..... 2-14
2.3 Energy Conservation Opportunities (ECO) ..... 2-14
2.3.1 ECO-1: Power Distribution Transformer Replacements ..... 2-14
2.3.2 Energy Conservation Measures and Opportunities Per Building ..... 2-15
3 Renewable Energy Measures ..... 3-1
3.1 Solar Photovoltaic Array ..... 3-1
3.2 Wind ..... 3-3
3.3 Cogeneration ..... 3-4
4 Recommendations ..... 4-1
Appendix A – Utility Data ..... I
Appendix B – Lighting ECM Calculations ..... XVIII
Appendix C – ECM Calculations ..... XXXVIII
Appendix D – Alternative Energy Calculations ..... CXXV

## LIST OF FIGURES

Figure E-1 – Buildings Evaluated for Energy Efficiency ..... b
Figure 1-1 – Electricity Usage Building Comparison ..... 1-3
Figure 1-2 – Natural Gas Usage Building Comparison ..... 1-3
Figure 3-1 – Solar PV Areas Considered ..... 3-2
Figure 3-2 – Wind Resource Map ..... 3-4

## LIST OF TABLES

Table E-1 – Norfolk Airport Audited Buildings ..... a
Table E-2 – Norfolk International Airport – Recommended ECM Summary ..... d
Table 1-1 – Utility Summary ..... 1-2
Table 1-2 – Main Terminal AHUs ..... 1-6
Table 1-3 – Concourse A AHUs ..... 1-6
Table 1-4 – Concourse A FCUs ..... 1-7
Table 1-5 – Concourse B AHUs ..... 1-7
Table 1-6 – Concourse B FCUs ..... 1-8

Table 1-7 – Arrivals Terminal AHUs ..... 1-11

Table 1-8 – ARFF AHUs ..... 1-15

Table 2-1 – Window Replacement ..... 2-2

Table 2-2 – Door Sweeps and Seals Replacements ..... 2-2

Table 2-3 – White Roof Covering ..... 2-2

Table 2-4 – Window Shading ..... 2-3

Table 2-5 – Boiler Replacements Information ..... 2-4

Table 2-6 – AHU Motor Upgrades ..... 2-4

Table 2-7 – AHU Fan Variable Speed Drives (VSD) ..... 2-4

Table 2-8 – Window AC Replacement ..... 2-5

Table 2-9 – Destratification Fan ..... 2-5

Table 2-10 – Pump Variable Speed Drives ..... 2-6

Table 2-11 – Duct Sealing ..... 2-6

Table 2-12 – Mini-Split System Upgrade ..... 2-6

Table 2-13 – Elevator Motor Upgrades ..... 2-7

Table 2-14 – Escalator Controls ..... 2-7

Table 2-15 – DHW Fuel Conversion ..... 2-8

Table 2-16 – Natural Gas DHW Upgrade ..... 2-8

Table 2-17 – Kitchen Hood Upgrades ..... 2-9

Table 2-18 – Walk-In Freezer and Cooler Controls ..... 2-10

Table 2-19 – Vending Miser ..... 2-10

Table 2-20 – Demand Control Ventilation ..... 2-11

Table 2-21 – Night Setback ..... 2-11

Table 2-22 – Garage Door Interlock ..... 2-12

Table 2-23 – Plug Load Controls ..... 2-12

Table 2-24 – Lighting Upgrade ..... 2-13

Table 2-25 – Utility Rates Summary (Per Building) ..... 2-15

Table 2-26 – ECM Payback Criteria ..... 2-15
Table 2-27 – Savings Summary - Main Terminal Complex ..... 2-16
Table 2-28 – Savings Summary - Automobile Parking Garages ..... 2-17
Table 2-29 – Savings Summary - Airfield Lighting Vault ..... 2-17
Table 2-30 – Savings Summary - Triturator ..... 2-17
Table 2-31 – Savings Summary - Arrivals Building and Baggage Claim ..... 2-18
Table 2-32 – Savings Summary - Aircraft Rescue and Firefighting Station ..... 2-18
Table 2-33 – Savings Summary - ARFF Storage Building ..... 2-19
Table 2-34 – Savings Summary - Air Cargo Buildings ..... 2-19
Table 2-35 – Savings Summary - TNC Staging Area ..... 2-19
Table 2-36 – Savings Summary – Fuel Farm ..... 2-20
Table 2-37 – Savings Summary - Ground Run-Up Enclosure (GRE) ..... 2-20
Table 2-38 – Savings Summary - Airfield Maintenance Facility ..... 2-20
Table 2-39 – Savings Summary - Airfield Maintenance Storage Building ..... 2-21
Table 2-40 – Savings Summary - Long-Term Parking Lot ..... 2-21
Table 2-41 – Savings Summary - Short-Term Parking Lot ..... 2-21
Table 2-42 – Savings Summary – Exterior ..... 2-22
Table 3-1 – PV Arrays ..... 3-1
Table 3-2 – PV Arrays ..... 3-3


# EXECUTIVE SUMMARY

An energy efficiency assessment is a key component of the Master Plan Update and one of the first steps towards a sustainable future at ORF. Currently, there are about 37 buildings at Norfolk International Airport ('ORF' or 'the Airport'). Most of these buildings are owned and maintained by their respective tenants, with ground leases provided by the Norfolk Airport Authority ('NAA' or 'the Authority'). The 16 facilities and locations that are owned and maintained by the Norfolk International Airport Authority are the subject of this energy efficiency assessment and are depicted in **Table E-1** and **Figure E-1**.

**Table E-1 – Norfolk Airport Audited Buildings**

| Building Number (Figure 1) | Building Name | Building Use | Building Size (SQFT) |
|---|---|---|---|
| 1 | Main Terminal Complex | General Aviation, Concourses A & B, Ticketing, offices, waiting areas, restaurants | 188,574 |
| 2 | Automobile Parking Garages | Short-term, long-term parking | 259,519 |
| 3 | Airfield Lighting Vault | | 1,216 |
| 4 | Triturator | Airline Waste Removal | 768 |
| 5 | Arrivals Building and Baggage Claim | Passenger baggage claim, offices, USO, rental car kiosks, ground transportation | 78,850 |
| 6 | Aircraft Rescue and Firefighting Station | Airport fire vehicle storage, firehouse, offices, and lounge areas | 11,400 |
| 7 | ARFF Storage Building | Fire Rescue boat storage | 2,115 |
| 8 | Air Cargo Building (1) | Air cargo transfer area, offices | 62,720 |
| 9 | Air Cargo Building (2) | Air cargo transfer area, offices | 22,989 |
| 12 | TNC Staging Area | Rental Car Return | 4,160 |
| 15 | Fuel Farm | Airline fuel storage area | 16,936 |
| 17 | Ground Run-up Enclosure (GRE) | | 36,816 |
| 27 | Airfield Maintenance Facility | Airport maintenance vehicle storage, offices | 38,760 |
| 34 | Airfield Maintenance Building | Airport maintenance vehicle, salt, and chemical storage | 6,153 |
| 35 | Long-Term Parking Lot | Uncovered parking area | 433,611 |
| 36 | Short-Term Parking Lot | Uncovered parking area | 137,483 |

Source: CHA, 2019.




**NORFOLK INTERNATIONAL AIRPORT**

# MASTER PLAN UPDATE

GRAPHIC SCALE (FEET)
0 600 1200

| # | Name of Existing Facility |
|---|---|
| 1 | Main Terminal Complex |
| 2 | Automobile Parking Garage |
| 3 | Airfield Lighting Vault |
| 4 | Triturator |
| 5 | Arrivals Building and Baggage Claim |
| 6 | Aircraft Rescue and Firefighting Station |
| 7 | ARFF Storage Building |
| 8 | Air Cargo Building |
| 9 | Air Cargo Building |
| 12 | TNC Staging Area |
| 15 | Fuel Farm |
| 17 | Ground Run-Up Enclosure (GRE) |
| 27 | Airfield Maintenance Facility |
| 34 | Airfield Maintenance Building |
| 35 | Long-Term Parking Lot |
| 36 | Short-Term Parking Lot |

**Figure E-1**
Buildings Evaluated for Energy Efficiency

This energy efficiency assessment identifies savings associated with HVAC, HVAC controls, lighting, lighting controls, domestic hot water, and building envelope (walls, roofs, doors and windows). Unless otherwise stated, make, model, efficiency, and capacity information contained in this report was collected directly from equipment nameplates during the site visit or assumed based on best engineering judgment. The typical hours of operation and scheduling information for each building were obtained during facility staff interviews.

Several energy conservation measures (ECMs) have been identified, which, if implemented, will decrease the facility's energy consumption and reduce carbon emissions, resulting in electric and natural gas cost savings. These measures include:

- Implement Night Temperature Setback
- Implement Economizer Controls for Air Handling Units and Rooftop Units
- Install Variable Frequency Drives on Fan Motors
- Schedule Setback at Maintenance Facility and Storage Building
- Replace Electric Hot Water Heaters with Natural Gas Units
- Install Kitchen Hood Controllers
- Install Walk-In Cooler Controls
- Install Vending Machine Controls
- Upgrade Lighting and Controls
- Implement Demand Controlled Ventilation
- Install De-Stratification Fans
- Install High-Efficiency Motors
- Window Replacements
- Door Seal Replacements

A summary of the total recommended energy savings per building can be seen in **Table E-2** below:

## Table E-2 – Norfolk International Airport – Recommended ECM Summary

| Building Number | Building Name | Budgetary Cost | Annual Utility Savings | | | | Simple Payback |
|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | |
| | | $ | kW | kWh | Therms | $ | Years |
| 1 | MAIN TERMINAL COMPLEX | 494,260 | 71 | 1,659,112 | 69,014 | 115,498 | 4.1 |
| 2 | AUTOMOBILE PARKING GARAGE | 1,688,538 | 314 | 2,500,800 | - | 166,941 | 10.1 |
| 3 | AIRFIELD LIGHTING VAULT | 5,343 | 1 | 6,188 | - | 594 | 12.4 |
| 4 | TRITURATOR | 4,945 | 1 | 1,728 | - | 166 | 29.8 |
| 5 | ARRIVALS BUILDING & BAGGAGE CLAIM | 267,287 | - | 494,963 | 8,176 | 39,081 | 7.8 |
| 6 | AIRCRAFT RESCUE AND FIREFIGHTING STATION | 34,424 | 5 | 24,413 | - | 2,344 | 14.7 |
| 7 | ARFF STORAGE BUILDING | 2,637 | 2 | 6,595 | - | 633 | 4.2 |
| 8 & 9 | AIR CARGO BUILDINGS | 169,782 | 40 | 239,216 | - | 15,969 | 10.6 |
| 12 | TNC STAGING AREA | 17,750 | 4 | 16,451 | 38 | 1,111 | 16.0 |
| 15 | FUEL FARM | 3,616 | 1 | 5,841 | - | 390 | 9.3 |
| 17 | GROUND RUN-UP ENCLOSURE (GRE) | 1,608 | 2 | 8,847 | - | 591 | 2.7 |
| 27 | AIRFIELD MAINTENANCE FACILITY | 44,380 | 14 | 50,034 | - | 5,760 | 7.7 |
| 34 | AIRFIELD MAINTENANCE BUILDING | 5,915 | 1 | 14,787 | - | 1,570 | 3.8 |
| 35 | LONG-TERM PARKING LOT | 73,440 | 26 | 121,470 | - | 8,109 | 9.1 |
| 36 | SHORT-TERM PARKING LOT | 19,440 | 5 | 22,335 | - | 1,491 | 13.0 |
| L-1 | EXTERIOR LIGHTING | 258,516 | 133 | 627,696 | - | 41,902 | 6.2 |
| Total | | 3,091,881 | 620 | 5,800,476 | 77,228 | 402,150 | 7.7 |

Source: CHA, 2019.

# 1 ENERGY EFFICIENCY ASSESSMENT

## 1.1 UTILITY ANALYSIS

Electricity, natural gas, and propane are supplied and delivered to the various ORF buildings as listed in **Table 1-1**. The Authority provided the usage summaries for the some of the 16 buildings for the energy efficiency assessment. The Main Terminal Complex electric usage listed in **Table 1-1** includes four meters. The Main Terminal Complex gas meter includes the entire Main Terminal Complex gas consumption which consists of the Main Departures Building and the Concourses. The Arrivals Building electric usage includes two meters and a single meter for the gas consumption. One of the Arrivals' electric meters includes the electric usage for Garage A; however, the annual usage for the Arrivals Building summarized in **Table 1-1** does not include the electric usage for Garage A. Garage A usage is included in the Automobile Parking Garage listing along with the electric meters for Garage B and Garage C. The Aircraft Rescue and Firefighting Station (ARFF) electric and propane meters include the respective usages for the ARFF Station (Building 6) and ARFF Storage Building (Building 7). The Airfield Maintenance Building's gas and electric meters includes Buildings 27 and 34. For all the other buildings, utility information was not available.

For energy calculation purposes, twelve months (January 2017 through December 2017) of electric and natural gas bills were examined, as available. This data was analyzed and a blended average cost per kilowatt (kWh) and cost per therm values were determined for the overall complex. These values were used in the energy savings calculations. In the 12-month period, the buildings that were included in the energy audit used approximately 27,700,000 kWh at a total cost of about $1,982,350, which results in an average blended rate of $0.07 per kWh. Natural gas usage was 464,780 therms at a cost of $157,025, which resulted in an average rate $0.34 per therm. Propane usage was 8,686 gallons at a cost of $12,173, which resulted in an average rate of $1.40 per gallon. The following table and charts summarize the utility data used per building.


## Table 1-1 – Utility Summary

| Building Number | Building Name | Electric | | | Natural Gas | | | Propane | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Annual Usage | Annual Cost | Blended Rate | Annual Usage | Annual Cost | Blended Rate | Annual Usage | Annual Cost | Blended Rate |
| | | kWh | $ | $/kWh | Therms | $ | $/Therm | LPG | $ | $/LPG |
| 1 | MAIN TERMINAL COMPLEX* | 16,487,430 | 1,259,381 | 0.08 | 241,260 | 81,509 | 0.34 | X | X | X |
| 2 | AUTOMOBILE PARKING GARAGE | 1,709,927 | 111,162 | 0.07 | X | X | X | X | X | X |
| 3 | AIRFIELD LIGHTING VAULT | 272,800 | 26,164 | 0.10 | X | X | X | X | X | X |
| 4 | TRITURATOR | - | - | - | X | X | X | X | X | X |
| 5 | ARRIVALS BUILDING & BAGGAGE CLAIM* | 8,956,201 | 559,899 | 0.06 | 201,210 | 67,978 | 0.34 | X | X | X |
| 6 | AIRCRAFT RESCUE AND FIREFIGHTING STATION | 106,120 | 10,189 | 0.10 | X | X | X | 8,686 | 12,173 | 1.40 |
| 7 | ARFF STORAGE BUILDING | Inc. in bldg. #6 | | | X | X | X | Inc. in bldg. #6 | | |
| 8 | AIR CARGO BUILDING | - | - | - | - | - | - | X | X | X |
| 9 | AIR CARGO BUILDING | - | - | - | - | - | - | X | X | X |
| 12 | TNC STAGING AREA | - | - | - | - | - | - | X | X | X |
| 15 | FUEL FARM | - | - | - | - | - | - | X | X | X |
| 17 | GROUND RUN-UP ENCLOSURE (GRE) | - | - | - | - | - | - | X | X | X |
| 27 | AIRFIELD MAINTENANCE FACILITY | 166,500 | 15,554 | 0.09 | 22,310 | 7,537 | 0.34 | X | X | X |
| 34 | AIRFIELD MAINTENANCE BUILDING | Inc. in bldg. #27 | | | Inc. in bldg. #27 | | | X | X | X |
| 35 | LONG-TERM PARKING LOT | - | - | - | - | - | - | - | - | - |
| 36 | SHORT-TERM PARKING LOT | - | - | - | - | - | - | - | - | - |
| KEY | X – Not Applicable | (-) – Utility Info N/A | | | | | | | | |

*The usage for this facility includes portions of exterior lighting consumption, per discussions with client staff


Source: CHA, 2019.

Figure 1-1 – Electricity Usage Building Comparison




Source: CHA, 2019.

Figure 1-2 – Natural Gas Usage Building Comparison




Source: CHA, 2019.

### 1.1.1 Utility Rate Descriptions

The natural gas for the complex is separated into a supply component and a delivery component. The supply component of utility service is open to competition; however, NAA is under contract with Virginia Gas for an interruptible gas delivery program which, upon request, the Airport switches boiler consumption from natural gas to #2 fuel oil. The Airport Authority has not been requested to switch fuels for at least for three years, if not longer. More investigation should be considered in eliminating this request, as the costs involved in maintaining #2 fuel oil tanks, distribution connections, and other government restrictions may outweigh the price of the reduction in this tariff.

## 1.2 BUILDING AND SYSTEM DESCRIPTIONS

### 1.2.1 Building 1: Main Terminal complex (Departures)

***Building Summary***

ORF's Main Terminal was originally constructed in 1971; however, there have been multiple additions and renovations. The largest of these are the Concourse B addition in 1989, the TSA pre-check Additions in 2012/2014 for the concourses, and the Arrivals Terminal addition in 2003. The Main Terminal Complex is comprised of several areas, including the ticketing area and departure concourses which consist of the airline gates, concessions, administrative services, Custom and Border Protection (CBP) offices and processing areas, Transportation Security Administration (TSA) screening, and a fully-functioning Federal Inspection Service (FIS) facility.

***Building Envelope***

The Main Terminal exterior walls are face brick, insulation, and masonry block, with interior plaster construction. A large amount of single pane windows were installed in the original portions of the building, as well as a combination of insulated steel frame and glass with metal frame doors. The roof of the Main Terminal has a tar coating with gravel over top; the concourse sections of the roofs have been replaced with white rubber membrane coverings, while the original sections of the roof have remained the same as the Main Terminal.

***HVAC Systems***

Heating Systems: The Main Terminal Complex is heated by two 10,206 MBH dual fuel natural gas/fuel oil #2 fire tube boilers that have a variable frequency drive (VFD) controlling the boilers' feedwater pump. The boilers were installed in 2016. This system has an estimated combustion efficiency of 83 percent as indicated from boiler maintenance logs. The boiler operation is manually turned on and off between the heating and cooling seasons. The boiler primarily utilizes natural gas; however, the facility is currently in a contract with the utility service provider for a demand reduction program and switches to fuel oil when called upon.

These boilers distribute hot water (HW) to various HW coils located in air handling units (AHUs), fan coil units (FCUs), and an indirect domestic hot water (DHW) heater. The HW coils are controlled by 2-way valves, except for AHU-25 and AHU-37 which have 3-way valves. There are

three HW bypass valves located at AHU-6, AHU-7, and the end of Concourse A. Details on the domestic hot water (DHW) and air side systems are identified in the sections below.

The HW system is served by two 60-HP, 1600 gpm HW pumps that operate when the boilers are operating and are controlled by drives. Three sets of HW booster pumps are also located in the penthouse. One set of pumps are 15-HP 700 gpm, and the other set are 20-HP 320 gpm.

Cooling Systems: Cooling for the Main Terminal complex is supplied by three chillers: one 770-ton Trane chiller and two 570-ton Trane chillers. At least two chillers are operating during the cooling season.

There are four Evapco cooling towers, which each have two variable speed fans operating in a lead/lag configuration. When a chiller is operating, at least one cooling tower is operating as well. There are three condenser water pumps, two are 50 HP 1650 gpm and the third is 75 HP 1650 gpm. The large condenser water pump has a VSD and is associated with Chiller #3. There are three chilled water pumps. Two of the CHW pumps are 100-HP 2640 gpm and operating in a lead/lag configuration. The third CHW pump is 60-HP 1320 gpm. All three CHW pumps have VSDs; however, they do not fluctuate in their speed, as the VSD are used for "soft-starts". The smaller pump (#7) is used for transitional periods, as there is too much water flow in Chiller #1. The chillers are staged using the overall tonnage needed with a wet-bulb economizer control.

These chillers distribute chilled water (CHW) to various CHW coils located in air handling units (AHUs) and fan coil units (FCUs). The CHW coils are controlled by 2-way valves, except for AHU-37, which has a 3-way valve.

Air-side Systems: The main source of heating and cooling for the Main Terminal facility is a combination of air handling units (AHUs) with fan coil units (FCUs) serving hallway spaces in the concourses. There are twelve air handling units that supply a mixture of return and outside air to their respective spaces in the Main Terminal. One AHU is a make-up air (MUA) unit that provides only outside air with HW and CHW coils. This serves the kitchen area in the Main Terminal. There are ten AHUs and two roof top units (RTUs) that serve the concourses. Some of the AHUs are a preheat HW coil and CHW coil configuration, others have hot deck/cold deck coil configuration, and one unit has a face/bypass damper on the preheat coil. The two RTUs have a HW and CHW coil. There are three heating ventilation (HV) units that have only a heating coil and provide outside air only ventilation. These AHU's and HV's units vary in size and are detailed in **Table 1-2**. Note that some of the information for the AHU-25 and AHU-38 was unavailable, as there were no engineering drawings found for those units.

Throughout the concourses, there are thirty-three FCUs ranging in sizes of 800 cfm to 1600 cfm, with either 2- 1/6 Hp, 1/3 Hp, or 1/2 Hp motors. Also included in the spaces are a variety of terminal boxes in the spaces. They range from pneumatic operated hot duct/cold duct mixing boxes, air volume fan boxes with electric heat and recirculated air, cold duct variable air volume boxes, and electronic operated hot duct/cold duct mixing boxes.

There are two 1-1/2 HP, 16,900 cfm exhaust fans located in the penthouse which draw warm air from the top of the atrium in the Main Terminal. There are two 15-HP, 39,250 cfm exhaust fans located in the crawl space of the basement. These basement fans continuously draw the air from the basement baggage tug area preventing buildup of fumes.

There are six exhaust fans associated with kitchen hoods located at The Local @ ORF, Burger King, James River Café, Here's to the Heroes, ORF/MKT, and Back Bay Bistro. Their sizes range from 1540 cfm to 12,000 cfm, 1 Hp to 5 Hp. The Local @ ORF has the largest fan at 12,000 cfm, 5 Hp.

Other exhaust fans serve the restrooms, mechanical rooms, and common areas in the Main Terminal.

**Table 1-2 – Main Terminal AHUs**

| Item | Area Served | Total CFM | OA CFM | Fan HP |
|---|---|---|---|---|
| AHU-01 | BASEMENT / 1ST FL DEPARTURE SOUTH (Southwest & United) | 38,100 | 6,500 | 50 |
| AHU-02 | BASEMENT / 1ST FL DEPARTURE NORTH (Delta & Frontier) | 33,560 | 5,280 | 50 |
| AHU-03 | BASEMENT / 1ST FLOOR | 13,200 | 3,320 | 25 |
| AHU-04 | 2ND FLOOR / COMMON AREAS - SOUTH | 18,000 | 2,700 | 10 |
| AHU-05 | 2ND FLOOR/AIRPORT OFFICES/BURGER KING | 14,855 | 2,775 | 7.5 |
| AHU-06 | 2ND FLOOR - FINANCE OFFICES/CONFERENCE ROOMS/INFORMATION | 38,200 | 4,900 | 60 |
| AHU-07 | 2ND FLOOR / COMMON AREAS - NORTH | 21,600 | 3,125 | 10 |
| AHU-08 | STARBUCKS AREA | 7,100 | 2,000 | 7.5 |
| AHU-09 | MUA – KITCHEN OF RESTAURANT | 10,200 | 10,200 | 7.5 |
| AHU-10 | THE LOCAL @ ORF | 13,680 | 3,500 | 10 |
| AHU-37 | BRIDGE AREA – CLOSEST TO MAIN TERM | 12,300 | 1,500 | 15 |
| AHU-39 | ATRIUM AREA – NORTH | 8,375 | - | 10 |
| AHU-40 | ATRIUM AREA - SOUTH | 8,375 | - | 10 |
| HV-1 | TUG BAY | 26,555 | 26,555 | 5 |
| HV-2 | TUG BAY | 26,555 | 26,555 | 5 |
| HV-3 | CENTRAL PLANT | 22,000 | 22,000 | 7.5 |

Source: CHA, 2019.

**Table 1-3 – Concourse A AHUs**

| Item | Area Served | Total CFM | OA CFM | Fan HP |
|---|---|---|---|---|
| AHU-11 | 1ST/2ND FL -ELEVATOR & W/M ROOMS NEAR GATE A2 | 18,990 | 6,000 | 30 |
| AHU-12 | GATES A3, A4, A5 | 20,305 | 6,000 | 30 |
| AHU-13 | GATES A6, A8, A9, A11 | 19,895 | 6,000 | 30 |
| AHU-25 | 1ST FL – TSA HOLDING AREAS | N/A | N/A | N/A |
| AHU-38 | F.I.S. AREA | N/A | N/A | N/A |
| RTU-1A | TSA | 9,500 | 2,000 | 20 |

Source: CHA, 2019.

### Table 1-4 – Concourse A FCUs

| Item | Area Served | Total CFM | Fan HP |
|---|---|---|---|
| FCU-A01 | Waiting Area between Gates A6 & A8 | 1,600 | Two - 1/6 |
| FCU-A02 | Waiting Area between Gates A6 & A8 | 1,600 | Two - 1/6 |
| FCU-A03 | Waiting Area between Gates A6 & A8 | 1,600 | Two - 1/6 |
| FCU-A04 | Corridor by Gate A8 | 1,600 | Two - 1/6 |
| FCU-A05 | Corridor by stairs to Gate A11 | 1,600 | Two - 1/6 |
| FCU-A06 | Waiting Area between Gates A9 & A11 | 1,600 | Two - 1/6 |
| FCU-A07 | Waiting Area between Gates A9 & A11 | 1,600 | Two - 1/6 |
| FCU-A08 | Waiting Area between Gates A9 & A11 | 1,600 | Two - 1/6 |
| FCU-A09 | Corridor between Gates A9 & A6 | 1,600 | Two - 1/6 |
| FCU-A10 | Corridor between Starbucks and Gate A9 | 1,600 | Two - 1/6 |
| FCU-A11 | Corridor by Starbucks | 1,600 | Two - 1/6 |
| FCU-A12 | Corridor between James River Grill and Gate A7 | 1,600 | Two - 1/6 |
| FCU-A13 | Corridor between Hudson News and Gate A4 | 1,600 | Two - 1/6 |
| FCU-A14 | Corridor between Tech on The Go and Gate A5 | 1,600 | Two - 1/6 |
| FCU-A15 | Corridor by Men's Room | 1,600 | Two - 1/6 |
| FCU-A16 | Corridor between Women's Room and Gate A3 | 1,600 | Two - 1/6 |
| FCU-A17 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A18 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A20 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A21 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A22 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A23 | Corridor from TSA to Gate A2 | 1,600 | Two - 1/6 |
| FCU-A25 | Corridor from Main Term to TSA | 1,600 | Two - 1/6 |
| FCU-A26 | Corridor from Main Term to TSA | 1,600 | Two - 1/6 |
| FCU-A27 | Corridor from Main Term to TSA | 1,600 | Two - 1/6 |
| FCU-A28 | Corridor from Main Term to TSA | 1,600 | Two - 1/6 |
| FCU-01A | Women's Restroom near Gate A3 | 1,570 | 1/2 |
| FCU-02A | Men's Restroom near Gate A3 | 1,405 | 1/2 |

Source: CHA, 2019.

### Table 1-5 – Concourse B AHUs

| Item | Area Served | Total CFM | OA CFM | Fan HP |
|---|---|---|---|---|
| AHU-14 | GATES B19, B20 | 12,720 | 2,605 | 25 |
| AHU-16 | GATES B17, B18 | 19,030 | 6,000 | 30 |
| AHU-18 | GATES B21, B23 | 12,320 | 2,250 | 25 |
| AHU-19 | END OF CONCOURSE GATES B27, B28, B29, B30 | 19,680 | 3,600 | 40 |
| AHU-20 | END OF CONCOURSE, GATES B24, B25, B26 | 20,270 | 3,710 | 50 |
| RTU-1 | TSA | 18,530 | 2,445 | 30 |

Source: CHA, 2019.

**Table 1-6 – Concourse B FCUs**

| Item | Area Served | Total CFM | OA CFM | Fan HP |
|---|---|---|---|---|
| FCU-A24 | Hudson News between Gate B17 and B18 | 1,600 | - | Two - 1/6 |
| FCU-B1 | Waiting area near Gate B26 | 800 | - | Two - 1/6 |
| FCU-B2 | Center of waiting area between Gates B26 & B27 | 800 | - | Two - 1/6 |
| FCU-B3 | Waiting area near Gate B27 | 800 | - | Two - 1/6 |
| FCU-B4 | Corridor between Gate B18 & B20 | 1,600 | - | Two - 1/6 |
| FCU-B5 | Corridor in front of Gate B18 | 1,600 | - | Two - 1/6 |
| FCU-B6 | Corridor between Gates B17 & B18 | 1,600 | - | Two - 1/6 |
| FCU-B7 | Corridor between Gates B17 & B18 | 1,600 | - | Two - 1/6 |
| FCU-B8 | Corridor between Gates B16 & B17 | 1,600 | - | Two - 1/6 |
| FCU-01B | Men's Restroom between Gates B18 & B20 | 1,275 | - | 1/2 |
| FCU-02B | Women's Restroom between Gates B18 & B20 | 1,250 | - | 1/2 |

Source: CHA, 2019.

***Controls Systems***

Most of the Main Terminal HVAC controls have direct digital control (DDC). The DDC system is supplied to the site's building management system (BMS), which is managed by Siemens Buildings Technology. There is a mix of pneumatic and electronic actuators for the AHU valves and dampers, as well as for the FCU, mixing boxes, and VAV. The temperature sensors in the spaces control the respective fan coil units, the variable volume (VAV) boxes, the fan-powered terminal boxes, or the mixing boxes.

In the Main Terminal, AHU-1, 2, 6, 39, and 40 have variable speed drives (VSD) on their respective supply fans. In the concourses, AHU-14, 18, 19, 20, 25, 38, RTU-1, and RTU-1A also have VSDs on their supply fans. All other units are constant volume. It appears that all units operate 24 hours per day, 7 days per week, even though the units have been programmed for different mode capabilities. For example, the units could operate in occupied or unoccupied or warmup mode, thereby allowing alternative control for periods of low or no occupancy. Only AHU-1 and 2 supply fans slow their speeds during the unoccupied hours (midnight to 4:00 am) according to staff.

There is an outside air fan that feeds AHU-1, 2, 3 in the basement of the Main Terminal. The outside air fan speed varies with the static pressure downstream of the fan. The Main Terminal units AHU-1, 2, 6, 39, and 40 VSD are possibly controlled by zone temperatures; however, that was not able to be confirmed. HV-1, 2, and 3 operate continuously, have a HW coil, and are controlled by the space temperature.

The concourse constant volume units AHU-11, 12, 13, 16 have a hot deck/cold deck configuration whereby the control valves for the deck coils are modulating to maintain the deck temperature setpoints. The respective terminal units of these AHUs maintain the space conditions.

The concourse units AHU-14, 18, 19, 20, 25, 38, RTU-1 and RTU-1A modulate their supply fan speed from their respective duct static pressures. The HW and CHW coil control valves and dampers modulate in series to maintain discharge air temperature setpoints. AHU-25 has a unique configuration in which there is a face/bypass damper upstream of the preheat coil. There is an economizer mode which allows dampers to open to mechanical "free-cooling" during

certain outside air conditions. The respective terminal units of these AHUs maintain the space conditions.

Some of the FCUs, mixing boxes, fan-powered mixing boxes with reheat coils, and VAV boxes are monitored by the BMS and thereby their temperature output is based on the space temperature. The FCUs nomenclature on the BMS and engineering drawings do not always match; however, the space temperature sensor determines the heating and cooling stages.

The exhaust fans in the penthouse are controlled by a temperature sensor in the high ceiling of the atrium. When the temperature rises, the fans will operate. The exhaust fans in the basement crawl space operate on a lead/lag basis where there is always one fan operating. The kitchen hood exhaust fans, restroom exhaust fans, and other exhaust fans operate continuously as well.

***Domestic Hot Water Systems***

The main domestic hot water for the Main Terminal is produced by two sources. The first source is an indirect domestic hot water heat exchanger that serves an 125-gallon storage tank; this source is utilized in the heating season and is supplied by the main boiler system. The second is a 125-gallon, 491.5 MBH, 144 kW electric DHW heater that is utilized during the cooling seasons while the main boiler system is off. The main domestic hot water services the restrooms throughout the Main Terminal.

Located within some of the vendor food service spaces of the Main Terminal and concourses are electric DHW heaters that vary in size depending on the size and service style of the food service spaces. Within the concourses, there are electric DHW heaters that service the restrooms.

***Electrical Systems***

Throughout the Main Terminal, there are many different electrical loads that consist of objects such as TV monitors, vending machines, baggage conveyors, computers, copiers, 12 elevators, six escalators, and charging stations. The elevators contain motors that range from 20 HP to 50 HP. The escalators are assumed to have 7.5 kW motors.

In the Main Terminal, there are two walk-in refrigerators and one walk-in freezer servicing the two restaurants. Concourse A has one walk-in refrigerator, and Concourse B has two walk-in refrigerators. There are also small enclosed beverage refrigerators in the bars, cold sandwich stations refrigerators in food preparation areas, large upright refrigerators, and no-door refrigerators in the various stores.

There is enough emergency power generation to the Airport to operate in an island mode if needed.

***Lighting***

The lighting throughout the Main Terminal consists of a combination of T-8, CFL and incandescent lighting in the mechanical and private spaces, with a combination of LED, and CFL lighting in the common public spaces and vendor spaces. There is limited control in these spaces with occupancy sensors and photocells in some spaces. The exterior lighting consists of MH and HPS fixtures.

### 1.2.2 Building 5: Arrivals Terminal

***Building Summary***

Norfolk International Airport's (ORF) Arrivals Terminal was originally constructed in 2003. This building is connected to the Main Terminal via a covered passenger bridge and contains the baggage claim, rental car counters, TSA offices, Airport Parking offices, the USO, and attaches to the garages.

***Building Envelope***

The exterior walls have double pane windows and a combination of glass steel frame, solid insulated steel frame and glass automatic sliding doors. The roof is flat with a tar coating and gravel over the top.

***HVAC Systems***

Heating Systems: The Arrivals Terminal is heated by two 8,370 MBH dual fuel natural gas/fuel oil #2 fire tube boiler. This system has an estimated efficiency of 85 percent as indicated from boiler maintenance logs and operates during both the heating and cooling seasons for dehumidification purposes. The boiler primarily utilizes natural gas; however, the facility is currently in a contract with the service provider for a demand reduction program and switches to fuel oil when called upon. The system is served by two 40-HP pumps that operate in lead lag and are not controlled by drives.

These boilers distribute HW to various HW coils located in air handling units (AHUs), make-up air units (MAUs), fan coil units (FCUs), HW unit heaters (UHs), and cabinet unit heaters (CUHs). The HW coil control valves for the AHUs and MUAs are 3-way valves, whereas for any FCU and UH the HW control valves are 2-way control valves.

Cooling Systems: Cooling for the Arrivals Terminal is supplied by two 450-ton water cooled centrifugal Trane chillers that are paired with two Evapco cooling towers located outside the penthouse on the roof and a heat exchanger that is interconnected to the system and can operate during warmer months to provide free cooling via the cooling towers. The cooling towers operate during the cooling season and are drained when the heating season begins. No cooling is provided in the winter months. The CHW is distributed by two pumps that operate in lead-lag fashion. These pumps are 30-HP 1080 gpm each and are not controlled by VSD. The condenser water is pumped by two 40-HP 1350 gpm pumps that operate when their respective cooling tower operates and are not controlled by drives. The third condenser water pump of the same size that serves the heat exchanger condenser water is uncontrolled.

These chillers distribute CHW to various CHW coils located in air handling units (AHUs). The CHW coils are controlled by 3-way valves.

Air-side Systems: The main source of heating and cooling for the Main Terminal facility is a combination of eleven air handling units (AHUs), six fan coil units (FCUs) and six make-up air units (MAUs), various unit heaters, cabinet unit heaters and VAV boxes. The air handling units supply a mixture of return and OA to their respective spaces and VAV boxes. The MUA units supply 100

percent OA to their respective AHUs and provide "heat reclaiming" from the return air. There is one MAU that serves the basement that provides 100 percent outside air across a HW coil and is not a heat reclaiming unit. All the AHUs have a CHW coil. The three AHU that do not have a reclaiming heat MAU have a preheat HW coil. The FCUs condition 100 percent return air and have HW and CHW coils. The AHUs, except AHU-26, 33, and 34, provide air to multiple levels in the building which includes offices in the basement, on the first floor, and the second floor, as well as open areas of the baggage claim carousels. The units vary in size and the primary units can be seen in the table below.

There are ten exhaust fans that serve the restrooms, mechanical rooms, and common areas in the Arrivals Terminal. These exhaust fans range in size of less than 1 HP to ½ HP, 105 cfm to 2720 cfm. There is a supply fan that provides 100 percent outside air, 7150 cfm, 1 HP to the boiler room and operates during boiler operation.

**Table 1-7 – Arrivals Terminal AHUs**

| Item | Area Served | Total CFM | OA CFM | Fan HP |
|---|---|---|---|---|
| AHU-26 | BASEMENT-NORTH | 3,560 | 740 | 7.5 |
| AHU-27 | 1FL/2FL - NORTH, 1FL/2FL - CENTER NORTH | 30,335 | 6,875 | 50 |
| AHU-28 | BSMT/1FL/2FL - CENTER NORTH | 17,900 | 4,360 | 30 |
| AHU-29 | BSMT/1FL/2FL - CENTER | 15,825 | 3,270 | 30 |
| AHU-30 | BSMT/1FL/2FL - CENTER | 15,640 | 3,395 | 25 |
| AHU-31 | BSMT/1FL/2FL - CENTER SOUTH | 14,410 | 3,240 | 25 |
| AHU-32 | 1FL/2FL - CENTER SOUTH, 1FL/2FL - SOUTH | 29,500 | 6,770 | 50 |
| AHU-33 | BASEMENT-SOUTH (TUGBAY) | 7,130 | 860 | 7.5 |
| AHU-34 | BRIDGE - ARRIVAL SIDE | 12,300 | 1,500 | 20 |
| AHU-35 | BSMT/1FL/2FL - CENTER NORTH | 14,000 | 1,400 | 15 |
| AHU-36 | BSMT/1FL/2FL - CENTER SOUTH | 14,000 | 1,400 | 15 |
| FCU-01 | BSMT - CENTER N, 0-222 COMM RM | 400 | - | <1 |
| FCU-02 | BSMT - CENTER, 0-308 COMM RM | 400 | - | <1 |
| FCU-03 | BSMT - CENTER S, 0-417 COMM RM | 400 | - | <1 |
| FCU-04 | PENTHOUSE 2 | 700 | - | <1 |
| FCU-05 | PENTHOUSE 1 | 700 | - | <1 |
| FCU-06 | PENTHOUSE 3 | 700 | - | <1 |
| MAU-1 | BASEMENT - W/AHU-26 | 1,800 | 1,800 | 3 |
| MAU-2 | AHU-27 & AHU-28 HEAT RECOVERY | 48,325 | 48,325 | 50 |
| MAU-3 | AHU-29 HEAT RECOVERY | 15,825 | 15,825 | 25 |
| MAU-4 | AHU-30 HEAT RECOVERY | 15,640 | 15,640 | 25 |
| MAU-5 | AHU-31 HEAT RECOVERY | 14,890 | 14,890 | 20 |
| MAU-6 | AHU-32 HEAT RECOVERY | 29,500 | 29,500 | 30 |

Source: CHA, 2019.

### *Controls Systems*

The Arrivals Terminal HVAC controls are direct digital control (DDC), except for the UH which have local thermostats. The DDC system is supplied to the site's building management system (BMS), which resides in the Main Terminal and is managed by Siemens. The temperature sensors in the spaces control the respective fan coil units and the variable volume boxes with reheat valves.

In the Arrivals Terminal, AHU-27, 28, 29, 30, 31, and 32 have variable speed drives (VSD) on their respective supply fans and return fans, which is controlled by the supply and return duct static pressure, respectively. The return air damper and outside air dampers also modulate to maintain static pressures in the plenum. These units provide cooling and dehumidification control to the space with the 3-way cooling coil control valve. The MAUs "reclaiming" 3-way HW coil control valve modulates with the supply temperature of their respective AHU. The AHUs have economizer modes and night setback temperature setpoints, but the units operate continuously.

AHU-26, 33, 35, and 36 are constant volume. They have a preheated HW coil valve and CHW coil valve, as well as a reheat HW coil valve, modulating to satisfy their respective supply temperature. The AHUs have economizer modes, except for AHU-33 which has its outside air drawn from the tug bay. They have night setback temperature setpoints, but the units operate continuously. The one MAU that does not have a "reclaiming coil" has a HW coil control valve that modulates to maintain the supply temperature with 100 percent outside air.

The VAV boxes throughout the terminal are controlled by the space temperature and will either modulate the airflow of the box or modulate the box reheat valve depending upon the space needs. For the FCUs, the space temperature sensor determines the heating and cooling stages.

***Domestic Hot Water Systems***

The domestic hot water for the Arrivals Terminal is produced by a 100-gallon 250 KBTUH non-condensing natural gas DHW with an 80 percent nameplate efficiency. The domestic hot water services the restrooms throughout the Arrivals Terminal.

***Electrical Systems***

Throughout the Arrivals Terminal there are many different electrical loads that consist of objects such as TV monitors, vending machines, baggage conveyors, computers, copiers, six elevators, two escalators and charging stations. The USO facility has a kitchenette facility which includes refrigerators, microwave, coffee machines and televisions throughout its area. The elevators contain motors that range from 20 HP to 50 HP, while the escalators are assumed to have 7.5 kW motors.

***Lighting***

The lighting throughout the Arrivals Terminal consists of a combination of T-8, CFL, and incandescent lighting in the mechanical and private spaces, with a combination of LED, CFL, T-8 and MH lighting in the common public spaces and vendor spaces. There is limited control in these spaces with occupancy sensors and photocells in some spaces. The exterior lighting consists of MH and HPS fixtures.

### 1.2.3 Building 3: Airfield Lighting Vault (AFLV)

***Building Summary***

The Airfield Lighting Vault is an above ground facility housing regulators, controls, and other equipment necessary to provide power and control for airfield light systems (e.g., approach lighting system, runway, taxiway, and special lighting).

***Building Envelope***

The airfield lighting vault has a CMU construction with no insulation. The facility does not have any exterior windows. The doors are steel frames with double pane glass. The roof is a flat metal with tar coating and minimal insulation.

***HVAC Systems***

There are two five-ton bard wall mounted air condition units with 9 kW electric heaters, a 7.5 kW unit heater, and a single 18,000 BTUH Friedrich wall mounted window air conditioner. There is also a fractional HP wall mounted exhaust fan.

***Controls Systems***

The HVAC consists of controlled non-programmable thermostats.

***Domestic Hot Water Systems***

There is no water used in this facility.

***Electrical Systems***

This vault contains the airfield lighting controls, transformers, and a computer.

***Lighting***

The lighting consists of interior T-8 lighting with LED exterior wall packs. These lights are not controlled.

### 1.2.4 Building 4: Triturator

***Building Summary***

This facility pre-treats the lavatory waste that has been removed from the aircraft for pre-treatment prior to discharge to the sanitary sewage. It also provides a wash facility for the vehicles which deliver the lavatory waste.

***Building Envelope***

The Triturator building has concrete masonry unit (CMU) construction with no insulation, and the building has no exterior windows. The doors are steel frames with double pane glass. The roof is flat metal with tar coating and minimal insulation. There are two overhead doors for vehicle pass-through access.

***HVAC Systems***

There is an electric unit heater in the pit area. There are four infrared electric heaters in the ceiling space above the bay area.

***Controls Systems***

There are standalone thermostats for the infrared heater and the pit area unit heater, respectively. Manual switches provide lighting control.

***Domestic Hot Water Systems***

There is no potable water used in this facility; however, there is an electric 25-gallon hot water heater for the process water.

***Electrical Systems***

There are multiple electric panels servicing the sewage pumps, grinders, air curtain fans, bay door operations, lighting, and ancillary items.

***Lighting***

The interior lighting for the Triturator consists of predominantly T-8 fixtures and are manually controlled. In the basement, there is some explosion-proof fixtures. The exterior lighting consists of wall mounted shoebox HPS fixtures on the building, as well as LED and HPS pole lights that are located at the fuel station next to the Triturator. The exterior fixtures are all controlled by photocell daylight controls.

### 1.2.5 Building 34: Airfield Maintenance Storage (Snow Removal)

***Building Summary***

This facility serves as the sand facility and houses the Airport's maintenance and utility vehicles.

***Building Envelope***

The airfield maintenance storage building has a CMU construction with no insulation, and there are no exterior windows on this facility. The doors are steel frames with double pane glass. The roof is a flat metal with minimal insulation. There are seven large overhead garage doors, as well as four single doors and one double-door for personnel access.

***HVAC Systems***

There are two sets of 125 MBTUH gas-fired infrared heaters in the salt storage area. The other bays have no HVAC systems.

***Controls Systems***

There is a standalone non-programmable thermostat next to the door entrance of the salt storage area.

***Domestic Hot Water Systems***

There is no water used in this facility.

***Electrical Systems***

There are no major electrical systems and no emergency power generation.

***Lighting***

The interior lighting in the facility consists of T-12 fluorescent lighting that is controlled manually by switches. The exterior lighting consists of metal halide wall pack fixtures on photocell daylight controls.

### 1.2.6 Building 6: Aircraft rescue and firefighting (ARFF) Station

***Building Summary***

This building houses the vehicles needed for fire and rescue services during aircraft emergencies. The vehicle areas have high-bay garage areas with bay doors at each end for pass-through vehicle access. In the other areas, there are sleeping quarters for the firefighters, as well as living spaces,

offices, washing facilities, equipment maintenance areas, and kitchen and dining areas. The facility operates 24 hours, 7 days per week year-round and has minimal opportunity for energy savings. The site mechanicals and their operation are controlled and maintained by the stations staff, rather than the Airport Authority.

***Building Envelope***

The ARFF facility has a CMU construction, with the upper section covered with metal and minimal insulation in one-third of the building. The other two-thirds of the building has insulation. The exterior windows are double-pane with aluminum frames, and the doors are steel frames with double pane glass. There are eight large overhead garage doors (four on each side of the building) for vehicle pass-through. The roof is a flat metal with minimal insulation.

***HVAC Systems***

There are four Trane forced air units that supply tempered air to the offices, conference rooms, sleeping areas, and common areas. Each of these units use propane gas for the burners, and each have an associated air-cooled condensing unit for the cooling and dehumidification.

**Table 1-8 – ARFF AHUs**

| Tag | Area Served | Heating Capacity (MBH) | Cooling Capacity (Ton) |
|---|---|---|---|
| AHU-1 / AC-1 | 1ST FLOOR WEST SHOP AREA, OFFICES, DINING AREA | 42 | 3.5 |
| AHU-2 / AC-2 | 2ND FLOOR WEST OFFICES | 60 | 5 |
| AHU-3 / AC-3 | 1ST FLOOR EAST BUNK AREAS | 60 | 2.5 |
| AHU-4 / AC-4 | 2ND FLOOR EAST COMMON AREAS | 30 | 5 |
| MU-1 | KITCHEN | 75 | |

Source: CHA, 2019.

There is one 75-MBH capacity Renzor make-up air unit and a Captive Aire exhaust hood for the kitchen area. The respective exhaust for the kitchen hood is 1 HP for 1800 cfm.

The bay has two 60-foot and two 20-foot infrared ceiling mounted heaters.

There are nine exhaust fans that range in size from ¼ HP to 3 ½ HP, and 180 to 6080 cfm.

***Controls Systems***

A wall-mounted thermostat for either AHU-1 or MU-1 could not be found. It is probably that the units are set internally at a specific temperature setpoint. There are two non-programmable wall-mounted thermostats for the infrared heaters.

There are also standalone programmable thermostats for the other AHU's. The change from cooling and heating is done manually. Siemens BMS is monitoring AHU-3 only.

***Domestic Hot Water Systems***

Domestic hot water for the ARFF facility is provided by a 200-gallon domestic hot water tank in the east mechanical room. The Teledyne Laars 250 MBH hot water boiler supplies the domestic hot water to the 150-gallon storage tank and serves the kitchen, showers, and sinks.

***Electrical Systems***

There is an emergency power generator, but no additional information was available. The plug load is consistent with computers, monitors, clothes washer and dryer. There are other firefighter equipment maintenance items, such as an air compressor and breathing apparatus devices, which use electricity.

***Lighting***

The majority of fixtures in this facility contain T-8 fluorescent lighting. These fixtures are manually controlled and appear to be turned off when rooms are unoccupied, or lighting is not needed. There are also various CFL lamps used in storage spaces controlled in the same manor. The exterior lighting for the facility consists of MH wall pack fixtures mounted to the facilities.

### 1.2.7 Building 17: Ground Run-Up Enclosure (GRE)

***Building Summary***

Airlines are required to inspect and maintain their aircrafts. The GRE is an airplane testing facility for small to midsize airplanes to prevent sound disturbance to the surrounding areas.

***Building Envelope***

There is a single metal insulated building with a small window to view the testing and an insulated steel door. The roof is a flat metal and insulated as well.

***HVAC Systems***

The test facility building has a 9 MBH mini-split system used for cooling and an electric wall heater for heating.

***Controls Systems***

The heating and cooling systems are controlled by in-unit thermostats that are non-programmable.

***Domestic Hot Water Systems***

There are no DHW systems in this facility.

***Electrical Systems***

There are no major electrical systems in the test facility.

***Lighting***

The interior lighting consists of T-8 fixtures that are manually controlled by switches. The exterior lighting consists of MH lighting fixtures that are on photocells with two fixtures are emergency lighting and on 24/7.

### 1.2.8 Building 27: Airfield Maintenance Facility

***Building Summary***

The maintenance facility houses the Airport's snow removal equipment, as well as an area for maintenance conducted on the Airport's vehicles and a storage facility for abandoned vehicles found in the site parking lots or garages.

***Building Envelope***

The Airfield Maintenance Facility has a CMU construction with the upper section covered with metal and minimal insulation in the garage space of the building. The remainder of the building is assumed to have insulation in the office areas. The exterior windows are double paned with aluminum frames. The doors are steel frames with double pane glass. There are three bay doors and several roll-up doors. The roof is a flat metal with minimal insulation.

***HVAC Systems***

The hot water coils in the ductwork are heated by a Laars Neotherm condensing boiler. The size of the boiler is unknown, as it was being installed at the time of the survey. AHU-1 serves the kitchen and locker room areas with a Carrier 6-ton D/X packaged unit. AHU-2 serves the office area with a Carrier 7-ton D/X packaged unit. There is one Renoir heating ventilation unit that services the storage area as shown as the welding room in the drawings.

There are sixteen exhaust fans that range in sizes of fractional Hp to 1 ½ Hp, 100 to 8500 cfm. There are twelve Modine gas unit ventilators surrounding the open garage areas and one in the generator room. In the garage areas, there are infrared heaters in the ceiling of the high bays of the facility.

***Controls Systems***

Programmable thermostats control the air handling units. There are also programmable thermostats for the interlocking unit heaters and infrared heaters. The facility has non-programmable thermostats for those unit heaters not interlocked with exhaust fans and infrared heaters.

Light switches control the small exhaust fans in the restrooms, locker room, shower room, and kitchen. The exhaust fan in the generator room is interlocked with the air intake damper. The exhaust fans in the repair bay are controlled by their respective thermostat. The exhaust fan in the welding room / storage room is interlocked with the wall-switch. The eight exhaust fans in the vehicle storage area are interlocked with the intake and exhaust dampers. The associated unit ventilators with the vehicle bay exhaust fans are also tied with the intake and exhaust dampers, turning off when the dampers open.

***Domestic Hot Water Systems***

The domestic hot water is provided by a State Proline gas-fired, 50-gallon, 50 MBH water heater.

***Electrical Systems***

There is no emergency power system in this facility. Plug loads are consistent with this facility type and include power tools, computers, vending machines, and small kitchen appliances.

***Lighting***

The interior lighting consists mainly of T-12, T-8 and MH fixtures that are manually controlled by the staff. The exterior lights consist of MH and HPS fixtures that are on photocell daylight sensors.

### 1.2.9 Building 12: TNC Staging

***Building Summary***

The TNC staging area during the first site visit was utilized as the rental car return facility. This facility housed the site rental car return. During the second site visit, the facility was no longer serving this function, and its future plans are unknown. All measures proposed for this facility are based off an assumed similar operation to when it was a rental car return facility.

***Building Envelope***

The TNC Staging is assumed to have a CMU construction with insulation, framing in office spaces and dry wall. The exterior windows are double paned with aluminum frames. The doors are steel frames with double pane glass. The roof is pitched with insulations and an asphalt shingle exterior covering.

***HVAC Systems***

Heating Systems: The TNC Staging is heated by a Parker 490 MBH natural gas boiler installed in 1999. This system has a nameplate efficiency of 80 percent. The system is distributed to a HW coil by a fractional horsepower pump.

Cooling Systems: Cooling for the TNC Staging is supplied by a Carrier 12.8-ton air cooled condensing unit. The CHW is distributed to a cooling coil by a fractional horsepower pump.

***Controls Systems***

The HVAC is controlled by non-programmable thermostats.

***Domestic Hot Water Systems***

The domestic hot water is supplied by a 33,500 BTUH natural gas boiler with a 30-gallon storage capacity. The water is distributed to the facility restroom sinks by a fractional horsepower pump.

***Electrical Systems***

There are three vending machines that are uncontrolled in the TNC building.

***Lighting***

The interior lighting for this facility consists mostly of CFL and T-8 fixtures. These fixtures are manually controlled by the staff. The exterior lighting consists of MH and HPS fixtures that are controlled by photocell daylight sensors.

### 1.2.10 Building 2: Automobile Parking Garage

***Building Summary***

The automobile parking garages contain short-term parking and long-term parking, as well as the rental car pick-up and new rental car return facilities. The three garages (Garages A, B and C) are attached to the Arrivals Terminal.

***Building Envelope***

There are three parking garages that service the ORF airport: Garage A, Garage B, and Garage C. Garage A is the newest of the three facilities and has nine floors. Garages B and C each have five floors. All the garages are typical concrete construction and are attached to the Arrivals Terminal.

***HVAC Systems***

There are no HVAC systems in the garages.

***Controls Systems***

There are no controls systems in the garages.

***Domestic Hot Water Systems***

There are no domestic hot water systems in the garages.

***Electrical Systems***

The only non-lighting electrical systems in the garages is one elevator mechanical room with three elevator motors located in Garage B and the security gates at the entrances and exists to the garages.

***Lighting***

The lighting in the garage spaces consists predominantly of MH and HPS ceiling-mounted fixtures. In Garage A, there are some photocell controls located on the perimeter fixtures. The remainder of the fixtures operate 24 hours, seven days a week, for 356 days a year. There are various T-8 fixtures located near side entrances that are also 24/7.

### 1.2.11 Building 8 and 9: Air Cargo Buildings (UPS & Fedex)

***Building Summary***

The air cargo buildings are leased spaces that are operated and maintained by UPS and FedEx. Due to limited access to the buildings, there is little information available for review.

***Building Envelope***

N/A

***HVAC Systems***

N/A

***Controls Systems***

N/A

***Domestic Hot Water Systems***

N/A

***Electrical Systems***

N/A

***Lighting***
Due to limited access, only a portion of the air cargo buildings was reviewed for lighting. The consensus was that the facilities consist of predominantly T-8 lighting fixtures with minimal use of occupancy controls.

### 1.2.12 Building 36: Short-Term Parking Lot

***Building Summary***
This an open-air, surface parking lot.

***Building Envelope***
There is no building within the short-term parking lot.

***HVAC Systems***
There are no HVAC systems.

***Controls Systems***
The exterior lighting is controlled by photocells.

***Domestic Hot Water Systems***
There is no DHW systems.

***Electrical Systems***
There are no major electrical systems pertaining to the short-term parking lot.

***Lighting***
The lighting is a combination of various MH and HPS poles.

### 1.2.13 Building 35: Long-Term Parking Lot

***Building Summary***
This an open-air, surface parking lot. The majority of lighting is operated and maintained by the electrical utility provider, Dominion Power. The lighting calculation for this site accounts for a possible transfer of ownership of these fixtures.

***Building Envelope***
There is no building within the long-term parking lot.

***HVAC Systems***
There are no HVAC systems.

***Controls Systems***
The lighting is controlled by photocells.

***Domestic Hot Water Systems***
There is no DHW systems.

***Electrical Systems***
There are no major electrical systems.

***Lighting***
The lighting is a combination of various MH and HPS poles, with some of these poles being owned and operated by Dominion power.

### 1.2.14 Building 15: Fuel Farm

***Building Envelope***
The fuel farm facility does not have a main building; however, there is a small security post and four large fuel tanks.

***Building Envelope***
The small guard post is assumed to be an aluminum frame structure with insulated panels and single pane windows. The roof is flat with minimal insulation.

***HVAC Systems***
On the roof of the security post, there is an electrical heating and cooling unit.

***Controls Systems***
The security post's HVAC system has an internal thermostat that is manually controlled.

***Domestic Hot Water Systems***
There is no domestic hot water.

***Electrical Systems***
There is a security gate that is used for access to and egress from the fuel farm.

***Lighting***
The lighting consists of MH pole lights of various size and a single T-8 lighting fixture that is manually controlled.

### 1.2.15 Building 7: ARFF Storage building

***Building Summary***
This building houses the marine rescue vehicles for the Airport. Like the main ARFF facility, this location is maintained and operated by the fire station staff.

***Building Envelope***
The ARFF storage building has a CMU construction with the upper section covered with metal and minimal to no insulation. The exterior windows are double paned with aluminum frames. The doors are steel frames with double pane glass; there are also two large overhead garage doors. The roof is a flat metal with minimal insulation.

***HVAC Systems***
The only HVAC systems in the garage are two gas fired infrared heaters that are manually controlled by a non-programmable thermostat.

***Controls Systems***
There are no universal controls systems at this facility.

***Domestic Hot Water Systems***

The building does not use DHW.

***Electrical Systems***

There are no major electrical systems in the facility.

***Lighting***

The lighting consists of MH fixtures both internal and external that are manually controlled.

# 2 ENERGY CONSERVATION

## 2.1 ENERGY CONSERVATION MEASURES

The energy conservation measures (ECMs) listed in this Chapter are potential improvements to the building envelopes, HVAC systems, controls, domestic hot water heaters and lighting, that, if implemented, will result in thermal and/or electrical savings. First, annual utility consumption values were generated utilizing end user energy consumption data. The utility information was then used in conjunction with known equipment and systems information to provide ECM calculations. In certain instances, industry benchmarking standards and building square footages were used as the basis for assumptions made in a calculation. The percentages could be used to allocate electricity usage for the different energy consuming functions in a building where equipment/system information was not available. Energy conservation opportunities (ECOs) are opportunities to reduce energy costs but are difficult to quantify actual energy savings. ECOs often require a more detailed analysis outside the scope of this Study, or a specialized vendor to determine possible installation costs.

Energy savings are calculated using estimated operating efficiencies, hours, ASHRAE data, DOE data and engineering judgment. Cost estimates are developed using RS Means 2018, vendor quotations and/or engineering judgment. These are not investment grade-level estimates and provide order of magnitude cost and saving estimates only. Should these ECMs be considered for implementation, a more detailed analysis is recommended to further evaluate savings and return on investment.

See **Section 2.3.2** for a summary of payback, cost and energy savings and **Appendix C** for the full calculation and cost breakdown pertaining to each building discussed in the subsequent sections.

### 2.1.1 Building Envelope ECMs

***BE-1: Window Replacements***

Many of the buildings have windows from original construction. The Main Terminal has windows with single glazing and aluminum frames. Single pane windows have poor thermal resistance and seals around the window frames can deteriorate and allow for outdoor air infiltration. This additional heat transfer results in an increased building load during the heating and cooling seasons. Infiltration will cause increased operation of the heating and cooling systems, and thus, unnecessary energy consumption. This ECM evaluates replacing single pane glazing with upgraded energy efficient windows with double pane glazing. All windows in the Main Terminal and Concourses A and B are proposed to be replaced. See **Table 2-1** for the building under consideration for this measure.

**Table 2-1 – Window Replacement**

| Building | Window Area (SQFT) | Window Glass Type | Window Frame |
|---|---|---|---|
| Main Terminal | 27,220 | Single Pane | Aluminum |

Source: CHA, 2019.

This measure is not recommended, as its payback exceeds 15 years. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***BE-2: Door Sweep and Seal Replacements***

During the site walkthroughs, the conditions of the exterior doors sweeps and seals were reviewed, forming a comprehensive list of all locations that were either deteriorating or nonexistent. When these seals are missing or in poor condition this can lead to infiltration of unconditioned air or exfiltration of conditioned air depending on the building's pressurization, thus leading to excess heating or cooling and an overall increase in energy consumption. The majority of the commonly used exterior doors are automatic sliding doors with high usage. New sweeps and seals can be installed at a low cost without replacing the existing doors. **Table 2-2** for buildings under consideration for this measure.

**Table 2-2 – Door Sweeps and Seals Replacements**

| Building | Door Count |
|---|---|
| Main Terminal | 10 |
| Arrivals Terminal | 17 |
| Old Rental Car Return | 1 |

Source: CHA, 2019.

This measure is recommended for door sweeps and seals in poor condition in all buildings listed in the table above. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown. If this measure is implemented, a detailed map of door locations can be provided upon request.

***BE-3: White Roof Covering***

The majority of the Main Terminal roof appears to be original to the facility and is assumed to be composed of minimal insulation, a tar coating, and a rock covering. The remainder of the roof was installed during the Concourse A and B renovations during 1989, 2012 and 2014; these roofing sections are assumed to have increased insulation and have a white rubber membrane coating. The original coating is of a darker shading and can be more susceptible to absorbing solar load and does not reflect UV rays. This results in an increased cooling load during the summer months and an overall increased energy consumption. White roof coatings have the ability to reflect UV rays and are proven to lower overall energy cost during cooling seasons. See **Table 2-3** for the building under consideration for this measure.

**Table 2-3 – White Roof Covering**

| Building | Roof (SQFT) |
|---|---|
| Main/Arrivals Terminal | 258,735 |

Source: CHA, 2019.

While this measure was considered, it does not have an attractive payback and, thus is not recommended. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation, cost breakdown and aerial view of roof areas to be replaced.

***BE-4: Window Shading***

Currently, the ORF facility has many windows that receive sunlight throughout the day. During the cooling seasons a noticeable temperature difference can be felt in the spaces of these windows. By installing operable window shadings in these spaces, energy savings and increased comfort can be obtained. Adding operable coverings allows the site to take advantage of solar heat gain in the heating season while reflecting the heat gain in the cooling season to reduce cooling energy usage. This measure proposes installing window shading on all windows facing the southern and eastern direction in the Main Terminal and Concourses. See **Table 2-4** for the building under consideration for this measure.

**Table 2-4 – Window Shading**

| Building | Window Area (SQFT) |
|---|---|
| Main Terminal | 12,922 |

Source: CHA, 2019.

While this measure was considered, it does not have an attractive payback and, thus, is not recommended. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

### 2.1.2 Mechanical Equipment ECMs

***M-1: Boiler Replacements***

The Airport has multiple hot water boilers serving the heating systems at the various facilities. The older boilers have maximum nameplate efficiencies of 83 percent, operating seasonally at typically lower efficiencies than nameplate.

The proposed condensing boiler replacements have peak efficiencies into the mid-90 percent range, and average seasonal efficiencies of 89 percent based on manufacturer's specification data and site operation conditions. Condensing boilers operate through a greater range of water temperatures and firing rates (turn-down), essentially matching the boiler load more precisely to the building load. The implementation of the new condensing boilers would also involve rebalancing the heating hot water piping system, reprogramming boiler controls, and new flue piping. It is proposed to replace only one boiler from the Main Terminal and the Arrivals Terminal with two smaller capacity condensing natural gas boilers. See **Table 2-5** for buildings under consideration for this measure.

**Table 2-5 – Boiler Replacements Information**

| Building | Existing Boiler Count | Existing Heating Output (MBH Per Boiler) | Existing Average Boiler Efficiency | Proposed Boiler Count | Proposed Heating Output (MBH Per Boiler) | Proposed Average Boiler Efficiency |
|---|---|---|---|---|---|---|
| Main Terminal | 2 | 8,639 | 82% | 2 | 6,000/2,500 | 89.3% |
| Arrivals Terminal | 2 | 6,695 | 83% | 2 | 6,000/1,500 | 90% |
| TNC Staging Area | 1 | 392 | 80% | 1 | 750 | 91% |

Source: CHA, 2019.

While this measure was considered for all facilities listed above, none of the facilities have an attractive payback; therefore, the measure is not recommended. The cost of installation versus the cost of operation and the potential energy savings does not make for an attractive project in any of the buildings. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-2: AHU Motor Upgrades***

Existing motors on some of the air handling unit fans are aging and have a lower efficiency compared to newer motors. Many newer, premium efficiency motors have a nominal efficiency of at least 90 percent. Significant energy savings are possible by replacing aging motors with premium efficiency motors. This measure considers the runtime of electric motors in fan and pump applications based on the approximate annual runtime hours of heating and cooling systems. See **Table 2-6** for the building under consideration for this measure.

**Table 2-6 – AHU Motor Upgrades**

| Building | Motor Count | Typical Motor Size (HP) | Considered (DWG #) |
|---|---|---|---|
| Main Terminal | 3 | 7.5, 15 | AHU 7,8 and Tunnel Exhaust 2 |

Source: CHA, 2019.

While more AHU and exhaust fans were considered for this measure, none except the equipment in the table above had an attractive payback; therefore, only the equipment in the table above is recommended to be replaced. See **Section 2.3.2** for a listing of the specific motor efficiencies for each AHU as well as a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-3: AHU Fan Variable Speed Drives (VSD)***

Several AHUs supply constant volume tempered air to the spaces they serve; however, it is possible to vary fan speed, allowing the fan to slow down at times and save energy. To do this, the fan motor typically needs to be replaced with an inverter-duty rated motor. Fan speed would be permitted to vary in order to meet system static pressure setpoint for AHU's 11, 12, 13, 16, 34, 37, 3, 4, 5, 7, 8, and 10. For AHU 37's supply and exhaust fan, fan speed will be permitted to vary based on OAT as it varies between design heating load and building balance point. See **Table 2-7** for the building under consideration for this measure:

**Table 2-7 – AHU Fan Variable Speed Drives (VSD)**

| Building | VSD Count | Typical Motor Size (HP) |
|---|---|---|
| Main Terminal | 14 | 7.5, 10, 15, 20, 25, 30 |

Source: CHA, 2019.

This measure is recommended as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-4: Window AC Replacement***

ORF has residential style window air conditioning units at various facilities throughout the site. The existing systems are aging and could be upgraded to higher efficiency units. Energy savings result from an increased EER efficiency, thus reducing overall electrical energy consumption. As shown in the **Table 2-8** below, the main unit considered was the window air conditioner at the airfield lighting vault.

**Table 2-8 – Window AC Replacement**

| Building | AC Count | Existing Efficiency (EER) | Proposed Efficiency (EER) |
|---|---|---|---|
| Airfield Lighting Vault | 1 | 11.7 | 13.3 |

Source: CHA, 2019.

While this measure was considered, it does not have an attractive payback and, thus, is not recommended. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-5: Destratification Fans***

Due to the of the configuration of the HVAC system in the Arrivals building baggage claim elevated ceiling area, the temperature on the lower levels may feel cold during the heating months due to warm air rising to the top of the room. Installing destratification ceiling fans will help to mitigate air stratification by pushing heated air down to ground level. This will increase occupant comfort and reduce the heating loads in the space, resulting in a savings of both electricity and natural gas. See **Table 2-9** for the building under consideration for this measure..

**Table 2-9 – Destratification Fan**

| Building | Fan Count (Added to Bldg) | Fan Motor Size (kW) |
|---|---|---|
| Arrivals Terminal | 50 | 35 |

Source: CHA, 2019.

This measure is recommended as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-6: Chilled Water (CHW) and Hot Water (HW) Pump Variable Speed Drives (VSD)***

The existing CHW and HW pumps are constant speed. This measure proposes adding differential pressure controlled VSDs on P-1 and P-2 (serving HHW), and P-3 and P-4 (serving CHW) in the Arrivals Terminal. By implementing this measure, the drives will slow the motors down to meet a differential pressure setpoint in the supply and return distribution header piping. This will allow the pumps to slow down when the heating or cooling demand is at a reduced state.

To implement this measure, the existing pumps are assumed to have non-inverter duty motors and will need to be replaced by premium efficiency inverter duty motors. Both pumps in each case would receive VFDs. If the motors are inverter duty premium efficiency motors, then the

project cost could decrease. See **Table 2-10** below for the building under consideration for this measure.

**Table 2-10 – Pump Variable Speed Drives**

| Building | VFD Count | Motor Size (HP) |
|---|---|---|
| Arrivals Terminal | 4 | 30, 40 |

Source: CHA, 2019.

This measure is recommended as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-7: Duct Sealing***

During the site walkthrough, it was observed that in mechanical spaces where older AHUs and ductwork were still utilized, there was significant air leakage. When conditioned air is leaking from ductwork, it is essentially conditioning unconditioned spaces, which can cause an increase in overall energy consumption of the facility. This also affects the conditioned spaces served by the leaking ductwork by reducing the airflow to these locations and ,at times starving the system and increasing the time required for the end site to meet its requested condition, or in serious cases not allowing the system to meet the requested setpoint. By sealing the air leaks in the air handling units and their ductwork, energy savings and increased comfort can be found. The measure was considered for AHU 16, 18, 19, and 20 in concourse B and AHU 11 in concourse A.

**Table 2-11 – Duct Sealing**

| Building | AHU Count | Existing Air Flow (CFM) | Existing Air Leakage (CFM) | Proposed Air Leakage (CFM) |
|---|---|---|---|---|
| Main Terminal | 5 | 90,290 | 1354 | 903 |

Source: CHA, 2019.

While this measure was considered, it does not have an attractive payback and therefore is not recommended. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-8: Mini-Split System Upgrade***

The Airport uses DX ductless mini-split cooling systems at various facilities throughout the airport. The existing systems are approaching or have passed their useful lives. By replacing these older units with newer high efficiency models, energy savings can be found. Energy savings result from an increased EER and HSPF efficiency, thus reducing overall electrical energy consumption. See **Table 2-12** below for the building under consideration for this measure.

**Table 2-12 – Mini-Split System Upgrade**

| Building | Unit Count | Existing Efficiency (EER/HSPF) | Proposed Efficiency (EER/HSPF) |
|---|---|---|---|
| Ground Run-Up Enclosure (GRE) | 1 | 13/8.2 | 13.3/10.8 |

Source: CHA, 2019.

While this measure was considered, it does not have an attractive payback and, thus, is not recommended. In this case, the difference in efficiencies between existing and proposed was

not high enough to justify the cost of replacement. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-9: Elevator Motor Upgrades***

There are multiple elevator mechanical rooms within the ORF facilities that contain elevator mechanical components. The elevators motors in these rooms vary from 20 HP to 50 HP with efficiencies as low as 77% NEMA. The remaining four (4) elevators contain 25 HP motors with a 72% NEMA efficiency. This ECM proposes replacing the existing elevator motors with higher NEMA efficiency motors.

The savings for this measure is the result of the motors' increased efficiency. It is assumed that all operation of the elevators will remain the same as before the change. See **Table 2-13** for buildings under consideration for this measure.

**Table 2-13 – Elevator Motor Upgrades**

| Building | Elevator Count |
|---|---|
| Arrivals Terminal | 6 |
| Main Terminal | 12 |

Source: CHA, 2019.

For the Arrivals building, elevators 12, 13, 14, 15, 17, and 18 were considered for this measure. The payback is attractive; therefore, it is recommended to implement this measure for these elevators. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

For the Main Terminal, elevators 1 through 11 and 16 were considered; however, only elevators 1, 3,4, 5, 8, 9, and 10 were found to have higher efficiency motors than existing available. The payback is attractive for the elevators considered; therefore, it is recommended to implement this measure for those motors. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***M-10: Escalator Controls***

The Airport contains many escalators. With the exception of the escalators in the customs area, the escalators in the facility run continuously at constant speed regardless if passengers are or are not present. This ECM proposes installing sensors, drives, and controls that will allow for the escalators to be slowed and possibly shut off during extended periods of non-use.

Energy savings for this measure are generated from the reduction in kW of the motors during slowed and stopped periods. This calculation is based on statistical studies for similar operations. See **Table 2-14** below for buildings under consideration for this measure.

**Table 2-14 – Escalator Controls**

| Building | Escalator Count |
|---|---|
| Arrivals Terminal | 2 |
| Main Terminal | 4 |

Source: CHA, 2019.

All escalators in both the Arrivals and Main Terminal were considered for this measure, except for the ones located in customs as they are shutdown when not in limited use. This measure was found to not have an attractive payback for either facility; therefore, this measure is not recommended to be implemented. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

### 2.1.3 Domestic Hot Water ECMs

***DHW-1: Domestic Hot Water Fuel Conversion***

Many domestic water heaters throughout ORF are electric tank type water heaters which require a substantial amount of electricity for operation. These tanks also incur a standby loss on unused water in the tank. Converting these existing electric water heaters to high efficiency gas-fired condensing water heaters will result in significant cost savings. To implement this measure, modification of electrical wiring and installation of natural gas piping is necessary. See **Table 2-15** for the building under consideration for this measure.

**Table 2-15 – DHW Fuel Conversion**

| Building | # Tank / Sizes | Existing Fuel Source | Proposed Fuel Source |
|---|---|---|---|
| Main Terminal | 2 -120 Gallon / 4 - 50 Gallon / 2 – 38 Gallon / 1 – 125 Gallon | Electric | Natural Gas |

Source: CHA, 2019.

For the Main Terminal, all DHW heaters located in the food service vendor spaces and the main DHW heater for the facilities cooling season were considered. This measure is recommended as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***DHW-2: Domestic Hot Water Condensing Water Heaters***

The remaining domestic water heaters at the Airport are natural gas tank style water heaters. These water heaters are noncondensing and have efficiencies in the 80 percent range. By replacing these water heaters with high efficiency gas fired condensing water heaters, their efficiencies can be boosted into the mid 90 percent range. This increase in efficiency will result in energy and cost savings. This measure typically requires modifications to electrical control wiring and installation of a condensing water heater; however, if the boilers in the main mechanical spaces are converted to condensing units, they can be utilized with indirect water heaters to reduce the overall cost of the project. See **Table 2-16** for buildings under consideration for this measure.

**Table 2-16 – Natural Gas DHW Upgrade**

| Building | Unit Count | Tank Size (Gal) | Existing Efficiency | Proposed Efficiency |
|---|---|---|---|---|
| Main Terminal | 1 | 125 | 83% | 92% |
| Arrivals Terminal | 1 | 100 | 80% | 92% |
| TNC Staging | 1 | 30 | 80% | 92% |

Source: CHA, 2019.

For the Main Terminal, Arrivals Terminal, and TNC Staging area, the main DHW heaters located in the mechanical spaces were considered. This measure is recommended for only the TNC

staging area and Main Terminal, as they have an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

### 2.1.4 Kitchen ECMs

***K-1: Kitchen Hood Upgrades***

The exhaust systems in the kitchen hoods are at a constant speed. Upgrading the current system will vary the amount of exhaust air volume, based on the heat and smoke load coming off the kitchen equipment. Upon activation of the system, the hood lights will turn on and the fans would reach a preset minimum speed of approximately 50 percent. When cooking appliances are turned on and heat is generated, the fan speed will increase based on the temperature sensed in the exhaust duct. During actual cooking, an optical sensor will sense particles entering the hood and will increase up to 100 percent speed until the smoke and heat are removed.

Depending upon the current kitchen hood system, a new system will include installing the kitchen hood control system, a NEMA premium efficiency motor for the exhaust fan, a NEMA premium efficiency motor for makeup air unit, variable frequency drives (VFDs) for both exhaust fan and makeup air fan motors, and sensors. If a kitchen hood control system is present (e.g., CaptiveAire), then all that would be required for installation are the VFDs, sensors, and programming. Due to the low hours of operations at the Fire House kitchen hood, this ECM was not considered.

The resultant energy savings are electrical and gas from the fan motor speed reduction and make-up air reduction, respectively. See **Table 2-17** for buildings under consideration for this measure.

**Table 2-17 – Kitchen Hood Upgrades**

| Building | # Hoods |
|---|---|
| Main Terminal | 5 |

Source: CHA, 2019.

For the Main Terminal, all kitchen hoods located in the food service vendor spaces were considered. This measure is recommended, as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***K-2: Walk-In Freezer and Cooler Controls***

The addition of cooler or freezer controls reduces energy consumption by using the dewpoint temperature for control. Compressor cycling is reduced, and the evaporator fans run 25 percent to 80 percent less. Door and frame heaters are also installed and controlled by dew point temperature. This can reduce run time by up to 95 percent in coolers and 60 percent in freezers. The evaporator fan motors are also replaced with hi-efficiency fan motors, saving 40 percent to 70 percent in energy. The proposed system is comprised of an anti-sweat door controller, evaporator fan motor replacement, and a cooler control system. See **Table 2-18** for buildings under consideration for this measure.

**Table 2-18 – Walk-In Freezer and Cooler Controls**

| Building | Freezer Count | Refrigerator Count |
|---|---|---|
| Main Terminal | 1 | 5 |

Source: CHA, 2019.

For the Main Terminal all walk-in freezers and coolers located in the food service vendor spaces were considered. This measure is recommended as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***K-3: Vending Miser***

The ORF facilities have various vending machines located throughout. The vending machines operate 24 hours, seven days a week, regardless of the actual usage or occupancy near the machines. This measure proposes installing vending machine controls to reduce the total run time of these units. The result is a reduction in total electrical energy usage. See **Table 2-19** for buildings under consideration for this measure:

**Table 2-19 – Vending Miser**

| Building | Vending Machine Count |
|---|---|
| Main Terminal | 4 |
| TNC Staging | 3 |

Source: CHA, 2019.

For the Main Terminal, only the vending machines located near the main mechanical room were considered, as they are known to be owned and operated by the facility. This measure is recommended for the Main Terminal and TNC staging area, as it has an attractive payback for both areas.

See **Section 2.3.2** for summaries of payback, cost, and energy savings and **Appendix C** for the full calculations and cost breakdowns.

### 2.1.5 Control System ECMs

***C-1: Demand Control Ventilation (DCV)***

The outdoor air introduced into the spaces is currently constant based on design occupancy conditions. Outside air can be significantly reduced for most of the time that the building is occupied. This ECM proposes the installation of carbon dioxide ($CO_2$) sensors in the space to allow for reduced outdoor air flow when conditions allow. An average outside air reduction of 25 percent is assumed possible with the implementation of DCV. The DCV system will automatically adjust the outdoor air damper position through the building management system (BMS) to reduce outdoor air flows based on indoor $CO_2$ levels. The AHUs in the Arrivals Terminal were not considered due to the configuration of the units and the number of zones served by each air handling unit (monitoring each zone is required, which increases installation cost significantly). Other units servicing the basement areas were not considered, as there are other contaminants in the air other than CO2 that drive ventilation requirements in some of the spaces.

Savings will result from the avoided heating and cooling of excessive outside air. See **Table 2-20** for the building under consideration for this measure.

**Table 2-20 – Demand Control Ventilation**

| Building | # Units | Equipment Considered |
|---|---|---|
| Main Terminal | 6 | AHU's 7, 8, 10, 39, and 40 |

Source: CHA, 2019.

This measure is recommended because it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

***C-2: Night Setback (NSB)***

Typically, there is a small unoccupied period at the Airport (typically 1:00 am to 5:00 am daily). During these times, the building could go into night setback mode. In this mode, the heating setpoint could be lowered and the cooling setpoint could be raised, while the respective air handling units could also be shut down. The change in unoccupied setpoints decreases the temperature difference between the indoor and outside temperatures, thereby allowing thermal energy savings. The shutdown of the units and their fans during unoccupied periods allows for electric energy savings.

These savings could increase because these calculations did not include the exhaust fans, as some of the fans are not on the BMS. Due to the overlap of automatic controlled zones and non-automatic controlled zones, some areas may not be able to obtain new setpoints. In the Airfield Storage Facility, the setpoint of the salt bay was lowered for all time periods and still allowed proper temperature storage. See **Table 2-21** for buildings under consideration for this measure.

**Table 2-21 – Night Setback**

| Building | Hour Reduction | Heating Setpoint | Cooling Setpoint |
|---|---|---|---|
| Main Terminal | 4 | 68 | 74 |
| Arrivals Terminal | 4 | 68 | 74 |
| Field Maintenance Facility | 15.5 | 68 | 72 |
| Field Storage Facility | 24 | 45 | N/A |

Source: CHA, 2019.

For the Main Terminal, this measure was considered for spaces served by AHU's 1-2, 4-7, 9-14, 16, 18-19, 20, 39-40, and RTU's 1 and 1A. This measure is recommended, as it has an attractive payback.

For the Arrivals Terminal, this measure was considered for spaces served by AHU's 26-33 and 35-36. This measure is recommended as it has an attractive payback.

For the Field Maintenance Facility this measure was considered for all spaces. This measure is recommended as it has an attractive payback.

For the Field Storage Facility this measure was considered for the snow removal storage room. This measure is recommended as it has an attractive payback.

See **Section 2.3.2** for a summary of paybacks, costs, and energy savings and **Appendix C** for the full calculations and cost breakdowns.

***C-3: Garage Door Interlock***

In the Airfield Maintenance Facility, there are large open spaces for vehicle work. The spaces' temperatures are controlled by unit heaters (UH) and infrared heaters (IR). With the large bay doors that allow large vehicle access, the UHs and IRs should be off when the doors are open. The interlock switches will shut power off to the UHs and IRs. When doors are closed, the devices will operate to maintain temperature. This prevents unneeded heating of the garage bays while the doors are open. See **Table 2-22** for the buildings under consideration for this measure.

**Table 2-22 – Garage Door Interlock**

| Building | # Switches |
|---|---|
| Airfield Maintenance Facility | 4 |

Source: CHA, 2019.

This measure is recommended, as it has an attractive payback. See **Section 2.3.2** for a summary of paybacks, costs, and energy savings and **Appendix C** for the full calculations and cost breakdowns.

***C-4: Plug Load Controls***

The Airport contains locations that could benefit from installation of plug load controllers. By installing plug load controllers with occupancy controls, energy consumption can be reduced. Energy savings result from a reduction in equipment runtime. In this case, only the window air conditioner in the airfield lighting vault was considered for this measure.

**Table 2-23 – Plug Load Controls**

| Building | Plug Load Controller Count | Equipment Controlled |
|---|---|---|
| Airfield Lighting Vault | 1 | Window Air Conditioner |

Source: CHA, 2019.

This measure is recommended, as it has an attractive payback. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix C** for the full calculation and cost breakdown.

### 2.1.6 Lighting/Electrical System ECMs

***L-1: Lighting Upgrade***

A non-investment grade lighting audit was performed throughout the airport. This consisted of a lighting inventory being collected during the field survey for each individual building. The energy usage for lighting was calculated using assumed existing fixture wattage and the typical occupied hours for each building, based on discussions with site staff. The cost estimate and savings for lighting replacement and controls for each building is based on a one for one replacement. More aesthetic fixtures or other upgrades could be made at an increased cost to the airport, resulting in a longer overall payback. This was not an investment grade lighting survey and installation costs and energy savings may vary slightly with a final investment grade audit based on fixture replacement selection, fixture counts, operation hours, and wattage assumptions.

The site has older fluorescent, incandescent, compact fluorescent, high pressure sodium and metal halide lamps. Replacing these lamps and fixtures with LED alternatives can result in energy and cost reductions. Additionally, lighting in select areas that is currently controlled by switches can be controlled by occupancy sensors to provide even more savings. The occupancy sensors can be adjusted to include a delay period to ensure that lights remain on during room occupancy. Private offices and break rooms are examples of spaces where occupancy sensors should typically be installed.

Several areas within the terminals have elevated skylights with decorative lighting fixtures directed upward towards architectural features. These fixtures were on during daytime hours regardless of ambient lighting. It is recommended that decorative lighting fixtures be connected to a daylight control sensor. A daylight control system will measure the level of natural sunlight in an area and adjust the levels of decorative lighting to maintain a constant lighting level. Energy savings are possible based on reduced fixture usage. Additional costs may result from the addition of a separate circuit connecting the sensors to the existing control system.

Many of the facilities' interior light fixtures use T-12, T-8 or T-5 fluorescent lamps and standard efficiency ballasts. These fixtures consume more energy than similar LEDs. The proposed interior lighting replacements consider upgrading lights to LED fixtures and ballasts or lamps. Lighting in some sections of the ORF facility has already been upgraded by staff when fixtures and lamps fail.

Many exterior fixtures contain high-pressure sodium or metal halide lamps that vary from 50 to 1000 watts. These fixtures can be retrofitted to new LED fixtures. While the runtime hours of exterior lighting will not change, the electricity savings will result from significantly lower fixture wattages.

There are additional savings possible on top of the LED conversion of the exterior lighting. Currently, there are 155 Dominion-owned exterior pole lights, which are charged out at a rate of roughly 0.145 $/kWh to the Airport Authority. By converting ownership to NAA, it is assumed that a similar rate to the existing exterior lighting of around 0.067 $/kWh could be negotiated. This lighting currently uses around 400,380 kWh per year and could result in a savings of around $31,157 per year. Costs for converting the ownership over to the Airport Authority are not included and should be negotiated with the energy provider. See **Table 2-24** for buildings under consideration for this measure.

**Table 2-24 – Lighting Upgrade**

| Building | Typical Existing Lighting Type | Typical Proposed Lighting Type |
|---|---|---|
| Main Terminal Complex | T-8, CFL, MH, INC, HPS, PAR38, LED | LED |
| Automobile Parking Garages | MH, HPS | LED |
| Airfield Lighting Vault | T-8 | LED |
| Triturator | T-8, MH, HPS | LED |

| Building | Typical Existing Lighting Type | Typical Proposed Lighting Type |
|---|---|---|
| Arrivals Building and Baggage Claim | T-8, CFL, MH, PAR38, HPS, LED | LED |
| Aircraft Rescue and Firefighting Station | T-8, CFL, MH | LED |
| ARFF Storage Building | MH | LED |
| Air Cargo Building (1) | T-8 | LED |
| Air Cargo Building (2) | T-8 | LED |
| TNC Staging Area | T-8, CFL | LED |
| Fuel Farm | MH, HPS | LED |
| Ground Run-up Enclosure (GRE) | T-8, MH | LED |
| Airfield Maintenance Facility | T-8, T-12, MH | LED |
| Airfield Maintenance Building | T-8 | LED |
| Long-Term Parking Lot | MH, HPS | LED |
| Short-Term Parking Lot | MH, HPS | LED |

Source: CHA, 2019.

This measure is recommended, as it has an attractive payback with all facilities combined. See **Section 2.3.2** for a summary of payback, cost, and energy savings and **Appendix B** for the full calculation, line by line fixture replacement and cost breakdown.

## 2.2 OPERATIONS AND MAINTENANCE OPPORTUNITIES

### 2.2.1 O&M-1: AHU HW/CHW Coil Cleaning and Replacement

The American Society of Heating, Refrigerating and Air-Conditioning Engineers' (ASHRAE) November 2006 publication states that coil cleaning saves energy. It further documents that cleaning coils can improve effectiveness of the coils by 10 to 15 percent. Cleaning coils improves the heat transfer efficiency, improves the coil life, and increases airflow through the unit. This is a maintenance solution and difficult to calculate the exact energy savings results.

### 2.2.2 O&M-2: Jetway Bridge Infiltration

As passengers embark and disembark their respective planes, the doors to the concourses are open to the outside temperatures, causing significant temperature and pressure fluctuations in the concourse. This causes the HVAC systems to compensate for the extreme temperature and pressure swings. The low-cost solution of plastic air curtains would inhibit passenger loading and unloading, which is not an ideal solution for the airlines. Another solution in these cases are passenger boarding bridges that provide pre-conditioned air that would help keep the concourse temperature swings to minimum; however, this would be up to the airlines to implement as it would be affixed to the jetways.

## 2.3 ENERGY CONSERVATION OPPORTUNITIES (ECO)

### 2.3.1 ECO-1: Power Distribution Transformer Replacements

As a power transformer ages, the winding insulation degrades, and the transformer efficiency decreases. In typical use, a transformer's life expectancy is 20 to 30 years. Some of the transformers at the Airport are from the 1971 original installation. A transformer replacement

study is recommended, as this Study could identify those transformers that are overloaded and under loaded and replace them with properly sized higher energy performance transformers.

### 2.3.2 Energy Conservation Measures and Opportunities Per Building

Utility rates from the Utility Analysis in **Chapter 1** were established from existing utility bill information. Energy Conservation Measure calculations used the utility rates show in **Table 2-25** for each building.

**Table 2-25 – Utility Rates Summary (Per Building)**

| Building | Blended electric Rate ($/kWh) | Natural Gas Rate ($/Therm) | Propane Rate ($/LPG) |
|---|---|---|---|
| Main Terminal Complex | 0.08 | 0.34 | - |
| Automobile Parking Garages | 0.07 | - | - |
| Airfield Lighting Vault | 0.10 | - | - |
| Triturator | 0.10 | - | - |
| Arrivals Building and Baggage Claim | 0.06 | 0.34 | - |
| Aircraft Rescue and Firefighting Station | 0.10 | - | 1.40 |
| ARFF Storage Building | 0.10 | - | 1.40 |
| Air Cargo Building (1) | 0.07 | 0.34 | - |
| Air Cargo Building (2) | 0.07 | 0.34 | - |
| TNC Staging Area | 0.07 | 0.34 | - |
| Fuel Farm | 0.07 | - | - |
| Ground Run-up Enclosure (GRE) | 0.07 | - | - |
| Airfield Maintenance Facility | 0.09 | 0.34 | - |
| Airfield Maintenance Building | 0.09 | 0.34 | - |
| Long-Term Parking Lot | 0.07 | - | - |
| Short-Term Parking Lot | 0.07 | - | - |

Source: CHA, 2019.

The basis for recommendations of Energy conservation measures (ECM) was the simple payback of each item. The simple payback considers the cost of implementation of each measure and anticipated savings over the useful life of the equipment. ECMs with payback periods of less than 15 years were recommended during this Study, whereas ECMs with payback periods greater than 15 years were not recommended. Energy conservation opportunities (ECO) require further analysis to determine feasibility, associated costs, and anticipated savings with implementation. These items were categorized in **Table 2-26**.

**Table 2-26 – ECM Payback Criteria**

| Item | Outcome | | Payback |
|---|---|---|---|
| ECM | Recommended | R | <15 Years |
| | Not Recommended | NR | >15 Years |
| ECO | Further Study Required | FS | - |

Source: CHA, 2019.

***Energy Conservation Measures and Opportunities for Bldg. 1: Main Terminal Complex***

**Table 2-27 – Savings Summary - Main Terminal Complex**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| BE-1 | 4,625,646 | 4,454,326 | 11,032 | 11,032 | 15,169 | 5,904 | >25 | NR | 86 |
| BE-2 | 809 | 890 | 644 | 644 | 264 | 135 | 6.0 | R | 2 |
| BE-3 | 584,309 | 568,743 | 227,803 | 227,803 | 352 | 16,219 | >25 | NR | 98 |
| BE-4 | 21,900 | 44,424 | 11,180 | 11,180 | - | 790 | >25 | NR | 5 |
| M-1 | 202,390 | 383,169 | - | 0 | 18,603 | 6,285 | >25 | NR | 99 |
| M-2 | 2,828 | 6,151 | 3,546 | 3,546 | - | 251 | 11.3 | R | 1 |
| M-3 | 202,093 | 199,352 | 993,978 | 993,978 | - | 70,251 | 2.9 | R | 418 |
| M-7 | 15,188 | 14,625 | 1,653 | 1,653 | 288 | 214 | >25 | R | 2 |
| M-9 | 18,315 | 17,637 | 24,077 | 24,077 | - | 1,702 | 10.8 | R | 10 |
| M-10 | 49,580 | 51,216 | 38,544 | 38,544 | - | 2,724 | 18.2 | NR | 16 |
| DHW-1 & 2 | 89,006 | 68,718 | 78,267 | 78,267 | (2,804) | 11,644 | 7.6 | R | 18 |
| C-1 | 35,210 | 25,066 | 28,130 | 28,130 | 4,331 | 3,451 | 10.2 | R | 35 |
| C-2 | 31,590 | 77,188 | 75,619 | 75,619 | 29,142 | 15,190 | 2.1 | R | 187 |
| K-1 | 60,922 | 51,404 | 78,674 | 78,674 | 3,668 | 6,800 | 9.0 | R | 53 |
| K-2 | 37,500 | 800 | 82,495 | 82,495 | - | 5,830 | 6.4 | R | 35 |
| K-3 | 800 | 37,500 | 3,469 | 3,469 | - | 245 | 3.3 | R | 1 |
| L-1 | 1,274,080 | 1,274,080 | 1,429,011 | 1,423,962 | - | 100,997 | 12.6 | R | 600 |
| Total Recommended | | 1,768,341 | 282 | 2,799,563 | 34,890 | 216,710 | 8 | - | 1,363 |
| Total | | 7,252,166 | 282 | 3,088,123 | 69,014 | 248,633 | >25 | - | 1,666 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 2: Automobile Parking Garages*

**Table 2-28 – Savings Summary - Automobile Parking Garages**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 1,688,538 | 314 | 2,500,800 | - | 166,941 | 10.1 | R | 1041.4 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 3: Airfield Lighting Vault*

**Table 2-29 – Savings Summary - Airfield Lighting Vault**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| M-4 | Window AC Replacement | 4,400 | - | 1,210 | - | 116 | >25 | NR | 0.5 |
| C-4 | Plug Load Controls | 200 | - | 1,077 | - | 103 | 1.9 | R | 0.5 |
| L-1 | Lighting Upgrade | 5,143 | 1 | 5,111 | - | 490 | 10.5 | R | 2.1 |
| Total Recommended | | 5,343 | 1 | 6,188 | - | 594 | 9.0 | - | 2.6 |
| Total | | 9,743 | 1 | 7,398 | - | 710 | 13.7 | - | 3.1 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 4: Triturator*

**Table 2-30 – Savings Summary - Triturator**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 4,945 | 1 | 1,728 | - | 166 | 29.8 | R | 0.8 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 5: Arrivals Building and Baggage Claim*

**Table 2-31 – Savings Summary - Arrivals Building and Baggage Claim**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| BE-2 | Door Sweeps and Seals | 2,003 | - | 1,097 | 475 | 230 | 8.7 | R | 3.0 |
| M-1 | Boiler Replacements | 179,950 | - | - | 15,530 | 5,247 | >25 | NR | 82.8 |
| M-5 | Destratification Fans | 61,089 | - | 110,365 | 7,309 | 9,481 | 6.4 | R | 85.4 |
| M-6 | Chilled Water (CHW and Hot Water (HHW) Pump Variable Speed Drives (VSD) | 90,911 | - | 127,490 | - | 8,100 | 11.2 | R | 53.6 |
| M-9 | Elevator Motor Upgrades | 34,047 | - | 38,772 | - | 2,463 | 13.8 | R | 16.3 |
| M-10 | Escalator Controls | 26,753 | - | 22,776 | - | 1,447 | 18.5 | NR | 9.6 |
| DHW-2 | Domestic Hot Water Condensing Water Heater | 15,308 | - | - | 213 | 72 | >25 | NR | 1.1 |
| C-2 | Night Setback | 16,031 | - | 24,601 | 954 | 1,885 | 8.5 | R | 15.4 |
| L-1 | Lighting Upgrade | 437,385 | 114 | 799,367 | - | 76,752 | 5.7 | R | 335.9 |
| **Total Recommended** | | 641,467 | 114 | 1,101,691 | 8,738 | 98,912 | 6.5 | - | 509.6 |
| **Total** | | 863,477 | 114 | 1,124,467 | 24,481 | 105,678 | 8.2 | | 603.1 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 6: Aircraft Rescue and Firefighting Station*

**Table 2-32 – Savings Summary - Aircraft Rescue and Firefighting Station**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 34,424 | 4.6 | 24,413 | - | 2,344 | 14.7 | R | 10.1 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 7: ARFF Storage Building*

**Table 2-33 – Savings Summary - ARFF Storage Building**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 2,637 | 1.5 | 6,595 | - | 633 | 4.2 | R | 1.2 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 8 & 9: Air Cargo Buildings*

**Table 2-34 – Savings Summary - Air Cargo Buildings**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 169,782 | 39.5 | 239,216 | - | 15,969 | 10.6 | R | 97.6 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 12: TNC Staging Area*

**Table 2-35 – Savings Summary - TNC Staging Area**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| BE-2 | Door Sweep and Seal Replacement | 180 | - | 190 | 38 | 25 | 7.1 | R | 0.3 |
| M-1 | Boiler Replacement | 37,300 | - | - | 1,412 | 477 | >25 | NR | 8.0 |
| DHW-2 | Domestic Hot Water Condensing Water Heaters | 4,740 | - | - | 1,117 | 377 | 12.6 | NR | 0.4 |
| K-3 | Vending Misers | 600 | - | 2,891 | - | 193 | 3.1 | R | 2.0 |
| L-1 | Lighting Upgrade | 16,970 | 4 | 13,370 | - | 893 | 19.0 | R | 5.6 |
| Total Recommended | | 17,750 | 4 | 16,451 | 38 | 1,111 | 16.0 | - | 7.9 |
| Total | | 59,790 | 4 | 16,451 | 2,567 | 1,965 | >25 | - | 16.3 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 15: Fuel Farm*

**Table 2-36 – Savings Summary – Fuel Farm**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 3,616 | 1 | 5,841 | - | 390 | 9.3 | R | 2.3 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 17: Ground Run-Up Enclosure (GRE)*

**Table 2-37 – Savings Summary - Ground Run-Up Enclosure (GRE)**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 1,608 | 1.5 | 8,847 | - | 591 | 2.7 | R | 3.6 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 27: Airfield Maintenance Facility*

**Table 2-38 – Savings Summary - Airfield Maintenance Facility**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| C-2 | Night Setback | 2,959 | - | 15,032 | 3,455 | 2,558 | 1.2 | R | 24.7 |
| C-3 | Garage Door Interlock | 2,791 | - | - | 2,787 | 942 | 3.0 | R | 14.9 |
| L-1 | Lighting Upgrade | 38,712 | 13.7 | 43,895 | - | 4,101 | 9.4 | R | 18.4 |
| Total Recommended | | 44,380 | 14 | 50,304 | 3,154 | 5,760 | 7.7 | - | 38.0 |
| Total | | 44,380 | 14 | 50,304 | 3,154 | 5,760 | 7.7 | - | 38.0 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 34: Airfield Maintenance Storage Building*

**Table 2-39 – Savings Summary - Airfield Maintenance Storage Building**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| C-2 | Night Setback | 2,278 | - | 11,911 | 590 | 1,301 | 1.8 | R | 8.2 |
| L-1 | Lighting Upgrade | 3,637 | 1 | 2,876 | - | 269 | 13.5 | R | 1.2 |
| Total Recommended | | 5,915 | 1 | 14,787 | 590 | 1,570 | 3.8 | - | 9.4 |
| Total | | 5,915 | 1 | 14,787 | 590 | 1,570 | 3.8 | - | 9.4 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 35: Long-Term Parking Lot*

**Table 2-40 – Savings Summary - Long-Term Parking Lot**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 73,440 | 25.7 | 121,470 | - | 8,109 | 9.1 | R | 47.1 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 36: Short-Term Parking Lot*

**Table 2-41 – Savings Summary - Short-Term Parking Lot**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 4.7 | 22,335 | - | 1,491 | 13 | R | 8.7 | 4.7 |

Source: CHA, 2019.

### *Energy Conservation Measures and Opportunities for Bldg. 36: Exterior*

**Table 2-42 – Savings Summary – Exterior**

| ECM No. | ECM Description | Budgetary Cost | Annual Utility Savings | | | | Simple Payback | Recommended for Implementation | GHG Emissions |
|---|---|---|---|---|---|---|---|---|---|
| | | | Utility | | | Total | | | |
| | | $ | kW | kWh | Therms | $ | Years | R/NR/FS | MTCDE |
| L-1 | Lighting Upgrade | 258,516 | 133.3 | 627,696 | - | 41,902 | 6.2 | R | 6.5 |

Source: CHA, 2019.

# 3 RENEWABLE ENERGY MEASURES

## 3.1 SOLAR PHOTOVOLTAIC ARRAY

A photovoltaic solar array is a renewable energy generation method that has been considered for ORF. Present technology incorporates the use of solar cell arrays that produce direct current (DC) electricity. This DC current is converted to alternating current (AC) with the use of an electrical device known as an inverter. The amount of available area and energy usage determines how large of a solar array can be installed.

ORF has multiple locations within airport property that a solar array could technically be developed; however, this Study focuses on the roofs of the Main Terminal, Arrivals Terminal, and parking garages. The photovoltaic screening calculation considered arrays depicted in **Table 3-1**.

**Table 3-1 – PV Arrays**

| Location | Area (Sqft) | Generation Size (kW) | Potential Yearly Electrical Generation (kWh) |
|---|---|---|---|
| Terminal Roofs | 311,817 | 1,770 | 2,582,466 |
| Parking Garage A | 108,602 | 630 | 919,783 |
| Parking Garage B | 44,793 | 230 | 335,575 |
| Parking Garage C | 45,509 | 230 | 335,575 |
| Total | 510,721 | 2,860 | 4,172,799 |

Source: CHA, 2019.

With these arrays generating 4,172,799 million kwh per year, installing solar would result in an annual electrical savings of $284,661. The generation capabilities of the proposed array would offset 20 percent of the annual electricity used. The PV WATTS solar power generation model was utilized to calculate PV power generation. An FAA Solar Glare Hazard Analysis would need to be conducted when examining the feasibility of this or any other solar installation measure further.

**Figure 3-1 – Solar PV Areas Considered**



Source: CHA, 2019.

Installation of (PV) arrays in the state of Virginia do not participate in the solar renewable energy certificates program (SREC). This is a program that has been set up to allow entities with large amounts of environmentally unfriendly emissions to purchase credits from zero emission (PV) solar producers. One SREC credit is equivalent to 1000 kilowatt hours of PV electrical production. These credits can be traded for a period of 15 years from the date of installation; however, there is currently a federal tax credit for up to 30 percent of the total installed solar array cost if installed before 2020. This amount will decrease yearly after this point, down to 10 percent in 2022.

The system costs for PV installations were derived from recent solar contractor budgetary pricing and include the total cost of the system installation (PV panels, inverters, wiring, ballast, controls and structures). The cost of installation is currently about $4.00 per watt, or $4,000 per kW of installed system. Photovoltaic systems will be roof mounted on the terminals and function as covered parking on the parking garages. PV panels have an approximate 20-year life span; however, the inverter device that converts DC electricity to AC has a life span of 10 to 12 years and will most likely need to be replaced during the useful life of the PV system.

The implementation cost and savings related to this measure are presented in **Appendix D** and are summarized in **Table 3-2**.

**Table 3-2 – PV Arrays**

| Budgetary Cost | Annual Utility Savings | | | | Payback | Federal Tax Credit | Payback (w/ Tax Credit) | Recommended for Implementation |
|---|---|---|---|---|---|---|---|---|
| $ | Electric (kWh) | Electric (kW) | Nat Gas (Therms) | Total ($) | Years | $ | Years | R/NR/FS |
| **11,440,000** | 4,172,799 | 2,860 | - | 284,661 | 40 | 3,432,000 | 28 | NR |


Source: CHA, 2019.

This measure is not recommended due to the long payback period. This measure could be re-examined if solar incentives and federal tax credit values increase in the future. Incorporating solar systems into new facility/building construction may present more viable opportunities. The Authority should continue to consider and evaluate alternative energy technologies in all facility development or rehabilitation projects.

## 3.2 WIND

Wind power is the conversion of kinetic energy from wind into mechanical power that is used to drive a generator which creates electricity by means of a wind turbine. A wind turbine consists of rotor and blades connected to a gearbox and generator that are mounted onto a tower. Newer wind turbines also use advanced technology to generate electricity at a variety of frequencies depending on the wind speed, convert it to DC, and then back to AC before sending it to the grid. Wind turbines range from 50 to 750 kW for utility scale turbines, down to below 50 kW for smaller commercial use. On a scale of 1 (the lowest) to 7 (the highest), Class 3 and above (wind speeds of 13 mph or greater) are generally considered a "good wind resource" according to the Wind Energy Development Programmatic EIS Information Center hosted by the Bureau of Land Management. According to the map published by NREL, the ORF is classified as Class 2/borderline Class 3, meaning the site would not be an ideal candidate for wind power. See **Figure 3-2**.

**Figure 3-2 – Wind Resource Map**




## 3.3 COGENERATION

Cogeneration utilizes variously sized systems to produce electricity and useful heat simultaneously. The method generally consists of the use of combustion of fuel in a turbine or engine to produce energy. The rejected heat from this electrical power generation is then recovered to supply heating to the facility or process. Note, absorption chillers can also be used in this process to create cooling energy.

In order for cogeneration to be beneficial to the facility, a significant consistent heating load is required. The effectiveness of cogeneration comes from the ability to produce and utilize multiple energy sources from one fuel source, thus reducing the overall energy cost to produce those energy sources separately. ORF lacks this significant consistent heat load and is not a good candidate for large scale cogeneration; however, further study of a Micro-CHP systems in the Arrivals Terminal could be considered, as there is dehumidification (hot water reheat) and domestic hot water load year-round.

# 4 RECOMMENDATIONS

CHA has identified multiple energy saving measures at the various buildings. The energy savings were calculated based on data collected in the field, historical utility usage data, staff interviews, and best engineering judgment to show an order of magnitude of potential energy savings. A more in-depth study may be performed prior to implementing these ECM's using actual logged temperatures, operating hours, fuel consumed, and energy modeling where applicable. Significant utility rebates and incentives may be available from the utility supplier or other agencies that could reduce the cost and the payback term. ECMs with payback time periods of greater than 15 years are not likely candidates for implementation; however, if or when a piece of equipment fails or ages, it should be replaced while considering the same or similar guidelines outlined in the ECM descriptions.

# APPENDIX A – UTILITY DATA

| Building Number (Figure 1) | Building Name | Electricity | | | Natural Gas | | | Propane | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Annual Usage | Annual Cost | Blended Rate | Annual Usage | Annual Cost | Blended Rate | Annual Usage | Annual Cost | Blended Rate |
| | | kWh | $ | $/kWh | Therm | $ | $/therm | gallon | $ | $/gallon |
| 1 | MAIN TERMINAL COMPLEX | 16,487,430 | $ 1,259,381 | $ 0.08 | 241,260 | $ 81,509 | $ 0.34 | | | |
| 2 | AUTOMOBILE PARKING GARAGE | 1,709,927 | $ 111,162 | $ 0.07 | | | | | | |
| 3 | AIRFIELD LIGHTING VAULT | 272,800 | $ 26,164 | $ 0.10 | | | | | | |
| 4 | TRITURATOR | | | | | | | | | |
| 5 | ARRIVALS BUILDING & BAGGAGE CLAIM | 8,956,201 | $ 559,899 | $ 0.06 | 201,210 | $ 67,978 | $ 0.34 | | | |
| 6 | AIRCRAFT RESCUE AND FIREFIGHTING STATION | 106,120 | $ 10,189 | $ 0.10 | | | | 8,686 | $ 12,173 | $ 1.40 |
| 7 | ARFF STORAGE BUILDING | Included in building #6 | | | | | | Included in building #6 | | |
| 8 | AIR CARGO BUILDING | | | | | | | | | |
| 9 | AIR CARGO BUILDING | | | | | | | | | |
| 12 | TNC STAGING AREA | | | | | | | | | |
| 15 | FUEL FARM | | | | | | | | | |
| 17 | GROUND RUN-UP ENCLOSURE (GRE) | | | | | | | | | |
| 27 | AIRFIELD MAINTENANCE FACILITY | 166,500 | $ 15,554 | $ 0.09 | 22,310 | $ 7,537 | $ 0.34 | | | |
| 34 | AIRFIELD MAINTENANCE BUILDING | Included in building #27 | | | Included in building #27 | | | | | |
| 35 | LONG-TERM PARKING LOT | | | | | | | | | |
| 36 | SHORT-TERM PARKING LOT | | | | | | | | | |
| | TOTAL | 27,698,978 | $ 1,982,350 | $ 0.07 | 464,780 | $ 157,025 | $ 0.34 | 8,686 | $ 12,173 | $ 1.40 |

Not applicable

Utility information not available


| Month | Read Date | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | | |
| Aug-2016 | 9/2/2016 | 29 | $1,148.28 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 12,300 | $0.0934 | | | |
| Sep-2016 | 10/6/2016 | 34 | $1,256.82 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 13,500 | $0.0931 | | | |
| Oct-2016 | 11/2/2016 | 27 | $1,099.37 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 11,700 | $0.0940 | | | |
| Nov-2016 | 12/6/2016 | 34 | $1,270.59 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 13,800 | $0.0921 | | | |
| Dec-2016 | 1/6/2017 | 31 | $1,392.43 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 15,300 | $0.0910 | | | |
| Jan-2017 | 2/7/2017 | 32 | $1,642.22 | 48 | 0 | 0 | 0 | 48 | 0 | 0 | 0 | 18,000 | $0.0912 | | | |
| Feb-2017 | 3/7/2017 | 28 | $1,146.31 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 12,300 | $0.0932 | | | |
| Mar-2017 | 4/5/2017 | 29 | $1,170.73 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 12,600 | $0.0929 | | | |
| Apr-2017 | 5/8/2017 | 33 | $1,195.16 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 12,900 | $0.0926 | | | |
| May-2017 | 6/6/2017 | 29 | $1,076.13 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 11,400 | $0.0944 | | | |
| Jun-2017 | 7/6/2017 | 30 | $1,234.37 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 13,200 | $0.0935 | | | |
| Jul-2017 | 8/4/2017 | 29 | $1,250.96 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 13,200 | $0.0948 | 160,200 | $14,883 | $0.0929 |
| Aug-2017 | 9/5/2017 | 32 | $1,375.38 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 14,700 | $0.0936 | 162,600 | $15,110 | $0.0929 |
| Sep-2017 | 10/4/2017 | 29 | $1,201.19 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 12,600 | $0.0953 | 161,700 | $15,055 | $0.0931 |
| Oct-2017 | 11/2/2017 | 29 | $1,250.96 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 13,200 | $0.0948 | 163,200 | $15,206 | $0.0932 |
| Nov-2017 | 12/7/2017 | 35 | $1,400.27 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 15,000 | $0.0934 | 164,400 | $15,336 | $0.0933 |
| Dec-2017 | 1/6/2018 | 30 | $1,610.46 | 45 | 0 | 0 | 0 | 45 | 0 | 0 | 0 | 17,400 | $0.0926 | 166,500 | $15,554 | $0.0934 |
| Jan-2018 | 2/5/2018 | 30 | $2,730.07 | 48 | 0 | 0 | 0 | 48 | 0 | 0 | 0 | 31,500 | $0.0867 | 180,000 | $16,642 | $0.0925 |
| Feb-2018 | 3/6/2018 | 29 | $1,802.13 | 36 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 20,400 | $0.0883 | 188,100 | $17,298 | $0.0920 |
| Mar-2018 | 4/6/2018 | 31 | $1,821.52 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 20,400 | $0.0893 | 195,900 | $17,949 | $0.0916 |
| Apr-2018 | 5/7/2018 | 31 | $1,156.46 | 36 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 12,300 | $0.0940 | 195,300 | $17,910 | $0.0917 |
| May-2018 | 6/5/2018 | 29 | $1,202.70 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 12,600 | $0.0955 | 196,500 | $18,036 | $0.0918 |
| Jun-2018 | 7/5/2018 | 30 | $1,277.11 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 13,500 | $0.0946 | 196,800 | $18,079 | $0.0919 |
| Jul-2018 | 8/3/2018 | 29 | $1,286.45 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 12,900 | $0.0997 | 196,500 | $18,115 | $0.0922 |
| Aug-2018 | 9/5/2018 | 33 | $1,496.79 | 42 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 15,300 | $0.0978 | 197,100 | $18,236 | $0.0925 |

0271317505 - Snow Removal
Dominion Energy: Schedule 100

Sep17 - Aug18 197,100 $18,236 $0.0925

SQFT 44,913

| YEAR | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | kwh/sqft | $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | |
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2015** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2016** | 155 | $ 6,167 | 198 | - | - | - | 198 | - | - | - | 66,600 | | 3.5 | $ 0.32 |
| **2017** | 365 | $ 15,554 | 504 | - | - | - | 504 | - | - | - | 166,500 | $ 0.0934 | 3.7 | $ 0.35 |
| **2018** | 242 | $ 12,773 | 324 | - | - | - | 324 | - | - | - | 138,900 | | 4.7 | $ 0.43 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |




| Month | Read Date | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | | |
| Aug-2016 | 9/2/2016 | 29 | $1,874.57 | 105 | 0 | 0 | 0 | 105 | 0 | 0 | 0 | 19,280 | $0.0972 | | | |
| Sep-2016 | 10/6/2016 | 34 | $2,412.72 | 103 | 0 | 0 | 0 | 103 | 0 | 0 | 0 | 25,440 | $0.0948 | | | |
| Oct-2016 | 11/2/2016 | 27 | $2,058.18 | 114 | 0 | 0 | 0 | 114 | 0 | 0 | 0 | 21,200 | $0.0971 | | | |
| Nov-2016 | 12/6/2016 | 34 | $2,416.03 | 85 | 0 | 0 | 0 | 85 | 0 | 0 | 0 | 25,840 | $0.0935 | | | |
| Dec-2016 | 1/6/2017 | 31 | $2,721.57 | 116 | 0 | 0 | 0 | 116 | 0 | 0 | 0 | 28,720 | $0.0948 | | | |
| Jan-2017 | 2/7/2017 | 32 | $2,819.05 | 122 | 0 | 0 | 0 | 122 | 0 | 0 | 0 | 29,760 | $0.0947 | | | |
| Feb-2017 | 3/7/2017 | 28 | $2,089.09 | 88 | 0 | 0 | 0 | 88 | 0 | 0 | 0 | 22,080 | $0.0946 | | | |
| Mar-2017 | 4/5/2017 | 29 | $1,847.96 | 78 | 0 | 0 | 0 | 78 | 0 | 0 | 0 | 19,520 | $0.0947 | | | |
| Apr-2017 | 5/8/2017 | 33 | $2,103.49 | 118 | 0 | 0 | 0 | 118 | 0 | 0 | 0 | 21,680 | $0.0970 | | | |
| May-2017 | 6/6/2017 | 29 | $1,809.13 | 97 | 0 | 0 | 0 | 97 | 0 | 0 | 0 | 18,720 | $0.0966 | | | |
| Jun-2017 | 7/6/2017 | 30 | $1,811.70 | 95 | 0 | 0 | 0 | 95 | 0 | 0 | 0 | 18,720 | $0.0968 | | | |
| Jul-2017 | 8/4/2017 | 29 | $1,919.35 | 120 | 0 | 0 | 0 | 120 | 0 | 0 | 0 | 19,200 | $0.1000 | 270,160 | $25,883 | $0.0958 |
| Aug-2017 | 9/5/2017 | 32 | $2,196.86 | 89 | 0 | 0 | 0 | 89 | 0 | 0 | 0 | 22,880 | $0.0960 | 273,760 | $26,205 | $0.0957 |
| Sep-2017 | 10/4/2017 | 29 | $1,991.84 | 73 | 0 | 0 | 0 | 73 | 0 | 0 | 0 | 20,880 | $0.0954 | 269,200 | $25,784 | $0.0958 |
| Oct-2017 | 11/2/2017 | 29 | $2,157.58 | 73 | 0 | 0 | 0 | 73 | 0 | 0 | 0 | 22,800 | $0.0946 | 270,800 | $25,884 | $0.0956 |
| Nov-2017 | 12/7/2017 | 35 | $2,740.42 | 98 | 0 | 0 | 0 | 98 | 0 | 0 | 0 | 28,800 | $0.0952 | 273,760 | $26,208 | $0.0957 |
| Dec-2017 | 1/6/2018 | 30 | $2,677.88 | 116 | 0 | 0 | 0 | 116 | 0 | 0 | 0 | 27,760 | $0.0965 | 272,800 | $26,164 | $0.0959 |
| Jan-2018 | 2/5/2018 | 30 | $2,759.27 | 116 | 0 | 0 | 0 | 116 | 0 | 0 | 0 | 28,640 | $0.0963 | 271,680 | $26,105 | $0.0961 |
| Feb-2018 | 3/6/2018 | 29 | $2,553.43 | 117 | 0 | 0 | 0 | 117 | 0 | 0 | 0 | 26,320 | $0.0970 | 275,920 | $26,569 | $0.0963 |
| Mar-2018 | 4/6/2018 | 31 | $2,193.53 | 120 | 0 | 0 | 0 | 120 | 0 | 0 | 0 | 22,240 | $0.0986 | 278,640 | $26,914 | $0.0966 |
| Apr-2018 | 5/7/2018 | 31 | $2,016.32 | 108 | 0 | 0 | 0 | 108 | 0 | 0 | 0 | 20,480 | $0.0985 | 277,440 | $26,827 | $0.0967 |
| May-2018 | 6/5/2018 | 29 | $2,014.13 | 72 | 0 | 0 | 0 | 72 | 0 | 0 | 0 | 21,120 | $0.0954 | 279,840 | $27,032 | $0.0966 |
| Jun-2018 | 7/5/2018 | 30 | $1,982.36 | 78 | 0 | 0 | 0 | 78 | 0 | 0 | 0 | 20,480 | $0.0968 | 281,600 | $27,203 | $0.0966 |
| Jul-2018 | 8/3/2018 | 29 | $2,112.80 | 119 | 0 | 0 | 0 | 119 | 0 | 0 | 0 | 20,320 | $0.1040 | 282,720 | $27,396 | $0.0969 |
| Aug-2018 | 9/5/2018 | 33 | $1,923.29 | 54 | 0 | 0 | 0 | 54 | 0 | 0 | 0 | 19,680 | $0.0977 | 279,520 | $27,123 | $0.0970 |

1835298553 - Airfield Lighting Vault Bldg
Dominion Energy: Schedule 100

Sep17 - Aug18 279,520 $27,123 $0.0970 $/kwh

SQFT 1,216


| YEAR | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | kwh/sqft | $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | |
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2015** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2016** | 155 | $ 11,483 | 523 | - | - | - | 523 | - | - | - | 120,480 | | 233.3 | $ 22.24 |
| **2017** | 365 | $ 26,164 | 1,167 | - | - | - | 1,167 | - | - | - | 272,800 | $ 0.0959 | 224.3 | $ 21.52 |
| **2018** | 242 | $ 17,555 | 784 | - | - | - | 784 | - | - | - | 179,280 | | 222.4 | $ 21.77 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |



| Month | Read Date | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | | |
| Aug-2016 | 9/2/2016 | 28 | $1,532.16 | 39 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 16,880 | $0.0908 | | | |
| Sep-2016 | 10/5/2016 | 33 | $1,469.98 | 36 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 17,440 | $0.0843 | | | |
| Oct-2016 | 11/2/2016 | 28 | $997.41 | 36 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 11,200 | $0.0891 | | | |
| Nov-2016 | 12/6/2016 | 34 | $1,010.41 | 31 | 0 | 0 | 0 | 31 | 0 | 0 | 0 | 11,600 | $0.0871 | | | |
| Dec-2016 | 1/6/2017 | | | 30 | | | | | | | | 11,160 | | | | |
| Jan-2017 | 2/6/2017 | 62 | $1,943.81 | 30 | 0 | 0 | 0 | 30 | 0 | 0 | 0 | 11,160 | $0.0871 | | | |
| Feb-2017 | 3/7/2017 | 29 | $883.63 | 27 | 0 | 0 | 0 | 27 | 0 | 0 | 0 | 10,160 | $0.0870 | | | |
| Mar-2017 | 4/5/2017 | 29 | $895.27 | 32 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 10,080 | $0.0888 | | | |
| Apr-2017 | 5/9/2017 | 34 | $1,149.98 | 31 | 0 | 0 | 0 | 31 | 0 | 0 | 0 | 13,440 | $0.0856 | | | |
| May-2017 | 6/7/2017 | 29 | $1,181.26 | 37 | 0 | 0 | 0 | 37 | 0 | 0 | 0 | 12,720 | $0.0929 | | | |
| Jun-2017 | 7/7/2017 | 30 | $1,526.63 | 36 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 16,960 | $0.0900 | | | |
| Jul-2017 | 8/4/2017 | 28 | $1,033.36 | 14 | 0 | 0 | 0 | 38 | 0 | 0 | 0 | 10,720 | $0.0964 | 153,520 | $13,624 | $0.0887 |
| Aug-2017 | 9/5/2017 | 32 | $480.71 | 13 | 0 | 0 | 0 | 13 | 0 | 0 | 0 | 5,120 | $0.0939 | 141,760 | $12,572 | $0.0887 |
| Sep-2017 | 10/4/2017 | 29 | $340.64 | 11 | 0 | 0 | 0 | 11 | 0 | 0 | 0 | 3,760 | $0.0906 | 128,080 | $11,443 | $0.0893 |
| Oct-2017 | 11/3/2017 | 30 | $350.48 | 12 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 3,840 | $0.0913 | 120,720 | $10,796 | $0.0894 |
| Nov-2017 | 12/8/2017 | 35 | $403.41 | 11 | 0 | 0 | 0 | 11 | 0 | 0 | 0 | 4,560 | $0.0885 | 113,680 | $10,189 | $0.0896 |
| Dec-2017 | 1/7/2018 | | | 9 | | | | | | | | 3,600 | | 106,120 | $10,189 | $0.0960 |
| Jan-2018 | 2/6/2018 | 60 | $642.51 | 9 | 0 | 0 | 0 | 9 | 0 | 0 | 0 | 3,600 | $0.0892 | 98,560 | $8,888 | $0.0902 |
| Feb-2018 | 3/6/2018 | 28 | $290.01 | 9 | 0 | 0 | 0 | 9 | 0 | 0 | 0 | 3,200 | $0.0906 | 91,600 | $8,294 | $0.0905 |
| Mar-2018 | 4/5/2018 | 30 | $343.86 | 10 | 0 | 0 | 0 | 10 | 0 | 0 | 0 | 3,840 | $0.0895 | 85,360 | $7,743 | $0.0907 |
| Apr-2018 | 5/7/2018 | 32 | $350.14 | 10 | 0 | 0 | 0 | 10 | 0 | 0 | 0 | 3,920 | $0.0893 | 75,840 | $6,943 | $0.0915 |
| May-2018 | 6/6/2018 | 30 | $454.55 | 13 | 0 | 0 | 0 | 13 | 0 | 0 | 0 | 4,800 | $0.0947 | 67,920 | $6,216 | $0.0915 |
| Jun-2018 | 7/5/2018 | 29 | $447.99 | 12 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 4,720 | $0.0949 | 55,680 | $5,138 | $0.0923 |
| Jul-2018 | 8/3/2018 | 29 | $454.36 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4,240 | $0.1072 | 49,200 | $4,559 | $0.0927 |
| Aug-2018 | 9/5/2018 | 33 | $555.75 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5,200 | $0.1069 | 49,280 | $4,634 | $0.0940 |

| | | | | | | | | | | | | | | | SQFT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5362040007 - Fire/Rescue Bldg | | | | | | | | Sep17 - Aug18 | | 49,280 | $4,634 | $0.0940 | $/kWh | | 13,515 |

| YEAR | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | kwh/sqft | $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | |
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2015** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2016** | 123 | $ 5,010 | 172 | - | - | - | 142 | - | - | - | 68,280 | | 15.0 | $ 1.10 |
| **2017** | 367 | $ 10,189 | 263 | - | - | - | 278 | - | - | - | 106,120 | $ 0.0960 | 7.8 | $ 0.75 |
| **2018** | 271 | $ 3,539 | 87 | - | - | - | 63 | - | - | - | 33,520 | | 3.3 | $ 0.35 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |




| Month | Read Date | Bill Days | *Transaction $ Amount | Metered kW On Peak | Metered kW Off Peak | Power Supply kW On Peak | Power Supply kW Off Peak | Dist kW | RkVa | kWh On Peak | kWh Off Peak | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh | MONTH |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sep-2016 | 10/5/2016 | 33 | $6,143.25 | 138 | 0 | 138 | 0 | 147 | 0 | 0 | 0 | 95,248 | $0.0645 | | | | 9 |
| Oct-2016 | 11/2/2016 | 28 | $5,224.67 | 138 | 0 | 138 | 0 | 147 | 0 | 0 | 0 | 81,184 | $0.0644 | | | | 10 |
| Nov-2016 | 12/6/2016 | 34 | $6,462.33 | 140 | 0 | 140 | 0 | 147 | 0 | 0 | 0 | 101,216 | $0.0638 | | | | 11 |
| Dec-2016 | 1/7/2017 | 32 | $6,118.84 | 142 | 0 | 142 | 0 | 147 | 0 | 0 | 0 | 95,600 | $0.0640 | | | | 12 |
| Jan-2017 | 2/6/2017 | 30 | $5,857.67 | 144 | 0 | 144 | 0 | 147 | 0 | 0 | 0 | 92,816 | $0.0631 | | | | 1 |
| Feb-2017 | 3/7/2017 | 29 | $5,447.08 | 141 | 0 | 141 | 0 | 145 | 0 | 0 | 0 | 84,512 | $0.0645 | | | | 2 |
| Mar-2017 | 4/5/2017 | 29 | $5,511.59 | 144 | 0 | 144 | 0 | 145 | 0 | 0 | 0 | 85,280 | $0.0646 | | | | 3 |
| Apr-2017 | 5/9/2017 | 34 | $6,137.43 | 140 | 0 | 140 | 0 | 145 | 0 | 0 | 0 | 92,016 | $0.0667 | | | | 4 |
| May-2017 | 6/6/2017 | 28 | $5,005.39 | 139 | 0 | 139 | 0 | 144 | 0 | 0 | 0 | 74,736 | $0.0670 | | | | 5 |
| Jun-2017 | 7/7/2017 | 31 | $5,495.63 | 138 | 0 | 138 | 0 | 144 | 0 | 0 | 0 | 80,832 | $0.0680 | | | | 6 |
| Jul-2017 | 8/4/2017 | 28 | $5,123.56 | 141 | 0 | 141 | 0 | 144 | 0 | 0 | 0 | 73,760 | $0.0695 | | | | 7 |
| Aug-2017 | 9/5/2017 | 32 | $5,868.18 | 138 | 0 | 138 | 0 | 144 | 0 | 0 | 0 | 85,888 | $0.0683 | 1,043,088 | $68,396 | $0.0656 | 8 |
| Sep-2017 | 10/4/2017 | 29 | $5,309.67 | 137 | 0 | 137 | 0 | 144 | 0 | 0 | 0 | 77,968 | $0.0681 | 1,025,808 | $67,562 | $0.0659 | 9 |
| Oct-2017 | 11/2/2017 | 29 | $5,351.00 | 137 | 0 | 137 | 0 | 144 | 0 | 0 | 0 | 79,152 | $0.0676 | 1,023,776 | $67,688 | $0.0661 | 10 |
| Nov-2017 | 12/8/2017 | 36 | $6,676.59 | 137 | 0 | 137 | 0 | 144 | 0 | 0 | 0 | 99,232 | $0.0673 | 1,021,792 | $67,903 | $0.0665 | 11 |
| Dec-2017 | 1/6/2018 | 29 | $5,380.35 | 137 | 0 | 137 | 0 | 144 | 0 | 0 | 0 | 79,936 | $0.0673 | 1,006,128 | $67,164 | $0.0668 | 12 |
| Jan-2018 | 2/6/2018 | 31 | $5,913.23 | 141 | 0 | 141 | 0 | 144 | 0 | 0 | 0 | 88,256 | $0.0670 | 1,001,568 | $67,220 | $0.0671 | 1 |
| Feb-2018 | 3/7/2018 | 29 | $5,308.95 | 137 | 0 | 137 | 0 | 144 | 0 | 0 | 0 | 77,680 | $0.0683 | 994,736 | $67,082 | $0.0674 | 2 |
| Mar-2018 | 4/6/2018 | 30 | $5,570.55 | 138 | 0 | 138 | 0 | 142 | 0 | 0 | 0 | 82,336 | $0.0677 | 991,792 | $67,141 | $0.0677 | 3 |
| Apr-2018 | 5/7/2018 | 31 | $5,754.62 | 140 | 0 | 140 | 0 | 141 | 0 | 0 | 0 | 84,304 | $0.0683 | 984,080 | $66,758 | $0.0678 | 4 |
| May-2018 | 6/6/2018 | 30 | $5,501.52 | 140 | 0 | 140 | 0 | 142 | 0 | 0 | 0 | 79,600 | $0.0691 | 988,944 | $67,254 | $0.0680 | 5 |
| Jun-2018 | 7/5/2018 | 29 | $5,404.27 | 141 | 0 | 141 | 0 | 143 | 0 | 0 | 0 | 78,000 | $0.0693 | 986,112 | $67,162 | $0.0681 | 6 |
| Jul-2018 | 8/3/2018 | 29 | $5,556.97 | 140 | 0 | 140 | 0 | 143 | 0 | 0 | 0 | 78,080 | $0.0712 | 990,432 | $67,596 | $0.0682 | 7 |
| Aug-2018 | 9/5/2018 | 33 | $6,380.12 | 140 | 0 | 140 | 0 | 143 | 0 | 0 | 0 | 90,480 | $0.0705 | 995,024 | $68,108 | $0.0684 | 8 |
| Sep-2018 | 10/3/2018 | 28 | $5,615.94 | 149 | 0 | 149 | 0 | 149 | 0 | 0 | 0 | 78,640 | $0.0714 | 995,696 | $68,414 | $0.0687 | 9 |

| | SQFT | SQFT |
|---|---|---|
| | 135,464 | 124,055 |

| | | | | | |
|---|---|---|---|---|---|
| 3356335004 - Park Garage | This is probably Garage B only. | Sep17 - Aug18 | 995,024 | $68,108 | $0.0684 |
| 5476292502 - Parking Garage C | This is probably Garage C only. | Oct17 - Sep18 | 995,696 | $68,414 | $0.0687 |

Garage A Lighting 705,733 kwh/year

| YEAR | Bill Days | *Transaction $ Amount | Metered kW On Peak | Metered kW Off Peak | Power Supply kW On Peak | Power Supply kW Off Peak | Dist kW | RkVa | kWh On Peak | kWh Off Peak | Total kWh | $/kwh | Garage B&C kwh/sqft | Garage B&C $/sqft | Garage A, B&C kwh/sqft | Garage A, B&C $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - | - | $ - |
| **2015** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - | - | $ - |
| **2016** | 127 | $ 23,949 | 558 | - | 558 | - | 588 | - | - | - | 373,248 | $ 0.0642 | 7.9 | $ 0.51 | 6.9 | $ 0.83 |
| **2017** | 364 | $ 67,164 | 1,673 | - | 1,673 | - | 1,734 | - | - | - | 1,006,128 | $ 0.0668 | 7.4 | $ 0.50 | 6.6 | $ 0.82 |
| **2018** | 270 | $ 51,006 | 1,266 | - | 1,266 | - | 1,291 | - | - | - | 737,376 | $ 0.0692 | 7.4 | $ 0.51 | 6.6 | $ 0.84 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - | - | $ - |




| Garage A kwh/year | Garage A $/year |
|---|---|
| - | $ - |
| - | $ 43,232 |
| 705,733 | $ 43,400 |
| 705,733 | $ 44,119 |
| 705,733 | $ 44,894 |
| - | $ - |

| Read Date | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh | MONTH |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | | | |
| 6/7/2016 | 32 | $76,068 | 2203 | 1669 | 2203 | 0 | 2722 | 825 | 0 | 0 | 1,179,720 | $0.0645 | | | | 5 |
| 7/7/2016 | 30 | $88,756 | 2292 | 1702 | 2292 | 0 | 2722 | 777 | 0 | 0 | 1,104,720 | $0.0803 | | | | 6 |
| 8/5/2016 | 29 | $91,111 | 2419 | 1896 | 2419 | 0 | 2775 | 811 | 0 | 0 | 1,179,840 | $0.0772 | | | | 7 |
| 9/2/2016 | 28 | $71,818 | 2394 | 1825 | 2394 | 0 | 2775 | 806 | 0 | 0 | 1,129,500 | $0.0636 | | | | 8 |
| 10/5/2016 | 33 | $79,281 | 1981 | 1558 | 2270 | 0 | 2775 | 752 | 0 | 0 | 1,217,340 | $0.0651 | | | | 9 |
| 11/2/2016 | 28 | $65,959 | 2049 | 1532 | 2339 | 0 | 2796 | 787 | 0 | 0 | 957,840 | $0.0689 | | | | 10 |
| 12/6/2016 | 34 | $81,666 | 2088 | 1500 | 2300 | 0 | 2811 | 794 | 0 | 0 | 1,235,940 | $0.0661 | | | | 11 |
| 1/6/2017 | 31 | $107,929 | 1908 | 1390 | 1799 | 0 | 2973 | 728 | 0 | 0 | 1,416,150 | $0.0762 | | | | 12 |
| 2/6/2017 | 31 | $139,018 | 2058 | 1500 | 2278 | 0 | 3495 | 694 | 0 | 0 | 1,308,570 | $0.1062 | | | | 1 |
| 3/7/2017 | 29 | $90,903 | 2898 | 1584 | 2251 | 0 | 3492 | 796 | 0 | 0 | 1,271,340 | $0.0715 | | | | 2 |
| 4/5/2017 | 29 | $90,318 | 2856 | 1567 | 2246 | 0 | 3187 | 763 | 0 | 0 | 1,267,980 | $0.0712 | | | | 3 |
| 5/9/2017 | 34 | $106,258 | 2824 | 1749 | 2368 | 0 | 3100 | 824 | 0 | 0 | 1,518,240 | $0.0700 | | | | 4 |
| 6/7/2017 | 29 | $91,355 | 2595 | 1461 | 2234 | 0 | 3079 | 773 | 0 | 0 | 1,286,460 | $0.0710 | 16,073,640 | $1,180,441 | $0.0734 | 5 |
| 7/7/2017 | 30 | $98,488 | 2679 | 1487 | 2272 | 0 | 3160 | 647 | 0 | 0 | 1,415,700 | $0.0696 | 16,309,620 | $1,202,861 | $0.0738 | 6 |
| 8/4/2017 | 28 | $101,786 | 3350 | 2057 | 2666 | 0 | 3430 | 1020 | 0 | 0 | 1,374,900 | $0.0740 | 16,579,800 | $1,215,891 | $0.0733 | 7 |
| 9/5/2017 | 32 | $112,008 | 2823 | 1553 | 2575 | 0 | 3424 | 784 | 0 | 0 | 1,495,980 | $0.0749 | 16,895,940 | $1,236,788 | $0.0732 | 8 |
| 10/4/2017 | 29 | $99,665 | 1964 | 1421 | 2474 | 0 | 3445 | 742 | 0 | 0 | 1,318,980 | $0.0756 | 17,085,420 | $1,264,634 | $0.0740 | 9 |
| 11/3/2017 | 30 | $110,904 | 3307 | 1828 | 3091 | 0 | 3912 | 1071 | 0 | 0 | 1,351,260 | $0.0821 | 17,219,340 | $1,296,257 | $0.0753 | 10 |
| 12/8/2017 | 35 | $118,255 | 2822 | 1527 | 2518 | 0 | 3990 | 805 | 0 | 0 | 1,556,400 | $0.0760 | 17,817,900 | $1,348,553 | $0.0757 | 11 |
| 1/6/2018 | 29 | $100,424 | 2681 | 1526 | 2511 | 0 | 3933 | 758 | 0 | 0 | 1,321,620 | $0.0760 | 16,487,430 | $1,259,381 | $0.0764 | 12 |
| 2/6/2018 | 31 | $112,889 | 2814 | 1474 | 2498 | 0 | 4059 | 765 | 0 | 0 | 1,474,800 | $0.0765 | 16,653,660 | $1,233,252 | $0.0741 | 1 |
| 3/6/2018 | 28 | $97,149 | 2857 | 1722 | 2549 | 0 | 3891 | 774 | 0 | 0 | 1,273,080 | $0.0763 | 16,655,400 | $1,239,499 | $0.0744 | 2 |
| 4/5/2018 | 30 | $101,703 | 2636 | 1286 | 2459 | 0 | 3891 | 769 | 0 | 0 | 1,330,440 | $0.0764 | 16,717,860 | $1,250,884 | $0.0748 | 3 |
| 5/7/2018 | 32 | $108,871 | 2662 | 1534 | 2548 | 0 | 3819 | 775 | 0 | 0 | 1,451,280 | $0.0750 | 16,650,900 | $1,253,497 | $0.0753 | 4 |
| 6/6/2018 | 30 | $103,417 | 2676 | 1483 | 2486 | 0 | 3846 | 764 | 0 | 0 | 1,403,760 | $0.0737 | 16,768,200 | $1,265,559 | $0.0755 | 5 |
| 7/5/2018 | 29 | $106,594 | 2774 | 1533 | 2567 | 0 | 3933 | 718 | 0 | 0 | 1,464,540 | $0.0728 | 16,817,040 | $1,273,665 | $0.0757 | 6 |
| 8/3/2018 | 29 | $103,332 | 2768 | 1513 | 2123 | 0 | 3496 | 609 | 0 | 0 | 1,462,260 | $0.0707 | 16,904,400 | $1,275,210 | $0.0754 | 7 |
| 9/5/2018 | 33 | $123,422 | 3003 | 1532 | 2391 | 0 | 3569 | 762 | 0 | 0 | 1,718,040 | $0.0718 | 17,126,460 | $1,286,624 | $0.0751 | 8 |
| 10/3/2018 | 28 | $101,422 | 2870 | 1542 | 2266 | 0 | 3563 | 775 | 0 | 0 | 1,414,080 | $0.0717 | 17,221,560 | $1,288,381 | $0.0748 | 9 |

Concourse A History and Billing Report
2406365003 - Concourse B-2
Dominion Energy: Schedule 130
7456305007 - Departure Terminal-TX1-CB43
7466242505 - Deaprture Terminal-TX2-CA19

| | | | | |
|---|---|---|---|---|
| Sep17 - Aug18 | 17,126,460 | $1,286,624 | $0.0751 | $/kwh |
| Oct17 - Sep18 | 17,221,560 | $1,288,381 | $0.0748 | $/kwh |
| AVG cooling (2018) | 1,485,660 | | | |
| COOLING TOTAL (6mon) | 8,913,960 | | | |

SQFT 188,574

| AVERAGE USAGE PER MONTH | | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh |
|---|---|---|---|---|---|---|---|---|---|---|
| | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | |
| 1 | | 2,436 | 1,487 | 2,388 | | 3,777 | 730 | | | 1,391,685 |
| 2 | | 2,878 | 1,653 | 2,400 | | 3,692 | 785 | | | 1,272,210 |
| 3 | | 2,746 | 1,427 | 2,353 | | 3,539 | 766 | | | 1,299,210 |
| 4 | | 2,743 | 1,642 | 2,458 | | 3,460 | 800 | | | 1,484,760 |
| 5 | | 2,491 | 1,538 | 2,308 | | 3,216 | 787 | | | 1,289,980 |
| 6 | | 2,582 | 1,574 | 2,377 | | 3,272 | 714 | | | 1,328,320 |
| 7 | | 2,846 | 1,822 | 2,403 | | 3,234 | 813 | | | 1,339,000 |
| 8 | | 2,740 | 1,637 | 2,453 | | 3,256 | 784 | | | 1,447,840 |
| 9 | | 2,272 | 1,507 | 2,337 | | 3,261 | 756 | | | 1,316,800 |
| 10 | | 2,678 | 1,680 | 2,715 | | 3,354 | 929 | | | 1,154,550 |
| 11 | | 2,455 | 1,514 | 2,409 | | 3,401 | 800 | | | 1,396,170 |
| 12 | | 2,295 | 1,458 | 2,155 | | 3,453 | 743 | | | 1,368,885 |

| | | |
|---|---|---|
| | AVG per cooling month | 1,367,783 |
| | COOLING TOTAL (6mon) | 8,206,700 |

| DIST DEMAND | DEMAND | | kwh $ |
|---|---|---|---|
| $ 1,675.13 | $ 4,041.64 | $ 5,716.77 | $95,705.12 |
| $ 0.470 | $ 1.784 | $ 2.52 | $0.068 |

| YEAR | Bill Days | *Transaction $ Amount | Metered kW | | Power Supply kW | | Dist kW | RkVa | kWh | | Total kWh | $/kwh | kwh/sqft | $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | On Peak/Off Peak | | On Peak/Off Peak | | | | On Peak/Off Peak | | | | | |
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2015** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |
| **2016** | 245 | $ 662,590 | 17,334 | 13,072 | 18,016 | - | 22,349 | 6,280 | - | - | 9,421,050 | | 74.4 | $ 5.23 |
| **2017** | 365 | $ 1,259,381 | 32,857 | 19,260 | 29,484 | - | 41,647 | 9,677 | - | - | 16,487,430 | $ 0.0764 | 87.4 | $ 6.68 |
| **2018** | 270 | $ 958,799 | 25,060 | 13,619 | 21,887 | - | 34,067 | 6,711 | - | - | 12,992,280 | | 93.1 | $ 6.87 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | | - | $ - |

| Month | Read Date | Bill Days | *Transaction $ Amount | Metered kW On Peak/Off Peak | | Power Supply kW On Peak/Off Peak | | Dist kW | RkVa | kWh On Peak/Off Peak | | Total kWh | $/kwh | rolling 12m kWh | rolling 12m $ | rolling 12m $/kWh | MONTH |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sep-2015 | 10/5/2015 | 31 | $53,644 | 1445 | 1446 | 1447 | 0 | 1807 | 878 | 0 | 0 | 907,200 | $0.0591 | | | | 9 |
| Oct-2015 | 11/4/2015 | 30 | $48,554 | 1358 | 1254 | 1395 | 0 | 1807 | 843 | 0 | 0 | 788,400 | $0.0616 | | | | 10 |
| Nov-2015 | 12/7/2015 | 33 | $53,250 | 1277 | 1267 | 1416 | 0 | 1807 | 740 | 0 | 0 | 853,200 | $0.0624 | | | | 11 |
| Dec-2015 | 1/8/2016 | 32 | $52,145 | 1408 | 1423 | 1424 | 0 | 1807 | 874 | 0 | 0 | 840,000 | $0.0621 | | | | 12 |
| Jan-2016 | 2/5/2016 | 28 | $44,527 | 1254 | 1255 | 1431 | 0 | 1807 | 784 | 0 | 0 | 693,000 | $0.0643 | | | | 1 |
| Feb-2016 | 3/8/2016 | 32 | $50,971 | 1390 | 1300 | 1436 | 0 | 1807 | 862 | 0 | 0 | 795,000 | $0.0641 | | | | 2 |
| Mar-2016 | 4/7/2016 | 30 | $47,895 | 1250 | 1257 | 1401 | 0 | 1807 | 830 | 0 | 0 | 763,800 | $0.0627 | | | | 3 |
| Apr-2016 | 5/6/2016 | 29 | $45,974 | 1250 | 1243 | 1407 | 0 | 1807 | 727 | 0 | 0 | 724,200 | $0.0635 | | | | 4 |
| May-2016 | 6/7/2016 | 32 | $51,921 | 1409 | 1405 | 1409 | 0 | 1807 | 876 | 0 | 0 | 840,000 | $0.0618 | | | | 5 |
| Jun-2016 | 7/7/2016 | 30 | $51,557 | 1490 | 1476 | 1493 | 0 | 1807 | 883 | 0 | 0 | 846,000 | $0.0609 | | | | 6 |
| Jul-2016 | 8/5/2016 | 29 | $53,678 | 1526 | 1531 | 1531 | 0 | 1807 | 898 | 0 | 0 | 933,600 | $0.0575 | | | | 7 |
| Aug-2016 | 9/2/2016 | 28 | $51,830 | 1553 | 1538 | 1553 | 0 | 1807 | 893 | 0 | 0 | 891,600 | $0.0581 | 9,876,000 | $605,946 | $0.0614 | 8 |
| Sep-2016 | 10/5/2016 | 33 | $57,053 | 1462 | 1456 | 1463 | 0 | 1807 | 896 | 0 | 0 | 963,600 | $0.0592 | 9,932,400 | $609,354 | $0.0614 | 9 |
| Oct-2016 | 11/2/2016 | 28 | $45,459 | 1269 | 1311 | 1412 | 0 | 1807 | 844 | 0 | 0 | 737,400 | $0.0616 | 9,881,400 | $606,259 | $0.0614 | 10 |
| Nov-2016 | 12/6/2016 | 34 | $54,544 | 1231 | 1239 | 1431 | 0 | 1807 | 726 | 0 | 0 | 867,600 | $0.0629 | 9,895,800 | $607,552 | $0.0614 | 11 |
| Dec-2016 | 1/7/2017 | 32 | $51,015 | 1239 | 1215 | 1432 | 0 | 1807 | 784 | 0 | 0 | 805,200 | $0.0634 | 9,861,000 | $606,422 | $0.0615 | 12 |
| Jan-2017 | 2/6/2017 | 30 | $46,950 | 1195 | 1179 | 1431 | 0 | 1807 | 743 | 0 | 0 | 727,800 | $0.0645 | 9,895,800 | $608,845 | $0.0615 | 1 |
| Feb-2017 | 3/7/2017 | 29 | $45,692 | 1236 | 1221 | 1428 | 0 | 1807 | 809 | 0 | 0 | 714,600 | $0.0639 | 9,815,400 | $603,566 | $0.0615 | 2 |
| Mar-2017 | 4/5/2017 | 29 | $45,590 | 1211 | 1223 | 1427 | 0 | 1807 | 747 | 0 | 0 | 711,600 | $0.0641 | 9,763,200 | $601,262 | $0.0616 | 3 |
| Apr-2017 | 5/8/2017 | 33 | $53,565 | 1391 | 1410 | 1429 | 0 | 1807 | 880 | 0 | 0 | 868,200 | $0.0617 | 9,907,200 | $608,853 | $0.0615 | 4 |
| May-2017 | 6/7/2017 | 30 | $48,090 | 1374 | 1352 | 1406 | 0 | 1807 | 866 | 0 | 0 | 777,600 | $0.0618 | 9,844,800 | $605,022 | $0.0615 | 5 |
| Jun-2017 | 7/7/2017 | 30 | $52,080 | 1447 | 1457 | 1457 | 0 | 1807 | 888 | 0 | 0 | 877,200 | $0.0594 | 9,876,000 | $605,546 | $0.0613 | 6 |
| Jul-2017 | 8/4/2017 | 28 | $51,718 | 1512 | 1503 | 1515 | 0 | 1807 | 921 | 0 | 0 | 859,200 | $0.0602 | 9,801,600 | $603,586 | $0.0616 | 7 |
| Aug-2017 | 9/5/2017 | 32 | $57,592 | 1485 | 1496 | 1496 | 0 | 1807 | 916 | 0 | 0 | 945,000 | $0.0609 | 9,855,000 | $609,348 | $0.0618 | 8 |
| Sep-2017 | 10/4/2017 | 29 | $49,169 | 1421 | 1396 | 1421 | 0 | 1807 | 887 | 0 | 0 | 789,600 | $0.0623 | 9,681,000 | $601,464 | $0.0621 | 9 |
| Oct-2017 | 11/3/2017 | 30 | $50,534 | 1439 | 1416 | 1442 | 0 | 1807 | 892 | 0 | 0 | 798,000 | $0.0633 | 9,741,600 | $606,539 | $0.0623 | 10 |
| Nov-2017 | 12/7/2017 | 34 | $55,269 | 1227 | 1220 | 1395 | 0 | 1807 | 790 | 0 | 0 | 865,800 | $0.0638 | 9,739,800 | $607,264 | $0.0623 | 11 |
| Dec-2017 | 1/6/2018 | 30 | $47,648 | 1172 | 1188 | 1396 | 0 | 1807 | 755 | 0 | 0 | 725,400 | $0.0657 | 9,660,000 | $603,897 | $0.0625 | 12 |
| Jan-2018 | 2/6/2018 | 31 | $48,763 | 1260 | 1247 | 1394 | 0 | 1807 | 749 | 0 | 0 | 733,800 | $0.0665 | 9,666,000 | $605,710 | $0.0627 | 1 |
| Feb-2018 | 3/6/2018 | 28 | $45,471 | 1230 | 1243 | 1388 | 0 | 1807 | 752 | 0 | 0 | 708,600 | $0.0642 | 9,660,000 | $605,488 | $0.0627 | 2 |
| Mar-2018 | 4/5/2018 | 30 | $47,355 | 1231 | 1227 | 1393 | 0 | 1807 | 739 | 0 | 0 | 715,200 | $0.0662 | 9,663,600 | $607,252 | $0.0628 | 3 |
| Apr-2018 | 5/7/2018 | 32 | $50,925 | 1215 | 1229 | 1372 | 0 | 1807 | 749 | 0 | 0 | 786,600 | $0.0647 | 9,582,000 | $604,612 | $0.0631 | 4 |
| May-2018 | 6/6/2018 | 30 | $50,854 | 1405 | 1394 | 1405 | 0 | 1807 | 895 | 0 | 0 | 820,800 | $0.0620 | 9,625,200 | $607,377 | $0.0631 | 5 |
| Jun-2018 | 7/5/2018 | 29 | $53,151 | 1479 | 1476 | 1483 | 0 | 1807 | 919 | 0 | 0 | 876,000 | $0.0607 | 9,624,000 | $608,447 | $0.0632 | 6 |
| Jul-2018 | 8/3/2018 | 29 | $55,960 | 1484 | 1575 | 1575 | 0 | 1830 | 917 | 0 | 0 | 867,600 | $0.0645 | 9,632,400 | $612,689 | $0.0636 | 7 |
| Aug-2018 | 9/5/2018 | 33 | $63,327 | 1478 | 1481 | 1481 | 0 | 1830 | 928 | 0 | 0 | 1,027,800 | $0.0616 | 9,715,200 | $618,424 | $0.0637 | 8 |

6106311225 - New Arrivals Bldg/ORF
9252884094 - Arrivals Bldg MDS2/ORF

Sep17 - Aug18 9,715,200 $618,424 $0.0637 $/kwh
Garage A Lighting 705,733 kwh/year
864,989
3,459,956


| SQFT | SQFT |
|---|---|
| 76,850 | 124,055 |

| AVERAGE USAGE PER MONTH | | Metered kW On Peak/Off | | Power Supply kW On Peak/Off | | Dist kW | RkVa |
|---|---|---|---|---|---|---|---|
| 1 | | 1,236 | 1,227 | 1,419 | | 1,807 | 759 |
| 2 | | 1,285 | 1,255 | 1,417 | | 1,807 | 808 |
| 3 | | 1,231 | 1,236 | 1,407 | | 1,807 | 772 |
| 4 | | 1,285 | 1,294 | 1,403 | | 1,807 | 785 |
| 5 | | 1,396 | 1,384 | 1,407 | | 1,807 | 879 |
| 6 | | 1,472 | 1,470 | 1,478 | | 1,807 | 897 |
| 7 | | 1,507 | 1,536 | 1,540 | | 1,815 | 912 |
| 8 | | 1,505 | 1,505 | 1,510 | | 1,815 | 912 |
| 9 | | 1,443 | 1,433 | 1,444 | | 1,807 | 887 |
| 10 | | 1,355 | 1,327 | 1,416 | | 1,807 | 860 |
| 11 | | 1,245 | 1,242 | 1,414 | | 1,807 | 752 |
| 12 | | 1,273 | 1,275 | 1,417 | | 1,807 | 804 |

| AVG per cooling month (2018) | |
|---|---|
| Garage A | COOLING TOTAL (4mon) |
| 58,811 | 659,389 |
| 58,811 | 680,589 |
| 58,811 | 671,389 |
| 58,811 | 734,189 |
| 58,811 | 753,989 |
| 58,811 | 807,589 |
| 58,811 | 827,989 |
| 58,811 | 895,989 |
| 58,811 | 827,989 |
| 58,811 | 715,789 |
| 58,811 | 803,389 |
| 58,811 | 731,389 |

AVG per cooling month 839,889
COOLING TOTAL (4mon) 3,359,556

| YEAR | Bill Days | *Transaction $ Amount | Metered kW On Peak/Off Peak | | Power Supply kW On Peak/Off Peak | | Dist kW | RkVa | kWh On Peak/Off Peak | | Total kWh | $/kwh | ARRIVALS | Cooling Only (4 months) | $/kwh (total) | Garage Lighting Cost | ARRIVALS ONLY kwh/sqft | ARRIVALS ONLY $/sqft |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **2014** | 0 | $ - | - | - | - | - | - | - | - | - | - | - | - | | | | - | $ - |
| **2015** | 126 | $ 207,594 | 5,488 | 5,390 | 5,682 | - | 7,228 | 3,335 | - | - | 3,388,800 | 243,623 | 3,145,177 | 848,389 | $ 0.0613 | $ 14,924 | 118.6 | $ 7.25 |
| **2016** | 365 | $ 606,422 | 16,323 | 16,226 | 17,399 | - | 21,684 | 10,003 | - | - | 9,861,000 | 705,733 | 9,155,267 | 3,399,556 | $ 0.0615 | $ 43,400 | 119.1 | $ 7.32 |
| **2017** | 364 | $ 603,897 | 16,110 | 16,061 | 17,243 | - | 21,684 | 10,094 | - | - | 9,660,000 | 703,799 | 8,956,201 | 3,235,756 | $ 0.0625 | $ 43,998 | 116.9 | $ 7.31 |
| **2018** | 242 | $ 415,805 | 10,782 | 10,872 | 11,491 | - | 14,502 | 6,648 | - | - | 6,536,400 | 467,911 | 6,068,489 | 3,459,956 | $ 0.0636 | $ 29,766 | 119.1 | $ 7.59 |
| **2019** | 0 | $ - | - | - | - | - | - | - | - | - | - | - | - | | | | | |



# BOILER NATURAL GAS SERVICE

**Site:** **NORFOLK AIRPORT AUTHORITY**
**Address:** NORFOLK, VA
**Delivery:**
**Supplier:**

| | Month | Billing Period Start Date | Billing Period End Date | Days | 1 mcf = 1.025 NG Consumption (mcf) | 1 mcf = 1.025 MMBTU Consumption (MMBTU) | MT BOILER GAS 1 mcf = 1.025 NG Consumption (mcf) | MT BOILER GAS 1 mcf = 1.025 MMBTU Consumption (MMBTU) | AV BOILER GAS 1 mcf = 1.025 NG Consumption (mcf) | AV BOILER GAS 1 mcf = 1.025 MMBTU Consumption (MMBTU) |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Jan-2017 | 1/1/2017 | 2/1/2017 | 31 | 8,244 | 8,451 | 7,608 | 7,798 | 636 | 652 |
| 2 | Feb-2017 | 2/1/2017 | 3/1/2017 | 28 | 6,329 | 6,487 | 5,841 | 5,987 | 488 | 500 |
| 3 | Mar-2017 | 3/1/2017 | 4/1/2017 | 31 | 7,582 | 7,772 | 6,706 | 6,873 | 877 | 898 |
| 4 | Apr-2017 | 4/1/2017 | 5/1/2017 | 30 | 2,549 | 2,612 | 1,669 | 1,711 | 879 | 901 |
| 5 | May-2017 | 5/1/2017 | 6/1/2017 | 31 | 1,149 | 1,178 | 894 | 916 | 255 | 261 |
| 6 | Jun-2017 | 6/1/2017 | 7/1/2017 | 30 | 164 | 168 | - | - | 164 | 168 |
| 7 | Jul-2017 | 7/1/2017 | 8/1/2017 | 31 | 146 | 150 | - | - | 146 | 150 |
| 8 | Aug-2017 | 8/1/2017 | 9/1/2017 | 31 | 270 | 277 | - | - | 270 | 277 |
| 9 | Sep-2017 | 9/1/2017 | 10/1/2017 | 30 | 160 | 164 | - | - | 160 | 164 |
| 10 | Oct-2017 | 10/1/2017 | 11/1/2017 | 31 | 874 | 896 | 657 | 673 | 217 | 223 |
| 11 | Nov-2017 | 11/1/2017 | 12/1/2017 | 30 | 3,046 | 3,122 | 1,368 | 1,402 | 1,679 | 1,721 |
| 12 | Dec-2017 | 12/1/2017 | 1/1/2018 | 31 | 6,111 | 6,263 | 2,011 | 2,061 | 4,100 | 4,203 |
| 1 | Jan-2018 | 1/1/2018 | 2/1/2018 | 31 | 4,874 | 4,996 | 4,768 | 4,887 | 107 | 109 |
| 2 | Feb-2018 | 2/1/2018 | 3/1/2018 | 28 | 8,220 | 8,425 | 2,643 | 2,709 | 5,577 | 5,716 |
| 3 | Mar-2018 | 3/1/2018 | 4/1/2018 | 31 | 3,861 | 3,958 | 3,253 | 3,334 | 609 | 624 |
| 4 | Apr-2018 | 4/1/2018 | 5/1/2018 | 30 | 2,840 | 2,911 | 2,402 | 2,462 | 438 | 449 |
| 5 | May-2018 | 5/1/2018 | 6/1/2018 | 31 | 3,479 | 3,566 | 441 | 452 | 3,038 | 3,114 |
| 6 | Jun-2018 | 6/1/2018 | 7/1/2018 | 30 | 2,407 | 2,467 | - | - | 2,407 | 2,467 |
| 7 | Jul-2018 | 7/1/2018 | 8/1/2018 | 31 | 1,729 | 1,772 | - | - | 1,729 | 1,772 |
| 8 | Aug-2018 | 8/1/2018 | 9/1/2018 | | - | - | - | - | | - |
| 9 | Sep-2018 | 9/1/2018 | 10/1/2018 | | - | - | - | - | | - |
| 10 | Oct-2018 | 10/1/2018 | 11/1/2018 | | - | - | - | - | | - |
| 11 | Nov-2018 | 11/1/2018 | 12/1/2018 | | - | - | - | - | | - |
| 12 | Dec-2018 | 12/1/2018 | 1/1/2019 | | - | - | - | - | | - |

| 2,750 | 584 |
|---|---|

| YEAR | TOTAL DAYS | Consumption (mcf) | Consumption (MMBTU) | MT BOILER GAS Consumption (mcf) | MT BOILER GAS Consumption (MMBTU) | AV BOILER GAS Consumption (mcf) | AV BOILER GAS Consumption (MMBTU) |
|---|---|---|---|---|---|---|---|
| **2014** | 365 | 56,936 | 58,360 | 18,639 | 19,105 | 38,297 | 39,254 |
| **2015** | 365 | 53,428 | 54,764 | 13,724 | 14,067 | 39,704 | 40,696 |
| **2016** | 366 | 24,019 | 24,620 | 19,521 | 20,009 | 4,498 | 4,611 |
| **2017** | 365 | 36,623 | 37,539 | 26,753 | 27,422 | 9,870 | 10,117 |
| **2018** | 212 | 27,410 | 28,095 | 13,505 | 13,843 | 13,905 | 14,252 |
| **2019** | | | | | | | |

| MONTH | | **AVERAGES** | | | | | |
|---|---|---|---|---|---|---|---|
| Jan | 1 | | 9,458 | 9,694 | 4,274 | 4,381 | 5,183 | 5,313 |
| Feb | 2 | | 7,000 | 7,175 | 2,978 | 3,053 | 4,022 | 4,122 |
| Mar | 3 | | 6,492 | 6,655 | 3,378 | 3,463 | 3,114 | 3,192 |
| Apr | 4 | | 4,631 | 4,746 | 1,717 | 1,760 | 2,913 | 2,986 |
| May | 5 | | 3,097 | 3,174 | 1,349 | 1,383 | 1,747 | 1,791 |
| Jun | 6 | | 887 | 909 | 8 | 9 | 878 | 900 |
| Jul | 7 | | 522 | 535 | - | - | 522 | 535 |
| Aug | 8 | | 216 | 221 | - | - | 269 | 221 |
| Sep | 9 | | 137 | 140 | - | - | 171 | 140 |
| Oct | 10 | | 510 | 523 | 282 | 290 | 285 | 234 |
| Nov | 11 | | 3,330 | 3,413 | 2,806 | 2,876 | 655 | 537 |
| Dec | 12 | | 3,405 | 3,490 | 1,635 | 1,676 | 2,212 | 1,814 |

| 2,263 | 2,319 |
|---|---|

# BOILER MMBTU CONSUMPTION


**THIS INCLUDES FUEL OIL AND NATURAL GAS**


**Site:** **NORFOLK AIRPORT AUTHORITY**
**Address:** NORFOLK, VA
**Delivery:**
**Supplier:**


| | | Month | Billing Period Start Date | Billing Period End Date | Days | TOTAL BOILER 1 MMBTU = 1 MMBTU Consumption (MMBTU) | TOTAL BOILER 1 MMBTU = 1 MMBTU Consumption (MMBTU) | MT BOILER MMBTU 1 MMBTU = 1 MMBTU Consumption (MMBTU) | MT BOILER MMBTU 1 MMBTU = 1 MMBTU Consumption (MMBTU) | difference previous year % | AV BOILER MMBTU 1 MMBTU = 1 MMBTU Consumption (MMBTU) | AV BOILER MMBTU 1 MMBTU = 1 MMBTU Consumption (MMBTU) | difference previous year % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Jan | 1 | Jan-2014 | 1/1/2014 | 2/1/2014 | 31 | 11,127 | 11,127 | 3,010 | 3,010 | | 8,117 | 8,117 | |
| Feb | 2 | Feb-2014 | 2/1/2014 | 3/1/2014 | 28 | 9,592 | 9,592 | 2,173 | 2,173 | | 7,419 | 7,419 | |
| Mar | 3 | Mar-2014 | 3/1/2014 | 4/1/2014 | 31 | 10,237 | 10,237 | 2,352 | 2,352 | | 7,884 | 7,884 | |
| Apr | 4 | Apr-2014 | 4/1/2014 | 5/1/2014 | 30 | 10,450 | 10,450 | 2,354 | 2,354 | | 8,095 | 8,095 | |
| May | 5 | May-2014 | 5/1/2014 | 6/1/2014 | 31 | 5,120 | 5,120 | 3,749 | 3,749 | | 1,370 | 1,370 | |
| Jun | 6 | Jun-2014 | 6/1/2014 | 7/1/2014 | 30 | 550 | 550 | - | - | | 550 | 550 | |
| Jul | 7 | Jul-2014 | 7/1/2014 | 8/1/2014 | 31 | 586 | 586 | - | - | | 586 | 586 | |
| Aug | 8 | Aug-2014 | 8/1/2014 | 9/1/2014 | 31 | 654 | 654 | - | - | | 654 | 654 | |
| Sep | 9 | Sep-2014 | 9/1/2014 | 10/1/2014 | 30 | 218 | 218 | - | - | | 218 | 218 | |
| Oct | 10 | Oct-2014 | 10/1/2014 | 11/1/2014 | 31 | 845 | 845 | 624 | 624 | | 221 | 221 | |
| Nov | 11 | Nov-2014 | 11/1/2014 | 12/1/2014 | 30 | 2,637 | 2,637 | 2,308 | 2,308 | | 329 | 329 | |
| Dec | 12 | Dec-2014 | 12/1/2014 | 1/1/2015 | 31 | 6,343 | 6,343 | 2,534 | 2,534 | | 3,809 | 3,809 | |
| | 1 | Jan-2015 | 1/1/2015 | 2/1/2015 | 31 | 18,005 | 18,005 | 1,144 | 1,144 | -62.00% | 16,861 | 16,861 | 107.7% |
| | 2 | Feb-2015 | 2/1/2015 | 3/1/2015 | 28 | 8,979 | 8,979 | 2,290 | 2,290 | 5.4% | 6,689 | 6,689 | -9.85% |
| | 3 | Mar-2015 | 3/1/2015 | 4/1/2015 | 31 | 7,970 | 7,970 | 1,984 | 1,984 | -15.67% | 5,986 | 5,986 | -24.08% |
| | 4 | Apr-2015 | 4/1/2015 | 5/1/2015 | 30 | 5,399 | 5,399 | 257 | 257 | -89.06% | 5,141 | 5,141 | -36.49% |
| | 5 | May-2015 | 5/1/2015 | 6/1/2015 | 31 | 3,913 | 3,913 | 36 | 36 | -99.04% | 3,878 | 3,878 | 182.9% |
| | 6 | Jun-2015 | 6/1/2015 | 7/1/2015 | 30 | 1,135 | 1,135 | - | - | | 1,135 | 1,135 | 106.1% |
| | 7 | Jul-2015 | 7/1/2015 | 8/1/2015 | 31 | 30 | 30 | - | - | | 30 | 30 | -94.88% |
| | 8 | Aug-2015 | 8/1/2015 | 9/1/2015 | 31 | 41 | 41 | - | - | | 41 | 41 | -93.70% |
| | 9 | Sep-2015 | 9/1/2015 | 10/1/2015 | 30 | 70 | 70 | - | - | | 70 | 70 | -67.79% |
| | 10 | Oct-2015 | 10/1/2015 | 11/1/2015 | 31 | 629 | 629 | 135 | 135 | -78.32% | 493 | 493 | 122.8% |
| | 11 | Nov-2015 | 11/1/2015 | 12/1/2015 | 30 | 8,415 | 8,415 | 8,067 | 8,067 | 249.5% | 348 | 348 | 5.9% |
| | 12 | Dec-2015 | 12/1/2015 | 1/1/2016 | 31 | 1,254 | 1,254 | 784 | 784 | -69.07% | 470 | 470 | -87.66% |
| | 1 | Jan-2016 | 1/1/2016 | 2/1/2016 | 31 | 5,891 | 5,891 | 5,067 | 5,067 | 342.9% | 824 | 824 | -95.11% |
| | 2 | Feb-2016 | 2/1/2016 | 3/1/2016 | 29 | 3,469 | 3,469 | 2,734 | 2,734 | 19.4% | 734 | 734 | -89.02% |
| | 3 | Mar-2016 | 3/1/2016 | 4/1/2016 | 31 | 3,338 | 3,338 | 2,769 | 2,769 | 39.6% | 568 | 568 | -90.51% |
| | 4 | Apr-2016 | 4/1/2016 | 5/1/2016 | 30 | 2,360 | 2,360 | 2,016 | 2,016 | 683.1% | 344 | 344 | -93.32% |
| | 5 | May-2016 | 5/1/2016 | 6/1/2016 | 31 | 2,093 | 2,093 | 1,760 | 1,760 | 4806.3% | 333 | 333 | -91.42% |
| | 6 | Jun-2016 | 6/1/2016 | 7/1/2016 | 30 | 224 | 224 | 43 | 43 | | 181 | 181 | -84.02% |
| | 7 | Jul-2016 | 7/1/2016 | 8/1/2016 | 31 | 135 | 135 | - | - | | 135 | 135 | 350.2% |
| | 8 | Aug-2016 | 8/1/2016 | 9/1/2016 | 31 | 133 | 133 | - | - | | 133 | 133 | 223.9% |
| | 9 | Sep-2016 | 9/1/2016 | 10/1/2016 | 30 | 250 | 250 | - | - | | 250 | 250 | 255.2% |
| | 10 | Oct-2016 | 10/1/2016 | 11/1/2016 | 31 | 329 | 329 | 15 | 15 | -88.55% | 314 | 314 | -36.44% |
| | 11 | Nov-2016 | 11/1/2016 | 12/1/2016 | 30 | 2,892 | 2,892 | 2,603 | 2,603 | -67.73% | 288 | 288 | -17.21% |
| | 12 | Dec-2016 | 12/1/2016 | 1/1/2017 | 31 | 3,589 | 3,589 | 3,001 | 3,001 | 282.9% | 589 | 589 | 25.2% |
| | 1 | Jan-2017 | 1/1/2017 | 2/1/2017 | 31 | 8,451 | 8,451 | 7,798 | 7,798 | 53.9% | 652 | 652 | -20.88% |
| | 2 | Feb-2017 | 2/1/2017 | 3/1/2017 | 28 | 2,976 | 2,976 | 5,987 | 5,987 | 118.9% | 500 | 500 | -31.92% |
| | 3 | Mar-2017 | 3/1/2017 | 4/1/2017 | 31 | 7,772 | 7,772 | 6,873 | 6,873 | 148.2% | 898 | 898 | 58.1% |
| | 4 | Apr-2017 | 4/1/2017 | 5/1/2017 | 30 | 2,612 | 2,612 | 1,711 | 1,711 | -15.15% | 901 | 901 | 162.3% |
| | 5 | May-2017 | 5/1/2017 | 6/1/2017 | 31 | 1,178 | 1,178 | 916 | 916 | -47.93% | 261 | 261 | -21.42% |
| | 6 | Jun-2017 | 6/1/2017 | 7/1/2017 | 30 | 168 | 168 | - | - | -100.00% | 168 | 168 | -7.57% |
| | 7 | Jul-2017 | 7/1/2017 | 8/1/2017 | 31 | 150 | 150 | - | - | | 150 | 150 | 10.8% |
| | 8 | Aug-2017 | 8/1/2017 | 9/1/2017 | 31 | 277 | 277 | - | - | | 277 | 277 | 107.2% |
| | 9 | Sep-2017 | 9/1/2017 | 10/1/2017 | 30 | 164 | 164 | - | - | | 164 | 164 | -34.39% |
| | 10 | Oct-2017 | 10/1/2017 | 11/1/2017 | 31 | 929 | 929 | 673 | 673 | 4250.3% | 256 | 256 | -18.40% |
| | 11 | Nov-2017 | 11/1/2017 | 12/1/2017 | 30 | 3,122 | 3,122 | 1,402 | 1,402 | -46.15% | 1,721 | 1,721 | 496.5% |
| | 12 | Dec-2017 | 12/1/2017 | 1/1/2018 | 31 | 6,290 | 6,290 | 2,087 | 2,087 | -30.44% | 4,203 | 4,203 | 614.1% |
| | 1 | Jan-2018 | 1/1/2018 | 2/1/2018 | 31 | 4,996 | 4,996 | 4,887 | 4,887 | -37.34% | 109 | 109 | -83.25% |
| | 2 | Feb-2018 | 2/1/2018 | 3/1/2018 | 28 | 8,425 | 8,425 | 2,709 | 2,709 | -54.76% | 5,716 | 5,716 | 1043.8% |
| | 3 | Mar-2018 | 3/1/2018 | 4/1/2018 | 31 | 3,958 | 3,958 | 3,334 | 3,334 | -51.50% | 624 | 624 | -30.54% |
| | 4 | Apr-2018 | 4/1/2018 | 5/1/2018 | 30 | 2,911 | 2,911 | 2,462 | 2,462 | 43.9% | 449 | 449 | -50.15% |
| | 5 | May-2018 | 5/1/2018 | 6/1/2018 | 31 | 3,566 | 3,566 | 452 | 452 | -50.69% | 3,114 | 3,114 | 1091.8% |
| | 6 | Jun-2018 | 6/1/2018 | 7/1/2018 | 30 | 2,467 | 2,467 | - | - | | 2,467 | 2,467 | 1372.2% |
| | 7 | Jul-2018 | 7/1/2018 | 8/1/2018 | 31 | 1,772 | 1,772 | - | - | | 1,772 | 1,772 | 1083.4% |
| | 8 | Aug-2018 | 8/1/2018 | 9/1/2018 | | - | - | - | - | | - | - | -100.00% |
| | 9 | Sep-2018 | 9/1/2018 | 10/1/2018 | | - | - | - | - | | - | - | -100.00% |
| | 10 | Oct-2018 | 10/1/2018 | 11/1/2018 | | - | - | - | - | -100.00% | - | - | -100.00% |
| | 11 | Nov-2018 | 11/1/2018 | 12/1/2018 | | - | - | - | - | -100.00% | - | - | -100.00% |
| | 12 | Dec-2018 | 12/1/2018 | 1/1/2019 | | - | - | - | - | -100.00% | - | - | -100.00% |

| YEAR | TOTAL DAYS | ORF BOILER MMBTU Consumption (MMBTU) | ORF BOILER MMBTU Consumption (MMBTU) | MT BOILER MMBTU Consumption (MMBTU) | MT BOILER MMBTU Consumption (MMBTU) | AV BOILER MMBTU Consumption (MMBTU) | AV BOILER MMBTU Consumption (MMBTU) |
|---|---|---|---|---|---|---|---|
| **2014** | 365 | 58,360 | 58,360 | 19,105 | 19,105 | 39,254 | 39,254 |
| **2015** | 365 | 55,840 | 55,840 | 14,697 | 14,697 | 41,143 | 41,143 |
| **2016** | 366 | 24,702 | 24,702 | 20,009 | 20,009 | 4,693 | 4,693 |
| **2017** | 365 | 34,088 | 34,088 | 27,448 | 27,448 | 10,150 | 10,150 |
| **2018** | 212 | 28,095 | 28,095 | 13,843 | 13,843 | 14,252 | 14,252 |
| **2019** | | | | | | | |

| | MONTH | | | | | |
|---|---|---|---|---|---|---|
| Jan | 1 | 9,694 | 9,694 | 4,381 | 4,381 | 5,313 | 5,313 |
| Feb | 2 | 6,688 | 6,688 | 2,477 | 2,477 | 4,212 | 4,212 |
| Mar | 3 | 6,655 | 6,655 | 3,463 | 3,463 | 3,192 | 3,192 |
| Apr | 4 | 4,746 | 4,746 | 1,760 | 1,760 | 2,986 | 2,986 |
| May | 5 | 3,174 | 3,174 | 1,383 | 1,383 | 1,791 | 1,791 |
| Jun | 6 | 909 | 909 | 9 | 9 | 900 | 900 |
| Jul | 7 | 535 | 535 | - | - | 535 | 535 |
| Aug | 8 | 221 | 221 | - | - | 221 | 221 |
| Sep | 9 | 140 | 140 | - | - | 140 | 140 |
| Oct | 10 | 546 | 546 | 290 | 290 | 257 | 257 |
| Nov | 11 | 3,413 | 3,413 | 2,876 | 2,876 | 537 | 537 |
| Dec | 12 | 3,495 | 3,495 | 1,681 | 1,681 | 1,814 | 1,814 |


Natural Gas Usage - Norfolk Airport
(MMBTU)
MT BOILER GAS
AV BOILER GAS
Total ($/MMBTU)
Consumption (Therms)
9,000
8,000
7,000
6,000
5,000
4,000
3,000
2,000
1,000
-
$6.000
$5.000
$4.000
$3.000
$2.000
$1.000
$-
Jan-17
Feb-17
Mar-17
Apr-17
May-17
Jun-17
Jul-17
Aug-17
Sep-17
Oct-17
Nov-17
Dec-17


Boiler Gas Usage - Norfolk Airport
MT BOILER GAS
AV BOILER GAS
Consumption (MMBTU)
45,000
40,000
35,000
30,000
25,000
20,000
15,000
10,000
5,000
-
Jan-14
Mar-14
May-14
Jul-14
Sep-14
Nov-14
Jan-15
Mar-15
May-15
Jul-15
Sep-15
Nov-15
Jan-16
Mar-16
May-16
Jul-16
Sep-16
Nov-16
Jan-17
Mar-17
May-17
Jul-17
Sep-17
Nov-17
Jan-18


Norfolk Airport - Average Monthly Boiler Usage
ORF BOILER MMBTU
MT BOILER MMBTU
AV BOILER MMBTU
MMBTU
12,000
10,000
8,000
6,000
4,000
2,000
-
Jan
Feb
Mar
Apr
May
Jun
Jul
Aug
Sep
Oct
Nov
Dec

## FUEL OIL SERVICE

**Site:** **NORFOLK AIRPORT AUTHORITY**
**Address:** NORFOLK, VA
**Delivery:**
**Supplier:**

| | Month | Billing Period Start Date | Billing Period End Date | Days | 1 GAL = 0.141 #2 FUEL OIL Consumption (GALLONS) | 1 GAL = 0.141 #2 FUEL OIL Consumption (MMBTU) | MT BOILER OIL 1 GAL = 0.141 #2 FUEL OIL Consumption (GALLONS) | MT BOILER OIL 1 GAL = 0.141 #2 FUEL OIL Consumption (MMBTU) | AV BOILER OIL 1 GAL = 0.141 #2 FUEL OIL Consumption (GALLONS) | AV BOILER OIL 1 GAL = 0.141 #2 FUEL OIL Consumption (MMBTU) |
|---|---|---|---|---|---|---|---|---|---|---|
| Jan | Jan-2014 | 1/1/2014 | 2/1/2014 | 31 | - | - | - | - | | - |
| Feb | Feb-2014 | 2/1/2014 | 3/1/2014 | 28 | - | - | | - | | - |
| Mar | Mar-2014 | 3/1/2014 | 4/1/2014 | 31 | - | - | - | - | | - |
| Apr | Apr-2014 | 4/1/2014 | 5/1/2014 | 30 | - | - | - | - | | - |
| May | May-2014 | 5/1/2014 | 6/1/2014 | 31 | - | - | - | - | | - |
| Jun | Jun-2014 | 6/1/2014 | 7/1/2014 | 30 | - | - | - | - | | - |
| Jul | Jul-2014 | 7/1/2014 | 8/1/2014 | 31 | - | - | - | - | | - |
| Aug | Aug-2014 | 8/1/2014 | 9/1/2014 | 31 | - | - | - | - | | - |
| Sep | Sep-2014 | 9/1/2014 | 10/1/2014 | 30 | - | - | - | - | | - |
| Oct | Oct-2014 | 10/1/2014 | 11/1/2014 | 31 | - | - | - | - | | - |
| Nov | Nov-2014 | 11/1/2014 | 12/1/2014 | 30 | - | - | - | - | | - |
| Dec | Dec-2014 | 12/1/2014 | 1/1/2015 | 31 | - | - | - | - | | - |
| | Jan-2015 | 1/1/2015 | 2/1/2015 | 31 | - | - | - | - | | - |
| | Feb-2015 | 2/1/2015 | 3/1/2015 | 28 | 7,633 | 1,076 | 4,468 | 630 | 3,165 | 446 |
| | Mar-2015 | 3/1/2015 | 4/1/2015 | 31 | - | - | - | - | | - |
| | Apr-2015 | 4/1/2015 | 5/1/2015 | 30 | - | - | - | - | | - |
| | May-2015 | 5/1/2015 | 6/1/2015 | 31 | - | - | - | - | | - |
| | Jun-2015 | 6/1/2015 | 7/1/2015 | 30 | - | - | - | - | | - |
| | Jul-2015 | 7/1/2015 | 8/1/2015 | 31 | - | - | - | - | | - |
| | Aug-2015 | 8/1/2015 | 9/1/2015 | 31 | - | - | - | - | | - |
| | Sep-2015 | 9/1/2015 | 10/1/2015 | 30 | - | - | - | - | | - |
| | Oct-2015 | 10/1/2015 | 11/1/2015 | 31 | - | - | - | - | | - |
| | Nov-2015 | 11/1/2015 | 12/1/2015 | 30 | - | - | - | - | | - |
| | Dec-2015 | 12/1/2015 | 1/1/2016 | 31 | - | - | - | - | | - |
| | Jan-2016 | 1/1/2016 | 2/1/2016 | 31 | - | - | - | - | | - |
| | Feb-2016 | 2/1/2016 | 3/1/2016 | 29 | - | - | | - | | - |
| | Mar-2016 | 3/1/2016 | 4/1/2016 | 31 | - | - | - | - | | - |
| | Apr-2016 | 4/1/2016 | 5/1/2016 | 30 | - | - | - | - | | - |
| | May-2016 | 5/1/2016 | 6/1/2016 | 31 | - | - | - | - | | - |
| | Jun-2016 | 6/1/2016 | 7/1/2016 | 30 | - | - | - | - | | - |
| | Jul-2016 | 7/1/2016 | 8/1/2016 | 31 | - | - | - | - | | - |
| | Aug-2016 | 8/1/2016 | 9/1/2016 | 31 | - | - | - | - | | - |
| | Sep-2016 | 9/1/2016 | 10/1/2016 | 30 | - | - | - | - | | - |
| | Oct-2016 | 10/1/2016 | 11/1/2016 | 31 | 586 | 83 | - | - | 586 | 83 |
| | Nov-2016 | 11/1/2016 | 12/1/2016 | 30 | - | - | - | - | | - |
| | Dec-2016 | 12/1/2016 | 1/1/2017 | 31 | - | - | - | - | | - |
| | Jan-2017 | 1/1/2017 | 2/1/2017 | 31 | - | - | - | - | | - |
| | Feb-2017 | 2/1/2017 | 3/1/2017 | 28 | - | - | | - | | - |
| | Mar-2017 | 3/1/2017 | 4/1/2017 | 31 | - | - | - | - | | - |
| | Apr-2017 | 4/1/2017 | 5/1/2017 | 30 | - | - | - | - | | - |
| | May-2017 | 5/1/2017 | 6/1/2017 | 31 | - | - | - | - | | - |
| | Jun-2017 | 6/1/2017 | 7/1/2017 | 30 | - | - | - | - | | - |
| | Jul-2017 | 7/1/2017 | 8/1/2017 | 31 | - | - | - | - | | - |
| | Aug-2017 | 8/1/2017 | 9/1/2017 | 31 | - | - | - | - | | - |
| | Sep-2017 | 9/1/2017 | 10/1/2017 | 30 | - | - | - | - | | - |
| | Oct-2017 | 10/1/2017 | 11/1/2017 | 31 | 235 | 33 | - | - | 235 | 33 |
| | Nov-2017 | 11/1/2017 | 12/1/2017 | 30 | - | - | - | - | | - |
| | Dec-2017 | 12/1/2017 | 1/1/2018 | 31 | 187 | 26 | 187 | 26 | | - |
| | Jan-2018 | 1/1/2018 | 2/1/2018 | 31 | - | - | - | - | | - |
| | Feb-2018 | 2/1/2018 | 3/1/2018 | 28 | - | - | | - | | - |
| | Mar-2018 | 3/1/2018 | 4/1/2018 | 31 | - | - | - | - | | - |
| | Apr-2018 | 4/1/2018 | 5/1/2018 | 30 | - | - | - | - | | - |
| | May-2018 | 5/1/2018 | 6/1/2018 | 31 | - | - | - | - | | - |
| | Jun-2018 | 6/1/2018 | 7/1/2018 | 30 | - | - | - | - | | - |
| | Jul-2018 | 7/1/2018 | 8/1/2018 | 31 | - | - | - | - | | - |
| | Aug-2018 | 8/1/2018 | 9/1/2018 | | - | - | - | - | | - |
| | Sep-2018 | 9/1/2018 | 10/1/2018 | | - | - | - | - | | - |
| | Oct-2018 | 10/1/2018 | 11/1/2018 | | - | - | - | - | | - |
| | Nov-2018 | 11/1/2018 | 12/1/2018 | | - | - | - | - | | - |
| | Dec-2018 | 12/1/2018 | 1/1/2019 | | - | - | - | - | | - |

| YEAR | | | TOTAL DAYS | Consumption (GALLONS) | Consumption (MMBTU) | | MT BOILER OIL Consumption (GALLONS) | MT BOILER OIL Consumption (MMBTU) | | AV BOILER OIL Consumption (GALLONS) | AV BOILER OIL Consumption (MMBTU) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **2014** | | | 365 | - | - | | - | - | | - | - |
| **2015** | | | 365 | 7,633 | 1,076 | | 4,468 | 630 | | 3,165 | 446 |
| **2016** | | | 366 | 586 | 83 | | - | - | | 586 | 83 |
| **2017** | | | 365 | 422 | 60 | | 187 | 26 | | 235 | 33 |
| **2018** | | | 212 | - | - | | - | - | | - | - |
| **2019** | | | | | | | | | | | |

# PROPANE SERVICE

**FIRE STATION**

**Site:** **NORFOLK AIRPORT AUTHORITY**
**Address:** NORFOLK, VA
**Delivery:**
**Supplier:**

**Data from Natural gas Usage.xlsx Workbook**


**1 GAL = 0.091333**
PROPANE MMBTU

| | Month | Billing Period Start Date | Billing Period End Date | Days | Consumption (GALLONS) | Consumption (MMBTU) |
|---|---|---|---|---|---|---|
| 1 | Jan-2015 | 1/1/2015 | 2/1/2015 | 31 | 1,673 | 153 |
| 2 | Feb-2015 | 2/1/2015 | 3/1/2015 | 28 | 3,919 | 358 |
| 3 | Mar-2015 | 3/1/2015 | 4/1/2015 | 31 | 36 | 3 |
| 4 | Apr-2015 | 4/1/2015 | 5/1/2015 | 30 | 876 | 80 |
| 5 | May-2015 | 5/1/2015 | 6/1/2015 | 31 | 941 | 86 |
| 6 | Jun-2015 | 6/1/2015 | 7/1/2015 | 30 | - | - |
| 7 | Jul-2015 | 7/1/2015 | 8/1/2015 | 31 | - | - |
| 8 | Aug-2015 | 8/1/2015 | 9/1/2015 | 31 | - | - |
| 9 | Sep-2015 | 9/1/2015 | 10/1/2015 | 30 | 471 | 43 |
| 10 | Oct-2015 | 10/1/2015 | 11/1/2015 | 31 | - | - |
| 11 | Nov-2015 | 11/1/2015 | 12/1/2015 | 30 | 310 | 28 |
| 12 | Dec-2015 | 12/1/2015 | 1/1/2016 | 31 | 1,471 | 134 |
| 1 | Jan-2016 | 1/1/2016 | 2/1/2016 | 31 | 1,740 | 159 |
| 2 | Feb-2016 | 2/1/2016 | 3/1/2016 | 29 | - | - |
| 3 | Mar-2016 | 3/1/2016 | 4/1/2016 | 31 | 2,493 | 228 |
| 4 | Apr-2016 | 4/1/2016 | 5/1/2016 | 30 | 1,833 | 167 |
| 5 | May-2016 | 5/1/2016 | 6/1/2016 | 31 | 12 | 1 |
| 6 | Jun-2016 | 6/1/2016 | 7/1/2016 | 30 | - | - |
| 7 | Jul-2016 | 7/1/2016 | 8/1/2016 | 31 | 116 | 11 |
| 8 | Aug-2016 | 8/1/2016 | 9/1/2016 | 31 | - | - |
| 9 | Sep-2016 | 9/1/2016 | 10/1/2016 | 30 | - | - |
| 10 | Oct-2016 | 10/1/2016 | 11/1/2016 | 31 | - | - |
| 11 | Nov-2016 | 11/1/2016 | 12/1/2016 | 30 | - | - |
| 12 | Dec-2016 | 12/1/2016 | 1/1/2017 | 31 | 1,601 | 146 |
| 1 | Jan-2017 | 1/1/2017 | 2/1/2017 | 31 | 2,826 | 258 |
| 2 | Feb-2017 | 2/1/2017 | 3/1/2017 | 28 | 1,578 | 144 |
| 3 | Mar-2017 | 3/1/2017 | 4/1/2017 | 31 | - | - |
| 4 | Apr-2017 | 4/1/2017 | 5/1/2017 | 30 | 1,402 | 128 |
| 5 | May-2017 | 5/1/2017 | 6/1/2017 | 31 | - | - |
| 6 | Jun-2017 | 6/1/2017 | 7/1/2017 | 30 | - | - |
| 7 | Jul-2017 | 7/1/2017 | 8/1/2017 | 31 | 262 | 24 |
| 8 | Aug-2017 | 8/1/2017 | 9/1/2017 | 31 | - | - |
| 9 | Sep-2017 | 9/1/2017 | 10/1/2017 | 30 | - | - |
| 10 | Oct-2017 | 10/1/2017 | 11/1/2017 | 31 | - | - |
| 11 | Nov-2017 | 11/1/2017 | 12/1/2017 | 30 | 818 | 75 |
| 12 | Dec-2017 | 12/1/2017 | 1/1/2018 | 31 | 1,800 | 164 |

| SQFT |
|---|
| 13,515 |

| YEAR | | | TOTAL DAYS | Consumption (GALLONS) | Consumption (MMBTU) | | | year-round MMBTU / sqft | winter MMBTU / sqft |
|---|---|---|---|---|---|---|---|---|---|
| **2014** | | | 365 | - | - | | | - | - |
| **2015** | | | 365 | 9,697 | 886 | | | 0.066 | - |
| **2016** | | | 366 | 7,795 | 712 | | | 0.053 | - |
| **2017** | | | 365 | 8,686 | 793 | | | 0.059 | - |
| **2018** | | | - | - | - | | | - | - |
| **2019** | | | | | | | | - | - |
| average yearly consumption | | | | 8,726 | 797 | | | | |

| | | | | |
|---|---|---|---|---|
| Jan-17 | $ 0.908 | $ 0.968 | $ 1.012 | $ 1.045 |
| Feb-17 | $ 1.160 | $ 1.030 | $ 1.015 | $ 9.000 |
| Mar-17 | $ 0.835 | $ 0.873 | $ 0.855 | $ 0.785 |
| Apr-17 | | | | |
| May-17 | | | | |
| Jun-17 | | | | |
| | | | | |
| | $ 1.402 | | | |



# NATURAL GAS SERVICE


**FIELD MAINTENANCE BLDG**

**Site:** **NORFOLK AIRPORT AUTHORITY**
**Address:** NORFOLK, VA
**Delivery:**
**Supplier:**

**Data from Natural gas Usage.xlsx Workbook**

| | | **1 CCF = 0.1025** | |
|---|---|---|---|
| | | NG | MMBTU |


| | Month | Billing Period Start Date | Billing Period End Date | Days | Consumption (CCF) | Consumption (MMBTU) |
|---|---|---|---|---|---|---|
| 1 | Jan-2015 | 1/1/2015 | 2/1/2015 | 31 | 4,958 | 508 |
| 2 | Feb-2015 | 2/1/2015 | 3/1/2015 | 28 | 6,364 | 652 |
| 3 | Mar-2015 | 3/1/2015 | 4/1/2015 | 31 | 3,169 | 325 |
| 4 | Apr-2015 | 4/1/2015 | 5/1/2015 | 30 | 1,470 | 151 |
| 5 | May-2015 | 5/1/2015 | 6/1/2015 | 31 | 211 | 22 |
| 6 | Jun-2015 | 6/1/2015 | 7/1/2015 | 30 | 43 | 4 |
| 7 | Jul-2015 | 7/1/2015 | 8/1/2015 | 31 | 41 | 4 |
| 8 | Aug-2015 | 8/1/2015 | 9/1/2015 | 31 | 41 | 4 |
| 9 | Sep-2015 | 9/1/2015 | 10/1/2015 | 30 | 216 | 22 |
| 10 | Oct-2015 | 10/1/2015 | 11/1/2015 | 31 | 830 | 85 |
| 11 | Nov-2015 | 11/1/2015 | 12/1/2015 | 30 | 2,016 | 207 |
| 12 | Dec-2015 | 12/1/2015 | 1/1/2016 | 31 | 2,183 | 224 |
| 1 | Jan-2016 | 1/1/2016 | 2/1/2016 | 31 | 4,851 | 497 |
| 2 | Feb-2016 | 2/1/2016 | 3/1/2016 | 29 | 5,287 | 542 |
| 3 | Mar-2016 | 3/1/2016 | 4/1/2016 | 31 | 2,534 | 260 |
| 4 | Apr-2016 | 4/1/2016 | 5/1/2016 | 30 | 2,004 | 205 |
| 5 | May-2016 | 5/1/2016 | 6/1/2016 | 31 | 911 | 93 |
| 6 | Jun-2016 | 6/1/2016 | 7/1/2016 | 30 | 689 | 71 |
| 7 | Jul-2016 | 7/1/2016 | 8/1/2016 | 31 | 470 | 48 |
| 8 | Aug-2016 | 8/1/2016 | 9/1/2016 | 31 | 19 | 2 |
| 9 | Sep-2016 | 9/1/2016 | 10/1/2016 | 30 | 12 | 1 |
| 10 | Oct-2016 | 10/1/2016 | 11/1/2016 | 31 | 661 | 68 |
| 11 | Nov-2016 | 11/1/2016 | 12/1/2016 | 30 | 3,146 | 322 |
| 12 | Dec-2016 | 12/1/2016 | 1/1/2017 | 31 | 5,022 | 515 |
| 1 | Jan-2017 | 1/1/2017 | 2/1/2017 | 31 | 6,303 | 646 |
| 2 | Feb-2017 | 2/1/2017 | 3/1/2017 | 28 | 3,127 | 321 |
| 3 | Mar-2017 | 3/1/2017 | 4/1/2017 | 31 | 3,367 | 345 |
| 4 | Apr-2017 | 4/1/2017 | 5/1/2017 | 30 | 1,116 | 114 |
| 5 | May-2017 | 5/1/2017 | 6/1/2017 | 31 | 285 | 29 |
| 6 | Jun-2017 | 6/1/2017 | 7/1/2017 | 30 | 74 | 8 |
| 7 | Jul-2017 | 7/1/2017 | 8/1/2017 | 31 | 37 | 4 |
| 8 | Aug-2017 | 8/1/2017 | 9/1/2017 | 31 | 19 | 2 |
| 9 | Sep-2017 | 9/1/2017 | 10/1/2017 | 30 | 43 | 4 |
| 10 | Oct-2017 | 10/1/2017 | 11/1/2017 | 31 | 185 | 19 |
| 11 | Nov-2017 | 11/1/2017 | 12/1/2017 | 30 | 1,367 | 140 |
| 12 | Dec-2017 | 12/1/2017 | 1/1/2018 | 31 | 5,843 | 599 |




| SQFT |
|---|
| 44,913 |

| YEAR | | | TOTAL DAYS | Consumption (CCF) | Consumption (MMBTU) | Winter Consumption (MMBTU) | | year-round MMBTU / sqft | winter MMBTU / sqft |
|---|---|---|---|---|---|---|---|---|---|
| **2014** | | | 365 | - | - | - | | - | - |
| **2015** | | | 365 | 21,542 | 2,208 | 2,066 | | 0.049 | 0.046 |
| **2016** | | | 366 | 25,606 | 2,625 | 2,342 | | 0.058 | 0.052 |
| **2017** | | | 365 | 21,766 | 2,231 | 2,165 | | 0.050 | 0.048 |
| **2018** | | | - | - | - | - | | - | - |
| **2019** | | | | | | | | - | - |
| average yearly consumption | | | | 22,971 | 2,355 | 2,191 | | | |

| | MONTH | **AVERAGES** | | | | | |
|---|---|---|---|---|---|---|---|
| Jan | 1 | | | | 5,371 | 550 | W |
| Feb | 2 | | | | 4,926 | 505 | W |
| Mar | 3 | | | | 3,023 | 310 | W |
| Apr | 4 | | | | 1,530 | 157 | W |
| May | 5 | | | | 469 | 48 | |
| Jun | 6 | | | | 269 | 28 | |
| Jul | 7 | | | | 183 | 19 | S |
| Aug | 8 | | | | 26 | 3 | s |
| Sep | 9 | | | | 90 | 9 | s |
| Oct | 10 | | | | 559 | 57 | |
| Nov | 11 | | | | 2,176 | 223 | W |
| Dec | 12 | | | | 4,349 | 446 | W |
| | | | TOTAL USAGE (average) | | 22,971 | 2,355 | |
| | | | WINTER USAGE | | 21,376 | 2,191 | |
| | | | SUMMER USAGE | | 299 | 31 | |
| | | | AVG SUMMER USAGE | | 100 | 10 | |


Fuel Oil #2 - Norfolk Airport
MT BOILER OIL
AV BOILER OIL
Consumption (MMBTU)
700
600
500
400
300
200
100
-
Jan-14
Mar-14
May-14
Jul-14
Sep-14
Nov-14
Jan-15
Mar-15
May-15
Jul-15
Sep-15
Nov-15
Jan-16
Mar-16
May-16
Jul-16
Sep-16
Nov-16
Jan-17
Mar-17
May-17
Jul-17
Sep-17
Nov-17
Jan-18

# APPENDIX B – LIGHTING ECM CALCULATIONS

***Energy Audit of Norfolk International Airport***
***CHA Project No. 33370***

**Total**

| Budgetary | Annual Utility Savings | | | | Total | Payback |
|---|---|---|---|---|---|---|
| Cost | | | | | Savings | (without incentive) |
| | | | | | | |
| $ | kW | kWh | therms | $ | $ | Years |
| **$4,032,873** | **870.5** | **5,854,117** | **0** | **$422,160** | **$422,160** | **9.6** |

**Out-Buildings**

| Budgetary | Annual Utility Savings | | | | Total | Payback |
|---|---|---|---|---|---|---|
| Cost | | | | | Savings | (without incentive) |
| | | | | | | |
| $ | kW | kWh | therms | $ | $ | Years |
| **$281,473** | **68.8** | **353,438** | **0** | **$25,968** | **$25,968** | **10.8** |

**Terminals**

| Budgetary | Annual Utility Savings | | | | Total | Payback |
|---|---|---|---|---|---|---|
| Cost | | | | | Savings | (without incentive) |
| | | | | | | |
| $ | kW | kWh | therms | $ | $ | Years |
| **$1,711,466** | **323.8** | **2,228,378** | **0** | **$177,749** | **$177,749** | **9.6** |

| Utility Rates Main Terminal | |
|---|---|
| $/kW | $/kWh |
| | 0.071 |

| Utility Rates Arrivals Terminal | |
|---|---|
| $/kW | $/kWh |
| | 0.096 |

| Utility Rates Exterior | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates Parking Garage | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates Airfield Lighting Vault | |
|---|---|
| $/kW | $/kWh |
| | 0.096 |

| Utility Rates Ground Run-Up Enclosure | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates Triturator | |
|---|---|
| $/kW | $/kWh |
| | 0.096 |

| Utility Rates Airfield Storage | |
|---|---|
| $/kW | $/kWh |
| | 0.093 |

| Utility Rates ARFF | |
|---|---|
| $/kW | $/kWh |
| | 0.096 |

| Utility Rates Airfield Building | |
|---|---|
| $/kW | $/kWh |
| | 0.093 |

| Utility Rates ARFF Storage | |
|---|---|
| $/kW | $/kWh |
| | 0.096 |

| Utility Rates Short-Term Parking | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

**Exterior**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Exterior** | **$258,516** | **133.3** | **627,696** | **0** | **$41,902** | **$41,902** | **6.2** |

**Parking Garage**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Parking Ga** | **$1,688,538** | **314.2** | **2,500,800** | **0** | **$166,941** | **$166,941** | **10.1** |

**Main Terminal**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Main Term** | **$1,274,080** | **210.3** | **1,429,011** | **0** | **$100,997** | **$100,997** | **12.6** |

**Arrivals**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Arrivals** | **$437,385** | **113.6** | **799,367** | **0** | **$76,752** | **$76,752** | **5.7** |

**Airfield Lighting Vault**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Airfield Lig** | **$5,143** | **0.6** | **5,111** | **0** | **$490** | **$490** | **10.5** |

**Ground Run-Up Enslosure**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Ground Ru** | **$1,608** | **1.5** | **8,847** | **0** | **$591** | **$591** | **2.7** |

**Triturator/Fuel Station**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Triturator/** | **$4,945** | **0.9** | **1,728** | **0** | **$166** | **$166** | **29.8** |

**Airfield Maintenance Storage Building**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Airfield Ma** | **$3,637** | **1.1** | **2,876** | **0** | **$269** | **$269** | **13.5** |

**ARFF**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **ARFF** | **$34,424** | **4.6** | **24,413** | **0** | **$2,344** | **$2,344** | **14.7** |

**Airfield Maintenance Facility**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Airfield Ma** | **$38,712** | **13.7** | **44,667** | **0** | **$4,173** | **$4,173** | **9.3** |

| Utility Rates Long-Term Parking | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates TNC Staging Area | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates Air Cargo Buildings | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

| Utility Rates Fuel Farm | |
|---|---|
| $/kW | $/kWh |
| | 0.067 |

**Fuel Storage**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Fuel Stora** | **$3,616** | **1.3** | **5,841** | **0** | **$390** | **$390** | **9.3** |

**Air Cargo Buildings**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Air Cargo** | **$169,782** | **39.5** | **239,216** | **0** | **$15,969** | **$15,969** | **10.6** |

**ARFF Storage**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **ARFF Stor** | **$2,637** | **1.5** | **6,595** | **0** | **$633** | **$633** | **4.2** |

**Short-Term Parking**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Short-Terr** | **$19,440** | **4.7** | **22,335** | **0** | **$1,491** | **$1,491** | **13.0** |

**Long-Term Parking**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **Long-Term** | **$73,440** | **25.7** | **121,470** | **0** | **$8,109** | **$8,109** | **9.1** |

**TNC Staging Area**

| | Budgetary Cost | Annual Utility Savings | | | | Total Savings | Payback (without incentive) |
|---|---|---|---|---|---|---|---|
| | $ | kW | kWh | therms | $ | $ | Years |
| **TNC Stagi** | **$16,970** | **4.2** | **14,142** | **0** | **$944** | **$944** | **18.0** |

***Energy Audit of Norfolk International Airport***

***CHA Project No. 33370***

| Recommended Y/N? | Item | Savings kW | kWh | therms | kgal/yr | $ | Cost | Simple Payback |
|---|---|---|---|---|---|---|---|---|
| Y | Main Terminal | 210.3 | 1429011 | 0 | 0 | $ 100,997 | $ 1,274,080 | 12.6 |
| Y | Arrivals | 113.6 | 799367 | 0 | 0 | $ 76,752 | $ 437,385 | 5.7 |
| Y | Parking Garage | 314.2 | 2500800 | 0 | 0 | $ 166,941 | $ 1,688,538 | 10.1 |
| Y | Exterior | 133.3 | 627696 | 0 | 0 | $ 41,902 | $ 258,516 | 6.2 |
| Y | Airfield Lighting Vault | 0.6 | 5111 | 0 | 0 | $ 490 | $ 5,143 | 10.5 |
| Y | Triturator/Fuel Station | 0.9 | 1728 | 0 | 0 | $ 166 | $ 4,945 | 29.8 |
| Y | Ground Run-Up Enslosure | 1.5 | 8847 | 0 | 0 | $ 591 | $ 1,608 | 2.7 |
| Y | Airfield Maintenance Storage Building | 1.1 | 2876 | 0 | 0 | $ 269 | $ 3,637 | 13.5 |
| Y | ARFF | 4.6 | 24413 | 0 | 0 | $ 2,344 | $ 34,424 | 14.7 |
| Y | Airfield Maintenance Facility | 13.7 | 44667 | 0 | 0 | $ 4,173 | $ 38,712 | 9.3 |
| Y | Fuel Storage | 1.3 | 5841 | 0 | 0 | $ 390 | $ 3,616 | 9.3 |
| Y | Air Cargo Buildings | 39.5 | 239216 | 0 | 0 | $ 15,969 | $ 169,782 | 10.6 |
| Y | ARFF Storage | 1.5 | 6595 | 0 | 0 | $ 633 | $ 2,637 | 4.2 |
| Y | Short-Term Parking | 4.7 | 22335 | 0 | 0 | $ 1,491 | $ 19,440 | 13.0 |
| Y | Long-Term Parking | 25.7 | 121470 | 0 | 0 | $ 8,109 | $ 73,440 | 9.1 |
| Y | TNC Staging Area | 4.2 | 14142 | 0 | 0 | $ 944 | $ 16,970 | 18.0 |
| N | Dominion Lighting Conversion | 0.0 | 0 | 0 | 0 | $ 31,157 | $ - | 0.0 |
| | **Total Recommended** | **870.5** | **5,854,117** | **-** | **-** | **$ 422,160** | **$ 4,032,873** | **9.6** |
| | **Total** | **870.5** | **5,854,117** | **0** | **0** | **$ 453,317** | **$ 4,032,873** | **8.9** |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| LED | Boiler Room | Main Terminal | 24/7 | 29 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Boiler Room | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Boiler Room | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 1LED | Generator Room | Main Terminal | 24/7 | 9 | 2x8 4 Lamp T-8 32W Hanging Tandem | F44ILL | 112 | 1.01 | SW | 8760 | 8,830 | NONE | |
| 2LED | Drawings Room | Main Terminal | 24/7toOCC12hr | 6 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.61 | SW | 8760 | 5,361 | OCC | |
| 2LED | Controls Room | Main Terminal | 24/7toOCC12hr | 2 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.20 | SW | 8760 | 1,787 | OCC | |
| 2LED | Office 0155 | Main Terminal | 24/7toOCC12hr | 4 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.41 | SW | 8760 | 3,574 | OCC | |
| 2LED | Building Maintenance Office | Main Terminal | 24/7toOCC12hr | 4 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.41 | SW | 8760 | 3,574 | OCC | |
| 2LED | Basement Hallway | Main Terminal | 24/7 | 48 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 4.90 | SW | 8760 | 42,889 | NONE | |
| 3LED | 151 | Main Terminal | 3 per week | 3 | 1x4 1 Lamp T-8 32W Ceiling Mounted | F41ILL | 31 | 0.09 | SW | 156 | 15 | NONE | |
| 4LED | 150 | Main Terminal | 3 per week | 1 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 156 | 9 | NONE | |
| 2LED | 120 | Main Terminal | 24/7 | 21 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 2.14 | SW | 8760 | 18,764 | NONE | |
| 5LED | Police K-9 Office | Main Terminal | 6 per day | 3 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.18 | SW | 2184 | 387 | NONE | |
| 6LED | 0134 Womens Room/Locker | Main Terminal | 24/7toOCC12hr | 4 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | OCC | |
| 6LED | 0134 Womens Room/Locker | Main Terminal | 24/7toOCC12hr | 3 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | OCC | |
| 7LED | 0134 Womens Room/Locker | Main Terminal | 24/7toOCC12hr | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.06 | SW | 8760 | 517 | OCC | |
| 5LED | 119 | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 5LED | Stair 105 (D6) | Main Terminal | 24/7 | 5 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 8LED | Stair 105 (D6) | Main Terminal | 24/7 | 5 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 6LED | 0126 Mens Room/Locker | Main Terminal | 24/7toOCC12hr | 4 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | OCC | |
| 9LED | 117 | Main Terminal | 9 per day | 8 | Single INC 60W | I60/1 | 60 | 0.48 | SW | 3276 | 1,572 | NONE | |
| 10LED | Basement Hallway 2 | Main Terminal | 24/7 | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 8760 | 1,559 | NONE | |
| 11LED | Janitor Break Room | Main Terminal | 8 per day | 3 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.18 | SW | 2912 | 515 | NONE | |
| 12LED | Storage 1 | Main Terminal | 2 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 12LED | Janitor Office | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 12LED | Janitor Assistance Office | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 12LED | Storage 2 | Main Terminal | 2 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 13LED | 0115 Telephone Eoom | Main Terminal | 3 per week | 1 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.11 | SW | 156 | 17 | NONE | |
| 5LED | 0115 Telephone Eoom | Main Terminal | 3 per week | 3 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.18 | SW | 156 | 28 | NONE | |
| 5LED | Chief of Police | Main Terminal | 8 per day | 7 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.41 | SW | 2912 | 1,203 | NONE | |
| 2LED | Police Administration Office | Main Terminal | 24/7 | 6 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.61 | SW | 8760 | 5,361 | NONE | |
| 14LED | Conference K Room | Main Terminal | 24/7toOCC12hr | 2 | 2x8 2 Lamp T-8 32W Ceiling Tandem | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | OCC | |
| 5LED | 116 | Main Terminal | 1 per day | 8 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.47 | SW | 364 | 172 | NONE | |
| 15LED | Tug Bay and Crosswalk Thru Tunnel | Main Terminal | 24/7 | 3 | 1x4 1 Lamp T-8 32W Wall Mounted | F41ILL | 31 | 0.09 | SW | 8760 | 815 | NONE | |
| 13LED | Squad Room | Main Terminal | 24/7 | 2 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 8760 | 1,962 | NONE | |
| 16LED | Squad Room Bathroom | Main Terminal | 24/7toOCC12hr | 4 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.24 | SW | 8760 | 2,067 | OCC | |
| 7LED | Squad Room Bathroom | Main Terminal | 24/7toOCC12hr | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.06 | SW | 8760 | 517 | OCC | |
| 10LED | Police Foyer | Main Terminal | 24/7 | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 8760 | 1,559 | NONE | |
| 10LED | Captin's Office | Main Terminal | 0 | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 0 | - | NONE | |
| 11LED | Dispach Center | Main Terminal | 24/7 | 11 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.65 | SW | 8760 | 5,685 | NONE | |
| 5LED | Storage Closet | Main Terminal | 2 per week | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 104 | 6 | NONE | |
| 11LED | Dispatch Office | Main Terminal | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 11LED | Evidence Room | Main Terminal | 2 per week | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 104 | 12 | NONE | |
| 17LED | Records Room | Main Terminal | 1 per week | 10 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.59 | SW | 52 | 31 | NONE | |
| 6LED | 125 | Main Terminal | 24/7 | 3 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | 125 | Main Terminal | 24/7 | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| 3LED | 118 | Main Terminal | 2 per week | 2 | 1x4 1 Lamp T-8 32W Celing Mounted | F41ILL | 31 | 0.06 | SW | 104 | 6 | NONE | |
| 3LED | 0120 Storage | Main Terminal | 24/7 | 3 | 1x4 1 Lamp T-8 32W Celing Mounted | F41ILL | 31 | 0.09 | SW | 8760 | 815 | NONE | |
| 18LED | 0117 Office | Main Terminal | 8 per day | 1 | 2x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.03 | SW | 2912 | 90 | NONE | |
| 6LED | 141 | Main Terminal | 2 per day | 9 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.53 | SW | 728 | 387 | NONE | |
| 19LED | Crosswalk Tunnel | Main Terminal | 24/7 | 6 | 2x8 1 Lamp T-8 58W Hanging | F81ILL | 58 | 0.35 | SW | 8760 | 3,048 | NONE | |
| 5LED | Stairwell D7 | Main Terminal | 24/7 | 7 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.41 | SW | 8760 | 3,618 | NONE | |
| 5LED | Stairs D3 | Main Terminal | 24/7 | 5 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 8LED | Stairs D3 | Main Terminal | 24/7 | 5 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 8LED | Hallway | Main Terminal | 24/7 | 10 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.59 | SW | 8760 | 5,168 | NONE | |
| LED | Ticketing Lobby (United) | Main Terminal | 24/7 | 121 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Ticketing Lobby (United) | Main Terminal | 24/7 | 32 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Entryway 1 by Aligent | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Entryway 2 by American Airline | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 9 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| LED | Mens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| LED | Mens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| 20LED | Mens Room Hallway by American Airlines | Main Terminal | 24/7toOCC16hr | 1 | 6"RC 1 Lamp CFL 23W | CFS23/1 | 23 | 0.02 | SW | 8760 | 201 | OCC | |
| LED | Womens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 9 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| LED | Womens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| LED | Womens Room by American Airlines | Main Terminal | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | OCC | |
| 20LED | Womens Room Hallway by American Airlines | Main Terminal | 24/7toOCC16hr | 1 | 6"RC 1 Lamp CFL 23W | CFS23/1 | 23 | 0.02 | SW | 8760 | 201 | OCC | |
| LED | Hallway to Southwest Ticket Side | Main Terminal | 24/7 | 12 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | None | |
| 8LED | Hallway to Southwest Ticket Side | Main Terminal | 24/7 | 14 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.83 | SW | 8760 | 7,236 | NONE | |
| 21LED | Hallway to Southwest Ticket Side | Main Terminal | 24/7 | 8 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.38 | SW | 8760 | 3,364 | NONE | |
| 5LED | Stairwell D4 | Main Terminal | 24/7 | 5 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 8LED | Elevator Lobby by Hallway | Main Terminal | 24/7 | 3 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 5LED | 1084 | Main Terminal | 2 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 5LED | Room Across from 1084 | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| LED | Ticketing Lobby Southwest | Main Terminal | 24/7 | 121 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 22LED | Ticketing Lobby Southwest | Main Terminal | 24/7 | 32 | 2x2 1 Lamp MH 250W Recessed | MH250/1 | 295 | 9.44 | SW | 8760 | 82,694 | NONE | |
| LED | Entryway 1 by Delta | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Entryway 2 by Southwest | Main Terminal | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Room by Southwest | Main Terminal | 24/7toOCC16hr | 9 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Mens Room by Southwest | Main Terminal | 24/7toOCC16hr | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Mens Room by Southwest | Main Terminal | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| 20LED | Mens Room Hallway by Southwest | Main Terminal | 24/7toOCC16hr | 1 | 6"RC 1 Lamp CFL 23W | CFS23/1 | 23 | 0.02 | OCC | 8760 | 201 | OCC | |
| LED | Womens Room by Southwest | Main Terminal | 24/7toOCC16hr | 9 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Womens Room by Southwest | Main Terminal | 24/7toOCC16hr | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Womens Room by Southwest | Main Terminal | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Womens Room Hallway by Southwest | Main Terminal | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| LED | Southwest Break Room | Main Terminal | 4 per day | 8 | Existing LED | 0 | 0 | 0.00 | SW | 1456 | - | NONE | |
| LED | Southwest Break Room | Main Terminal | 24/7 | 5 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | SW Break Room conference | Main Terminal | 4 per day | 6 | Existing LED | 0 | 0 | 0.00 | OCC | 1456 | - | OCC | |
| LED | SW Break Room Office | Main Terminal | 4 per day | 3 | Existing LED | 0 | 0 | 0.00 | OCC | 1456 | - | OCC | |
| 5LED | SW Break Room Office | Main Terminal | 1 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| LED | SW Office 1 | Main Terminal | 6 per day | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | SW Office 2 | Main Terminal | 6 per day | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | SW Office 3 | Main Terminal | 6 per day | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | SW Office 4 | Main Terminal | 6 per day | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| 14LED | Behind SW Counter | Main Terminal | 24/7 | 11 | 2x8 2 Lamp T-8 32W Ceiling Tandem | F42ILL | 59 | 0.65 | SW | 8760 | 5,685 | NONE | |
| 7LED | Behind SW Counter | Main Terminal | 24/7 | 22 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 1.30 | SW | 8760 | 11,370 | NONE | |
| LED | Behind Delta Counter | Main Terminal | 24/7 | 14 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Behind Delta Counter | Main Terminal | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | 1089 TSA Xray | Main Terminal | 24/7 | 12 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | 1092 | Main Terminal | 3 per day | 1 | Existing LED | 0 | 0 | 0.00 | OCC | 1092 | - | OCC | |
| LED | Delta Hallway | Main Terminal | 3 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 1092 | - | OCC | |
| 5LED | 1086 | Main Terminal | 3 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | OCC | 1092 | 64 | OCC | |
| LED | Delta Hallway | Main Terminal | 3 per day | 20 | Existing LED | 0 | 0 | 0.00 | OCC | 1092 | - | OCC | |
| 5LED | 1512 | Main Terminal | 1 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 3LED | 1097 | Main Terminal | 1 per day | 1 | 1x4 1 Lamp T-8 32W Celing Mounted | F41ILL | 31 | 0.03 | SW | 364 | 11 | NONE | |
| LED | 1098 | Main Terminal | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | Delta Hallway | Main Terminal | 6 per day | 5 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | 1096 | Main Terminal | 5 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 1820 | - | OCC | |
| LED | 1095 | Main Terminal | 5 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 1820 | - | OCC | |
| 14LED | Behing American Airlines Counter | Main Terminal | 24/7 | 11 | 2x8 2 Lamp T-8 32W Ceiling Tandem | F42ILL | 59 | 0.65 | SW | 8760 | 5,685 | NONE | |
| 7LED | Behing American Airlines Counter | Main Terminal | 24/7 | 22 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 1.30 | SW | 8760 | 11,370 | NONE | |
| LED | Behing American Airlines Counter | Main Terminal | 24/7 | 7 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 12LED | Amberican Airlines Office Hallway | Main Terminal | 24/7 | 8 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.90 | SW | 8760 | 7,849 | NONE | |
| 5LED | 1544 Server Room | Main Terminal | 1 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 11LED | 1545 | Main Terminal | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 11LED | 1547 | Main Terminal | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 16LED | AA Office Hallway | Main Terminal | 24/7 | 9 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.53 | SW | 8760 | 4,652 | NONE | |
| 16LED | AA Kitchen | Main Terminal | 24/7toOCC16hr | 4 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.24 | OCC | 8760 | 2,067 | OCC | |
| 16LED | AA Locker Room | Main Terminal | 24/7toOCC16hr | 3 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.18 | OCC | 8760 | 1,551 | OCC | |
| 12LED | AA Manager Office 1 | Main Terminal | 17 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 6188 | 2,772 | NONE | |
| 12LED | AA Manager Office 2 | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 12LED | AA Manager Office 3 | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 12LED | AA Manager Office 4 | Main Terminal | 8 per day | 1 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.11 | SW | 2912 | 326 | NONE | |
| 16LED | AA Manager Office 4 | Main Terminal | 8 per day | 1 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.06 | SW | 2912 | 172 | NONE | |
| 23LED | Frontier Baggage Conveyor Room | Main Terminal | 24/7 | 3 | 1x8 1 Lamp T-8 58W Wall Mounted | F81ILL | 58 | 0.17 | SW | 8760 | 1,524 | NONE | |
| 15LED | Frontier Baggage Conveyor Room | Main Terminal | 24/7 | 1 | 1x4 1 Lamp T-8 32W Wall Mounted | F41ILL | 31 | 0.03 | SW | 8760 | 272 | NONE | |
| 16LED | Frontier Hallway Offices | Main Terminal | 24/7 | 2 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 16LED | Frontier Hallway Offices | Main Terminal | 4 per day | 6 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.35 | SW | 1456 | 515 | NONE | |
| 12LED | Frontier Breakroom | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 12LED | Frontier Storage Office | Main Terminal | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | NONE | |
| 10LED | 1563 Office | Main Terminal | 4 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 1456 | 259 | NONE | |
| 10LED | 1565 Server | Main Terminal | 20 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 7280 | 1,296 | NONE | |
| 24LED | United Behind Counter | Main Terminal | 20 per day | 15 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 1.68 | SW | 7280 | 12,230 | NONE | |
| 25LED | United Behind Counter | Main Terminal | 20 per day | 15 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 1.64 | SW | 7280 | 11,903 | NONE | |
| 16LED | United Office Hallway | Main Terminal | 20 per day | 8 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.47 | SW | 7280 | 3,436 | NONE | |
| 11LED | United Office Hallway | Main Terminal | 20 per day | 5 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 7280 | 2,148 | NONE | |
| 11LED | United Break Room | Main Terminal | 20 per day | 5 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 7280 | 2,148 | NONE | |
| 11LED | United Lockers | Main Terminal | 20 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 7280 | 859 | NONE | |
| 12LED | United Office Space | Main Terminal | 20 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 7280 | 1,631 | NONE | |
| 26LED | United Supply Closet | Main Terminal | 2 per day | 1 | 1x2 1 Lamp T-8 XXW Ceiling Mounted | F21ILL | 20 | 0.02 | SW | 728 | 15 | NONE | |
| 26LED | United Supply Closet | Main Terminal | 2 per day | 1 | 1x2 1 Lamp T-8 XXW Ceiling Mounted | F21ILL | 20 | 0.02 | SW | 728 | 15 | NONE | |
| 16LED | Allegient Office Hallway | Main Terminal | 24/7 | 3 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 16LED | Allegient Office Hallway | Main Terminal | 0 | 11 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.65 | SW | 0 | - | NONE | |
| 10LED | Allegient Office Hallway | Main Terminal | 10 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 3640 | 648 | NONE | |
| 10LED | Allegient Supply Office | Main Terminal | 6 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 2184 | 389 | NONE | |
| 8LED | Storage Hall | Main Terminal | 1 per day | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 4LED | Electrical Finance | Main Terminal | 1 per day | 1 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 5LED | HMS Hosts Storage | Main Terminal | 1 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 364 | 86 | NONE | |
| 5LED | Storage | Main Terminal | 1 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 364 | 86 | NONE | |
| LED | Family Room | Concoarse B | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Family Room | Concoarse B | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Family Room | Concoarse B | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mothers Room | Concoarse B | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | Mothers Room | Concoarse B | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 2184 | - | OCC | |
| LED | Norfolk Airport Athority Hall | Main Terminal | 8 per day | 8 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | NONE | |
| 8LED | Norfolk Airport Athority Hall Department Head Office | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | Norfolk Airport Athority Hall Storage | Main Terminal | 8 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 27LED | Norfolk Airport Athority Hall Kitchen | Main Terminal | 8 per day | 8 | 2x2 2 Lamp CFT 40W Recessed | CFT40/2-BX | 72 | 0.58 | SW | 2912 | 1,677 | NONE | |
| LED | Norfolk Airport Athority Hall Lounge | Main Terminal | 8 per day | 6 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | NONE | |
| 28LED | Norfolk Airport Athority Hall Restroom 1 | Main Terminal | 1 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 364 | 11 | NONE | |
| 28LED | Norfolk Airport Athority Hall Restroom 2 | Main Terminal | 1 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 364 | 11 | NONE | |
| 28LED | Norfolk Airport Athority Hall Restroom 3 | Main Terminal | 1 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 364 | 11 | NONE | |
| 8LED | 2137 Office | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | Receptionest Office | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | MR.Bowen Office | Main Terminal | 8 per day | 10 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.59 | SW | 2912 | 1,718 | NONE | |
| 28LED | MR.Bowen Office restroom | Main Terminal | 8 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 2912 | 90 | NONE | |
| 8LED | Mrs. Ward Office | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | MR Sterling Office | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 11LED | Norfolk Airport Athority lobby | Main Terminal | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 29LED | Norfolk Airport Athority lobby | Main Terminal | 8 per day | 2 | Table Lamp | CFS23/1 | 23 | 0.05 | SW | 2912 | 134 | NONE | |
| 21LED | Norfolk Airport Athority lobby | Main Terminal | 8 per day | 3 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.14 | SW | 2912 | 419 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 30LED | Conference Room A-D Hall | Main Terminal | 8 per day | 10 | 6"RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 0.70 | SW | 2912 | 2,038 | NONE | |
| LED | Conference Room A-D Hall | Main Terminal | 8 per day | 3 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | NONE | |
| 8LED | Conference Room A-D Hall | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | Conference Room C | Main Terminal | 8 per day | 5 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 2912 | 859 | NONE | |
| 31LED | Conference Room B | Main Terminal | 2 per day | 18 | 6"RC 1 Lamp Par38 40W | Par38-40W/1 | 40 | 0.72 | SW | 728 | 524 | NONE | |
| 4LED | Conference Room B | Main Terminal | 2 per day | 10 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.59 | SW | 728 | 430 | NONE | |
| 30LED | Conference Room A | Main Terminal | 2 per day | 52 | 6"RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 3.64 | SW | 728 | 2,650 | NONE | |
| 16LED | Conference Room A Closet | Main Terminal | 1 per day | 2 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 8LED | Conference Room D | Main Terminal | 2 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 728 | 258 | NONE | |
| 8LED | Copy Room | Main Terminal | 2 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| LED | Restroom | Main Terminal | 2 per day | 1 | Existing LED | 0 | 0 | 0.00 | SW | 728 | - | NONE | |
| 5LED | Electrical Room 2539 | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 8LED | Payroll | Main Terminal | 8 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 8LED | Directors Office | Main Terminal | 6 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2184 | 773 | NONE | |
| 8LED | Kitchen | Main Terminal | 8 per day | 1 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 2912 | 172 | NONE | |
| 6LED | HR storage | Main Terminal | 2 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 11LED | TSA Office | Main Terminal | 8 per day | 6 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 11LED | TSA Office | Main Terminal | 24/7 | 1 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| 28LED | Volunteer Office Mens Restroom | Main Terminal | 2 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 728 | 23 | NONE | |
| 28LED | Volunteer Office Womens Restroom | Main Terminal | 4 per day | 1 | Wall CFL | CFT13/2 | 31 | 0.03 | SW | 1456 | 45 | NONE | |
| LED | Kitchen | Main Terminal | 8 per day | 3 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | NONE | |
| 8LED | Voulenteer Office Lead | Main Terminal | 8 per day | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 8LED | Voulenteer lounge | Main Terminal | 8 per day | 9 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.53 | SW | 2912 | 1,546 | NONE | |
| 8LED | Airport authority Marketing Hallway | Main Terminal | 8 per day | 7 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.41 | SW | 2912 | 1,203 | NONE | |
| 8LED | Airport authority Marketing Office | Main Terminal | 8 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 8LED | Airport authority Marketing Copy Room | Main Terminal | 8 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 8LED | Airport authority Marketing Office 2 | Main Terminal | 8 per day | 3 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.18 | SW | 2912 | 515 | NONE | |
| 10LED | Burger King Kitchen | Main Terminal | 16 per day | 10 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.89 | SW | 5824 | 5,183 | NONE | |
| 5LED | Breaker Room By Burger King | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 8LED | Storage By Burger King | Main Terminal | 2 per day | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 10LED | Starbucks Storage/Ice Room | Main Terminal | 24/7toOCC16hr | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | OCC | 8760 | 780 | NONE | |
| 13LED | The Local Kitchen | Main Terminal | 24/7 | 28 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 3.14 | SW | 8760 | 27,471 | NONE | |
| 12LED | Starbucks Hallway Office | Main Terminal | 24/7toOCC16hr | 1 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.11 | OCC | 8760 | 981 | NONE | |
| 12LED | Starbucks Internal Office | Main Terminal | 24/7toOCC16hr | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | OCC | 8760 | 3,924 | NONE | |
| 31LED | The Local Break Room/Storage | Main Terminal | 6 per day | 6 | 6"RC 1 Lamp Par38 40W | Par38-40W/1 | 40 | 0.24 | SW | 2184 | 524 | NONE | |
| 30LED | The Local Break Room/Storage | Main Terminal | 4 per day | 28 | 6"RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 1.96 | SW | 1456 | 2,854 | NONE | |
| 12LED | The Local Office | Main Terminal | 4 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 1456 | 326 | NONE | |
| LED | Zone 15 Service Area | Concoarse B | 12 per day | 48 | Existing LED | 0 | 0 | 0.00 | SW | 4368 | - | NONE | |
| 28LED | Zone 15 Service Area | Concoarse B | 16 per day | 50 | Wall CFL | CFT13/2 | 31 | 1.55 | SW | 5824 | 9,027 | NONE | |
| LED | Under Concoarse B New Addition | Concoarse B | 24/7 | 16 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 33LED | Under Concoarse B New Addition | Concoarse B | 24/7 | 139 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 4.31 | SW | 8760 | 37,747 | NONE | |
| LED | Under Concoarse B New Addition | Concoarse B | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 33LED | Under Concoarse B New Addition | Concoarse B | 12 per day | 108 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 3.35 | SW | 4368 | 14,624 | NONE | |
| 32LED | Concoarse B Gate24/25 | Concoarse B | 24/7 | 46 | 1 Lamp T-5 28W Recessed | F41ILL/T5 | 27 | 1.24 | SW | 8760 | 10,880 | NONE | |
| 34LED | Concoarse B Gate24/25 | Concoarse B | 24/7 | 4 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.11 | SW | 8760 | 946 | NONE | |
| 35LED | Concoarse B Gate 26 | Concoarse B | 24/7 | 20 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 35LED | Concoarse B 27-30 | Concoarse B | 24/7 | 84 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 4.54 | SW | 8760 | 39,735 | NONE | |
| 34LED | Concoarse B 27-30 | Concoarse B | 24/7 | 12 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.32 | SW | 8760 | 2,838 | NONE | |
| 35LED | Concoarse B "Y" Lobby | Concoarse B | 24/7 | 178 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 9.61 | SW | 8760 | 84,201 | NONE | |
| 35LED | Concoarse B "Y" Lobby | Concoarse B | 24/7 | 1 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.05 | SW | 8760 | 473 | NONE | |
| LED | Concoarse B "Y" Lobby | Concoarse B | 24/7 | 26 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Concoarse B Gates 21 and 23 | Concoarse B | 24/7 | 52 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 2.81 | SW | 8760 | 24,598 | NONE | |
| LED | Concoarse B Gates 21 and 23 | Concoarse B | 24/7 | 26 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 34LED | Concoarse B Gates 21 and 23 | Concoarse B | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| 35LED | Mens Restroom by "Y" | Concoarse B | 24/7 | 12 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.65 | SW | 8760 | 5,676 | NONE | |
| LED | Mens Restroom by "Y" | Concoarse B | 24/7 | 12 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Restroom by "Y" | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Restroom by "Y" | Concoarse B | 24/7 | 32 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Womens Restroom by "Y" | Concoarse B | 24/7 | 12 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.65 | SW | 8760 | 5,676 | NONE | |
| LED | Womens Restroom by "Y" | Concoarse B | 24/7 | 12 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Womens Restroom by "Y" | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Womens Restroom by "Y" | Concoarse B | 24/7 | 32 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 17LED | Janitors Closet in RR | Concoarse B | 24/7 | 2 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| LED | ORF Market | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | ORF Market | Concoarse B | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | ORF Market | Concoarse B | 24/7 | 11 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | ORF Market | Concoarse B | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Hudson News "Middle" | Concoarse B | 24/7 | 38 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Hudson News "Middle" | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Hudson News "Middle" | Concoarse B | 24/7 | 16 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Hudson News "Middle" | Concoarse B | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Waiting Area | Concoarse B | 24/7 | 12 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.65 | SW | 8760 | 5,676 | NONE | |
| 34LED | Waiting Area | Concoarse B | 24/7 | 8 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.22 | SW | 8760 | 1,892 | NONE | |
| LED | Waiting Area | Concoarse B | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Gate B20 | Concoarse B | 24/7 | 32 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.73 | SW | 8760 | 15,137 | NONE | |
| 34LED | Gate B20 | Concoarse B | 24/7 | 12 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.32 | SW | 8760 | 2,838 | NONE | |
| LED | Gate B20 | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Gate B19 | Concoarse B | 24/7 | 28 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.51 | SW | 8760 | 13,245 | NONE | |
| 34LED | Gate B19 | Concoarse B | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate B19 | Concoarse B | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Mens Restroom "Middle" | Concoarse B | 24/7 | 11 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.59 | SW | 8760 | 5,203 | NONE | |
| LED | Mens Restroom "Middle" | Concoarse B | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Restroom "Middle" | Concoarse B | 24/7 | 36 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Womens Restroom "Middle" | Concoarse B | 24/7 | 11 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.59 | SW | 8760 | 5,203 | NONE | |
| LED | Womens Restroom "Middle" | Concoarse B | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Womens Restroom "Middle" | Concoarse B | 24/7 | 36 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 17LED | Mechanical Room In RR | Concoarse B | 24/7 | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| LED | Family Room | Concoarse B | 24/7toOCC16hr | 4 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Family Room | Concoarse B | 24/7toOCC16hr | 2 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Family Room | Concoarse B | 24/7toOCC16hr | 1 | Existing LED | 0 | 0 | 0.00 | OCC | 8760 | - | OCC | |
| LED | Mothers Room | Concoarse B | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 2184 | - | NONE | |
| LED | Mothers Room | Concoarse B | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 2184 | - | NONE | |
| 17LED | Supply Room | Concoarse B | 2 per day | 3 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.18 | SW | 728 | 129 | NONE | |
| 35LED | Gate B18 | Concoarse B | 24/7 | 20 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 34LED | Gate B18 | Concoarse B | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate B18 | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Gate B17 | Concoarse B | 24/7 | 24 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.30 | SW | 8760 | 11,353 | NONE | |
| 34LED | Gate B17 | Concoarse B | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate B17 | Concoarse B | 24/7 | 7 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse B | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse B | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse B | 24/7 | 22 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse B | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 10LED | Starbucks | Concoarse B | 24/7 | 3 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.27 | SW | 8760 | 2,339 | NONE | |
| 35LED | Gate B16 | Concoarse B | 24/7 | 19 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.03 | SW | 8760 | 8,988 | NONE | |
| 34LED | Gate B16 | Concoarse B | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate B16 | Concoarse B | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | TSA Room 1 | Concoarse B | 4 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 1456 | - | NONE | |
| LED | TSA Room 2 | Concoarse B | 4 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 1456 | - | NONE | |
| LED | TSA Room 3 | Concoarse B | 4 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 1456 | - | NONE | |
| 35LED | TSA After Checkpoint | Concoarse B | 24/7 | 25 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.35 | SW | 8760 | 11,826 | NONE | |
| LED | TSA Office | Concoarse B | 24/7 | 5 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | TSA Office | Concoarse B | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 2184 | - | NONE | |
| LED | TSA Office | Concoarse B | 18 per day | 8 | Existing LED | 0 | 0 | 0.00 | SW | 6552 | - | NONE | |
| 8LED | TSA Break Room | Concoarse B | 18 per day | 8 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 6552 | 3,093 | NONE | |
| 35LED | Concorse B Hallwau | Concoarse B | 24/7 | 462 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 24.95 | SW | 8760 | 218,544 | NONE | |
| 34LED | Concorse B Hallwau | Concoarse B | 24/7 | 8 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.22 | SW | 8760 | 1,892 | NONE | |
| LED | Hudson News "Y" | Concoarse B | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | BackBay Bestro | Concoarse B | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 7LED | Stairwell By "Y" | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | Stairwell By "Y" 2 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | Stairwell By "Y" 3 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | Stairwell By "Y" 4 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 10LED | Air Ops Managers Office | Concoarse B | 8 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 2912 | 1,037 | NONE | |
| 10LED | Air Ops Managers Office | Concoarse B | 2 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 728 | 130 | NONE | |
| 10LED | Air Ops Managers Office | Concoarse B | 2 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 728 | 130 | NONE | |
| 10LED | Air Ops Managers Office Hall | Concoarse B | 2 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 728 | 65 | NONE | |
| 36LED | Garage Wild Life Storage | Concoarse B | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 10LED | RR-1 | Concoarse B | 2 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 728 | 65 | NONE | |
| 10LED | RR-2 | Concoarse B | 2 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 728 | 65 | NONE | |
| 10LED | Break Room | Concoarse B | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 7LED | Stairwell 5 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 10LED | United Offices | Concoarse B | 16 per day | 25 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 2.23 | SW | 5824 | 12,958 | NONE | |
| 36LED | United Garage | Concoarse B | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 36LED | AHU18 Room | Concoarse B | 2 per day | 13 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.77 | SW | 728 | 558 | NONE | |
| 7LED | Stairwell 6 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | Stairwell 7 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 36LED | Airline Contractors Shop | Concoarse B | 8 per day | 15 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.89 | SW | 2912 | 2,577 | NONE | |
| 11LED | Airline Contractors Shop | Concoarse B | 8 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 2912 | 344 | NONE | |
| 36LED | Airline Contractors Shop Locker Room | Concoarse B | 8 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 2912 | 344 | NONE | |
| 5LED | Delta Storage | Concoarse B | 2 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 5LED | Delta Storage | Concoarse B | 24/7 | 6 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 10LED | Delta Operations | Concoarse B | 24/7 | 36 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 3.20 | SW | 8760 | 28,067 | NONE | |
| 6LED | Mens Restroom | Concoarse B | 16 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 5824 | 687 | NONE | |
| 7LED | Mens Restroom | Concoarse B | 16 per day | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.06 | SW | 5824 | 344 | NONE | |
| 6LED | Womens Restroom | Concoarse B | 16 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 5824 | 687 | NONE | |
| 7LED | Womens Restroom | Concoarse B | 16 per day | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.06 | SW | 5824 | 344 | NONE | |
| 5LED | Janitors Closet Delta | Concoarse B | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 7LED | Stairwell 8 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 36LED | AHU Room 14 (1101) | Concoarse B | 2 per day | 12 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.71 | SW | 728 | 515 | NONE | |
| 7LED | Stairwell 9 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 36LED | Delta Paint Shop BC05 | Concoarse B | 2 per day | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 728 | 258 | NONE | |
| 36LED | Delta Paint Shop BC06 | Concoarse B | 2 per day | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 36LED | Snow Plow Room 1052 | Concoarse B | 6 per day | 10 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.59 | SW | 2184 | 1,289 | NONE | |
| 7LED | Stairwell 10 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 10LED | Storage Room | Concoarse B | 2 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 728 | 130 | NONE | |
| 36LED | Empty Chemical Bin Room | Concoarse B | 2 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 36LED | BB16 Comm Room | Concoarse B | 2 per day | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 36LED | BB17 AHU Room 16 | Concoarse B | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.47 | SW | 728 | 344 | NONE | |
| 10LED | Old Signiture Office | Concoarse B | 0 | 11 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.98 | SW | 0 | - | NONE | |
| 5LED | Old Signiture Office | Concoarse B | 0 | 9 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.53 | SW | 0 | - | NONE | |
| 6LED | Old Signiture Office | Concoarse B | 0 | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 0 | - | NONE | |
| 5LED | Aligent Office | Concoarse B | 8 per day | 6 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 7LED | Stairwell 11 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 7LED | Stairwell 12 | Concoarse B | 24/7 | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 8LED | Old American Airline Space/New Storage | Concoarse B | 24/7 | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 5LED | Old American Airline Space/New Storage | Concoarse B | 2 per day | 6 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.35 | SW | 728 | 258 | NONE | |
| 8LED | Old American Airline Space/New Storage | Concoarse B | 24/7 | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 5LED | Old American Airline Space/New Storage | Concoarse B | 2 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 10LED | Empy Office (Contractors) | Concoarse B | 1 per day | 30 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 2.67 | SW | 364 | 972 | NONE | |
| 36LED | 1014 Electrical Room | Concoarse B | 1 per day | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 5LED | SRE Storage | Concoarse B | 1 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 364 | 86 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 33LED | SRE Storage | Concoarse B | 24/7 | 3 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.09 | SW | 8760 | 815 | NONE | |
| 17LED | Old AHU 15 BA02 | Concoarse B | 1 per day | 3 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.18 | SW | 364 | 64 | NONE | |
| 10LED | Air Field Maintenance Shop | Concoarse B | 2 per day | 6 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.53 | SW | 728 | 389 | NONE | |
| 37LED | Air Field Maintenance Shop | Concoarse B | 2 per day | 1 | 1x2 1 Lamp T-8 20W Wall Mounted | F21ILL | 20 | 0.02 | SW | 728 | 15 | NONE | |
| 36LED | Air Field Maintenance Shop Garage | Concoarse B | 16 per day | 17 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 1.00 | SW | 5824 | 5,841 | NONE | |
| 11LED | Air Field Maintenance Shop | Concoarse B | 12 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 4368 | 2,062 | NONE | |
| 36LED | BA03 Light Cart Storage | Concoarse B | 6 per day | 11 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.65 | SW | 2184 | 1,417 | NONE | |
| 11LED | Empty Office | Concoarse B | 1 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 364 | 172 | NONE | |
| LED | Empty Office | Concoarse B | 1 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 364 | - | NONE | |
| 8LED | Stairwell 13 | Concoarse B | 24/7 | 6 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 8LED | Office Contractor | Concoarse B | 6 per day | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2184 | 515 | NONE | |
| 5LED | Drawing Room | Concoarse B | 1 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 35LED | Concoarse B Exit Hall | Concoarse B | 24/7 | 45 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 2.43 | SW | 8760 | 21,287 | NONE | |
| 38LED | Electrical Room | Concoarse B | 2 per day | 2 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.11 | SW | 728 | 79 | NONE | |
| 35LED | TSA Pre-Check | Concoarse B | 24/7 | 126 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 6.80 | SW | 8760 | 59,603 | NONE | |
| 39LED | TSA Pre-Check | Concoarse B | 24/7 | 18 | 1 Lamp T-5 28W Surface | F41ILL/T5 | 27 | 0.49 | SW | 8760 | 4,257 | NONE | |
| 39LED | TSA Pre-Check | Concoarse B | 12 per day | 18 | 1 Lamp T-5 28W Surface | F41ILL/T5 | 27 | 0.49 | SW | 4368 | 2,123 | NONE | |
| 5LED | Communication Room | Arrivals | 2 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 11LED | Family Room | Arrivals | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 11LED | Elevator Room+Janitor Closet | Arrivals | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 11LED | Janitor Closet | Arrivals | 2 per day | 1 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 5LED | Hudson office | Arrivals | 14 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 5096 | 1,203 | NONE | |
| 10LED | USO Office | Arrivals | 4 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 1456 | 259 | NONE | |
| 10LED | Empty Office Space | Arrivals | 1 per day | 5 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.45 | SW | 364 | 162 | NONE | |
| 10LED | Storage/Office | Arrivals | 1 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 364 | 65 | NONE | |
| 10LED | TSA Office | Arrivals | 12 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 4368 | 778 | NONE | |
| 10LED | TSA Office | Arrivals | 0 | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 0 | - | NONE | |
| 10LED | TSA Office | Arrivals | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 10LED | TSA Office | Arrivals | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 10LED | TSA Office | Arrivals | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 10LED | Elevator Room+Janitor Closet | Arrivals | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 10LED | Janitor Closet | Arrivals | 2 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 728 | 65 | NONE | |
| 10LED | TSA Office | Arrivals | 12 per day | 6 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.53 | SW | 4368 | 2,333 | NONE | |
| 10LED | TSA Office | Arrivals | 1 per day | 6 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.53 | SW | 364 | 194 | NONE | |
| 5LED | Communication Room | Arrivals | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 10LED | Parking Manager | Arrivals | 24/7 | 3 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.27 | SW | 8760 | 2,339 | NONE | |
| 10LED | Communication Room | Arrivals | 1 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 364 | 130 | NONE | |
| 11LED | Parking Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Parking Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Parking Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Parking Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Parking Office | Arrivals | 8 per day | 6 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 11LED | Parking Office | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | NONE | |
| 21LED | Tug Bay | Arrivals | 24/7 | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | SW | 8760 | 841 | NONE | |
| 40LED | Tug Bay Garage A entry | Arrivals | 24/7 | 244 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 27.33 | SW | 8760 | 239,393 | NONE | |
| 40LED | Tug Bay Holdings Side | Arrivals | 2 per day | 40 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 4.48 | SW | 728 | 3,261 | NONE | |
| 40LED | Electric Switch Gear | Arrivals | 2 per day | 6 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.67 | SW | 728 | 489 | NONE | |
| 7LED | Basement Hallway | Arrivals | 24/7 | 13 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.77 | SW | 8760 | 6,719 | NONE | |
| 41LED | Zone 25 Service Area | Arrivals | 12 per day | 10 | 1 lamp MH 100W Ceiling Mounded | MH100/1 | 128 | 1.28 | SW | 4368 | 5,591 | NONE | |
| 24LED | Storage Room | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 42LED | Zone 25 Service Area | Arrivals | 12 per day | 2 | 1 Lamp HPS 250W Shoe Box | HPS250/1 | 295 | 0.59 | SW | 4368 | 2,577 | NONE | |
| 43LED | Zone 25 Service Area | Arrivals | 12 per day | 2 | 2 Lamp HPS 250W Shoe Box | HPS250/2 | 590 | 1.18 | SW | 4368 | 5,154 | NONE | |
| 40LED | Arrivals Snow Removal | Arrivals | 2 per day | 8 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.90 | SW | 728 | 652 | NONE | |
| 40LED | Emergency Generator Room | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | NONE | |
| 10LED | Fire Command | Arrivals | 2 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 728 | 259 | NONE | |
| 11LED | Police Investrigation Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Securitas (Old Baggage Claim) | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 11LED | Police K-9 Office | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | NONE | |
| 10LED | IT Office | Arrivals | 8 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 2912 | 259 | NONE | |
| 11LED | Janitor Closet | Arrivals | 2 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | 4 total but only one on with one lamp |
| 25LED | Mens Restroom | Arrivals | 24/7toOCC16hr | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | OCC | 8760 | 1,910 | OCC | |
| 21LED | Mens Restroom | Arrivals | 24/7toOCC16hr | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | OCC | 8760 | 841 | OCC | |
| 25LED | Womens Restroom | Arrivals | 24/7toOCC16hr | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | OCC | 8760 | 1,910 | OCC | |
| 21LED | Womens Restroom | Arrivals | 24/7toOCC16hr | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | OCC | 8760 | 841 | OCC | |
| 24LED | Boiler/Chiller Room | Arrivals | 24/7 | 17 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 1.90 | SW | 8760 | 16,679 | NONE | |
| 10LED | Parking Maintenance | Arrivals | 11 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 4004 | 1,425 | NONE | |
| 10LED | Parking Maintenance | Arrivals | 24/7 | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 8760 | 3,119 | NONE | |
| 16LED | Parking Maintenance | Arrivals | 2 per day | 2 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 24LED | AHU Equipment Room 1 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 24LED | Elevator Room+Janitor Closet | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.34 | SW | 728 | 245 | NONE | |
| 24LED | Elevator Equipment Room 1 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 24LED | Storage Romm B.2 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 21LED | Tug Bay | Arrivals | 24/7 | 9 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.43 | SW | 8760 | 3,784 | NONE | |
| 40LED | Communication Equipment 1 | Arrivals | 24/7 | 9 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 1.01 | SW | 8760 | 8,830 | NONE | |
| 40LED | Storage Room B.3 | Arrivals | 24/7 | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 8760 | 2,943 | NONE | |
| 11LED | Tug Bay Server/Electrical Room 4 | Arrivals | 24/7 | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 17LED | Elevator Equipment Room | Arrivals | 2 per day | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 40LED | holding 15 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 40LED | Holding 14 | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | NONE | |
| 40LED | Electrical Equipment 2 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 728 | 163 | NONE | |
| 40LED | HVAC Fan room | Arrivals | 4 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 1456 | 326 | NONE | |
| 21LED | Stairwell A-3 | Arrivals | 24/7 | 4 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.19 | SW | 8760 | 1,682 | NONE | |
| 6LED | Storage Room B.4 | Arrivals | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 25LED | Mens Restroom | Arrivals | 24/7toOCC16hr | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | OCC | 8760 | 1,910 | OCC | |
| 21LED | Mens Restroom | Arrivals | 24/7toOCC16hr | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | OCC | 8760 | 841 | OCC | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | | Retrofit control device | Notes |
| 25LED | Womens Restroom | Arrivals | 24/7toOCC16hr | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | OCC | 8760 | 1,910 | | OCC | |
| 21LED | Womens Restroom | Arrivals | 24/7toOCC16hr | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | OCC | 8760 | 841 | | OCC | |
| 11LED | Janitor Closet | Arrivals | 2 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 728 | 86 | | NONE | |
| 40LED | Storage B.6 | Arrivals | 2 per day | 1 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.11 | SW | 728 | 82 | | NONE | |
| 17LED | Elevator toom 5 | Arrivals | 2 per day | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 11LED | Elevator Server Room 5 Tug Bay | Arrivals | 24/7 | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 40LED | Storage B.7 | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | | NONE | |
| 40LED | Storage B.8 | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | | NONE | |
| 40LED | Communications Equipment 5 | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | | NONE | |
| 21LED | Stairwell A4 | Arrivals | 24/7 | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | SW | 8760 | 841 | | NONE | |
| 40LED | Electrial Equipment 3 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 40LED | Storage B.9 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 40LED | AHU Room 2 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 40LED | Elevator Room | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | | NONE | |
| 40LED | Storage B.10 | Arrivals | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | | NONE | |
| 40LED | Building Maintenance Shop | Arrivals | 6 per day | 18 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 2.02 | SW | 2184 | 4,403 | | NONE | |
| 16LED | Stairlwell A5 | Arrivals | 24/7 | 4 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 40LED | Storage B.11 | Arrivals | 2 per day | 5 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.56 | SW | 728 | 408 | | NONE | |
| 17LED | Communication Room 4 | Arrivals | 2 per day | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 17LED | Communication Room 3 | Arrivals | 2 per day | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 17LED | Communication Room 2 | Arrivals | 2 per day | 1 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 11LED | Alamo | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Enterprise | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Hertz | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Budget | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Avis | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 24LED | Storage 1.3 | Arrivals | 2 per day | 1 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.11 | SW | 728 | 82 | | NONE | |
| 24LED | Communication Room | Arrivals | 2 per day | 1 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.11 | SW | 728 | 82 | | NONE | |
| 11LED | Elevator Room + Janitor | Arrivals | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 728 | 172 | | NONE | |
| 11LED | Janitor Closet | Arrivals | 2 per day | 1 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| LED | Southwest Baggage Claim | Arrivals | 8 per day | 4 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | | NONE | |
| LED | Southwest Baggage Claim | Arrivals | 8 per day | 4 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | | NONE | |
| 11LED | Delta Baggage Claim | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | | NONE | |
| 11LED | Delta Baggage Claim | Arrivals | 8 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 2912 | 687 | | NONE | |
| 27LED | Huntleigh | Arrivals | 20/7 | 6 | 2x2 2 Lamp CFT 40W Recessed | CFT40/2-BX | 72 | 0.43 | SW | 7280 | 3,145 | | NONE | |
| 11LED | Huntleigh | Arrivals | 20/7 | 6 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 7280 | 2,577 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | American Airlines Baggage Claim | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Elevator Room + Janitor | Arrivals | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 728 | 172 | | NONE | |
| 11LED | Janitor Closet | Arrivals | 2 per day | 1 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 24LED | Communication Room | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 24LED | Storage 1.8 | Arrivals | 2 per day | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | United Baggage | Arrivals | 20/7 | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 7280 | 3,436 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | Old Baggage Claim | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | Old Baggage Claim Office | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 11LED | Old Office | Arrivals | 2 per day | 8 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.47 | SW | 728 | 344 | | NONE | |
| 44LED | Tunnel to Arrivals (Driving) | Exterior | 24/7 | 50 | 1 Lamp MH 70W Wallpack | MH70/1 | 95 | 4.75 | SW | 8760 | 41,610 | | NONE | |
| 45LED | Concoarse A Poles | Exterior | 12 per day | 63 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 69.30 | SW | 4368 | 302,702 | | NONE | |
| 46LED | Concoarse A Wall Shoebox | Exterior | 12 per day | 3 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 1.40 | SW | 4368 | 6,093 | | NONE | |
| 5LED | Stairwell 1 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 17LED | Fire Pump Room | Concoarse A | 24/7 | 2 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | | NONE | |
| 33LED | Stairwell 2 | Concoarse A | 24/7 | 4 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.12 | SW | 8760 | 1,086 | | NONE | |
| 12LED | Storage Room End Of Concoarse | Concoarse A | 2 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 12LED | 1139 Electrical Room | Concoarse A | 2 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 728 | 163 | | NONE | |
| 47LED | 1139 Electrical Room | Concoarse A | 2 per day | 1 | 1x4 1 Lamp T-8 32W Hanging | F41ILL | 31 | 0.03 | SW | 728 | 23 | | NONE | |
| 11LED | Storage | Concoarse A | 2 per day | 3 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.18 | SW | 728 | 129 | | NONE | |
| 12LED | 1145 (lighting/Storage) | Concoarse A | 2 per day | 16 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 1.79 | SW | 728 | 1,305 | | NONE | |
| 25LED | 1145 (lighting/Storage) | Concoarse A | 2 per day | 3 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.33 | SW | 728 | 238 | | NONE | |
| 11LED | PSA Hallway | Concoarse A | 24/7 | 5 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.30 | SW | 8760 | 2,584 | | NONE | |
| 12LED | PSA Office | Concoarse A | 4 per day | 7 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.78 | SW | 1456 | 1,142 | | NONE | |
| 12LED | PSA Office | Concoarse A | 1 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 364 | 82 | | NONE | |
| 12LED | PSA Office | Concoarse A | 8 per day | 2 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.22 | SW | 2912 | 652 | | NONE | |
| 36LED | 1122 | Concoarse A | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | | NONE | |
| 36LED | SRE Storage | Concoarse A | 2 per day | 23 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 1.36 | SW | 728 | 988 | | NONE | |
| 5LED | Stairwell 3 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 12LED | AE 15 (RR) | Concoarse A | 2 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 728 | 326 | | NONE | |
| 5LED | AE 15 (RR) | Concoarse A | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | | NONE | |
| 1LED | Old Generator Room (Storage) | Concoarse A | 2 per day | 1 | 2x8 4 Lamp T-8 32W Hanging Tandem | F44ILL | 112 | 0.11 | SW | 728 | 82 | | NONE | |
| 12LED | 1107 Signiture Office | Concoarse A | 8 per day | 7 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.78 | SW | 2912 | 2,283 | | NONE | |
| 33LED | Signiture Hallway | Concoarse A | 24/7 | 2 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.06 | SW | 8760 | 543 | | NONE | |
| 6LED | AE12 (AHU-13 Room) | Concoarse A | 2 per day | 3 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.18 | SW | 728 | 129 | | NONE | |
| 5LED | Stairwell 4 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 5LED | Stairwell 5 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 11LED | American Airlines Office | Concoarse A | 8 per day | 18 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 1.06 | SW | 2912 | 3,093 | | NONE | |
| 5LED | American Airlines Office | Concoarse A | 8 per day | 8 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.47 | SW | 2912 | 1,374 | | NONE | |
| 7LED | American Airlines Office | Concoarse A | 8 per day | 2 | 1x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.12 | SW | 2912 | 344 | | NONE | |
| 6LED | American Airlines Storage | Concoarse A | 24/7 | 10 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.59 | SW | 8760 | 5,168 | | NONE | |
| 33LED | American Airlines Storage | Concoarse A | 24/7 | 10 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.31 | SW | 8760 | 2,716 | | NONE | |
| 5LED | Stairwell 6 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | | NONE | |
| 11LED | Old Office | Concoarse A | 2 per day | 6 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.35 | SW | 728 | 258 | | NONE | |
| 12LED | 1069 American Airline Operations | Concoarse A | 8 per day | 22 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 2.46 | SW | 2912 | 7,175 | | NONE | |
| 33LED | Under Concoarse A | Concoarse A | 24/7 | 70 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 2.17 | SW | 8760 | 19,009 | | NONE | |
| LED | Under Concoarse A | Concoarse A | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh  $0.00 $/kW  **Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 36LED | AD11 (AHU-12 Room) | Concoarse A | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| LED | Southwest Office | Concoarse A | 8 per day | 32 | Existing LED | 0 | 0 | 0.00 | SW | 2912 | - | NONE | |
| 11LED | Southwest Office | Concoarse A | 8 per day | 11 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.65 | SW | 2912 | 1,890 | NONE | |
| 5LED | Stairwell 7 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 36LED | American Airline Storage/Repair | Concoarse A | 6 per day | 10 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.59 | SW | 2184 | 1,289 | NONE | |
| 8LED | Customs | Concoarse A | 24/7 | 51 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 3.01 | SW | 8760 | 26,359 | NONE | |
| 8LED | Customs | Concoarse A | 3 per day | 51 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 3.01 | SW | 1092 | 3,286 | NONE | |
| 36LED | AHU11/25 Mechanical Equipment Room | Concoarse A | 2 per day | 7 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.41 | SW | 728 | 301 | NONE | |
| 21LED | Customs | Concoarse A | 24/7 | 20 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.96 | SW | 8760 | 8,410 | NONE | |
| 10LED | Agriculture Lab | Concoarse A | 4 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 1456 | 518 | NONE | |
| 10LED | Agriculture Lab Office | Concoarse A | 8 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 2912 | 518 | NONE | |
| 10LED | holding | Concoarse A | 1 per day | 4 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.36 | SW | 364 | 130 | NONE | |
| 10LED | Chashier | Concoarse A | 1 per day | 2 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.18 | SW | 364 | 65 | NONE | |
| 8LED | Customs Lobby | Concoarse A | 24/7 | 7 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.41 | SW | 8760 | 3,618 | NONE | |
| 21LED | Customs Lobby | Concoarse A | 24/7 | 12 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.58 | SW | 8760 | 5,046 | NONE | |
| 6LED | Escelator Equipment Room | Concoarse A | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 6LED | Elevator Equipment Room | Concoarse A | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 10LED | Customs Office | Concoarse A | 8 per day | 14 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 1.25 | SW | 2912 | 3,628 | NONE | |
| 8LED | Holding 1 | Concoarse A | 1 per day | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 8LED | Holding 2 | Concoarse A | 1 per day | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 8LED | Holding 3 | Concoarse A | 1 per day | 2 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 21LED | Customs Office Supervisors | Concoarse A | 8 per day | 5 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.24 | SW | 2912 | 699 | NONE | |
| 5LED | Stairwell 8 | Concoarse A | 24/7 | 4 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 21LED | Customs Hallway | Concoarse A | 24/7 | 2 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.10 | SW | 8760 | 841 | NONE | |
| 8LED | Customs Elevator lobby RR | Concoarse A | 24/7 | 18 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 1.06 | SW | 8760 | 9,303 | NONE | |
| 25LED | Womens Restroom | Concoarse A | 2 per day | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | SW | 728 | 159 | NONE | |
| 16LED | Womens Restroom | Concoarse A | 2 per day | 1 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 25LED | Mens Restroom | Concoarse A | 2 per day | 2 | 1x8 2 Lamp T-8 58W Wall Mounted | F82ILL | 109 | 0.22 | SW | 728 | 159 | NONE | |
| 16LED | Mens Restroom | Concoarse A | 2 per day | 1 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 5LED | Janitor Closet | Concoarse A | 2 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 6LED | Electrical Closet | Concoarse A | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 6LED | Elevator Equipment Room | Concoarse A | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 36LED | Southwest Garage | Concoarse A | 24/7 | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 36LED | Southwest Ice Room | Concoarse A | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 45LED | Concoarse A Poles | Concoarse A | 12 per day | 24 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 26.40 | SW | 4368 | 115,315 | NONE | |
| LED | Under TSA Precheck | Concoarse A | 12 per day | 35 | Existing LED | 0 | 0 | 0.00 | SW | 4368 | - | NONE | |
| 48LED | Crawl Space A to Departures | Main Terminal | 24/7 | 10 | 1x4 1 Lamp T-5 28W Ceiling Mount | F41ILL/T5 | 27 | 0.27 | SW | 8760 | 2,365 | NONE | |
| 49LED | Crawl Space A to Departures | Main Terminal | 24/7 | 15 | Single CFL 23W | CFS23/1 | 23 | 0.35 | SW | 8760 | 3,022 | NONE | |
| 48LED | Crawl Space 2 | Main Terminal | 24/7 | 10 | 1x4 1 Lamp T-5 28W Ceiling Mount | F41ILL/T5 | 27 | 0.27 | SW | 8760 | 2,365 | NONE | |
| 49LED | Crawl Space 2 | Main Terminal | 24/7 | 15 | Single CFL 23W | CFS23/1 | 23 | 0.35 | SW | 8760 | 3,022 | NONE | |
| 4LED | Storage | Main Terminal | 2 per day | 2 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 4LED | Storage | Main Terminal | 2 per day | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 4LED | Tunnel A to Departures | Main Terminal | 24/7 | 26 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 1.53 | SW | 8760 | 13,438 | NONE | |
| 24LED | Tunnel A to Departures | Main Terminal | 24/7 | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 0.22 | SW | 8760 | 1,962 | NONE | |
| 38LED | Elevator Room | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.05 | SW | 728 | 39 | NONE | |
| 38LED | Elevator Room | Main Terminal | 2 per day | 1 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.05 | SW | 728 | 39 | NONE | |
| 4LED | Fan Room | Main Terminal | 2 per day | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 4LED | Fan Room | Main Terminal | 2 per day | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 17LED | Tug Bay | Main Terminal | 24/7 | 35 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 2.07 | SW | 8760 | 18,089 | NONE | |
| 47LED | Tug Bay | Main Terminal | 24/7 | 330 | 1x4 1 Lamp T-8 32W Hanging | F41ILL | 31 | 10.23 | SW | 8760 | 89,615 | NONE | |
| 38LED | Customs | Concoarse A | 24/7 | 32 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 1.73 | SW | 8760 | 15,137 | NONE | |
| 34LED | Customs | Concoarse A | 24/7 | 8 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.22 | SW | 8760 | 1,892 | NONE | |
| 38LED | Concoarse A Hallway | Concoarse A | 24/7 | 384 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 20.74 | SW | 8760 | 181,647 | NONE | |
| 38LED | Access Hallway | Concoarse A | 24/7 | 8 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.43 | SW | 8760 | 3,784 | NONE | |
| 38LED | Gate A 8 | Concoarse A | 24/7 | 20 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 34LED | Gate A 8 | Concoarse A | 24/7 | 8 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.22 | SW | 8760 | 1,892 | NONE | |
| LED | Gate A 8 | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 38LED | Opposite Gate A 8 | Concoarse A | 24/7 | 17 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.92 | SW | 8760 | 8,042 | NONE | |
| 34LED | Opposite Gate A 8 | Concoarse A | 24/7 | 8 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.22 | SW | 8760 | 1,892 | NONE | |
| LED | Opposite Gate A 8 | Concoarse A | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 34LED | Elevator Entrance | Concoarse A | 24/7 | 2 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.05 | SW | 8760 | 473 | NONE | |
| 38LED | Gate A6 | Concoarse A | 24/7 | 20 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 34LED | Gate A6 | Concoarse A | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate A6 | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 38LED | Gate A7 and A9 | Concoarse A | 24/7 | 44 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 2.38 | SW | 8760 | 20,814 | NONE | |
| 34LED | Gate A7 and A9 | Concoarse A | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate A7 and A9 | Concoarse A | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse A | 24/7 | 19 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Starbucks | Concoarse A | 24/7 | 3 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 34LED | Starbucks | Concoarse A | 24/7 | 7 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.19 | SW | 8760 | 1,656 | NONE | |
| 12LED | Starbucks | Concoarse A | 24/7 | 1 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.11 | SW | 8760 | 981 | NONE | |
| LED | Starbucks | Concoarse A | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Concoarse A Hallway | Concoarse A | 24/7 | 16 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 28 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 9 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 6 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | James River Café | Concoarse A | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 16LED | James River Café | Concoarse A | 24/7 | 5 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.30 | SW | 8760 | 2,584 | NONE | |
| 16LED | Great American Begal | Concoarse A | 24/7 | 9 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.53 | SW | 8760 | 4,652 | NONE | |
| 50LED | Great American Begal | Concoarse A | 24/7 | 8 | 1 Lamp MH 35W Track Lighting | MH35/1 | 44 | 0.35 | SW | 8760 | 3,084 | NONE | |
| LED | Great American Begal | Concoarse A | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Hudson News | Concoarse A | 24/7 | 14 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 51LED | Hudson News | Concoarse A | 24/7 | 18 | Track Lighting 2 Lamp CFT 18W | CFT18/2 | 48 | 0.86 | SW | 8760 | 7,569 | NONE | |
| 52LED | Hudson News | Concoarse A | 24/7 | 12 | 1x4 1 Lamp T-8 32W Surface Mounted | F41ILL | 31 | 0.37 | SW | 8760 | 3,259 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| LED | Hudson News | Concoarse A | 24/7 | 32 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 38LED | Gate A4 | Concoarse A | 24/7 | 20 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 34LED | Gate A4 | Concoarse A | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate A4 | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 38LED | Gate A3 and A5 | Concoarse A | 24/7 | 40 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 2.16 | SW | 8760 | 18,922 | NONE | |
| 34LED | Gate A3 and A5 | Concoarse A | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate A3 and A5 | Concoarse A | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| | Tech On The Go | Concoarse A | 24/7 | | | | | | SW | 8760 | | NONE | |
| 35LED | Mens Restroom | Concoarse A | 24/7 | 11 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.59 | SW | 8760 | 5,203 | NONE | |
| LED | Mens Restroom | Concoarse A | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mens Restroom | Concoarse A | 24/7 | 36 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 35LED | Womens Restroom | Concoarse A | 24/7 | 11 | 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.59 | SW | 8760 | 5,203 | NONE | |
| LED | Womens Restroom | Concoarse A | 24/7 | 20 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Womens Restroom | Concoarse A | 24/7 | 36 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Family Room | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Family Room | Concoarse A | 24/7 | 2 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Family Room | Concoarse A | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Heres to The Heros | Concoarse A | 24/7 | 9 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Heres to The Heros | Concoarse A | 24/7 | 9 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Heres to The Heros | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Heres to The Heros | Concoarse A | 24/7 | 26 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 10LED | Heres to The Heros | Concoarse A | 16 per day | 3 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.27 | SW | 5824 | 1,555 | NONE | |
| 38LED | Gate A2 | Concoarse A | 24/7 | 20 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 1.08 | SW | 8760 | 9,461 | NONE | |
| 34LED | Gate A2 | Concoarse A | 24/7 | 16 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.43 | SW | 8760 | 3,784 | NONE | |
| LED | Gate A2 | Concoarse A | 24/7 | 4 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Mothers Room | Concoarse A | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 2184 | - | NONE | |
| LED | Mothers Room | Concoarse A | 6 per day | 2 | Existing LED | 0 | 0 | 0.00 | SW | 2184 | - | NONE | |
| LED | Sweet Indulgences | Concoarse A | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Future Retail | Concoarse A | 0 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 0 | - | NONE | |
| LED | Past TSA | Concoarse A | 24/7 | 7 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | TSA Break Room | Concoarse A | 18 per day | 7 | Existing LED | 0 | 0 | 0.00 | SW | 6552 | - | NONE | |
| 53LED | TSA Office | Concoarse A | 18 per day | 9 | 2x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.49 | SW | 6552 | 3,184 | NONE | |
| LED | TSA Office | Concoarse A | 18 per day | 4 | Existing LED | 0 | 0 | 0.00 | SW | 6552 | - | NONE | |
| 53LED | TSA Storage | Concoarse A | 2 per day | 2 | 2x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.11 | SW | 728 | 79 | NONE | |
| 53LED | TSA Storage | Concoarse A | 2 per day | 2 | 2x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.11 | SW | 728 | 79 | NONE | |
| 53LED | regular Storage | Concoarse A | 4 per day | 4 | 2x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 0.22 | SW | 1456 | 314 | NONE | |
| 38LED | Electrical Closet | Concoarse A | 2 per day | 2 | 1x4 2 Lamp T-5 28W Hanging | F42ILL/T5 | 54 | 0.11 | SW | 728 | 79 | NONE | |
| 36LED | AHU Room 2 | Concoarse A | 2 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 54LED | Post TSA | Concoarse A | 24/7 | 38 | 1x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 2.05 | SW | 8760 | 17,976 | NONE | |
| 54LED | Pre TSA | Concoarse A | 24/7 | 105 | 1x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 5.67 | SW | 8760 | 49,669 | NONE | |
| LED | Pre TSA | Concoarse A | 24/7 | 12 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 54LED | TSA Exit | Concoarse A | 24/7 | 25 | 1x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 1.35 | SW | 8760 | 11,826 | NONE | |
| 55LED | Pre TSA | Concoarse A | 24/7 | 28 | 1x4 1 Lamp T-8 28W Surface Mounted | F41ILL/T5 | 27 | 0.76 | SW | 8760 | 6,623 | NONE | |
| 54LED | TSA Exit | Concoarse A | 24/7 | 40 | 1x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 2.16 | SW | 8760 | 18,922 | NONE | |
| LED | BK Common | Main Terminal | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 34LED | BK Common | Main Terminal | 17 per day | 7 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.19 | SW | 6188 | 1,170 | NONE | |
| 34LED | BK Common | Main Terminal | 17 per day | 14 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.38 | SW | 6188 | 2,339 | NONE | |
| 57LED | BK Common | Main Terminal | 17 per day | 24 | 1 Lamp T-8 32W Surface | F41ILL | 31 | 0.74 | SW | 6188 | 4,604 | NONE | |
| 34LED | BK Common | Main Terminal | 17 per day | 6 | 6" RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.16 | SW | 6188 | 1,002 | NONE | |
| 12LED | BK Kitchen | Main Terminal | 17 per day | 9 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 1.01 | SW | 6188 | 6,238 | NONE | |
| 16LED | BK Kitchen | Main Terminal | 17 per day | 1 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.06 | SW | 6188 | 365 | NONE | |
| LED | Starbucks Common | Main Terminal | 24/7 | 1 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 30LED | Lobby | Main Terminal | 24/7 | 394 | 6"RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 27.58 | SW | 8760 | 241,601 | NONE | |
| 8LED | Elevator Lobby By BK | Main Terminal | 24/7 | 4 | 1x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| LED | Lobby | Main Terminal | 24/7 | 216 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 56LED | Lobby | Main Terminal | 12 per day | 9 | Custom Fixture 24 Lamp T-8 32W Wall Mounted | F424ILL | 744 | 6.70 | SW | 4368 | 29,248 | NONE | |
| LED | Lobby | Main Terminal | 12 per day | 18 | Existing LED | 0 | 0 | 0.00 | SW | 4368 | - | NONE | |
| 57LED | Above Lobby | Main Terminal | 24/7 | 96 | 1 Lamp T-8 32W Surface | F41ILL | 31 | 2.98 | SW | 8760 | 26,070 | NONE | |
| 21LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 56 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 2.69 | SW | 8760 | 23,547 | NONE | |
| 2LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 62 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 6.32 | SW | 8760 | 55,398 | NONE | |
| 58LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 29 | Display Lighting 2 Lamp T-8 32W | F42ILL | 59 | 1.71 | SW | 8760 | 14,988 | NONE | |
| 59LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 15 | Display Lighting 1 Lamp T-8 20W | F21ILL | 20 | 0.30 | SW | 8760 | 2,628 | NONE | |
| 57LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 17 | 1 Lamp T-8 32W Surface | F41ILL | 31 | 0.53 | SW | 8760 | 4,617 | NONE | |
| LED | Hudson News/Tech On The Go | Main Terminal | 24/7 | 14 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| LED | Discover/Kids | Main Terminal | 24/7 | 44 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 21LED | Discover/Kids | Main Terminal | 24/7 | 11 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.53 | SW | 8760 | 4,625 | NONE | |
| LED | Discover/Kids | Main Terminal | 24/7 | 28 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 2LED | Discover/Kids | Main Terminal | 24/7 | 3 | 2x2 3 Lamp CFT 40W Recessed | CFT40/3-BX | 102 | 0.31 | SW | 8760 | 2,681 | NONE | |
| 58LED | Discover/Kids | Main Terminal | 24/7 | 28 | Display Lighting 2 Lamp T-8 32W | F42ILL | 59 | 1.65 | SW | 8760 | 14,472 | NONE | |
| 58LED | Discover/Kids | Main Terminal | 24/7 | 13 | Display Lighting 2 Lamp T-8 32W | F42ILL | 59 | 0.77 | SW | 8760 | 6,719 | NONE | |
| 59LED | Discover/Kids | Main Terminal | 24/7 | 10 | Display Lighting 1 Lamp T-8 20W | F21ILL | 20 | 0.20 | SW | 8760 | 1,752 | NONE | |
| LED | Information Booth | Main Terminal | 24/7 | 8 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 60LED | Bridge T oArrivals | Arrivals | 24/7 | 32 | 2x8 4 Lamp T-8 32W Hanging Tandem | F44ILL | 112 | 3.58 | SW | 8760 | 31,396 | NONE | |
| 61LED | Bridge T oArrivals | Arrivals | 24/7 | 4 | 2x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 21LED | Bridge T oArrivals | Arrivals | 24/7 | 58 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 2.78 | SW | 8760 | 24,388 | NONE | |
| 30LED | Arrivals Lobby 2nd Floor | Arrivals | 24/7 | 402 | 6"RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 28.14 | SW | 8760 | 246,506 | NONE | |
| 62LED | Arrivals Lobby 2nd Floor | Arrivals | 24/7 | 174 | 1 lamp MH 100W Ceiling Mounded | MH100/1 | 128 | 22.27 | SW | 8760 | 195,103 | NONE | |
| 61LED | Arrivals Lobby 2nd Floor | Arrivals | 24/7 | 170 | 2x4 2 Lamp T-8 32W Wall Mounted | F42ILL | 59 | 10.03 | SW | 8760 | 87,863 | NONE | |
| 31LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 220 | 6"RC 1 Lamp Par38 40W | Par38-40W/1 | 40 | 8.80 | SW | 8760 | 77,088 | NONE | |
| 63LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 15 | 1x30 4 Lamp T-8 32W Hanging | F44ILL | 112 | 1.68 | SW | 8760 | 14,717 | NONE | |
| 64LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 25 | 1x30 6 Lamp T-8 32W Hanging | F46ILL | 175 | 4.38 | SW | 8760 | 38,325 | NONE | |
| 65LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 6 | 1x10 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 66LED | Arrivals Entrance Vestibules | Arrivals | 24/7 | 40 | 6" RC 1 lamp MH 70W | MH70/1 | 95 | 3.80 | SW | 8760 | 33,288 | NONE | |
| 50LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 13 | 1 Lamp MH 35W Track Lighting | MH35/1 | 44 | 0.57 | SW | 8760 | 5,011 | NONE | |
| 33LED | Arrivals 1st Floor Lobby | Arrivals | 24/7 | 28 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.87 | SW | 8760 | 7,604 | NONE | |
| 67LED | Main Therminal Pent House | Main Terminal | 8 per day | 66 | 1x8 2 Lamp T-8 32W Hanging | F42ILL | 59 | 3.89 | SW | 2912 | 11,339 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh  $0.00 $/kW  **Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 47LED | Main Therminal Pent House | Main Terminal | 8 per day | 9 | 1x4 1 Lamp T-8 32W Hanging | F41ILL | 31 | 0.28 | SW | 2912 | 812 | NONE | |
| 40LED | Garage A Penthouse | Parking Garage | 24/7 | 66 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 7.39 | SW | 8760 | 64,754 | NONE | |
| 40LED | Garage C Penthouse | Parking Garage | 24/7 | 16 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 1.79 | SW | 8760 | 15,698 | NONE | |
| 66LED | Garage A Stairwell | Parking Garage | 24/7 | 200 | 6" RC 1 lamp MH 70W | MH70/1 | 95 | 19.00 | SW | 8760 | 166,440 | NONE | |
| 68LED | Garage A Stairwell | Parking Garage | 24/7 | 56 | Decorative 2 Lamp CFL 18W Ceiling Mount | CFT18/2 | 48 | 2.69 | SW | 8760 | 23,547 | NONE | |
| 66LED | Garage B Stairwell | Parking Garage | 24/7 | 100 | 6" RC 1 lamp MH 70W | MH70/1 | 95 | 9.50 | SW | 8760 | 83,220 | NONE | |
| 68LED | Garage B Stairwell | Parking Garage | 24/7 | 28 | Decorative 2 Lamp CFL 18W Ceiling Mount | CFT18/2 | 48 | 1.34 | SW | 8760 | 11,773 | NONE | |
| 66LED | Garage C Stairwell | Parking Garage | 24/7 | 200 | 6" RC 1 lamp MH 70W | MH70/1 | 95 | 19.00 | SW | 8760 | 166,440 | NONE | |
| 68LED | Garage C Stairwell | Parking Garage | 24/7 | 56 | Decorative 2 Lamp CFL 18W Ceiling Mount | CFT18/2 | 48 | 2.69 | SW | 8760 | 23,547 | NONE | |
| 40LED | Garage A Stairwell To Penthouse | Parking Garage | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | NONE | |
| 40LED | Garage C Stairwell To Penthouse | Parking Garage | 2 per day | 3 | 1x8 4 Lamp T-8 32W Hanging | F44ILL | 112 | 0.34 | SW | 728 | 245 | NONE | |
| 54LED | Entry To Concoarse A | Main Terminal | 24/7 | 140 | 1x4 2 Lamp T-5 28W Recessed | F42ILL/T5 | 54 | 7.56 | SW | 8760 | 66,226 | NONE | |
| LED | Entry To Concoarse A | Main Terminal | 24/7 | 14 | Existing LED | 0 | 0 | 0.00 | SW | 8760 | - | NONE | |
| 6LED | Air Field Lighting Vault | Airfield Lighting Vault | 24/7 | 20 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 1.18 | SW | 8760 | 10,337 | NONE | |
| 11LED | Air Field Lighting Vault Office | Airfield Lighting Vault | 4 per day | 1 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.06 | SW | 1456 | 86 | NONE | |
| LED | Exterior | Airfield Lighting Vault | PHC | 4 | Existing LED | 0 | 0 | 0.00 | SW | 4732 | - | NONE | |
| 69LED | Ground Run-Up Enclosure Exterior | Ground Run-Up Enslosure | PHC | 4 | 1 lamp MH Fixture | MH250/1 | 295 | 1.18 | SW | 4732 | 5,584 | NONE | |
| 69LED | Ground Run-Up Enclosure Exterior | Ground Run-Up Enslosure | 24/7 | 2 | 1 lamp MH Fixture | MH250/1 | 295 | 0.59 | SW | 8760 | 5,168 | NONE | |
| 6LED | Ground Run-Up Enclosure Interior | Ground Run-Up Enslosure | 2 per day | 3 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.18 | SW | 728 | 129 | NONE | |
| 6LED | Office | Triturator/Fuel Station | 4 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 1456 | 86 | NONE | |
| 5LED | Basement | Triturator/Fuel Station | 2 per day | 8 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.47 | SW | 728 | 344 | NONE | |
| 71LED | Car wash | Triturator/Fuel Station | 4 per day | 2 | 150 HPS lamp | HPS150/1 | 170 | 0.34 | SW | 1456 | 495 | NONE | |
| 70LED | Exterior | Triturator/Fuel Station | 10 per day | 2 | 150 HPS SHOEBOX | HPS150/1 | 170 | 0.34 | SW | 3640 | 1,238 | NONE | |
| LED | Fuel Station | Triturator/Fuel Station | 10 per day | 3 | Existing LED | 0 | 0 | 0.00 | SW | 3640 | - | NONE | |
| 70LED | Fuel Station | Triturator/Fuel Station | 10 per day | 1 | 150 HPS SHOEBOX | HPS150/1 | 170 | 0.17 | SW | 3640 | 619 | NONE | |
| 72LED | Garage | Airfield Maintenance Storage Building | 4 per day | 7 | 2x8 2 lamp 75W T-12 Hanging Fixture | F82SE | 158 | 1.11 | SW | 1456 | 1,610 | NONE | |
| 73LED | Exterior | Airfield Maintenance Storage Building | 12 per day | 3 | 150 MH Wallpack | MH150/1 | 190 | 0.57 | SW | 4368 | 2,490 | NONE | |
| 36LED | Captians office | ARFF | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 36LED | Dispach Center | ARFF | 24/7 | 3 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 36LED | Conference/Wash Room | ARFF | 24/7toOCC8hr | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 60LED | Garage | ARFF | 24/7 | 20 | 2x8 4 Lamp T-8 32W Hanging Tandem | F44ILL | 112 | 2.24 | SW | 8760 | 19,622 | NONE | |
| 15LED | Restroom | ARFF | 2 per day | 1 | 1x4 1 Lamp T-8 32W Wall Mounted | F41ILL | 31 | 0.03 | SW | 728 | 23 | NONE | |
| 15LED | Restroom | ARFF | 2 per day | 1 | 1x4 1 Lamp T-8 32W Wall Mounted | F41ILL | 31 | 0.03 | SW | 728 | 23 | NONE | |
| 36LED | Restroom | ARFF | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 36LED | Restroom | ARFF | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 36LED | bunk room | ARFF | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | |
| 36LED | captains bunk room | ARFF | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | |
| 36LED | Hallway | ARFF | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 36LED | Restroom | ARFF | 2 per day | 4 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.24 | SW | 728 | 172 | NONE | |
| 36LED | bunk room | ARFF | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | |
| 36LED | captains bunk room | ARFF | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | |
| 36LED | Hallway | ARFF | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 5LED | Stairs | ARFF | 24/7 | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| 5LED | Hallway | ARFF | 24/7 | 3 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.18 | SW | 8760 | 1,551 | NONE | |
| 36LED | Lounge Room | ARFF | 4 per day | 9 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.53 | SW | 1456 | 773 | NONE | |
| 36LED | Weight Room | ARFF | 4 per day | 11 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.65 | SW | 1456 | 945 | NONE | |
| 5LED | Stairs | ARFF | 24/7 | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 36LED | stairs | ARFF | 24/7 | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| 36LED | Stairs | ARFF | 24/7 | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 8760 | 517 | NONE | |
| 36LED | Command Center | ARFF | 24/7 | 12 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.71 | SW | 8760 | 6,202 | NONE | |
| 5LED | Hallway | ARFF | 8 per day | 3 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.18 | SW | 2912 | 515 | NONE | |
| 5LED | storage | ARFF | 1 per day | 1 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 26LED | Restroom | ARFF | 2 per day | 1 | 1x2 1 Lamp T-8 XXW Ceiling Mounted | F21ILL | 20 | 0.02 | SW | 728 | 15 | NONE | |
| 36LED | conference room | ARFF | 8 per day | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 3LED | storage | ARFF | 2 per day | 3 | 1x4 1 Lamp T-8 32W Celing Mounted | F41ILL | 31 | 0.09 | SW | 728 | 68 | NONE | |
| 6LED | Mechanical Room | ARFF | 2 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 6LED | Electrical Room | ARFF | 1 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 364 | 43 | NONE | |
| 73LED | Exterior | ARFF | PHC | 6 | 150 MH Wallpack | MH150/1 | 190 | 1.14 | SW | 4732 | 5,394 | NONE | |
| 36LED | Kitchen | ARFF | 8 per day | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 2912 | 1,031 | NONE | |
| 6LED | Mechanical Room | ARFF | 2 per day | 2 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | |
| 74LED | Garage | Airfield Maintenance Facility | 8 per day | 26 | 100 MH Hanging | MH100/1 | 128 | 3.33 | SW | 2912 | 9,691 | NONE | |
| 72LED | Garage | Airfield Maintenance Facility | 8 per day | 6 | 2x8 2 lamp 75W T-12 Hanging Fixture | F82SE | 158 | 0.95 | SW | 2912 | 2,761 | NONE | |
| 17LED | Workshop | Airfield Maintenance Facility | 2 per week | 12 | 1x4 2 Lamp T-8 32W Hanging | F42ILL | 59 | 0.71 | SW | 104 | 74 | NONE | |
| 5LED | Room 119 | Airfield Maintenance Facility | 8 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 2912 | 344 | NONE | |
| 72LED | Room117 | Airfield Maintenance Facility | 8 per day | 4 | 2x8 2 lamp 75W T-12 Hanging Fixture | F82SE | 158 | 0.63 | SW | 2912 | 1,840 | NONE | |
| 12LED | Room101 | Airfield Maintenance Facility | 8 per day | 8 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.90 | SW | 2912 | 2,609 | NONE | |
| 12LED | Room103 | Airfield Maintenance Facility | 8 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 2912 | 1,305 | NONE | |
| 12LED | Room 102 | Airfield Maintenance Facility | 8 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 2912 | 1,305 | NONE | |
| 12LED | Room 105 | Airfield Maintenance Facility | 8 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 2912 | 1,305 | NONE | |
| 12LED | Room 100 | Airfield Maintenance Facility | 1 per day | 4 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.45 | SW | 364 | 163 | NONE | |
| 12LED | Room 111 | Airfield Maintenance Facility | 8 per day | 6 | 2x4 4 Lamp T-8 32W Recessed | F44ILL | 112 | 0.67 | SW | 2912 | 1,957 | NONE | |
| 16LED | Hallway | Airfield Maintenance Facility | 24/7 | 6 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.35 | SW | 8760 | 3,101 | NONE | |
| 36LED | Exit Door | Airfield Maintenance Facility | 24/7 | 2 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.12 | SW | 8760 | 1,034 | NONE | |
| 36LED | Room 114 | Airfield Maintenance Facility | 4 per day | 6 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.35 | SW | 1456 | 515 | NONE | |
| 5LED | Room 115 | Airfield Maintenance Facility | 1 per day | 4 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.24 | SW | 364 | 86 | NONE | |
| 36LED | Restroom | Airfield Maintenance Facility | 1 per day | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 36LED | Restroom | Airfield Maintenance Facility | 1 per day | 1 | 2x4 2 Lamp T-8 32W Recressed | F42ILL | 59 | 0.06 | SW | 364 | 21 | NONE | |
| 16LED | Main Entry | Airfield Maintenance Facility | 24/7 | 4 | 2x2 2 Lamp T-8U 32W Recessed | FU2ILL | 59 | 0.24 | SW | 8760 | 2,067 | NONE | |
| 21LED | Main Entry | Airfield Maintenance Facility | 24/7 | 8 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.38 | SW | 8760 | 3,364 | NONE | |
| 10LED | Room 107 | Airfield Maintenance Facility | 4 per day | 6 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.53 | SW | 1456 | 778 | NONE | |
| 10LED | Drawing Room | Airfield Maintenance Facility | 4 per day | 1 | 2x4 3 Lamp T-8 32W Recessed | F43ILL | 89 | 0.09 | SW | 1456 | 130 | NONE | |
| 75LED | Back Garage | Airfield Maintenance Facility | 8 per day | 18 | 250 HPS Hanging | HPS250/1 | 295 | 5.31 | SW | 2912 | 15,463 | NONE | |
| 6LED | Guard Booth | Fuel Storage | 2 per day | 1 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 0.06 | SW | 728 | 43 | NONE | |
| 42LED | Exterior | Fuel Storage | PHC | 4 | 1 Lamp HPS 250W Shoe Box | HPS250/1 | 295 | 1.18 | SW | 4732 | 5,584 | NONE | |
| 46LED | Exterior | Fuel Storage | PHC | 2 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 0.93 | SW | 4732 | 4,401 | NONE | |
| 46LED | Exterior | Airfield Maintenance Facility | PHC | 6 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 2.79 | SW | 4732 | 13,202 | NONE | |
| 76LED | Exterior | Airfield Maintenance Facility | PHC | 1 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 0.93 | SW | 4732 | 4,401 | NONE | |
| 45LED | Exterior | Air Cargo Buildings | PHC | 5 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 5.50 | SW | 4732 | 26,026 | NONE | |
| LED | Exterior | Air Cargo Buildings | PHC | 4 | Existing LED | 0 | 0 | 0.00 | SW | 4732 | - | NONE | |
| 45LED | Exterior | Air Cargo Buildings | PHC | 16 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 17.60 | SW | 4732 | 83,283 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh
$0.00 $/kW

**Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 44LED | Exterior | Air Cargo Buildings | PHC | 6 | 1 Lamp MH 70W Wallpack | MH70/1 | 95 | 0.57 | SW | 4732 | 2,697 | NONE | |
| 44LED | Exterior | Air Cargo Buildings | PHC | 21 | 1 Lamp MH 70W Wallpack | MH70/1 | 95 | 2.00 | SW | 4732 | 9,440 | NONE | |
| 13LED | Interior | Air Cargo Buildings | 20 per day | 170 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 19.04 | SW | 7280 | 138,611 | NONE | Estimations based of off count and sqft |
| 6LED | Interior | Air Cargo Buildings | 20 per day | 85 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 5.02 | SW | 7280 | 36,509 | NONE | Estimations based of off count and sqft |
| 4LED | Interior | Air Cargo Buildings | 20 per day | 60 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 3.54 | SW | 7280 | 25,771 | NONE | Estimations based of off count and sqft |
| 20LED | Interior | Air Cargo Buildings | 20 per day | 34 | 6"RC 1 Lamp CFL 23W | CFS23/1 | 23 | 0.78 | SW | 7280 | 5,693 | NONE | Estimations based of off count and sqft |
| 13LED | Interior | Air Cargo Buildings | 20 per day | 60 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F44ILL | 112 | 6.72 | SW | 7280 | 48,922 | NONE | Estimations based of off count and sqft |
| 6LED | Interior | Air Cargo Buildings | 20 per day | 30 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 1.77 | SW | 7280 | 12,886 | NONE | Estimations based of off count and sqft |
| 4LED | Interior | Air Cargo Buildings | 20 per day | 21 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42ILL | 59 | 1.24 | SW | 7280 | 9,020 | NONE | Estimations based of off count and sqft |
| 20LED | Interior | Air Cargo Buildings | 20 per day | 12 | 6"RC 1 Lamp CFL 23W | CFS23/1 | 23 | 0.28 | SW | 7280 | 2,009 | NONE | Estimations based of off count and sqft |
| 42LED | Exterior | ARFF Storage | 10 per day | 3 | 1 Lamp HPS 250W Shoe Box | HPS250/1 | 295 | 0.89 | SW | 3640 | 3,221 | NONE | |
| 74LED | Garage | ARFF Storage | 24/7 | 3 | 100 MH Hanging | MH100/1 | 128 | 0.38 | SW | 8760 | 3,364 | NONE | |
| 74LED | Garage | ARFF Storage | 8 per day | 6 | 100 MH Hanging | MH100/1 | 128 | 0.77 | SW | 2912 | 2,236 | NONE | |
| 15LED | Garage | ARFF Storage | 8 per day | 1 | 1x4 1 Lamp T-8 32W Wall Mounted | F41ILL | 31 | 0.03 | SW | 2912 | 90 | NONE | |
| 76LED | Exterior | Exterior | PHC | 28 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 26.04 | SW | 4732 | 123,221 | NONE | |
| 43LED | Exterior | Exterior | PHC | 58 | 2 Lamp HPS 250W Shoe Box | HPS250/2 | 590 | 34.22 | SW | 4732 | 161,929 | NONE | |
| 42LED | Exterior | Exterior | PHC | 56 | 1 Lamp HPS 250W Shoe Box | HPS250/1 | 295 | 16.52 | SW | 4732 | 78,173 | NONE | |
| 46LED | Exterior | Exterior | PHC | 54 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 25.11 | SW | 4732 | 118,821 | NONE | |
| 77LED | Exterior | Arrivals | PHC | 66 | 400 HPS 1 Lamp | HPS400/1 | 465 | 30.69 | SW | 4732 | 145,225 | NONE | |
| 78LED | Exterior | Main Terminal | PHC | 39 | 250 HPS 1 Lamp | HPS250/1 | 295 | 11.51 | SW | 4732 | 54,442 | NONE | |
| 77LED | Exterior | Main Terminal | PHC | 13 | 400 HPS 1 Lamp | HPS400/1 | 465 | 6.05 | SW | 4732 | 28,605 | NONE | |
| 43LED | Short-Term Parking (Dominion) | Short-Term Parking | PHC | 8 | 2 Lamp HPS 250W Shoe Box | HPS250/2 | 590 | 4.72 | SW | 4732 | 22,335 | NONE | |
| 70LED | Short-Term Parking (Dominion) | Short-Term Parking | PHC | 16 | 150 HPS SHOEBOX | HPS150/1 | 170 | 2.72 | SW | 4732 | 12,871 | NONE | |
| 76LED | Long-Term Parking (Dominion) | Long-Term Parking | PHC | 36 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 33.48 | SW | 4732 | 158,427 | NONE | |
| 43LED | Long-Term Parking (Dominion) | Long-Term Parking | PHC | 6 | 2 Lamp HPS 250W Shoe Box | HPS250/2 | 590 | 3.54 | SW | 4732 | 16,751 | NONE | |
| 46LED | Long-Term Parking (Dominion) | Long-Term Parking | PHC | 10 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 4.65 | SW | 4732 | 22,004 | NONE | |
| 70LED | Long-Term Parking | Long-Term Parking | PHC | 16 | 150 HPS SHOEBOX | HPS150/1 | 170 | 2.72 | SW | 4732 | 12,871 | NONE | |
| 76LED | Exterior (Dominion) | TNC Staging Area | PHC | 2 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 1.86 | SW | 4732 | 8,802 | NONE | |
| 46LED | Exterior (Dominion) | TNC Staging Area | PHC | 4 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 1.86 | SW | 4732 | 8,802 | NONE | |
| 46LED | Top Floor | Parking Garage | PHC | 9 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 4.19 | SW | 4732 | 19,803 | NONE | |
| 76LED | Top Floor | Parking Garage | PHC | 30 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 27.90 | SW | 4732 | 132,023 | NONE | |
| 76LED | Employee Parking (1) (Dominion) | Exterior | PHC | 10 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 9.30 | SW | 4732 | 44,008 | NONE | |
| 46LED | Employee Parking (1) (Dominion) | Exterior | PHC | 20 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 9.30 | SW | 4732 | 44,008 | NONE | |
| 46LED | Employee Parking (2) (Dominion) | Exterior | PHC | 15 | 1 Lamp HPS 400W Shoebox | HPS400/1 | 465 | 6.98 | SW | 4732 | 33,006 | NONE | |
| 76LED | Employee Parking (2) (Dominion) | Exterior | PHC | 4 | 400 HPS 2 Head Shoebox | HPS400/2 | 930 | 3.72 | SW | 4732 | 17,603 | NONE | |
| 21LED | Waiting Area | TNC Staging Area | 4 per day | 12 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.58 | SW | 1456 | 839 | NONE | Could Not Find Notes this is estimated based on picture |
| 21LED | Lobby Area | TNC Staging Area | 4 per day | 8 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.38 | SW | 1456 | 559 | NONE | Could Not Find Notes this is estimated based on picture |
| 21LED | Lobby Area | TNC Staging Area | 10 per day | 8 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.38 | SW | 3640 | 1,398 | NONE | Could Not Find Notes this is estimated based on picture |
| 28LED | Lobby Area | TNC Staging Area | 4 per day | 8 | Wall CFL | CFT13/2 | 31 | 0.25 | SW | 1456 | 361 | NONE | Could Not Find Notes this is estimated based on picture |
| 33LED | Lobby Area | TNC Staging Area | 4 per day | 8 | 1x4 1 Lamp T-8 32W Recessed | F41ILL | 31 | 0.25 | SW | 1456 | 361 | NONE | Could Not Find Notes this is estimated based on picture |
| 21LED | Behind Counters | TNC Staging Area | 4 per day | 16 | 6"RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.77 | SW | 1456 | 1,118 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Vending Area | TNC Staging Area | 10 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 3640 | 859 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 1 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 2 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 3 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 4 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 5 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Office 6 | TNC Staging Area | 4 per day | 2 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.12 | SW | 1456 | 172 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Mens Restroom | TNC Staging Area | 10 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 3640 | 859 | NONE | Could Not Find Notes this is estimated based on picture |
| 11LED | Womens Restroom | TNC Staging Area | 10 per day | 4 | 2x4 2 Lamp T-8 32W Recessed | F42ILL | 59 | 0.24 | SW | 3640 | 859 | NONE | Could Not Find Notes this is estimated based on picture |
| 5LED | Mechanical Room | TNC Staging Area | 2 per day | 2 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 0.12 | SW | 728 | 86 | NONE | Could Not Find Notes this is estimated based on picture |
| 79LED | Second Floor Garage C (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | Second Floor Garage C | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | First Floor Garage C (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | First Floor Garage C | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | Third Floor Garage C (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | Third Floor Garage C | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | Partial First Floor Garage C (Outside Fxitures) | Parking Garage | 24/7toPHC | 20 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 1.70 | SW | 8760 | 14,892 | PHC | Based Off Drawings |
| 79LED | Partial First Floor Garage C | Parking Garage | 24/7 | 28 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 2.38 | SW | 8760 | 20,849 | NONE | Based Off Drawings |
| 79LED | Second Floor Garage B (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | Second Floor Garage B | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | First Floor Garage B (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | First Floor Garage B | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | Third Floor Garage B (Outside Fxitures) | Parking Garage | 24/7toPHC | 54 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 4.59 | SW | 8760 | 40,208 | PHC | Based Off Drawings |
| 79LED | Third Floor Garage B | Parking Garage | 24/7 | 100 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 8.50 | SW | 8760 | 74,460 | NONE | Based Off Drawings |
| 79LED | Partial First Floor Garage B (Outside Fxitures) | Parking Garage | 24/7toPHC | 20 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 1.70 | SW | 8760 | 14,892 | PHC | Based Off Drawings |
| 79LED | Partial First Floor Garage B | Parking Garage | 24/7 | 28 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 2.38 | SW | 8760 | 20,849 | NONE | Based Off Drawings |
| 80LED | Garage A Ground | Parking Garage | 24/7 | 109 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 13.08 | SW | 8760 | 114,581 | NONE | |
| 80LED | Garage A First Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Second Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Third Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Fourth Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Fifth Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Sixth Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Seventh Floor | Parking Garage | 24/7 | 102 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 12.24 | SW | 8760 | 107,222 | NONE | |
| 80LED | Garage A Ground | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A First Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Second Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Third Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Fourth Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Fifth Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Sixth Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Seventh Floor | Parking Garage | PHC | 75 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 9.00 | SW | 4732 | 42,588 | NONE | |
| 80LED | Garage A Ground Emergency | Parking Garage | 24/7 | 70 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 8.40 | SW | 8760 | 73,584 | NONE | |
| 80LED | Garage A First Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 80LED | Garage A Second Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |

**Energy Audit of Norfolk International Airport**
***CHA Project No. 33370***
**Existing Lighting & Audit Input**

**Cost of Electricity:** $0.000 $/kWh  $0.00 $/kW  **Cost of Lighting:** $0.145 $/kWh

| | | | | EXISTING CONDITIONS | | | | | | | | Retrofit Control | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | Usage | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | | |
| Field Code | Unique description of the location - Room number/Room name: Floor number (if applicable) | | Describe Usage Type using Operating Hours | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fixt) * (Fixt No.) | Pre-inst. control device | Estimated annual hours for the usage group | (kW/space) * (Annual Hours) | Retrofit control device | Notes |
| 80LED | Garage A Third Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 80LED | Garage A Fourth Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 80LED | Garage A Fifth Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 80LED | Garage A Sixth Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 80LED | Garage A Seventh Floor Emergency | Parking Garage | 24/7 | 54 | 100W HPS Ceilings Mounted Fixture | HPS100/1 | 120 | 6.48 | SW | 8760 | 56,765 | NONE | |
| 81LED | Helix | Parking Garage | 24/7toPHC | 89 | 150W HPS Ceilings Mounted Fixture | HPS150/1 | 170 | 15.13 | SW | 8760 | 132,539 | NONE | |
| 81LED | Helix Emergency | Parking Garage | 24/7toPHC | 47 | 150W HPS Ceilings Mounted Fixture | HPS150/1 | 170 | 7.99 | SW | 8760 | 69,992 | NONE | |
| 79LED | Garage A | Parking Garage | 24/7 | 6 | 70 HPS 1 Lamp Wallpack | HPS70/1 | 85 | 0.51 | SW | 8760 | 4,468 | NONE | |
| 5LED | Garage A | Parking Garage | 24/7 | 42 | 1x4 2 Lamp T-8 32W Celing Mounted | F42ILL | 59 | 2.48 | SW | 8760 | 21,707 | NONE | |
| 44LED | Garage A | Parking Garage | 24/7 | 30 | 1 Lamp MH 70W Wallpack | MH70/1 | 95 | 2.85 | SW | 8760 | 24,966 | NONE | |
| 82LED | Garage A | Parking Garage | 24/7 | 24 | 70W HPS Ceiling Mounted Fixture | HPS70/1 | 85 | 2.04 | SW | 8760 | 17,870 | NONE | |
| 82LED | Garage A Emergency | Parking Garage | 24/7 | 8 | 70W HPS Ceiling Mounted Fixture | HPS70/1 | 85 | 0.68 | SW | 8760 | 5,957 | NONE | |
| 83LED | Garage A | Parking Garage | 24/7 | 19 | 150W HPS Wallpack | HPS150/1 | 170 | 3.23 | SW | 8760 | 28,295 | NONE | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | Total | | | 1,406 | | | | 68.17 | | | 411,836 | | |

**Energy Audit of Norfolk International Airport**
**CHA Project No. 33370**
**L-1: Lighting Retrofit**

| | | | EXISTING CONDITIONS | | | | | | | RETROFIT CONDITIONS | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | Number of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Retrofit Control | Annual Hours | Annual kWh | ANALYSIS | | | | | | |
| Field Code | Unique description of the location - Room number/Room name / Floor number (if applicable) | | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix1) * (Fix1 / No.) | Pre-req. control device | Estimated daily hours for the usage group | (kWh/space) * (Annual Hours) | No. of fixtures after the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix) * (Number of Fixtures) | Retrofit control device | Estimated annual hours for the usage group | (kWh/space) * (Annual Hours) | Annual kWh Saved (Original Annual kWh) - (Retrofit Annual kWh) | Annual kW Saved (Original Annual kW) - (Retrofit Annual kW) | Annual $ Saved (kWh Saved) / ($/kWh) | Retrofit Cost Cost for renovations to lighting system | Simple Payback Length of time for renovations cost to be recovered |
| LED | Boiler Room | Main Terminal | 29 | Exiting LED | 0 | 0 | 0.0 | SW | 8760 | - | 29 | Exiting LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | | $ - | $ - | |
| LED | Boiler Room | Main Terminal | 3 | Exiting LED | 0 | 0 | 0.0 | SW | 8760 | - | 3 | Exiting LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | | $ - | $ - | |
| LED | Boiler Room | Main Terminal | 3 | Exiting LED | 0 | 0 | 0.0 | SW | 8760 | - | 3 | Exiting LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | | $ - | $ - | |
| 1LED | Generator Room | Main Terminal | 9 | 2x8 4 Lamp T-8 32W Hanging Tandem | F48/L | 112 | 1.0 | SW | 8760 | 8,830 | 9 | 4 ft LED Tube | 2007/32/4Z | 50 | 0.5 | NONE | 8760 | 4,730 | 4,100 2.5 | | $ - | $ 4,301.10 | |
| 2LED | Drawings Room | Main Terminal | 6 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.6 | SW | 8760 | 5,361 | 6 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.2 | OCC | 4368 | 655 | 4,706 0.5 | | $ - | $ - | |
| 2LED | Drawings Room | Main Terminal | 6 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.6 | SW | 8760 | 5,361 | 6 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.2 | OCC | 4368 | 655 | 4,706 0.5 | | $ - | $ - | |
| 2LED | Office 3105 | Main Terminal | 4 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.4 | SW | 8760 | 3,574 | 4 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.1 | OCC | 4368 | 437 | 3,137 0.3 | | $ - | $ - | |
| 2LED | Office 3105 | Main Terminal | 4 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.4 | SW | 8760 | 3,574 | 4 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.1 | OCC | 4368 | 437 | 3,137 0.3 | | $ - | $ - | |
| 2LED | Building Maintenance Office | Main Terminal | 4 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.4 | SW | 8760 | 3,574 | 4 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.1 | OCC | 4368 | 437 | 3,137 0.3 | | $ - | $ - | |
| 2LED | Basement Hallway | Main Terminal | 48 | 2x4 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 4.9 | SW | 8760 | 42,889 | 48 | 2x4 LED Troffer Recessed | 2ATL/ED | 25 | 1.2 | NONE | 8760 | 10,512 | 32,377 3.7 | | $ - | $ 23,232.80 | |
| 3LED | 101 | Main Terminal | 3 | 1x4 1 Lamp T-8 32W Ceiling Mounted | F41/L | 31 | 0.1 | SW | 8760 | 136 | 3 | 4 ft LED Tube | 2007/32/4T | 15 | 0.0 | NONE | 156 | 7 | 129 0.0 | | $ - | $ 358.43 | |
| 3LED | 101 | Main Terminal | 3 | 1x4 1 Lamp T-8 32W Ceiling Mounted | F41/L | 31 | 0.1 | SW | 8760 | 136 | 3 | 4 ft LED Tube | 2007/32/4T | 15 | 0.0 | NONE | 156 | 7 | 129 0.0 | | $ - | $ 358.43 | |
| 3LED | 102 | Main Terminal | 21 | 2x2 4 Lamp T-8 32W Recessed | F48/L | 112 | 2.4 | SW | 8760 | 18,764 | 21 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.5 | OCC | 4368 | 4,599 | 14,165 1.6 | | $ - | $ 10,503.98 | |
| 3LED | Police K-9 Office | Main Terminal | 5 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2184 | 387 | 3 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | NONE | 2184 | 197 | 190 0.1 | | $ - | $ 716.88 | |
| 4LED | 0134 Womens Room/Locker | Main Terminal | 4 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | OCC | 4368 | 524 | 1,543 0.1 | | $ - | $ - | |
| 4LED | 0134 Womens Room/Locker | Main Terminal | 3 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | OCC | 4368 | 393 | 1,157 0.1 | | $ - | $ - | |
| 4LED | 0134 Womens Room/Locker | Main Terminal | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/L | 59 | 0.1 | SW | 8760 | 517 | 1 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.0 | NONE | 8760 | 131 | 386 0.0 | | $ - | $ - | |
| 5LED | 119 | Main Terminal | 1 | 1x2 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.1 | SW | 720 | 43 | 1 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.0 | NONE | 720 | 22 | 21 0.0 | | $ - | $ 238.95 | |
| 5LED | Stair 105 (DE) | Main Terminal | 5 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.3 | SW | 8760 | 2,584 | 5 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 8760 | 1,752 | 832 0.1 | | $ - | $ 1,650.38 | |
| 5LED | Stair 105 (DE) | Main Terminal | 5 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.3 | SW | 8760 | 2,584 | 5 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 8760 | 1,752 | 832 0.1 | | $ - | $ 1,650.38 | |
| 6LED | 0126 Mens Room/Locker | Main Terminal | 4 | 2x2 3 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | OCC | 4368 | 524 | 1,543 0.1 | | $ - | $ - | |
| 6LED | 115 | Main Terminal | 8 | Single R/C 90W | B50/L | 90 | 0.7 | SW | 8760 | 3,272 | 8 | Single 4/3 9W | A19-9W/1 | 9 | 0.1 | NONE | 8760 | 236 | 1,537 0.4 | | $ - | $ 108.00 | |
| 10LED | Basement Hallway 2 | Main Terminal | 2 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.2 | SW | 8760 | 1,558 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.1 | NONE | 8760 | 666 | 894 0.1 | | $ - | $ 727.65 | |
| 11LED | Janitor Storage Room | Main Terminal | 2 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.2 | SW | 8760 | 1,956 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.2 | NONE | 8760 | 873 | 1,083 0.1 | | $ - | $ 795.15 | |
| 12LED | Janitor Office | Main Terminal | 2 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.2 | SW | 8760 | 783 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.1 | NONE | 8760 | 349 | 434 0.0 | | $ - | $ 795.15 | |
| 13LED | Janitor Office | Main Terminal | 2 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.2 | SW | 2912 | 652 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.1 | NONE | 2912 | 291 | 361 0.1 | | $ - | $ 795.15 | |
| 14LED | Janitor Assistance Office | Main Terminal | 2 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.2 | SW | 2912 | 652 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.1 | NONE | 2912 | 291 | 361 0.1 | | $ - | $ 795.15 | |
| 13LED | Storage 2 | Main Terminal | 2 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.2 | SW | 728 | 163 | 2 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.1 | NONE | 728 | 73 | 90 0.1 | | $ - | $ 795.15 | |
| 15LED | 0115 Telephone Room | Main Terminal | 1 | 2x4 4 Lamp T-8 32W Ceiling Mounted | F48/L | 112 | 0.1 | SW | 196 | 44 | 1 | 2X4 LED Troffer Ceiling Mounted | 2ATL/ED50 | 50 | 0.1 | NONE | 196 | 8 | 36 0.0 | | $ - | $ 367.98 | |
| 9LED | 0115 Telephone Room | Main Terminal | 3 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 35 | 3 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | NONE | 2912 | 44 | 14 0.1 | | $ - | $ 716.85 | |
| 9LED | Police Office | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 2912 | 1,035 | 4 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | NONE | 2912 | 133 | 902 0.1 | | $ - | $ 1,433.70 | |
| 25LED | Police Administration Office | Main Terminal | 6 | 2x2 3 Lamp CFT 40W Recessed | CFT4S/3-BX | 102 | 0.6 | SW | 8760 | 5,361 | 6 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.2 | NONE | 8760 | 1,314 | 4,047 0.5 | | $ - | $ 2,903.85 | |
| 14LED | Conference K Room | Main Terminal | 2 | 2x2 2 Lamp T-8 32W Ceiling Tandem | F42/L | 59 | 0.1 | SW | 8760 | 1,034 | 2 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | OCC | 4368 | 262 | 772 0.1 | | $ - | $ - | |
| 8LED | 116 | Main Terminal | 8 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.5 | SW | 964 | 172 | 8 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.2 | NONE | 964 | 87 | 84 0.2 | | $ - | $ 1,911.60 | |
| 19LED | Tug Bay and Crosswalk Thru Tunnel | Main Terminal | 3 | 1x4 1 Lamp T-8 32W Wall Mounted | F41/L | 31 | 0.1 | SW | 8760 | 815 | 3 | 4 ft LED Tube | 2007/32/4T | 15 | 0.0 | NONE | 8760 | 394 | 420 0.0 | | $ - | $ 435.60 | |
| 20LED | 0117 Office | Main Terminal | 3 | 1x4 1 Lamp T-8 32W Ceiling Mounted | F41/L | 31 | 0.0 | SW | 2912 | 90 | 3 | 4 ft LED Tube | 2007/32/4T | 15 | 0.0 | NONE | 2912 | 44 | 47 0.0 | | $ - | $ 116.48 | |
| 21LED | Norfolk Airport Authority Hall Department Head Office | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Norfolk Airport Authority Hall Storage | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2912 | 687 | 4 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 466 | 221 0.1 | | $ - | $ 1,320.30 | |
| 27LED | Norfolk Airport Authority Hall Kitchen | Main Terminal | 8 | 2x2 4 Lamp CFT 40W Recessed | CFT4S/2-BX | 72 | 0.6 | SW | 2912 | 1,677 | 8 | 2x2 LED Troffer Recessed | 2ATL/ED | 25 | 0.2 | NONE | 2912 | 582 | 1,095 0.4 | | $ - | $ 3,871.80 | |
| LED | Norfolk Airport Athority Hall Lounge | Main Terminal | 6 | Existing LED | 0 | 0 | 0.0 | SW | 2912 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 2912 | - | - 0.0 | | $ - | $ - | |
| 28LED | Norfolk Airport Athority Hall Restroom 1 | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 364 | 11 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 364 | 7 | 5 0.0 | | $ - | $ 27.00 | |
| 29LED | Norfolk Airport Athority Hall Restroom 2 | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 364 | 11 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 364 | 7 | 5 0.0 | | $ - | $ 27.00 | |
| 30LED | Norfolk Airport Authority Hall Restroom 3 | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 364 | 11 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 364 | 7 | 5 0.0 | | $ - | $ 27.00 | |
| 8LED | Office 2137 Office | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Receptionist Office | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | MR Screen Office | Main Terminal | 10 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.6 | SW | 2912 | 1,719 | 10 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.4 | NONE | 2912 | 1,165 | 553 0.2 | | $ - | $ 3,300.75 | |
| 29LED | MR Bowen Office restroom | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 2912 | 90 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 2912 | 52 | 38 0.0 | | $ - | $ 27.00 | |
| 8LED | MR Office 2139 | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | MR Sterling Office | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 11LED | Norfolk Airport Athority lobby | Main Terminal | 4 | 2x2 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2912 | 687 | 4 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.2 | NONE | 2912 | 443 | 245 0.1 | | $ - | $ 1,453.30 | |
| 29LED | Norfolk Airport Athority lobby | Main Terminal | 2 | Table Lamp | CFS13/1 | 23 | 0.0 | SW | 2912 | 134 | 2 | A19LED | A19-9W/1 | 9 | 0.0 | NONE | 2912 | 52 | 82 0.0 | | $ - | $ 27.00 | |
| 21LED | Norfolk Airport Athority lobby | Main Terminal | 3 | 4'RC 2 Lamp CFT 18W | CFT18/2 | 48 | 0.1 | SW | 2912 | 419 | 3 | A19LED | A19-9W/2 | 18 | 0.1 | NONE | 2912 | 167 | 252 0.1 | | $ - | $ 81.00 | |
| 22LED | Conference Room A-D Hall | Main Terminal | 10 | 2'RC 4 Lamp T-8 28W | Par38-70W/1 | 70 | 2.8 | SW | 2912 | 2,038 | 10 | Par38LED 1 Lamp | PAR38LED-700W/1 | 70 | 2.8 | NONE | 2912 | 728 | 1,310 2.8 | | $ - | $ 130.00 | |
| 23LED | Conference Room A-D Hall | Main Terminal | 5 | 2'RC 4 Lamp T-8 28W | Par38-70W/1 | 70 | 1.4 | SW | 2912 | 1,019 | 5 | Par38LED 1 Lamp | PAR38LED-700W/1 | 70 | 1.4 | NONE | 2912 | 364 | 655 1.4 | | $ - | $ 65.00 | |
| 8LED | Conference Room A-D Hall | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Conference Room C | Main Terminal | 5 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.3 | SW | 2912 | 859 | 5 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 582 | 277 0.1 | | $ - | $ 1,650.38 | |
| 31LED | Conference Room B | Main Terminal | 18 | 6'RC 1 Lamp Par38 400 | Par38-400W/1 | 400 | 0.7 | SW | 728 | 524 | 18 | Par38LED 1 Lamp | PAR38LED-400W/1 | 111 | 0.2 | NONE | 728 | 144 | 380 0.5 | | $ - | $ 243.00 | |
| 4LED | Conference Room B | Main Terminal | 10 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.6 | SW | 728 | 430 | 10 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.3 | NONE | 728 | 215 | 211 0.3 | | $ - | $ 2,389.30 | |
| 35LED | Conference Room C | Main Terminal | 52 | 6'RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 3.6 | SW | 728 | 2,650 | 52 | Par38LED 1 Lamp | PAR38LED-70W/1 | 275 | 1.3 | NONE | 728 | 946 | 1,704 2.3 | | $ - | $ 702.00 | |
| 32LED | Conference Room D - Quiet | Main Terminal | 4 | 2x2 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.4 | SW | 728 | 259 | 4 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.2 | NONE | 728 | 173 | 86 0.1 | | $ - | $ 1,960.60 | |
| 8LED | Conference Room D | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 728 | 259 | 4 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 728 | 173 | 83 0.1 | | $ - | $ 1,960.60 | |
| 8LED | Copy Room | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 728 | 172 | 4 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 728 | 118 | 55 0.1 | | $ - | $ 1,320.30 | |
| LED | Restroom | Main Terminal | 1 | Existing LED | 0 | 0 | 0.0 | SW | 728 | - | 1 | Existing LED | 0 | 0 | 0.0 | NONE | 728 | - | - 0.0 | | $ - | $ - | |
| 8LED | Electrical Room 2039 | Main Terminal | 1 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.0 | NONE | 728 | 22 | 21 0.0 | | $ - | $ 238.95 | |
| LED | Pantry | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2184 | 773 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2184 | 524 | 249 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Dishwashing Area | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2184 | 773 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2184 | 524 | 249 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Kitchen | Main Terminal | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.1 | SW | 728 | 86 | 2 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.1 | NONE | 728 | 44 | 42 0.1 | | $ - | $ 477.90 | |
| 11LED | TSA Office | Main Terminal | 6 | 2x2 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.2 | NONE | 2912 | 664 | 367 0.1 | | $ - | $ 2,182.95 | |
| 11LED | TSA Office | Main Terminal | 5 | 2x2 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.1 | SW | 2912 | 617 | 5 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.2 | NONE | 2912 | 333 | 284 0.0 | | $ - | $ 909.83 | |
| 29LED | Volunteer Office Mens Restroom | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 728 | 23 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 728 | 13 | 9 0.0 | | $ - | $ 27.00 | |
| 29LED | Volunteer Office Womens Restroom | Main Terminal | 1 | Wall CFL | CFT13/2 | 31 | 0.0 | SW | 728 | 23 | 1 | A19LED | A19-9W/2 | 13 | 0.0 | NONE | 728 | 13 | 9 0.0 | | $ - | $ 27.00 | |
| LED | Kitchen | Main Terminal | 3 | Existing LED | 0 | 0 | 0.0 | SW | 2912 | - | 3 | Existing LED | 0 | 0 | 0.0 | NONE | 2912 | - | - 0.0 | | $ - | $ - | |
| 8LED | Voulenteer Office Lead | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| 8LED | Voulenteer lounge | Main Terminal | 9 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 2912 | 1,546 | 9 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.3 | NONE | 2912 | 1,048 | 498 0.2 | | $ - | $ 2,970.68 | |
| 8LED | Airport authority Marketing Hallway | Main Terminal | 7 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,203 | 7 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.3 | NONE | 2912 | 815 | 387 0.1 | | $ - | $ 2,310.53 | |
| 8LED | Airport authority Marketing Office | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2912 | 687 | 4 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 466 | 221 0.1 | | $ - | $ 1,320.30 | |
| 8LED | Airport authority Marketing Room | Main Terminal | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2912 | 687 | 4 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 466 | 221 0.1 | | $ - | $ 1,320.30 | |
| 8LED | Airport Authority Marketing Office | Main Terminal | 5 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 2912 | 515 | 3 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.1 | NONE | 2912 | 349 | 166 0.1 | | $ - | $ 990.23 | |
| 18LED | Burger King Kitchen | Main Terminal | 10 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.6 | SW | 8760 | 5,183 | 10 | 1X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.4 | NONE | 8760 | 2,213 | 2,970 0.5 | | $ - | $ 3,836.25 | |
| 8LED | Breaker Room By Burger King | Main Terminal | 1 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.0 | NONE | 728 | 22 | 21 0.0 | | $ - | $ 238.95 | |
| 17LED | Storage By Burger King | Main Terminal | 5 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.3 | SW | 728 | 215 | 5 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 728 | 108 | 107 0.1 | | $ - | $ 963.15 | |
| 16LED | Starbucks Storage/Ice Room | Main Terminal | 3 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.1 | DOC | 8760 | 786 | 3 | 2X4 LED Troffer Recessed | 2ATL/ED38 | 38 | 0.1 | NONE | 8760 | 393 | 393 0.1 | | $ - | $ 1,153.13 | |
| 16LED | Starbucks Kitchen | Main Terminal | 28 | 2x4 3 Lamp T-8 32W Ceiling Mounted | F43/L | 89 | 2.5 | DOC | 8760 | 27,471 | 28 | 2X4 LED Troffer Ceiling Mounted | 2ATL/ED38 | 38 | 1.1 | NONE | 8760 | 12,264 | 15,207 1.7 | | $ - | $ 11,153.13 | |
| 15LED | Starbucks Hallway Office | Main Terminal | 1 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.1 | DOC | 8760 | 981 | 1 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.1 | NONE | 8760 | 438 | 543 0.1 | | $ - | $ 397.58 | |
| 13LED | Starbucks Internal Office | Main Terminal | 4 | 2x4 4 Lamp T-8 32W Recessed | F48/L | 112 | 0.4 | DOC | 8760 | 3,924 | 4 | 2X4 LED Troffer Recessed | 2ATL/ED50 | 50 | 0.2 | NONE | 8760 | 1,752 | 2,172 0.2 | | $ - | $ 1,590.30 | |
| 31LED | The Local Break Room/Storage | Main Terminal | 40 | 6'RC 1 Lamp Par38 400 | Par38-400W/1 | 400 | 2.7 | SW | 2184 | 524 | 6 | Par38LED 1 Lamp | PAR38LED-400W/1 | 111 | 0.2 | NONE | 2184 | 144 | 380 0.2 | | $ - | $ 81.00 | |
| 39LED | The Local Break Room/Storage | Main Terminal | 28 | 6'RC 1 Lamp Par38 70W | Par38-70W/1 | 70 | 2.0 | SW | 1456 | 2,854 | 28 | Par38LED 1 Lamp | PAR38LED-70W/1 | 275 | 0.7 | NONE | 1456 | 1,019 | 1,835 1.3 | | $ - | $ 378.00 | |
| 8LED | Office 2141 | Main Terminal | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.4 | SW | 2912 | 1,031 | 6 | 1X4 LED Troffer Recessed | 2ATL 4 6S, SW, EZ1 LP850 40 | 30 | 0.2 | NONE | 2912 | 699 | 332 0.1 | | $ - | $ 1,980.45 | |
| LED | Zone 15 Service Area | Main Terminal | 49 | Existing LED | 0 | 0 | 0.0 | SW | 4368 | - | 49 | Existing LED | 0 | 0 | 0.0 | NONE | 4368 | - | - 0.0 | | $ - | $ - | |
| 26LED | Zone 15 Service Area | Main Terminal | 50 | Wall CFL | CFT13/2 | 31 | 1.6 | SW | 5824 | 9,037 | 50 | A19LED | A19-9W/2 | 18 | 0.9 | NONE | 5824 | 5,242 | 3,796 0.7 | | $ - | $ 1,350.00 | |
| LED | Under Concourse B New Addition | Concourse B | 16 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 16 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | | $ - | $ - | |
| 33LED | Under Concourse B New Addition | Concourse B | 15 | 1x4 1 Lamp T-8 32W Recessed | F41/L | 31 | 4.3 | SW | 8760 | 37,747 | 139 | 4 ft LED Tube | 2007/32/4T | 15 | 2.1 | NONE | 8760 | 18,265 | 19,482 2.2 | | $ - | $ 16,807.03 | |
| LED | Under Concourse B New Addition | Concourse B | 1 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 1 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | | $ - | $ - | |
| 34LED | Under Concourse B New Addition | Concourse B | 59 | 6'RC 1 Lamp T-8 32W Recessed | F96/L | 96 | 5.7 | SW | 8760 | 14,624 | 108 | 6 ft LED Tube | 2007/32/6T | 53 | 5.7 | NONE | 8760 | 7,074 | 7,549 5.7 | | $ - | $ 12,903.30 | |
| 35LED | Concourse B Gate2A/2B | Concourse B | 48 | 1 Lamp T-8 28W Recessed | F41ALT5 | 27 | 1.3 | SW | 8760 | 10,680 | 48 | 4 ft LED Tube | 2007/32/4T | 15 | 0.7 | NONE | 8760 | 6,044 | 4,636 0.6 | | $ - | $ 6,670.20 | |
| 34LED | Concourse B Gate2A/2B | Concourse B | 4 | 4' RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.1 | SW | 8760 | 946 | 4 | A19LED | A19-9W/3 | 9 | 0.0 | NONE | 8760 | 375 | 571 0.1 | | $ - | $ 286.80 | |
| 39LED | Concourse B Gate 2B | Concourse B | 20 | 1 Lamp T-5 28W Recessed | F42ALT5 | 54 | 1.1 | SW | 8760 | 9,461 | 20 | 4 ft LED Tube | 2007/32/4Z | 30 | 0.6 | NONE | 8760 | 5,256 | 4,205 0.5 | | $ - | $ 4,779.00 | |
| 37LED | Concourse B 2J-2I | Concourse B | 54 | 1 Lamp T-5 28W Recessed | F42ALT5 | 54 | 4.5 | SW | 8760 | 39,730 | 54 | 4 ft LED Tube | 2007/32/4Z | 30 | 2.5 | NONE | 8760 | 22,070 | 17,660 2.0 | | $ - | $ 20,071.80 | |
| 34LED | Concourse B 2J-2I | Concourse B | 12 | 4' RC 1 Lamp CFL | CFQ26/1-L | 27 | 0.3 | SW | 8760 | 2,838 | 12 | A19LED | A19-9W/3 | 9 | 0.1 | NONE | 8760 | 946 | 1,892 0.2 | | $ - | $ 800.40 | |
| 38LED | Concourse B 2J-2I | Concourse B | 54 | 1 Lamp T-5 28W Recessed | F42ALT5 | 54 | 4.5 | SW | 8760 | 39,730 | 54 | 4 ft LED Tube | 2007/32/4Z | 30 | 2.5 | NONE | 8760 | 22,070 | 17,660 2.0 | | $ - | $ 20,071.80 | |
| 39LED | Concourse B 1J-1H | Concourse B | 11 | 1 Lamp T-5 28W Recessed | F42ALT5 | 54 | 1.0 | SW | 8760 

**Energy Audit of Norfolk International Airport**
**CHA Project No. 33370**
**L-1 Lighting Retrofit**

| | | | | EXISTING CONDITIONS | | | | | | | RETROFIT CONDITIONS | | | | | | | HAVLT'S$$ | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Area Description | | Facility | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | Number of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Retrofit Control | Annual Hours | Annual kWh | Annual kWh Saved | Annual $ Saved | Retrofit Cost | Simple Payback |
| Field Code | Unique description of the location - Room number/Room name/ Floor number (if applicable) | | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix) * (Fix / No.) | Pre-req. control device | Estimated daily hours for the usage group | (kWh/space) * (Annual Hours) | No. of fixtures after the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix) * (Number of Fixtures) | Retrofit control device | Estimated annual hours for the usage group | (kWh/space) * (Annual Hours) | (Original Annual kWh) - (Retrofit Annual kWh) | (Original Annual kW) - (Retrofit Annual kW) | ($/kWh) | Cost for renovations to lighting system | Length of time for renovations cost to be recovered |
| LED | ORF Market | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | ORF Market | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | ORF Market | Concourse B | 11 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 11 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | ORF Market | Concourse B | 3 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 3 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Hudson News "Middle" | Concourse B | 38 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 38 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Hudson News "Middle" | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Hudson News "Middle" | Concourse B | 16 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 16 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Hudson News "Middle" | Concourse B | 4 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 4 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Waiting Area | Concourse B | 12 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 0.6 | SW | 8760 | 5,678 | 12 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.4 | NONE | 8760 | 3,154 | 2,523 33.3 | $ - | $ 2,867.40 | |
| 34LED | Waiting Area | Concourse B | 6 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 6 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 631 | 1,261 33.1 | $ - | $ 533.60 | |
| 34LED | Waiting Area | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Gate 8/20 | Concourse B | 32 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.7 | SW | 8760 | 10,137 | 32 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.5 | NONE | 8760 | 8,410 | 5,728 5.6 | $ - | $ 7,646.40 | |
| 34LED | Gate 8/20 | Concourse B | 12 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.3 | SW | 8760 | 2,838 | 12 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 946 | 1,892 33.2 | $ - | $ 800.40 | |
| Existing LED | Gate 8/20 | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Gate 8/19 | Concourse B | 28 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.5 | SW | 8760 | 13,245 | 28 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.8 | NONE | 8760 | 7,358 | 5,887 23.7 | $ - | $ 6,690.60 | |
| 34LED | Gate 8/19 | Concourse B | 16 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.4 | SW | 8760 | 3,784 | 16 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 1,261 | 2,523 33.3 | $ - | $ 1,067.20 | |
| Existing LED | Gate 8/19 | Concourse B | 8 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 8 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Gate 8/17 | Concourse B | 20 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.0 | SW | 8760 | 9,463 | 20 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.5 | NONE | 8760 | 5,256 | 4,205 33.6 | $ - | $ 4,779.00 | |
| 34LED | Gate 8/17 | Concourse B | 16 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.4 | SW | 8760 | 3,784 | 16 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 1,261 | 2,523 33.3 | $ - | $ 1,067.20 | |
| Existing LED | Gate 8/17 | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Gate 8/17 | Concourse B | 24 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.3 | SW | 8760 | 11,353 | 24 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.7 | NONE | 8760 | 6,307 | 5,046 0.8 | $ - | $ 5,734.80 | |
| 34LED | Gate 8/17 | Concourse B | 16 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.4 | SW | 8760 | 3,784 | 16 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 1,261 | 2,523 33.3 | $ - | $ 1,067.20 | |
| LED | Gate 8/17 | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Starbucks | Concourse B | 20 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 20 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Starbucks | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Starbucks | Concourse B | 22 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 22 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | Starbucks | Concourse B | 4 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 4 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 39LED | Starbucks | Concourse B | 84 | 2x4 1 Lamp T-8 32W Recessed | F32/LT8 | 59 | 5.0 | SW | 8760 | 21,329 | 10 | 2x4 LED Troffer Recessed | RTLED38 | 38 | 0.4 | NONE | 8760 | 999 | 4,343 32.2 | $ - | $ 1,081.48 | |
| 34LED | Gate 8/16 | Concourse B | 19 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.0 | SW | 8760 | 8,989 | 19 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.5 | NONE | 8760 | 4,993 | 3,995 33.6 | $ - | $ 4,540.20 | |
| 34LED | Gate 8/16 | Concourse B | 16 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.4 | SW | 8760 | 3,784 | 16 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 1,261 | 2,523 33.3 | $ - | $ 1,067.20 | |
| LED | Gate 8/16 | Concourse B | 6 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 6 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | TSA Room 1 | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 1456 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 1456 | - | - 0.0 | $ - | $ - | |
| LED | TSA Room 2 | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 1456 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 1456 | - | - 0.0 | $ - | $ - | |
| LED | TSA Room 3 | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 1456 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 1456 | - | - 0.0 | $ - | $ - | |
| 39LED | TSA After Checkpoint | Concourse B | 25 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 1.4 | SW | 8760 | 11,828 | 25 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.8 | NONE | 8760 | 6,570 | 5,258 10.6 | $ - | $ 5,973.75 | |
| LED | TSA Office | Concourse B | 5 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 5 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | TSA Office | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 2184 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 2184 | - | - 0.0 | $ - | $ - | |
| LED | TSA Office | Concourse B | 8 | Existing LED | 0 | 0 | 0.0 | SW | 6552 | - | 8 | Existing LED | 0 | 0 | 0.0 | NONE | 6552 | - | - 0.0 | $ - | $ - | |
| 39LED | TSA Break Room | Concourse B | 12 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 0.6 | SW | 3,093 | 6 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.2 | NONE | 8760 | 2,097 | 996 33.2 | $ - | $ 2,640.00 | | |
| 39LED | Concourse B Hallway | Concourse B | 462 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 24.9 | SW | 8760 | 116,544 | 462 | 4 ft LED Tube | 2007/2Q2 | 30 | 13.9 | NONE | 8760 | 121,414 | 97,131 13.4 | $ - | $ 122,364.20 | |
| 34LED | Concourse B Hallway | Concourse B | 6 | 4' RC 1 Lamp CFL | CFQ/26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 6 | A19LED | A19-06W1 | 9 | 0.1 | NONE | 8760 | 631 | 1,261 33.1 | $ - | $ 533.60 | |
| LED | Hudson News "" | Concourse B | 1 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 1 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| LED | BackBay Bestro | Concourse B | 1 | Existing LED | 0 | 0 | 0.0 | SW | 8760 | - | 1 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - 0.0 | $ - | $ - | |
| 7LED | Stairwell By "A" | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 7LED | Stairwell By "A" 2 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 7LED | Stairwell By "A" 3 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 10LED | Av Ops Managers Office | Concourse B | 4 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.4 | SW | 2912 | 1,037 | 4 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.2 | NONE | 2912 | 443 | 594 33.2 | $ - | $ 1,455.30 | |
| 10LED | Av Ops Managers Office | Concourse B | 2 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.2 | SW | 728 | 130 | 2 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.1 | NONE | 728 | 55 | 74 33.1 | $ - | $ 727.65 | |
| 10LED | Av Ops Managers Office | Concourse B | 2 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.2 | SW | 728 | 130 | 2 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.1 | NONE | 728 | 55 | 74 33.1 | $ - | $ 727.65 | |
| 10LED | Av Ops Managers Office Hall | Concourse B | 4 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.4 | SW | 2912 | 1,037 | 4 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.2 | NONE | 2912 | 443 | 594 33.2 | $ - | $ 1,455.30 | |
| 36LED | Garage Wing/Ele Storage | Concourse B | 4 | 1x4 2 Lamp T-8 32W Recessed | F41/IL | 89 | 0.3 | SW | 728 | 173 | 4 | 1X4 LED Troffer Recessed | RTLED18 | 18 | 0.1 | NONE | 728 | 87 | 84 33.1 | $ - | $ 363.83 | |
| 10LED | RR-1 | Concourse B | 1 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.1 | SW | 728 | 65 | 1 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.0 | NONE | 728 | 28 | 37 33.1 | $ - | $ 363.83 | |
| 10LED | RR-2 | Concourse B | 1 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.1 | SW | 728 | 65 | 1 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.0 | NONE | 728 | 28 | 37 33.1 | $ - | $ 363.83 | |
| 10LED | Break Room | Concourse B | 4 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.4 | SW | 728 | 259 | 4 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.2 | NONE | 728 | 111 | 149 33.2 | $ - | $ 1,455.30 | |
| 7LED | Stairwell 5 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 10LED | United Offices | Concourse B | 25 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 2.2 | SW | 9624 | 12,958 | 25 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 1.0 | NONE | 9624 | 8,533 | 7,426 1.3 | $ - | $ 9,095.63 | |
| 10LED | Delta Ops | Concourse B | 6 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 0.5 | SW | 2184 | 778 | 6 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.2 | NONE | 2184 | 333 | 445 33.2 | $ - | $ 1,092.00 | |
| 36LED | Ark/Lib Room | Concourse B | 13 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.8 | SW | 728 | 556 | 13 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.4 | NONE | 728 | 254 | 214 0.4 | $ - | $ 556.33 | |
| 7LED | Stairwell 6 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 7LED | Stairwell 7 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 36LED | Airline Contractors Shop | Concourse B | 15 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.9 | SW | 2912 | 2,577 | 15 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.5 | NONE | 2912 | 1,310 | 1,267 33.4 | $ - | $ 3,584.25 | |
| 36LED | Airline Contractors Shop | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 344 | 2 | 1X4 LED Troffer Recessed | RTLED18 | 18 | 0.0 | NONE | 728 | 175 | 169 33.2 | $ - | $ 477.90 | |
| 36LED | Airline Contractors Locker Room | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 2912 | 344 | 2 | 1X4 LED Troffer Recessed | RTLED18 | 18 | 0.0 | NONE | 2912 | 175 | 169 33.0 | $ - | $ 477.90 | |
| 8LED | Delta Storage | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 728 | 86 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 728 | 44 | 42 33.1 | $ - | $ 477.90 | |
| 8LED | Delta Storage | Concourse B | 6 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.4 | SW | 8760 | 3,501 | 6 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.3 | NONE | 8760 | 1,577 | 1,924 33.2 | $ - | $ 1,433.70 | |
| 10LED | Delta Operations | Concourse B | 36 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 3.2 | SW | 8760 | 28,067 | 36 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 1.4 | NONE | 8760 | 11,984 | 16,083 11.8 | $ - | $ 13,067.70 | |
| 8LED | Mens Restroom | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 9624 | 697 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 9624 | 349 | 338 33.1 | $ - | $ 477.90 | |
| 7LED | Mens Restroom | Concourse B | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.1 | SW | 9624 | 344 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 9624 | 175 | 169 33.0 | $ - | $ 238.95 | |
| 8LED | Womens Restroom | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 9624 | 697 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 9624 | 349 | 338 33.1 | $ - | $ 477.90 | |
| 7LED | Womens Restroom | Concourse B | 1 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.1 | SW | 9624 | 344 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 9624 | 175 | 169 33.0 | $ - | $ 238.95 | |
| 8LED | Janitors Closet Delta | Concourse B | 1 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 728 | 22 | 21 33.0 | $ - | $ 238.95 | |
| 7LED | Stairwell 8 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 36LED | Ark/ Room 14 (1321) | Concourse B | 12 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.7 | SW | 728 | 515 | 12 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.4 | NONE | 728 | 262 | 253 33.3 | $ - | $ 2,867.40 | |
| 8LED | Storage B.7 | Concourse B | 1 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 86 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 728 | 44 | 42 33.1 | $ - | $ 238.95 | |
| 36LED | Delta Paint Shop BC06 | Concourse B | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.4 | SW | 728 | 259 | 4 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.2 | NONE | 728 | 111 | 127 33.2 | $ - | $ 1,433.70 | |
| 36LED | Delta Paint Shop BC06 | Concourse B | 1 | 2x2 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 728 | 22 | 21 33.0 | $ - | $ 238.95 | |
| 36LED | Snow Room 1002 | Concourse B | 10 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.6 | SW | 2184 | 1,289 | 10 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.3 | NONE | 2184 | 655 | 633 33.3 | $ - | $ 2,389.50 | |
| 7LED | Stairwell 10 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 36LED | Storage Room | Concourse B | 2 | 1x4 4 Lamp T-8 32W Hanging | F44/IL | 112 | 0.2 | SW | 728 | 130 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 728 | 55 | 74 33.1 | $ - | $ 727.65 | |
| 36LED | Storage B.9 | Concourse B | 2 | 1x4 4 Lamp T-8 32W Hanging | F44/IL | 112 | 0.2 | SW | 728 | 163 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 728 | 87 | 76 33.1 | $ - | $ 955.80 | |
| 36LED | Empty Chemical Bin Room | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 728 | 44 | 42 33.0 | $ - | $ 477.90 | |
| 36LED | Storage B.10 | Concourse B | 2 | 1x4 4 Lamp T-8 32W Hanging | F44/IL | 112 | 0.2 | SW | 728 | 163 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 728 | 87 | 76 33.1 | $ - | $ 955.80 | |
| 36LED | 5917/ Ark/ Room 15 | Concourse B | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.5 | SW | 728 | 344 | 8 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.2 | NONE | 728 | 175 | 169 33.2 | $ - | $ 1,911.60 | |
| 10LED | Old Signiture Office | Concourse B | 11 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 1.0 | SW | 0 | - | 11 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.4 | NONE | 0 | - | - 0.8 | $ - | $ 4,002.08 | |
| 8LED | Old Signiture Office | Concourse B | 9 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.5 | SW | 0 | - | 9 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.3 | NONE | 0 | - | - 0.3 | $ - | $ 2,150.55 | |
| 8LED | Old Signiture Office | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 0 | - | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 0 | - | - 0.1 | $ - | $ 477.90 | |
| 7LED | Stairwell 11 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 2912 | 1,031 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 2912 | 798 | 324 33.1 | $ - | $ 716.85 | |
| 7LED | Stairwell 12 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 7LED | Stairwell 13 | Concourse B | 3 | 1x4 2 Lamp T-8 32W Wall Mounted | F42/IL | 59 | 0.2 | SW | 8760 | 1,551 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 798 | 752 33.1 | $ - | $ 716.85 | |
| 8LED | Old American Airline Space/New Storage | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 1,034 | 2 | 1X4 LED Troffer Recessed | GTL 4 6L SWL EZ1LPB064C | 30 | 0.1 | NONE | 728 | 701 | 333 33.0 | $ - | $ 895.15 | |
| 8LED | Old American Airline Space/New Storage | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.4 | SW | 728 | 256 | 6 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.2 | NONE | 728 | 131 | 127 33.2 | $ - | $ 1,433.70 | |
| 8LED | Old American Airline Space/New Storage | Concourse B | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.4 | SW | 8760 | 3,772 | 6 | 1X4 LED Troffer Recessed | GTL 4 6L SWL EZ1LPB064C | 30 | 0.2 | NONE | 8760 | 1,701 | 2,071 33.1 | $ - | $ 1,980.60 | |
| 8LED | Old American Airline Space/New Storage | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 172 | 4 | 1X4 LED Troffer Recessed | RTLED38 | 38 | 0.1 | NONE | 728 | 87 | 84 33.1 | $ - | $ 955.80 | |
| 10LED | Kings Office Contractors | Concourse B | 30 | 2x4 3 Lamp T-8 32W Recessed | F41/IL | 89 | 2.7 | SW | 364 | 972 | 30 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 1.1 | NONE | 364 | 415 | 557 11.5 | $ - | $ 10,514.70 | |
| 8LED | 1014 Electrical Room | Concourse B | 1 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 364 | 21 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 364 | 11 | 11 33.0 | $ - | $ 238.95 | |
| 8LED | SRE Storage | Concourse B | 4 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.2 | SW | 364 | 86 | 4 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 364 | 44 | 42 33.1 | $ - | $ 955.80 | |
| 39LED | SRE Storage | Concourse B | 3 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.2 | SW | 8760 | 815 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 8760 | 394 | 420 33.0 | $ - | $ 358.43 | |
| 11LED | OH Ark/ 11 SVAD | Concourse B | 1 | 1x4 2 Lamp T-8 32W Hanging | F42/IL | 59 | 0.2 | SW | 364 | 64 | 3 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 364 | 33 | 32 33.1 | $ - | $ 716.85 | |
| 36LED | Air Field Maintenance Shop | Concourse B | 2 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 728 | 172 | 4 | 1X4 LED Troffer Recessed | RTLED18 | 18 | 0.1 | NONE | 728 | 87 | 84 33.1 | $ - | $ 955.80 | |
| 36LED | Air Field Maintenance Shop | Concourse B | 1 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.0 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.0 | NONE | 728 | 22 | 21 33.0 | $ - | $ 91.13 | |
| 36LED | Air Field Maintenance Shop Garage | Concourse B | 17 | 2x2 2 Lamp T-8 32W Recessed | F42/IL | 59 | 1.0 | SW | 5824 | 5,841 | 17 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.5 | NONE | 5824 | 2,870 | 2,871 33.5 | $ - | $ 4,062.15 | |
| 11LED | Air Field Maintenance Shop | Concourse B | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.5 | SW | 4366 | 2,062 | 8 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.3 | NONE | 4366 | 1,328 | 734 33.2 | $ - | $ 2,910.60 | |
| 11LED | BAS Light Garage | Concourse B | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.5 | SW | 4366 | 2,062 | 8 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.3 | NONE | 4366 | 1,328 | 734 33.2 | $ - | $ 2,910.60 | |
| 11LED | Empty Office | Concourse B | 1 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.1 | SW | 364 | 43 | 1 | 2X4 LED Troffer Recessed | RTLED38 | 38 | 0.0 | NONE | 364 | 22 | 21 33.0 | $ - | $ 727.65 | |
| LED | Empty Office | Concourse B | 2 | Existing LED | 0 | 0 | 0.0 | SW | 364 | - | 2 | Existing LED | 0 | 0 | 0.0 | NONE | 364 | - | - 0.0 | $ - | $ - | |
| 8LED | Stairwell 13 | Concourse B | 6 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.4 | SW | 8760 | 3,101 | 6 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.3 | NONE | 8760 | 2,102 | 999 33.1 | $ - | $ 1,980.45 | |
| 8LED | Office Contractor | Concourse B | 4 | 1x4 2 Lamp T-8 32W Recessed | F42/IL | 59 | 0.2 | SW | 2184 | 515 | 4 | 1X4 LED Troffer Recessed | GTL 4 4S SWL EZ1LPB064C | 30 | 0.2 | NONE | 2184 | 349 | 166 33.1 | $ - | $ 1,320.30 | |
| 8LED | Drawing Room | Concourse B | 2 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/IL | 59 | 0.1 | SW | 364 | 43 | 2 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 364 | 22 | 21 33.0 | $ - | $ 477.90 | |
| 39LED | Concourse B Exit Hall | Concourse B | 45 | 2 Lamp T-5 28W Recessed | F42/ILT5 | 54 | 2.4 | SW | 8760 | 21,287 | 45 | 4 ft LED Tube | 2007/2Q2 | 30 | 1.4 | NONE | 8760 | 11,826 | 9,461 11.1 | $ - | $ 10,752.75 | |
| 39LED | TSA Pre-Check | Concourse B | 4 | Lamp T-5 28W Recessed | F42/ILT5 | 54 | 0.2 | SW | 1,498 | 359 | 4 | 4 ft LED Tube | 2007/2Q2 | 30 | 0.1 | NONE | 1,498 | 599 | 359 33.3 | $ - | $ 955.80 | |
| 39LED | TSA Pre-Check | Concourse B | 126 | Lamp T-5 28W Recessed | F42/ILT5 | 54 | 6.8 | SW | 8760 | 59,603 | 126 | 4 ft LED Tube | 2007/2Q2 | 30 | 3.8 | NONE | 8760 |

**Energy Audit of Norfolk International Airport**
**Ch4 Project No. 33370**
**L-1 Lighting Retrofit**

| | | | | | EXISTING CONDITIONS | | | | | | RETROFIT CONDITIONS | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Area Description | Facility | No. of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Exist Control | Annual Hours | Annual kWh | Number of Fixtures | Standard Fixture Code | Fixture Code | Watts per Fixture | kW/Space | Retrofit Control | Annual Hours | Annual kWh | MMLV'SS Annual kWh Saved | Annual kW Saved | Annual $ Saved | Retrofit Cost | Simple Payback |
| Field Code | Unique description of the location - Room number/Room name / Floor number (if applicable) | | No. of fixtures before the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix) * (Fix / No.) | Pre-retrofit control device | Estimated daily hours for the usage group | (kW/spaces) * (Annual Hours) | No. of fixtures after the retrofit | Lighting Fixture Code | Code from Table of Standard Fixture Wattages | Value from Table of Standard Fixture Wattages | (Watts/Fix) * (Number of Fixtures) | Retrofit control device | Estimated annual hours for the usage group | (kW/spaces) * (Annual Hours) | (Original Annual kWh) - (Retrofit Annual kWh) | (Original Annual kW) - (Retrofit Annual kW) | (kWh Saved) * ($/kWh) | Cost for renovations to lighting system | Length of time for renovations cost to be recovered |
| 24LED | Communication Room | Arrivals | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F48/L | 112 | 0.2 | SW | 728 | 163 | 2 | 4 ft LED Tube | 2007/32x4 | 50 | 0.1 | NONE | 728 | 87 | 76 | 0.1 | $ - | $ | 955.80 |
| 24LED | Storage 1 B | Arrivals | 2 | 1x8 4 Lamp T-8 32W Ceiling Mounted | F48/L | 112 | 0.2 | SW | 728 | 163 | 2 | 4 ft LED Tube | 2007/32x4 | 50 | 0.1 | NONE | 728 | 87 | 76 | 0.1 | $ - | $ | 955.80 |
| 11LED | Old Baggage Claim | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 728 | 344 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 728 | 221 | 122 | 0.2 | $ - | $ | 2,910.80 |
| 11LED | United Baggage | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 7280 | 3,436 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 7280 | 2,213 | 1,223 | 0.2 | $ - | $ | 2,910.80 |
| 11LED | Old Baggage Claim | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 728 | 344 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 728 | 221 | 122 | 0.2 | $ - | $ | 2,910.80 |
| 11LED | Old Baggage Claim | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 728 | 344 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 728 | 221 | 122 | 0.2 | $ - | $ | 2,910.80 |
| 11LED | Old Baggage Claim Office | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 728 | 344 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 728 | 221 | 122 | 0.2 | $ - | $ | 2,910.80 |
| 11LED | Old Office | Arrivals | 8 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.5 | SW | 728 | 344 | 8 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.3 | NONE | 728 | 221 | 122 | 0.2 | $ - | $ | 2,910.80 |
| 44LED | Tunnel to Arrivals (Driving) | Exterior | 50 | 1 Lamp MH 70W Wallpack | MH70/1 | 95 | 4.8 | SW | 8760 | 41,610 | 50 | 27W LED Wallpack | FXLED18/1 | 18 | 0.9 | NONE | 8760 | 7,884 | 33,726 | 3.9 | $ - | $ | 1,181.25 |
| 49LED | Concourse A Poles | Exterior | 63 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 69.3 | SW | 4366 | 302,702 | 63 | 300W LED Shoebox | 30KLED/HD/E | 300 | 18.9 | NONE | 4368 | 82,555 | 220,147 | 50.4 | $ - | $ | 51,030.00 |
| 49LED | Concourse A Wall Sconce | Exterior | 4 | 1 Lamp HPS 150W Wallpack | HPS150/1 | 400 | 1.6 | SW | 8760 | 14,016 | 4 | 60W LED Flood Box | 20KLED/HD/E | 200 | 0.8 | NONE | 8760 | 7,884 | 6,132 | 0.8 | $ - | $ | 1,418.00 |
| 17LED | Fire Pump Room | Concourse A | 2 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F48/L | 112 | 0.2 | SW | 8760 | 3,501 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 876 | 2,625 | 0.2 | $ - | $ | 607.50 |
| 17LED | Fire Pump Room | Concourse A | 2 | 1x8 2 Lamp T-8 32W Hanging | F42/L | 59 | 0.1 | SW | 8760 | 1,034 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 526 | 508 | 0.1 | $ - | $ | 477.90 |
| 33LED | Concourse A Stairwell 2 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Hanging | F42/L | 59 | 0.1 | SW | 8760 | 1,086 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 526 | 561 | 0.1 | $ - | $ | 477.90 |
| 13LED | Storage Room End Of Concourse | Concourse A | 2 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.2 | SW | 728 | 163 | 2 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.1 | NONE | 728 | 73 | 90 | 0.1 | $ - | $ | 795.15 |
| 13LED | 1139 Electrical Room | Concourse A | 2 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.2 | SW | 728 | 163 | 2 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.1 | NONE | 728 | 73 | 90 | 0.1 | $ - | $ | 795.15 |
| 47LED | 1139 Electrical Room | Concourse A | 1 | 1x4 1 Lamp T-8 32W Hanging | F41/L | 31 | 0.0 | SW | 728 | 23 | 1 | 4 ft LED Tube | 2007/32x1 | 15 | 0.0 | NONE | 728 | 11 | 12 | 0.0 | $ - | $ | 119.48 |
| 13LED | 1140 | Concourse A | 2 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.2 | SW | 728 | 163 | 2 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.1 | NONE | 728 | 73 | 90 | 0.1 | $ - | $ | 795.15 |
| 15LED | 1145 (lighting/Storage) | Concourse A | 16 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 1.8 | SW | 728 | 1,305 | 16 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.8 | NONE | 728 | 582 | 722 | 0.8 | $ - | $ | 6,361.20 |
| 29LED | 1145 (lighting/Storage) | Concourse A | 3 | 1x8 2 Lamp T-8 65W Wall Mounted | F65/L | 109 | 0.3 | SW | 728 | 238 | 3 | 8 ft LED Tube | 2016/65x2 | 70 | 0.2 | NONE | 728 | 153 | 85 | 0.1 | $ - | $ | 843.62 |
| 11LED | PSA Hallway | Concourse A | 5 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.3 | SW | 8760 | 2,584 | 5 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.2 | NONE | 8760 | 1,664 | 920 | 0.1 | $ - | $ | 1,819.13 |
| 12LED | PSA Office | Concourse A | 7 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.8 | SW | 1456 | 1,142 | 7 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.4 | NONE | 1456 | 910 | 232 | 0.4 | $ - | $ | 2,783.03 |
| 12LED | PSA Office | Concourse A | 2 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.2 | SW | 728 | 163 | 2 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.1 | NONE | 728 | 73 | 90 | 0.1 | $ - | $ | 795.15 |
| 12LED | PSA Office | Concourse A | 2 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.2 | SW | 2912 | 652 | 2 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.1 | NONE | 2912 | 291 | 361 | 0.1 | $ - | $ | 795.15 |
| 36LED | 1152 | Concourse A | 2 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 84 | 0.1 | SW | 8760 | 1,034 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 526 | 508 | 0.1 | $ - | $ | 477.90 |
| 36LED | SRE Storage | Concourse A | 23 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 84 | 1.4 | SW | 728 | 689 | 23 | 4 ft LED Tube | 2007/32x2 | 50 | 0.4 | NONE | 728 | 302 | 488 | 0.7 | $ - | $ | 5,495.85 |
| 9LED | Stairwell 3 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 10LED | AE 10 (WK) | Concourse A | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 112 | 0.4 | SW | 728 | 326 | 4 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.2 | NONE | 728 | 146 | 181 | 0.2 | $ - | $ | 1,590.30 |
| 9LED | AE 10 (WK) | Concourse A | 1 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 21 | 0.0 | $ - | $ | 238.95 |
| 9LED | Old General Storage (Storage) | Concourse A | 1 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 21 | 0.0 | $ - | $ | 238.95 |
| 13LED | 1107 Signture Office | Concourse A | 7 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 0.8 | SW | 2912 | 2,283 | 7 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 0.4 | NONE | 2912 | 1,019 | 1,264 | 0.4 | $ - | $ | 2,783.03 |
| 33LED | Signture Hallway | Concourse A | 2 | 1x4 1 Lamp T-8 32W Hanging | F41/L | 31 | 0.1 | SW | 8760 | 543 | 2 | 4 ft LED Tube | 2007/32x1 | 15 | 0.0 | NONE | 8760 | 263 | 280 | 0.0 | $ - | $ | 238.95 |
| 6LED | AE12 (WK)(13 Room) | Concourse A | 3 | 1x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 129 | 3 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 66 | 63 | 0.1 | $ - | $ | 716.85 |
| 9LED | Stairwell 4 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 9LED | Stairwell 5 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 34LED | American Airlines Office | Concourse A | 18 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 1.1 | SW | 2912 | 5,693 | 18 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.7 | NONE | 2912 | 1,992 | 3,701 | 0.4 | $ - | $ | 5,468.03 |
| 8LED | American Airlines Office | Concourse A | 8 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.5 | SW | 2912 | 1,574 | 8 | 4 ft LED Tube | 2007/32x2 | 50 | 0.2 | NONE | 2912 | 699 | 876 | 0.2 | $ - | $ | 1,911.60 |
| 7LED | American Airlines Office | Concourse A | 2 | 1x8 2 Lamp T-8 32W Wall Mounted | F42/L | 59 | 0.1 | SW | 2912 | 544 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 2912 | 175 | 169 | 0.1 | $ - | $ | 477.90 |
| 6LED | American Airlines Storage | Concourse A | 10 | 2x4 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.6 | SW | 8760 | 5,168 | 10 | 4 ft LED Tube | 2007/32x2 | 50 | 0.3 | NONE | 8760 | 2,628 | 2,540 | 0.3 | $ - | $ | 2,389.50 |
| 33LED | American Airlines Storage | Concourse A | 10 | 1x4 2 Lamp T-8 32W Recessed | F41/L | 31 | 0.3 | SW | 8760 | 2,716 | 10 | 4 ft LED Tube | 2007/32x1 | 15 | 0.1 | NONE | 8760 | 1,314 | 1,402 | 0.2 | $ - | $ | 1,194.75 |
| 11LED | Stairwell 1 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 11LED | Stairwell 2 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 10LED | 1069 American Airline Operations | Concourse A | 22 | 2x4 4 Lamp T-8 32W Recessed | F44/L | 112 | 2.5 | SW | 2912 | 7,175 | 22 | 2X4 LED Troffer Recessed | RTL/ED50 | 50 | 1.1 | NONE | 2912 | 3,203 | 3,972 | 1.4 | $ - | $ | 8,748.83 |
| 33LED | Under Concourse A | Concourse A | 70 | 1x4 1 Lamp T-8 32W Recessed | F41/L | 31 | 2.2 | SW | 8760 | 19,009 | 70 | 4 ft LED Tube | 2007/32x1 | 15 | 1.1 | NONE | 8760 | 9,198 | 9,811 | 1.1 | $ - | $ | 8,363.25 |
| 1LED | Under Concourse A | Concourse A | 20 | 1 Lamp LED Lamp | | 0 | 0.0 | SW | 8760 | - | 20 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - | 0.0 | $ - | $ | - |
| 36LED | AD11 (AA) (12 Room) | Concourse A | 4 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.2 | SW | 728 | 172 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 87 | 84 | 0.1 | $ - | $ | 955.80 |
| 1LED | Under Concourse A | Concourse A | 20 | 1 Lamp LED Lamp | | 0 | 0.0 | SW | 8760 | - | 20 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - | 0.0 | $ - | $ | - |
| 11LED | Southwest Office | Concourse A | 11 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.6 | SW | 2912 | 1,990 | 11 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.4 | NONE | 2912 | 1,217 | 673 | 0.2 | $ - | $ | 4,002.08 |
| 9LED | Stairwell 7 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 39LED | American Airline Storage/Repair | Concourse A | 10 | 2x4 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.6 | SW | 2184 | 1,289 | 10 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.6 | NONE | 2184 | 655 | 633 | 0.3 | $ - | $ | 2,389.50 |
| 8LED | Customs | Concourse A | 51 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 3.0 | SW | 8760 | 26,359 | 51 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 2.0 | NONE | 8760 | 17,870 | 8,488 | 1.0 | $ - | $ | 16,933.83 |
| 8LED | Customs | Concourse A | 51 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 3.0 | SW | 8760 | 26,359 | 51 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 2.0 | NONE | 8760 | 17,870 | 8,488 | 1.0 | $ - | $ | 16,933.83 |
| 56LED | AH5/2100 Mechanical Equipment Room | Concourse A | 1 | EPBC 2 Lamp CFT 18W | CFT18/2 | 40 | 0.0 | SW | 7280 | 1,680 | 1 | 1X4 LED Troffer Recessed | A18LED | 18 | 0.0 | NONE | 7280 | 1,008 | 672 | 0.0 | $ - | $ | 67.20 |
| 21LED | Chaplain | Concourse A | 20 | EPBC 2 Lamp CFT 18W | CFT18/2 | 40 | 1.0 | SW | 8760 | 8,410 | 20 | A18LED | A18-09/02 | 18 | 0.4 | NONE | 8760 | 3,154 | 5,256 | 0.6 | $ - | $ | 840.00 |
| 10LED | Agriculture Lab | Concourse A | 4 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 84 | 0.4 | SW | 1456 | 518 | 4 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.1 | NONE | 1456 | 221 | 297 | 0.2 | $ - | $ | 1,455.30 |
| 10LED | Agriculture Lab Office | Concourse A | 2 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.2 | SW | 2912 | 518 | 2 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.1 | NONE | 2912 | 221 | 297 | 0.1 | $ - | $ | 727.65 |
| 10LED | Isolation | Concourse A | 4 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.4 | SW | 364 | 130 | 4 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.2 | NONE | 364 | 55 | 74 | 0.2 | $ - | $ | 1,455.30 |
| 10LED | Chaplain | Concourse A | 2 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 0.2 | SW | 364 | 65 | 2 | 2X4 LED Troffer Recessed | RTL/ED38 | 38 | 0.1 | NONE | 364 | 28 | 37 | 0.1 | $ - | $ | 727.65 |
| 21LED | Customs Office | Concourse A | 14 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 89 | 1.2 | SW | 2912 | 3,628 | 14 | 2X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.5 | NONE | 2912 | 1,549 | 2,079 | 0.7 | $ - | $ | 5,093.55 |
| 21LED | Customs Lobby | Concourse A | 12 | EPBC 2 Lamp CFT 18W | CFT18/2 | 40 | 0.5 | SW | 8760 | 4,205 | 12 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.2 | NONE | 8760 | 1,892 | 2,313 | 0.3 | $ - | $ | 460.13 |
| 8LED | Holding 2 | Concourse A | 2 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.1 | SW | 364 | 43 | 2 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.1 | NONE | 364 | 14 | 14 | 0.0 | $ - | $ | 660.13 |
| 8LED | Holding 3 | Concourse A | 2 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.1 | SW | 364 | 43 | 2 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.1 | NONE | 364 | 29 | 14 | 0.0 | $ - | $ | 660.13 |
| 21LED | Customs Office Supervisors | Concourse A | 5 | EPBC 2 Lamp CFT 18W | CFT18/2 | 40 | 0.2 | SW | 2912 | 699 | 5 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 2912 | 262 | 437 | 0.2 | $ - | $ | 126.00 |
| 9LED | Stairwell 8 | Concourse A | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 8760 | 2,067 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 1,051 | 1,016 | 0.1 | $ - | $ | 955.80 |
| 21LED | Customs Hallway | Concourse A | 6 | EPBC 2 Lamp CFT 18W | CFT18/2 | 40 | 0.2 | SW | 8760 | 2,524 | 6 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 8760 | 631 | 1,893 | 0.2 | $ - | $ | 54.00 |
| 8LED | Customs Elevator lobby RR | Concourse A | 18 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 1.1 | SW | 8760 | 9,303 | 18 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.7 | NONE | 8760 | 6,307 | 2,996 | 0.3 | $ - | $ | 5,941.35 |
| 8LED | Customs Elevator lobby | Concourse A | 1 | 1x8 2 Lamp T-8 32W Recessed | F42/L | 59 | 0.1 | SW | 8760 | 517 | 1 | 1X4 LED Troffer Recessed | GTL 4 6S, SW, EZ1 LPB5040 | | 0.0 | NONE | 8760 | 351 | 166 | 0.0 | $ - | $ | 330.08 |
| 16LED | Womens Restroom | Concourse A | 1 | 2x2 Lamp 1-6U 32W Recessed | FU26/L | 59 | 0.1 | SW | 728 | 43 | 1 | 2x2 LED Troffer Recessed | 2HTLED | 25 | 0.0 | NONE | 728 | 18 | 25 | 0.0 | $ - | $ | 363.83 |
| 29LED | Mens Restroom | Concourse A | 2 | 1x8 2 Lamp T-8 65W Wall Mounted | F65/L | 109 | 0.2 | SW | 728 | 159 | 2 | 8 ft LED Tube | 2016/65x2 | 70 | 0.1 | NONE | 728 | 102 | 57 | 0.1 | $ - | $ | 562.41 |
| 16LED | Mens Restroom | Concourse A | 1 | 2x2 Lamp 1-6U 32W Recessed | FU26/L | 59 | 0.1 | SW | 728 | 43 | 1 | 2x2 LED Troffer Recessed | 2HTLED | 25 | 0.0 | NONE | 728 | 18 | 25 | 0.0 | $ - | $ | 363.83 |
| 8LED | Janitor Closet | Concourse A | 1 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 21 | 0.0 | $ - | $ | 238.95 |
| 8LED | Janitor Closet | Concourse A | 1 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 21 | 0.0 | $ - | $ | 238.95 |
| 8LED | Electrical Room Room | Concourse A | 1 | 1x8 2 Lamp T-8 32W Mounted | F42/L | 59 | 0.1 | SW | 728 | 43 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 21 | 0.0 | $ - | $ | 238.95 |
| 36LED | Southeast Garage | Concourse A | 6 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 84 | 0.5 | SW | 3,101 | 1,577 | 6 | 4 ft LED Tube | 2007/32x2 | 50 | 0.2 | NONE | 8760 | 1,577 | 1,524 | 0.2 | $ - | $ | 1,433.70 |
| 36LED | Southwest Ice Room | Concourse A | 2 | 2x4 3 Lamp T-8 32W Recessed | F43/L | 84 | 0.2 | SW | 8760 | 1,034 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 8760 | 526 | 508 | 0.1 | $ - | $ | 477.90 |
| 49LED | Concourse A Poles | Concourse A | 24 | 1 Lamp HPS 1000W Shoebox | HPS1000/1 | 1100 | 26.4 | SW | 4366 | 115,315 | 24 | 300W LED Shoebox | 30KLED/HD/E | 300 | 7.2 | NONE | 4368 | 31,490 | 83,866 | 19.2 | $ - | $ | 19,440.00 |
| 1LED | Under E&A Precheck | Concourse A | 35 | 1 Lamp LED Lamp | | 0 | 0.0 | SW | 4368 | - | 35 | Existing LED | 0 | 0 | 0.0 | NONE | 4368 | - | - | 0.0 | $ - | $ | - |
| 49LED | Crawl Space A to Departures | Main Terminal | 10 | 1x4 1 Lamp T-2 28W Ceiling Mount | F41/L/T2 | 27 | 0.3 | SW | 8760 | 2,365 | 10 | 4 ft LED Tube | 2007/32x1 | 15 | 0.2 | NONE | 8760 | 1,314 | 1,051 | 0.1 | $ - | $ | 1,194.75 |
| 49LED | Crawl Space A to Departures | Main Terminal | 10 | Single CFL 23W | CF32/1 | 23 | 0.2 | SW | 8760 | 2,014 | 10 | A18LED | A18-09/02 | 18 | 0.2 | NONE | 8760 | 1,810 | 1,204 | 0.1 | $ - | $ | 1,194.75 |
| 49LED | Crawl Space 2 | Main Terminal | 10 | 1x4 1 Lamp T-2 28W Ceiling Mount | F41/L/T2 | 27 | 0.3 | SW | 8760 | 2,365 | 10 | 4 ft LED Tube | 2007/32x1 | 15 | 0.2 | NONE | 8760 | 1,314 | 1,051 | 0.1 | $ - | $ | 1,194.75 |
| 49LED | Crawl Space 2 | Main Terminal | 15 | Single CFL 23W | CF32/1 | 23 | 0.3 | SW | 8760 | 3,022 | 15 | A18LED | A18-09/02 | 18 | 0.3 | NONE | 8760 | 1,183 | 1,840 | 0.2 | $ - | $ | 202.50 |
| 41LED | Storage | Main Terminal | 2 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 86 | 2 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 44 | 42 | 0.1 | $ - | $ | 477.90 |
| 41LED | Storage | Main Terminal | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 172 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 87 | 84 | 0.1 | $ - | $ | 955.80 |
| 1LED | Tunnel A to Departures | Main Terminal | 20 | 1 Lamp LED Lamp | | 0 | 0.0 | SW | 8760 | 15,768 | 20 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - | 0.0 | $ - | $ | - |
| 24LED | Tunnel A to Departures | Main Terminal | 20 | 1x8 4 Lamp T-8 32W Recessed | F48/L | 112 | 2.2 | SW | 8760 | 1,960 | 20 | 4 ft LED Tube | 2007/32x4 | 50 | 0.5 | NONE | 8760 | 1,051 | 911 | 0.1 | $ - | $ | 9,559.00 |
| 39LED | Elevator Room | Main Terminal | 1 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 0.1 | SW | 728 | 39 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 17 | 0.0 | $ - | $ | 238.95 |
| 39LED | Elevator Room | Main Terminal | 1 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 0.1 | SW | 728 | 39 | 1 | 4 ft LED Tube | 2007/32x2 | 50 | 0.0 | NONE | 728 | 22 | 17 | 0.0 | $ - | $ | 238.95 |
| 41LED | Fan Room | Main Terminal | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 172 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 87 | 84 | 0.1 | $ - | $ | 955.80 |
| 41LED | Fan Room | Main Terminal | 4 | 1x8 2 Lamp T-8 32W Ceiling Mounted | F42/L | 59 | 0.2 | SW | 728 | 172 | 4 | 4 ft LED Tube | 2007/32x2 | 50 | 0.1 | NONE | 728 | 87 | 84 | 0.1 | $ - | $ | 955.80 |
| 17LED | Lg Bay | Main Terminal | 10 | 1x32 4 Lamp T-8 32W Hanging | F48/L | 112 | 1.7 | SW | 8760 | 14,717 | 10 | 4 ft LED Tube | 2007/32x4 | 50 | 0.5 | NONE | 8760 | 7,884 | 6,833 | 0.8 | $ - | $ | 1,195.50 |
| 17LED | Lg Bay | Main Terminal | 33 | 1x32 4 Lamp T-8 32W Hanging | F48/L | 112 | 5.6 | SW | 8760 | 48,553 | 33 | 4 ft LED Tube | 2007/32x4 | 50 | 1.7 | NONE | 8760 | 26,020 | 22,533 | 2.7 | $ - | $ | 3,943.65 |
| 39LED | Customs | Concourse A | 32 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 1.7 | SW | 8760 | 15,137 | 32 | 4 ft LED Tube | 2007/32x2 | 50 | 1.0 | NONE | 8760 | 8,410 | 6,728 | 0.8 | $ - | $ | 7,646.40 |
| 34LED | Customs | Concourse A | 8 | 9' PC 1 Lamp CFL | CFQ26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 8 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 8760 | 631 | 1,261 | 0.1 | $ - | $ | 533.60 |
| 39LED | Concourse A Hallway | Concourse A | 384 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 20.7 | SW | 8760 | 181,447 | 384 | 4 ft LED Tube | 2007/32x2 | 50 | 11.5 | NONE | 8760 | 100,915 | 80,732 | 9.2 | $ - | $ | 91,756.80 |
| 39LED | Access Hallway | Concourse A | 8 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 0.4 | SW | 8760 | 3,784 | 8 | 4 ft LED Tube | 2007/32x2 | 50 | 0.2 | NONE | 8760 | 2,102 | 1,682 | 0.2 | $ - | $ | 1,911.60 |
| 34LED | Gate A 8 | Concourse A | 8 | 9' PC 1 Lamp CFL | CFQ26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 8 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 8760 | 631 | 1,261 | 0.1 | $ - | $ | 533.60 |
| 34LED | Gate A 8 | Concourse A | 4 | 9' PC 1 Lamp CFL | CFQ26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 4 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 8760 | 631 | 1,261 | 0.1 | $ - | $ | 533.60 |
| LED | Gate A 8 | Concourse A | 4 | Existing LED | | 0 | 0.0 | SW | 8760 | - | 4 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - | 0.0 | $ - | $ | - |
| 38LED | Opposite Gate A 8 | Concourse A | 17 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 0.9 | SW | 8760 | 8,042 | 17 | 4 ft LED Tube | 2007/32x2 | 50 | 0.5 | NONE | 8760 | 4,468 | 3,574 | 0.4 | $ - | $ | 4,062.15 |
| 34LED | Opposite Gate A 8 | Concourse A | 8 | 9' PC 1 Lamp CFL | CFQ26/1-L | 27 | 0.2 | SW | 8760 | 1,892 | 8 | A18LED | A18-09/02 | 18 | 0.1 | NONE | 8760 | 631 | 1,261 | 0.1 | $ - | $ | 533.60 |
| LED | Opposite Gate A 8 | Concourse A | 4 | Existing LED | | 0 | 0.0 | SW | 8760 | - | 4 | Existing LED | 0 | 0 | 0.0 | NONE | 8760 | - | - | 0.0 | $ - | $ | - |
| 34LED | Elevator Alcove | Concourse A | 2 | 9' PC 1 Lamp CFL | CFQ26/1-L | 27 | 0.1 | SW | 8760 | 473 | 2 | A18LED | A18-09/02 | 18 | 0.0 | NONE | 8760 | 158 | 316 | 0.0 | $ - | $ | 133.40 |
| 38LED | Gate A8 | Concourse A | 20 | 1x4 2 Lamp T-5 28W Hanging | F42/L/T5 | 54 | 1.1 | SW | 8760 | 9,461 | 20 | 4 ft LED Tube | 2007/32x2 | 50 | 0

**Energy Audit of Norfolk International Airport**
**Ch4 Project No. 22270**
**L-1 Lighting Retrofit**

| | | | EXISTING CONDITIONS | | | | | | | RETROFIT CONDITIONS | | | | | | |

# APPENDIX C – ECM CALCULATIONS

**Norfolk Airport**
**CHA Project # 33370**

| Utility Costs | | Yearly Usage | MTCDE |
|---|---|---|---|
| $ 0.096 | $/kWh blended | | 0.00042021 |
| $ 0.096 | $/kWh supply | 279,520 | 0.00042021 |
| | $/kW | 120 | 0 |
| | $/Therm | | 0.00533471 |
| | $/kgals | | 0 |

# Air Field Lighting Vault

| Recommended Y/N? | | Item | Savings kW | kWh | therms | cooling kWh | kgal/yr | $ | Cost | Simple Payback | MTCDE | Life Expectancy |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| N | M-4 | Window AC Replacement | 0.0 | 1,210 | 0 | 0 | 0 | $ 116 | $ 4,400 | >25 | 0.5 | |
| Y | C-4 | Plug Load Contols | 0.0 | 1,077 | 0 | 0 | 0 | $ 103 | $ 200 | 1.9 | 0.5 | |
| Y | L-1 | Lighting Upgrade | 0.6 | 5,111 | 0 | 0 | 0 | $ 490 | $ 5,143 | 10.5 | 2.1 | |
| | | | **0.6** | **6,188** | **0** | **0** | **0** | **$ 594** | **$ 5,343** | **12.4** | **2.6** | |
| | | **Total** | **0.6** | **7,398** | **0** | **0** | **0** | **$ 710** | **$ 9,743** | **13.7** | **3.1** | |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Lighting Vault**

| EQUIPMENT | AREA/EQUIPMENT SERVED | COOLING CAPACITY (MBH) |
|---|---|---|
| AC-1 | Estimated based off brand and picture | 18 |
| | *Total Electric DX Cooling:* | *18* *MBH* |

**ECM-01: DX Split System Upgrade**

**ECM Description Summary**

*By replacing window DX equipment with DX split systems with higher SEER/EER condensing units, electrical energy can be saved. Control schemes can be incorporated that were not possible with the older equipment as well. It is recommended these units be replaced by more modern DX split system equipment with high efficiency fans and compressors and controls.*

| ASSUMPTIONS | | | Comments |
|---|---|---|---|
| Electric Cost | $0.096 | / kWh | |
| Existing run hours per Week | 168 | Hours | Unit has built in thermostat |
| Proposed run hours per week | 84 | Hours | |
| Space Balance Point | 55 | F | |
| Space Temperature Setpoint | 72 | deg F | Setpoint. |
| BTU/Hr Rating of existing DX equipment | 18,000 | Btu / Hr | Total BTU/hr of DX cooling equipment to be replaced. |
| Average EER | 11.2 | | |
| Existing Annual Electric Usage | 2,090 | kWh | |

| Item | Value | Units | Comments |
|---|---|---|---|
| Proposed EER | 13.3 | | New ductless mini-splits (per manufacturer) |
| Proposed Annual Electric Usage | 880 | kWh | |

| ANNUAL SAVINGS | | |
|---|---|---|
| Annual Electrical Usage Savings | 1,210 | kWh |
| Annual Cost Savings | $116 | |
| Total Project Cost | $4,400 | |
| Simple Payback | 37.9 | years |

| OAT - DB Bin Temp F | Annual Hours | Cooling Hrs at Temp Above balance point | Assumed % of time of operation | Assumed hrs of Operation | Proposed hrs of Operation |
|---|---|---|---|---|---|
| 102.5 | 0 | 0 | 100% | 0 | 0 |
| 97.5 | 10 | 10 | 89% | 9 | 4 |
| 92.5 | 39 | 39 | 79% | 31 | 15 |
| 87.5 | 215 | 215 | 68% | 147 | 74 |
| 82.5 | 557 | 557 | 58% | 322 | 161 |
| 77.5 | 910 | 910 | 47% | 431 | 216 |
| 72.5 | 978 | 978 | 37% | 360 | 180 |
| 67.5 | 971 | 0 | 0% | 0 | 0 |
| 62.5 | 1101 | 0 | 0% | 0 | 0 |
| 57.5 | 655 | 0 | 0% | 0 | 0 |
| 52.5 | 581 | 0 | 0% | 0 | 0 |
| 47.5 | 561 | 0 | 0% | 0 | 0 |
| 42.5 | 781 | 0 | 0% | 0 | 0 |
| 37.5 | 680 | 0 | 0% | 0 | 0 |
| 32.5 | 386 | 0 | 0% | 0 | 0 |
| 27.5 | 191 | 0 | 0% | 0 | 0 |
| 22.5 | 102 | 0 | 0% | 0 | 0 |
| 17.5 | 41 | 0 | 0% | 0 | 0 |
| 12.5 | 1 | 0 | 0% | 0 | 0 |
| 7.5 | 0 | 0 | 0% | 0 | 0 |
| **Total** | 8,760 | 2,709 | 48% | 1301 | 650 |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Lighting Vault**

**ECM-01: DX Split System Upgrade - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | **0.98** |
| Labor: | **0.70** |
| Equipment: | **0.86** |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| Existing window AC removal and wall repair | 1 | EA | $ 200 | $ 100 | $ - | $ 196 | $ 70 | $ - | $ 266 | Eng Est |
| (1) AC, 1.5 ton air conditioner condensing unit | 1 | EA | $ 1,500 | $ 750 | $ - | $ 1,472 | $ 523 | $ - | $ 1,994 | Internet |
| Refrigerant Lines | 10 | LF | $ 5 | $ 5 | $ - | $ 49 | $ 35 | $ - | $ 84 | RS Means |
| Electrical - misc. | 1 | LS | $ 500 | $ 250 | $ - | $ 491 | $ 174 | $ - | $ 665 | Eng Est |
| Programmable thermostat | 1 | EA | $ 200 | $ 50 | $ - | $ 196 | $ 35 | $ - | $ 231 | Eng Est |
| | | | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 3,240 | Subtotal |
| $ 648 | 20% Contingency |
| $ 485.98 | 15% O&P |
| **$ 4,400** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Lighting Vault**

**ECM-02: Install Plug load control**

**ECM Description Summary**
*The Air field lighting vault contains an office with a window air conditioning unit. This unit is currently on 24/7 365 days per year. This measure proposes adding a plug load controller that will turn the unit off during unoccupied times.*

| ASSUMPTIONS | | | Comments |
|---|---|---|---|
| Electric Cost | $0.096 | / kWh | |
| Existing run hours per Week | 168 | Hours | Unit has built in thermostat |
| Proposed Run Hours Per Week | 84 | Hours | |
| Space Balance Point | 55 | F | |
| Space Temperature Setpoint | 72 | deg F | setpoint |
| Avg. BTU / Hr Rating of existing RTU | 18,000 | Btu / Hr | (typical size for cooling spaces in this type of building) |
| Average EER | 11.2 | | |

| Item | Value | Units | Comments |
|---|---|---|---|
| Existing Annual Electric Usage | 2,090 | kWh | |
| Proposed Annual Electric Usage | 1,013 | kWh | Unit will cycle on w/ temp of room. Possible operating time shown below |

| ANNUAL SAVINGS | | |
|---|---|---|
| Annual Savings | 1,077 | kWh |
| Annual Cost Savings | $103 | |

| OAT - DB Bin Temp F | Annual Hours | Cooling Hrs at Temp Above balance point | Assumed % of time of operation | Assumed hrs of Operation | Cooling Hrs at Temp Above balance point | Assumed % of time of | Assumed hrs of Operation |
|---|---|---|---|---|---|---|---|
| 102.5 | 0 | 0 | 100% | 0 | 0 | 100% | 0 |
| 97.5 | 10 | 10 | 89% | 9 | 0 | 89% | 0 |
| 92.5 | 39 | 39 | 79% | 31 | 0 | 79% | 0 |
| 87.5 | 215 | 215 | 68% | 147 | 108 | 68% | 74 |
| 82.5 | 557 | 557 | 58% | 322 | 279 | 58% | 161 |
| 77.5 | 910 | 910 | 47% | 431 | 455 | 47% | 216 |
| 72.5 | 978 | 978 | 37% | 360 | 489 | 37% | 180 |
| 67.5 | 971 | 0 | 0% | 0 | 0 | 0% | 0 |
| 62.5 | 1,101 | 0 | 0% | 0 | 0 | 0% | 0 |
| 57.5 | 655 | 0 | 0% | 0 | 0 | 0% | 0 |
| 52.5 | 581 | 0 | 0% | 0 | 0 | 0% | 0 |
| 47.5 | 561 | 0 | 0% | 0 | 0 | 0% | 0 |
| 42.5 | 781 | 0 | 0% | 0 | 0 | 0% | 0 |
| 37.5 | 680 | 0 | 0% | 0 | 0 | 0% | 0 |
| 32.5 | 386 | 0 | 0% | 0 | 0 | 0% | 0 |
| 27.5 | 191 | 0 | 0% | 0 | 0 | 0% | 0 |
| 22.5 | 102 | 0 | 0% | 0 | 0 | 0% | 0 |
| 17.5 | 41 | 0 | 0% | 0 | 0 | 0% | 0 |
| 12.5 | 1 | 0 | 0% | 0 | 0 | 0% | 0 |
| 7.5 | 0 | 0 | 0% | 0 | 0 | 0% | 0 |
| **Total** | 8,760 | 2,709 | 48% | 1301 | 1,330 | 47% | 630 |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Lighting Vault**

**ECM-02: Install Plug load control - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| Plug Load Controller | 1 | EA | $ 100 | $ 25 | | $ 98 | $ 17 | $ - | $ 116 | Eng Est |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 116 | Subtotal |
| $ 23.11 | 20% Contingency |
| $ 17.33 | 15% O&P |
| **$ 200** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**

| Utility Costs | | | Yearly Usage | MTCDE |
|---|---|---|---|---|
| $ 0.0925 | $/kWh blended | | | 0.00042021 |
| $ 0.0925 | $/kWh supply | | 197,100 | 0.00042021 |
| $ 10.47 | $/kW | | 41.25 | 0 |
| $ 0.34 | $/Therm | | 22,310 | 0.00533471 |
| | $/kgals | | | 0 |

$ 3.378 2,231
2,165

# Air Field Maintenance Building (BLDG 27)

| Recommended Y/N? | | Item | Savings kW | kWh | therms | cooling kWh | kgal/yr | $ | Cost | Simple Payback | MTCDE | Life Expectancy |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Y | C-2 | Night Setback | 0 | 5,637 | 1,296 | 0 | 0 | $ 959 | $ 2,393 | 2.5 | 9.3 | 5 |
| Y | C-3 | Garage Door Interlock | 0 | 0 | 1,858 | 0 | 0 | $ 628 | $ 3,275 | 5.2 | 9.9 | 5 |
| Y | L-1 | Lighting | 13.7 | 44,667 | 0 | 0 | 0 | $ 4,173 | $ 38,712 | 9.3 | 18.8 | 5 |
| | | **Total Recommended** | **14** | **50,304** | **3,154** | - | - | **$ 5,760** | **$ 44,380** | **7.7** | **38.0** | |
| | | **Total** | **14** | **50,304** | **3,154** | - | - | **$ 5,760** | **$ 44,380** | **7.7** | **38.0** | |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Building (BLDG 27)**

**C-2: Night Setback**

Night setback for the office area during the unoccupied hours. High costs prohibit a DDC panel to be tied to the Airport EMS. However a programmable thermostat would provide the unoccupied setpoints for operations M-F.

| EXISTING CONDITIONS | | |
|---|---|---|
| Existing Facility Total Electric usage | 167,535 | kWh |
| Existing Facility Natural Gas Usage | 19,254 | Therms |
| Cost of Electricity | $ 0.09 | $/kWh |
| Cost of Natural Gas | $ 0.34 | $/Therm |
| SAVINGS | | |
| TOD Electric savings | 5,637 | kWh[1] |
| TOD Natural Gas savings | 1,296 | Therms[2] |
| Total Cost Savings | $959 | |
| Estimated Total Project Cost | $2,393 | [4] |
| Simple Payback | 2.5 | **years** |

Assumptions

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 1 | 6.7% | Approximate percent of total electric savings due to night setback | | | | 1.5 | % per degree electric savings |
| 2 | 13.5% | Approximate percent of total gas savings due to night setback | | | | 1.5 | % per degree gas savings |
| 3 | 12 | | 80 | 68 | HEATING SETPOINT SETBACK | | |
| 4 | 6 | | 72 | 78 | COOLING SETPOINT SETBACK | | |
| 5 | 15.5 | hours of setback | | | | | |
| | 8.5 | Hours of operations | Start | end | #days/week | hours/year | |
| | | 6am - 2:30pm, M-F | 6:00 | 14:30 | 5 | 2,210 | hours/year |
| | | | | | | 6,550 | hours/year setback |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Building (BLDG 27)**

**C-2: Night Setback - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Programmable thermostat | 2 | ea | $ 590 | $ 200 | $ - | $ 1,158 | $ 279 | $ - | $ 1,437 | Eng Est |
| Miscellaneous Electrical | 1 | LS | $ 200 | $ 200 | | $ 196 | $ 139 | $ - | $ 336 | Eng Est |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 1,773 | Subtotal |
| $ 354.55 | 20% Contingency |
| $ 265.91 | 15% O&P |
| **$ 2,393** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Building (BLDG 27)**

## C-3: Garage Door Interlock

When the garage doors are opened, the UH's and IR's should be off. The interlock switches will shut power off to the UH's and IR's. When doors are closed then the devices with operate to maintain temperature. Prevents unneeded heating of the garage bays.

Heat used for heating season

| | |
|---|---|
| 21,651 | therms of winter usage |
| | btu/gallon |
| | btu |
| 21,651 | therms |

| | |
|---|---|
| 38,760 | square footage of building |
| 33,531 | square footage of garage bays |
| 86.5% | of floor space affected |

| | |
|---|---|
| 18,730 | therms used for heating garage bays |
| 2,610 | occupied heating hours |
| 20% | of occupied hours affected |
| 522 | affected hours |

assumed 8.5 hours day, doors left open greater than 30% of occupied hours

| | | |
|---|---|---|
| **1,858** | therms saved | 8.58% |
| $ 0.338 | $/therm | |
| **$ 628** | SAVED | |
| $ 3,275 | COST | |
| 5.22 | YEARS PAYBACK | |

| | |
|---|---|
| 75 | degF heat on setpoint |
| 22,935 | heat loss factor (btu/hr/degF total heatloss (ventilation included)) |

| Avg Outdoor Air Temp. Bins °F | Avg Outdoor Air Enthalpy | Existing Equipment Bin Hours | Occupied Equipment Bin Hours | Affected hours | % total affected heating hours | Therms heatloss | Therms saved |
|---|---|---|---|---|---|---|---|
| 102.5 | | - | - | - | | - | |
| 97.5 | 41.95 | 10 | 2 | 0.40 | 4.0% | - | - |
| 92.5 | 39.72 | 39 | 16 | 3.20 | 8.2% | - | - |
| 87.5 | 37.33 | 215 | 105 | 21.00 | 9.8% | - | - |
| 82.5 | 33.63 | 557 | 234 | 46.80 | 8.4% | - | - |
| 77.5 | 31.23 | 910 | 300 | 60.00 | 6.6% | - | - |
| 72.5 | 29.24 | 978 | 299 | 59.80 | 6.1% | 560.77 | 34.29 |
| 67.5 | 27.21 | 971 | 237 | 47.40 | 4.9% | 1,670.26 | 81.53 |
| 62.5 | 24.46 | 1,101 | 346 | 69.20 | 6.3% | 3,156.46 | 198.39 |
| 57.5 | 21.62 | 655 | 163 | 32.60 | 5.0% | 2,628.95 | 130.85 |
| 52.5 | 18.72 | 581 | 127 | 25.40 | 4.4% | 2,998.20 | 131.07 |
| 47.5 | 16.29 | 561 | 179 | 35.80 | 6.4% | 3,538.33 | 225.80 |
| 42.5 | 14.50 | 781 | 211 | 42.20 | 5.4% | 5,821.53 | 314.56 |
| 37.5 | 12.68 | 680 | 198 | 39.60 | 5.8% | 5,848.48 | 340.59 |
| 32.5 | 10.81 | 386 | 118 | 23.60 | 6.1% | 3,762.52 | 230.04 |
| 27.5 | 8.54 | 191 | 49 | 9.80 | 5.1% | 2,080.80 | 106.76 |
| 22.5 | 7.10 | 102 | 18 | 3.60 | 3.5% | 1,228.18 | 43.35 |
| 17.5 | 5.35 | 41 | 8 | 1.60 | 3.9% | 540.70 | 21.10 |
| 12.5 | 4.50 | 1 | - | - | 0.0% | 14.33 | - |
| 7.5 | | - | - | - | | - | |
| 2.5 | | - | - | - | | - | |
| -2.5 | | - | - | - | | - | |
| -7.5 | | - | - | - | | - | |
| **TOTALS** | | **8,760** | **2,610** | **522** | | **33,849** | **1,858** |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Building (BLDG 27)**

**C-3: Garage Door Interlock - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Interlock switches | 4 | LS | $ 100 | $ 100 | | $ 392 | $ 279 | $ - | $ 671 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 1,200 | $ 500 | $ 491 | $ 836 | $ 428 | $ 1,754 | wiring from interlock swithes to t'stats. Power wire is already installed from t'stat to UH's. |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 2,426 | Subtotal |
| $ 485 | 20% Contingency |
| $ 363.84 | 15% O&P |
| **$ 3,275** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**

**Engineer:** Name

| Utility Costs | | Yearly Usage | MTCDE |
|---|---|---|---|
| $ 0.0925 | $/kWh blended | | 0.00042021 |
| | $/kWh supply | 197,100 | 0.00042021 |
| $ 10.47 | $/kW | 41.25 | 0 |
| $ 0.34 | $/Therm | 22,310 | 0.00533471 |
| | $/kgals | | 0 |

$ 3.378 2,231

# Air Field Maintenance Storage (BLDG 34)

| Recommended Y/N? | | Item | Savings kW | kWh | therms | cooling kWh | kgal/yr | $ | Cost | Simple Payback | MTCDE | Life Expectancy |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Y | C-2 | C-2: Night Setback | 0 | 11,911 | 590 | 0 | 0 | $ 1,301 | $ 2,278 | 1.8 | 8.2 | 5 |
| Y | L-1 | Lighting | 1 | 2,876 | 0 | 0 | 0 | $ 269 | $ 3,637 | 13.5 | 1.2 | 5 |
| | | **Total Recommended** | **1** | **14,787** | **590** | **0** | **0** | **1,570** | **5,915** | **3.8** | **9** | |
| | | **Total** | **1** | **14,787** | **590** | **0** | **0** | **1,570** | **5,915** | **3.8** | **9** | |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Storage (BLDG 34)**

**C-2: Night Setback** **: Heating 65° to 45° F**

**ECM Description Summary**

*The thermostat is reading a higher setpoint than needed for this storage facility. Lower the setpoint temperature to reduce the need for the infrared heaters.*

| EXISTING CONDITIONS | | |
|---|---|---|
| Existing Facility Total Electric Usage | 197,100 | kWh |
| Existing Facility Natural Gas Usage | 1,474 | Therms |
| Cost of Electricity | $ 0.09 | $/kWh |
| Cost of Natural Gas | $ 0.34 | $/Therm |
| SAVINGS | | |
| TOD Electric savings | 11,911 | kWh[1] |
| TOD Natural Gas savings | 590 | Therms[2] |
| Total Cost Savings | $ 1,301 | |
| Estimated Total Project Cost | $ 2,278 | [4] |
| Simple Payback | 1.8 | **years** |

6.0%

2.6% of total gas usage

Assumptions

| | | | | | |
|---|---|---|---|---|---|
| 1 | 0.0% | Approximate percent of total electric savings due to night setback | | | |
| 2 | 40.0% | Approximate percent of total gas savings due to night setback | | | |
| 3 | 20 | | 65 | 45 | HEATING SETPOINT SETBACK |
| 4 | 0 | | 0 | 0 | COOLING SETPOINT SETBACK |
| 5 | 24 | hours of setback | | | |

**Norfolk Airport**
**CHA Project # 33370**
**Air Field Maintenance Storage (BLDG 34)**

**C-2: Night Setback - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Programmable thermostat | 1 | ea. | $ 600 | $ 150 | $ - | $ 589 | $ 105 | $ - | $ 693 | |
| new temp sensor relocation | 1 | ea. | $ 200 | $ 50 | $ - | $ 196 | $ 35 | $ - | $ 231 | |
| ~100ft electric conduit | 1 | ls | $ 500 | $ 200 | $ - | $ 491 | $ 139 | $ - | $ 630 | |
| protective cover | 1 | ea. | $ 100 | $ 50 | $ - | $ 98 | $ 35 | $ - | $ 133 | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 1,687 | Subtotal |
| $ 337 | 20% Contingency |
| $ 253 | 15% O&P |
| **$ 2,278** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**

| Utility Costs | | Yearly Usage | MTCDE | TOTAL (2017) | Arrivals | Arrivals2 | Garage A |
|---|---|---|---|---|---|---|---|
| $ 0.064 | $/kWh blended | | 0.00042021 | 9,009,467 | 4,270,200 | 5,445,000 | 705,733 |
| | $/kWh supply | 5,445,000 | 0.00042021 | | | | |
| | $/kW | 979 | 0 | | | | |
| $ 0.34 | $/Therm | 201,210 | 0.00533471 | | | | |
| | $/kgals | | 0 | | | | |

## Arrivals

| Recommended Y/N? | | Item | Savings kW | Savings kWh | Savings therms | Savings cooling kWh | Savings kgal/yr | Savings $ | Cost | Simple Payback | MTCDE | Life Expectancy | Simple Projected Lifetime Savings kW | Simple Projected Lifetime Savings kWh | Simple Projected Lifetime Savings therms | Simple Projected Lifetime Savings cooling | Simple Projected Lifetime Savings kgal/yr | Simple Projected Lifetime Savings $ | ROI |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Y | BE-2 | Door Sweeps and Seals Replacements | 0 | 1,097 | 475 | 0 | 0 | $ 230 | $ 2,003 | 8.7 | 3.0 | 5 | - | 5,484 | 2,377 | - | - | $ 1,151 | (0.43) |
| N | M-1 | Boiler Replacements | 0 | 0 | 15,530 | 0 | 0 | $ 5,247 | $ 179,950 | >25 | 82.8 | 15 | - | - | 232,943 | - | - | $ 78,699 | (0.56) |
| Y | M-5 | Destratification Fans | 0 | 110,365 | 7,309 | 0 | 0 | $ 9,481 | $ 61,089 | 6.4 | 85.4 | 10 | - | 1,103,651 | 73,089 | - | - | $ 94,812 | 0.55 |
| Y | M-6 | Chilled Water (CHW) and Hot Water (HHW) Pump Variable Speed Drives (VSD) | 0 | 127,490 | 0 | 0 | 0 | $ 8,100 | $ 90,911 | 11.2 | 53.6 | 15 | - | 1,912,347 | - | - | - | $ 121,499 | 0.34 |
| Y | M-9 | Elevator Motor Upgrades | 0 | 38772 | 0 | 0 | 0 | $ 2,463 | $ 34,047 | 13.8 | 16.3 | 15 | - | 581,580 | - | - | - | $ 36,950 | 0.09 |
| N | M-10 | Escelator Controls | 0 | 22,776 | 0 | 0 | 0 | $ 1,447 | $ 26,753 | 18.5 | 9.6 | 15 | - | 341,640 | - | - | - | $ 21,706 | (0.19) |
| N | DHW-2 | Domestic Hot Water Condensing Water Heaters | 0 | 0 | 213 | 0 | 0 | $ 72 | $ 15,308 | >25 | 1.1 | 15 | - | - | 3,202 | - | - | $ 1,082 | (0.93) |
| Y | C-2 | Night Setback | 0 | 24,601 | 954 | 0 | 0 | $ 1,885 | $ 16,031 | 8.5 | 15.4 | 15 | - | 369,009 | 14,305 | - | - | $ 28,277 | 0.76 |
| Y | L-1 | Lighting | 113.6 | 799,367 | 0 | 0 | 0 | $ 76,752 | $ 437,385 | 5.7 | 335.9 | 15 | 1,704 | 11,990,505 | - | - | - | $ - | (1.00) |
| | | **Total Recommended** | **114** | **1,101,691** | **8,738** | **0** | **0** | **$ 98,912** | **$ 641,467** | **6.5** | **510** | | | | | | | | |
| | | **Total** | **114** | **1,124,467** | **24,481** | **0** | **0** | **$ 105,678** | **$ 863,477** | **8.2** | **603** | | 1,704 | 16,304,216 | 325,917 | - | - | $ 384,176 | (0.56) |
| | | **% of Existing** | **12%** | **21%** | **12%** | **0%** | **#DIV/0!** | | | | | | | | | | | | |

| **City:** | Norfolk, VA | | | | | |
|---|---|---|---|---|---|---|
| | | Occupied | Occupied | Occupied | Occupied | Occupied |
| Temp | Bin Hours | Hours | Hours | Hours | Hours | Hours |
| 102.5 | 0 | 0 | 0 | 0 | 0 | 0 |
| 97.5 | 10 | 4 | 1 | 0 | 0 | 0 |
| 92.5 | 39 | 14 | 5 | 2 | 1 | 0 |
| 87.5 | 215 | 77 | 27 | 10 | 3 | 1 |
| 82.5 | 557 | 199 | 71 | 25 | 9 | 3 |
| 77.5 | 910 | 325 | 116 | 41 | 15 | 5 |
| 72.5 | 978 | 349 | 125 | 45 | 16 | 6 |
| 67.5 | 971 | 347 | 124 | 44 | 16 | 6 |
| 62.5 | 1,101 | 393 | 140 | 50 | 18 | 6 |
| 57.5 | 655 | 234 | 84 | 30 | 11 | 4 |
| 52.5 | 581 | 208 | 74 | 26 | 9 | 3 |
| 47.5 | 561 | 200 | 72 | 26 | 9 | 3 |
| 42.5 | 781 | 279 | 100 | 36 | 13 | 5 |
| 37.5 | 680 | 243 | 87 | 31 | 11 | 4 |
| 32.5 | 386 | 138 | 49 | 18 | 6 | 2 |
| 27.5 | 191 | 68 | 24 | 9 | 3 | 1 |
| 22.5 | 102 | 36 | 13 | 5 | 2 | 1 |
| 17.5 | 41 | 15 | 5 | 2 | 1 | 0 |
| 12.5 | 1 | 0 | 0 | 0 | 0 | 0 |
| 7.5 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |

| Multipliers | |
|---|---|
| Material: | 0.981 |
| Labor: | 0.697 |
| Equipment: | 0.855 |

| | |
|---|---|
| Exist Heating Efficiency | 83% |
| Cooling Eff (kW/ton) | 0.76 |

C-1 NAMEPLATE 0.604 kW/ton
C-2 NAMEPLATE 0.604 kW/ton

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

## BE-2: Install Door Seals

### ECM Description Summary

*Some of the existing door sweeps and seals at the airport are in poor condition or nonexistent. This lack of seals results in excessive heat loss and infiltration. By installing new door seals air infiltration and heat loss can be reduced resulting in decreased energy consumption.*

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Heating System Efficiency | 83% | | Ex Occupied Clng Temp. | 74 | *F | Ex Occupied Htg Temp. | 72 | *F |
| Cooling System Efficiency | 0.76 | kW/ton | Ex Unoccupied Clng Temp. | 74 | *F | Ex Unoccupied Htg Temp. | 72 | *F |
| Linear Feet of Door Edge | 274 | Ft | Cooling Occ Enthalpy Setpoint | 27.5 | Btu/lb | Electricity | $ 0.06 | $/kWh |
| Existing Infiltration Factor* | 1.5 | cfm/LF | Cooling Unocc Enthalpy Setpoint | 27.5 | Btu/lb | Natural Gas | $ 0.34 | $/MMBtu |
| Proposed Infiltration Factor* | 0.45 | cfm/LF | | | | | | |

*Infiltration Factor per Carrier Handbook of Air Conditioning System Design based on average door seal gap calculated below.

| | | | | | EXISTING LOADS | | PROPOSED LOADS | | COOLING ENERGY | | HEATING ENERGY | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Occupied | Unoccupied | Occupied | Unoccupied | | | | |
| Avg Outdoor Air Temp. Bins °F | Avg Outdoor Air Enthalpy | Existing Equipment Bin Hours | Occupied Equipment Bin Hours | Unoccupied Equipment Bin Hours | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Existing Cooling Energy kWh | Proposed Cooling Energy kWh | Existing Heating Energy therms | Proposed Heating Energy therms |
| A | | B | C | D | E | F | G | H | I | J | K | L |
| 102.5 | 0.0 | 0 | 0 | 0 | 50,861 | 50,861 | 15,258 | 15,258 | 0 | 0 | 0 | 0 |
| 97.5 | 42.4 | 10 | 10 | 0 | -27,506 | -27,506 | -8,252 | -8,252 | 17 | 5 | 0 | 0 |
| 92.5 | 39.7 | 39 | 39 | 0 | -22,591 | -22,591 | -6,777 | -6,777 | 55 | 17 | 0 | 0 |
| 87.5 | 38.1 | 215 | 215 | 0 | -19,585 | -19,585 | -5,875 | -5,875 | 265 | 80 | 0 | 0 |
| 82.5 | 35.9 | 557 | 557 | 0 | -15,448 | -15,448 | -4,635 | -4,635 | 542 | 163 | 0 | 0 |
| 77.5 | 34.0 | 910 | 910 | 0 | -11,995 | -11,995 | -3,598 | -3,598 | 687 | 206 | 0 | 0 |
| 72.5 | 31.6 | 978 | 978 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 67.5 | 28.3 | 971 | 971 | 0 | 1,997 | 1,997 | 599 | 599 | 0 | 0 | 23 | 7 |
| 62.5 | 24.5 | 1,101 | 1,101 | 0 | 4,217 | 4,217 | 1,265 | 1,265 | 0 | 0 | 56 | 17 |
| 57.5 | 21.5 | 655 | 655 | 0 | 6,436 | 6,436 | 1,931 | 1,931 | 0 | 0 | 51 | 15 |
| 52.5 | 18.7 | 581 | 581 | 0 | 8,656 | 8,656 | 2,597 | 2,597 | 0 | 0 | 61 | 18 |
| 47.5 | 16.3 | 561 | 561 | 0 | 10,875 | 10,875 | 3,263 | 3,263 | 0 | 0 | 74 | 22 |
| 42.5 | 14.6 | 781 | 781 | 0 | 13,094 | 13,094 | 3,928 | 3,928 | 0 | 0 | 123 | 37 |
| 37.5 | 12.6 | 680 | 680 | 0 | 15,314 | 15,314 | 4,594 | 4,594 | 0 | 0 | 125 | 38 |
| 32.5 | 10.8 | 386 | 386 | 0 | 17,533 | 17,533 | 5,260 | 5,260 | 0 | 0 | 82 | 24 |
| 27.5 | 8.6 | 191 | 191 | 0 | 19,753 | 19,753 | 5,926 | 5,926 | 0 | 0 | 45 | 14 |
| 22.5 | 7.2 | 102 | 102 | 0 | 21,972 | 21,972 | 6,592 | 6,592 | 0 | 0 | 27 | 8 |
| 17.5 | 5.4 | 41 | 41 | 0 | 24,191 | 24,191 | 7,257 | 7,257 | 0 | 0 | 12 | 4 |
| 12.5 | 4.5 | 1 | 1 | 0 | 26,411 | 26,411 | 7,923 | 7,923 | 0 | 0 | 0 | 0 |
| 7.5 | 0.0 | 0 | 0 | 0 | 28,630 | 28,630 | 8,589 | 8,589 | 0 | 0 | 0 | 0 |
| **TOTALS** | | **8,760** | **8,760** | **0** | | | | | **1,567** | **470** | **679** | **204** |

| | | |
|---|---|---|
| Existing Door Infiltration | 411 | cfm |
| Existing Unoccupied Door Infiltration | 411 | cfm |
| Proposed Door Infiltration | 123 | cfm |
| Proposed Unoccupied Door Infiltration | 123 | cfm |

| | | | |
|---|---|---|---|
| Savings | 475 | therms | $ 16 |
| | 1,097 | kWh | $ 70 |
| | | | $ 86 |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**BE-2: Install Door Seals - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | $ - | |
| Door Seals | 274 | LF | $ 2 | $ - | $ - | $ 578 | $ - | $ - | $ 578 | Internet |
| Install | 26 | ea. | $ - | $ 50 | $ - | $ - | $ 906 | $ - | $ 906 | Eng. Est |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 1,484 | Subtotal |
| $ 296.80 | 20% Contingency |
| $ 223 | 15% O&P |
| **$ 2,003** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-1: Boiler Replacement w/ Condensing, Hot Water Reset**

## Utility Costs


| | | |
|---|---|---|
| Blended Electric Rate | $0.06 | / kWh |
| Blended Natural Gas Rate | $0.34 | / Therm |

## ECM Description Summary

*The arrivals facility at Norfolk airport was constructed in 2003, the boilers are original to construction. The existing boilers are 2 - 8000 MBH dual fuel natural gas/fuel oil #2 fire-tube boilers with a name plate efficiency of 82%.This measure proposes replacing the existing boiler with 1 - 6000 MBH and 1 - 1500 MBH Condensing natural gas boilers and implement a HW reset. The smaller boiler will be utilized for lower loads and Summer DHW production.*

| INPUTS - BOILER AND HHW PIPING | | |
|---|---|---|
| Boiler Input | 8,165 | MBH |
| Boiler Output | 6,695 | MBH |
| Nameplate Eff. | 82.0% | |
| Blended Natural Gas Rate | $0.34 | / MMBTU |
| Heating On Temperature [4] | 65 | °F |
| Building Balance Point | 55 | °F |
| Existing Average HHW Setpoint High | 180 | °F |
| Existing HHW Setpoint Low | 160 | °F |
| Proposed Avg HHW Setpoint Low | 120 | °F |

| INPUTS - PROPOSED BOILER EFFICIENCY DATA | | | | | | |
|---|---|---|---|---|---|---|
| RWT (F) | % Firing Rate | | | | | |
| | 100% | 80% | 60% | 40% | 20% | 8% |
| 80 | 95.6% | 95.9% | 96.5% | 97.2% | 98.0% | 98.2% |
| 100 | 93.4% | 94.0% | 94.2% | 94.6% | 95.0% | 95.1% |
| 120 | 88.8% | 88.9% | 89.0% | 89.8% | 89.9% | 90.2% |
| 140 | 87.3% | 87.3% | 87.6% | 87.7% | 87.7% | 87.9% |
| 160 | 86.5% | 86.7% | 86.9% | 87.0% | 87.0% | 87.0% |




**SAVINGS ANALYSIS**

| Local Temperature Bin Data | | | | Existing Conditions | | | | | | | | | Proposed Conditions | | | | | | | | SAVINGS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Avg. DB Bin Temp °F | Boiler On? | Bin Hours | Heating Bin HOURS | Leaving Water Temp | Delta T | Return Water Temp | Total Boiler Heat Load ( MBH ) | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MMBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Firing Rate | Existing Utility Use Therms/Yr | Leaving Water Temp | Delta T | Return Water Temp | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MMBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Delta T and Firing Rate | Existing Utility Use Therms/Yr | Savings Utility Use Therms/Yr |
| 92.5 | YES | 10 | 10 | 160 | 10 | 150 | 950 | 950 | 10 | 16% | 83.0% | 114 | 120 | 15 | 105 | 950 | 10 | 16% | 93.6% | 101 | 13 |
| 87.5 | YES | 39 | 39 | 160 | 10 | 150 | 950 | 950 | 37 | 16% | 83.0% | 446 | 120 | 15 | 105 | 950 | 37 | 16% | 93.6% | 396 | 51 |
| 82.5 | YES | 215 | 215 | 160 | 10 | 150 | 950 | 950 | 204 | 16% | 83.0% | 2,461 | 120 | 15 | 105 | 950 | 204 | 16% | 93.6% | 2,182 | 279 |
| 77.5 | YES | 557 | 557 | 160 | 10 | 150 | 950 | 950 | 529 | 16% | 83.0% | 6,375 | 120 | 15 | 105 | 950 | 529 | 16% | 93.6% | 5,652 | 723 |
| 72.5 | YES | 910 | 910 | 160 | 10 | 150 | 950 | 950 | 865 | 16% | 83.0% | 10,416 | 120 | 15 | 105 | 950 | 865 | 16% | 93.6% | 9,234 | 1,181 |
| 67.5 | YES | 978 | 978 | 160 | 10 | 150 | 950 | 950 | 929 | 16% | 83.0% | 11,194 | 120 | 15 | 105 | 950 | 929 | 16% | 93.6% | 9,924 | 1,270 |
| 62.5 | YES | 971 | 971 | 160 | 10 | 150 | 950 | 950 | 922 | 16% | 83.0% | 11,114 | 120 | 15 | 105 | 950 | 922 | 16% | 93.6% | 9,853 | 1,260 |
| 57.5 | YES | 1,101 | 1,101 | 160 | 10 | 150 | 1,312 | 1,312 | 1,445 | 22% | 83.0% | 17,407 | 120 | 15 | 105 | 1,312 | 1,445 | 22% | 93.3% | 15,484 | 1,923 |
| 52.5 | YES | 655 | 655 | 161 | 10 | 151 | 1,743 | 1,743 | 1,142 | 29% | 83.0% | 13,758 | 123 | 15 | 108 | 1,743 | 1,142 | 29% | 92.5% | 12,346 | 1,412 |
| 47.5 | YES | 581 | 581 | 163 | 10 | 153 | 2,175 | 2,175 | 1,263 | 36% | 83.0% | 15,222 | 129 | 15 | 114 | 2,175 | 1,263 | 36% | 91.0% | 13,891 | 1,331 |
| 42.5 | YES | 561 | 561 | 165 | 10 | 155 | 2,606 | 2,606 | 1,462 | 43% | 83.0% | 17,612 | 136 | 15 | 121 | 2,606 | 1,462 | 43% | 88.9% | 16,450 | 1,162 |
| 37.5 | YES | 781 | 781 | 167 | 10 | 157 | 3,037 | 3,037 | 2,372 | 50% | 83.0% | 28,576 | 142 | 15 | 127 | 3,037 | 2,372 | 50% | 88.0% | 26,946 | 1,630 |
| 32.5 | YES | 680 | 680 | 169 | 10 | 159 | 3,468 | 3,468 | 2,358 | 58% | 83.0% | 28,413 | 148 | 15 | 133 | 3,468 | 2,358 | 58% | 87.6% | 26,911 | 1,502 |
| 27.5 | YES | 386 | 386 | 172 | 10 | 162 | 3,899 | 3,899 | 1,505 | 65% | 83.0% | 18,133 | 155 | 15 | 140 | 3,899 | 1,505 | 65% | 87.3% | 17,240 | 893 |
| 22.5 | YES | 191 | 191 | 174 | 10 | 164 | 4,330 | 4,330 | 827 | 72% | 83.0% | 9,965 | 161 | 15 | 146 | 4,330 | 827 | 72% | 87.4% | 9,467 | 498 |
| 17.5 | YES | 102 | 102 | 176 | 10 | 166 | 4,761 | 4,761 | 486 | 79% | 83.0% | 5,851 | 167 | 15 | 152 | 4,761 | 486 | 79% | 87.4% | 5,560 | 292 |
| 12.5 | YES | 41 | 41 | 178 | 10 | 168 | 5,193 | 5,193 | 213 | 86% | 83.0% | 2,565 | 174 | 15 | 159 | 5,193 | 213 | 86% | 86.7% | 2,456 | 109 |
| 7.5 | YES | 1 | 1 | 180 | 10 | 170 | 5,624 | 5,624 | 6 | 93% | 83.0% | 68 | 180 | 15 | 165 | 5,624 | 6 | 93% | 85.4% | 66 | 2 |
| **Totals** | | **8,760** | **8,760** | | | | | | **16,574** | | **83.0%** | **199,690** | | | | | **16,574** | | **90.0%** | **184,160** | **15,530** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-1: Boiler Replacement w/ Condensing, Hot Water Reset - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| **6,000 MBH Condensing Boiler** | 1 | EA | $ 93,000 | $ 2,500 | $ - | $ 91,233 | $ 1,743 | $ - | $ 92,976 | Vendor Quote |
| **1,500 MBH Condensing Boiler** | 1 | EA | $ 32,200 | $ 2,500 | $ - | $ 31,588 | $ 1,743 | $ - | $ 33,331 | Vendor Quote |
| **Condensing Boiler Electrical** | 1 | LS | $ 500 | $ 1,000 | $ - | $ 491 | $ 697 | $ - | $ 1,188 | Eng. Est |
| **Venting Kit** | 2 | EA | $ 450 | $ 650 | $ - | $ 440 | $ 785 | $ - | $ 1,225 | Eng. Est |
| **Miscellaneous Piping and Valves** | 1 | LS | $ 500 | $ 500 | $ - | $ 489 | $ 604 | $ - | $ 1,093 | Eng. Est |
| **Demolition** | 1 | LS | $ - | $ 5,000 | $ - | $ - | $ 3,485 | $ - | $ 3,485 | Eng. Est |
| | | | | | | | | | | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 133,296 | Subtotal |
| $ 26,659.21 | 20% Contingency |
| $ 19,994 | 15% O&P |
| **$ 179,950** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-5: Install Destratification Fans**

**ECM Description Summary**

*The Arrivals Building has an approximately 35' high ceiling. Due to the configuration of the HVAC system, this space may feel cold during the winter due to the warm air rising to the top of the room. It is recommended to install Air Pear destratification fans or similar in the ceilings of the baggage claim areas to push the heated air down towards where occupants can feel it. This will provide better occupant comfort, increase light fixture life, as well as reduce the total heating and cooling loads within the space. This reduction in loads will result in electrical cooling and natural gas heating savings.*

| EXISTING CONDITIONS | | | |
|---|---|---|---|
| Existing Facility Total Electric usage | 9,009,467 | kWh | |
| Existing Facility Natural Gas Usage | 201,210 | Therms | |
| Baggage Claim Area HVAC Electric Use | 816,202 | kWh | |
| Baggage Claim Area HVAC Gas Use | 47,461 | Therms | |
| Cost of Electricity | $ 0.06 | $/kWh | |
| Cost of Natural Gas | $ 0.34 | $/Therm | |
| SAVINGS | | | |
| **Annual Destratification Electric savings** | **110,365** | **kWh**[7] | 1.22% |
| **Annual Destratification Natural Gas savings** | **7,309** | **Therms**[7] | 3.63% |
| Total Cost Savings | $ 9,481 | | |
| | $ 6,788 | INSTALL COST | |
| | 0.72 | YEARS PAYBACK | |

Assumptions

| | | | |
|---|---|---|---|
| 1 | 36% | Percent of total facility electric usage for HVAC for airports, see chart below (cooling + ventilation) | |
| 2 | 94% | Percent of total facility natural gas usage for HVAC for airports, see chart below | |
| 3 | 76,850 | Total Facility Area (SF) | |
| 4 | 19,385 | Baggage Claim Area (SF) | 25.2% |
| 5 | 5 | Estimated floor to ceiling Δt (°F) | |
| 6 | 35 | Estimated floor to ceiling height (Ft) | |
| 7 | 15.4% | Percent HVAC savings for destratification per manufacturer (see table below), Source: http://www.theairpear.com/hvacenergysavings.html | |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-5: Install Destratification Fans - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Air Pear Model 25 SP | 50 | ea. | $ 415 | $ 150 | $ - | $ 20,356 | $ 5,228 | $ - | $ 25,583 | From Airius Fans Sales Rep |
| Reprogram DDC system | | ea. | $ - | $ - | $ - | $ - | $ - | $ - | $ - | no need to program for this model. |
| | | | | | | $ - | $ - | $ - | $ - | |
| electrical/wiring | 50 | ls | $ 100 | $ 350 | | $ 4,905 | $ 12,198 | $ - | $ 17,103 | swag |
| Lift | 2 | Per Week | $ - | $ - | $ 1,500 | $ - | $ - | $ 2,565 | $ 2,565 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 45,251 | Subtotal |
| $ 9,050.15 | 20% Contingency |
| $ 6,788 | 15% O&P |
| **$ 61,089** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

## M-6A: Install Variable Speed Drives - HW Pump

### Variable Inputs

| | |
|---|---|
| Blended Electric Rate | $0.06 |
| Heating System "On" Point | 65 |
| VFD Efficiency | 98.5% |

### ECM Description Summary

*Hot water pumps P-1 and P-2 provide heating hot water and chilled water pumps P-3 and P-4 provide chilled water to the air handling units located throughout the facility. These pump sets currently operate in lead/lag fashion with only one pump operating at a time. The hot and chilled water coils on the air handlers served by these pumps are equipped with 3-way control valves. The intent is to install a single VFD with bypass and selector switch to control both pumps based on pressure.*

**PUMP SCHEDULE**

| Pump ID | Qty | HP | Total HP | Existing Motor Motor Eff. | New Motor Motor Eff. | Exist. Motor kW Note 1 | New Motor kW Note 2 |
|---|---|---|---|---|---|---|---|
| P-1 | 1 | 30.0 | 30.0 | 93.0% | 94.1% | 19.25 | 19.03 |
| P-2 | 0 | 30.0 | 0.0 | 93.0% | 94.1% | 0.00 | 0.00 |
| | | | | | Total: | 19.25 | 19.03 |

**SAVINGS ANALYSIS**

| OAT - DB Avg Temp F | Annual Hours in Bin | Heating Hours Bin | Pump Load % | Existing Pump kWh | Proposed Pump kW | Speed efficiency % | Proposed Pump kWh | Proposed Savings kWh |
|---|---|---|---|---|---|---|---|---|
| (A) | (B ) | (C) | (D) | (E) | (F) | (G) | (H) | (I) |
| See Note 3 | See Note 3 | | See Note 4 | | See Note 5 | | | |
| 97.5 | 10 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 92.5 | 39 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 87.5 | 215 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 82.5 | 557 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 77.5 | 910 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 72.5 | 978 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 67.5 | 971 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 62.5 | 1,101 | 1,101 | 38% | 21,196 | 1.7 | 67.2% | 2,726 | 18,470 |
| 57.5 | 655 | 655 | 43% | 12,610 | 2.3 | 73.4% | 2,030 | 10,580 |
| 52.5 | 581 | 581 | 53% | 11,185 | 3.9 | 84.1% | 2,699 | 8,486 |
| 47.5 | 561 | 561 | 58% | 10,800 | 5.0 | 88.8% | 3,171 | 7,630 |
| 42.5 | 781 | 781 | 64% | 15,036 | 6.3 | 92.7% | 5,308 | 9,728 |
| 37.5 | 680 | 680 | 69% | 13,091 | 7.8 | 95.9% | 5,507 | 7,584 |
| 32.5 | 386 | 386 | 75% | 7,431 | 9.4 | 98.2% | 3,699 | 3,732 |
| 27.5 | 191 | 191 | 81% | 3,677 | 11.3 | 99.8% | 2,154 | 1,523 |
| 22.5 | 102 | 102 | 86% | 1,964 | 13.3 | 100.0% | 1,356 | 608 |
| 17.5 | 41 | 41 | 92% | 789 | 15.5 | 100.0% | 637 | 152 |
| 12.5 | 1 | 1 | 97% | 19 | 18.0 | 99.7% | 18 | 1 |
| 7.5 | 0 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| | **8,760** | **5,080** | | **97,798** | | | **29,305** | **68,494** |

Notes:
1) Existing motor power was determined using nameplate data
2) New motor power is the same as existing motor power adjusted for the new efficiency, if a new motor is proposed.
3) Weather data from NOAA for Norfolk VA
4) The pump load is estimated at 100% at 10 deg. OAT and 50% at 55 deg. OAT and varies linearly in between.
5) The required VFD motor draw is based on a 2.5 power relationship to load.

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

## M-6B: Install Variable Speed Drives -CHW Pump

### Variable Inputs

| | |
|---|---|
| Blended Electric Rate | $0.06 |
| Cooling System "On" Point | 65 |
| VFD Efficiency | 98.5% |

### ECM Description Summary

*Chilled water pump description*
*See ECM-16A HW Pump VFD for example*

**PUMP SCHEDULE**

| Pump ID | Qty | HP | Total HP | Existing Motor Motor Eff. | New Motor Motor Eff. | Exist. Motor kW Note 1 | New Motor kW Note 2 |
|---|---|---|---|---|---|---|---|
| P-3 | 1 | 40.0 | 40.0 | 91.7% | 94.1% | 26.03 | 25.37 |
| P-4 | 0 | 40.0 | 0.0 | 91.7% | 94.1% | 0.00 | 0.00 |
| | | | | | Total: | 26.03 | 25.37 |

**SAVINGS ANALYSIS**

| OAT - DB Avg Temp F | Annual Hours in Bin | Heating Hours Bin | Pump Load % | Existing Pump kWh | Proposed Pump kW | Speed efficiency % | Proposed Pump kWh | Proposed Savings kWh |
|---|---|---|---|---|---|---|---|---|
| (A) | (B) | (C ) | (D) | (E) | (F) | (G) | (H) | (I) |
| See Note 3 | See Note 3 | | See Note 4 | | See Note 5 | | | |
| 97.5 | 10 | 10 | 100% | 260 | 25.8 | 99.0% | 260 | 0 |
| 92.5 | 39 | 39 | 93% | 1,015 | 21.5 | 100.0% | 837 | 178 |
| 87.5 | 215 | 215 | 85% | 5,597 | 17.2 | 100.0% | 3,705 | 1,892 |
| 82.5 | 557 | 557 | 77% | 14,500 | 13.5 | 98.9% | 7,627 | 6,873 |
| 77.5 | 910 | 910 | 70% | 23,690 | 10.4 | 95.9% | 9,852 | 13,838 |
| 72.5 | 978 | 978 | 62% | 25,460 | 7.7 | 91.3% | 8,256 | 17,204 |
| 67.5 | 971 | 971 | 54% | 25,278 | 5.5 | 85.1% | 6,266 | 19,012 |
| 62.5 | 1,101 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 57.5 | 655 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 52.5 | 581 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 47.5 | 561 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 42.5 | 781 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 37.5 | 680 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 32.5 | 386 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 27.5 | 191 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 22.5 | 102 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 17.5 | 41 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 12.5 | 1 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 7.5 | 0 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| 2.5 | 0 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| -2.5 | 0 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| -7.5 | 0 | 0 | 0% | 0 | 0.0 | 0.0% | 0 | 0 |
| | 8,760 | 3,680 | | 95,800 | | | 36,804 | 58,996 |

Notes:

1) Existing motor power was determined using Nameplate data
2) New motor power is the same as existing motor power adjusted for the new efficiency, if a new motor is proposed.
3) Weather data from NOAA for Norfolk VA
4) The pump load is estimated at 100% at 100 deg. OAT and 50% at 60 deg. OAT and varies linearly in between.
5) The required VFD motor draw is based on a 2.5 power relationship to load.

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-6: Install Variable Speed Drives - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| 40 HP VFD | 2 | ea. | $ 8,025 | $ 1,400 | $ - | $ 15,745 | $ 1,952 | $ - | $ 17,697 | RS Means |
| 40 HP Motor | 2 | ea. | $ 3,975 | $ 233 | $ - | $ 7,799 | $ 325 | $ - | $ 8,124 | RS Means |
| 30 HP VFD | 2 | ea. | $ 6,950 | $ 1,400 | $ - | $ 13,636 | $ 1,952 | $ - | $ 15,588 | RS Means |
| 30 HP Motor | 2 | ea. | $ 3,250 | $ 194 | $ - | $ 6,377 | $ 270 | $ - | $ 6,647 | RS Means |
| Electrical - misc. | 1 | ls | $ 1,000 | $ 500 | $ - | $ 981 | $ 349 | $ - | $ 1,330 | Eng. Est |
| 2-Way valves | 27 | ea. | $ 500 | $ 100 | $ - | $ 13,244 | $ 1,882 | $ - | $ 15,125 | RS Means |
| Differential Pressure Controls | 2 | Ea. | $ 200 | $ 500 | $ - | $ 392 | $ 697 | $ - | $ 1,089 | Internet |
| Reprogram Controls | 1 | LS | $ - | $ 2,500 | $ - | $ - | $ 1,743 | $ - | $ 1,743 | Eng. Est |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 67,342 | Subtotal |
| $ 13,468.33 | 20% Contingency |
| $ 10,101 | 15% O&P |
| **$ 90,911** | **Total** |

**Norfolk Airport**

**CHA Project # 33370**

**Arrivals**

## M-9: Install Premium Efficiency Elevator Motors

### ECM Description Summary

*The existing Arrivals elevators have motors that are original to the facility. This measure proposes replacing the existing elevator motors with high efficiency motors.*

| Savings Analysis | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| # | Description | Location | Existing HP | Load Factor | Existing Efficiency | Existing kW | New HP | New Load Factor | New Efficiency | New kW | Demand Savings | Annual Hours | kWh Savings | |
| 1 | Elevator-12 | Arrivals | 50 | 0.8 | 80.0% | 37.3 | 50 | 0.8 | 0.930 | 32.1 | 5.212 | 1,460 | 7,609 | STD |
| 2 | Elevator-13 | Arrivals | 50 | 0.8 | 80.0% | 37.3 | 50 | 0.8 | 0.930 | 32.1 | 5.212 | 1,460 | 7,609 | STD |
| 3 | Elevator-14 | Arrivals | 50 | 0.8 | 80.0% | 37.3 | 50 | 0.8 | 0.930 | 32.1 | 5.212 | 1,460 | 7,609 | STD |
| 4 | Elevator-15 | Arrivals | 50 | 0.8 | 80.0% | 37.3 | 50 | 0.8 | 0.930 | 32.1 | 5.212 | 1,460 | 7,609 | STD |
| 5 | Elevator-17 | Garage B | 30 | 0.8 | 80.0% | 22.4 | 30 | 0.8 | 0.917 | 19.5 | 2.854 | 1,460 | 4,167 | STD |
| 6 | Elevator-18 | Garage B | 30 | 0.8 | 80.0% | 22.4 | 30 | 0.8 | 0.917 | 19.5 | 2.854 | 1,460 | 4,167 | STD |
| **Total** | | | **260** | | | **193.9** | **260** | | | **167.3** | **26.56** | | **38,772** | |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**M-9: Install Premium Efficiency Elevator Motors - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| 50HP STD motor | 4 | ea. | $ 4,200 | $ 750 | $ - | $ 16,481 | $ 2,091 | $ - | $ 18,572 | Internet |
| 30HP STD motor | 2 | ea. | $ 1,790 | $ 750 | $ - | $ 3,512 | $ 1,046 | $ - | $ 4,557 | Internet |
| Demolition/Remove Existing Motors | 6 | ea. | $ - | $ 500 | $ - | $ - | $ 2,091 | $ - | $ 2,091 | Estimate |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 25,220 | Subtotal |
| $ 5,044.06 | 20% Contingency |
| $ 3,783 | 15% O&P |
| **$ 34,047** | **Total** |

**Norfolk Airport**

**CHA Project # 33370**
**Arrivals**

**M-10 Upgrade Escalator Controls**

**ECM Description Summary**
Description: There are 2 escalators in this terminal. The existing escalators operate continuously with constant speed regardless whether passengers are using them or not. This ECM evaluates installing sensors, drives and controls that will allow for energy savings for periods of lower usage or stops when no passengers are around.

**Building Information:**
Electricity rate $0.06 $/kWh Blended

| ESCALATOR CONTROLS | | |
|---|---|---|
| EXISTING CONDITIONS | | |
| Number of Escalators | 2 | |
| Average Motor Size | 7.5 | kW |
| Operating Hours | 8,760 | |
| Average Motor Load | 0.4 | |
| Existing Operating Usage | 52,560 | kWh |
| PROPOSED CONDITIONS | | |
| Reduction due to speed controls and stops for slow or no traffic | 20% | |
| Hours of slow period | 7 | |
| Operating Hours | 6,205 | |
| Proposed Operating Usage | 29,784 | kWh |
| SAVINGS | | |
| Electric Savings | 22,776 | **kWh** |

Assumptions
1 Average 3,500 passengers per day

Reduction due to controls depends on traffic volume and utilization of controls. Statistics range from 15-25 % reduction

**Norfolk Airport**

**CHA Project # 33370**
**Arrivals**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

**M-10 Upgrade Escalator Controls**

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| Drive 10HP | 2 | ea. | $ 2,500 | $ 675 | | $ 4,905 | $ 941 | $ - | $ 5,846 | RS Means |
| Controller, sensors | 2 | ea. | $ 5,200 | $ 1,200 | | $ 10,202 | $ 1,673 | $ - | $ 11,875 | Vendor Info |
| calibration, start up | 1 | ls | | $ 340 | | $ - | $ 237 | $ - | $ 237 | Estimate |
| Misc. | 2 | ea. | $ 450 | $ 700 | | $ 883 | $ 976 | $ - | $ 1,859 | Estimate |
| | | | | | | | | | | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 19,817 | Subtotal |
| $ 3,963.37 | 20% Contingency |
| $ 2,973 | 15% O&P |
| **$ 26,753** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

## DHW-2: Install Condensing Gas-Fired DHW Heater

### ECM Description Summary

*The existing Arrivals DHW is provided by an inefficient natural gas-fired unit with an 80% efficiency. This measure proposes replacing the existing DHW heater with a high efficiency condensing natural gas DHW heater. If the existing boilers are replaced with a condensing boilers these can be used with an indirect water heater to achieve similar results for a lower cost.*

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 663 | gal/day | Calculated from usage below |
| Annual Hot Water Energy Demand | 130,571 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 100 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | Per building personnel |
| Average Room Temperature | 70 | ˚F | |
| Standby Losses (% by Volume) | 0.9% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.4 | MBH | |
| Annual Standby Hot Water Load | 3,285 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 133,856 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 80% | | Per Manufacturer |
| Total Annual Energy Required | 1,673 | Therms/yr | |
| | | | |
| New Tank Size | 100 | Gallons | tankless |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 70 | ˚F | |
| Standby Losses (% by Volume) | 0.9% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.4 | MBH | |
| Annual Standby Hot Water Load | 3,285 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 133,856 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 92% | | Based on Navien CR180 instantaneous, condensing DHW Heater |
| Proposed Total Annual Energy Required | 1,460 | Therms/yr | |
| | | | |
| Elec Utility Demand Unit Cost | $0.00 | $/kW | |
| Elec Utility Supply Unit Cost | $0.00 | $/kWh | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $565 | $/yr | |
| Proposed Operating Cost of DHW | $493 | $/yr | |
| **Annual Utility Cost Savings** | **$72** | **$/yr** | |

**Daily Hot Water Demand**

| | | | #USES PER DAY | | FULL TIME OCCUPANTS** | | | | |
|---|---|---|---|---|---|---|---|---|---|
| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | MALE | FEMALE | MALE | FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 1 | 1 | 1250 | 1250 | 1,250 | 50% | 625 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 5 | 5 | 50 | 75% | 38 |
| Dishwasher (gal per use) | 10 | 1 | 0 | 0 | 0 | 0 | 0 | 100% | 0 |
| | | | | | | **TOTAL** | 1,300 | | **663** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**DHW-2: Install Condensing Gas-Fired DHW Heater - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Gas-Fired DHW Heater Removal | 1 | LS | $ - | $ 500 | $ - | $ - | $ 349 | $ - | $ 349 | Eng. Est. |
| | | | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 100 Gallon Gas-Fired DHW Heater | 1 | EA | $ 7,250 | $ 1,000 | $ - | $ 7,112 | $ 697 | $ - | $ 7,809 | Internet |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | $ - | $ 491 | $ 174 | $ - | $ 665 | Eng. Est. |
| Venting Kit | 1 | EA | $ 1,000 | $ 1,500 | $ - | $ 981 | $ 1,046 | $ - | $ 2,027 | Eng. Est. |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ - | $ - | $ 491 | $ - | $ - | $ 491 | Eng. Est. |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 11,340 | Subtotal |
| $ 2,267.90 | 20% Contingency |
| $ 1,701 | 15% O&P |
| **$ 15,308** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

## C-2: Unoccupied Temperature Setback

**ECM Description Summary**

*During the hours of 1am - 5am, the Arrivals Building is usually empty as the scheduled arrivals are complete. This ECM would lower the heating setpoint and raise the cooling setpoint. This measure will modify programs to close OA damper during unoccupied periods while maintaining night setback temperatures, thus reducing heating and cooling loads during unoccupied periods.*

| EXISTING CONDITIONS | | |
|---|---|---|
| Existing Facility Total Electric usage | 3,235,756 | kWh |
| Existing Facility Natural Gas Usage | 188,153 | Therms |
| Cost of Electricity | $ 0.06 | $/kWh |
| Cost of Natural Gas | $ 0.34 | $/Therm |
| SAVINGS | | |
| TOD Electric savings | 24,601 | kWh[1] |
| TOD Natural Gas savings | 954 | Therms[2] |
| Total Cost Savings | $ 1,885 | |
| Estimated Total Project Cost | $ 16,031 | [4] |
| Simple Payback | 8.5 | **years** |

| | |
|---|---|
| AHU-26 | |
| AHU-27 | |
| AHU-28 | |
| AHU-29 | |
| AHU-30 | |
| AHU-31 | |
| AHU-32 | |
| AHU-33 | |
| AHU-35 | |
| AHU-36 | |
| TOTAL | 10 units to be setback |

Assumptions

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 1 | 0.8% | Approximate percent of total electric savings due to night setback | | | | 0.75 | % per degree electric savings |
| 2 | 0.5% | Approximate percent of total gas savings due to night setback | | | | 0.75 | % per degree gas savings |
| 3 | 4 | 72 | 68 | HEATING SETPOINT SETBACK | | | |
| 4 | 6 | 74 | 80 | COOLING SETPOINT SETBACK | | | |
| 5 | 4.0 | hours of setback | | | | | |
| | 20.0 | Hours of operations | Start | end | #days/wee | hours/year | |
| | | 5am - 1am, S-S | 5:00 | 1:00 | 7 | 7,280 | hours/year |
| | | | | | | 1,480 | hours/year setback |

**Norfolk Airport**
**CHA Project # 33370**
**Arrivals**

**C-2: Unoccupied Temperature Setback - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Reprogram DDC system | 10 | ea. | $ 500 | $ 1,000 | $ - | $ 4,905 | $ 6,970 | $ - | $ 11,875 | per temperature program |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 11,875 | Subtotal |
| $ 2,375 | 20% Contingency |
| $ 1,781 | 15% O&P |
| **$ 16,031** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**

| Utility Costs | | Yearly Usage | MTCDE | TOTAL (Jan17-Dec17) | DeptsTX1 | DeptsTX2 | CCB | *Concourse A* |
|---|---|---|---|---|---|---|---|---|
| $ 0.07 | $/kWh blended | | 0.00042021 | 13,094,430 | 5,402,880 | 4,341,600 | 3,349,950 | |
| $ 0.046 | $/kWh supply | 13,094,430 | 0.00042021 | | | | | |
| $ 10.47 | $/kW | 150 | 0 | | | | | |
| $ 0.34 | $/Therm | 241,260 | 0.00533471 | 24,126 MMBTU | | MAIN TERM 2017 | | |
| $ 12.91 | $/kgals | | 0 | | | | | |

# Main Terminal

| Recommended Y/N? | | Item | Savings kW | kWh | therms | kgal/yr | $ | Cost | Simple Payback | MTCDE | Life Expectancy | Simple kW | kWh | therms | kgal/yr | $ | ROI |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| N | BE-1 | Window Replacements | 0 | 11,032 | 15,169 | 0 | $ 5,904 | $ 4,625,646 | >25 | 85.6 | 15 | 0 | 165477.8655 | 227533.6608 | 0 | $ 88,567 | -0.980853016 |
| Y | BE-2 | Door Sweeps and Seal Replacements | 0 | 644 | 264 | 0 | $ 135 | $ 809 | 6.0 | 1.7 | 15 | 0 | 9664.071453 | 3955.830025 | 0 | $ 2,019 | 1.495733472 |
| N | BE-3 | White Roof Covering | 0 | 227,803 | 352 | 0 | $ 16,219 | $ 584,309 | >25 | 97.6 | 15 | 0 | 3417041.534 | 5278.185697 | 0 | $ 243,288 | -0.583631958 |
| N | BE-4 | Window Shading | 0 | 11,180 | 0 | 0 | $ 790 | $ 21,900 | >25 | 4.7 | 15 | 0 | 167707.1664 | 0 | 0 | $ 11,853 | -0.458775604 |
| N | M-1 | Boiler Replacements | 0 | 0 | 18,603 | 0 | $ 6,285 | $ 202,390 | >25 | 99.2 | 15 | 0 | 0 | 279046.6372 | 0 | $ 94,275 | -0.534190763 |
| Y | M-2 | AHU Motor Upgrades | 0 | 3,546 | 0 | 0 | $ 251 | $ 2,828 | 11.3 | 1.5 | 15 | 0 | 53188.1452 | 0 | 0 | $ 3,759 | 0.32934141 |
| Y | M-3 | Install Variable Speed Drives - AHU Fans | 0 | 993,978 | 0 | 0 | $ 70,251 | $ 202,093 | 2.9 | 417.7 | 15 | 0 | 14909668.61 | 0 | 0 | $ 1,053,763 | 4.214254971 |
| N | M-7 | Duct Sealing | 0 | 1,653 | 288 | 0 | $ 214 | $ 15,188 | >25 | 2.2 | 15 | 0 | 24795.34555 | 4320.157992 | 0 | $ 3,212 | -0.788510023 |
| Y | M-9 | Install Premium Efficiency Elevator Motors | 0 | 24,077 | 0 | 0 | $ 1,702 | $ 18,315 | 10.8 | 10.1 | 15 | 0 | 361155.8501 | 0 | 0 | $ 25,525 | 0.393658827 |
| N | M-10 | Upgrade Escalator Controls | 0 | 38,544 | 0 | 0 | $ 2,724 | $ 49,580 | 18.2 | 16.2 | 15 | 0 | 578160 | 0 | 0 | $ 40,862 | -0.17582434 |
| Y | DHW-1 & 2 | Domestic Hot Water Condensing Water Heaters | 71 | 78,267 | -2,804 | 0 | $ 11,644 | $ 89,006 | 7.6 | 17.9 | 15 | 1070.73348 | 1174009.84 | -42054.94925 | 0 | $ 174,654 | 0.962273437 |
| Y | C-1 | Demand Control Ventilation | 0 | 28,130 | 4,331 | 0 | $ 3,451 | $ 35,210 | 10.2 | 34.9 | 15 | 0 | 421944.8323 | 64970.34333 | 0 | $ 51,772 | 0.470378554 |
| Y | C-2 | Night Setback | 0 | 75,619 | 29,142 | 0 | $ 15,190 | $ 31,590 | 2.1 | 187.2 | 15 | 0 | 1134287.378 | 437135.94 | 0 | $ 227,853 | 6.212817806 |
| Y | K-1 | Kitchen Hood Upgrades | 0 | 78,674 | 3,668 | 0 | $ 6,800 | $ 60,922 | 9.0 | 52.6 | 15 | 0 | 1180114.963 | 55023.37524 | 0 | $ 101,996 | 0.674197443 |
| Y | K-2 | Walk-in Cooler and Freezer Controls | 0 | 82,495 | 0 | 0 | $ 5,830 | $ 37,500 | 6.4 | 34.7 | 15 | 0 | 1237423.635 | 0 | 0 | $ 87,457 | 1.332179486 |
| Y | K-3 | Vending Miser | 0 | 3,469 | 0 | 0 | $ 245 | $ 800 | 3.3 | 1.5 | 15 | 0 | 52034.4 | 0 | 0 | $ 3,678 | 3.597009444 |
| Y | L-1 | Lighting | 210 | 1,429,011 | 0 | 0 | $ 100,997 | $ 1,274,080 | 12.6 | 600.5 | 15 | 3154.5 | 21435165 | 0 | 0 | $ 1,388,342 | 0.089681691 |
| | | **Total Recommended** | **282** | **2,797,910** | **34,602** | **0** | **$ 216,495** | **$ 1,753,153.10** | **8.1** | **1,360** | | | | | | | |
| | | **Total** | **282** | **3,088,123** | **69,014** | **0** | **$ 248,633** | **$ 7,252,166** | **29.2** | **1666** | | | | | | | |
| | | **% of Existing** | **188%** | **24%** | **29%** | **#DIV/0!** | | | | | | | | | | | |

| **City:** | Norfolk, VA | | | | | |
|---|---|---|---|---|---|---|
| | | Occupied | Occupied | Off Hours | Occupied | Occupied |
| Temp | Bin Hours | Hours | Hours | Hours | Hours | Hours |
| 102.5 | 0 | 0 | 0 | 0 | 0 | 0 |
| 97.5 | 10 | 4 | 1 | 10 | 4 | 1 |
| 92.5 | 39 | 14 | 5 | 39 | 14 | 5 |
| 87.5 | 215 | 77 | 27 | 215 | 77 | 27 |
| 82.5 | 557 | 199 | 71 | 550 | 196 | 70 |
| 77.5 | 910 | 325 | 116 | 813 | 290 | 104 |
| 72.5 | 978 | 349 | 125 | 815 | 291 | 104 |
| 67.5 | 971 | 347 | 124 | 796 | 284 | 102 |
| 62.5 | 1,101 | 393 | 140 | 881 | 315 | 112 |
| 57.5 | 655 | 234 | 84 | 521 | 186 | 66 |
| 52.5 | 581 | 208 | 74 | 472 | 169 | 60 |
| 47.5 | 561 | 200 | 72 | 469 | 168 | 60 |
| 42.5 | 781 | 279 | 100 | 634 | 226 | 81 |
| 37.5 | 680 | 243 | 87 | 525 | 188 | 67 |
| 32.5 | 386 | 138 | 49 | 303 | 108 | 39 |
| 27.5 | 191 | 68 | 24 | 148 | 53 | 19 |
| 22.5 | 102 | 36 | 13 | 76 | 27 | 10 |
| 17.5 | 41 | 15 | 5 | 32 | 11 | 4 |
| 12.5 | 1 | 0 | 0 | 1 | 0 | 0 |
| 7.5 | 0 | 0 | 0 | 0 | 0 | 0 |

| Multipliers | |
|---|---|
| Material: | 0.981 |
| Labor: | 0.697 |
| Equipment: | 0.855 |

| | |
|---|---|
| Exist Heating Efficiency | 83% |
| Cooling Eff (kW/ton) | 0.80 |

MAX KW/TON
0.593 Old Chiller
0.450 New Chiller
0.522 AVG MAX KW/TON

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## BE-1: Window Replacement/Upgrade

**Description**

Windows can lead to increased energy consumption due to infiltration/exfiltration and heat gain/loss. Replacing older windows with more panes and low-emissivity coatings and insulated frames can decrease energy usage.

**Given**

| | | | | |
|---|---|---|---|---|
| Occupied Cooling Hours per Week | 168 | Hours | | |
| Occupied Heating Hours per Week | 168 | Hours | | |
| Heating Energy Cost | $0.34 | $/therm | | |
| Cooling Cost | $0.071 | $/kWh | | |
| Occupied Cooling Setpoint Temperature | 73.0 | Degrees F | | (Assumption) |
| Occupied Cooling Avg Space Air Enthalpy | 24.5 | btu/# air | | (Assumption) |
| Occupied Heating Setpoint Temperature | 68.0 | Degrees F | Occupied | (Assumption) |
| Unoccupied Heating Setpoint Temperature | 68.0 | Degrees F | Unoccupied | (Assumption) |
| Window Area | 27,220 | sq. Ft. | | (From Drawings and estimates) |
| Window Perimeter | 26,248 | ft | | (From Drawings and estimates) |
| Proposed U factor | 0.50 | Btu/(h*Sqft*degf) | | (From window vendor) |
| Proposed Air Infiltration | 0.20 | cfm/ft | | (From window vendor) |
| Cooling Conversion | 12,000 | Btu/ton | | |
| Heating Btu Conversion | 1,000,000 | Btu/MMBtu | | |

**Assumptions**

| | | | |
|---|---|---|---|
| Existing U factor | 0.95 | Btu/(h*Sqft*degf) | (From ASHRAE Fundamentals) |
| Existing Air Infiltration | 0.20 | cfm/ft | (From ASHRAE Fundamentals) |
| Heating System Efficiency | 83% | | |
| Cooling System Efficiency | 0.80 | kW/ton | |

**Formula**

Cooling Energy Conduction = (Existing U x Area x (OA Temp - RA Temp) x Op Hours)

Heating Energy Conduction = (Existing U x Area x (RA Temp - OA Temp) x Op Hours)
Cooling Energy Infiltration = (4.5 x Leakage x Perimeter x (OA Enthalpy - RA Enthalpy) x Op Hours)
Heating Energy Infiltration = 1.08 x Leakage x Perimeter x (RA temp - OA temp) x Op Hours)
Load = (Conduction) + (Infiltration)
Cooling Energy = (Cooling Load) / (12,000 Btu/Ton) x (kw/Ton)
Heating Energy = (Heating Load) / (1,000,000 Btu/MMBtu) / (Boiler Efficiency)
Energy Cost = (Energy) x (Cost/Unit)

**Existing**

| Operation | OA Enthalpy | OA Temp | Total Hours | Cooling Occupied Hours | Heating Occupied Hours | Heating Unoccupied Hours | Cooling Occupied Conduction | Heating Occupied Conduction | Heating Unoccupied Conduction | | Cooling Occupied Infiltration | Heating Occupied Infiltration | Heating Unoccupied Infiltration | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Cooling | 42.372 | 97.5 | 10 | 10.0 | 0.0 | 0.0 | 6,335,455 | 0 | 0 | | 4,221,915 | 0 | 0 | |
| Cooling | 39.715 | 92.5 | 39 | 39.0 | 0.0 | 0.0 | 19,665,770 | 0 | 0 | | 14,017,191 | 0 | 0 | |
| Cooling | 38.089 | 87.5 | 215 | 215.0 | 0.0 | 0.0 | 80,615,433 | 0 | 0 | | 69,019,058 | 0 | 0 | |
| Cooling | 35.853 | 82.5 | 557 | 557.0 | 0.0 | 0.0 | 136,832,899 | 0 | 0 | | 149,380,456 | 0 | 0 | |
| Cooling | 33.985 | 77.5 | 910 | 910.0 | 0.0 | 0.0 | 105,892,605 | 0 | 0 | | 203,907,126 | 0 | 0 | |
| Heating | 31.583 | 72.5 | 978 | 0.0 | 0.0 | 0.0 | 0 | 0 | 0 | | 0 | 0 | 0 | |
| Heating | 28.27 | 67.5 | 971 | 0.0 | 971.0 | 0.0 | 0 | 12,554,545 | 0 | | 0 | 2,752,560 | 0 | |
| Heating | 24.533 | 62.5 | 1,101 | 0.0 | 1101.0 | 0.0 | 0 | 156,589,175 | 0 | | 0 | 34,331,882 | 0 | |
| Heating | 21.544 | 57.5 | 655 | 0.0 | 655.0 | 0.0 | 0 | 177,845,273 | 0 | | 0 | 38,992,242 | 0 | |
| Heating | 18.652 | 52.5 | 581 | 0.0 | 581.0 | 0.0 | 0 | 232,873,225 | 0 | | 0 | 51,057,017 | 0 | |
| Heating | 16.338 | 47.5 | 561 | 0.0 | 561.0 | 0.0 | 0 | 297,391,430 | 0 | | 0 | 65,202,512 | 0 | |
| Heating | 14.555 | 42.5 | 781 | 0.0 | 781.0 | 0.0 | 0 | 514,994,915 | 0 | | 0 | 112,911,667 | 0 | |
| Heating | 12.606 | 37.5 | 680 | 0.0 | 680.0 | 0.0 | 0 | 536,315,660 | 0 | | 0 | 117,586,200 | 0 | |
| Heating | 10.771 | 32.5 | 386 | 0.0 | 386.0 | 0.0 | 0 | 354,345,877 | 0 | | 0 | 77,689,667 | 0 | |
| Heating | 8.5873 | 27.5 | 191 | 0.0 | 191.0 | 0.0 | 0 | 200,032,295 | 0 | | 0 | 43,856,705 | 0 | |
| Heating | 7.2196 | 22.5 | 102 | 0.0 | 102.0 | 0.0 | 0 | 120,011,619 | 0 | | 0 | 26,312,322 | 0 | |
| Heating | 5.3544 | 17.5 | 41 | 0.0 | 41.0 | 0.0 | 0 | 53,541,060 | 0 | | 0 | 11,738,777 | 0 | |
| Heating | 4.4951 | 12.5 | 1 | 0.0 | 1.0 | 0.0 | 0 | 1,435,175 | 0 | | 0 | 314,659 | 0 | |
| Subtotal = | | | **8,760** | **1,731** | **6,051** | **0** | **349,342,161** | **2,657,930,245** | **0** | **btu** | **440,545,746** | **582,746,210** | **0** | **btu** |

| | Conduction | Infiltration | | |
|---|---|---|---|---|
| Cooling Load = | 349342161 | 440545746 | **789,887,907** | **btu** |
| | Cooling Load | | | |
| Cooling Energy = | 789887907 | 12000 / 0.80 | **52,659** | **kWh** |
| | Cooling Energy | Cooling Cost | | |
| Cooling Energy Cost = | 52659.19 | $0.071 | **$ 3,721.77** | |
| | Conduction | Infiltration | | |
| Heating Load = | 2657930245 | 582746210 | **3,240,676,454** | **btu** |
| | Heating Load | Heat Content | | |
| Heating Energy = | 3240676454 | 83% / 100000 | **39,044** | **therms** |
| | Heating Energy | Heating Cost | | |
| Heating Energy Cost = | 39044.29 | $0.338 | **$ 13,191** | |

65,824 Ton-Hrs
38.0 Avg. Tons during Cooling Season

| Operation | OA Enthalpy | OA Temp | Total Hours | Cooling Occupied Hours | Heating Occupied Hours | Heating Unoccupied Hours | Cooling Occupied Conduction | Heating Occupied Conduction | Heating Unoccupied Conduction | Cooling Occupied Infiltration | Heating Occupied Infiltration | Heating Unoccupied Infiltration |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Cooling | 42.372 | 97.5 | 10 | 10.0 | 0.0 | 0.0 | 3,334,450 | 0 | 0 | 4,221,915 | 0 | 0 |
| Cooling | 39.715 | 92.5 | 39 | 39.0 | 0.0 | 0.0 | 10,350,405 | 0 | 0 | 14,017,191 | 0 | 0 |
| Cooling | 38.089 | 87.5 | 215 | 215.0 | 0.0 | 0.0 | 42,429,175 | 0 | 0 | 69,019,058 | 0 | 0 |
| Cooling | 35.853 | 82.5 | 557 | 557.0 | 0.0 | 0.0 | 72,017,315 | 0 | 0 | 149,380,456 | 0 | 0 |
| Cooling | 33.985 | 77.5 | 910 | 910.0 | 0.0 | 0.0 | 55,732,950 | 0 | 0 | 203,907,126 | 0 | 0 |
| Heating | 31.583 | 72.5 | 978 | 0.0 | 0.0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Heating | 28.27 | 67.5 | 971 | 0.0 | 971.0 | 0.0 | 0 | 6,607,655 | 0 | 0 | 2,752,560 | 0 |
| Heating | 24.533 | 62.5 | 1,101 | 0.0 | 1101.0 | 0.0 | 0 | 82,415,355 | 0 | 0 | 34,331,882 | 0 |
| Heating | 21.544 | 57.5 | 655 | 0.0 | 655.0 | 0.0 | 0 | 93,602,775 | 0 | 0 | 38,992,242 | 0 |
| Heating | 18.652 | 52.5 | 581 | 0.0 | 581.0 | 0.0 | 0 | 122,564,855 | 0 | 0 | 51,057,017 | 0 |
| Heating | 16.338 | 47.5 | 561 | 0.0 | 561.0 | 0.0 | 0 | 156,521,805 | 0 | 0 | 65,202,512 | 0 |
| Heating | 14.555 | 42.5 | 781 | 0.0 | 781.0 | 0.0 | 0 | 271,049,955 | 0 | 0 | 112,911,667 | 0 |
| Heating | 12.606 | 37.5 | 680 | 0.0 | 680.0 | 0.0 | 0 | 282,271,400 | 0 | 0 | 117,586,200 | 0 |
| Heating | 10.771 | 32.5 | 386 | 0.0 | 386.0 | 0.0 | 0 | 186,497,830 | 0 | 0 | 77,689,667 | 0 |
| Heating | 8.5873 | 27.5 | 191 | 0.0 | 191.0 | 0.0 | 0 | 105,280,155 | 0 | 0 | 43,856,705 | 0 |
| Heating | 7.2196 | 22.5 | 102 | 0.0 | 102.0 | 0.0 | 0 | 63,164,010 | 0 | 0 | 26,312,322 | 0 |
| Heating | 5.3544 | 17.5 | 41 | 0.0 | 41.0 | 0.0 | 0 | 28,179,505 | 0 | 0 | 11,738,777 | 0 |
| Heating | 4.4951 | 12.5 | 1 | 0.0 | 1.0 | 0.0 | 0 | 755,355 | 0 | 0 | 314,659 | 0 |
| Subtotal = | | | **8,760** | **1,731** | **6,051** | **0** | **183,864,295** | **1,398,910,655** | **0 btu** | **440,545,746** | **582,746,210** | **0 btu** |

| | Conduction | Infiltration | | |
|---|---|---|---|---|
| Cooling Load = | ( 183864295 ) + ( 440545746 ) = | | **624,410,041 btu** | |
| | Cooling Load | | | |
| Cooling Energy = | ( 624410041 )/( 12000 ) * ( 0.80 ) = | | **41627 kWh** | |
| | Cooling Energy | Cooling Cost | | |
| Cooling Energy Cost = | ( 41627.34 ) x ( $0.071 ) = | | **$ 2,942.07** | |
| | Conduction | Infiltration | | |
| Heating Load = | ( 1398910655 ) + ( 582746210 ) = | | **1,981,656,865 btu** | |
| | Heating Load | Heat Content | | |
| Heating Energy = | ( 1981656865 )/( 83% ) / ( 100000 ) = | | **23875 therms** | |
| | Heating Energy | Heating Cost | | |
| Heating Energy Cost = | ( 23875.38 ) x ( $0.338 ) = | | **$ 8,066** | |

**Summary**

| | | | | Existing Annual | % of Existing |
|---|---|---|---|---|---|
| **EXISTING COOLING ENERGY** | **52,659** | **kWh** | **$ 3,721.77** | 13,094,430 | 0.4% |
| **EXISTING HEATING ENERGY** | **39,044** | **therms** | **$ 13,191.04** | 241,260 | 16.2% |
| **EXISTING ENERGY COST** | | | **$ 16,912.80** | | |
| **PROPOSED COOLING ENERGY** | **41,627** | **kWh** | **$ 2,942.07** | 13,094,430 | 0.3% |
| **PROPOSED HEATING ENERGY** | **23,875** | **therms** | **$ 8,066.25** | 241,260 | 9.9% |
| **PROPOSED ENERGY COST** | | | **$ 11,008.32** | | |
| **COOLING ENERGY SAVINGS** | **11,032** | **kWh** | **$ 779.69** | **20.9% of existing** | |
| **HEATING ENERGY SAVINGS** | **15,169** | **therms** | **$ 5,124.79** | **38.9% of existing** | |
| **ENERGY COST SAVINGS** | | | **$ 5,904.48** | **34.9% of existing** | |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**BE-1: Window Replacement/Upgrade - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| double pane aluminum frame store front windows | 27220 | SQFT | $ 181 | | | $ 3,426,405 | $ - | $ - | $ 3,426,405 | Based off of previous audit costing for storefront style aluminum frame double pane windows |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 3,426,405 | Subtotal |
| $ 685,281 | 20% Contingency |
| $ 513,960.69 | 15% O&P |
| **$ 4,625,646** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## BE-2: Install Door Seals

### ECM Description Summary

*Some of the existing door sweeps and seals at the airport are in poor condition or nonexistent. This lack of seals results in excessive heat loss and infiltration. By installing new door seals air infiltration and heat loss can be reduced resulting in decreased energy consumption.*

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Heating System Efficiency | 83% | | Ex Occupied Clng Temp. | 74 | *F | Ex Occupied Htg Temp. | 72 | *F |
| Cooling System Efficiency | 0.80 | kW/ton | Ex Unoccupied Clng Temp. | 74 | *F | Ex Unoccupied Htg Temp. | 72 | *F |
| Linear Feet of Door Edge | 152 | | Cooling Occ Enthalpy Setpoint | 27.5 | Btu/lb | Electricity | $ 0.07 | $/kWh |
| Existing Infiltration Factor* | 1.5 | cfm/LF | Cooling Unocc Enthalpy Setpoint | 27.5 | Btu/lb | Natural Gas | $ 0.34 | $/therm |
| Proposed Infiltration Factor* | 0.45 | cfm/LF | | | | | | |

*Infiltration Factor per Carrier Handbook of Air Conditioning System Design based on average door seal gap calculated below.

| | | | | | EXISTING LOADS | | PROPOSED LOADS | | COOLING ENERGY | | HEATING ENERGY | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Occupied | Unoccupied | Occupied | Unoccupied | | | | |
| Avg Outdoor Air Temp. Bins °F | Avg Outdoor Air Enthalpy | Existing Equipment Bin Hours | Occupied Equipment Bin Hours | Unoccupied Equipment Bin Hours | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Existing Cooling Energy kWh | Proposed Cooling Energy kWh | Existing Heating Energy Therms | Proposed Heating Energy Therms |
| A | | B | C | D | E | F | G | H | I | J | K | L |
| 102.5 | 0.0 | 0 | 0 | 0 | 28,215 | 28,215 | 8,465 | 8,465 | 0 | 0 | 0 | 0 |
| 97.5 | 42.4 | 10 | 10 | 0 | -15,259 | -15,259 | -4,578 | -4,578 | 10 | 3 | 0 | 0 |
| 92.5 | 39.7 | 39 | 39 | 0 | -12,532 | -12,532 | -3,760 | -3,760 | 33 | 10 | 0 | 0 |
| 87.5 | 38.1 | 215 | 215 | 0 | -10,865 | -10,865 | -3,259 | -3,259 | 156 | 47 | 0 | 0 |
| 82.5 | 35.9 | 557 | 557 | 0 | -8,570 | -8,570 | -2,571 | -2,571 | 318 | 95 | 0 | 0 |
| 77.5 | 34.0 | 910 | 910 | 0 | -6,654 | -6,654 | -1,996 | -1,996 | 404 | 121 | 0 | 0 |
| 72.5 | 31.6 | 978 | 978 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 67.5 | 28.3 | 971 | 971 | 0 | 1,108 | 1,108 | 332 | 332 | 0 | 0 | 13 | 4 |
| 62.5 | 24.5 | 1,101 | 1,101 | 0 | 2,339 | 2,339 | 702 | 702 | 0 | 0 | 31 | 9 |
| 57.5 | 21.5 | 655 | 655 | 0 | 3,570 | 3,570 | 1,071 | 1,071 | 0 | 0 | 28 | 8 |
| 52.5 | 18.7 | 581 | 581 | 0 | 4,802 | 4,802 | 1,441 | 1,441 | 0 | 0 | 34 | 10 |
| 47.5 | 16.3 | 561 | 561 | 0 | 6,033 | 6,033 | 1,810 | 1,810 | 0 | 0 | 41 | 12 |
| 42.5 | 14.6 | 781 | 781 | 0 | 7,264 | 7,264 | 2,179 | 2,179 | 0 | 0 | 68 | 21 |
| 37.5 | 12.6 | 680 | 680 | 0 | 8,495 | 8,495 | 2,549 | 2,549 | 0 | 0 | 70 | 21 |
| 32.5 | 10.8 | 386 | 386 | 0 | 9,726 | 9,726 | 2,918 | 2,918 | 0 | 0 | 45 | 14 |
| 27.5 | 8.6 | 191 | 191 | 0 | 10,958 | 10,958 | 3,287 | 3,287 | 0 | 0 | 25 | 8 |
| 22.5 | 7.2 | 102 | 102 | 0 | 12,189 | 12,189 | 3,657 | 3,657 | 0 | 0 | 15 | 4 |
| 17.5 | 5.4 | 41 | 41 | 0 | 13,420 | 13,420 | 4,026 | 4,026 | 0 | 0 | 7 | 2 |
| 12.5 | 4.5 | 1 | 1 | 0 | 14,651 | 14,651 | 4,395 | 4,395 | 0 | 0 | 0 | 0 |
| 7.5 | 0.0 | 0 | 0 | 0 | 15,882 | 15,882 | 4,765 | 4,765 | 0 | 0 | 0 | 0 |
| **TOTALS** | | **8,760** | **8,760** | **0** | | | | | **920** | **276** | **377** | **113** |

| | | |
|---|---|---|
| **Existing Door Infiltration** | **228** | **cfm** |
| **Existing Unoccupied Door Infiltration** | **228** | **cfm** |
| **Proposed Door Infiltration** | **68** | **cfm** |
| **Proposed Unoccupied Door Infiltration** | **68** | **cfm** |

| **Savings** | | | |
|---|---|---|---|
| | **264** | **therms** | **$ 89** |
| | **644** | **kWh** | **$ 46** |
| | | | **$ 135** |

| Door | Width (ft) | Height (ft) | Linear Feet (LF) | gap (in) | gap location | LF of gap | % door w/ gap | Average gap for door (in) |
|---|---|---|---|---|---|---|---|---|
| 1 | 3 | 7 | 20 | 0 | None | 0 | 0% | 0.0000 |
| 2 | 3 | 7 | 20 | 0 | None | 0 | 0% | 0.0000 |
| 3 | 6 | 7 | 26 | 0.5 | Bottom | 6 | 23% | 0.1154 |
| 4 | 6 | 7 | 26 | 0 | None | 0 | 0% | 0.0000 |
| 5a | 3 | 7 | 20 | 0.5 | Bottom | 3 | 15% | 0.0750 |
| 5b | 3 | 7 | 20 | 0.25 | Bottom | 3 | 15% | 0.0375 |
| 6 | 6 | 7 | 26 | 0 | None | 0 | 0% | 0.0000 |
| 7a | 3 | 7 | 20 | 0.75 | Bottom | 3 | 15% | 0.1125 |
| 7b | 3 | 7 | 20 | 0.25 | Bottom | 1.5 | 8% | 0.0188 |
| 8 | 6 | 7 | 26 | 0.75 | Bottom | 6 | 23% | 0.1731 |
| 9 | 6 | 7 | 26 | 0 | None | 0 | 0% | 0.0000 |
| 10 | 3 | 7 | 20 | 0.5 | Bottom | 3 | 15% | 0.0750 |
| **Total** | **27** | **49** | **152** | **0.292** | | **25.5** | **17%** | **0.087** |

Note: Doors labeled 'a', 'b', etc. are a part of the same door assembly.

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**BE-2: Install Door Seals - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Door Seals | 152 | LF | $ 2.15 | $ - | $ - | $ 321 | $ - | $ - | $ 321 | Internet |
| Install | 8 | EA | $ - | $ 50 | $ - | $ - | $ 279 | $ - | $ 279 | Eng. Est |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 599 | Subtotal |
| $ 120 | 20% Contingency |
| $ 89.91 | 15% O&P |
| **$ 809** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## BE-3: White Roof Coating

| | City | State | |
|---|---|---|---|
| **Location** | Norfolk | Virginia | |
| Square Footage | 258,735 | | |

**Inputs**

| **Property** | **Proposed Case (existing)** | |
|---|---|---|
| **Roof R-Value (Insulation)** | 10 | Enter # between 5 and 32 h·ft²·°F/Btu |
| **Solar Reflectance** | 0.5 | Enter # between 5% and 85% |
| **Emissivity** | 0.6 | Enter # between 5% and 95% |

| **Utility Data** | | |
|---|---|---|
| Summertime Cost of Electricity | $ 0.07 | $/kWh |
| Cooling System Efficiency (COP) | 0.8 | kW/ton |
| Heating Energy System | Fuel | Fuel Or Electric |
| Heating System Cost | $ 0.34 | |
| Heating System Efficiency | 83% | |

| **Electric Demand** | | |
|---|---|---|
| Demand Charge During Cooling Season | $ 10.47 | $/kW |
| Months Charged for Peak Demand | 12 | Months |

Enter inputs from above at:
https://web.ornl.gov/sci/buildings/tools/cool-roof/

**Outputs**

| | **Outputs** (Enter from calculator) | | |
|---|---|---|---|
| Cooling Energy Savings | 0.025 | $/sq. ft. | |
| Heating Energy Savings | 0 | $/sq. ft. | Note: Negative number represents a heating penalty |
| Cooling season demand savings | 0 | $/sq. ft. | |
| Total $ Saved | $ 3,234.18 | | |

| | | | |
|---|---|---|---|
| **Insulation in Black Roof for Same Total Annual Energy Savings (Ignores demand savings)** | 10 | R-Value | 13.7 h·ft²·°F/Btu |

| **Details of Energy and Demand Savings:** | | |
|---|---|---|
| Heating degree days for location chosen | 3,489 | Annual °F-day |
| Cooling degree days for location chosen | 1,439 | Annual °F-day |
| Solar load for location chosen | 1,339 | Annual average Btu/ft² per day |
| Cooling load for black roof | 9,247 | Btu/ft² per year |
| Heating load for black roof | 11,798 | Btu/ft² per year |
| Cooling load for proposed roof | 6,240 | Btu/ft² per year |
| Heating load for proposed roof | 11,662 | Btu/ft² per year |

| **Itemized Savings** | | | |
|---|---|---|---|
| kW Demand Reduced | 0 | kW | |
| kWh Saved | 227,803 | kWh | |
| Therms Saved | 352 | Therms | Note: Negative number represents a heating penalty |

| **Installation Costs** | | |
|---|---|---|
| Cost of Product per square foot | 0.8 | $/sq. ft. |
| Estimated material cost | $ 203,055 | |
| Labor Rate | 1.3 | $/sq. ft. |
| Estimated labor cost | $ 234,439 | |
| Estimated cost of installation | $ 437,494 | |



**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**BE-3: White Roof Coating - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| **White Roof** | 258,735 | Sqft | $ 0.84 | $ 0.47 | $ - | $ 213,208 | $ 84,759 | $ - | $ 297,967 | RS Means |
| **1" Insulation** | 258,735 | Sqft | $ 0.2 | $ 0.4 | | $ 60,916 | $ 73,939 | $ - | $ 134,855 | RS Means |
| | | | | | | $ - | $ - | $ - | $ - | |

| | |
|---|---|
| $ 432,822 | Subtotal |
| $ 86,564.32 | 20% Contingency |
| $ 64,923.24 | 15% O&P |
| **$ 584,309** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## BE-4: Install Blinds or Shades

**Description**

**Given**

| | | |
|---|---|---|
| Cooling Hours per Week | 168 | Hours |
| Heating Hours per Week | 168 | Hours |
| Heating Energy Cost | $0.34 | $/therm |
| Cooling Cost | $0.071 | $/kWh |
| Occupied Cooling Setpoint Temperature | 74.0 | Degrees F |
| Occupied Cooling Avg Space Air Enthalpy | 25.5 | btu/# air |
| Occupied Heating Setpoint Temperature | 72.0 | Degrees F |
| Unoccupied Heating Setpoint Temperature | 72.0 | Degrees F |
| Window Area | 12,922 | sq. Ft. |
| Window Perimeter | 12,461 | ft |
| Proposed U factor | 0.95 | Btu/(h*Sqft*deg) |
| Proposed Air Infiltration | 0.20 | cfm/ft |
| Cooling Conversion | 12,000 | Btu/ton |
| Heating Btu Conversion | 1,000,000 | Btu/MMBtu |
| Existing Solar Load - North Wall | 47,196 | Btu/hr |
| Existing Solar Load - East Wall | - | Btu/hr |
| Existing Solar Load - South Wall | 85,777 | Btu/hr |
| Existing Solar Load - West Wall | 28,564 | Btu/hr |
| New Shading Coefficient | 0.25 | |

**Existing CLF**

| | |
|---|---|
| North Wall | 0.75 |
| East Wall | 0.31 |
| South Wall | 0.58 |
| West Wall | 0.29 |

**Existing SC**

| | |
|---|---|
| North Wall | 0.8 |
| East Wall | 0.8 |
| South Wall | 0.8 |
| West Wall | 0.8 |

**Existing SHGF**

| | |
|---|---|
| North Wall | 38 |
| East Wall | 216 |
| South Wall | 109 |
| West Wall | 216 |

**Assumptions**

| | | |
|---|---|---|
| Existing U factor | 0.95 | Btu/(h*Sqft*deg) |
| Existing Air Infiltration | 0.20 | cfm/ft |
| Cooling System Efficiency | 0.80 | kW/ton |
| Heating Energy Equipment Efficiency | 83% | |

**Formula**

Cooling Energy Conduction = (Existing U x Area x (OA Temp - RA Temp) x Op Hours)
Heating Energy Conduction = (Existing U x Area x (RA Temp - OA Temp) x Op Hours)
Cooling Energy Infiltration = (4.5 x Leakage x Perimeter x (OA Enthalpy - RA Enthalpy) x Op Hours)
Heating Energy Infiltration = 1.08 x Leakage x Perimeter x (RA temp - OA temp) x Op Hours)
Load = (Conduction) + (Infiltration)
Cooling Energy = (Cooling Load) / (12,000 Btu/Ton) x (kw/Ton)
Heating Energy = (Heating Load) / (1,000,000 Btu/MMBtu) / (Boiler Efficiency)
Energy Cost = (Energy) x (Cost/Unit)

**Existing**

| Operation | OA Enthalpy | OA Temp | Total Hours | Cooling Occupied Hours | Heating Occupied Hours | Heating Unoccupied Hours | Cooling Occupied Conduction | Heating Occupied Conduction | Heating Unoccupied Conduction | | Cooling Occupied Infiltration | Heating Occupied Infiltration | Heating Unoccupied Infiltration | Solar Cooling Load |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Cooling | 42.4 | 97.5 | 10 | 10.0 | 0.0 | 0.0 | 2,884,837 | 0 | 0 | | 1,892,102 | 0 | 0 | 1,615,367 |
| Cooling | 39.7 | 92.5 | 39 | 39.0 | 0.0 | 0.0 | 8,857,062 | 0 | 0 | | 6,216,940 | 0 | 0 | 6,299,933 |
| Cooling | 38.1 | 87.5 | 215 | 215.0 | 0.0 | 0.0 | 35,630,800 | 0 | 0 | | 30,353,929 | 0 | 0 | 34,730,398 |
| Cooling | 35.9 | 82.5 | 557 | 557.0 | 0.0 | 0.0 | 58,120,249 | 0 | 0 | | 64,668,109 | 0 | 0 | 89,975,962 |
| Cooling | 34.0 | 77.5 | 910 | 910.0 | 0.0 | 0.0 | 39,098,742 | 0 | 0 | | 86,594,552 | 0 | 0 | 146,998,430 |
| Heating | 31.6 | 72.5 | 978 | 0.0 | 0.0 | 0.0 | 0 | 0 | 0 | | 0 | 0 | 0 | - |
| Heating | 28.3 | 67.5 | 971 | 0.0 | 971.0 | 0.0 | 0 | 53,639,545 | 0 | | 0 | 11,760,369 | 0 | - |
| Heating | 24.5 | 62.5 | 1,101 | 0.0 | 1101.0 | 0.0 | 0 | 128,399,776 | 0 | | 0 | 28,151,410 | 0 | - |
| Heating | 21.5 | 57.5 | 655 | 0.0 | 655.0 | 0.0 | 0 | 116,590,360 | 0 | | 0 | 25,562,217 | 0 | - |
| Heating | 18.7 | 52.5 | 581 | 0.0 | 581.0 | 0.0 | 0 | 139,079,809 | 0 | | 0 | 30,492,987 | 0 | - |
| Heating | 16.3 | 47.5 | 561 | 0.0 | 561.0 | 0.0 | 0 | 168,726,108 | 0 | | 0 | 36,992,882 | 0 | - |
| Heating | 14.6 | 42.5 | 781 | 0.0 | 781.0 | 0.0 | 0 | 282,830,598 | 0 | | 0 | 62,010,077 | 0 | - |
| Heating | 12.6 | 37.5 | 680 | 0.0 | 680.0 | 0.0 | 0 | 287,992,614 | 0 | | 0 | 63,141,839 | 0 | - |
| Heating | 10.8 | 32.5 | 386 | 0.0 | 386.0 | 0.0 | 0 | 187,170,647 | 0 | | 0 | 41,036,813 | 0 | - |
| Heating | 8.6 | 27.5 | 191 | 0.0 | 191.0 | 0.0 | 0 | 104,339,012 | 0 | | 0 | 22,876,132 | 0 | - |
| Heating | 7.2 | 22.5 | 102 | 0.0 | 102.0 | 0.0 | 0 | 61,981,019 | 0 | | 0 | 13,589,222 | 0 | - |
| Heating | 5.4 | 17.5 | 41 | 0.0 | 41.0 | 0.0 | 0 | 27,430,499 | 0 | | 0 | 6,014,085 | 0 | - |
| Heating | 4.5 | 12.5 | 1 | 0.0 | 1.0 | 0.0 | 0 | 730,416 | 0 | | 0 | 160,142 | 0 | - |
| Subtotal = | | | **8,760** | **1,731** | **6,051** | **0** | **141,706,852** | **1,558,910,403** | **0** | **btu** | **187,833,530** | **341,788,176** | **0** | **279,620,090** |

| | Conduction | Infiltration | Solar | |
|---|---|---|---|---|
| Cooling Load = | ( 141706852 ) + ( | 187833530 ) + ( | 279,620,090 ) = | **609,160,472 btu** |
| | Cooling Load | Btu/ton | kW/ton | |
| Cooling Energy = | ( 609160472 )/( | 12000 ) * ( | 0.80 ) = | **40,611 kWh** |
| | Cooling Energy | Cooling Cost | | |
| Cooling Energy Cost = | ( 40610.70 ) x ( | $0.071 ) = | | **$ 2,870.22** |

**Proposed**

| Operation | OA Enthalpy | OA Temp | Total Hours | Cooling Occupied Hours | Heating Occupied Hours | Heating Unoccupied Hours | Cooling Occupied Conduction | Heating Occupied Conduction | Heating Unoccupied Conduction | Cooling Occupied Infiltration | Heating Occupied Infiltration | Heating Unoccupied Infiltration | Solar Cooling Load |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Cooling | 42.372 | 97.5 | 10 | 10.0 | 0.0 | 0.0 | 2,884,837 | 0 | 0 | 1,892,102 | 0 | 0 | 646,522 |
| Cooling | 39.715 | 92.5 | 39 | 39.0 | 0.0 | 0.0 | 8,857,062 | 0 | 0 | 6,216,940 | 0 | 0 | 2,521,435 |
| Cooling | 38.089 | 87.5 | 215 | 215.0 | 0.0 | 0.0 | 35,630,800 | 0 | 0 | 30,353,929 | 0 | 0 | 13,900,219 |
| Cooling | 35.853 | 82.5 | 557 | 557.0 | 0.0 | 0.0 | 58,120,249 | 0 | 0 | 64,668,109 | 0 | 0 | 36,011,264 |
| Cooling | 33.985 | 77.5 | 910 | 910.0 | 0.0 | 0.0 | 39,098,742 | 0 | 0 | 86,594,552 | 0 | 0 | 58,833,484 |
| Heating | 31.583 | 72.5 | 978 | 0.0 | 0.0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 | - |
| Heating | 28.27 | 67.5 | 971 | 0.0 | 971.0 | 0.0 | 0 | 53,639,545 | 0 | 0 | 11,760,369 | 0 | - |
| Heating | 24.533 | 62.5 | 1101 | 0.0 | 1101.0 | 0.0 | 0 | 128,399,776 | 0 | 0 | 28,151,410 | 0 | - |
| Heating | 21.544 | 57.5 | 655 | 0.0 | 655.0 | 0.0 | 0 | 116,590,360 | 0 | 0 | 25,562,217 | 0 | - |
| Heating | 18.652 | 52.5 | 581 | 0.0 | 581.0 | 0.0 | 0 | 139,079,809 | 0 | 0 | 30,492,987 | 0 | - |
| Heating | 16.338 | 47.5 | 561 | 0.0 | 561.0 | 0.0 | 0 | 168,726,108 | 0 | 0 | 36,992,882 | 0 | - |
| Heating | 14.555 | 42.5 | 781 | 0.0 | 781.0 | 0.0 | 0 | 282,830,598 | 0 | 0 | 62,010,077 | 0 | - |
| Heating | 12.606 | 37.5 | 680 | 0.0 | 680.0 | 0.0 | 0 | 287,992,614 | 0 | 0 | 63,141,839 | 0 | - |
| Heating | 10.771 | 32.5 | 386 | 0.0 | 386.0 | 0.0 | 0 | 187,170,647 | 0 | 0 | 41,036,813 | 0 | - |
| Heating | 8.5873 | 27.5 | 191 | 0.0 | 191.0 | 0.0 | 0 | 104,339,012 | 0 | 0 | 22,876,132 | 0 | - |
| Heating | 7.2196 | 22.5 | 102 | 0.0 | 102.0 | 0.0 | 0 | 61,981,019 | 0 | 0 | 13,589,222 | 0 | - |
| Heating | 5.3544 | 17.5 | 41 | 0.0 | 41.0 | 0.0 | 0 | 27,430,499 | 0 | 0 | 6,014,085 | 0 | - |
| Heating | 4.4951 | 12.5 | 1 | 0.0 | 1.0 | 0.0 | 0 | 730,416 | 0 | 0 | 160,142 | 0 | - |
| Subtotal = | | | **8,760** | **1,731** | **6,051** | **0** | **141,706,852** | **1,558,910,403** | **0 btu** | **187,833,530** | **341,788,176** | **0** | **111,912,924** |

| | Conduction | Infiltration | Solar | |
|---|---|---|---|---|
| Cooling Load = | ( 141706852 ) + ( | 187833530 ) + ( | 111,912,924 ) = | **441,453,305 btu** |
| | Cooling Load | Btu/ton | kW/ton | |
| Cooling Energy = | ( 441453305 )/( | 12000 ) * ( | 0.80 ) = | **29,430 kWh** |
| | Cooling Energy | Cooling Cost | | |
| Cooling Energy Cost = | ( 29430.22 ) x ( | $0.071 ) = | | **$ 2,080.02** |

**Summary**

| | | | |
|---|---|---|---|
| **EXISTING COOLING ENERGY** | **40,611 kWh** | **$** | **2,870.22** |
| **PROPOSED COOLING ENERGY** | **29,430 kWh** | **$** | **2,080.02** |
| **COOLING ENERGY SAVINGS** | **11,180 kWh** | **$** | **790.20** |

**27.5% of existing**

**Comments**

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**BE-4: Install Blinds or Shades - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Roller Shades, mylar, dbl reflective | 12,922 | Sqft. | $ 0.96 | $ 0.45 | $ - | $ 12,169 | $ 4,053 | $ - | $ 16,222 | From Table Below Not sure how old |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 16,222 | Subtotal |
| $ 3,244.48 | 20% Contingency |
| $ 2,433.36 | 15% O&P |
| **$ 21,900** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**M-1: Boiler Replacement w/ Condensing, Incl. Hot Water Temperature Reset**

## ECM Description Summary


*The main terminal at Norfolk airport was constructed in 1971, the boilers were upgraded in 2016. The existing boilers are 2 - 10,000 MBH dual fuel natural gas/fuel oil #2 fire-tube boilers with a name plate efficiency of 82%.This measure proposes replacing one of the existing boiler with 1 - 6000 MBH and 1 - 2500 MBH Condensing natural gas boilers and implement a HW reset. The smaller boiler will be utilized for lower loads and Summer DHW production.*

### Utility Costs

| | | |
|---|---|---|
| Blended Electric Rate | $0.07 | / kWh |
| Blended Natural Gas Rate | $0.34 | / Therm |

| INPUTS - BOILER AND HHW PIPING | | |
|---|---|---|
| Boiler Input | 10,206 | MBH |
| Boiler Output | 8,369 | MBH |
| Nameplate Eff. | 82.0% | |
| Blended Natural Gas Rate | $0.34 | / Therm |
| Heating On Temperature [4] | 65 | °F |
| Building Balance Point | 55 | °F |
| Existing Average HHW Setpoint High | 180 | °F |
| Existing HHW Setpoint Low | 180 | °F |
| Proposed Avg HHW Setpoint Low | 120 | °F |

| INPUTS - PROPOSED BOILER EFFICIENCY DATA | | | | | | |
|---|---|---|---|---|---|---|
| RWT (F) | % Firing Rate | | | | | |
| | 100% | 80% | 60% | 40% | 20% | 8% |
| 80 | 95.6% | 95.9% | 96.5% | 97.2% | 98.0% | 98.2% |
| 100 | 93.4% | 94.0% | 94.2% | 94.6% | 95.0% | 95.1% |
| 120 | 88.8% | 88.9% | 89.0% | 89.8% | 89.9% | 90.2% |
| 140 | 87.3% | 87.3% | 87.6% | 87.7% | 87.7% | 87.9% |
| 160 | 86.5% | 86.7% | 86.9% | 87.0% | 87.0% | 87.0% |




**SAVINGS ANALYSIS**

| Local Temperature Bin Data | | | | Existing Conditions | | | | | | | | Proposed Conditions | | | | | | | | SAVINGS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Avg. DB Bin Temp °F | Boiler On? | Bin Hours | Heating Bin HOURS | Leaving Water Temp | Delta T | Return Water Temp | Total Boiler Heat Load ( MBH ) | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MMBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Firing Rate | Existing Utility Use Therms/Yr | Leaving Water Temp | Delta T | Return Water Temp | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Delta T and Firing Rate | Existing Utility Use Therms/Yr | Savings Utility Use Therms/Yr |
| 92.5 | NO | 10 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 87.5 | NO | 39 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 82.5 | NO | 215 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 77.5 | NO | 557 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 72.5 | NO | 910 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 67.5 | NO | 978 | 0 | 180 | 15 | 165 | 603 | 603 | 0 | 8% | 82.0% | 0 | 120 | 15 | 105 | 603 | 0 | 8% | 93.8% | 0 | 0 |
| 62.5 | YES | 971 | 971 | 180 | 15 | 165 | 1,180 | 1,180 | 1,146 | 16% | 82.0% | 13,973 | 120 | 15 | 105 | 1,180 | 1,146 | 16% | 93.6% | 12,239 | 1,734 |
| 57.5 | YES | 1101 | 1,101 | 180 | 15 | 165 | 1,757 | 1,757 | 1,935 | 23% | 82.0% | 23,598 | 120 | 15 | 105 | 1,757 | 1,935 | 23% | 93.3% | 20,738 | 2,860 |
| 52.5 | YES | 655 | 655 | 180 | 15 | 165 | 2,335 | 2,335 | 1,529 | 31% | 82.0% | 18,651 | 123 | 15 | 108 | 2,335 | 1,529 | 31% | 92.5% | 16,536 | 2,115 |
| 47.5 | YES | 581 | 581 | 180 | 15 | 165 | 2,912 | 2,912 | 1,692 | 39% | 82.0% | 20,636 | 129 | 15 | 114 | 2,912 | 1,692 | 39% | 91.0% | 18,605 | 2,031 |
| 42.5 | YES | 561 | 561 | 180 | 15 | 165 | 3,490 | 3,490 | 1,958 | 46% | 82.0% | 23,876 | 136 | 15 | 121 | 3,490 | 1,958 | 46% | 88.9% | 22,032 | 1,844 |
| 37.5 | YES | 781 | 781 | 180 | 15 | 165 | 4,067 | 4,067 | 3,177 | 54% | 82.0% | 38,739 | 142 | 15 | 127 | 4,067 | 3,177 | 54% | 88.0% | 36,090 | 2,649 |
| 32.5 | YES | 680 | 680 | 180 | 15 | 165 | 4,645 | 4,645 | 3,158 | 62% | 82.0% | 38,518 | 148 | 15 | 133 | 4,645 | 3,158 | 62% | 87.4% | 36,136 | 2,382 |
| 27.5 | YES | 386 | 386 | 180 | 15 | 165 | 5,222 | 5,222 | 2,016 | 69% | 82.0% | 24,583 | 155 | 15 | 140 | 5,222 | 2,016 | 69% | 87.3% | 23,091 | 1,492 |
| 22.5 | YES | 191 | 191 | 180 | 15 | 165 | 5,800 | 5,800 | 1,108 | 77% | 82.0% | 13,509 | 161 | 15 | 146 | 5,800 | 1,108 | 77% | 87.4% | 12,679 | 830 |
| 17.5 | YES | 102 | 102 | 180 | 15 | 165 | 6,377 | 6,377 | 650 | 85% | 82.0% | 7,933 | 167 | 15 | 152 | 6,377 | 650 | 85% | 87.2% | 7,459 | 473 |
| 12.5 | YES | 41 | 41 | 180 | 15 | 165 | 6,955 | 6,955 | 285 | 92% | 82.0% | 3,477 | 174 | 15 | 159 | 6,955 | 285 | 92% | 86.7% | 3,289 | 188 |
| 7.5 | YES | 1 | 1 | 180 | 15 | 165 | 7,532 | 7,532 | 8 | 100% | 82.0% | 92 | 180 | 15 | 165 | 7,532 | 8 | 100% | 85.4% | 88 | 4 |
| **Totals** | | **8,760** | **6,051** | | | | | | **18,662** | | **82.0%** | **227,584** | | | | | **18,662** | | **89.3%** | **208,981** | **18,603** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

**M-1: Boiler Replacement w/ Condensing, Incl. Hot Water Temperature Reset - Cost**

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| **6000 MBH Condensing Boiler** | 1 | EA | $ 96,000 | $ 2,500 | | $ 94,176 | $ 1,743 | $ - | $ 95,919 | |
| **2500 MBH Condensing Boiler** | 1 | EA | $ 46,500 | $ 2,000 | | $ 45,617 | $ 1,394 | $ - | $ 47,011 | |
| **Condensing Boiler Electrical** | 1 | LS | $ 500 | $ 1,000 | $ - | $ 491 | $ 697 | $ - | $ 1,188 | |
| **Venting Kit** | 3 | EA | $ 450 | $ 650 | $ - | $ 440 | $ 785 | $ - | $ 1,225 | |
| **Miscellaneous Piping and Valves** | 1 | LS | $ 500 | $ 500 | $ - | $ 489 | $ 604 | $ - | $ 1,093 | |
| **Demolition** | 1 | LS | $ - | $ 5,000 | $ - | $ - | $ 3,485 | $ - | $ 3,485 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 149,919 | Subtotal |
| $ 29,984 | 20% Contingency |
| $ 22,488 | 15% O&P |
| **$ 202,390** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**M-2: Install Premium Efficiency Motors**

| Demand Cost |
|---|
| $/kW-month |
| $ 10.47 |

| Energy Cost |
|---|
| $/kWh |
| $ 0.05 |

| Norfolk, VA Multipliers | | |
|---|---|---|
| Material | Labor | Equipment |
| 0.98 | 0.70 | 0.86 |

**ECM Description Summary**

*The fan motor below have been reviewed for replacement with premium efficiency equivalent motors. By replacing the existing motors with premium efficient models the overall electrical energy consumption can be reduced.*

**Savings Analysis**

**Cost Estimates**

| | | | | | | | | New | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Existing | Load | Existing | Existing | New | Load | New | New | Demand | Demand | Annual | kWh | $ kWh | Total $ | Estimated | Payback | Unit Costs | | | Subtotal Costs | | | | |
| # | Description | Location | HP | Factor | Efficiency | kW | $HP_b$ | Factor | Efficiency | kW | Savings | Savings $ | Hours | Savings | Savings | Savings | Cost | Years | Materials | Labor | Equipment | Materials | Labor | Equipment | Total Cost | Remarks |
| 1 | AHU-4 | | 15 | 0.9 | 91.2% | 11.0 | 15.0 | 0.9 | 91.2% | 11.0 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | Does not run anymore |
| 2 | AHU-5 | | 7.5 | 0.9 | 91.7% | 5.5 | 7.5 | 0.9 | 91.7% | 5.5 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 3 | AHU-7 | | 15 | 0.9 | 89.5% | 11.2 | 15.0 | 0.9 | 91.7% | 11.0 | 0.270 | $ 34 | 8,760 | 2,364 | $ 109 | $ 143 | $ 1,769 | 12.3 | $ 1,700 | $ 146 | $ - | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| 4 | AHU-8 | | 7.5 | 0.9 | 89.5% | 5.6 | 7.5 | 0.9 | 91.7% | 5.5 | 0.135 | $ 17 | 8,760 | 1,182 | $ 55 | $ 72 | $ 1,058 | 14.8 | $ 1,000 | $ 111 | $ - | $ 981 | $ 77 | $ - | $ 1,058 | |
| 5 | AHU-10 | | 10 | 0.9 | 91.7% | 7.3 | 10.0 | 0.9 | 91.7% | 7.3 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 6 | AHU-11 | | 30 | 0.9 | 93.6% | 21.5 | 30.0 | 0.9 | 93.6% | 21.5 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 7 | AHU-12 | | 30 | 0.9 | 93.6% | 21.5 | 30.0 | 0.9 | 93.6% | 21.5 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 8 | AHU-13 | | 30 | 0.9 | 93.6% | 21.5 | 30.0 | 0.9 | 93.6% | 21.5 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 9 | AHU-16 | | 30 | 0.9 | 92.4% | 21.8 | 30.0 | 0.9 | 92.4% | 21.8 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 10 | Tunnel Exhaust-1 | | 15 | 0.9 | 91.0% | 11.1 | 15.0 | 0.9 | 91.0% | 11.1 | 0.000 | $ - | 8,760 | - | $ - | $ - | $ - | #DIV/0! | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| 11 | Tunnel Exhaust-2 | | 15 | 0.9 | 89.5% | 11.2 | 15.0 | 0.9 | 91.7% | 11.0 | 0.270 | $ 34 | 8,760 | 2,364 | $ 109 | $ 143 | $ 1,769 | 12.3 | $ 1,700 | $ 146 | $ - | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| 12 | Tunnel Exhaust-3 | | 15 | 0.9 | 91.0% | 11.1 | 15.0 | 0.9 | 91.7% | 11.0 | 0.084 | $ 11 | 8,760 | 740 | $ 34 | $ 45 | $ - | - | $ 1,700 | $ 146 | $ - | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| 13 | Tunnel Exhaust-4 | | 15 | 0.9 | 91.0% | 11.1 | 15.0 | 0.9 | 91.7% | 11.0 | 0.084 | $ 11 | 8,760 | 740 | $ 34 | $ 45 | $ - | - | $ 1,700 | $ 146 | $ - | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| | | Total | **235** | | | **171.5** | **235** | | | **137.7** | **0.40** | **$ 51** | | **3,546** | **$ 164** | **$ 215** | **$ 2,828** | 13.2 | | | | | | | | |

Notes

a Existing and new efficiencies should be entered if known. If not known, use provided curve fit based on "DOE Survey Installed Average" and NEMA Premium values, respectively.

b Same as existing HP unless resized to better match load

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## M-3A: Install Variable Speed Drives - AHU-37

**ECM Description Summary**

*AHU's supplies constant volume heated air to the Bridge Area. This is the only unit in the Main Terminal that has 3-way valves. The fan motor will also be replaced with a premium efficiency motor. Control strategy is to program the EMCS system to permit the AHU fan to ramp speed linearly between 100% and 50% as OAT varies between the design heating load and building balance point. System static pressure will be permitted to float with fan speed. Pressure will not be controlled or monitored.*

| UNIT | HP | Existing Motor Eff (Note 1) | New Motor Eff (Note 1) | Existing Motor kW | New Motor kW | | |
|---|---|---|---|---|---|---|---|
| AHU-37 SA | 15.0 | 91.0% | 93.6% | 9.84 | 9.56 | | |
| AHU-37 RA | 7.5 | 91.0% | 93.6% | 4.92 | 4.78 | | |
| | | | | 14.76 | 14.35 | VFD Eff. (CC) | 98.5% |

| Building Balance Point |
|---|
| 55.0 |

**Utility Costs**

| | |
|---|---|
| Blended Electric Rate | $0.07 / kWh |
| Blended Natural Gas Rate | $0.03 / Therm |

| OAT - DB Avg Temp F | Bin Hours | Occupied Hours in Bin | AHU Hours in Bin | Existing Fan kW | Existing Fan kWh | Fan Load % | Proposed Fan kW | Speed efficiency % | Proposed Fan kWh | Savings Fan kWh |
|---|---|---|---|---|---|---|---|---|---|---|
| (A) | (B) | (C ) | (D) | (F) | (F) | (E) | (G) | (H) | (I) | (J) |
| 102.5 | 0 | 0 | 0 | 14.8 | 0 | 100% | 14.56 | 99.0% | 0 | 0 |
| 97.5 | 10 | 10 | 10 | 14.8 | 148 | 100% | 14.56 | 99.0% | 147 | 0 |
| 92.5 | 39 | 39 | 39 | 14.8 | 575 | 95% | 12.44 | 100.0% | 485 | 90 |
| 87.5 | 215 | 215 | 215 | 14.8 | 3,173 | 90% | 10.53 | 100.0% | 2263 | 909 |
| 82.5 | 557 | 557 | 557 | 14.8 | 8,219 | 85% | 8.82 | 100.0% | 4915 | 3,304 |
| 77.5 | 910 | 910 | 910 | 14.8 | 13,428 | 79% | 7.31 | 99.5% | 6689 | 6,739 |
| 72.5 | 978 | 978 | 978 | 14.8 | 14,431 | 74% | 5.99 | 98.0% | 5978 | 8,453 |
| 67.5 | 971 | 971 | 971 | 14.8 | 14,328 | 69% | 4.83 | 95.8% | 4901 | 9,427 |
| 62.5 | 1,101 | 1,101 | 1,101 | 14.8 | 16,246 | 64% | 3.84 | 92.9% | 4548 | 11,698 |
| 57.5 | 655 | 655 | 655 | 14.8 | 9,665 | 59% | 2.99 | 89.3% | 2191 | 7,474 |
| 52.5 | 581 | 581 | 581 | 14.8 | 8,573 | 52% | 2.08 | 83.7% | 1445 | 7,129 |
| 47.5 | 561 | 561 | 561 | 14.8 | 8,278 | 57% | 2.67 | 87.6% | 1710 | 6,568 |
| 42.5 | 781 | 781 | 781 | 14.8 | 11,524 | 61% | 3.37 | 91.1% | 2887 | 8,638 |
| 37.5 | 680 | 680 | 680 | 14.8 | 10,034 | 66% | 4.17 | 94.0% | 3018 | 7,016 |
| 32.5 | 386 | 386 | 386 | 14.8 | 5,696 | 70% | 5.09 | 96.3% | 2041 | 3,655 |
| 27.5 | 191 | 191 | 191 | 14.8 | 2,818 | 75% | 6.14 | 98.2% | 1195 | 1,623 |
| 22.5 | 102 | 102 | 102 | 14.8 | 1,505 | 80% | 7.33 | 99.5% | 751 | 754 |
| 17.5 | 41 | 41 | 41 | 14.8 | 605 | 84% | 8.66 | 100.0% | 355 | 250 |
| 12.5 | 1 | 1 | 1 | 14.8 | 15 | 89% | 10.14 | 100.0% | 10 | 5 |
| 7.5 | 0 | 0 | 0 | 14.8 | 0 | 93% | 11.78 | 100.0% | 0 | 0 |
| 2.5 | 0 | 0 | 0 | 14.8 | 0 | 98% | 13.59 | 99.6% | 0 | 0 |
| -2.5 | 0 | 0 | 0 | 14.8 | 0 | 100% | 14.56 | 99.0% | 0 | 0 |
| -7.5 | 0 | 0 | 0 | 14.8 | 0 | 100% | 14.56 | 99.0% | 0 | 0 |
| **TOTALS** | | **8,760** | **8,760** | **339** | **129,263** | | | | **45,529** | **83,734** |

Notes:

1) Existing motor power based on operation with existing motor efficiency, operating at 80% load factor when at full load. Formula: Motor HP x 0.746 x 0.8 / Exist. Motor Eff., New motor power is based on same formula using the new motor efficiency.
2) Weather data from NOAA for Concord, MA
3) Occupied & AHU Bin Hours are based upon existing schedule.
4) The required VFD motor power draw is based on a 3.0 power relationship to load, since system static pressure will not be controlled.

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**M-3A: Install Variable Speed Drives - AHU-37 - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| VFD 15Hp | 15 | 1 | ea. | $ 3,825 | $ 1,050 | | $ 3,752 | $ 732 | $ - | $ 4,484 | **26 29 23.10 0140** |
| Motor 15 Hp | 15 | 1 | ea. | $ 1,700 | $ 146 | | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| Electrical - misc. | | 1 | ls | $ 250 | $ 100 | | $ 245 | $ 70 | $ - | $ 315 | |
| VFD 7.5Hp | 7.5 | 1 | ea. | $ 2,700 | $ 695 | | $ 2,649 | $ 484 | $ - | $ 3,133 | **26 29 23.10 0120** |
| Motor 7.5 Hp | 7.5 | 1 | ea. | $ 1,000 | $ 111 | | $ 981 | $ 77 | $ - | $ 1,058 | |
| Electrical - misc. | | 1 | ls | $ 1,000 | $ 500 | | $ 981 | $ 349 | $ - | $ 1,330 | |
| Programming | | 2 | ea. | $ 500 | $ 2,000 | | $ 981 | $ 2,788 | $ - | $ 3,769 | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 15,859 | Subtotal |
| $ 3,172 | 20% Contingency |
| $ 2,378.79 | 15% O&P |
| **$ 21,409** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## M-3B: Install Variable Speed Drives - AHU-3,4,5,7,8,10,11,12,13,16,34,37

**ECM Description Summary**

*AHU's supplies constant volume tempered air to areas. The fan motor will also be replaced with a premium efficiency motor. Control strategy is to program the BMS to permit the AHU fan to ramp speed linearly between 100% and 50% as OAT varies between the design heating load and respective unit's zone temperatures. System static pressure will be permitted to float with fan speed to provide at least a minimum building pressure. For all Multizone system there are a mixture of either mixing boxes or VAV boxes that's dampers will be modulated with static pressure setpoint.*

| UNIT | HP | Existing Motor Eff (Note 1) | New Motor Eff (Note 1) | Existing Motor kW | New Motor kW | | |
|---|---|---|---|---|---|---|---|
| AHU-11 | 30.0 | 92.4% | 93.6% | 19.38 | 19.13 | | |
| AHU-12 | 30.0 | *93.6%* | 93.6% | 19.13 | 19.13 | | |
| AHU-13 | 30.0 | 93.6% | 93.6% | 19.13 | 19.13 | | |
| AHU-16 | 30.0 | 92.4% | 93.6% | 19.38 | 19.13 | | |
| AHU-34 | 20.0 | *93.6%* | 93.6% | 12.75 | 12.75 | | |
| AHU-37 | 15.0 | *93.6%* | 93.6% | 9.56 | 9.56 | | |
| AHU-03 | 25.0 | *90.0%* | 93.6% | 16.58 | 15.94 | | |
| AHU-04 | 10.0 | *90.0%* | 93.6% | 6.63 | 6.38 | | |
| AHU-05 | 7.5 | *90.0%* | 93.6% | 4.97 | 4.78 | | |
| AHU-07 | 10.0 | 89.5% | 93.6% | 6.67 | 6.38 | | |
| AHU-08 | 7.5 | 88.5% | 93.6% | 5.06 | 4.78 | | |
| AHU-10 | 10.0 | 91.7% | 93.6% | 6.51 | 6.38 | | |
| | | | | 145.74 | 143.46 | **VFD Eff. (CC)** | 98.5% |

| Building Balance Point |
|---|
| 55.0 |

**Utility Costs**

| | |
|---|---|
| Blended Electric Rate | $0.07 / kWh |
| Blended Natural Gas Rate | $0.03 / Therm |

| OAT - DB Avg Temp F (A) | Bin Hours (B) | Occupied Hours in Bin (C ) | AHU Hours in Bin (D) | Existing Fan kW (F) | Existing Fan kWh (F) | Fan Load % (E) | Proposed Fan kW (G) | Speed efficiency % (H) | Proposed Fan kWh (I) | Savings Fan kWh (J) |
|---|---|---|---|---|---|---|---|---|---|---|
| 102.5 | 0 | 0 | 0 | 145.7 | 0 | 93% | 117.84 | 100.0% | 0 | 0 |
| 97.5 | 10 | 10 | 10 | 145.7 | 1,457 | 89% | 101.42 | 100.0% | 1014 | 443 |
| 92.5 | 39 | 39 | 39 | 145.7 | 5,684 | 84% | 86.61 | 100.0% | 3378 | 2,306 |
| 87.5 | 215 | 215 | 215 | 145.7 | 31,335 | 80% | 73.31 | 99.5% | 15836 | 15,499 |
| 82.5 | 557 | 557 | 557 | 145.7 | 81,178 | 75% | 61.44 | 98.2% | 34853 | 46,326 |
| 77.5 | 910 | 910 | 910 | 145.7 | 132,625 | 70% | 50.94 | 96.3% | 48112 | 84,513 |
| 72.5 | 978 | 978 | 978 | 145.7 | 142,536 | 66% | 41.70 | 94.0% | 43404 | 99,132 |
| 67.5 | 971 | 971 | 971 | 145.7 | 141,516 | 61% | 33.65 | 91.1% | 35888 | 105,627 |
| 62.5 | 1,101 | 1,101 | 1,101 | 145.7 | 160,462 | 57% | 26.72 | 87.6% | 33568 | 126,894 |
| 57.5 | 655 | 655 | 655 | 145.7 | 95,461 | 52% | 20.80 | 83.7% | 16286 | 79,175 |
| 52.5 | 581 | 581 | 581 | 145.7 | 84,676 | 52% | 20.80 | 83.7% | 14446 | 70,230 |
| 47.5 | 561 | 561 | 561 | 145.7 | 81,761 | 57% | 26.72 | 87.6% | 17104 | 64,657 |
| 42.5 | 781 | 781 | 781 | 145.7 | 113,825 | 61% | 33.65 | 91.1% | 28866 | 84,959 |
| 37.5 | 680 | 680 | 680 | 145.7 | 99,105 | 66% | 41.70 | 94.0% | 30179 | 68,926 |
| 32.5 | 386 | 386 | 386 | 145.7 | 56,256 | 70% | 50.94 | 96.3% | 20408 | 35,849 |
| 27.5 | 191 | 191 | 191 | 145.7 | 27,837 | 75% | 61.44 | 98.2% | 11951 | 15,885 |
| 22.5 | 102 | 102 | 102 | 145.7 | 14,866 | 80% | 73.31 | 99.5% | 7513 | 7,353 |
| 17.5 | 41 | 41 | 41 | 145.7 | 5,975 | 84% | 86.61 | 100.0% | 3551 | 2,425 |
| 12.5 | 1 | 1 | 1 | 145.7 | 146 | 89% | 101.42 | 100.0% | 101 | 44 |
| 7.5 | 0 | 0 | 0 | 145.7 | 0 | 93% | 117.84 | 100.0% | 0 | 0 |
| 2.5 | 0 | 0 | 0 | 145.7 | 0 | 98% | 135.94 | 99.6% | 0 | 0 |
| -2.5 | 0 | 0 | 0 | 145.7 | 0 | 100% | 145.65 | 99.0% | 0 | 0 |
| -7.5 | 0 | 0 | 0 | 145.7 | 0 | 100% | 145.65 | 99.0% | 0 | 0 |
| **TOTALS** | | **8,760** | **8,760** | **3,352** | **1,276,701** | | | | **366,457** | **910,244** |

Notes:

1) Existing motor power based on operation with existing motor efficiency, operating at 80% load factor when at full load. Formula: Motor HP x 0.746 x 0.8 / Exist. Motor Eff., New motor power is based on same formula using the new motor efficiency.
2) Weather data from NOAA for Concord, MA
3) Occupied & AHU Bin Hours are based upon existing schedule.
4) The required VFD motor power draw is based on a 3.0 power relationship to load, since system static pressure will not be controlled.

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**M-3B: Install Variable Speed Drives - AHU-3,4,5,7,8,10,11,12,13,16,34,37 - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | | |
| 30 HP VFD | 30 | 4 | EA | $ 6,950 | $ 1,400 | | $ 27,272 | $ 3,903 | $ - | $ 31,175 | |
| 30 HP Motor | 30 | 4 | EA | $ 3,250 | $ 194 | | $ 12,753 | $ 541 | $ - | $ 13,294 | |
| 25 HP VFD | 25 | 1 | EA | $ 5,550 | $ 1,400 | | $ 5,445 | $ 976 | $ - | $ 6,420 | |
| 25 HP Motor | 25 | 1 | EA | $ 3,300 | $ 186 | | $ 3,237 | $ 130 | $ - | $ 3,367 | |
| 20 HP VFD | 20 | 1 | EA | $ 4,525 | $ 1,050 | | $ 4,439 | $ 732 | $ - | $ 5,171 | |
| 20 HP Motor | 20 | 1 | EA | $ 2,300 | $ 179 | | $ 2,256 | $ 125 | $ - | $ 2,381 | |
| 15 HP VFD | 15 | 1 | EA | $ 3,825 | $ 1,050 | | $ 3,752 | $ 732 | $ - | $ 4,484 | |
| 15 HP Motor | 15 | 1 | EA | $ 1,700 | $ 146 | | $ 1,668 | $ 102 | $ - | $ 1,769 | |
| 10 HP VFD | 10 | 3 | EA | $ 2,975 | $ 695 | | $ 8,755 | $ 1,453 | $ - | $ 10,209 | |
| 10 HP Motor | 10 | 3 | EA | $ 1,425 | $ 116 | | $ 4,194 | $ 243 | $ - | $ 4,436 | |
| 7.5 HP VFD | 7.5 | 2 | EA | $ 2,700 | $ 695 | | $ 5,297 | $ 969 | $ - | $ 6,266 | |
| 7.5 HP Motor | 7.5 | 2 | EA | $ 1,000 | $ 111 | | $ 1,962 | $ 155 | $ - | $ 2,117 | |
| Electrical - misc. | | 12 | EA | $ 1,000 | $ 1,000 | | $ 11,772 | $ 8,364 | $ - | $ 20,136 | |
| Programming | | 12 | EA | $ 500 | $ 2,000 | | $ 5,886 | $ 16,728 | $ - | $ 22,614 | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 133,840 | Subtotal |
| $ 26,768 | 20% Contingency |
| $ 20,075.96 | 15% O&p |
| **$ 180,684** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## M-7: Duct Sealing

**ECM Description Summary**

*Most of the ductwork in Norfolk airport was originally installed in 1971 with new breakoffs installed over the years during renovations. From the site walkthrough it appears these original ducts are leaking air. Leaking air causes an increase in energy usage and a loss in heating/cooling effectiveness as the units are now heating/cooling space that is not designed to be temperature controlled. This ECM evaluates the benefits of sealing the ductwork on the equipment below.*

| Assumptions | | |
|---|---|---|
| **Data** | **Value** | **Units** |
| **Existing CFM Leakage** | 1.5% | % |
| **Proposed CFM Leakage** | 0.5% | % |
| **Heating Setpoint** | 72 | °F |
| **SA Enthalpy** | 26 | Btu/lb |
| **Heating "ON"** | 55 | °F |
| **Heating Eff** | 83% | % |
| **Outside Air** | 24% | % |
| **Average Heating Temp** | 72 | °F |

| Provided/Collected Data | | |
|---|---|---|
| **Data** | **Value** | **Units** |
| **Average Cooling Temp** | 74 | °F |
| **Average Enthalpy** | 26 | Btu/lb |
| **Cooling Eff** | 0.8 | kW/Ton |

| Energy/Cost Savings | | |
|---|---|---|
| **Data** | **Value** | **Savings ($)** |
| **Electric (kWh)** | 1,653 | $ 116.83 |
| **Natural Gas (Therms)** | 288 | $ 97.30 |
| **Total** | | $ 214.13 |

| Existing Equipment List | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location Information | | | Unit Information | | | | | Duct Leakage Reduction | |
| **2005 Survey Tag** | **Location** | **Area Served** | **Supply Fan CFM** | **OA CFM** | **Motor HP** | **Efficiency** | **kW** | **Existing CFM Leakage** | **Proposed CFM Leakage** |
| AHU-16 | | CON B Section G / Gate 20 | 19,030 | 6,000 | 30 | 92.4% | 21.8 | 285 | 95 |
| AHU-18 | | CON B Section K / Gate 30 | 12,320 | 2,250 | 25 | 93.6% | 17.9 | 185 | 62 |
| AHU-19 | | CON B Section J / Gate 29 | 19,680 | 3,600 | 40 | 94.1% | 28.5 | 295 | 98 |
| AHU-20 | | CON B Section K | 20,270 | 3,710 | 50 | 94.1% | 35.7 | 304 | 101 |
| AHU-11 | | CON A Section L/M | 18,990 | 6,000 | 30 | 92.4% | 21.8 | 285 | 95 |
| **Total** | | | 90,290 | 21,560 | | | | 1,354 | 451 |

| A | B | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Data | | | | | Existing | | | | | Proposed | | | | | Savings | |
| **Avg. DB Bin Temp (°F)** | **OA Enthalpy (Btu/lb)** | **Occupied Bin (HOURS)** | **Mixed Air Temp (°F)** | **Mixed Air Enthalpy (Btu/lb)** | **SA (CFM)** | **Cooling Load (MBH)** | **Heating Load (MBH)** | **Cooling (kWh)** | **Heating (Therms)** | **Derated S.A. (CFM)** | **Cooling Load (MBH)** | **Heating Load (MBH)** | **Cooling (kWh)** | **Heating (Therms)** | **Cooling (kWh)** | **Heating (Therms)** |
| 97.5 | 42.4 | 10 | 80 | 29.5 | 1,354 | 25 | - | 16 | - | 451 | 8 | - | 5 | - | 11 | - |
| 92.5 | 39.7 | 39 | 78 | 28.9 | 1,354 | 21 | - | 54 | - | 451 | 7 | - | 18 | - | 36 | - |
| 87.5 | 38.1 | 215 | 77 | 28.5 | 1,354 | 18 | - | 263 | - | 451 | 6 | - | 88 | - | 175 | - |
| 82.5 | 35.9 | 557 | 76 | 28.0 | 1,354 | 15 | - | 559 | - | 451 | 5 | - | 186 | - | 373 | - |
| 77.5 | 34.0 | 910 | 75 | 27.5 | 1,354 | 12 | - | 749 | - | 451 | 4 | - | 250 | - | 499 | - |
| 72.5 | 31.6 | 978 | 74 | 27.0 | 1,354 | 9 | - | 577 | - | 451 | 3 | - | 192 | - | 385 | - |
| 67.5 | 28.3 | 971 | 72 | 26.2 | 1,354 | 4 | - | 261 | - | 451 | 1 | - | 87 | - | 174 | - |
| 62.5 | 24.5 | 1,101 | 71 | 25.3 | 1,354 | - | - | - | - | 451 | - | - | - | - | - | - |
| 57.5 | 21.5 | 655 | 70 | 24.6 | 1,354 | - | - | - | - | 451 | - | - | - | - | - | - |
| 52.5 | 18.7 | 581 | 67 | 23.9 | 1,354 | - | 7 | - | 48 | 451 | - | 2 | - | 16 | - | 32 |
| 47.5 | 16.3 | 561 | 66 | 23.3 | 1,354 | - | 9 | - | 58 | 451 | - | 3 | - | 19 | - | 39 |
| 42.5 | 14.6 | 781 | 65 | 22.9 | 1,354 | - | 10 | - | 97 | 451 | - | 3 | - | 32 | - | 65 |
| 37.5 | 12.6 | 680 | 64 | 22.4 | 1,354 | - | 12 | - | 99 | 451 | - | 4 | - | 33 | - | 66 |
| 32.5 | 10.8 | 386 | 63 | 22.0 | 1,354 | - | 14 | - | 64 | 451 | - | 5 | - | 21 | - | 43 |
| 27.5 | 8.6 | 191 | 61 | 21.5 | 1,354 | - | 16 | - | 36 | 451 | - | 5 | - | 12 | - | 24 |
| 22.5 | 7.2 | 102 | 60 | 21.1 | 1,354 | - | 17 | - | 21 | 451 | - | 6 | - | 7 | - | 14 |
| 17.5 | 5.4 | 41 | 59 | 20.7 | 1,354 | - | 19 | - | 9 | 451 | - | 6 | - | 3 | - | 6 |
| 12.5 | 4.5 | 1 | 58 | 20.5 | 1,354 | - | 21 | - | 0 | 451 | - | 7 | - | 0 | - | 0 |
| 7.5 | - | - | 57 | 19.4 | 1,354 | - | 23 | - | - | 451 | - | 8 | - | - | - | - |
| **Total** | | **8,760** | | | | **104** | **147** | **2,480** | **432** | | **35** | | **827** | **144** | **1,653** | **288** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Duct Sealing | 5 | EA | $ 1,500 | $ 750 | $ - | $ 7,500 | $ 3,750 | $ - | $ 11,250 | Internet Price http://homeenergypros.lbl.gov/profiles/blogs/does-aeroseal-work-an-auditors-review |
| | | | $ - | $ - | $ - | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| Cost Summary | | |
|---|---|---|
| $ 11,250 | Subtotal | |
| $ 2,250 | 20% | Contingency |
| $ 1,688 | 15% | O&P |
| **$ 15,188** | **Total** | |

**Norfolk Airport**

**CHA Project # 33370**

**Main Terminal**

## M-09: Install Premium Efficiency Elevator Motors

### ECM Description Summary

*Seven of the existing departures/main terminal elevators, listed below, have motors that are older and inefficient. This measure proposes replacing the existing elevator motors with high efficiency motors.*

| Savings Analysis | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | New | | | | | |
| | | | Existing | Load | Existing | Existing | New | Load | New | New | Demand | Annual | kWh |
| # | Description | Location | HP | Factor | Efficiency | kW | HP | Factor | Efficiency | kW | Savings | Hours | Savings |
| 1 | Elevator-1 | Departures | 50 | 0.8 | 0.800 | 37.3 | 50 | 0.8 | 0.840 | 35.5 | 1.775 | 1,460 | 2,592 |
| 2 | Elevator-2 | Departures | 25 | 0.8 | 0.800 | 18.6 | 25 | 0.8 | 0.800 | 18.6 | 0.000 | 1,460 | - |
| 3 | Elevator-3 | Departures | 50 | 0.8 | 0.800 | 37.3 | 50 | 0.8 | 0.840 | 35.5 | 1.775 | 1,460 | 2,592 |
| 4 | Elevator-4 | Departures | 50 | 0.8 | 0.800 | 37.3 | 50 | 0.8 | 0.840 | 35.5 | 1.775 | 1,460 | 2,592 |
| 5 | Elevator-5 | Departures | 30 | 0.8 | 0.740 | 24.2 | 30 | 0.8 | 0.800 | 22.4 | 1.814 | 1,460 | 2,648 |
| 6 | Elevator-6 | Concourse B | 20 | 0.8 | 0.800 | 14.9 | 20 | 0.8 | 0.800 | 14.9 | 0.000 | 1,460 | - |
| 7 | Elevator-7 | Concourse B | 20 | 0.8 | 0.8 | 14.9 | 20 | 0.8 | 0.800 | 14.9 | 0.000 | 1,460 | - |
| 8 | Elevator-8 | Customs | 20 | 0.8 | 0.72 | 16.6 | 20 | 0.8 | 0.800 | 14.9 | 1.657 | 1,460 | 2,419 |
| 9 | Elevator-9 | Customs | 50 | 0.8 | 0.72 | 41.4 | 50 | 0.8 | 0.840 | 35.5 | 5.918 | 1,460 | 8,641 |
| 10 | Elevator-10 | Customs | 50 | 0.8 | 0.8 | 37.3 | 50 | 0.8 | 0.840 | 35.5 | 1.775 | 1,460 | 2,592 |
| 11 | Elevator-11 | nerican Airline Op | ? | 0.8 | ? | 0.0 | ? | 0.8 | ? | 0.0 | 0.000 | 1,460 | - |
| 12 | Elevator-16 | Concourse A | ? | 0.8 | ? | 0.0 | ? | 0.8 | ? | 0.0 | 0.000 | 1,460 | - |
| **Total** | | | **365** | | | **279.8** | **365** | | | **263.3** | **16.49** | | **24,077** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**M-09: Install Premium Efficiency Elevator Motors - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| 50HP SUB motor | 5 | ea. | $ 1,048 | $ 750 | | $ 5,140 | $ 2,614 | $ - | $ 7,754 | Internet |
| 30HP SUB motor | 1 | ea. | $ 717 | $ 750 | | $ 703 | $ 523 | $ - | $ 1,226 | Internet |
| 25HP SUB motor | 0 | ea. | $ 643 | $ 750 | | $ - | $ - | $ - | $ - | Internet |
| 20HP SUB motor | 1 | ea. | $ 590 | $ 750 | | $ 579 | $ 523 | $ - | $ 1,102 | Internet |
| Demolition/Remove Existing Motors | 1 | ls | $ - | $ 5,000 | $ - | $ - | $ 3,485 | $ - | $ 3,485 | Eng. Est |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 13,567 | Subtotal |
| $ 2,713 | 20% Contingency |
| $ 2,035.03 | 15% O&P |
| **$ 18,315** | **Total** |

**Norfolk Airport**

**CHA Project # 33370**
**Main Terminal**

**M-10 Upgrade Escalator Controls**

## ECM Description Summary

*There are 4 escalators in this terminal. The existing escalators operate continuously with constant speed regardless of whether passengers are using them or not. This ECM evaluates installing sensors, drives and controls that will allow for energy savings for periods of lower usage or stops when no passengers are around.*

**Building Information:**

Electricity rate $0.07 $/kWh Blended

**ESCALATOR CONTROLS**

| | | |
|---|---|---|
| EXISTING CONDITIONS | | |
| Number of Escalators | 4 | |
| Average Motor Size | 7.5 | kW |
| Operating Hours | 8,760 | |
| Average Motor Load | 0.4 | |
| Existing Operating Usage | 105,120 | kWh |
| PROPOSED CONDITIONS | | |
| Reduction due to speed controls and stops for slow or no traffic | 20% | |
| Hours of slow period | 5 | |
| Operating Hours | 6,935 | |
| Proposed Operating Usage | 66,576 | kWh |
| SAVINGS | | |
| Electric Savings | 38,544 | **kWh** |

Assumptions

1 Average 3,500 passengers per day

Reduction due to controls depends on traffic volume and utilization of controls. Statistics range from 15-35 % reduction

**Norfolk Airport**

**CHA Project # 33370**
**Main Terminal**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

**M-10 Upgrade Escalator Controls**

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Drive 10HP | 4 | ea. | $ 2,975 | $ 695 | | $ 11,674 | $ 1,938 | $ - | $ 13,612 | RS Means |
| Controller, sensors | 4 | ea. | $ 5,200 | $ 1,200 | | $ 20,405 | $ 3,346 | $ - | $ 23,750 | Vendor Info |
| Labor, calibration, start up | 1 | ls | | $ 340 | | $ - | $ 237 | $ - | $ 237 | Estimate |
| Misc. | 4 | ea. | $ 450 | $ 700 | | $ 1,766 | $ 1,952 | $ - | $ 3,717 | Estimate |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 41,316 | Subtotal |
| $ 8,263 | 20% Contingency |
| $ 6,197.45 | 15% O&P |
| **$ 49,580** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## DHW-1&2A: Replace Large Electric DHW Heater Servicing The Local @ ORF w/ Condensing Gas-Fired DHW Heater

**ECM Description Summary**
*Replace Large Electric DHW Heater servicing the Local @ORF Restaurant w/ Instantaneous, Condensing, Gas-Fired DHW*

**The Local @ORF Restaurant**

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 753 | gal/day | Calculated from usage below |
| Annual Hot Water Energy Demand | 57,067 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 119 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | Per building personnel |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 819 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 57,887 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 100% | | Per Manufacturer |
| Total Annual Energy Required | 57,887 | Mbtu/yr | |
| **Total Annual Electric Required** | **16,961** | **kWh/yr** | **Electrical Savings** |
| Average Annual Electric Demand | | kW | |
| Peak Electric Demand | 27.0 | kW | Per Manufacturer's Nameplate (Demand Savings) |
| **Avg peak demand & diversity factor** | **9.0** | | **33% of peak demand (6 elements)** |
| | | | |
| New Tank Size | 120 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 826 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 57,894 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 96% | | Based on A.O Smith Cyclone Mxi BTH-500A condensing DHW Heater |
| Proposed Total Annual Energy Required | 60,306 | MBTU/yr | |
| Proposed Fuel Use | 603 | Therms/yr | Standby Losses and inefficient DHW heater eliminated |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.05 | $/kWh | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $ 1,916 | $/yr | |
| Proposed Operating Cost of DHW | $ 204 | $/yr | |
| **Annual Utility Cost Savings** | **$ 1,712** | **$/yr** | |
| **Project cost** | **$ 20,255** | **$** | |
| **Project Payback** | **11.8** | **Yrs.** | |

**Daily Hot Water Demand The Local @ORF Restaurant**

| | | | #USES PER DAY | | FULL TIME OCCUPANTS** | | | | |
|---|---|---|---|---|---|---|---|---|---|
| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | MALE | FEMALE | MALE | FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 0.75 | 0.75 | 0 | 0 | 0 | 50% | 0 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 15 | 0 | 5 | 0 | 94 | 75% | 70 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 3 | 0 | 15 | 75% | 11 |
| Dishwasher (gal per min) | 4.26 | 157.5 | 1 | 0 | 1 | 0 | 671 | 100% | 671 |
| | | | | | | **TOTAL** | 109 | | **752.8** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**DHW-1&2A: Replace Large Electric DHW Heater Servicing The Local @ ORF w/ Condensing Gas-Fired DHW Heater - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Electric DHW Heater Removal | 1 | LS | | $ 500 | | $ - | $ 349 | $ - | $ 349 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| 130 Gal Condensing Natural Gas DHW Heater | 1 | EA | $ 10,500 | $ 1,000 | | $ 10,301 | $ 697 | $ - | $ 10,998 | Could go down to 100 gal for $6200 |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Venting Kit & Roof Penetration | 1 | EA | $ 1,000 | $ 1,500 | | $ 981 | $ 1,046 | $ - | $ 2,027 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Natural Gas Piping and fittings | 100 | LF | $ 1.07 | $ 2.82 | | $ 105 | $ 197 | $ - | $ 302 | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 15,004 | Subtotal |
| $ 3,001 | 20% Contingency |
| $ 2,250.53 | 15% O&P |
| **$ 20,255** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## DHW-1&2B: Replace Small Electric DHW Heater Used in the Concourse Restaurants w/ Tankless Condensing Gas-Fired DHW Heater

**ECM Description Summary**

*Replace the Small Electric Water Heater Units Used for the Restaurants w/ Instantaneous, Condensing, Gas-Fired DHW Heater*

**Smaller Units @ Concourse A & B**

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 775 | gal/day | Calculated from table to right |
| Annual Hot Water Energy Demand | 58,734 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 50 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | Per building personnel |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.9% | | |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 574 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 59,308 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 100% | | Per Manufacturer |
| Total Annual Energy Required | 59,308 | Mbtu/yr | |
| **Total Annual Electric Required** | **17,377** | **kWh/yr** | **Electrical Savings** |
| Average Annual Electric Demand | | kW | |
| Peak Electric Demand | 9.0 | kW | Per Manufacturer's Nameplate (Demand Savings) |
| **avg peak demand & diversity factor** | **3.0** | **kW** | **33% of peak demand** |
| | | | |
| New Tank Size | 50 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.0% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.0 | MBH | |
| Annual Standby Hot Water Load | 0 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 58,734 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 80% | | Based on Navien CR180 instantaneous, condensing DHW Heater |
| Proposed Total Annual Energy Required | 73,418 | MBTU/yr | |
| Proposed Fuel Use | 734 | Therms/yr | Standby Losses and inefficient DHW heater eliminated |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.05 | $/kWh | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $ 1,181 | $/yr | |
| Proposed Operating Cost of DHW | $ 248 | $/yr | |
| **Annual Utility Cost Savings** | **$ 933** | **$/yr** | **EACH TANK** |
| **Total Annual Utility Cost Savings** | **$ 3,732** | **$/yr** | **4 tanks** |
| **Total Project cost** | **$ 11,637** | **$** | |
| **Project cost** | **$ 46,548** | **$** | |
| **Project Payback** | **12.5** | **Yrs.** | |

**Daily Hot Water Demand Smaller Units @ Concourse A & B**

| | | | #USES PER DAY | | FULL TIME OCCUPANTS** | | | | |
|---|---|---|---|---|---|---|---|---|---|
| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | MALE | FEMALE | MALE | FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 0.75 | 0.75 | 0 | 0 | 0 | 50% | 0 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 2 | 15 | 0 | 5 | 0 | 375 | 75% | 281 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 3 | 0 | 15 | 75% | 11 |
| Dishwasher (gal per min) | 0.58 | 157.5 | 5.25 | 0 | 1 | 1 | 482 | 100% | 482 |
| | | | | | | **TOTAL** | 390 | | **775** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**DHW-1&2B: Replace Small Electric DHW Heater Used in the Concourse Restaurants w/ Tankless Condensing Gas-Fired DHW Heater - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Electric DHW Heater Removal | 1 | LS | | $ 500 | | $ - | $ 349 | $ - | $ 349 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Rheem RTGH-84DVLN-2 8.4 GPM direct vent tankless n'gas | 1 | EA | $ 1,000 | $ 1,000 | | $ 981 | $ 697 | $ - | $ 1,678 | If a residential unit of this type is all |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Venting Kit & Roof Penetrations | 1 | EA | $ 1,000 | $ 1,500 | | $ 981 | $ 1,046 | $ - | $ 2,027 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Natural Gas Piping and fittings | 650 | LF | $ 1.07 | $ 5.64 | | $ 682 | $ 2,555 | $ - | $ 3,237 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 8,620 | Subtotal |
| $ 1,724 | 20% Contingency |
| $ 1,293.00 | 15% O&P |
| **$ 11,637** | **Total** |

owed.

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## DHW-1&2C: Replace for Concourse Restroom Electric DHW Heaters w/ Tankless Condensing Gas-Fired DHW Heaters

**ECM Description Summary**

*Replace Concourse Restroom Electric DHW Heaters w/ Instantaneous, Condensing, Gas-Fired DHW Heaters*

**CONCOURSE B - 1 unit 120 GAL**

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 788 | gal/day | Calculated from usage below |
| Annual Hot Water Energy Demand | 59,695 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 119 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | Per building personnel |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 819 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 60,514 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 100% | | Per Manufacturer |
| Total Annual Energy Required | 60,514 | Mbtu/yr | |
| **Total Annual Electric Required** | **17,730** | **kWh/yr** | **Electrical Savings** |
| Average Annual Electric Demand | | kW | |
| Peak Electric Demand | 24.0 | kW | Per Manufacturer's Nameplate (Demand Savings) |
| **avg peak demand & diversity factor** | **8.0** | | **33% of peak demand (6 elements)** |
| | | | |
| New Tank Size | 120 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 826 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 60,521 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 96% | | Based on Navien CR180 instantaneous, condensing DHW Heater |
| Proposed Total Annual Energy Required | 63,043 | MBTU/yr | |
| Proposed Fuel Use | 630 | Therms/yr | Standby Losses and inefficient DHW heater eliminated |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.05 | $/kWh | |
| NG Utility Unit Cost | $0.03 | $/Therm | |
| Existing Operating Cost of DHW | $ 1,826 | $/yr | |
| Proposed Operating Cost of DHW | $ 21 | $/yr | |
| **Annual Utility Cost Savings** | **$ 1,804** | **$/yr** | |
| **Project cost** | **$ 24,218** | **$** | |
| **Project Payback** | **13.4** | **Yrs.** | |

**CONCOURSE A - 2 units 38 GAL**

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 300 | gal/day | Calculated from table below |
| Annual Hot Water Energy Demand | 22,741 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 38 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | Per building personnel |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.9% | | |
| Standby Losses (Heat Loss) | 0.1 | MBH | |
| Annual Standby Hot Water Load | 436 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 23,177 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 100% | | Per Manufacturer |
| Total Annual Energy Required | 23,177 | Mbtu/yr | |
| **Total Annual Electric Required** | **6,791** | **kWh/yr** | **Electrical Savings** |
| Average Annual Electric Demand | | kW | |
| Peak Electric Demand | 3.5 | kW | Per Manufacturer's Nameplate (Demand Savings) |
| **avg peak demand & diversity factor** | **1.2** | **kW** | **33% of peak demand** |
| | | | |
| New Tank Size | 50 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.9% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 574 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 23,315 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 80% | | Based on Navien CR180 instantaneous, condensing DHW Heater |
| Proposed Total Annual Energy Required | 29,143 | MBTU/yr | |
| Proposed Fuel Use | 291 | Therms/yr | Standby Losses and inefficient DHW heater eliminated |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.05 | $/kWh | |
| NG Utility Unit Cost | $0.03 | $/Therm | |
| Existing Operating Cost of DHW | $ 461 | $/yr | |
| Proposed Operating Cost of DHW | $ 10 | $/yr | |
| **Annual Utility Cost Savings** | **$ 451** | **$/yr** | **EACH TANK** |
| **Total Annual Utility Cost Savings** | **$ 902** | **$/yr** | |
| **Total Project cost** | **$ 23,274** | **$** | |
| **Project cost** | **$ 11,637** | **$** | |
| **Project Payback** | **25.8** | **Yrs.** | |

**Daily Hot Water Demand CONCOURSE B - 1 unit 120 GAL**

| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | #USES PER DAY MALE | #USES PER DAY FEMALE | FULL TIME OCCUPANTS** MALE | FULL TIME OCCUPANTS** FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
|---|---|---|---|---|---|---|---|---|---|
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 0.75 | 0.75 | 2000 | 2000 | 1500 | 50% | 750 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 5 | 5 | 50 | 75% | 38 |
| Dishwasher (gal per min) | 0.00 | 0 | 1 | 0 | 1 | 0 | 0 | 100% | 0 |
| | | | | | | **TOTAL** | 1550 | | **787.5** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Daily Hot Water Demand CONCOURSE A - 2 units 38 GAL**

| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | #USES PER DAY MALE | #USES PER DAY FEMALE | FULL TIME OCCUPANTS** MALE | FULL TIME OCCUPANTS** FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
|---|---|---|---|---|---|---|---|---|---|
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 0.75 | 0.75 | 1500 | 1500 | 1125 | 50% | 563 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 5 | 5 | 50 | 75% | 38 |
| Dishwasher (gal per min) | 0.00 | 0 | 1 | 0 | 1 | 0 | 0 | 100% | 0 |
| | | | | | | **TOTAL** | 1175 | | **600.0** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

**DHW-1&2C: Replace for Concourse Restroom Electric DHW Heaters w/ Tankless Condensing Gas-Fired DHW Heaters - Cost**

CONCOURSE B - 1 unit 120 GAL

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| Electric DHW Heater Removal | 1 | LS | | $ 500 | | $ - | $ 349 | $ - | $ 349 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| 130 Gal Condensing Natural Gas DHW Heater | 1 | EA | $ 10,500 | $ 1,000 | | $ 10,301 | $ 697 | $ - | $ 10,998 | Could go down to 100 gal for $6200 |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Venting Kit & Roof Penetration | 1 | EA | $ 1,000 | $ 1,500 | | $ 981 | $ 1,046 | $ - | $ 2,027 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Natural Gas Piping and fittings | 650 | LF | $ 1.07 | $ 5.64 | | $ 682 | $ 2,555 | $ - | $ 3,237 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

| | |
|---|---|
| $ 17,939 | Subtotal |
| $ 3,588 | 20% Contingency |
| $ 2,690.92 | 15% O&P |
| **$ 24,218** | **Total** |

CONCOURSE A - 2 units 38 GAL

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| Electric DHW Heater Removal | 1 | LS | | $ 500 | | $ - | $ 349 | $ - | $ 349 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Rheem RTGH-84DVLN-2 8.4 GPM direct vent tankless n'gas | 1 | EA | $ 1,000 | $ 1,000 | | $ 981 | $ 697 | $ - | $ 1,678 | If a residential unit of this type is allowed. |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Venting Kit & Roof Penetration | 1 | EA | $ 1,000 | $ 1,500 | | $ 981 | $ 1,046 | $ - | $ 2,027 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Natural Gas Piping and fittings | 650 | LF | $ 1.07 | $ 5.64 | | $ 682 | $ 2,555 | $ - | $ 3,237 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

| | |
|---|---|
| $ 8,620 | Subtotal |
| $ 1,724 | 20% Contingency |
| $ 1,293.00 | 15% O&P |
| **$ 11,637** | **Total** |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**DHW-1&2D: Replace Electric DHW Heater w/ Condensing Gas-Fired DHW Heater**

**ECM Description Summary**

*The existing departures/main terminal DHW is provided by an electric unit during the summer months and the main boiler system with an 85% efficiency during the heating season. This measure proposes replacing the existing DHW heater with a high efficiency condensing natural gas DHW heater. If the existing boilers are replaced with a condensing boilers these can be used with an indirect water heater to achieve similar results for a lower cost.*

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 863 | gal/day | Calculated from usage below |
| Annual Weeks of Operation | 20 | Weeks/yr | Summer Operation Only |
| Annual Hot Water Energy Demand | 65,380 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 125 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 861 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 66,241 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 100% | | Electric |
| Total Annual Energy Required | 66,241 | Mbtu/yr | |
| **Total Annual Electric Required** | **19,408** | **kWh/yr** | **Electrical Savings** |
| Average Annual Electric Demand | 2.2 | kW | |
| **Peak Electric Demand** | **144.0** | **kW** | **Per Manufacturer's Nameplate (Demand Savings)** |
| **avg peak demand & diversity factor** | **48.0** | | **33% of peak demand** |
| | | | |
| New Tank Size | 125 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 75 | ˚F | |
| Standby Losses (% by Volume) | 0.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.2 | MBH | |
| Annual Standby Hot Water Load | 861 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 66,241 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 96% | | |
| Proposed Total Annual Energy Required | 69,001 | MBTU/yr | |
| Proposed Fuel Use | 690 | Therms/yr | |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.05 | $/kWh | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $3,411 | $/yr | |
| Proposed Operating Cost of DHW | $233 | $/yr | |
| **Annual Utility Cost Savings** | **$3,178** | **$/yr** | |

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 863 | gal/day | Calculated from usage below |
| Annual Weeks of Operation | 32 | Weeks/yr | Non-Summer Operation |
| Annual Hot Water Energy Demand | 104,608 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 125 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 85 | ˚F | |
| Standby Losses (% by Volume) | 2.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.9 | MBH | |
| Annual Standby Hot Water Load | 3,281 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 107,889 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 85% | | |
| Total Annual Energy Required | 126,929 | Mbtu/yr | |
| **Total Annual Utility Required** | **1,269** | **Therms/yr** | |
| | | | |
| | | | |
| New Tank Size | 125 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 85 | ˚F | |
| Standby Losses (% by Volume) | 2.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.9 | MBH | |
| Annual Standby Hot Water Load | 3,281 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 107,889 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 96% | | |
| Proposed Total Annual Energy Required | 112,385 | MBTU/yr | |
| Proposed Fuel Use | 1,124 | Therms/yr | |
| | | | |
| Elec Utility Demand Unit Cost | $10.47 | $/kW | |
| Elec Utility Supply Unit Cost | $0.07 | $/kWh | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $429 | $/yr | |
| Proposed Operating Cost of DHW | $380 | $/yr | |
| **Annual Utility Cost Savings** | **$49** | **$/yr** | |

**Daily Hot Water Demand**

| | | | #USES PER DAY | | FULL TIME OCCUPANTS** | | | | |
|---|---|---|---|---|---|---|---|---|---|
| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | MALE | FEMALE | MALE | FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 1 | 0.5 | 0.75 | 0.75 | 2,000 | 2,000 | 1,500 | 50% | 750 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| MOP SINK | 2.5 | 2 | 3 | 3 | 5 | 5 | 150 | 75% | 113 |
| Dishwasher (gal per use) | 10 | 1 | 0 | 0 | 1 | 1 | 0 | 100% | 0 |
| | | | | | | **TOTAL** | 1,650 | | **863** |

*GPM is per standard fixtures, adjust as necessary if actual GPM is known.
**These are the occupant that use the fixtures. If fixture does not exist change to (0).

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**DHW-1&2D: Replace Electric DHW Heater w/ Condensing Gas-Fired DHW Heater - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Gas-Fired DHW Heater Removal | 1 | LS | | $ 500 | | $ - | $ 349 | $ - | $ 349 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| 125 Gal Condensing Natural Gas DHW Heater | 1 | EA | $ 10,500 | $ 1,000 | | $ 10,301 | $ 697 | $ - | $ 10,998 | |
| Miscellaneous Electrical | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| Venting Kit & Roof Penetration | 1 | EA | $ 1,000 | $ 3,000 | | $ 981 | $ 2,091 | $ - | $ 3,072 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 500 | $ 250 | | $ 491 | $ 174 | $ - | $ 665 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 15,748 | Subtotal |
| $ 3,149.50 | 20% Contingency |
| $ 2,362.13 | 15% O&P |
| **$ 21,259** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-1A: Install Demand Control Ventilation (AHUs-Main Terminal)**

**ECM Description Summary**
*Outside air can be significantly reduced for most of the time that the building is occupied. Savings will result from the avoided heating and cooling of excessive outside air.*

| | Total CFM | O.A. CFM | O.A. % | |
|---|---|---|---|---|
| Org. scheduled CFM | 42,380 | 8,625 | 20% | |
| Derated CFM | 42,380 | 6,469 | 15% | |
| SA Enthalpy | 24.5 | BTU/lbma | | |
| SA Set point, Winter | 72.0 | °F | | |
| SA Set point, Summer | 74.0 | °F | | |
| Heating "On" Point | 55.0 | °F | | |
| Cooling System Eff. | 0.80 | kW/Ton | | (Includes ancillary equipment) |
| Heating System Eff. | 83% | | | (Includes distribution losses) |

**Utility Costs**

| | | |
|---|---|---|
| Blended Electric Rate | $0.07 | / kWh |
| Blended Natural Gas Rate | $0.34 | / Therm |

**Method:**
The outdoor air introduced into the spaces is currently constant based on design occupancy conditions.
This ECM proposes the installation of CO2 sensors in the space to allow for reduced outdoor air flows when conditions allow.
An average reduction of 50% is assumed possible with the implementation of DCV
The DCV system will automatically adjust the outdoor air damper position through the EMS to reduce outdoor air flows based on indoor CO2 levels.

| A | B | C | D | E | F | G | H | I | J | K | L | M | N | O |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Existing | | | | | Proposed Demand Ventilation | | | | | Savings | |
| Avg. DB Bin Temp °F | OA Enthalpy Btu/lb | Occupied Bin HOURS | OA CFM | Cooling Load MBH | Heating Load MBH | Cooling kWh | Heating therms | Derated O.A. CFM | Cooling Load MBH | Heating Load MBH | Cooling kWh | Heating therms | Cooling kWh | Heating therms |
| 102.5 | - | 0 | 8,625 | 0 | 0 | 0 | - | 6,469 | 0 | 0 | 0 | - | 0 | - |
| 97.5 | 42.37 | 10 | 8,625 | 694 | 0 | 462 | - | 6,469 | 520 | 0 | 347 | - | 116 | - |
| 92.5 | 39.71 | 39 | 8,625 | 591 | 0 | 1,535 | - | 6,469 | 443 | 0 | 1,152 | - | 384 | - |
| 87.5 | 38.09 | 215 | 8,625 | 527 | 0 | 7,560 | - | 6,469 | 396 | 0 | 5,670 | - | 1890 | - |
| 82.5 | 35.85 | 557 | 8,625 | 441 | 0 | 16,362 | - | 6,469 | 330 | 0 | 12,272 | - | 4091 | - |
| 77.5 | 33.99 | 910 | 8,625 | 368 | 0 | 22,335 | - | 6,469 | 276 | 0 | 16,751 | - | 5584 | - |
| 72.5 | 31.58 | 978 | 8,625 | 275 | 0 | 17,925 | - | 6,469 | 206 | 0 | 13,444 | - | 4481 | - |
| 67.5 | 28.27 | 971 | 8,625 | 146 | 0 | 9,472 | - | 6,469 | 110 | 0 | 7,104 | - | 2368 | - |
| 62.5 | 24.53 | 1,101 | 8,625 | 1 | 0 | 94 | - | 6,469 | 1 | 0 | 70 | - | 23 | - |
| 57.5 | 21.54 | 655 | 8,625 | 0 | 0 | 0 | - | 6,469 | 0 | 0 | 0 | - | 0 | - |
| 52.5 | 18.65 | 581 | 8,625 | 0 | 182 | 0 | 1,271 | 6,469 | 0 | 136 | 0 | 954 | 0 | 318 |
| 47.5 | 16.34 | 561 | 8,625 | 0 | 228 | 0 | 1,543 | 6,469 | 0 | 171 | 0 | 1,157 | 0 | 386 |
| 42.5 | 14.56 | 781 | 8,625 | 0 | 275 | 0 | 2,586 | 6,469 | 0 | 206 | 0 | 1,939 | 0 | 646 |
| 37.5 | 12.61 | 680 | 8,625 | 0 | 321 | 0 | 2,633 | 6,469 | 0 | 241 | 0 | 1,975 | 0 | 658 |
| 32.5 | 10.77 | 386 | 8,625 | 0 | 368 | 0 | 1,711 | 6,469 | 0 | 276 | 0 | 1,283 | 0 | 428 |
| 27.5 | 8.59 | 191 | 8,625 | 0 | 415 | 0 | 954 | 6,469 | 0 | 311 | 0 | 715 | 0 | 238 |
| 22.5 | 7.22 | 102 | 8,625 | 0 | 461 | 0 | 567 | 6,469 | 0 | 346 | 0 | 425 | 0 | 142 |
| 17.5 | 5.35 | 41 | 8,625 | 0 | 508 | 0 | 251 | 6,469 | 0 | 381 | 0 | 188 | 0 | 63 |
| 12.5 | 4.50 | 1 | 8,625 | 0 | 554 | 0 | 7 | 6,469 | 0 | 416 | 0 | 5 | 0 | 2 |
| 7.5 | - | 0 | 8,625 | 0 | 601 | 0 | - | 6,469 | 0 | 451 | 0 | - | 0 | - |
| **Total** | | **8,760** | | **3,043** | | **75,744** | **11,522** | | **2,282** | | **56,808** | **8,641** | **18,936** | **2,880** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-1A: Install Demand Control Ventilation (AHUs-Main Terminal) - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| CO2 sensor | 3 | ea. | $ 400 | $ 100 | $ - | $ 1,177 | $ 209 | $ - | $ 1,386 | |
| Replace damper actuators | 6 | ea. | $ 500 | $ 800 | $ - | $ 2,943 | $ 3,346 | $ - | $ 6,289 | replace pneu actuators with electronic |
| Control system programming | 1 | ls | $ 3,000 | $ 2,000 | $ - | $ 2,943 | $ 1,394 | $ - | $ 4,337 | possible panel upgrades |
| electrical/wiring | 1 | ls | $ 2,000 | $ 2,000 | $ - | $ 1,962 | $ 1,394 | $ - | $ 3,356 | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 15,368 | Subtotal |
| $ 3,074 | 20% Contingency |
| $ 2,305 | 15% O&P |
| **$ 20,747** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-1B: Install Demand Control Ventilation (AHU-39 & 40)**

**ECM Description Summary**
*Outside air can be significantly reduced for most of the time that the building is occupied. Savings will result from the avoided heating and cooling of excessive outside air.*

| | Total CFM | O.A. CFM | O.A. % | |
|---|---|---|---|---|
| Org. scheduled CFM | 16,750 | 4,188 | 25% | |
| Derated CFM | 16,750 | 3,141 | 19% | |
| SA Enthalpy | 24.5 | BTU/lbma | | |
| SA Set point, Winter | 72.0 | °F | | |
| SA Set point, Summer | 72.0 | °F | | |
| Heating "On" Point | 55.0 | °F | | |
| Cooling System Eff. | 0.80 | kW/Ton | | (Includes ancillary equipment) |
| Heating System Eff. | 80% | | | (Includes distribution losses) |

**Utility Costs**

| | | |
|---|---|---|
| Blended Electric Rate | $0.07 | / kWh |
| Blended Natural Gas Rate | $0.34 | / Therm |

**Method:**
The outdoor air introduced into the spaces is currently constant based on design occupancy conditions.
This ECM proposes the installation of CO2 sensors in the space to allow for reduced outdoor air flows when conditions allow.
An average reduction of 50% is assumed possible with the implementation of DCV
The DCV system will automatically adjust the outdoor air damper position through the EMS to reduce outdoor air flows based on indoor CO2 levels.

| A | B | C | D | E | F | G | H | I | J | K | L | M | N | O |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Existing | | | | | Proposed Demand Ventilation | | | | | Savings | |
| Avg. DB Bin Temp °F | OA Enthalpy Btu/lb | Occupied Bin HOURS | OA CFM | Cooling Load MBH | Heating Load MBH | Cooling kWh | Heating therms | Derated O.A. CFM | Cooling Load MBH | Heating Load MBH | Cooling kWh | Heating therms | Cooling kWh | Heating therms |
| 102.5 | - | 0 | 4,188 | 0 | 0 | 0 | - | 3,141 | 0 | 0 | 0 | - | 0 | - |
| 97.5 | 42.37 | 10 | 4,188 | 337 | 0 | 225 | - | 3,141 | 253 | 0 | 168 | - | 56 | - |
| 92.5 | 39.71 | 39 | 4,188 | 287 | 0 | 745 | - | 3,141 | 215 | 0 | 559 | - | 186 | - |
| 87.5 | 38.09 | 215 | 4,188 | 256 | 0 | 3,670 | - | 3,141 | 192 | 0 | 2,753 | - | 918 | - |
| 82.5 | 35.85 | 557 | 4,188 | 214 | 0 | 7,944 | - | 3,141 | 160 | 0 | 5,958 | - | 1986 | - |
| 77.5 | 33.99 | 910 | 4,188 | 179 | 0 | 10,844 | - | 3,141 | 134 | 0 | 8,133 | - | 2711 | - |
| 72.5 | 31.58 | 978 | 4,188 | 133 | 0 | 8,703 | - | 3,141 | 100 | 0 | 6,527 | - | 2176 | - |
| 67.5 | 28.27 | 971 | 4,188 | 71 | 0 | 4,599 | - | 3,141 | 53 | 0 | 3,449 | - | 1150 | - |
| 62.5 | 24.53 | 1,101 | 4,188 | 1 | 0 | 45 | - | 3,141 | 0 | 0 | 34 | - | 11 | - |
| 57.5 | 21.54 | 655 | 4,188 | 0 | 0 | 0 | - | 3,141 | 0 | 0 | 0 | - | 0 | - |
| 52.5 | 18.65 | 581 | 4,188 | 0 | 88 | 0 | 640 | 3,141 | 0 | 66 | 0 | 480 | 0 | 160 |
| 47.5 | 16.34 | 561 | 4,188 | 0 | 111 | 0 | 777 | 3,141 | 0 | 83 | 0 | 583 | 0 | 194 |
| 42.5 | 14.56 | 781 | 4,188 | 0 | 133 | 0 | 1,302 | 3,141 | 0 | 100 | 0 | 977 | 0 | 326 |
| 37.5 | 12.61 | 680 | 4,188 | 0 | 156 | 0 | 1,326 | 3,141 | 0 | 117 | 0 | 995 | 0 | 332 |
| 32.5 | 10.77 | 386 | 4,188 | 0 | 179 | 0 | 862 | 3,141 | 0 | 134 | 0 | 646 | 0 | 215 |
| 27.5 | 8.59 | 191 | 4,188 | 0 | 201 | 0 | 480 | 3,141 | 0 | 151 | 0 | 360 | 0 | 120 |
| 22.5 | 7.22 | 102 | 4,188 | 0 | 224 | 0 | 285 | 3,141 | 0 | 168 | 0 | 214 | 0 | 71 |
| 17.5 | 5.35 | 41 | 4,188 | 0 | 246 | 0 | 126 | 3,141 | 0 | 185 | 0 | 95 | 0 | 32 |
| 12.5 | 4.50 | 1 | 4,188 | 0 | 269 | 0 | 3 | 3,141 | 0 | 202 | 0 | 3 | 0 | 1 |
| 7.5 | - | 0 | 4,188 | 0 | 292 | 0 | - | 3,141 | 0 | 219 | 0 | - | 0 | - |
| **Total** | | **8,760** | | **1,477** | | **36,774** | **5,804** | | **1,108** | | **27,581** | **4,353** | **9,194** | **1,451** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-1B: Install Demand Control Ventilation (AHU-39 & 40) - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| CO2 sensor | 2 | ea. | $ 400 | $ 100 | $ - | $ 785 | $ 139 | $ - | $ 924 | |
| Replace damper actuators | 2 | ea. | $ 500 | $ 800 | $ - | $ 981 | $ 1,115 | $ - | $ 2,096 | Need modulating actuators |
| Control system programming | 1 | ls | $ 3,000 | $ 2,000 | $ - | $ 2,943 | $ 1,394 | $ - | $ 4,337 | possible panel upgrades |
| electrical/wiring | 1 | ls | $ 2,000 | $ 2,000 | $ - | $ 1,962 | $ 1,394 | $ - | $ 3,356 | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 10,713 | Subtotal |
| $ 2,143 | 20% Contingency |
| $ 1,607 | 15% O&P |
| **$ 14,463** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-2: Unoccupied AHU Schedule and Night Setback**

**ECM Description Summary**
*This measure will install programs to shutdown units and close OA damper during unoccupied periods while maintaining night setback temperatures.*

| AIR HANDLING & FAN COIL Unit Data | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Unit Data | | | Air Flow | | | | Capacities | | | | Fan Motor Data | | | | | Totals | | | |
| Given Tag | VFD | VFD Speed (avg) | Count | CFM | RA CFM | OA CFM | Total OA | COOLING GPM | Cooling MBH | HEATING GPM | Total HEAT Loss | Volts | Phases | HP | Motor Efficiency | kW | Total kW | Area Served | NOTES |
| AHU-1 | Y | 100.0% | 1 | 38,100 | 31,600 | 6,500 | 6,500 | 250 | 692 | 135 | 1,336 | 460 | 3 | 50 | 90.0% | 31 | 31 | 1st Floor Tickets Departures area | VFD controlled. |
| AHU-2 | Y | 100.0% | 1 | 33,560 | 28,280 | 5,280 | 5,280 | 230 | 621 | 120 | 1,186 | 460 | 3 | 50 | 90.0% | 31 | 31 | 1st Floor Tickets Departures area | Unoccupied period, units |
| AHU-3 | N | | 0 | 13,200 | 9,880 | 3,320 | - | 90 | 199 | 40 | 369 | 460 | 3 | 25 | 90.0% | 16 | - | Services the basement area, security offices 24/7. | Removed from NSB due to offices 24/7 |
| AHU-4 | N | | 1 | 18,000 | 15,900 | 2,100 | 2,100 | 125 | 333 | 71 | 710 | 460 | 3 | 10 | 90.0% | 6 | 6 | 2ND FLOOR/COMMON AREAS | |
| AHU-5 | N | | 1 | 14,855 | 12,580 | 2,275 | 2,275 | 265 | 615 | 140 | 1,372 | 460 | 3 | 25 | 90.0% | 16 | 16 | 2ND FLOOR/AIRPORT OFFICES/BURGER KING | |
| AHU-6 | Y | 85.0% | 1 | 38,200 | 33,300 | 4,900 | 4,900 | 100 | 273 | 55 | 531 | 460 | 3 | 60 | 91.5% | 25 | 25 | 2ND FLOOR -FINANCE OFFICES/CONFERENCE | VFD controlled. Savings calculation for shutting off unit would be less than constant volume calculation. |
| AHU-7 | N | | 1 | 21,600 | 18,475 | 3,125 | 3,125 | 165 | 394 | 85 | 847 | 460 | 3 | 10 | 89.5% | 6 | 6 | 2ND FLOOR/COMMON AREAS/HALLWAYS TO CONCOURSES | |
| AHU-8 | N | | 0 | 7,100 | 5,100 | 2,000 | - | 70 | 130 | 35 | 337 | 460 | 3 | 8 | 88.5% | 5 | - | Starbucks Area opened 24/7 | |
| AHU-9 | N | | 1 | 10,200 | - | 10,200 | 10,200 | 40 | 187 | 66 | 660 | 460 | 3 | 8 | 91.7% | 5 | 5 | MUA - KITCHEN AREA | |
| AHU-10 | N | | 1 | 13,680 | 10,180 | 3,500 | 3,500 | 115 | 251 | 85 | 854 | 460 | 3 | 10 | 91.7% | 6 | 6 | 2ND FLOOR- RESTAURANT | |
| AHU-39 | Y | 80.0% | 1 | 8,375 | - | 8,375 | 8,375 | 37 | 204 | 6 | 98 | 460 | 3 | 10 | 91.5% | 4 | 4 | | VFD controlled. Savings calculation for shutting off unit would be less than constant volume calculation. |
| AHU-40 | Y | 80.0% | 1 | 8,375 | - | 8,375 | 8,375 | 37 | 204 | 6 | 98 | 460 | 3 | 10 | 91.5% | 4 | 4 | | VFD controlled. Savings calculation for shutting off unit would be less than constant volume calculation. |
| AHU-11 | N | | 1 | 18,990 | 12,990 | 6,000 | 6,000 | 172 | 857 | 64 | 640 | 460 | 3 | 30 | 92.4% | 18 | 18 | | |
| AHU-12 | N | | 1 | 20,305 | 19,705 | 6,000 | 6,000 | 180 | 901 | 68 | 676 | 460 | 3 | 30 | 92.4% | 18 | 18 | | |
| AHU-13 | N | | 1 | 19,895 | 13,895 | 6,000 | 6,000 | 178 | 886 | 86 | 861 | 460 | 3 | 30 | 93.6% | 18 | 18 | | |
| AHU-25 | Y | 82.1% | 0 | | | | - | | | | | | | | | | | NO DRAWING INFORMATION OF UNIT | |
| AHU-38 | Y | 62.4% | 0 | | | | - | | | | | | | | | | | NO DRAWING INFORMATION OF UNIT | |
| RTU-1A | Y | 48.3% | 1 | 9,500 | 9,000 | 2,000 | 2,000 | 77 | 471 | 16 | 161 | 460 | 3 | 28 | 92.5% | 3 | 3 | | |
| AHU-14 | Y | 98.1% | 1 | 12,720 | 10,115 | 2,605 | 2,605 | 124 | 620 | 46 | 458 | 460 | 3 | 25 | 92.4% | 14 | 14 | | |
| AHU-16 | N | | 1 | 19,030 | 13,030 | 6,000 | 6,000 | 172 | 866 | 64 | 640 | 460 | 3 | 30 | 92.4% | 18 | 18 | | |
| AHU-18 | Y | 100.0% | 1 | 12,320 | 10,070 | 2,250 | 2,250 | 123 | 615 | 47 | 465 | 460 | 3 | 25 | 93.6% | 15 | 15 | | |
| AHU-19 | Y | 100.0% | 1 | 19,680 | 16,080 | 3,600 | 3,600 | 184 | 921 | 97 | 970 | 460 | 3 | 40 | 94.1% | 24 | 24 | | |
| AHU-20 | Y | 100.0% | 1 | 20,270 | 16,560 | 3,710 | 3,710 | 197 | 985 | 98 | 981 | 460 | 3 | 50 | 92.4% | 30 | 30 | | |
| FCU-21 | N | | 1 | 800 | 800 | - | - | 5 | 24 | 2 | 26 | 120 | 1 | 0.167 | 89.0% | 0.10 | 0 | | |
| FCU-22 | N | | 1 | 800 | 800 | - | - | 5 | 24 | 2 | 26 | 120 | 1 | 0.167 | 89.0% | 0.10 | 0 | | |
| FPTB - RTU1A | N | | 1 | 12,955 | 12,955 | - | - | - | - | 41 | 405 | 277 | 1 | 7 | 92.5% | 4 | 4 | | |
| RTU-1 | Y | 81.2% | 1 | 18,530 | 16,700 | 2,445 | 2,445 | 128 | 777 | 56 | 574 | 460 | 3 | 45 | 92.5% | 17 | 17 | | |
| **Totals** | | | | **411,040** | | | **95,240** | | | | | | | | | | **314** | | |

| AIR HANDLING & FAN COIL Unit Data | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Unit Data | | | | Air Flow | | | | Capacities | | | | Fan Motor Data | | | | | Totals |
| Given Tag | VFD | VFD Speed (avg) | Count | CFM | RA CFM | OA CFM | Total OA | COOLING GPM | Cooling MBH | HEATING GPM | Heating MBH | Volts | Phases | HP | Motor Efficiency | kW | Total kW |
| AHU-1 | Y | 100.0% | 1 | 38,100 | 31,600 | 6,500 | *3,250* | 250 | 692 | 135 | 1,336 | 460 | 3 | 50 | 0.90 | *4* | 4 |
| AHU-2 | Y | 100.0% | 1 | 33,560 | 28,280 | 5,280 | *2,640* | 230 | 621 | 120 | 1,186 | 460 | 3 | 50 | 0.90 | *4* | 4 |
| AHU-3 | N | | 0 | 13,200 | 9,880 | 3,320 | - | 90 | 199 | 40 | 369 | 460 | 3 | 25 | 0.90 | 16 | - |
| AHU-4 | N | | 1 | 18,000 | 15,900 | 2,100 | 2,100 | 125 | 333 | 71 | 710 | 460 | 3 | 10 | 0.90 | 6 | 6 |
| AHU-5 | N | | 1 | 14,855 | 12,580 | 2,275 | 2,275 | 265 | 615 | 140 | 1,372 | 460 | 3 | 25 | 0.90 | 16 | 16 |
| AHU-6 | Y | 85.0% | 1 | 38,200 | 33,300 | 4,900 | 4,900 | 100 | 273 | 55 | 531 | 460 | 3 | 60 | 0.92 | 37 | 37 |
| AHU-7 | N | | 1 | 21,600 | 18,475 | 3,125 | 3,125 | 165 | 394 | 85 | 847 | 460 | 3 | 10 | 0.90 | 6 | 6 |
| AHU-8 | N | | 0 | 7,100 | 5,100 | 2,000 | - | 70 | 130 | 35 | 337 | 460 | 3 | 8 | 0.89 | 5 | - |
| AHU-9 | N | | 1 | 10,200 | - | 10,200 | 10,200 | 40 | 187 | 66 | 660 | 460 | 3 | 8 | 0.92 | 5 | 5 |
| AHU-10 | N | | 1 | 13,680 | 10,180 | 3,500 | 3,500 | 115 | 251 | 85 | 854 | 460 | 3 | 10 | 0.92 | 6 | 6 |
| AHU-39 | Y | 80.0% | 1 | 8,375 | - | 8,375 | 8,375 | 37 | 204 | 6 | 98 | 460 | 3 | 10 | 0.92 | 6 | 6 |
| AHU-40 | Y | 80.0% | 1 | 8,375 | - | 8,375 | 8,375 | 37 | 204 | 6 | 98 | 460 | 3 | 10 | 0.92 | 6 | 6 |
| AHU-11 | N | | 1 | 18,990 | 12,990 | 6,000 | 6,000 | 172 | 857 | 64 | 640 | 460 | 3 | 30 | 0.92 | 18 | 18 |
| AHU-12 | N | | 1 | 20,305 | 19,705 | 6,000 | 6,000 | 180 | 901 | 68 | 676 | 460 | 3 | 30 | 0.92 | 18 | 18 |
| AHU-13 | N | | 1 | 19,895 | 13,895 | 6,000 | 6,000 | 178 | 886 | 86 | 861 | 460 | 3 | 30 | 0.94 | 18 | 18 |
| AHU-25 | Y | 82.1% | 0 | | | | | | | | | | | | | | |
| AHU-38 | Y | 62.4% | 0 | | | | | | | | | | | | | | |
| RTU-1A | Y | 48.3% | 1 | 9,500 | 9,000 | 2,000 | 2,000 | 77 | 471 | 16 | 161 | 460 | 3 | 28 | 0.93 | 17 | 17 |
| AHU-14 | Y | 98.1% | 1 | 12,720 | 10,115 | 2,605 | 2,605 | 124 | 620 | 46 | 458 | 460 | 3 | 25 | 0.92 | 15 | 15 |
| AHU-16 | N | | 1 | 19,030 | 13,030 | 6,000 | 6,000 | 172 | 866 | 64 | 640 | 460 | 3 | 30 | 0.92 | 18 | 18 |
| AHU-18 | Y | 100.0% | 1 | 12,320 | 10,070 | 2,250 | 2,250 | 123 | 615 | 47 | 465 | 460 | 3 | 25 | 0.94 | 15 | 15 |
| AHU-19 | Y | 100.0% | 1 | 19,680 | 16,080 | 3,600 | 3,600 | 184 | 921 | 97 | 970 | 460 | 3 | 40 | 0.94 | 24 | 24 |
| AHU-20 | Y | 100.0% | 1 | 20,270 | 16,560 | 3,710 | 3,710 | 197 | 985 | 98 | 981 | 460 | 3 | 50 | 0.92 | 30 | 30 |
| FCU-21 | N | | 1 | 800 | 800 | - | - | 5 | 24 | 2 | 26 | 120 | 1 | 0.167 | 0.89 | 0.10 | 0 |
| FCU-22 | N | | 1 | 800 | 800 | - | - | 5 | 24 | 2 | 26 | 120 | 1 | 0.167 | 0.89 | 0.10 | 0 |
| FPTB - RTU1A | N | | 1 | 12,955 | 12,955 | - | - | - | - | 41 | 405 | 277 | 1 | 7 | 0.93 | 4 | 4 |
| RTU-1 | Y | 81.2% | 1 | 18,530 | 16,700 | 2,445 | 2,445 | 128 | 777 | 56 | 574 | 460 | 3 | 45 | 0.93 | 27 | 27 |
| **Totals** | | | | | | 100,560 | 89,350 | | | | | | | | | | 300 |

| Assumptions | | |
|---|---|---|
| Variable | Value | Unit |
| Existing Temperature set point | 72 | F |
| Heating On | 65 | F |
| Enthalpy Set point | 24.5 | BTU/lbm |
| Chiller Efficiency (3) | 0.8 | kW/Ton |

| Utility Rates | |
|---|---|
| Electrical Rate ($/kWh) | Natural Gas Rate ($/Therm) |
| $ 0.071 | $ 0.338 |

| Savings Summary | | | | |
|---|---|---|---|---|
| Electrical Consumption (kWh) | Natural Gas Consumption (Therms) | Savings ($) | Cost | Payback (Yrs.) |
| 75,619 | 29,142 | $ 15,190 | $ 31,590 | 2.08 |

| Common Space | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| General Data | | | | | | | | Existing | | | | | Proposed | | | | | | | | Savings | | |
| OAT - DB | OAH | Bin Hours (1) | Occupied Bin Hours (2) | Unoccupied Bin Hours (2) | Occupied OA (CFM) | Unoccupied OA (CFM) (5) | Boiler Efficiency % (4) | Motor Consumption (kWh) | Heating Load (MBH) | Cooling Load (MBH) | Heating Consumption (Therms) | Cooling Consumption (kWh) | Occupied Motor Consumption (kWh) | Unoccupied Motor Consumption (kWh) | Occupied Heating Load (MBH) | Occupied Cooling Load (MBH) | Unoccupied Heating Load (MBH) | Unoccupied Cooling Load (MBH) | Heating Consumption (Therms) | Cooling Consumption (kWh) | Motor Consumption (kWh) | Heating Consumption (Therms) | Cooling Consumption (kWh) |
| 97.5 | 42.372 | 10 | 10 | 0 | 89,350 | 0 | 83.0% | 3,002 | - | 7,186 | - | 4,791 | 3,002 | - | 0 | 7185.88 | 0.00 | 0.00 | 0 | 4,791 | - | - | - |
| 92.5 | 39.715 | 39 | 39 | 0 | 89,350 | 0 | 83.0% | 11,709 | - | 6,117 | - | 15,905 | 11,709 | - | 0 | 6117.40 | 0.00 | 0.00 | 0 | 15,905 | - | - | - |
| 87.5 | 38.089 | 215 | 215 | 0 | 89,350 | 0 | 83.0% | 64,552 | - | 5,464 | - | 78,316 | 64,552 | - | 0 | 5463.88 | 0.00 | 0.00 | 0 | 78,316 | - | - | - |
| 82.5 | 35.853 | 557 | 550 | 7 | 89,350 | 0 | 83.0% | 167,235 | - | 4,565 | - | 169,501 | 165,134 | 2,102 | 0 | 4564.67 | 0.00 | 0.00 | 0 | 167,371 | - | - | 2,130 |
| 77.5 | 33.985 | 910 | 813 | 97 | 89,350 | 0 | 83.0% | 273,221 | - | 3,814 | - | 231,373 | 244,097 | 29,124 | 0 | 3813.83 | 0.00 | 0.00 | 0 | 206,710 | - | - | 24,663 |
| 72.5 | 31.583 | 978 | 815 | 163 | 89,350 | 0 | 83.0% | 293,638 | - | 2,848 | - | 185,689 | 244,698 | 48,940 | 0 | 2847.99 | 0.00 | 0.00 | 0 | 154,741 | - | - | 30,948 |
| 67.5 | 28.270 | 971 | 796 | 175 | 89,350 | 0 | 83.0% | 291,536 | - | 1,516 | - | 98,122 | 238,993 | 52,543 | 0 | 1515.78 | 0.00 | 0.00 | 0 | 80,438 | - | - | 17,684 |
| 62.5 | 24.533 | 1101 | 881 | 220 | 89,350 | 0 | 83.0% | 330,567 | 917 | 13 | 12,160 | 970 | 264,514 | 66,053 | 917 | 13.22 | 0.00 | 0.00 | 9,731 | 776 | - | 2,430 | 194 |
| 57.5 | 21.544 | 655 | 521 | 134 | 89,350 | 0 | 83.0% | 196,659 | 1,399 | - | 11,042 | - | 156,427 | 40,233 | 1,399 | 0.00 | 0.00 | 0.00 | 8,783 | 0 | - | 2,259 | - |
| 52.5 | 18.652 | 581 | 472 | 109 | 89,350 | 0 | 83.0% | 174,441 | 1,882 | - | 13,172 | - | 141,715 | 32,726 | 1,882 | 0.00 | 0.00 | 0.00 | 10,701 | 0 | - | 2,471 | - |
| 47.5 | 16.338 | 561 | 469 | 92 | 89,350 | 0 | 83.0% | 168,436 | 2,364 | - | 15,980 | - | 140,814 | 27,622 | 2,364 | 0.00 | 0.00 | 0.00 | 13,359 | 0 | - | 2,621 | - |
| 42.5 | 14.555 | 781 | 634 | 147 | 89,350 | 0 | 83.0% | 234,490 | 2,847 | - | 26,786 | - | 190,354 | 44,136 | 2,847 | 0.00 | 0.00 | 0.00 | 21,745 | 0 | - | 5,042 | - |
| 37.5 | 12.606 | 680 | 525 | 155 | 89,350 | 0 | 83.0% | 204,165 | 3,329 | - | 27,275 | - | 157,628 | 46,538 | 3,329 | 0.00 | 0.00 | 0.00 | 21,058 | 0 | - | 6,217 | - |
| 32.5 | 10.771 | 386 | 303 | 83 | 89,350 | 0 | 83.0% | 115,894 | 3,812 | - | 17,727 | - | 90,974 | 24,920 | 3,812 | 0.00 | 0.00 | 0.00 | 13,915 | 0 | - | 3,812 | - |
| 27.5 | 8.587 | 191 | 148 | 43 | 89,350 | 0 | 83.0% | 57,346 | 4,294 | - | 9,882 | - | 44,436 | 12,910 | 4,294 | 0.00 | 0.00 | 0.00 | 7,657 | 0 | - | 2,225 | - |
| 22.5 | 7.220 | 102 | 76 | 26 | 89,350 | 0 | 83.0% | 30,625 | 4,777 | - | 5,870 | - | 22,818 | 7,806 | 4,777 | 0.00 | 0.00 | 0.00 | 4,374 | 0 | - | 1,496 | - |
| 17.5 | 5.354 | 41 | 32 | 9 | 89,350 | 0 | 83.0% | 12,310 | 5,259 | - | 2,598 | - | 9,608 | 2,702 | 5,259 | 0.00 | 0.00 | 0.00 | 2,028 | 0 | - | 570 | - |
| 12.5 | 4.495 | 1 | 1 | 0 | 89,350 | 0 | 83.0% | 300 | 5,742 | - | 69 | - | 300 | - | 5,742 | 0.00 | 0.00 | 0.00 | 69 | 0 | - | - | - |
| 7.5 | 0.000 | 0 | 0 | 0 | 89,350 | 0 | 83.0% | - | 6,224 | - | - | - | - | - | 6,224 | 0.00 | 0.00 | 0.00 | 0 | 0 | - | - | - |
| 2.5 | 0.000 | 0 | 0 | 0 | 89,350 | 0 | 83.0% | - | 6,707 | - | - | - | - | - | 6,707 | 0.00 | 0.00 | 0.00 | 0 | 0 | - | - | - |
| -2.5 | 0.000 | 0 | 0 | 0 | 89,350 | 0 | 83.0% | - | 7,189 | - | - | - | - | - | 7,189 | 0.00 | 0.00 | 0.00 | 0 | 0 | - | - | - |
| **Total** | **18.7868** | **8,760** | **7,300** | **1,460** | **89,350** | **0** | 83.0% | **2,630,128** | **56,741** | **31,523** | **142,561** | **784,666** | **2,191,773** | **438,355** | **56,741** | **31,523** | - | - | **113,419** | **709,047** | **-** | **29,142** | **75,619** |

**Notes:**

**(1) Based on TMY3 Bin Data for NORFOLK, VA**
**(2) Based on an assumption of X hrs. per day of unoccupied time**
**(3) Based On Dakin Manufacturer Documentation**
**(4) Data Calculated in the Boiler DT calc**
**(5) It is assumed that in the common spaces all OA dampers can be closed during unoccupied (night) hours**
BASED 4 HOURS SHUTDOWN 140 HOURS/WEEK ON

Total Bldg. Usage 241260

% of Bldg. Usage 59%

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**C-2: Unoccupied AHU Schedule and Night Setback - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| Reprogram DDC system for 23 Units | 138 | hr | | $ 150 | $ - | $ - | $ 20,700 | $ - | $ 20,700 | No Area Multiplier Applied To Labor |
| Travel time (4 hours/day, 2 hours/each way) | 18 | days | | $ 150 | | $ - | $ 2,700 | $ - | $ 2,700 | No Area Multiplier Applied To Labor |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 23,400 | Subtotal |
| $ 4,680 | 20% Contingency |
| $ 3,510 | 15% O&P |
| **$ 31,590** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## K-1A: Kitchen Hood Control - Main Terminal

### ECM Description Summary

*The exhaust systems in the kitchen hoods are at a constant speed. Adding a kitchen exhaust hood system would vary the amount of exhaust air volume, based on the heat and smoke load coming off the kitchen equipment. Upon activation of the system, the hood lights will turn on and the fans would reach a preset minimum speed of approximately 50 percent. When cooking appliances are turned on, the fan speed would increase based on the temperature sensed in the exhaust duct. During actual cooking, an optical sensor will sense particulates entering the hood and will increase up to 100 percent speed until smoke and heat are effectively exhausted.*

**Motor Operating Savings**

| | | | |
|---|---|---|---|
| Hours of Operation (per day) | 15 | | A |
| Days/Year | 365 | | B |
| Weeks/Year | 52 | | C |
| Motor HP | 12.5 | | D |
| Equivalent KW | 8.29 | KW | E |
| Cost of Electricity | $0.07 | KWh | F |
| Total Time/Year | 5,475 | hrs/year | G |
| Total KWH/YR | 45,382 | KWh | H |

| % Rated RPM<br>I | % Run Time<br>J | Time<br>K<br>J * G | Output<br>L<br>I * E ^ 2.5 | KWH/YR<br>M<br>L *K |
|---|---|---|---|---|
| 100% | 10% | 548 | 8.3 | 4,538 |
| 90% | 20% | 1,095 | 6.4 | 6,975 |
| 80% | 13% | 712 | 4.7 | 3,377 |
| 70% | 12% | 657 | 3.4 | 2,233 |
| 60% | 12% | 657 | 2.3 | 1,519 |
| 50% | 33% | 1,807 | 1.5 | 2,647 |
| 40% | 0% | 0 | 0.8 | 0 |
| 30% | 0% | 0 | 0.4 | 0 |
| 20% | 0% | 0 | 0.1 | 0 |
| 10% | 0% | 0 | 0.0 | 0 |
| | | | | 21,288 N |

Total Savings .= H - N 24,093 KWh

| | | |
|---|---|---|
| **Reduced Electricity Savings =** | **44,333** | **kWh** |
| **Reduced Fuel Savings =** | **2,237** | **therms** |
| **Reduced Financial Savings =** | **$3,889** | |
| **Installation Cost =** | **$ 34,474** | **$** |
| **Payback =** | **8.9** | **Yrs.** |

**Conditioned Make Up Air: Heating**

| | | | |
|---|---|---|---|
| Previous Net Exhaust Volume | 12,000 | CFM | |
| New Net Exhaust Volume | 8,460 | CFM | Note 1 |
| Previous net heat load | 365,185 | BTU/hr | |
| New net heat load | 257,455 | BTU/hr | |
| Design Indoor Conditions | 72 | F | |
| Average Outdoor Air Temp (during Heating) | 43.8 | F | |
| Heating Hours | 3,322 | hrs/yr | |
| Total Therms Savings | 2,237 | Therms | |

| % Rated RPM I | % Run Time J | H * J |
|---|---|---|
| 100% | 10% | 10.00% |
| 90% | 20% | 18.00% |
| 80% | 13% | 10.40% |
| 70% | 12% | 8.40% |
| 60% | 12% | 7.20% |
| 50% | 33% | 16.50% |
| 40% | 0% | 0.00% |
| 30% | 0% | 0.00% |
| 20% | 0% | 0.00% |
| 10% | 0% | 0.00% |
| Avg RPM | | 70.50% |

Cost of Fuel = $0.34 / therm

**Cooling Savings Summary**

| | | |
|---|---|---|
| Design Indoor Conditions | 27.5 | btu/lb |
| Average Outdoor Enthalpy (during Cooling) | 31.8 | btu/lb |
| Reduction in Avg. Airflow | 3,540 | CFM |
| Cooling Load | 5.7 | Tons |
| Cooling Energy Demand | 4.6 | kW |
| Cooling Hours | 4,409 | Hrs/yr |
| Total Cooling kWh Savings | 20,240 | kWh |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**K-1A: Kitchen Hood Control - Main Terminal - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| Me-Link Kitchen Hood Control System | 1 | ea. | $ 15,000 | $ 2,000 | $ - | $ 14,715 | $ 1,394 | $ - | $ 16,109 | |
| Motor 5 Hp | 0 | ea. | $ 373 | $ 79 | | $ - | $ - | $ - | $ - | |
| 5 HP VFD (exhaust fan) 5 | 1 | ea. | $ 2,225 | $ 580 | $ - | $ 2,183 | $ 404 | $ - | $ 2,587 | **26 29 23.10 0110** |
| Motor 7.5 Hp | 0 | ea. | $ 536 | $ 84 | | $ - | $ - | $ - | $ - | |
| 7.5 HP VFD (supply fan) 7.5 | 1 | ea. | $ 2,700 | $ 695 | $ - | $ 2,649 | $ 484 | $ - | $ 3,133 | **26 29 23.10 0120** |
| Electrical - Misc. | 1 | ls | $ 500 | $ 1,000 | $ - | $ 491 | $ 697 | $ - | $ 1,188 | |
| Control Devices | 4 | ea. | $ 500 | $ 200 | $ - | $ 1,962 | $ 558 | $ - | $ 2,520 | sensors |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 25,536 | Subtotal |
| $ 5,107 | 20% Contingency |
| $ 3,830.43 | 15% O&P |
| **$ 34,474** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**K-1B: Kitchen Hood Control - Concourse A & B**

**ECM Description Summary**

*The exhaust systems in the kitchen hoods are at a constant speed. Adding a kitchen exhaust hood system would vary the amount of exhaust air volume, based on the heat and smoke load coming off the kitchen equipment. Upon activation of the system, the hood lights will turn on and the fans would reach a preset minimum speed of approximately 50 percent. When cooking appliances are turned on, the fan speed would increase based on the temperature sensed in the exhaust duct. During actual cooking, an optical sensor will sense particulates entering the hood and will increase up to 100 percent speed until smoke and heat are removed.*

**Motor Operating Savings**

| | | | |
|---|---|---|---|
| Hours of Operation (per day) | 14 | | A |
| Days/Year | 365 | | B |
| Weeks/Year | 52 | | C |
| Motor HP | 11.5 | | D |
| Equivalent KW | 7.63 | KW | E |
| Cost of Electricity | $0.07 | KWh | F |
| Total Time/Year | 4,928 | hrs/year | G |
| Total KWH/YR | 37,576 | KWh | H |

| % Rated RPM<br>I | % Run Time<br>J | Time<br>K<br>J * G | Output<br>L<br>I * E ^ 2.5 | KWH/YR<br>M<br>L *K |
|---|---|---|---|---|
| 100% | 10% | 493 | 7.626 | 3,758 |
| 90% | 20% | 986 | 5.860 | 5,775 |
| 80% | 13% | 641 | 4.365 | 2,796 |
| 70% | 12% | 591 | 3.126 | 1,849 |
| 60% | 12% | 591 | 2.126 | 1,257 |
| 50% | 33% | 1,626 | 1.348 | 2,192 |
| 40% | 0% | 0 | 0.772 | 0 |
| 30% | 0% | 0 | 0.376 | 0 |
| 20% | 0% | 0 | 0.136 | 0 |
| 10% | 0% | 0 | 0.024 | 0 |
| | | | | 17,627 N |

| | | | |
|---|---|---|---|
| Total Savings | = H - N | 19,949 | KWh |

| | | |
|---|---|---|
| **Reduced Electricity Savings =** | **34,342** | **kWh** |
| **Reduced Fuel Savings =** | **1,431** | **therms** |
| **Reduced Financial Savings =** | **$2,911** | |
| **Installation Cost =** | **$ 26,448** | **$** |
| **Payback =** | **9.1** | **Yrs.** |

**Conditioned Make Up Air: Heating**

| | | | |
|---|---|---|---|
| Previous Net Exhaust Volume | 8,533 | CFM | |
| New Net Exhaust Volume | 6,016 | CFM | Note 1 |
| Previous net heat load | 259,684 | BTU/hr | |
| new net heat load | 183,077 | BTU/hr | |
| Design Indoor Conditions | 72 | F | |
| Average Outdoor Air Temp (during Heating) | 43.8 | F | |
| Heating Hours | 3,322 | hrs/yr | |
| Total Therms Savings | 1,431 | Therms | |

| % Rated RPM I | % Run Time J | H * J |
|---|---|---|
| 100% | 10% | 10.00% |
| 90% | 20% | 18.00% |
| 80% | 13% | 10.40% |
| 70% | 12% | 8.40% |
| 60% | 12% | 7.20% |
| 50% | 33% | 16.50% |
| 40% | 0% | 0.00% |
| 30% | 0% | 0.00% |
| 20% | 0% | 0.00% |
| 10% | 0% | 0.00% |
| Avg RPM | | 70.50% |

Cost of Fuel = $0.34 / therm

**Cooling Savings Summary**

| | | |
|---|---|---|
| Design Indoor Conditions | 27.5 | btu/lb |
| Average Outdoor Enth (during Cooling) | 31.8 | btu/lb |
| Reduction in Avg. Airflow | 2,517 | CFM |
| Cooling Load | 4.1 | Tons |
| Cooling Energy Demand | 3.3 | kW |
| Cooling Hours | 4,409 | Hrs/yr |
| Total Cooling kWh Savings | 14,392 | kWh |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

**K-1B: Kitchen Hood Control - Concourse A & B - Cost**

| Norfolk, VA Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| CaptivAir Kitchen Hood Control System | 4 | ea. | $ 3,000 | $ 1,200 | $ - | $ 11,772 | $ 3,346 | $ - | $ 15,118 | includes vfd (sup&exh) controller |
| | | | | | | $ - | $ - | $ - | $ - | |
| VFD's exhaust & supply | 8 | ea. | | $ 200 | $ - | $ - | $ 1,115 | $ - | $ 1,115 | labor for installation only |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | $ - | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | $ - | $ - | $ - | $ - | $ - | |
| Electrical - Misc. | 4 | ea. | $ 125 | $ 125 | $ - | $ 491 | $ 349 | $ - | $ 839 | |
| Control Devices | 4 | ea. | $ 500 | $ 200 | | $ 1,962 | $ 558 | $ - | $ 2,520 | sensors |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 19,591 | Subtotal |
| $ 3,918 | 20% Contingency |
| $ 2,939 | 15% O&P |
| **$ 26,448** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## K-2: Walk-in Cooler & Freezer Controls

### ECM Description Summary

*For kitchens that contain walk-in coolers and freezers, Control is a controller that reduces energy consumption by controlling off of dewpoint temperature. Compressor cycling is reduced and the evaporator fans run 25% to 80% less. Door and frame heaters are also installed and controlled by store dew point temperature; this can reduce run time by up to 95% in coolers and 60% in freezers. The evaporator fan motors are also replaced with hi-efficiency fan motors saving 40% to 70% in energy. The proposed system comprises of an anti-sweat door controller, evaporator fan motor replacement and Control Cooler Control System.*

### Utility Cost

$0.07 $/kWh Blended

| EXISTING CONDITIONS | | |
|---|---|---|
| Existing Facility Total Electric usage | 13,094,430 | kWh |
| Existing Facility Refrigeration Electric usage | 916,610 | kWh[1] |
| Existing Facility Walk-In Electric usage | 274,983 | kWh[2] |
| Walk-In Controls System Annual Electric savings | 82,495 | kWh[3] |
| SAVINGS | | |
| Walk-In Controls Electric Usage Savings | 82,495 | **kWh** |
| Total cost savings | $ 5,830.45 | |
| Estimated Total Project Cost to Install 5 Units | $ 37,500 | [4] |
| Simple Payback | 6.4 | **years** |

Assumptions

| | | |
|---|---|---|
| 1 | 7% | of facility total electricity; Source: E source, data from U.S. Energy Information Administration |
| 2 | 30% | of refrigeration attributable to walk-in based on site observations |
| 3 | 30% | Electric load reduction typical for walk-in controllers |
| 4 | $ 7,500 | Based on (1) "Cooltrol" walk-in controls systems from previous workbooks |

**Norfolk Airport**
**CHA Project # 33370**
**Main Terminal**

## K-3: Install Vending Machine Controls

**ECM Description Summary**

*Vending machines generally operate 24/7 regardless of the actual usage. This measure proposes installing vending machine controls to reduce the total run time of these units. The result is a reduction in total electrical energy usage.*

**Unit Cost:** $0.071 $/kWh blended

**Energy Savings Calculations:**

| | | |
|---|---|---|
| Ex. Cold Beverage Vending Machine Electric Usage | 7,008 | kWh[1,4,7] |
| Ex. Snack Vending Machine Electric usage | 3,504 | kWh[2,5,7] |
| Ex. Dual Vending Machine Electric Usage | - | kWh[3,6,7] |
| Total Vending Machine Electric Usage | 10,512 | kWh |
| Proposed Vending Machine Electric usage | 7,043 | kWh[8] |
| **Vending Machine Controls Usage Savings** | **3,469** | **kWh** |
| **Total cost savings** | **$ 245** | |
| **Estimated Total Project Cost** | **$ 800** | [9] |
| **Simple Payback** | **3.3** | **years** |

Assumptions

| | | |
|---|---|---|
| 1 | 2 | Number of cold beverage vending machines |
| 2 | 2 | Number of snack vending machines |
| 3 | 0 | Number of dual snack/beverage vending machines |
| 4 | 400 | Average wattage, typical of cold beverage machines based on prior project experience |
| 5 | 200 | Average wattage, typical of snack machines based on prior project experience |
| 6 | 300 | Average wattage, typical of dual snack/beverage machines based on prior project experience |
| 7 | 8760 | Hours per year vending machine plugged in |
| 8 | 33% | Typical savings for vending machines based on historical data for runtime savings |
| 9 | $200 | Estimated installed cost per vending machine |

**Norfolk Airport**
**CHA Project # 33370**

| Utility Costs | | Yearly Usage | MTCDE |
|---|---|---|---|
| $ 0.067 | $/kWh blended | | 0.00042021 |
| $ 0.067 | $/kWh supply | | 0.00042021 |
| | $/kW | | 0 |
| $ 0.34 | $/Therm | | 0.00533471 |
| | $/kgals | | 0 |

# TNC Staging Area

| Recommended Y/N? | | Item | Savings kW | kWh | therms | kgal/yr | $ | Cost | Simple Payback | MTCDE | Life Expectancy | Simple kW |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Y | BE-2 | Door Sweep and Seal Replacement | 0 | 190 | 38 | 0 | $ 25 | $ 180 | 7.1 | 0.3 | 5 | 0 |
| N | M-1 | Boiler Replacement | 0 | 0 | 1,412 | 0 | $ 477 | $ 37,300 | >25 | 7.5 | 15 | 0 |
| N | DHW-2 | Domestic Hot Water Condensing Water Heater | 0 | 0 | 1,117 | 0 | $ 377 | $ 4,740 | 12.6 | 6.0 | 15 | 0 |
| Y | K-3 | Vending Misers | 0 | 2,891 | 0 | 0 | $ 193 | $ 600 | 3.1 | 1.2 | 5 | 0 |
| Y | L-1 | Lighting Upgrade | 4.2 | 13,370 | 0 | 0 | $ 893 | $ 16,970 | 19.0 | 5.6 | 5 | 21 |
| | | **Total Recommended** | **4.2** | **16,451** | **38** | **-** | **$ 1,111** | **$ 17,750** | **16.0** | **7.1** | | |
| | | **Total** | **4.2** | **16,451** | **2,567** | **0** | **$ 1,965** | **$ 59,790** | **30.4** | **20.6** | | |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

## BE-2: Install Door Seals

**Existing: Lack of door seals result in excessive heat loss and infiltration**
**Proposed: Install door seals and/or weather-stripping to reduce air infiltration**

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Heating System Efficiency | 80% | | Ex Occupied Clng Temp. | 72 | *F | Ex Occupied Htg Temp. | 68 | *F |
| Cooling System Efficiency | 1.06 | kW/ton | Ex Unoccupied Clng Temp. | 72 | *F | Ex Unoccupied Htg Temp. | 68 | *F |
| Linear Feet of Door Edge | 26 | | Cooling Occ Enthalpy Setpoint | 27.5 | Btu/lb | Electricity | $ 0.07 | $/kWh |
| Existing Infiltration Factor* | 1.5 | cfm/LF | Cooling Unocc Enthalpy Setpoint | 27.5 | Btu/lb | Natural Gas | $ 0.34 | $/therm |
| Proposed Infiltration Factor* | 0.45 | cfm/LF | | | | | | |

*Infiltration Factor per Carrier Handbook of Air Conditioning System Design based on average door seal gap calculated below.

| | | | | | EXISTING LOADS | | PROPOSED LOADS | | COOLING ENERGY | | HEATING ENERGY | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Occupied | Unoccupied | Occupied | Unoccupied | | | | |
| Avg Outdoor Air Temp. Bins °F | Avg Outdoor Air Enthalpy | Existing Equipment Bin Hours | Occupied Equipment Bin Hours | Unoccupied Equipment Bin Hours | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Door Infiltration Load BTUH | Existing Cooling Energy kWh | Proposed Cooling Energy kWh | Existing Heating Energy therms | Proposed Heating Energy therms |
| A | | B | C | D | E | F | G | H | I | J | K | L |
| 102.5 | 0.0 | 0 | 0 | 0 | 4,826 | 4,826 | 1,448 | 1,448 | 0 | 0 | 0 | 0 |
| 97.5 | 42.4 | 10 | 10 | 0 | -2,610 | -2,610 | -783 | -783 | 2 | 1 | 0 | 0 |
| 92.5 | 39.7 | 39 | 39 | 0 | -2,144 | -2,144 | -643 | -643 | 7 | 2 | 0 | 0 |
| 87.5 | 38.1 | 215 | 215 | 0 | -1,858 | -1,858 | -558 | -558 | 35 | 11 | 0 | 0 |
| 82.5 | 35.9 | 557 | 557 | 0 | -1,466 | -1,466 | -440 | -440 | 72 | 22 | 0 | 0 |
| 77.5 | 34.0 | 910 | 910 | 0 | -1,138 | -1,138 | -341 | -341 | 92 | 27 | 0 | 0 |
| 72.5 | 31.6 | 978 | 978 | 0 | -717 | -717 | -215 | -215 | 62 | 19 | 0 | 0 |
| 67.5 | 28.3 | 971 | 971 | 0 | 21 | 21 | 6 | 6 | 0 | 0 | 0 | 0 |
| 62.5 | 24.5 | 1,101 | 1,101 | 0 | 232 | 232 | 69 | 69 | 0 | 0 | 3 | 1 |
| 57.5 | 21.5 | 655 | 655 | 0 | 442 | 442 | 133 | 133 | 0 | 0 | 4 | 1 |
| 52.5 | 18.7 | 581 | 581 | 0 | 653 | 653 | 196 | 196 | 0 | 0 | 5 | 1 |
| 47.5 | 16.3 | 561 | 561 | 0 | 863 | 863 | 259 | 259 | 0 | 0 | 6 | 2 |
| 42.5 | 14.6 | 781 | 781 | 0 | 1,074 | 1,074 | 322 | 322 | 0 | 0 | 10 | 3 |
| 37.5 | 12.6 | 680 | 680 | 0 | 1,285 | 1,285 | 385 | 385 | 0 | 0 | 11 | 3 |
| 32.5 | 10.8 | 386 | 386 | 0 | 1,495 | 1,495 | 449 | 449 | 0 | 0 | 7 | 2 |
| 27.5 | 8.6 | 191 | 191 | 0 | 1,706 | 1,706 | 512 | 512 | 0 | 0 | 4 | 1 |
| 22.5 | 7.2 | 102 | 102 | 0 | 1,916 | 1,916 | 575 | 575 | 0 | 0 | 2 | 1 |
| 17.5 | 5.4 | 41 | 41 | 0 | 2,127 | 2,127 | 638 | 638 | 0 | 0 | 1 | 0 |
| 12.5 | 4.5 | 1 | 1 | 0 | 2,338 | 2,338 | 701 | 701 | 0 | 0 | 0 | 0 |
| 7.5 | 0.0 | 0 | 0 | 0 | 2,548 | 2,548 | 764 | 764 | 0 | 0 | 0 | 0 |
| **TOTALS** | | **8,760** | **8,760** | **0** | | | | | **271** | **81** | **54** | **16** |

| | | |
|---|---|---|
| **Existing Door Infiltration** | **39** | **cfm** |
| **Existing Unoccupied Door Infiltration** | **39** | **cfm** |
| **Proposed Door Infiltration** | **12** | **cfm** |
| **Proposed Unoccupied Door Infiltration** | **12** | **cfm** |

| | | | | |
|---|---|---|---|---|
| **Savings** | **38** | **therms** | **$** | **13** |
| | **190** | **kWh** | **$** | **13** |
| | | | **$** | **25** |

| Door | Width (ft) | Height (ft) | Linear Feet (LF) | gap (in) | gap location | LF of gap | % door w/ gap | Average gap for door (in) |
|---|---|---|---|---|---|---|---|---|
| 1 | 6 | 7 | 26 | 0.25 | bottom | 6 | 23% | 0.058 |
| **Total** | **6** | **7** | **26** | **0.25** | | **6** | **23%** | **0.058** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

**BE-2: Install Door Seals - Cost**

| Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | $ - | |
| Door Seals (double door - 6' x 7') | 1 | ea | $ 65 | $ 100 | $ - | $ 64 | $ 70 | $ - | $ 133 | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 133 | Subtotal |
| $ 27 | 20% Contingency |
| $ 20.02 | 15% Contingency |
| **$ 180** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**


**M-1: Boiler Replacement w/ Condensing, Incl. Hot Water Temperature Reset**

**Utility Costs**

| | | |
|---|---|---|
| Blended Electric Rate | $0.07 | / kWh |
| Blended Natural Gas Rate | $0.34 | / Therm |

| INPUTS - BOILER AND HHW PIPING | | |
|---|---|---|
| Boiler Input | 490 | MBH |
| Boiler Output | 368 | MBH |
| Nameplate Eff. w/ Losses | 75.0% | |
| Blended Natural Gas Rate | $0.34 | / MMBTU |
| Heating On Temperature [4] | 65 | °F |
| Building Balance Point | 55 | °F |
| Existing Average HHW Setpoint High | 180 | °F |
| Existing HHW Setpoint Low | 180 | °F |
| Proposed Avg HHW Setpoint Low | 120 | °F |

| INPUTS - PROPOSED BOILER EFFICIENCY DATA | | | |
|---|---|---|---|
| RWT (F) | % Firing Rate | | |
| | 100% | 50% | 8% |
| 80 | 97.8% | 98.0% | 98.2% |
| 100 | 95.5% | 95.8% | 96.1% |
| 120 | 91.0% | 91.4% | 91.8% |
| 140 | 87.5% | 87.9% | 88.1% |
| 160 | 87.2% | 87.3% | 87.5% |




**SAVINGS ANALYSIS**

| Local Temperature Bin Data | | | | Existing Conditions | | | | | | | | | Proposed Conditions | | | | | | | | SAVINGS | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Avg. DB Bin Temp °F | Boiler On? | Bin Hours | Heating Bin HOURS | Leaving Water Temp | Delta T | Return Water Temp | Total Boiler Heat Load ( MBH ) | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MMBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Firing Rate | Existing Utility Use Therms/Yr | Leaving Water Temp | Delta T | Return Water Temp | Bldg. Heat Load ( MBH ) | Bldg. Heat Usage ( MMBTU ) | Resulting Boiler Firing Rate ( % ) | Efficiency Based on Delta T and Firing Rate | Existing Utility Use Therms/Yr | Savings Utility Use Therms/Yr |
| 92.5 | NO | 10 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 87.5 | NO | 39 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 82.5 | NO | 215 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 77.5 | NO | 557 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 72.5 | NO | 910 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 67.5 | NO | 978 | 0 | 180 | 20 | 160 | 29 | 29 | 0 | 8% | 80.0% | 0 | 120 | 20 | 100 | 29 | 0 | 8% | 96% | 0 | 0 |
| 62.5 | YES | 971 | 971 | 180 | 20 | 160 | 58 | 58 | 56 | 16% | 80.0% | 699 | 120 | 20 | 100 | 58 | 56 | 16% | 96% | 584 | 115 |
| 57.5 | YES | 1101 | 1,101 | 180 | 20 | 160 | 86 | 86 | 94 | 23% | 80.0% | 1,180 | 120 | 20 | 100 | 86 | 94 | 23% | 96% | 985 | 195 |
| 52.5 | YES | 655 | 655 | 180 | 20 | 160 | 114 | 114 | 75 | 31% | 80.0% | 933 | 123 | 20 | 103 | 114 | 75 | 31% | 95% | 784 | 149 |
| 47.5 | YES | 581 | 581 | 180 | 20 | 160 | 142 | 142 | 83 | 39% | 80.0% | 1,032 | 129 | 20 | 109 | 142 | 83 | 39% | 94% | 880 | 152 |
| 42.5 | YES | 561 | 561 | 180 | 20 | 160 | 170 | 170 | 96 | 46% | 80.0% | 1,194 | 136 | 20 | 116 | 170 | 96 | 46% | 92% | 1,034 | 160 |
| 37.5 | YES | 781 | 781 | 180 | 20 | 160 | 198 | 198 | 155 | 54% | 80.0% | 1,937 | 142 | 20 | 122 | 198 | 155 | 54% | 91% | 1,712 | 225 |
| 32.5 | YES | 680 | 680 | 180 | 20 | 160 | 227 | 227 | 154 | 62% | 80.0% | 1,926 | 148 | 20 | 128 | 227 | 154 | 62% | 89% | 1,727 | 200 |
| 27.5 | YES | 386 | 386 | 180 | 20 | 160 | 255 | 255 | 98 | 69% | 80.0% | 1,229 | 155 | 20 | 135 | 255 | 98 | 69% | 88% | 1,115 | 114 |
| 22.5 | YES | 191 | 191 | 180 | 20 | 160 | 283 | 283 | 54 | 77% | 80.0% | 676 | 161 | 20 | 141 | 283 | 54 | 77% | 87% | 618 | 57 |
| 17.5 | YES | 102 | 102 | 180 | 20 | 160 | 311 | 311 | 32 | 85% | 80.0% | 397 | 167 | 20 | 147 | 311 | 32 | 85% | 87% | 365 | 32 |
| 12.5 | YES | 41 | 41 | 180 | 20 | 160 | 339 | 339 | 14 | 92% | 80.0% | 174 | 174 | 20 | 154 | 339 | 14 | 92% | 87% | 160 | 14 |
| 7.5 | YES | 1 | 1 | 180 | 20 | 160 | 368 | 368 | 0 | 100% | 80.0% | 5 | 180 | 20 | 160 | 368 | 0 | 100% | 87% | 4 | 0 |
| **Totals** | | **8,760** | **6,051** | | | | | | **911** | | **80.0%** | **11,382** | | | | | **911** | | **91%** | **9,970** | **1,412** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

**M-1: Boiler Replacement w/ Condensing, Incl. Hot Water Temperature Reset - Cost**

| Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | $ - | $ - | $ - | $ - | |
| **750 MBH Condensing Boiler** | 1 | EA | $ 22,000 | $ 2,500 | | $ 21,582 | $ 1,743 | $ - | $ 23,325 | |
| **Condensing Boiler Electrical** | 1 | LS | $ 250 | $ 500 | $ - | $ 245 | $ 349 | $ - | $ 594 | |
| **Venting Kit** | 1 | EA | $ 450 | $ 650 | $ - | $ 440 | $ 785 | $ - | $ 1,225 | |
| **Miscellaneous Piping and Valves** | 1 | LS | $ 250 | $ 250 | $ - | $ 489 | $ 604 | $ - | $ 1,093 | |
| **Demolition** | 1 | LS | $ - | $ 2,000 | $ - | $ - | $ 1,394 | $ - | $ 1,394 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 27,630 | Subtotal |
| $ 5,526 | 20% Contingency |
| $ 4,144 | 15% O&P |
| **$ 37,300** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

## DHW-2: Replace DHW Heater w/ Condensing Gas-Fired DHW Heater

**Summary**

* Replace DHW Heater w/ Indirect, Condensing, Gas-Fired DHW Heater

| Item | Value | Units | Formula/Comments |
|---|---|---|---|
| Occupied days per week | 7 | days/wk. | |
| Water supply Temperature | 55 | ˚F | Temperature of water coming into building |
| Hot Water Temperature | 120 | ˚F | |
| Hot Water Usage per day | 508 | gal/day | Calculated from usage below |
| Annual Hot Water Energy Demand | 100,022 | MBTU/yr | Energy required to heat annual quantity of hot water to setpoint |
| | | | |
| Existing Tank Size | 30 | Gallons | Per manufacturer nameplate |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 70 | ˚F | |
| Standby Losses (% by Volume) | 2.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.3 | MBH | |
| Annual Standby Hot Water Load | 2,738 | MBTU/yr | |
| | | | |
| Total Annual Hot Water Demand (w/ standby losses) | 102,760 | Mbtu/yr | Building demand plus standby losses |
| Existing Water Heater Efficiency | 80% | | Per Manufacturer |
| Total Annual Energy Required | 128,449 | Mbtu/yr | |
| **Total Annual Electric Required** | **1,284** | **Therms** | |
| | | | |
| New Tank Size | 30 | Gallons | |
| Hot Water Temperature | 120 | ˚F | |
| Average Room Temperature | 70 | ˚F | |
| Standby Losses (% by Volume) | 2.5% | | ( 2.5% of stored capacity per hour, per U.S. Department of Energy ) |
| Standby Losses (Heat Loss) | 0.3 | MBH | |
| Annual Standby Hot Water Load | 2,738 | MBTU/yr | |
| | | | |
| Prop Annual Hot Water Demand (w/ standby losses) | 102,760 | MBTU/yr | |
| Proposed Avg. Hot water heater efficiency | 92% | | |
| Proposed Total Annual Energy Required | 111,695 | MBTU/yr | |
| Proposed Fuel Use | 1,117 | Therms/yr | |
| | | | |
| NG Utility Unit Cost | $0.34 | $/Therm | |
| Existing Operating Cost of DHW | $434 | $/yr | |
| Proposed Operating Cost of DHW | $377 | $/yr | |
| **Annual Utility Cost Savings** | **$57** | **$/yr** | |

**Daily Hot Water Demand**

| | | | #USES PER DAY | | FULL TIME OCCUPANTS** | | | | |
|---|---|---|---|---|---|---|---|---|---|
| FIXTURE | *BASE WATER USE GPM | DURATION OF USE (MIN) | MALE | FEMALE | MALE | FEMALE | TOTAL GAL/DAY | % HOT WATER | TOTAL HW GAL/DAY |
| LAVATORY (Low-Flow Lavs use 0.5 GPM) | 2.5 | 0.25 | 1 | 1 | 800 | 800 | 1000 | 50% | 500 |
| SHOWER | 2.5 | 5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| KITCHEN SINK | 2.5 | 0.5 | 0 | 0 | 0 | 0 | 0 | 75% | 0 |
| MOP SINK | 2.5 | 2 | 1 | 1 | 1 | 1 | 10 | 75% | 8 |
| Dishwasher (gal per | 10 | 1 | 0 | 0 | 0 | 0 | 0 | 100% | 0 |
| | | | | | | **TOTAL** | 1010 | | **508** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

| Multipliers | |
|---|---|
| Material: | 0.98 |
| Labor: | 0.70 |
| Equipment: | 0.86 |

**DHW-2: Replace DHW Heater w/ Condensing Gas-Fired DHW Heater - Cost**

| Description | QTY | UNIT | UNIT COSTS | | | SUBTOTAL COSTS | | | TOTAL COST | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | MAT. | LABOR | EQUIP. | MAT. | LABOR | EQUIP. | | |
| | | | | | | | | | | |
| Gas-Fired DHW Heater Removal | 1 | LS | | $ 50 | | $ - | $ 35 | $ - | $ 35 | |
| Indirect Water Heater | 1 | EA | $ 1,599 | $ 250 | | $ 1,569 | $ 174 | $ - | $ 1,743 | |
| Miscellaneous Electrical | 1 | LS | $ 250 | $ 250 | | $ 245 | $ 174 | $ - | $ 420 | |
| Venting Kit | 1 | EA | $ 450 | $ 650 | | $ 441 | $ 453 | $ - | $ 895 | |
| Miscellaneous Piping and Valves | 1 | LS | $ 250 | $ 250 | | $ 245 | $ 174 | $ - | $ 420 | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | $ - | $ - | $ - | $ - | |
| | | | | | | | | | | |

**Cost Estimates are for Energy Savings calculations only, do not use for procurement

| | |
|---|---|
| $ 3,511 | Subtotal |
| $ 702 | 20% Contingency |
| $ 526.68 | 15% Contingency |
| **$ 4,740** | **Total** |

**Norfolk Airport**
**CHA Project # 33370**
**TNC Staging Area**

**K-3: Install Vending Machine Controls**

**Summary:** Vending machines generally operate 24/7 regardless of the actual usage. This measure proposes installing vending machine controls to reduce the total run time of these units. The result is a reduction in total electrical energy usage.

**Unit Cost:** $0.067 $/kWh blended

**Energy Savings Calculations:**

| | | |
|---|---|---|
| Ex. Cold Beverage Vending Machine Electric usage | 7,008 | kWh[1,4,7] |
| Ex. Snack Vending Machine Electric usage | 1,752 | kWh[2,5,7] |
| Ex. Dual Vending Machine Electric Usage | - | kWh[3,6,7] |
| Total Vending Machine Electric Usage | 8,760 | kWh |
| Proposed Vending Machine Electric usage | 5,869 | kWh[8] |
| **Vending Machine Controls Usage Savings** | **2,891** | **kWh** |
| **Total cost savings** | **$ 193** | |
| **Estimated Total Project Cost** | **$ 600** | [9] |
| **Simple Payback** | **3.1** | **years** |

Assumptions

| | | |
|---|---|---|
| 1 | 2 | Number of cold beverage vending machines |
| 2 | 1 | Number of snack vending machines |
| 3 | 0 | Number of dual snack/beverage vending machines |
| 4 | 400 | Average wattage, typical of cold beverage machines based on prior project experience |
| 5 | 200 | Average wattage, typical of snack machines based on prior project experience |
| 6 | 300 | Average wattage, typical of dual snack/beverage machines based on prior project experience |
| 7 | 8760 | Hours per year vending machine plugged in |
| 8 | 33% | Typical savings for cold vending machines based on historical data for runtime savings |
| 9 | $200 | Estimated installed cost per vending machine |

# APPENDIX D – ALTERNATIVE ENERGY CALCULATIONS

**Norfolk Airport Authority**
**Norfolk Airport - Garage A**

| | | |
|---|---|---|
| Cost of Electricity | $0.07 | /kWh |
| Electricity Usage | 20,969,456 | kWh/yr |
| System Unit Cost | $4,000 | /kW |

## Photovoltaic (PV) Solar Power Generation - Screening Assessment

| Budgetary Cost | Annual Utility Savings | | | | Estimated Maintenance Savings | Total Savings | Federal Tax Credit | Payback (without incentive) |
|---|---|---|---|---|---|---|---|---|
| $ | kW | kWh | therms | $ | $ | $ | $ | Years |
| **$2,520,000** | **630.0** | **919,183** | **0** | **$62,705** | **0** | **$62,705** | **$756,000** | **40.2** |

** Estimated Solar Renewable Energy Certificate Program (SREC) SREC for 15 Years= $0 /1000kwh

**Area Output***
10,089 m2
108,602 ft2

**Perimeter Output***
442 m
1,450 ft

**Available Roof Space for PV:**
(Area Output - 10 ft x Perimeter) x 85%
79,984 ft2

**Approximate System Size:** Is the roof flat? (Yes/No) Yes

**8** watt/ft2
639,873 DC watts
630 kW Enter into PV Watts


**PV Watts Inputs*****

| | | |
|---|---|---|
| Array Tilt Angle | 20 | Enter into PV Watts (always 20 if flat, if pitched - enter estimated roof angle) |
| Array Azimuth | 180 | Enter into PV Watts (default) |
| Zip Code | 23518 | Enter into PV Watts |
| DC/AC Derate Factor | 0.83 | Enter info PV Watts |

**PV Watts Output**
919,183 annual kWh calculated in PV Watts program

**% Offset Calc**

| | | |
|---|---|---|
| Usage | ######## | (from utilities) |
| PV Generation | 919,183 | (generated using PV Watts ) |
| % offset | 4% | |



* http://www.freemaptools.com/area-calculator.htm
** http://www.flettexchange.com
*** https://pvwatts.nrel.gov/

**Norfolk Airport Authority**
**Norfolk Airport - Garage B**

| | | |
|---|---|---|
| Cost of Electricity | $0.07 | /kWh |
| Electricity Usage | 20,969,456 | kWh/yr |
| System Unit Cost | $4,000 | /kW |

**Photovoltaic (PV) Solar Power Generation - Screening Assessment**

| Budgetary Cost | Annual Utility Savings | | | | Estimated Maintenance Savings | Total Savings | Federal Tax Credit | Payback (without incentive) |
|---|---|---|---|---|---|---|---|---|
| $ | kW | kWh | therms | $ | $ | $ | $ | Years |
| **$920,000** | **230.0** | **335,575** | **0** | **$22,892** | **0** | **$22,892** | **$276,000** | **40.2** |

** Estimated Solar Renewable Energy Certificate Program (SREC) SREC for 15 Years= $0 /1000kwh

**Area Output***
4,161 m2
44,793 ft2

**Perimeter Output***
314 m
1,030 ft

**Available Roof Space for PV:**
(Area Output - 10 ft x Perimeter) x 85%
29,318 ft2

**Approximate System Size:** Is the roof flat? (Yes/No) Yes

| | | |
|---|---|---|
| 8 | watt/ft2 | |
| 234,546 | DC watts | |
| 230 | kW | Enter into PV Watts |

**PV Watts Inputs*****

| | | |
|---|---|---|
| Array Tilt Angle | 20 | Enter into PV Watts (always 20 if flat, if pitched - enter estimated roof angle) |
| Array Azimuth | 180 | Enter into PV Watts (default) |
| Zip Code | 23518 | Enter into PV Watts |
| DC/AC Derate Factor | 0.83 | Enter info PV Watts |

**PV Watts Output**
335,575 annual kWh calculated in PV Watts program

**% Offset Calc**

| | | |
|---|---|---|
| Usage | ######## | (from utilities) |
| PV Generation | 335,575 | (generated using PV Watts ) |
| % offset | 2% | |



* http://www.freemaptools.com/area-calculator.htm
** http://www.flettexchange.com
*** https://pvwatts.nrel.gov/

**Norfolk Airport Authority**
**Norfolk Airport - Garage C**

| | | |
|---|---|---|
| Cost of Electricity | $0.07 | /kWh |
| Electricity Usage | 20,969,456 | kWh/yr |
| System Unit Cost | $4,000 | /kW |

## Photovoltaic (PV) Solar Power Generation - Screening Assessment

| Budgetary Cost | Annual Utility Savings | | | | Estimated Maintenance Savings | Total Savings | Federal Tax Credit | Payback (without incentive) |
|---|---|---|---|---|---|---|---|---|
| $ | kW | kWh | therms | $ | $ | $ | $ | Years |
| **$920,000** | **230.0** | **335,575** | **0** | **$22,892** | **0** | **$22,892** | **$276,000** | **40.2** |

** Estimated Solar Renewable Energy Certificate Program (SREC) SREC for 15 Years= $0 /1000kwh

**Area Output***
4,228 m2
45,509 ft2

**Perimeter Output***
317 m
1,040 ft

**Available Roof Space for PV:**
(Area Output - 10 ft x Perimeter) x 85%
29,845 ft2

**Approximate System Size:** Is the roof flat? (Yes/No) Yes

| | | |
|---|---|---|
| **8** | watt/ft2 | |
| 238,763 | DC watts | |
| 230 | kW | Enter into PV Watts |

**PV Watts Inputs*****

| | | |
|---|---|---|
| Array Tilt Angle | 20 | Enter into PV Watts (always 20 if flat, if pitched - enter estimated roof angle) |
| Array Azimuth | 180 | Enter into PV Watts (default) |
| Zip Code | 23518 | Enter into PV Watts |
| DC/AC Derate Factor | 0.83 | Enter info PV Watts |

**PV Watts Output**
335,575 annual kWh calculated in PV Watts program

**% Offset Calc**

| | | |
|---|---|---|
| Usage | ######## | (from utilities) |
| PV Generation | 335,575 | (generated using PV Watts ) |
| % offset | 2% | |



* http://www.freemaptools.com/area-calculator.htm
** http://www.flettexchange.com
*** https://pvwatts.nrel.gov/

**Norfolk Airport Authority**
**Norfolk Airport - Garage C**

| | | |
|---|---|---|
| Cost of Electricity | $0.07 | /kWh |
| Electricity Usage | 20,969,456 | kWh/yr |
| System Unit Cost | $4,000 | /kW |

## Photovoltaic (PV) Solar Power Generation - Screening Assessment

| Budgetary Cost | Annual Utility Savings | | | | Estimated Maintenance Savings | Total Savings | Federal Tax Credit | Payback (without incentive) |
|---|---|---|---|---|---|---|---|---|
| $ | kW | kWh | therms | $ | $ | $ | $ | Years |
| **$7,080,000** | **1770.0** | **2,582,466** | **0** | **$176,172** | **0** | **$176,172** | **$2,124,000** | **40.2** |

** Estimated Solar Renewable Energy Certificate Program (SREC) SREC for 15 Years= $0 /1000kwh

**Area Output***
28,969 m2
311,817 ft2

**Perimeter Output***
474 m
1,554 ft

**Available Roof Space for PV:**
(Area Output - 10 ft x Perimeter) x 75%
222,204 ft2

**Approximate System Size:** Is the roof flat? (Yes/No) Yes

8 watt/ft2
1,777,633 DC watts
1,770 kW Enter into PV Watts

**PV Watts Inputs*****

| | | |
|---|---|---|
| Array Tilt Angle | 20 | Enter into PV Watts (always 20 if flat, if pitched - enter estimated roof angle) |
| Array Azimuth | 180 | Enter into PV Watts (default) |
| Zip Code | 23518 | Enter into PV Watts |
| DC/AC Derate Factor | 0.83 | Enter info PV Watts |

**PV Watts Output**
2,582,466 annual kWh calculated in PV Watts program

**% Offset Calc**

| | | |
|---|---|---|
| Usage | ######## | (from utilities) |
| PV Generation | 2,582,466 | (generated using PV Watts ) |
| % offset | 12% | |



* http://www.freemaptools.com/area-calculator.htm
** http://www.flettexchange.com
*** https://pvwatts.nrel.gov/